

ADDENDUM NO. 06.1

DATE: March 15, 2021

TO: All Potential Bidders

FROM: Penny Owens, Purchasing Agent, City of Knoxville

SUBJECT: Addendum No. 06.1 – Public Safety Complex Construction

BID DATE: March 23, 2021, at 2:00:00 p.m. (Eastern Time)

This addendum becomes a part of the Contract Document and modifies the original specifications as noted.



ADDENDUM 06.1

Project: 19018_COK Public Safety Complex
Date: 15 March 2021

Addendum 06.1 forms a part of Construction Documents and modifies the original drawings and specifications issued on February 1, 2021.

SPECIFICATIONS:

Unless noted otherwise, replace the following sections with the attached updated sections dated 3.15.2021.

1. None.

BP3 DRAWINGS:

Unless noted otherwise, replace the following sections with the attached updated sections dated 3.15.2021.

2. **Sheet G002:** Add "6" to REV NO. column and "ADD #06.1" to REVISION TITLE column on Sheets G002, A620, A621, A622 and A710.
3. **Sheets A620, A621, and A622:** Remove Shadow box note reading "PROVIDE LUMINOUS EGRESS PATH MARKINGS AT THE LEADING EDGE OF EACH STEP, STAIR LANDING, AND AT THE STAIR PERIMETER IN COMPLIANCE WITH IBC 2018 1025.2.1 THROUGH 1025.2.2." Luminous Egress markings not required on project per COK permitting office.
4. **Sheets A620, A621, and A622:** Remove Shadow box note reading "PROVIDE LUMINOUS EGRESS PATH MARKINGS ON ALL HANDRAILS AND EXTENSIONS IN COMPLIANCE WITH IBC 2018 1025.2.3." Luminous Egress markings not required on project per COK permitting office.
5. **Sheets A620, A621, and A622:** Remove Shadow box note reading: "PROVIDE HARDWARE AND LUMINOUS EGRESS MARKINGS ON ALL DOORS WITHIN THE EXIT PATH IN COMPLIANCE WITH IBC 2018 1025.2.6." Luminous Egress markings not required on project per COK permitting office.
6. **Sheet A710:** Refer to attached Sheet A710 from Addendum 04.1. It was brought to our attention that Sheet A720 was issued twice instead of both Sheets.
7. **Alternate #2 – Prefabricated Firing Range:** Basis of Design reference range drawing provided in Addendum 04.1 is a SAMPLE DRAWING ONLY. The project scope is accurately demonstrated in the proposal.

END OF ADDENDUM 06.1.



Project Information:

19018

COK PUBLIC SAFETY COMPLEX

900 East Oak Hill Ave, Knoxville, TN

Scale:



Architects Design Group

Issue Date: FEBRUARY 01, 2021

PKC DAVID COLLINS

PM JOHN THURMAN

PA LAUREN BUSH /

Drawn By: ADG

Checked By: BP

Drawing Info:

ISSUE DATE
2 ADD #02.1 02/17/21
6 ADD #06.1 03/15/21

Table with columns: DOOR SCHEDULE MARK, To Room: Number, MARK, ROOM NAME, LEAF QTY, W, H, SIZE, THK, TYPE, MATL, FINIS, H, GLZ, TYPE, MATL, FINISH, HEAD, DETAILS, JAMB, SILL, FIRE RATIN, G, HARDWARE, SET NO, REMARKS, WIRED. Includes sections for CA LEVEL L3, CA LEVEL L1, CA LEVEL L2, and CA GROUND LEVEL.

Table with columns: DOOR SCHEDULE MARK, To Room: Number, MARK, ROOM NAME, LEAF QTY, W, H, SIZE, THK, TYPE, MATL, FINIS, H, GLZ, TYPE, MATL, FINISH, HEAD, DETAILS, JAMB, SILL, FIRE RATIN, G, HARDWARE, SET NO, REMARKS, WIRED. Includes sections for CA LEVEL L1, CA LEVEL L2, CA GROUND LEVEL, and CA TOP OF PARAPET.

DOOR REMARKS LEGEND:
A. EXISTING DOOR FRAME TO REMAIN UNLESS OTHERWISE NOTED. CONTRACTOR TO VERIFY CONSTRUCTION AT EXISTING HALL HEAD A JAMB DETAILS SIM TO NOTED ON SCHEDULE. CONTRACTOR TO VERIFY CONSTRUCTION, CLEAN & REPAIR AS REQD. CONTRACTOR TO PROVIDE NEW HARDWARE KEYS TO MATCH ALL NEW HARDWARE THROUGHOUT PROJECT.
B. EXISTING GLASS LENS TO REMAIN UNLESS OTHERWISE NOTED. CONTRACTOR TO VERIFY CONSTRUCTION, CLEAN & REPAIR AS REQD. CONTRACTOR TO PROVIDE NEW GLASS LENS. SEE SPECIFICATIONS FOR REQUIREMENTS.
C. EXISTING ELEVATOR DOOR TO REMAIN. CONTRACTOR TO INSTALL NEW SURROUND ON EXISTING DOORS. SEE ELEVATOR INFO SHEET #012.

Table with columns: LEAF Selections, Frame Type, FRAME Selections, Frame Material. Includes rows for PTD - Painted, STD - Stained Wood, GLAN - Clear Anodized, BLAN - Black Anodized, S1, A1, AL - Aluminum, HM - Hollow Metal, EX - Existing.

- D. NEW OVERHEAD ROLLING DOOR.
E. NEW BALLISTIC TYPE 3 RATED DOOR.
F. WIRED / SECURE - CARD ACCESS. SEE ELECTRICAL DRAWINGS FOR REQD SECURE EXIT SWITCHES.
G. WIRED / SECURE - KEYPAD ACCESS. SEE ELECTRICAL DRAWINGS FOR REQD SECURE EXIT SWITCHES.
H. WIRED / SECURE - ALARM UPON OPENING.
I. EMERGENCY EGRESS PUSH BAR.
J. SECURE FROM INTERIOR - NO ACCESS / HARDWARE ON EXTERIOR.
K. SOUND ISOLATION DOOR. MIN. STC-43. PROVIDE REQUIRED FRAME & ACOUSTIC THRESHOLD.
L. SPECIALTY COURTROOM DOOR - NATURAL WOOD VENEER, MAPLE FINISH, TO MATCH WOOD WALL PANEL.
M. (NOT USED)
N. INTERIOR SIGNAGE - NOT AN EXIT

3/15/2021 3:42:20 PM