

**BID NUMBER: 0101**  
**BID TITLE: UCPS CO RENO & GAP DECK REPLACEMENT**

**UCPS GAP BUILDING DECK REPLACEMENT SCOPE OF WORK:**

- Remove the existing wooden deck, handrail and support posts.
- Drill new holes and install new 6" x 6" support posts secured with concrete.
- Install a 2" x 10" Pressure Treated wood beam on both sides of the support posts. Install 2" x 6" wood blocking under each wood beam and attach to the support posts.
- Install 2" x 6" wood joists between the wood beams. Attach joists to the beams with joist hangers.
- Install 2" x 6" wood boards for decking over the wood joists.
- Install a new wood handrail in between the wood supports with 2" x 2" wood pickets.
- Finished decking, handrail, supplies and materials must be to code.
- Progressive clean up.
- Project safety and management.

**ADDENDUM:**

- Remove and dispose of existing vinyl skirting from the building.
- Install new pressure treated 2x4 lumber to mount new skirting.
- Install 26gauge metal base and head trims.
- Install 26gauge Purlin Bearing Rib metal siding panels for new skirting. The color is to match the current metal panels that are on the 1<sup>st</sup> portable.
- Install outside corners as required.