BID PROPOSAL CITY OF KNOXVILLE, TENNESSEE

2020 Resurfacing Project Project No. 19W-P-0685

TO THE PURCHASING AGENT
CITY OF KNOXVILLE, TENNESSEE

hereby propose(s) to furnish all material, labor, and appliances and do all work required to complete the Contract for the 2020 Resurfacing Project, Project No. 19W-P-0685, located in the City of Knoxville, Tennessee, in a workmanlike manner and in accordance with the plans of the Department of Engineering and specifications herewith attached.

Bidder further agrees that in case of failure to sign a delivered contract within thirty (30) days, the certified check or bid bond accompanying this bid and the proceeds thereof shall be the property of the City of Knoxville if the City chooses to retain said bid bond or check.

BID SCHEDULE

ITEM			TOTAL	PRICE	TOTAL PRICE
NO.	DESCRIPTION	UNITS	QUANTITY	PER UNIT	PER ITEM
5.10	Mineral Aggregate Base	TON	600		
7.10	Trackless Tack Coat (TTT-1)	GAL	20,000		
9.10	Bituminous Plan Mix, Grading B	TON	1,200		
9.30	Bituminous Plan Mix, Grading C	TON	1,200		
10.10	Asphaltic Concrete Surface,				
	Grading D (PG64-22)	TON	33,600		
10.12	Asphaltic Concrete Surface,				
	Grading D (PG76-22)	TON	100		
10.30	Asphalt Curb	LF	7,250		
10.40	Pavement Removal				
	(up to 3 ft. in depth)	SY	1,000		
10.60	Speed Humps	EA	5		
12.61	6" Concrete Combined Curb			_	
	& Gutter	LF	500		
13.20	Concrete Driveways	SF	500		
23.10	Adjusting Storm Sewer Manhole				
	Frames & Catch Basin Grates	EA	50		
23.20	Adjusting Storm Sewer -				
	Ring Only	EA	10		
26.10	Top Soil	CY	50		

ITEM NO.	DESCRIPTION	UNITS	TOTAL QUANTITY	PRICE PER UNIT	TOTAL PRICE PER ITEM
27.10	Seeding	SY	500		
38.10	<u> </u>	51	500		
36.10	Milling or Grinding of Asphalt Streets (Surface Milling)	TON	700		
38.20	Milling or Grinding of Asphalt Streets (Full Depth & Profile Mill)	TON	16,300		
39.10	Painted Pavement Marking Line (4" Line)	LMI	42		
39.20	Thermoplastic Pavement Marking (STOP Line)	LF	1,040		
39.30	Thermoplastic Pavement Marking (Crosswalk Striping)	LF	1,494		
39.40	Thermoplastic Pavement Marking (Turn Lane Arrow)	EA	76		
39.50	Thermoplastic Pavement Marking (Only)	EA	4		
39.60	Thermoplastic Pavement Marking (Rumble Strip)	EA	3		
39.70	Thermoplastic Pavement Marking (Channelization Striping)	SY	64		
39.80	Thermoplastic Pavement Marking	31	04		
50.10	(RR Crossing Symbol)	EA	1		
58.10	Adjusting Manhole Frames (Full Depth Mill)	EA	13		
58.20	Adjusting Manhole Frames (Adjustment Ring Only)	EA	450		
59.10	Adjusting Valve Boxes (Full Depth Mill)				
59.20	Adjusting Valve Boxes	EA	13		
730-14.02	Saw Slot	EA	450		
		LF	3,770		
730-14.03	Loop Wire	LF	8,700		
		\$			

TOTAL BID (In Words):