

**CITY OF GRIFFIN 2020 CDBG  
PARK DISTRICT 2: PHASE II  
BID TABULATION**

Item	Description	Unit	Quantity	Unit Price	Item Total
<b>GENERAL</b>					
1.	PAYMENT & PERFORMANCE BONDS	LS	1		
2.	GENERAL CONDITIONS	LS	1		
3.	CONSTRUCTION STAKING (LAYOUT) BY REGISTERED SURVEYOR	LS	1		
4.	AS-BUILT SURVEY PLAN (WATER & SANITARY SEWER) BY REGISTERED SURVEYOR	LS	1		
5.	WATER MAIN CHLORINATION & TESTING COMPLETE PER CITY OF GRIFFIN SPECIFICATIONS	LS	1		
6.	SANITARY SEWER TESTING COMPLETE PER CITY OF GRIFFIN SPECIFICATIONS	LS	1		
7.	TRAFFIC CONTROL	LS	1		
<i>General Subtotal =</i>					
<b>DEMOLITION/REMOVAL</b>					
8.	PAVEMENT CUT (CONCRETE OR ASPHALT, VARIOUS DEPTHS)	LF	8,810		
9.	CONCRETE OR ASPHALT STREET DEMOLITION INCLUDING OFFSITE DISPOSAL (VARIOUS THICKNESSES)	SY	2,884		
10.	CONCRETE DRIVEWAY DEMOLITION INCLUDING SAW CUT & DISPOSAL	SF	252		
11.	CONCRETE CURB DEMOLITION INCLUDING SAW CUT & DISPOSAL	LF	160		
<i>Demolition/Removal Subtotal =</i>					
<b>WATER MAIN</b>					
12.	6" DIP WATER MAIN (PRESSURE CLASS 350)	LF	5,475		
13.	6" MJ GATE VALVE COMPLETE	EA	16		
14.	6" x 6" STAINLESS STEEL FULL CIRCLE TAPPING SLEEVE & FLANGED BY MJ VALVE, COMPLETE	EA	1		
15.	12" x 6" STAINLESS STEEL FULL CIRCLE TAPPING SLEEVE & FLANGED BY MJ VALVE, COMPLETE	EA	1		
16.	6" x 6" MJ TEE COMPLETE WITH RESTRAINTS & CONCRETE BLOCKING	EA	7		
17.	6" 90° MJ BEND COMPLETE WITH RESTRAINTS & CONCRETE BLOCKING	EA	3		
18.	6" 45° MJ BEND COMPLETE WITH RESTRAINTS & CONCRETE BLOCKING	EA	9		
19.	6" 22.5° MJ BEND COMPLETE WITH RESTRAINTS & CONCRETE BLOCKING	EA	1		
20.	6" MJ CAP COMPLETE INCLUDING CONCRETE BLOCKING	EA	1		
21.	6" MJ COUPLING COMPLETE	EA	1		
21.	8" DIP WATER MAIN (PRESSURE CLASS 350)	LF	777		
22.	12" STEEL ENCASEMENT PIPE	LF	25		
23.	8" x 6" MJ TEE COMPLETE WITH RESTRAINTS & CONCRETE BLOCKING	EA	2		
24.	8" MJ GATE VALVE COMPLETE	EA	2		
25.	8" 90° MJ BEND COMPLETE WITH RESTRAINTS & CONCRETE BLOCKING	EA	1		
26.	8" 45° MJ BEND COMPLETE WITH RESTRAINTS & CONCRETE BLOCKING	EA	1		
27.	8" 22.5° MJ BEND COMPLETE WITH RESTRAINTS & CONCRETE BLOCKING	EA	1		
26.	2" DR13.5 HDPE WATER MAIN	LF	150		
27.	2" SADDLE TAP	EA	1		

Item	Description	Unit	Quantity	Unit Price	Item Total
27.	8" x 6" STAINLESS STEEL FULL CIRCLE TAPPING SLEEVE & FLANGED BY MJ VALVE, COMPLETE	EA	1		
28.	8" x 8" STAINLESS STEEL FULL CIRCLE TAPPING SLEEVE & FLANGED BY MJ VALVE, COMPLETE	EA	1		
29.	CUT, CAP AND ABANDON EXISTING SMALL DIAMETER WATER MAIN	EA	1		
30.	CUT, CAP AND ABANDON EXISTING 6" AC WATER MAIN	EA	4		
31.	CUT, CAP AND ABANDON EXISTING 8" CI WATER MAIN	EA	2		
32.	SHORT SIDE 3/4" SERVICE RENEWAL COMPLETE TO EXISTING METER (INCLUDING SADDLE TAP, CURB STOP, SERVICE LINE & CORP. STOP)	EA	45		
33.	LONG SIDE 3/4" SERVICE RENEWAL COMPLETE TO EXISTING METER (INCLUDING SADDLE TAP, CURB STOP, SERVICE LINE, CORP. STOP & BORE)	EA	34		
34.	SHORT SIDE 2" SERVICE RENEWAL COMPLETE TO EXISTING METER (INCLUDING SADDLE TAP, CURB STOP, SERVICE LINE & CORP. STOP)	EA	2		
35.	LONG SIDE 2" SERVICE RENEWAL COMPLETE TO EXISTING METER (INCLUDING SADDLE TAP, CURB STOP, SERVICE LINE, CORP. STOP & BORE)	EA	2		
36.	WATER SERVICE CONNECTION FROM METER TO HOUSE COMPLETE WITH REQUIRED FITTINGS	EA	79		
37.	FIRE HYDRANT ASSEMBLY COMPLETE (WITH 6" X 6" HYDRANT TEE)	EA	8		
38.	FIRE HYDRANT ASSEMBLY COMPLETE (WITH 8" X 6" HYDRANT TEE)	EA	3		
39.	REMOVE AND STOCKPILE EXISTING FIRE HYDRANT (RETURN TO CITY OF GRIFFIN)	EA	9		
<b>Water Main Subtotal =</b>					
<b>SANITARY SEWER</b>					
40.	REMOVE EXISTING 8-INCH SANITARY SEWER MAIN COMPLETE, INCLUDING OFF-SITE DISPOSAL	LF	1,170		
41.	8-INCH DUCTILE IRON PIPE SANITARY SEWER MAIN	LF	1,170		
42.	8-INCH FERNCO STRON BACK RC 1000 SERIES COUPLINGS OR APPROVED EQUAL	EA	17		
42.	REMOVE EXISTING 12-INCH SANITARY SEWER MAIN COMPLETE, INCLUDING OFF-SITE DISPOSAL	LF	300		
43.	12-INCH DUCTILE IRON PIPE SANITARY SEWER MAIN	LF	300		
44.	4 FT. DIAMETER SANITARY SEWER MANHOLE INCLUDING RING/COVER (4FT. BASE SECTION)	EA	4		
45.	ADDITIONAL VERTICAL FOOTAGE OF 4 FT. DIAMETER SANITARY SEWER MANHOLE	VF	6		
46.	SANITARY SEWER LATERAL COMPLETE WITH WYE & 6" CLEANOUT AT EASEMENT/ROW (UP TO 25 LF)	EA	19		
47.	ADDITIONAL LINEAR FOOTAGE OF SANITARY SEWER LATERAL	LF	95		
<b>Sanitary Sewer Subtotal =</b>					
<b>PAVEMENT</b>					
48.	CONCRETE PAVEMENT PATCH (PER DETAIL)	SY	2,516		
49.	CONCRETE DRIVEWAY PATCH (PER DETAIL)	SF	1,008		
50.	CONCRETE & ASPHALT PATCH PER TYPICAL PAVEMENT PATCH DETAIL FOR APARTMENT COMPLEX	SY	368		
51.	1.5" 9.5MM SUPERPAVE ASPHALT OVERLAY	SY	17,425		
52.	ASPHALT MILLING	SY	17,425		
53.	SPEED HUMP REPAIR	EA	2		
54.	THERMOPLASTIC, 5-INCH TRAFFIC STRIPE, DOUBLE YELLOW	LF	5,466		
55.	THERMOPLASTIC, 10' WIDE CROSS WALK, WHITE	LF	26		
55.	THERMOPLASTIC, 24-INCH STOP BAR, WHITE	LF	156		
<b>Pavement Subtotal =</b>					

Item	Description	Unit	Quantity	Unit Price	Item Total
<b>EROSION CONTROL</b>					
56.	WATER SERVICE RENEWAL EROSION CONTROL INCLUDING PERMANENT GRASSING & MULCH	EA	83		
57.	INLET PROTECTION (Sd2-G)	EA	15		
58.	INLET PROTECTION (Sd2-F)	EA	1		
59.	GROUTED RIPRAP OUTLET PAD	EA	1		
60.	SEWER LATERAL RENEWAL EROSION CONTROL INCLUDING PERMANENT GRASSING & MULCH	EA	19		
61.	TYPE "C" SILT FENCE INCLUDING MAINTENANCE AND REMOVAL (Sd1-S)	LF	1,460		
62.	PERMANENT GRASSING INCLUDING MULCH	SF	13,004		
<i>Erosion Control Subtotal =</i>					
<b>MISCELLANEOUS</b>					
63.	6" CONCRETE CURB REPLACEMENT	LF	400		
64.	DESIGN AND CONSTRUCTION OF MODULAR BLOCK WING WALL	SF	20		
65.	TRENCH ROCK	CY	150		
66.	ADDITIONAL #57 STONE (IF NEEDED)	TN	100		
<i>Miscellaneous Subtotal =</i>					
<b>TOTAL CONSTRUCTION =</b>					