

City of Havelock
McCotter Canal Utility Stabilization
Addendum 2
August 20, 2018

Questions Received

1. The prints and specs. indicate live stakes "tubers" to be installed to anchor the geotextiles however the species of the live stakes was not indicated. Is there a particular species that the City would prefer?

Preferred species are:

- Cephalanthus occidentalis – Button Bush
- Salix nigra – Black willow
- Sambucus Canadensis – Elderberry

2. After visiting the site, it appeared to us that the canal bank has failed in areas outside of the 5 "areas of construction" which are impacting the access road. Do we need to include those areas in our estimate as well?

The bid should only include bank repairs for those areas presented in the bid documents.

3. There is a soil berm located on the south side the access road which is what we believe to be spoils for previous canal cleanings. Are we to include the removal of this berm for complete length of the road in our bid?

Removal of the berm from the complete length of the road is not proposed within the bid documents.

4. In order to access areas 3, 4, and 5, it appears the access road needs to be improved (see attached photos) is there any standard detail we need to improve the road too?

The section for completed access road is shown on Sheet D-02, in association with the drain basin details.