

SPALDING COUNTY  
LOCAL MAINTENANCE AND IMPROVEMENT GRANT  
RESURFACING PROJECT

FROM: SPALDING COUNTY  
PURCHASING  
119 EAST SOLOMON STREET  
GRIFFIN, GA 30223

TO: ALL BIDDERS OF RECORD

RE: Addendum No. 1, dated August 15, 2016

This Addendum forms a part of the Contract Documents and modifies the original Bidding Documents dated August 5, 2016.

This Addendum consists of two (2) pages

- Add. 1.1 Clarification: The application rate for 402-1802 RECYCLED ASPH CONC PATCHING, INCL BITUM MATL & H LIME is 330 lbs/sy.
- Add. 1.2 Clarification: The application rate for 402-1812 RECYCLED ASPH CONC LEVELING, INCL BITUM MATL & H LIME, TP 1 is 85 lbs/sy.
- Add. 1.3 Clarification: The application rate for 402-3100 RECYCLED ASPH CONC 9.5 MM SUPERPAVE, TP 1, GP 1, INCL BITUM MATL & H LIME is 165 lbs/sy.
- Add. 1.4 Clarification: All work shall be performed Monday – Friday between the hours of 7:00AM and dusk. Work may be performed on Saturday with prior written permission from Spalding County.
- Add. 1.5 Clarification: The Contractor shall install temporary pavement markings and allow the new asphalt surface to cure 30 – 45 days before installing permanent pavement markings. This cost for temporary markings may be included in the 150-1000 TRAFFIC CONTROL line item.
- Add. 1.6 Clarification: Spalding County will install any Low/Soft Shoulder signs needed for the project.
- Add. 1.7 Clarification: Spalding County will perform any road shoulder graded needed to backfill the new asphalt when paving is complete.
- Add. 1.8 Clarification: Portable advanced warning signs on spring-loaded stands are acceptable for this project.
- Add. 1.9 Clarification: To estimate quantities a road width of 22 feet was assumed for all roads. The actual road widths may vary from 20 – 22 feet in width.

Add. 1.10 Clarification: It is anticipated that Spalding County will issue the Notice to Proceed for the project on September 26, 2016.

End of Addendum No. 1