

Addendum #9

East Lake Community Center Renovations

CONTRACT NO. Y-17-005

Bid schedule per this Addendum

Pre-Bid Meeting January 9th, 2020 at 10:00am
Last Day for Questions January 17th, 2020
Bid Opening January 30th, 2020 at 2:00 pm

Clarifications:

SPECIFICATIONS

Specifications 28 3100 FIRE DETECTION AND ALARM:

- Paragraph 1.5.B.5. Delete this paragraph and substitute: "Currently licensed in the State of Tennessee by the Alarm Systems Contractors Board for the installation of Fire Alarm Systems. "
- Paragraph 2.1.D.1. Honeywell Fire Lite Systems Control Equipment and Gentech devices are not approved for use in this project.

DRAWINGS

Electrical

Electrical Sheet E0.01; ELECTRICAL SYMBOLS, FIRE CONTROLS DEVICE LEGEND:

- The third symbol in this section "Audible Water Flow Warning Horn" description is deleted. Replace the description with:
- "Strobe, light level 75cd unless otherwise noted. Mounted 95" A.F.F. or 12" below ceiling, whichever is lower. In areas with Lay-In Ceilings, strobes may be combined with a Strobe/Speaker mounted flush in the ceiling".
- The seventh symbol in this section "Strobe..." is replaced by the above indicated symbol on the plans.

Electrical Sheet E0.2; ELECTRICAL SITE PLAN:

- KEY NOTE 8: Add the following sentence to this key note:
Coordinate with Sprinkler Contractor for provision of an Audible Signal and signage mounted on the exterior of the building to be activated by the Water Flow alarm on the interior of the building. Furnish an audible device monitored, supervised and controlled by the Fire Alarm system if not otherwise provided by the Sprinkler contractor.

Electrical Sheet E4.0 FIRE ALARM PLAN:

- Fire Alarm Speakers in areas without lay-in ceilings are pendant mounted from structure at an elevation of 10'-0" A.F.F., except in the Gymnasium, where they are mounted from structure at an elevation of 20'-0" A.F.F.

Questions Received via Email:

- Request to approve CPI Translucent Wall and Roof Assemblies for this project.
 - Subject to compliance with requirements, this product appears to be an acceptable alternative.

END OF ADDENDUM #9