

Sullivan Central HVAC, Controls, and Switchgear Replacement

November 29, 2022

ADDENDUM 1

The Bid Documents dated November 14, 2022 are amended as follows:

CLARIFICATION

- 1.) All classroom units, whether horizontal or vertical cabinet type units, shall have CO₂ sensors to control the amount of outside air to the classrooms. The outside air fans will be variable speed and controlled by the unit controller with input from a room mounted CO₂ sensor. All wiring, sensors and interconnection shall be provided as a part of a complete and operating HVAC system. Coordinate location and length of conduit with electrical contractor for CO₂ sensor and thermostat.
- 2.) Piping to and from the pool dry air cooler that is exterior to the pool equipment room shall be painted schedule 40 carbon steel piping as sized on the drawings.
- 3.) Humidity sensor, thermostat, incoming outside air temperature, discharge incoming air temperature, and unit discharge temperature shall be provided with pool unit as shown on drawings. Conduit, wire, and interconnection for each of these devices with pool unit shall be coordinated with electrical contractor and engineer for exact placement in pool area based on manufacturer's recommendations. All items shall be installed as a part of a complete and functional pool area heater and dehumidification system.

END OF ADDENDUM 1