

REVISED - Addendum #1

**UPPER BLOOMERY SWAMP INTERCEPTOR: PHASE II - A**

**SEWER IMPROVEMENTS STATION 21+15.00 TO STATION 28+21.54**

<u>ITEM</u>	<u>QTY.</u>	<u>DESCRIPTION</u>	<u>BID UNIT PRICE</u>	<u>BID AMOUNT</u>
1	1	LS Mobilzation	\$	\$
2	1	LS Make Connection to Existing SSMH #9	\$	\$
3	90	LF 42-Inch Steel Casing (Bore and Jack) Under Hwy 42 to Include 24-Inch DIP (Protecto 401 Lined) Carrier Pipe, DIP Supplied by City	\$	\$
4	280	LF 24" Dia. PVC (PS46) Sewer (6-8) w/Stone Bedding, Install Only	\$	\$
5	280	LF 24" Dia. PVC (PS46)Sewer (8-10) w/Stone Bedding, Install Only	\$	\$
6	80	LF 24" Dia. PVC (PS46) Sewer (10-12) w/Stone Bedding, Install	\$	\$
7	20	LF 24" Dia. PVC (PS46) Sewer (12-14) w/Stone Bedding, Install	\$	\$
8	50	LF 12" Dia. PVC Sewer (10-12) w/Stone Bedding	\$	\$
9	1	EA 6' ID Manhole (12-14) w/Bury Depth (8-10)	\$	\$
10	1	EA 6' ID Manhole (12-14) w/Bury Depth (10-12)	\$	\$
11	1	EA 6' ID Manhole (14-16), Vented	\$	\$
12	1	LS Make 8" Dia. Connection to SSMH #11 from Existing SSMH #41049 on North Side of Hwy 42	\$	\$
13	1	LS Core Ex. SSMH #40028 for 12" Dia. PVC to SSMH #11	\$	\$
14	1	LS By-Pass Pumping As Required for All Proposed Sanitary Sewer Improvements Each Side of Hwy 42	\$	\$
15	1	LS Abandon Existing 15" Dia. Sewer Between Ex. SSMH #40026 and Ex. SSMH #40028 (Under Hwy 42) w/Flowable Fill	\$	\$
16	50	CY Select Backfill	\$	\$
17	1	LS Erosion Control as Shown on Plans per COW specifications	\$	\$
18	1	LS Seeding and Mulching	\$	\$
19	22	EA Anti-Flotation Collar (As Required)	\$	\$
20	25	TNS Additional Stone Bedding	\$	\$
<b>TOTAL CONSTRUCTION</b>			<b>\$</b>	

**Note 1: City shall supply all 24" pipe (PVC and DI) required to complete this project.** The 24" PVC is located near the project site at Hwy 42. The 24" DIP is located at the City of Wilson's Operations Center (1800 Herring Avenue). The selected contractor will be responsible for delivering all pipe to the job site. The delivery cost should be included in the pipe install line items above. City staff will assist with loading the material onto the selected contractors trailer at the Operations Center.

**Note 2: Addition Stone Bedding (Line Item #20) to be used for undercut excavation.** Additional undercut and stone shall only be installed upon approval be Engineer or Onsite City Inspector.