

## **Addendum #1**

Project Identification: ***Upper Bloomery Swamp Interceptor: Phase II-A  
Wilson, North Carolina***

Issue Date: ***May 9, 2023***

### Summary of Changes:

- Drawings revised. Sheets 1, 2 & 3 Only. In general, clarified location of anti-floatation collars, revised pipe material between Ex SSMH 9 to Proposed SSMH 10 to Ductile Iron (pipe still supplied by City), some note changes, and showed proposed easement locations.
- Bid tab revised to include a line item for additional stone bedding due to over excavation (Line Item 20).
- Revised bid tab quantity for anti-floatation collars to match revised plan sheets (quantity increased from 20 to 22).

### Other Question and Answers:

Q1. Was Ex MH #9 installed with a hole or must it be cored?

A1. Ex MH #9 was installed with a core and a 10' section of PVC pipe was installed with a cap. PVC pipe to be removed and replaced with the appropriate DI as shown on the plans. We do not anticipate the need to core the manhole again.

Q2. Would you consider adding a line item for Undercut Excavation with Stone

A2. Line Item 20 has been added to the bid sheet.

Q3. Will the City do the CCTV or do we sub it out?

A3. The City shall perform the CCTV inspection. Additionally, the contractor will not have to wait to pull the mandrel test for the PVC pipe. The mandrel may be pulled after the CCTV inspection is performed by the City.