




LAGRANGE

GEORGIA

To: Bidders for the LaGrange Thread Phase 2
From: Robi Higgins, LaGrange Purchasing Agent 
Date: September 19, 2017
RE: Granger Thread Project
Addendum Number 1 to the August 25, 2017 Bid Document

Below are clarifications on the "Issue for Bid" plan set and responses to questions received from contractors during the bidding process prior to September 19, 2017:

1. Question: "Can the project completion time be extended?"

Response: The City of LaGrange agrees to extend the project completion to 180 days rather than 120 days.

2. The City of LaGrange desires to have the option for self-performing asphalt removal. The bid item list has been revised to separate the cost of asphalt removal.
3. An alternate bid item for "3000 PSI concrete with mix to be approved by the city" has been added within the bid. See alternate within the bid item list.
4. Contractor to provide material cost of concrete for both "3000 PSI concrete, mix approved by city" and "Class A Concrete".

Attachments to Addendum Number 1 include:

- Revised bid item list

END OF DOCUMENT

LaGRANGE THREAD-PHASE 2 - BID FORM PROPOSAL

Section A: Roadway / Trail					
Item Number	Quantity	Units	Item Description	Unit Price	Cost
140-1000	1	LS	MOBILIZATION		
150-1000	1	LS	TRAFFIC CONTROL		
210-0100	1	LS	GRADING COMPLETE (INCLUDING DEMOLITION)		
310-5060	200	SY	GR AGGR BASE COURSE, 6 IN, INL MATL		
403-1000	1	LS	SAWCUT AND REMOVE EXISTING ASPHALT PAVEMENT AND DRIVEWAYS		
403-1010	1	LS	REMOVAL OF ASPHALT PAVEMENT		
404-1000	1	LS	REMOVE EXISTING CURB AND GUTTER		
405-1000	1	LS	TREE CLEARING		
444-1000	7887	LF	SAWED JOINTS IN EXISTING PAVEMENTS -PCC		
441-6012	235	LF	CURB AND GUTTER 6"X24", TP2		
441-5002	235	LF	CONCRETE HEADER CURB, 6 IN TP 2		
500-3101	1700	CY	CLASS A CONCRETE TRAIL, 5 IN, 12 FT, (INCL ADA RAMPS)		
500-3102	5	CY	CLASS A CONCRETE TRAIL, 8 IN, HEAVY DUTY (STA 58+40)		
999-5200	13	EA	DETECTABLE WARNING PADS (BRICK PAVERS)		
652-0095	2	EA	THERMOPLASTIC PVMT MARKING, HANDICAP SYMBOL		
652-5301	260	LF	THERMO SOLID TRAF STRIPE, 8 IN, (GDOT CROSSWALKS)		
652-6502	7887	LF	SKIP TRAF STRIPE, 5 IN, YELLOW (TRAIL CL)		
6523-1500	350	LF	THERMOPLASTIC SOLID TRAF STRIPE, 5 IN, WHITE		
653-1704	12	LF	THERMOPLASTIC SOLID TRAF STRIPE, 24 IN WHITE (STOP BARS)		
900-000	2	EA	CONC. WHEEL STOPS		
900-0526	15	EA	FIXED STEEL BOLLARDS		
900-0527	16	EA	REMOVABLE STEEL BOLLARDS		
Section A Sub Total					

Section B: Bridges / Retaining Walls					
Item Number	Quantity	Units	Item Description	Unit Price	Cost
445-1001	1	LS	BRIDGE 1 (STATION 12+00)		
445-1002	1	LS	RETAINING WALL 1 (STATION 5+75)		
Section B Sub Total					

Section C: Erosion Control / Storm Drainage					
Item Number	Quantity	Units	Item Description	Unit Price	Cost
163-0300	13	EA	CONSTRUCTION EXIT		
163-0310	3	EA	TEMPORARY REFUELING AREA		
163-0320	11	EA	TEMPORARY CONC. WASHDOWN		
163-0529	550	LF	CONSTRUCT, REMOVE COMPOST FILTER SOCK CHECK DAM		
163-0550	6	EA	CONSTRUCT, REMOVE, MAINT INLET SEDIMENT TRAPS -TYPE F		
163-0550	3	EA	CONSTRUCT, REMOVE, MAINT INLET SEDIMENT TRAPS-TYPE B		
164-001	7,000	LF	NON-SENSITIVE TYPE SEDIMENT BARRIERS		
164-002	5,000	LF	SENSITIVE TYPE SEDIMENT BARRIERS		
165-0030	6,000	LF	MAINT OF TEMPORARY SILT FENCE/COMPOST SOCK		
165-0101	7	EA	MAINT OF CONSTRUCTION EXIT		
164-003	45,000	SF	SLOPE STABILIZATION		
164-004	1,200	TN	RIVER ROCK OUTLET PROTECTION, GADOT TYPE 3 EQUIVALENT		
164-005	6,000	SF	ROCK OUTLET PROTECTION GEOTEXTILE FABRIC		
167-1000	1	LS	WATER QUALITY MONITORING AND SAMPLING		
167-1010	1	LS	EROSION CONTROL INSPECTIONS, WEEKLY AND MONTHLY		
550-1120	350	LF	STORM DRAIN PIPE, 12 IN, HDPE, H 1-10		
550-4112	4	EA	FLARED END SECTION, 12 IN, HDPE, STORM DRAIN		
550-1150	40	LF	STORM DRAIN PIPE, 15 IN, HDPE, H 1-10		
550-4115	2	EA	FLARED END SECTION, 15 IN, HDPE, STORM DRAIN		
550-1180	250	LF	STORM DRAIN PIPE, 18 IN, HDPE, H 1-10		
550-4280	2	EA	FLARED END SECTION, 18 IN, HDPE, STORM DRAIN		

500-3200	1	EA	IN PLACE CONCRETE HEADWALL OR PRECAST 18 IN, HDPE WITH ENERGY DISSIPATING BLOCKS		
550-1240	250	LF	STORM DRAIN PIPE, 24 IN, HDPE, H 1-10		
550-4124	3	EA	FLARED END SECTION, 24 IN, HDPE, STORM DRAIN		
550-4140	1	EA	JUNCTION BOX		
550-4150	1	EA	PEDESTAL TOP D.I.		
550-4160	2	EA	GRATE INLET, USF 4640-6494 FRAME & GRATE		
700-6910	5	AC	PERMANENT GRASSING		
700-8000	6	AC	FERTILIZER MIX GRADE		
Section C Sub Total					

Section D: Allowances					
Item Number	Quantity	Units	Item Description	Unit Price	Cost
999-1000	1	ALLOW	MISCELLANEOUS CONSTRUCTION	\$30,000.00	
999-1001	1	ALLOW	UNFORSEEN CONDITIONS	\$30,000.00	
Section D Sub Total					

Section A Sub Total					
Section B Sub Total					
Section C Sub Total					
Section D Sub Total					
TOTAL ESTIMATED CONSTRUCTION COST					