

Bid #4788 Concrete Pad
Third set of Questions and Answer
August 30, 2017

1. Q: Vapor barrier
A: Yes

2. Q: Sawing expansion joints and sealing concrete
A: Yes

3. Q: Larger PEMB column footings
A: 2' x 2' x 16" deep, will have exact location when building plans are provided by vendor.

4. Q: Provide/install anchor bolts for columns
A: Not necessary, building contractor can drill and install bolts.

5. Q: Rebar reinforcement in perimeter footing
A: Yes, 2 x #4

6. Q: Engineer stamped plans
A: No, have plans