



Georgetown County, South Carolina

129 Screven Street, Suite 239
Post Office Drawer 421270
Georgetown, SC 29442-4200
(843) 545-3083 • Fax (843) 545-3500
E-Mail • purch@gtcounty.org
Website • <http://www.gtcounty.org>

ADDENDUM #1 TO Bid #23-030

BID NUMBER: 23-030

ISSUE DATE: Friday, June 16, 2023

(REVISED) OPENING DATE: Wed., June 28, 2023 OPENING TIME: 3:00 PM ET

Pre-Bid Conference/Site Inspection: [None]

PROCUREMENT FOR: Fabrication/Installation of Stormwater Outfall Improvements at Georgetown County Landfill

This addendum will amend **Bid #23-030, Fabrication/Installation of Stormwater Outfall Improvements at Georgetown County Landfill** originally issued on Monday, June 5, 2023. This clarification is being provided to all known and registered correspondents in response to questions received. All addenda and original bid documents are also available online at: www.gtcounty.org, select "Bid Opportunities" from the Quick Links section.

Question 1: Please clarify the following regarding the above bid. The drawings show Basin A and Basin B, but you only want bids for Basin A?

Response: Yes, the drawings show both but we only want bids for Basin A.

Question 2: Regarding Basin A, the scope of work measurements differ a bit than that of the drawings. Do you want the measurements as they appear on the drawings?

Response: Please use the following measurements:

One (1) – 42" inch Diameter 12 GA 3"x1" corrugation aluminum risers
x 5.0' **(Corrected from 6' to 5.0')** high with ½ inch diameter perforations on 3 inch centers in bottom half of riser.

One (1) trash rack 60"inch diameter (Confirmed diameter trash rack A- field and drawings "section c-c") x 3ft (Corrected from 2 ft. to 3 ft. (36in) high) trash rack with the support bars at 18 inches (half way)

52LF – 30"inch diameter 12 GA, 2 2/3" x 1/2" corrugation, flanged joint aluminum outlet pipe

Question 3: The gauge stated in the scope of work as 12 gauge is shown as 14 gauge on the drawings. Which is correct?

Response: Yes, we want 12 gauge instead of 14.

Question 4: Is it acceptable to use Anti-Seeps plates designed to bolt between two flanges (same hole pattern)?

Response: Yes, this is acceptable as equivalent.

Question 5: Are you considering extending the deadline for this bid submission?

Response: Yes, we can extend the deadline by an additional week to allow additional time for firms to put together their proposals after receipt of this addendum. See revised bid opening date & time below.

Time Line: Invitation for Bid #23-030

Item	Date	Time	Location*
Advertised Date of Issue:	Monday, June 5, 2023	n/a	n/a
Pre-Bid Site Inspection:	By Prior Appointment Only	n/a	Landfill
Deadline for Questions:	Wednesday, June 14, 2023	3:00PM ET	n/a
(REVISED) Bids Must be Received on/or Before:	Wednesday, June 28, 2023	3:00PM ET	Electronic
(REVISED) Public Bid Opening & Tabulation:	Wednesday, June 28, 2023	3:00PM ET	Hybrid



ADDENDUM ACKNOWLEDGEMENT

Bid #23-030

**Fabrication/Installation of Stormwater Outfall Improvements at
Georgetown County Landfill
Mandatory Submittal Form**

To be returned with the final proposal submission to Georgetown County.

COMPANY NAME: _____

- Addendum #1 Received Date: _____ Initialed By: _____
- Addendum #2 Received Date: _____ Initialed By: _____
- Addendum #3 Received Date: _____ Initialed By: _____
- Addendum #4 Received Date: _____ Initialed By: _____
- Addendum #5 Received Date: _____ Initialed By: _____
- Addendum #6 Received Date: _____ Initialed By: _____