BID PROPOSAL FOR ITB 2018-003 NW 105th Way (SW-0125) Drainage Improvements

Bid prices stated in the proposal include all costs and expenses for labor, equipment, materials, contractor's overhead, and profit. Payment for this project will be based upon completion of the entire project as a unit price contract, in accordance with the Project Manual.

BID FORM

02-01-2018 Revision 2

ITEM NO.	ITEM DESCRIPTION	EST. QTY	UNIT	UNIT COST	TOTAL COST
	Demolition				
101-1	Mobilization (2% of budget)	1	L.S.	L.S.	
102-1	Maintenance of Traffic (2% of budget)	1	L.S.	L.S.	
104-18	Storm Water Pollution Prevention & Erosion Control per Catch Basin	19	EA.		
	Removal of Drainage Items (Pipe and Catch Basin)	1	L.S.		
				Sub-Total	

	Paving , Grading and Drainage				
125-1	Excavation for Structures	1,397	C.Y.		
110-4-1	Existing Asphalt to be removed	5,095	S.Y.		
334-1-13	Asphalt Concrete, Type SP-9.5 (2" Thick)	509	TON		
	Inlet Curb Type (D-3-SD 2.2) P< 10'	16	EA.		
	Inlet Curb Type (D-1-SD 3.1) P< 10'	2	EA.		
	Inlet Curb Type (SD 2.6) J< 10' w/ USF 4700-6223	1	EA.		
	Pollution Retardant Baffles	17	EA.		
425-2-41	Manholes Type P-7 < 10'	10	EA.		
430-175-118	Solid Pipe 18" diameter H.D.P.E	679	L.F.		
443-70-3	Exfiltration Drain (18" perforated pipe)	851	L.F.		
	As-Built (Entire Project)	1	L.S.		
	Survey (Entire Project)	1	L.S.		
	Utility Verification Prior to Construction of Drainage Structures	1	L.S.		
				Sub-Total	
	·	•			
	Pavement Marking and Signage				
706-3	Retro-Reflective Pavement Marker (Yellow/Yellow)	50	EA.		
711-11-121	6" White (Thermoplastic)	2,401	L.F.		

711-11-124	18" White (Thermoplastic)	31	L.F.		
711-11-125	24" White Stopbar (Thermoplastic)	22	L.F.		
711-11-221	6" Double Yellow (Thermoplastic)	2,070	L.F.		
				Sub-Total	

Subtotal Amount		
Bond & Insurance (2% of subtotal amount)		
TOTAL PROJECT COST:		

A. Subtotal (NW 105th Way DRAINAGE IMPROVMENTS)

B. 10% Continency Allowance (10% of A)

Grand Total (Add A+B)

Written Bid Amount:

The total contract time is 180 calendar days to Final Completion from Notice to Proceed.