



**CITY OF CALLAWAY  
JAN DR. & GENEVIEVE AVE.  
DRAINAGE IMPROVEMENTS  
BID NO: PW2022-13**

**ADDENDUM #1**

Date Issued: July 19, 2022

This addendum is being released to provide clarification for the following:

- 1. There are existing driveways that will need to be removed and replaced in order to install the new Storm pipe. Do you want us to repave these once installing new pipe or would you like us to just install lime rock and bring it to grade to be paved on a future project?
  - A. The contractor will need to patch/reconstruct open cuts back to original condition whether asphalt roadway or concrete driveway. These items are considered incidental to pipe install and should be reflected in the unit cost provided in your bids.

The following are from the general notes which are pertinent to the question.

**CONSTRUCTION PLANS  
TASK 2 - Genevieve Drainage Piping  
Page G-001 General Notes**

- 3. All roads damaged by construction operations are to be patched or reconstructed as directed by the Project Administrator or designee.
- 26. All concrete driveway turnouts are to be constructed as Type G1 per FDOT Standard Plans Index 522-003 unless otherwise noted on the plans.
- 27. All ramps and driveways must meet ADA compliance and must be built to current Florida Design Standards.

Janice L. Peters  
Janice L. Peters, City Clerk

\*\*\*\*\*

This Addendum must be acknowledged and included with the bid packet submission.

\_\_\_\_\_  
Signature

\_\_\_\_\_  
Company Name

\_\_\_\_\_  
Date