



**CITY OF CALLAWAY
CHERRY STREET RESURFACING, SIDEWALKS
& DRAINAGE IMPROVEMENTS
BID NO: PW2022-14**

ADDENDUM #1

Date Issued: August 18, 2022

This addendum is being released to amend the attached Bid Certification Form page 4.

Item 30 Bedding Stone FDOT #053474 590 tons (amount)

Janice L. Peters
Janice L. Peters, City Clerk

This Addendum must be acknowledged and included with the bid packet submission.

Signature

Company Name

Date

**TASK – 3 CHERRY STREET DRAINAGE IMPROVEMENTS
TYNDALL PARKWAY TO STAR AVENUE**

ITEM	DESCRIPTION	QTY	UNIT	UNIT PRICE	AMOUNT
1	Sediment Barrier	15,862	LF		
2	Inlet Protection System	62	EA		
3	Remove Existing Pipe	5,327	LF		
4	Remove Existing Inlet	63	EA		
5	Excavation for Structures	1,615	CY		
6	Type P-3 Curb Inlets	32	EA		
7	Type J-3 Curb Inlets	22	EA		
8	Type P-4 Curb Inlets	7	EA		
9	Type J-4 Curb Inlets	5	EA		
10	DOT Type C Ditch Bottom Inlet	4	EA		
11	DOT Type C Ditch Bottom Inlet J Bottom	2	EA		
12	DOT Type H Ditch Bottom Inlet	2	EA		
13	Drainage Junction Box P	1	EA		
14	Drainage Junction Box J	3	EA		
15	18" Concrete MES	3	EA		
16	19" x 30" Concrete MES	1	EA		
17	24" x 38" Concrete MES	2	EA		
18	Modify Existing Drainage Structure	11	EA		
19	18" Pipe Culvert	2,806	LF		
20	24" Pipe Culvert	1,662	LF		
21	30" Pipe Culvert	1,057	LF		
22	36" Pipe Culvert	1,587	LF		
23	42" Pipe Culvert	360	LF		
24	14" x 23" Pipe Culvert	35	LF		
25	19" x 30" Pipe Culvert	423	LF		
26	24" x 38" Pipe Culvert	990	LF		
27	29" x 45" Pipe Culvert	615	LF		
28	38" x 60" Pipe Culvert	446	LF		
29	Sod	3,080	SY		
30	Optional Base Group 9 Bedding Stone FDOT #053474	4,440 590	SY Tons		
B - BID SUBTOTAL FOR DRAINAGE					

BONDS & INSURANCE COSTS \$ _____

MOBILIZATION & GENERAL CONDITIONS \$ _____

A – BID SUBTOTAL RESURFACING & SIDEWALK \$ _____

B – BID SUBTOTAL FOR DRAINAGE (TASK 3) \$ _____

TOTAL BID \$ _____