

II. ARLINGTON COUNTY DES ENGINEERING
SPECIAL CONDITIONS

Contents

PROJECT SUMMARY.....	3
SUPPLEMENTS TO THE GENERAL CONDITIONS	4
ARTICLE B – DRAWINGS, SPECIFICATIONS AND RELATED DATA	4
SC-B.10 TESTS.....	4
SC-B.13 SURVEYS AND CONTROLS	4
SC-B.14 AS-BUILT DRAWINGS.....	5
ARTICLE C – COUNTY, COUNTY PROJECT OFFICER, AND CONTRACTOR RELATIONS.....	6
SC-C.4 INSPECTION OF WORK	6
SC-C.9 SUPERINTENDENCE BY CONTRACTOR	6
SC-C.13 PROTECTION OF WORK AND PROPERTY.....	7
ARTICLE E – LEGAL RESPONSIBILITY AND PUBLIC SAFETY	7
SC-E.1 SITE INVESTIGATION AND CONDITIONS AFFECTING THE WORK.....	7
SC-E.2 PUBLIC CONVENIENCE	7
SC-E.10 SITE CLEAN-UP AND WASTE DISPOSAL.....	9
SC-E.11 STORMWATER POLLUTION PREVENTION PLAN (SWPPP).....	9
ARTICLE F– PROGRESS AND COMPLETION OF THE WORK	10
SC-F.2 TIME FOR COMPLETION.....	10
ARTICLE G– MEASUREMENT AND PAYMENT.....	11
SC-G.1 PAYMENTS TO CONTRACTOR.....	11
SPECIAL CONDITIONS.....	12
1. CONSTRUCTION STANDARDS.....	12
2. PERMITS	13
3. SPECIAL CONTRACTOR/SUBCONTRACTOR QUALIFICATIONS	14
4. STAKEOUT AND CUT-SHEETS	14
5. SCHEDULE, DURATION, AND PHASING REQUIREMENTS	14
6. WORK HOURS.....	15
7. GENERAL SITE SECURITY AND CONTROLS.....	15

8. SPECIAL TRAFFIC MAINTENANCE CONSIDERATIONS 16

9. TRAFFIC SIGNALS AND STREETLIGHTS 16

10. BIORETENTION CONSTRUCTION AND MATERIALS 17

11. WORK ASSIGNMENTS..... 17

12. UNLISTED WORK 17

13. JOB SIZE LIMITATION & ESTIMATED ACTIVITY 17

14. OTHER COUNTY CONTRACTS 17

15. OTHER SPECIAL PROVISIONS..... 17

SUPPLEMENTS TO THE DES CONSTRUCTION STANDARDS AND SPECIFICATIONS..... 18

Supplemental Specifications List 19

PROJECT SUMMARY

This contract contains two Arlington County Projects. 12th Street South Complete Streets (CC16) and Transitway Extension to Pentagon City (MA13). These two projects will be constructed concurrently.

The 12th Street South Complete Streets project is along 12th Street South in Crystal City between South Eads Street and Long Bridge Drive. The project reconfigures the street section as a multimodal complete street featuring transit, environmental, and pedestrian facilities. The improvements include: installing sidewalks, asphalt pavement, street lights, storm water infrastructure improvements, landscaping, and traffic signals.

The Transitway Extension to Pentagon City project starts at Crystal Drive and 15th Street South and ends at 12th Street South and Long Bridge Drive. This project will have a designated bus only lane, which will be provided by restriping and removing the on-street parking currently located along Crystal Drive and 12th Street South. Two new Transit Stations are proposed, one on Crystal Dr north of 15th Street and another one on 12th Street and Long Bridge Drive. The construction will include a near level boarding platform, detectable warning surfaces, ADA accessibility features, prefabricated bus shelters, amenities such as benches, bike racks and trash receptacles and street improvements. A concrete bus pad will replace existing asphalt roadway pavement, in the roadway, in front of transit station to accommodate the additional loading in this area. The entire project area will include restriping to accommodate the bus lanes and new traffic patterns.

The Transitway transition at Crystal Drive and 12th Street S requires curb and road improvements in order to provide adequate road width for bus movements. Proposed curb improvements are proposed on the west side and east side of the roadway. The ramps and the curbs will be constructed to comply with ADA requirements. Rapid Flashing Beacons (RBF) are proposed at the proposed crosswalk to increase visibility.

The Contractor shall provide all resources to successfully perform the terms of this contract in accordance with project plans, and in compliance with Arlington County and VDOT Standards and Specifications. The Contractor shall perform the work complete, in place, tested, and ready for continuous service.

All work within the VDOT Right-Of-Way shall be performed in accordance with the VDOT Standards and Specifications, unless otherwise noted. All work within the County Right-Of-Way shall be in accordance with the Arlington County Standards and Specifications, unless otherwise noted.

Click or tap here to enter text.

SUPPLEMENTS TO THE GENERAL CONDITIONS

These Conditions modify the Arlington County Construction General Conditions. All provisions that are not modified or deleted by these Supplemental Conditions shall remain in full force and effect.

The address system used in these Supplemental Conditions is the same as the address system used in the General Conditions, with the prefix "SC" added thereto.

ARTICLE B – DRAWINGS, SPECIFICATIONS AND RELATED DATA

SC-B.10 TESTS

Add the following new language to Paragraph B.10:

All materials testing shall be in compliance with the Arlington County Materials Testing Specification Reference. This document specifies the method and frequency of testing for Arlington County projects. A copy of this document is included in the bid documents. This shall be incidental to the work and no separate payment will be made.

The Contractor shall engage the services of a geotechnical company, acceptable to both the County and VDOT, to conduct all materials testing per the County and VDOT Specifications.

If it is observed that samples for testing are being improperly taken or that samples are being taken from an area that is not fully representative of all project conditions, then Contractor shall take and test additional samples at the County Project Officer's request from areas designated by the County Project Officer and at the Contractor's expense.

In addition, the Contractor shall provide the County with unfettered site access as needed for VDOT/County personnel or VDOT/County consultants to enter the site, inspect, and perform any additional testing for any and all materials (including soil, concrete, asphalt, etc.).

Compaction results must meet VDOT Specifications and be certified by a Geotechnical Engineer licensed in Virginia. This work shall be at no cost to the County.

SC-B.13 SURVEYS AND CONTROLS

Delete Paragraph B.13 in its entirety and insert the following in its place:

Unless otherwise stated, the County will provide horizontal and vertical reference points necessary for the Contractor to proceed with the Work. The Contractor shall carefully preserve all reference points, and in the case of destruction thereof by the Contractor or

ITB No. XXXXX

due to the negligence of the Contractor or of any subcontractor, the Contractor shall be responsible for expense and damage resulting therefrom and shall be responsible for any mistakes or construction errors that may be caused by the loss or disturbance of such reference points. The Contractor shall be responsible for laying out the Work and shall retain a professional land surveyor licensed in the Commonwealth of Virginia to survey and provide all necessary construction layouts and to establish all control lines, grades, and elevations during construction.

SC-B.14 AS-BUILT DRAWINGS

ARTICLE C – COUNTY, COUNTY PROJECT OFFICER, AND CONTRACTOR RELATIONS

SC-C.4 INSPECTION OF WORK

Add the following new language to Paragraph C.4:

Contractor shall notify the Project Officer at least 3 working days prior to disturbing any existing, or installing any new, traffic signs, signals, or other traffic control devices. The Contractor shall allow 3 working days for the inspection and approval of the premarkings prior to placing the permanent markings.

SC-C.9 SUPERINTENDENCE BY CONTRACTOR

Add the following new language to Paragraph C.9:

Site Supervisor:

The Contractor shall have a qualified and experienced site supervisor who can clearly communicate technical matters on-site at all times when construction activity is occurring or when the site is not in a secure state.

Safety Project Officer:

The Contractor shall have at least one (1) employee certified by VDOT in Basic Work Zone Traffic Control on-site at all times that work is occurring and be responsible for the following:

- Placement, maintenance, and removal of work zone traffic control devices,
- Compliance with permit requirements and conditions, approved plans and specifications, the Virginia Work Area Protection Manual, and the Manual of Uniform Traffic Control Devices.

The flagger shall be certified in accordance with the VDOT Flagger Certification Program, the American Traffic Safety Services Association Flagger Certification Program or any other VDOT approved flagger program. The flagger shall have his/her certification card with them at all times while performing flagging activities.

The Contractor shall have at least one (1) employee certified in OSHA 10 on-site at all times that work is occurring. The employee shall have served as a Project Safety Officer on at least three (3) prior projects. If the contractor has multiple employees with these requirements, the Contractor shall clearly identify which employee shall serve as the Project Safety Officer.

Environmental Project Officer:

ITB No. XXXXX

The Contractor shall have at least one (1) employee that has successfully completed the VDOT Erosion & Sediment Control Contractor Certification training. The contractor employee shall be on-site during all land disturbance activities. The Contractor shall be responsible for ensuring compliance with all applicable local, State, and Federal erosion and sediment control regulations and permits during land disturbance activities.

If the Contractor proposes to deviate from the approved Erosion and Sediment Control Plan, it shall be the Contractor's responsibility to coordinate and obtain approval from the County Project Officer prior to implementing any changes.

SC-C.13 PROTECTION OF WORK AND PROPERTY

Add the following new language to Subparagraph C.13.c:

The Contractor shall be responsible for all damages caused by their construction activities. The Contractor shall perform or provide repairs, replacements, and restoration to all property that has been damaged resulting from construction operations performed by the Contractor, and shall meet the following requirements:

1. Restore all areas to conditions that existed prior to construction. Remove and Replace damaged items with items equal to or better than the damaged items.

ARTICLE E – LEGAL RESPONSIBILITY AND PUBLIC SAFETY

SC-E.1 SITE INVESTIGATION AND CONDITIONS AFFECTING THE WORK

Add the following new language at the end of E.1:

When construction activity reaches in proximity to existing utilities, the trench(es) shall be opened a sufficient distance ahead of the work or test pits shall be made to verify the exact location and inverts of the utility to allow for possible changes in the line or grade as directed by the Project Officer. This shall be incidental to the work and no separate payment shall be made.

SC-E.2 PUBLIC CONVENIENCE

Add the following new language to Paragraph E.2:

The Contractor shall set up controls at the beginning of each work day and take down controls at the end of each work day for the duration of the project. At all times the Contractor shall maintain safe two-way vehicular traffic, and safe accessible pedestrian traffic in conformance with County and VDOT standards.

At all times the Contractor shall use the personnel and traffic control signs and devices necessary to comply with the Virginia Work Area Protection Manual and Part VI of the

"National Manual on Uniform Traffic Control Devices." The Contractor has sole responsibility for ensuring that its operations are conducted in a safe manner and notwithstanding any other provision to the contrary, shall fully indemnify Arlington County, its officers, agents and employees for any damage or injury related to traffic operations which is caused by negligent or otherwise improper or deficient performance under the Contract or nonperformance of the terms of the Contract. All personnel, signs, barricades and any other items necessary for the maintenance of traffic and safety shall be provided by the Contractor.

When conditions warrant due to traffic volumes, patterns, or special events, the County may suspend or otherwise direct the Contractor's activities to protect the public and or the County's transportation network.

When the project includes a VDOT and/or County approved MOT Plan (or Plans), the Contractor shall strictly abide by this plan. If the Contractor proposes to deviate from the approved MOT Plan for a County road, it shall be the Contractor's responsibility to coordinate and obtain approval from the County Project Officer prior to implementing any changes. If the Contractor proposes to deviate from the approved MOT Plan for a VDOT road, it shall be the Contractor's responsibility to coordinate and obtain approval directly from VDOT prior to implementing any changes.

Prior to any lane closures within the VDOT Right-of-Way, the County Project Officer and VDOT Field Inspector must be notified in advance of such lane closure in accordance with VDOT requirements.

The Contractor shall not be entitled to any additional payment for changes to MOT which are the result of the Contractor's work schedule or resource allocation, weather delays, or other factors not controlled by the County.

Failure of the Contractor to correct any MOT deficiency immediately upon notification may result in the project being shut down until the deficiency is corrected, and a reduction from the amount of payment due in the amount of \$1,000.00 per violation. Repeated violations of this provision may result in contract termination.

The Contractor shall install project information signs (size - 36"x48") at least two (2) different locations for each site. Signs will be supplied by the County. Sign posts and incidentals necessary for a complete installation of the signs shall be furnished by the Contractor. Signs shall be installed at least two (2) weeks prior to the start of the construction. The Contractor shall coordinate the location of the signs with the Project Officer. After the project has been completed the Contractor shall remove and return the signs to the County Project Officer. The cost for this work shall be considered incidental to other items within the Contract and no separate payment will be made.

At the close of each work day, the area of work shall be confined to the smallest area possible, but in no event larger than the area designated in the Construction Documents, so that the maximum use of the street and sidewalk shall be restored and the hazard to traffic reduced to the minimum.

The Contractor shall preserve all bus stops, including maintaining adequate accessibility through and adjacent to the construction for buses and their passengers. The Contractor shall not close, relocate, or otherwise modify a bus stop without prior request of the Project Officer. Any relocation or closure of a bus stop will require at least four weeks advance notice for coordination with the county's bus stop coordinator.

SC-E.10 SITE CLEAN-UP AND WASTE DISPOSAL

Add the following new language to Paragraph E.10:

The County's Earth Products Recycling Yard (located at 4300 29th Street South, Arlington, VA) shall **not** be used on an as-needed basis for unspecified quantities of waste (due in part to the limited size of the Yard). Although atypical, the Yard **may** be considered, on a case-by-case basis, for disposal of specific types/quantities of waste from County construction projects. In such cases disposal arrangements must be approved by the County Project Officer, be made in advance, depend on available space and the type/quantity of waste, and comply with certain requirements (for example, concrete shall be broken into pieces no longer than 24" in any dimension, contain less than 20% soil content, and be free of rebar).

SC-E.11 STORMWATER POLLUTION PREVENTION PLAN (SWPPP)

Delete Paragraph 2.

ARTICLE F— PROGRESS AND COMPLETION OF THE WORK

SC-F.2 TIME FOR COMPLETION

Delete Paragraph F.2 and replace with the following language:

It is hereby understood and mutually agreed by and between the Contractor and the County that the Commencement Date, the rate of progress, and the Time for Completion of the Work to be done hereunder are essential conditions of the Contract. The Contractor agrees that the Work shall be started promptly upon receipt of a written Notice to Proceed in accordance with the accepted schedule. Additional time shall not be allowed for holidays or weather delays except as allowed in the contract.

Click or tap here to enter text.

ARTICLE G– MEASUREMENT AND PAYMENT

SC-G.1 PAYMENTS TO CONTRACTOR

Add the following new language to Section G.1:

Payments will be based on actual quantities and site measurements of the approved work taken in the field by the County Project Officer using the Contract Unit Prices. Any Work that is not shown on the approved plans that has not been previously authorized in writing by the Project Officer shall be at the Contractor's expense, and at no cost to the County.

Payment applications shall be submitted monthly including a detailed description of work performed services and products and the dollar amount. An updated schedule must accompany each application for payment. Arlington County Standards 01320.1.7.H

SPECIAL CONDITIONS

These Special Conditions include any project-specific requirements in addition to the General Condition, Supplementary Specifications, and the County Standards Referenced herein.

1. **CONSTRUCTION STANDARDS**

All work shall conform to project plans and specifications along with the current edition of following County and VDOT construction standards and specifications:

- **The Arlington County Department of Environmental Services (DES) Bike Parking Standards**, a copy of which may be downloaded at no charge from the internet at: <https://info.arlingtontransportationpartners.com/arlington-county-bike-parking-standards>
- **The Arlington County Department of Environmental Services (DES) Construction Standards and Specifications**, a copy of which may be downloaded at no charge from the internet at: <http://topics.arlingtonva.us/building/construction-standards-specifications/>
- **The Arlington County Department of Environmental Services (DES) Traffic Signal Specifications**, a copy of which may be downloaded at no charge from the internet at: <https://transportation.arlingtonva.us/traffic-signal-specification-updates/>
- **The Arlington County Department of Environmental Services (DES) Streetlight Specifications**, a copy of which may be downloaded at no charge from the internet at: <https://transportation.arlingtonva.us/streets/street-lights/lighting-standards-specifications-updates/>
- **The Arlington County Department of Environmental Services (DES) Pavement Marking Specifications**, a copy of which may be downloaded at no charge from the internet at: <https://transportation.arlingtonva.us/streets/street-maintenance/>
- **The Arlington County Department of Parks and Recreation (DPR) Specifications**, a copy of which may be downloaded at no charge from the internet at: <http://parks.arlingtonva.us/design-standards/>
- **The Virginia Department of Transportation (VDOT) Road and Bridge Standards and Specifications**, a copy of which may be downloaded at no charge from the internet at: <http://www.virginiadot.org/business/const/spec-default.asp>
- **The Virginia Work Area Protection Manual (WAPM)**, a copy of which may be downloaded at no charge from the internet at: <http://www.virginiadot.org/business/trafficeng-WZS.asp>
- **Manual on Uniform Traffic Control Devices(MUTCD)**, a copy of which may be downloaded at no charge from the internet at: http://mutcd.fhwa.dot.gov/pdfs/2009r1r2/pdf_index.htm

- **The Arlington County Department of Environmental Services (DES) Dechlorination and Disposal Procedures**, a copy of which may be downloaded at no charge from the internet at: <http://topics.arlingtonva.us/building/discharging-chlorinated-water/>
- **The Arlington County Department of Environmental Services (DES) Bus Stop Guidelines and Standards Manual**, a copy of which may be downloaded at no charge from the internet at: https://projects.arlingtonva.us/wp-content/uploads/sites/31/2021/03/DES-Bus-Stop-2020-03-17-FINAL_Guidelines_and_Standards.pdf
- **The Supplementary Specifications listed within the Contract.**

In case of a discrepancy, the following order of priority will apply, with the highest governing item appearing first and the least governing item appearing last:

The Contract Bid Items
 Special Conditions
 Contract Drawings
 Supplemental Specifications
 Arlington County Construction Standards and Specifications
 External Agency Specifications

2. PERMITS

Permits required for the project include, but are not limited to:

- **County Land Disturbing Activities (LDA) permit**
- **County Public Right-Of-Way (PROW) permit**
- **County Transportation Right-Of-Way(TROW) permits**
- **County Water Meter and Fire Hydrant permits**
- **County Building Permit**
- **County Electrical Permit**

All fees for County permits will be waived by Arlington County, and fees for non-County permits will be paid by Arlington County.

The County will obtain the County LDA and Building permit prior to the start of work. The Contractor shall transfer the County LDA and County Building permit in the Contractors name as the permittee and/or responsible party prior to the start of Work.

The Contractor shall provide a Responsible Land Disturber (RLD) that meets all the required qualifications of the permits. The Contractor shall complete and sign the RLD certificate and submit to the County Project Officer prior to the start of Work.

The Contractor shall obtain the County PROW permit, the County TROW permits, the County Water Meter and Fire Hydrant permits, and County Electrical Permit. The Contractor is

ITB No. XXXXX

responsible for investigating and satisfying all permit requirements for the above-mentioned permits.

3. SPECIAL CONTRACTOR/SUBCONTRACTOR QUALIFICATIONS

The Contractor shall have three (3) continuous years of services and construction contract experience conducting public works infrastructure and street improvement projects in an urban environment. The experience shall be work of similar size and scope, construction, re-construction, and maintenance.

The Contractor obtained project experience shall consist of the following:

- **State and County streets**
- **Curbs and gutters**
- **Sidewalks and walkways**
- **Driveway aprons**
- **Storm sewer pipes and inlets**
- **Wet Utilities**
- **Pavement markings and signage**
- **Electrical conduits**
- **Traffic signals and Street lighting**
- **Streetscapes and related site work**
- **Vertical Construction**

The Contractor shall provide a complete list of projects completed within the last five (5) years with reference contact information for each project for Bidder qualification verification. Failure to qualify according to the foregoing requirements will result in bid rejection by the Arlington County Purchasing Office. The County will randomly contact at least five (5) of the references provided.

4. STAKEOUT AND CUT-SHEETS

The Contractor shall be responsible for laying out the work and shall retain a professional land surveyor licensed in the Commonwealth of Virginia to provide all necessary construction layouts and establish all control lines, grades, and elevation during construction. The Contractor shall submit a copy of all cut-sheets for review, per the Arlington County Specifications. All cut-sheets for layout and construction shall be provided as submittals at least seven (7) calendar days prior to construction of the work included on that cut-sheet. The cost of all necessary surveying services shall be considered incidental to the work and no separate payment shall be made.

5. SCHEDULE, DURATION, AND PHASING REQUIREMENTS

ITB No. XXXXX

The Contractor shall provide a schedule for all work listed on plans including any additional work not specifically mentioned on plans but was agreed upon with the County prior to work commencing.

Work Duration per task order shall be calculated in accordance with Supplements to the General Condition "SC-F.2 TIME FOR COMPLETION". The Time for completion shall be used as the basis for the project schedule.

Contractor shall make sure that the submittals/shop drawings are reviewed and accepted and materials ordered and delivered on site as no additional time will be granted for this. Submittals and review time shall be incorporated on the construction schedule to ensure materials are delivered on time and there's no construction delays.

The Contractor shall prepare and submit a detailed Baseline of "Initial" Construction Schedule Ten (10) business days after the Notice to Proceed. This schedule shall be submitted in MS Project and pdf format on eBuilder for the County review and approval. The Initial Schedule shall be develop using the Critical Path Method per the requirements described on the Arlington County Standards Section 01320.1.4.B-1.7. The Construction Schedule shall in all respects conform to and be consistent with the time requirements for the Project as set forth in this Construction Contract.

6. WORK HOURS

The Contractor shall comply with **normal daytime working hours** as defined in the County Noise Control Ordinance unless otherwise defined by the project plans and specifications, or approved by the Project Officer.

The Contractor shall comply with **restricted working hours** of 9:00 am to 3:00 pm when working in Arlington County arterial streets unless otherwise indicated on the Maintenance of Traffic Plans for each project.

In addition, the County reserves the right to restrict working days and hours to accommodate special site conditions as required.

7. GENERAL SITE SECURITY AND CONTROLS

The Contractor is responsible for securing its work area for safety and security. The Contractor shall confine its construction and presence to the Limits of Work, unless otherwise approved by the County Project Officer.

The Contractor shall provide, erect, and maintain barricades, fences, and/or signage as required to protect the general public, workers, and adjoining properties at no additional cost to the County. Before leaving the site at the end of each day, the Contractor shall

replace any and all sections of the security fence or barricade moved or removed during work hours.

The Contractor shall maintain clear vehicular access to existing driveways and entrances at all times unless such access is otherwise addressed on County-approved project plans, precluding concrete pouring and curing of such access points, unless otherwise directed by the County Project Officer.

Homeowners shall be notified by the Contractor a minimum of fourteen (14) calendar days in advance of any driveway closure, and driveways can only be closed for a maximum of five (5) calendar days.

The Contractor shall monitor parking of construction personnel's private vehicles and ensure that the public has unobstructed access to and through parking areas.

8. SPECIAL TRAFFIC MAINTENANCE CONSIDERATIONS

9. TRAFFIC SIGNALS AND STREETLIGHTS

Materials and construction of the communications conduit, streetlights, and traffic signals shall abide by the latest versions of the 'Arlington County Traffic Signal Specifications and Standards' and 'Arlington County Lighting Specifications and Standards. All materials for these areas shall be approved by Arlington County Transportation Engineering and Operations Bureau. The County Project Officer will facilitate the material specification submissions for review by the Transportation Engineering and Operations Bureau.

The Contractor shall abide by VDOT's requirement to submit signal foundation details for review. These details include, but are not limited to soil tests to verify the detail design, along with any other supporting information required by VDOT in their submission package. Details shall be created for each signal pole foundation and shall be for both three feet and four feet diameter foundations. The County will assist only in the submission of these details to VDOT, if requested. The Contractor is responsible for satisfying all VDOT requirements. The Contractor shall incorporate all costs for this in relevant items and no payment will be made by the County. The submission shall be submitted with enough time for VDOT to adequately review it. The Contractor cannot claim any time delay or any additional compensation due to such delay.

Prior to removal of the existing signal equipment and materials, the Contractor shall meet with the Project Officer to verify which equipment will be returned to the County, when and where the returned equipment will be delivered, and which equipment will be disposed. All costs associated with this shall be incidental to other items in the Contract.

Installation of electrical service for temporary services such as signals, streetlights, signal cabinets, construction trailers, or for equipment use are incidental to the contract.

ITB No. XXXXX

Intercepting existing streetlight conduits and splicing into existing cables are incidental to the contract.

References to a CCTV camera shall mean to both furnish and install the CCTV camera, unless specifically excluded.

As part of the luminaire installation, Contractor shall install house-side shields in each fixture. These shields will be provided by the County. If requested, the County will demonstrate how to install the shields. The Contractor shall contact the Streetlights Operations Team Manager at (703) 228-6531 to obtain the shields prior to ordering any streetlight materials to ensure they will be available at the time of construction, and to request a demonstration on how to install the shields. Failure to do so will be at the Contractor's expense for time if construction is stopped because the shields are not available. The installation of the shields is considered incidental to the contract and no additional payments shall be made for this work.

10. BIORETENTION CONSTRUCTION AND MATERIALS

11. WORK ASSIGNMENTS

12. UNLISTED WORK

13. JOB SIZE LIMITATION & ESTIMATED ACTIVITY

14. OTHER COUNTY CONTRACTS

15. OTHER SPECIAL PROVISIONS

SUPPLEMENTS TO THE DES CONSTRUCTION STANDARDS AND SPECIFICATIONS

SECTION 02900 – PAVEMENT MARKINGS

PART 4 - MEASUREMENT AND PAYMENT

PARAGRAPH 4.3 Colored Asphalt Coating

Delete

A. Measurement of colored asphalt coating shall be per square foot of area completed. Payment for colored asphalt coating shall be per square foot and shall include all labor, materials, tools, equipment, transportation, supplies, and incidentals required to complete the coating.

Add

A. Measurement of colored asphalt coating shall be per square yard of area completed. Payment for colored asphalt coating shall be per square yard and shall include all labor, materials, tools, equipment, transportation, supplies, and incidentals required to complete the coating.

PARAGRAPH 4.4 Removal/Eradication of Existing Pavement Markings

Delete

A. Payment for pavement line markings (type, class, width) removal and/or eradication shall be paid by actual work performed as listed in the contract and shall include all labor, materials, tools, equipment, transportation, supplies, and incidentals required to remove and/or eradicate the line markings as specified.

Add

A. Payment for pavement line markings (type, class, width) removal and/or eradication shall be incidental to the work and no separate payment shall be made.

SECTION 05500 –STRUCTURE STEEL AND MISCELLANEOUS METAL

Remove this section in its entirety

Supplemental Specifications List

- **Section 02614** – Cast In Place Detectable Warning Surfaces
- **Section 07110** – Hot-Applied Rubberized Waterproofing
- **Section 10531** – Assembly and Installation of Transit Stations
- **Transitway Extension to Pentagon City Station Design Specifications**
 - **Section 03320** - Concrete Foundations for Transit Stations
 - **Section 05501** - Stainless Steel
 - **Section 10425** - Specialty Signs
 - **Section 16020** - Basic Electrical