

ENGINEER DEPARTMENT OF **ENVIRONMENTAL SERVICES**

WWW.ARLINGTONVA.US

CONSTRUCTION DRAWINGS FOR:

TRANSITWAY EXTENSION TO PENTAGON CITY


CRYSTAL DR & 12TH ST S (CIVIL SITE WORK)

FACILITIES & ENGINEERING DIVISION ENGINEERING BUREAU 2100 CLARENDON BOULEVARD, SUITE 813 ARLINGTON, VA 22201 PHONE: 703.228.3629 FAX: 703.228.3606

OWNER ARLINGTON COUNTY DES - TRANSIT BUREAU 2100 CLARENDON BOULEVARD, SUITE 900 ARLINGTON, VA 22201

CONSULTANT TO BE DETERMINED CONTRACTOR TO BE DETERMINED

LOCATION MAP



TRANSPORTATION DIRECTOR

ARLINGTON

DEPARTMENT OF

ENVIRONMENTAL SERVICES

PROJECT MANAGER

REVISIONS

GENERAL NOTES:

GENERAL CONSTRUCTION NOTES

PROJECT CODE: MA13 - SEGMENT I

BETWEEN ACTUAL FIELD CONDITIONS AND THE APPROVED PLANS.

- ALL CONSTRUCTION WORK FOR THIS PROJECT SHALL CONFORM TO THE ARLINGTON COUNTY DEPARTMENT OF ENVIRONMENTAL SERVICES, CONSTRUCTION STANDARDS AND SPECIFICATIONS, AND WHERE APPLICABLE THE VIRGINIA DEPARTMENT OF TRANSPORTATION (VDOT) ROAD AND BRIDGE SPECIFICATIONS, AND ROAD AND BRIDGE STANDARDS. THE LATEST EDITIONS OF EACH RELEVANT MANUAL SHALL BE USED.
- ALL CONSTRUCTION AND WORK ACTIVITIES SHALL COMPLY WITH THE VIRGINIA WORK AREA PROTECTION MANUAL AND ALL OTHER RELEVANT WORK SAFETY REQUIREMENTS, LATEST EDITIONS.
- . THE CONTRACTOR SHALL IMMEDIATELY NOTIFY THE PROJECT OFFICER OF ANY DISCREPANCIES
- 4. THE CONTRACTOR SHALL CONTACT "MISS UTILITY" AT 811 FOR MARKING THE LOCATIONS OF EXISTING UNDERGROUND UTILITIES (i.e. WATER, SEWER, GAS, TELEPHONE, ELECTRIC, AND CABLE TV) AT LEAST 72 HOURS PRIOR TO ANY EXCAVATION OR CONSTRUCTION. THE CONTRACTOR IS REQUIRED TO IDENTIFY AND PROTECT ALL OTHER UTILITY LINES FOUND IN THE WORK SITE AREA BELONGING TO OTHER OWNERS THAT ARE NOT MEMBERS OF "MISS UTILITY". PRIVATE WATER, SEWER AND GAS LATERALS WILL NOT BE MARKED BY MISS UTILITY OR THE COUNTY. THE CONTRACTOR SHALL LOCATE AND PROTECT THESE SERVICES DURING CONSTRUCTION.
- THE CONTRACTOR SHALL BE RESPONSIBLE FOR LAYING OUT THE WORK AND SHALL RETAIN A PROFESSIONAL LAND SURVEYOR LICENSED IN THE COMMONWEALTH OF VIRGINIA TO PROVIDE ALI NECESSARY CONSTRUCTION LAYOUTS AND ESTABLISH ALL CONTROL LINES, GRADES, AND ELEVATION DURING CONSTRUCTION. THE CONTRACTOR SHALL SUBMIT A COPY OF ALL CUT SHEETS FOR REVIEW, PER THE SPECIFICATIONS. THE COST OF ALL NECESSARY SURVEYING SERVICES SHALL BE CONSIDERED INCIDENTAL TO THE WORK AND, UNLESS OTHERWISE SPECIFIED, THE COST SHALL BE INCORPORATED INTO THE COSTS FOR RELEVANT ITEMS.
- . THE LOCATION OF ALL EXISTING UTILITIES SHOWN ON THESE PLANS ARE FROM BEST AVAILABLE RECORDS AND SHALL BE CONSIDERED TO BE APPROXIMATE. WHEN CONSTRUCTION ACTIVITY REACHES IN PROXIMITY TO EXISTING UTILITIES, THE TRENCH(ES) SHALL BE OPENED A SUFFICIENT DISTANCE AHEAD OF THE WORK OR TEST PITS SHALL BE MADE TO VERIFY THE EXACT LOCATION AND INVERTS OF THE UTILITY TO ALLOW FOR POSSIBLE CHANGES IN THE LINE OR GRADE AS DIRECTED BY OFFICER. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ANY DAMAGE TO THE EXISTING UTILITIES AND THE RELATED STRUCTURES. ALL EXISTING UTILITY SYSTEMS SHALL BE PROTECTED TO PREVENT DAMAGE DURING THE CONTRACTOR'S OPERATIONS. ANY SYSTEM DAMAGED SHALL BE PROMPTLY REPAIRED AT NO COST TO THE OWNER.
- EXISTING MANHOLE FRAMES, COVERS, VALVE BOXES, AND OTHER APPURTENANCES SHALL BE ADJUSTED TO THE FINAL GRADE OR REPLACED, AS NECESSARY. UNLESS OTHERWISE SPECIFIED, THE COST FOR THIS SHALL BE CONSIDERED INCIDENTAL TO THE WORK, AND SHALL BE INCORPORATED INTO THE COSTS FOR RELEVANT ITEMS.
- THE CONTRACTOR SHALL PROVIDE ADA COMPLIANT ACCESS THROUGH OR AROUND THE SITE AT ALL TIMES AND SHALL ENSURE THE SAFETY OF ALL THOSE PASSING THROUGH OR ADJACENT TO THE SITE.
- ALL SIDEWALK AND CURB AND GUTTER DEMOLITION SHALL BEGIN AND END AT THE CONSTRUCTION JOINT NEAREST TO THE DEPICTED DEMOLITION EXTENTS WITH A NEAT SAWCUT LINE TO FULL DEPTH OF PAVEMENT SECTION.

STORMWATER AND ENVIRONMENTAL PROTECTION

10. THE CONTRACTOR SHALL CONFINE ALL ACTIVITIES AT THE SITE ASSOCIATED WITH CONSTRUCTION ACTIVITIES, TO INCLUDE STORAGE OF EQUIPMENT AND OR MATERIALS, ACCESS TO THE WORK, FORMWORK, ETC. TO WITHIN THE DESIGNATED LIMITS OF DISTURBANCE (LOD).

TREE PROTECTION

11. TREES SHALL BE PROTECTED PER THE REQUIREMENTS OF ARLINGTON PARKS & RECREATION STANDARD.

REVISED ON 11/08/2016

FRAFFIC CONTROL

- 12. CONTRACTOR SHALL NOTIFY THE PROJECT OFFICER AT LEAST 3 WORKING DAYS PRIOR TO DISTURBING ANY EXISTING, OR INSTALLING ANY NEW, TRAFFIC SIGNS, SIGNALS, OR OTHER TRAFFIC CONTROL
- 13. THE CONTRACTOR SHALL PREMARK THE LAYOUT OF ANY PERMANENT TRAFFIC CONTROL STRIPING, INDICATING THE PROPOSED LOCATION AND TYPE OF MARKING TO BE INSTALLED. THE PREMARKING MAY CONSIST OF TYPE D TAPE, CHALK, OR LUMBER CRAYONS, THE CONTRACTOR SHALL ALLOW 3 WORKING DAYS FOR THE INSPECTION AND APPROVAL OF THE PREMARKINGS PRIOR TO PLACING THE
- 14. THE CONTRACTOR SHALL SUBMIT ANY REQUESTS FOR TEMPORARY "NO PARKING" RESTRICTIONS TO THE PROJECT OFFICER AT LEAST 5 BUSINESS DAYS PRIOR TO THE DESIRED ONSET OF RESTRICTIONS. PRIOR TO A REQUEST FOR THE REMOVAL OF ACCESS TO ANY ADA PARKING SPACE THE CONTRACTOR MUST HAVE MADE PROVISION FOR ALTERNATIVE ADA PARKING AS INDICATED ON THE APPROVED PLAN OR AS DIRECTED BY THE PROJECT OFFICER.
- 15. WHEN THE APPROVED PLAN CALLS FOR THE REMOVAL OF ANY PARKING METER THE CONTRACTOR MUST MAKE A REQUEST TO THE PROJECT OFFICER AT LEAST ONE WEEK IN ADVANCE OF THE DESIRED REMOVAL. THE PROJECT OFFICER WILL THEN COORDINATE THE PARKING METER REMOVAL WITH TRAFFIC ENGINEERING AND OPERATIONS.
- 16. THE CONTRACTOR SHALL PRESERVE ALL BUS STOPS, INCLUDING MAINTAINING ADEQUATE ACCESSIBILITY THROUGH AND ADJACENT TO THE CONSTRUCTION FOR BUSES AND THEIR PASSENGERS. THE CONTRACTOR SHALL NOT CLOSE, RELOCATE, OR OTHERWISE MODIFY A BUS STOP WITHOUT PRIOR REOUEST OF THE PROJECT OFFICER. ANY RELOCATION OR CLOSURE OF A BUS STOP SHALL REQUIRE AT LEAST FOUR WEEKS ADVANCE NOTICE FOR COORDINATION WITH THE COUNTY'S BUS STOP COORDINATOR - 703-228-3049.
- 17. WHEN CONDITIONS WARRANT DUE TO TRAFFIC VOLUMES, PATTERNS, OR SPECIAL EVENTS, THE COUNTY MAY SUSPEND OR OTHERWISE DIRECT THE CONTRACTOR'S ACTIVITIES TO PROTECT THE PUBLIC AND OR THE COUNTY'S TRANSPORTATION NETWORK.

WATER DISTRIBUTION, STORM AND SANITARY SEWER SYSTEMS

18. UNLESS OTHERWISE DIRECTED, CONTRACTORS ARE EXPRESSLY PROHIBITED FROM OPERATING ANY

- WATER VALVES OR APPURTENANCES. CONTRACTORS SHALL SUBMIT ALL REQUESTS FOR VALVE OPERATIONS TO THE PROJECT OFFICER AT LEAST 1 WEEK IN ADVANCE OF THE REQUIRED OPERATION.
- 19. IN THE EVENT OF A WATER OR SEWER EMERGENCY, THE CONTRACTOR SHALL IMMEDIATELY NOTIFY THE COUNTY'S WATER CONTROL CENTER AT 703-228-6555 AND THE PROJECT OFFICER.
- 20. THE CONTRACTOR SHALL COORDINATE ALL UTILITY SHUTOFFS, DISCONNECTS, AND/OR ABANDONMENT WITH UTILITY OWNER AND PROJECT OFFICER AT LEAST 1 WEEK IN ADVANCE OF THE REQUIRED

FIRE DEPARTMENT NOTES:

- 21. ALL EXISTING FIRE HYDRANTS AND FIRE DEPARTMENT CONNECTIONS SHALL BE MAINTAINED UNOBSTRUCTED AND ACCESSIBLE AT ALL TIMES IN ACCORDANCE WITH SECTIONS 508.5.4 AND 508.5.5 OF THE ARLINGTON COUNTY FIRE PREVENTION CODE.
- 22. ACCESS TO BUILDINGS FOR FIREFIGHTING SHALL BE MAINTAINED AT ALL TIMES. EXISTING FIRE APPARATUS ACCESS ROADS (FIRE LANES) SHALL BE KEPT CLEAR OF OBSTRUCTIONS IN ACCORDANCE WITH SECTION 503.4 OF THE ARLINGTON COUNTY FIRE PREVENTION CODE. ACCESS TO CONSTRUCTION SITES SHALL BE PROVIDED AND MAINTAINED IN ACCORDANCE WITH SECTION 1410 OF THE ARLINGTON COUNTY FIRE PREVENTION CODE.
- 23. IN THE EVENT THAT EXISTING FIRE DEPARTMENT CONNECTIONS OR FIRE APPARATUS ACCESS ROADS (FIRE LANES) MUST BE OBSTRUCTED TO FACILITATE CONSTRUCTION ACTIVITIES, CONTACT THE ARLINGTON COUNTY FIRE DEPARTMENT FIRE PREVENTION OFFICE AT 703-228-4644 TO COORDINATE REVIEW AND APPROVAL OF TEMPORARY FIRE DEPARTMENT CONNECTIONS AND/OR FIRE APPARATUS ACCESS ROADS PRIOR TO CREATING THE OBSTRUCTION.

Sheet List Table

SITE DETAILS

BRASCO DETAILS

BRASCO DETAILS

BRASCO DETAILS

EXISTING CONDITIONS

EXISTING CONDITIONS

E&S CONTROL PLAN

E&S CONTROL PLAN

E&S CONTROL DETAILS

E&S CONTROL NOTES

DEMOLITION PLAN

DEMOLITION PLAN

SITE PLAN & PROFILE

SITE PLAN & PROFILE

SITE PLAN & PROFILE

STATION DETAIL

STATION DETAIL

LANDSCAPE PLAN

LANDSCAPE PLAN

UTILITY PLAN

CROSS SECTIONS

CROSS SECTIONS

CROSS SECTIONS

CROSS SECTIONS

CROSS SECTIONS

MOT PLAN

MOT PLAN

MOT PLAN

LANDSCAPE DETAILS

20B

31A

GEOMETRIC CONTROL PLAN

GEOMETRIC CONTROL PLAN

RAMP DETAILS - GRADING PLAN

RAMP DETAILS - GRADING PLAN

BRASCO & FURNISHING DETAILS

SW POLLUTION PREVENTION PLAN

SW POLLUTION PREVENTION PLAN

SW POLLUTION PREVENTION PLAN

STORMWATER MANAGEMENT PLAN

TEST HOLE PIT LOGS **TEST HOLE PIT LOGS COVER SHEET** LEGEND SIGNAGE AND STRIPING PLAN OVERALL PLAN SIGNAGE AND STRIPING PLAN SECTION DETAILS

SWM18-0167

15,000 VPD - 15TH ST S BETWEEN US ROUTE 1 AND CRYSTAL DR - 2018 - VDOT 5,200 VPD - CRYSTAL DR BETWEEN 26TH ST S AND 12TH ST S - 2018 - VDOT 5,300 VPD - 12TH ST S BETWEEN CRYSTAL DR AND S EADS ST- 2018 - VDOT

STREET CLASSIFICATION

25 MPH - 12TH ST S (OBTAINED FROM GIS DATA)

POSTED SPEED 30 MPH - CRYSTAL DR (OBTAINED FROM GIS DATA)


ITWAY PENTA


DESIGNED: PB DRAWN: NS CHECKED: TL


MISS UTILITY TRANSMITTAL #: N/A FILENAME: MA13-200-COVER.DWG PATH:\\DES-CAD-S2\ENGINEERING_DATA\DA A\MA1

PLOTTED: AUGUST 4 2021 PLOTTED BY:NSHARP

SCALE: H: 1" = 600'







ARLINGTON

VIRGINIA

DEPARTMENT OF ENVIRONMENTAL SERVICES

FACILITIES & ENGINEERING DIVISION

ENGINEERING BUREAU

2100 CLARENDON BOULEVARD, SUITE 813

ARLINGTON, VA 22201

PHONE: 703.228.3629

FAX: 703.228.3606

COPYRIGHT © 2016 ARLINGTON COUNT

VIRGINIA - ALL RIGHTS RESERVED

REVOR M. LANTZY

8/4/2021

CONSTRUCTION MANAGEMENT SUPERVISOR

WATER, SEWER, STREETS BUREAU CHIEF

Dennis M. Leach 03/17/21

APPROVALS

QUALITY CONTROL ENGINEER

TRANSPORTATION DIRECTOR

Diana Isaza
PROJECT MANAGER

REVISIONS

ENSION CITY

TRANSITWAY PENTA(

DESIGNED: PB DRAWN: NS

CHECKED: TL

FILENAME:

MISS UTILITY TRANSMITTAL #: N/A

MA13-210-TYPICAL_SECTIONS.DWG

PLOTTED: AUGUST 4 2021

PLOTTED BY:NSHARP

SCALE:

SHEET

PATH:\\DES-CAD-S2\ENGINEERING_DATA\DATA\MA13

04 OF 35

Kamal Taktak

DATE


DATE


()


ST


ON

S













ARLINGTON


VIRGINIA














Date: 8/6/2010











ARLINGTON VIRGINIA DEPARTMENT OF **ENVIRONMENTAL SERVICES** FACILITIES & ENGINEERING DIVISION ENGINEERING BUREAU 2100 CLARENDON BOULEVARD, SUITE 813 ARLINGTON, VA 22201 PHONE: 703.228.3629 FAX: 703.228.3606 COPYRIGHT © 2016 ARLINGTON COUNTY VIRGINIA - ALL RIGHTS RESERVED APPROVALS DATE QUALITY CONTROL ENGINEER Kamal Taktak CONSTRUCTION MANAGEMENT SUPERVISOR WATER, SEWER, STREETS BUREAU CHIEF Dennis M. Leach 03/17/21 TRANSPORTATION DIRECTOR Diana Isaza PROJECT MANAGER **REVISIONS** TRANSITWAY EXTENSION PENTAGON CITY 2TH DESIGNED: PB DRAWN: NS CHECKED: TL MISS UTILITY TRANSMITTAL #: N/A FILENAME: MA13-204-DETAILS.DWG PATH:\\DES-CAD-S2\ENGINEERING_DATA\DATA\MA13 PLOTTED: AUGUST 4 2021 PLOTTED BY:NSHARP SCALE: N/A


REVISED ON 11/08/2016


SHEET


ARLINGTON **VIRGINIA** DEPARTMENT OF **ENVIRONMENTAL SERVICES** FACILITIES & ENGINEERING DIVISION ENGINEERING BUREAU 2100 CLARENDON BOULEVARD, SUITE 813 ARLINGTON, VA 22201 PHONE: 703.228.3629 FAX: 703.228.3606 COPYRIGHT © 2016 ARLINGTON COUNTY VIRGINIA - ALL RIGHTS RESERVED APPROVALS CONSTRUCTION MANAGEMENT SUPERVISOR WATER, SEWER, STREETS BUREAU CHIEF Dennis M. Leach 03/17/21 TRANSPORTATION DIRECTOR Diana Isaza PROJECT MANAGER **REVISIONS** INTENTIONALLY LEFT BLANK TRANSITWAY EXTENSION PENTAGON CITY 12TH DESIGNED: PB DRAWN: NS CHECKED: TL MISS UTILITY TRANSMITTAL #: N/A FILENAME: MA13-204-DETAILS.DWG
PATH:\\DES-CAD-S2\ENGINEERING_DATA\DATA\MA13 PLOTTED: AUGUST 4 2021 PLOTTED BY:NSHARP SCALE: N/A SHEET 09 OF 35 REVISED ON 11/08/2016 COPYRIGHT © 2016 ARLINGTON COUNTY VIRGINIA - ALL RIGHTS RESERVED
















BAY PRESERVATION ORDINANCE UNDER 61-15 OF THE ARLINGTON COUNTY CODE.

STORM WATER RUNOFF CONSIDERATIONS:

ENTERING THE STORM SEWER INLETS.


ARLINGTON

DPR

PLATE: 3.26-2 SOURCE: VA. DSWC

CBPO / BMP NARRATIVE:

THIS PROJECT IS A PUBLIC ROAD PROJECT AND IS THEREFORE EXEMPT FROM THE REQUIREMENTS OF THE CHESAPEAKE



THE SUBJECT SITE IS LOCATED IN ZONE X ON FEMA FIRM # 51013C0081C AND IS NOT LOCATED IN THE RPA. THE PROJECT SITE (CRYSTAL DRIVE AND 12TH STREET SOUTH) HAS NO HISTORY OF RECORDED FLOODING AND/OR PONDING ON THE STREETS DURING HEAVY RAIN EVENTS. THE REHABILITATION SITE HAS 2 (TWO) OUTFALL AREAS. STORM COMPUTATIONS HAS BEEN PROVIDED TO DEMONSTRATE THE ADEQUATE CAPACITY OF THE EXISTING STORM SYSTEMS. THE RESULTS SHOWED EXISTING STORM DRAINAGE SYSTEMS AND PROPOSED INLETS RELOCATION ARE ADEQUATE. SEE SHEETS XX - XX. EXISTING STORMWATER SYSTEM WILL BE USED TO DRAIN OUT THE STORMWATER RUNOFF DURING CONSTRUCTION. RUNOFF SHALL BE TREATED WITH INLET PROTECTION PRIOR TO ENTERING MAJOR STORM SEWER SYSTEMS. THERE IS NO ANTICIPATED CHANGE IN STORM WATER RUNOFF AFTER COMPLETION OF THE PROJECT.

STORM DRAIN INLET PROTECTION:

INLET PROTECTION WILL BE INSTALLED AS SHOWN. ALL STORM SEWER INLETS SHALL BE PROTECTED DURING CONSTRUCTION. SEDIMENT-LADEN WATER SHALL BE FILTERED BEFORE ENTERING THE STORM SEWER INLETS. STORM DRAIN INLET PROTECTION: ALL EXISTING & PROPOSED STORM SEWER INLETS IN AND AROUND THE PROJECT LIMITS SHALL BE PROTECTED DURING CONSTRUCTION, SEDIMENT-LADEN WATER SHALL BE FILTERED BEFORE

DEWATERING STRUCTURE: SEDIMENT LADEN OR TURBID WATER SHALL BE FILTERED, SETTLED OR SIMILARLY TREATED

VIRGINIA DEPARTMENT OF ENVIRONMENTAL QUALITY (DEQ) MUNICIPAL SEPARATE STORM SEWER SYSTEM (MS4) NOTE:


ONLY THE FOLLOWING NON-STORMWATER DISCHARGES ARE AUTHORIZED BY ARLINGTON COUNTY'S MS4 PERMIT, UNLESS THE STATE WATER CONTROL BOARD, THE VIRGINIA SOIL AND WATER CONSERVATION BOARD (BOARD), OR ARLINGTON COUNTY DETERMINES THE DISCHARGE TO BE A SIGNIFICANT SOURCE OF POLLUTANTS TO SURFACE WATERS:

WATER LINE FLUSHING; LANDSCAPE IRRIGATION; DIVERTED STREAM FLOWS; RISING GROUND WATERS; UNCONTAMINATED GROUND WATER INFILTRATION (AS DEFINED AT 40 CFR 35.2005(20)); UNCONTAMINATED PUMPED GROUND WATER; DISCHARGES FROM POTABLE WATER SOURCES; FOUNDATION DRAINS; AIR CONDITIONING CONDENSATION; IRRIGATION WATER; SPRINGS; WATER FROM CRAWLSPACE PUMPS; FOOTING DRAINS; LAWN WATERING; INDIVIDUAL RESIDENTIAL CAR WASHING; FLOWS FROM RIPARIAN HABITATS AND WETLANDS; DECHLORINATED SWIMMING POOL DISCHARGES; DISCHARGES OR FLOWS FROM FIRE FIGHTING; AND, OTHER ACTIVITIES GENERATING DISCHARGES IDENTIFIED BY THE DEPARTMENT OF ENVIRONMENTAL QUALITY AS NOT REQUIRING VPDES AUTHORIZATION.

APPROPRIATE CONTROLS MUST BE IMPLEMENTED TO PREVENT ANY NON-STORMWATER DISCHARGES NOT INCLUDED ON THE ABOVE LIST (E.G., CONCRETE WASH WATER, PAINT WASH WATER, VEHICLE WASH WATER, DETERGENT WASH WATER, ETC.) FROM BEING DISCHARGED INTO ARLINGTON COUNTY'S MS4 SYSTEM, WHICH INCLUDES THE CURB AND GUTTER SYSTEM, AS WELL AS CATCH BASINS AND OTHER STORM DRAIN INLETS, OR STREAM NETWORK.

PER CHAPTER 26 OF THE ARLINGTON COUNTY CODE, IT SHALL BE UNLAWFUL FOR ANY PERSON TO DISCHARGE DIRECTLY OR INDIRECTLY INTO THE STORM SEWER SYSTEM OR STATE WATERS, ANY SUBSTANCE LIKELY, IN THE OPINION OF THE COUNTY MANAGER, TO HAVE AN ADVERSE EFFECT ON THE STORM SEWER SYSTEM.

TREES 30" DBH OR GREATER OR TREES 8.1-29.9" DBH I" DBH = I' CRZ RADIUS TREES DESIGNATED AS SPECIMEN TREES I" DBH = 1.5' CRZ RADIUS I. GRAPHICALLY, THE CRITICAL ROOT ZONE (CRZ) IS REPRESENTED AS A CIRCULAR REGION MEASURED OUTWARD FROM A TREE TRUNK REPRESENTING THE AREA OF ROOTS THAT MUST BE MAINTAINED OR PROTECTED FOR THE TREE'S SURVIVAL . THE CRZ OF A TREE IS THE ZONE IN WHICH MOST OF THE MAJORITY OF THE ROOTS LAY. 95% OF THE ROOTS OF MOST TREES WILL BE FOUND IN THE UPPER 12-18" OF THE SOIL. MOST OF THE ROOTS THAT SUPPLY THE NUTRIENTS AND WATER TO THE TREE ARE FOUND JUST BELOW THE SOIL SURFACE. THE TOTAL AMOUNT OF A TREE'S ROOTS ARE GENERALLY PROPORTIONAL TO THE VOLUME OF THE TREE'S 30" DBH CANOPY. THEREFORE, IF THE ROOTS ONLY PENETRATE A THIN LAYER OF SOIL, THEN THE ROOTS MUST SPREAD FAR FROM THE TREE, BEYOND THE EXTENSION OF THE CANOPY. PLOT ACCURATE TRUNK LOCATIONS OF ALL TREES REES 8" DBH AND SMALLER 8' CRZ RADIUS AROUND THE GREATER THAN 3" DIAMETER AT BREAST HEIGHT (DBH) TRUNK OF TREE AND/OR TREE STANDS WITHIN DEVELOPMENT AREAS ON ALL PLANS FOR THE PROJECT AND DELINEATE THEIR ESTIMATED CRITICAL ROOT ZONE. 4. PLOT ACCURATE TRUNK LOCATIONS OF OFFSITE ELEVATION TREES WHICH WILL HAVE THEIR CRZ AFFECTED BY DEVELOPMENT AND DELINEATE THEIR ESTIMATED CRITICAL ROOT ZONE. ECTION DETAIL FOR DETERMINING CRITICAL ROOT ZONE 311300.3 (2016) (02231.3)



CONSTRUCTION MANAGEMENT SUPERVISO WATER, SEWER, STREETS BUREAU CHIEF Dennis M. Leach 03/17/21

Diana Isaza PROJECT MANAGER

- I. CONTRACTOR TO CONTACT THE ARLINGTON FORESTER TO SCHEDULE A PRE-CONSTRUCTION INSPECTION OF TREE PROTECTION MEASURES BEFORE ANY WORK NEAR THE CRITICAL ROOT ZONES OF TREES. TO SCHEDULE THE PRE-CONSTRUCTION MEETING CALL 703-228-1863.
- II. CONTRACTOR TO PROTECT TREES PER THE PLAN ACCORDING TO THE ARLINGTON COUNTY DPR DESIGN STANDARD DETAIL 02231.1.
- III. CONTRACTOR TO ROOT PRUNE TREES PER THE PLAN ACCORDING TO THE ARLINGTON COUNTY DPR DESIGN

STANDARD DETAIL 02231.5, WHERE CALLED OUT ON THE PLAN.

- IV. CONTRACTOR TO CALL THE URBAN FORESTER AT 703-228-1863, 72 HOURS BEFORE PLANTING, TO SCHEDULE INSPECTION OF THE TREES TO BE PLANTED. WARRANTY FOR 1 YEAR AFTER PLANTING SHALL BE THE
- CONTRACTOR'S RESPONSIBILITY. THE URBAN FORESTER AND DPR IS RESPONSIBLE FOR INSPECTION. $\hbox{V. CONTRACTOR TO PREPARE TREE PLANTING STRIPS FOR THE REPLACEMENT TREES ACCORDING TO ARLINGTON}\\$
- COUNTY DPR DESIGN STANDARD DETAIL 02930.4A AND 02930.4B. VI. CONTRACTOR TO PREPARE STREET TREE PLANTING PITS ACCORDING TO THE ARLINGTON COUNTY DPR DESIGN STANDARD DETAIL 02930.3A, 02930.3B, AND 02930.11C.
- VII. CONTRACTOR TO PLANT THE TREES ACCORDING TO ARLINGTON COUNTY DPR DESIGN STANDARD DETAIL 02930.1 (ON FLAT LAND) OR 02930.2 (ON SLOPES).

THIS SHEET IS FOR EROSION AND SEDIMENT CONTROL USE ONLY FOR ALL DETAILS AND SPECIFICATIONS, SEE THE VIRGINIA EROSION & SEDIMENT CONTROL HANDBOOK

ARLINGTON

VIRGINIA

DEPARTMENT OF ENVIRONMENTAL SERVICES **FACILITIES & ENGINEERING DIVISION** ENGINEERING BUREAU 2100 CLARENDON BOULEVARD, SUITE 813 ARLINGTON, VA 22201

FAX: 703.228.3606 COPYRIGHT © 2016 ARLINGTON COUNT VIRGINIA - ALL RIGHTS RESERVED

PHONE: 703.228.3629

APPROVALS Kamal Taktak

TRANSPORTATION DIRECTOR

REVISIONS DATE

> 2 0

SITWAY

DRAWN: NS CHECKED: TL MISS UTILITY TRANSMITTAL #: N/A

MA13-224-E_AND_S_PLAN.DWG

PATH:\\DES-CAD-S2\ENGINEERING_DATA\DA_A\MA1

PLOTTED: AUGUST 4 2021 PLOTTED BY:NSHARP

SCALE: N/A

SHEET 12 OF 35

COPYRIGHT © 2016 ARLINGTON COUNTY VIRGINIA - ALL RIGHTS RESERVED

REVISED ON 11/08/2016

311300.1 (2016) (02231.1)

EROSION AND SEDIMENT CONTROL NARRATIVE

PROJECT DESCRIPTION

TWO STATIONS ARE PROPOSED TO BE CONSTRUCTED FOR THE SEGMENT F OF THE CRYSTAL CITY POTOMAC YARD TRANSITWAY (TRANSITWAY). PROPOSED IMPROVEMENTS ARE ALSO PROPOSED AT THE TRANSITION FROM CRYSTAL DRIVE TO 12TH STREET S.

THE TRANSITWAY STATION AT CRYSTAL DRIVE NORTH BOUND AND 15TH STREET SOUTH INTERSECTION (STA 61+18) CONSIST OF CURBSIDE 9.5" HIGH PLATFORM AND TWO CUSTOM BUS SHELTERS SIMILAR TO THE BUS SHELTERS INSTALLED AT CRYSTAL DRIVE NORTH BOUND AND 18TH STREET SOUTH INTERSECTION

THE TRANSITWAY STATION AT 12TH STREET SOUTH NORTH BOUND AND LONG BRIDGE DRIVE INTERSECTION (STA 74+54) CONSIST OF CURBSIDE 9.5" HIGH PLATFORM AND ONE BUS SHELTER PREFABRICATED AND PROVIDED BY

THE CRYSTAL DRIVE TO 12TH STREET S TRANSITION IMPROVEMENTS WILL INCLUDE THE INSTALLATION OF TWO CURB RAMPS, CURB AND GUTTER, SIDEWALK AND ASPHALT.

THE TRANSITWAY STATION AT CRYSTAL DRIVE NORTH BOUND AND 15TH STREET SOUTH INTERSECTION (STA 61+18)

INCLUDES: ROAD ASPHALT DEMOLITION AND REPAVING WITH 10" REINFORCED CONCRETE BUS PAD;

- CURB & GUTTER DEMOLITION AND CONSTRUCTION OF NEW MODIFIED CURB & GUTTER WITH 9.5" CURB HIGH AND TWO TRANSITIONS FROM 6" TO 9.5";
- SIDEWALK BRICK PAVEMENT DEMOLITION AND CONSTRUCTION OF NEW ELEVATED CONCRETE BUS PLATFORM,
- FOUNDATION FOR BUS SHELTERS AND TWO RAMPS WITH BRICK PAVEMENT; • TREE/LANDSCAPING STRIP AND TREE REMOVAL ASSOCIATED WITH CONCRETE BUS PLATFORM CONSTRUCTION;
- EXISTING STREET LANDSCAPING SHALL BE RESTORED AND EXISTING TREES SHALL BE PROTECTED.

<u>THE TRANSITWAY STATION AT 12TH STREET SOUTH NORTH BOUND AND LONG BRIDGE DRIVE INTERSECTION (STA</u> 74+54) INCLUDES:

ROAD ASPHALT DEMOLITION AND REPAVING WITH 10" REINFORCED CONCRETE BUS PAD;

- CURB & GUTTER DEMOLITION AND CONSTRUCTION OF NEW MODIFIED CURB & GUTTER WITH 9.5" CURB HIGH AND TWO TRANSITIONS FROM 6" TO 9.5";
- SIDEWALK BRICK PAVEMENT DEMOLITION AND CONSTRUCTION OF NEW ELEVATED CONCRETE BUS PLATFORM, FOUNDATION FOR BUS SHELTERS AND TWO RAMPS WITH BRICK PAVEMENT:
- TREE REMOVAL ASSOCIATED WITH CONCRETE BUS PLATFORM CONSTRUCTION;
- EXISTING STREET LANDSCAPING SHALL BE RESTORED;
- CATCH BASIN SHALL BE REPLACED WITH MODIFIED CATCH BASIN TO ACCOMMODATE ELEVATED PLATFORM 9.5"

HE CRYSTAL DRIVE TO 12TH STREET SOUTH TRANSITION (STA 67+00 TO STA 69+00) INCLUDES:

- ROAD ASPHALT DEMOLITION AND REPAVING;
- CURB & GUTTER DEMOLITION AND CONSTRUCTION OF NEW CURB & GUTTER;
- SIDEWALK DEMOLITION AND CONSTRUCTION OF NEW SIDEWALK WITH BRICK BAND;
- RAMP DEMOLITION AND CONSTRUCTION OF TWO NEW RAMPS;
- EXISTING STREET LANDSCAPING AND/OR GRASS AREAS SHALL BE RESTORED;

DISTURBED AREA, PRE DEVELOPED AND POST DEVELOPED IMPERVIOUS CONDITIONS PROVIDED IN THE TABLE - SEE

THIS PROJECT DOES NOT IMPACT VDOT RIGHT-OF-WAY.

EXISTING SITE CONDITIONS

THE PROJECT SITES ARE LOCATED IN BUSINESS AREAS AND CONSIST ENTIRELY OF IMPERVIOUS AREA (ASPHALT ROADWAY AND CONCRETE/BRICK PAVER SIDEWALK). SUFFICIENT STORM DRAINAGE SYSTEM IS IN PLACE AND THERE IS NO KNOWN RECORD OF FLOODING IN THE AREA.

THE PROJECT LIMITS ARE LOCATED WITHIN THE ROACHES RUN WATERSHED.

ADJACENT PROPERTIES

COMMERCIAL PROPERTIES ARE LOCATED BEHIND PROPOSED TRANSITWAY STATIONS, AND THE PROPOSED TRANSITION IMPROVEMENTS.

OFF-SITE AREAS

THE EXTENT OF OFFSITE CONSTRUCTION IS LIMITED TO CONNECTING TO EXISTING STREETS ADJACENT TO THIS PARCELS, AND CONNECTING PROPOSED UTILITIES TO EXISTING UTILITIES.

AS THE PROJECT AREA IS WITHIN THE EXISTING ROADWAY, THERE ARE NO EXISTING EROSION PROBLEMS IDENTIFIED.

<u>SOILS</u>

COMPLEX: URBAN LAND-UDORTHENTS COMPLEX 2 TO 15 PERCENT

SLOPE: URBAN: 85-100

SOIL HYDRAULIC GROUP: D

THE SOILS IN CONSTRUCTION AREA ARE DISTURBED BY URBANIZATION DEVELOPMENT WITH ROAD/SIDEWALK PAVEMENT OVER SAND/GRAVEL BASE. SOIL HYDRAULIC GROUP FOR THE PROJECT AREA IS D.

NOT STABILIZED WITH PAVEMENT WILL BE STABILIZED WITH GRASS, MULCH, OR SOD.

ALL OF THE AREA DISTURBED WITH THIS PLAN WILL BE RESTORED TO A SIMILAR EXISTING CONDITION. ALL AREA

THE EROSION AND SEDIMENT CONTROL INSPECTOR SHALL HAVE THE AUTHORITY TO ADD OR DELETE EROSION AND

SEDIMENT CONTROLS AS NEEDED IN THE FIELD OR AS SITE CONDITIONS WARRANT. IN ADDITION, NO SEDIMENT TRAPS OR BASINS MAY BE REMOVED WITHOUT PRIOR APPROVAL OF THE INSPECTOR. LANDSCAPE / TREE PRESERVATION NOTES

PRIOR TO ANY LAND DISTURBING ACTIVITY THE CONTRACTOR SHALL CONTACT THE ARLINGTON COUNTY ARBORIST TO SCHEDULE AN INSPECTION. STORMWATER RUNOFF CONSIDERATIONS:

EXISTING STORMWATER SYSTEM WILL BE USED TO DRAIN THE STORMWATER RUNOFF, THE IMPERVIOUS AREA

WITHIN THE PROJECT LIMIT IS INCREASED BY 420 SF (0.0096 AC), THEREFORE THERE IS NO SIGNIFICANT CHANGE IN STORM WATER QUANTITY RESULTING FROM THIS PROJECT.

EROSION AND SEDIMENT CONTROL MEASURES

THE EROSION AND SEDIMENT CONTROL MEASURES FOR THIS PROJECT AREA INCLUDES INLET PROTECTION. INLET PROTECTION MAY BE REQUIRED OUTSIDE THE PROJECT LIMITS WHEN WATER FROM DISTURBED AREA WILL FLOW

UNLESS OTHERWISE INDICATED, ALL VEGETATIVE AND STRUCTURAL EROSION AND SEDIMENT CONTROL PRACTICES SHALL BE CONSTRUCTED AND MAINTAINED ACCORDING TO THE MINIMUM STANDARDS AND SPECIFICATIONS OF THE VIRGINIA EROSION AND SEDIMENT CONTROL HANDBOOK (VESCH) AND THE ARLINGTON COUNTY EROSION AND SEDIMENT CONTROL ORDINANCE. THE MINIMUM STANDARDS OF THE VIRGINIA EROSION ANS SEDIMENT CONTROL REGULATIONS (VESCR) SHALL BE ADHERED TO UNLESS WAIVED OR APPROVED BY VARIANCE.

RUNOFF REDUCTION SPREADSHEET INFORMATION:

THE RUNOFF REDUCTION SPREADSHEET INFORMATION ON THIS PLAN IS FOR DATA TRACKING PURPOSES TO DOCUMENT THE AREA OF LAND DISTURBANCE AND TO CHARACTERIZE PRE- AND POST-DEVELOPMENT LAND USE CONDITIONS.

IN ACCORDANCE WITH ARLINGTON COUNTY'S CHESAPEAKE BAY TOTAL MAXIMUM DAILY LOAD (TMDL) ACTION PLAN, APPROVED BY THE VIRGINIA DEPARTMENT OF ENVIRONMENTAL QUALITY (DEQ) ON SEPTEMBER 1, 2015, LINEAR DEVELOPMENT PROJECTS CONDUCTED BY THE COUNTY ARE ADMINISTERED AND TRACKED AS FOLLOWS CONSISTENT WITH 9VAC25-870-69.A.4, 9VAC25-870-76, AND 9VAC25-870-92:

- POLLUTANT LOAD CHANGES WILL BE COMPUTED AS DESCRIBED IN SECTION 3.A OF THE ACTION PLAN.
- RETROFIT OPPORTUNITIES WILL BE EVALUATED FOR EACH PROJECT, USING THE SCREENING AND SELECTION CRITERIA APPLIED AND DESCRIBED IN THE ADOPTED STORMWATER MASTER PLAN.
- RETROFIT PROJECTS THAT MEET THE SCREENING CRITERIA AND ARE DETERMINED BY ARLINGTON TO BE FEASIBLE AND COST-EFFECTIVE WILL BE IMPLEMENTED WITH SPECIFIC LINEAR DEVELOPMENT PROJECTS. POLLUTANT LOAD REDUCTIONS FROM RETROFIT PROJECTS WILL BE COMPUTED AS DESCRIBED IN SECTION 5 OF THE ACTION PLAN.
- IN CASES WHERE RETROFIT PROJECTS ARE NOT FEASIBLE AND COST-EFFECTIVE FOR A PARTICULAR LINEAR PROJECT, ANY POLLUTANT OF CONCERN (POC) LOAD INCREASES THAT MIGHT OCCUR FOR THAT PROJECT WILL BE ADDRESSED BY LARGER OVERALL POC LOAD REDUCTIONS IN PLACE OR ADDED THROUGH TMDL ACTION PLAN

IN THE ABOVE MANNER ARLINGTON, AS THE MS4 OPERATOR AND THE CONSTRUCTION SITE OPERATOR FOR ITS LINEAR DEVELOPMENT PROJECTS, IMPLEMENTS LINEAR PROJECTS AND RETROFIT PROJECTS IN A MANNER THAT ACHIEVES THE MOST TMDL POC REDUCTION FOR THE LEAST COST, WHILE FULLY ACCOUNTING FOR LOAD CHANGES THAT OCCUR WITH LINEAR DEVELOPMENT PROJECT ACTIVITY CONSISTENT WITH THE DEO CHESAPEAKE BAY TMDL SEPVEISIAD CONNIDITION POUT BOANCE.

GENERAL EROSION & SEDIMENT CONTROL NOTES

- 1. UNLESS OTHERWISE INDICATED, ALL VEGETATIVE AND STRUCTURAL EROSION AND SEDIMENT CONTROL PRACTICES SHALL BE CONSTRUCTED AND MAINTAINED ACCORDING TO THE LATEST EDITIONS OF THE VIRGINIA EROSION AND SEDIMENT CONTROL HANDBOOK (VESCH) AND THE ARLINGTON COUNTY EROSION AND SEDIMENT CONTROL ORDINANCE.
- 2. THE PLAN APPROVING AUTHORITY MUST BE NOTIFIED ONE WEEK PRIOR TO THE PRE-SCONSTRUCTION CONFERENCE, ONE WEEK PRIOR TO THE COMMENCEMENT OF LAND DISTURBING ACTIVITY AND ONE WEEK PRIOR TO THE FINAL INSPECTION.
- 3. ALL EROSION AND SEDIMENT CONTROL MEASURES ARE TO BE PLACED PRIOR TO OR AS A FIRST STEP IN CLEARING.
- 4. A COPY OF THE APPROVED EROSION AND SEDIMENT CONTROL PLANS SHALL BE MAINTAINED ON THE SITE AT ALL TIMES.
- 5. PRIOR TO COMMENCING LAND DISTURBING ACTIVITIES IN AREAS OTHER THAN INDICATED ON THESE PLANS (INCLUDING BUT NOT LIMITED TO OFF-SITE BORROW OR WASTE AREAS), THE CONTRACTOR SHALL SUBMIT A SUPPLEMENTARY EROSION CONTROL PLAN TO THE OWNER FOR REVIEW AND APPROVAL BY THE PLAN APPROVING AUTHORITY.
- 6. THE CONTRACTOR IS RESPONSIBLE FOR INSTALLATION OF ANY ADDITIONAL EROSION CONTROL MEASURES NECESSARY TO PREVENT EROSION SEDIMENTATION AS DETERMINED BY THE PLAN APPROVING AUTHORITY.
- 7. ALL DISTURBED AREAS ARE TO DRAIN TO APPROVED SEDIMENT CONTROL MEASURES AT ALL TIMES DURING LAND DISTURBING ACTIVITIES DURING SITE DEVELOPMENT UNTIL FINAL STABILIZATION IS ACHIEVED.
- 8. DURING DENATURING OPERATIONS, WATER WILL BE PUMPED INTO AN APPROVED FILTERING DEVICE.

GENERAL LAND CONSERVATION NOTES

- 1. NO DISTURBED AREA WHICH IS NOT ACTIVELY BEING WORKED SHALL REMAIN DENUDED FOR MORE THAN 7 CALENDAR DAYS UNLESS OTHERWISE AUTHORIZED BY THE DIRECTOR OR
- 2. ALL E&S CONTROL MEASURES APPROVED WITH THE E&S CONTROL PLAN SHALL BE PLACED AS THE FIRST STEP IN GRADING.
- 3. ALL STORM AND SANITARY SEWER LINES NOT IN STREETS SHALL BE SEEDED AND MULCHED
- WITHIN 5 DAYS AFTER BACKFILL. NO MORE THAN 500' (150M) SHALL BE OPEN AT ANY TIME. 4. ELECTRIC POWER, TELEPHONE AND GAS SUPPLY TRENCHES SHALL BE COMPACTED, SEEDED AND MULCHED WITHIN 5 DAYS AFTER BACKFILL
- 5. ALL TEMPORARY EARTH BERMS, DIVERSIONS AND SEDIMENT CONTROL DAMS SHALL BE SEEDED AND MULCHED FOR TEMPORARY VEGETATIVE COVER IMMEDIATELY AFTER. STRAW OR HAY MULCH IS REQUIRED. ALL SOIL STOCKPILES SHALL BE SEEDED AND MULCHED IMMEDIATELY AFTER GRADING.
- 6. DURING CONSTRUCTION, ALL STORM SEWER INLETS SHALL BE PROTECTED BY SEDIMENT TRAPS, MAINTAINED AND MODIFIED DURING CONSTRUCTION PROGRESS AS REQUIRED.
- 7. ANY DISTURBED AREA NOT COVERED BY NOTE 1 ABOVE AND NOT PAVED, SODDED OR BUILT UPON BY NOV. 1, OR DISTURBED AFTER THAT DATE, SHALL BE MULCHED IMMEDIATELY WITH HAY OR STRAW MULCH AT THE RATE OF 2 TONS/ACRE AND OVER-SEEDED BY APRIL 15.
- 8. AT THE COMPLETION OF ANY PROJECT CONSTRUCTION AND PRIOR TO BOND RELEASE, ALL TEMPORARY SEDIMENT CONTROLS SHALL BE REMOVED AND ALL DENUDED AREAS SHALL BE STABILIZED.

UTILITY INSTALLATION

UNDERGROUND UTILITY LINES SHALL BE INSTALLED IN ACCORDANCE WITH THE FOLLOWING STANDARDS IN ADDITION TO OTHER APPLICABLE CRITERIA:

- 1. NO MORE THAN 500 LINEAR FEET OF TRENCH MAY BE OPENED AT ONE TIME.
- 2. EXCAVATED MATERIAL SHALL BE PLACED ON THE UPHILL SIDE OF TRENCHES.
- 3. EFFLUENT FROM DEWATERING OPERATIONS SHALL BE FILTERED OR PASSED THROUGH AN APPROVED SEDIMENT TRAPPING DEVICE, OR BOTH, AND DISCHARGED IN A MANNER THAT DOES NOT ADVERSELY AFFECT FLOWING STREAMS OR OFF-SITE PROPERTY.
- 4. MATERIAL USED FOR BACKFILLING TRENCHES SHALL BE PROPERLY COMPACTED IN ORDER TO MINIMIZE EROSION AND PROMOTE STABILIZATION.
- 5. RESTABILIZATION SHALL BE ACCOMPLISHED IN ACCORDANCE WITH THESE REGULATIONS.

6. APPLICABLE SAFETY REGULATIONS SHALL BE COMPLIED WITH. **TEMPORARY SEEDING:**

SEE SHEET III-288 OF THE VIRGINIA EROSION AND SEDIMENT CONTROL HANDBOOK (VESCH) FOR ALLOWABLE PLANTING MATERIAL, SEEDING RATES, AND DATES. THE REQUIREMENTS OF THE "SOUTH" PLANTING REQUIREMENTS SHALL BE FOLLOWED. LIMING SHALL BE BASED ON TABLE 3.31-A OF VESCH. FERTILIZERS SHALL BE APPLIED AS 600 LB/ACRE. THE FERTILIZER SHALL BE INCORPORATED INTO THE TOP 2-4" OF SOIL. SEED SHALL BE EVENLY APPLIED AND SMALL GRAINS SHALL BE PLANTED NO MORE THAN 1.5" DEEP. SEEDING MADE IN FALL FOR WINTER COVER AND DURING HOT SUMMER MONTHS SHALL BE MULCHED.

PERMANENT SEEDING:

THE SUBJECT SITE IS LOCATED IN THE COASTAL PLAIN AREA OF VIRGINIA, SO SHEET III-304 OF THE VIRGINIA EROSION AND SEDIMENT CONTROL HANDBOOK SHALL BE FOLLOWED FOR FINAL SEEDING MATERIAL, SEEDING RATES, AND DATES OF APPLICATION.

SODDED AREAS SHALL BE BROUGHT TO FINAL GRADE IN ACCORDANCE WITH THE APPROVED PLANS, SOIL TEST SHOULD BE MADE TO DETERMINE THE EXACT REQUIREMENTS FOR LIME AND FERTILIZER. PRIOR TO LAYING SOD, SOIL SURFACE SHALL BE CLEAR OF TRASH, DEBRIS AND LARGE OBJECTS, OUALITY OF SOD SHALL BE STATE CERTIFIED AND ENSURE GENETIC PURITY AND HIGH QUALITY. SOD SHALL NOT BE LAID IN EXCESSIVELY WET OR DRY WEATHER AND BE DELIVERED AND INSTALLED WITHIN 36 HOURS. SOD SHOULD NOT BE LAID ON FROZEN SOIL SURFACE AND SHALL BE INSTALLED PER PAGE III-339 OF VESCH.

DUST CONTROL:

DUST SHALL BE CONTROLLED USING A VARIETY OF METHODS TO INCLUDE VEGETATIVE COVER, MULCH, TILLAGE, IRRIGATION, SPRAY-ON ADHESIVES, STONE, BARRIERS, AND CALCIUM CHLORIDE. THE IMPLEMENTATION OF THE DUST CONTROL METHODS SHALL BE INSTALLED PER SECTION 3.39 OF VESCH.

MAINTENANCE PROGRAM:

THE FOLLOWING IS A PROGRAM OF MAINTENANCE FOR THE MECHANICAL CONTROLS SPECIFIED IN THIS NARRATIVE AND ON THE PLAN:

- 1. THE SITE SUPERINTENDENT OR HIS/HER REPRESENTATIVE SHALL MAKE A VISUAL INSPECTION OF ALL MECHANICAL CONTROLS AND NEWLY STABILIZED AREA (I.E. SEEDED AND MULCHED AND/OR SODDED AREAS) ON A DAILY BASIS; ESPECIALLY AFTER A HEAVY RAINFALL EVENT TO INSURE THAT ALL CONTROLS ARE MAINTAINED AND PROPERLY FUNCTIONING. ANY DAMAGED CONTROLS SHALL BE REPAIRED PRIOR TO THE END OF THE WORK DAY INCLUDING RE-SEEDING AND MULCHING OR RE-SODDING IF NECESSARY.
- 2. ALL SEDIMENT TRAPPING DEVICES SHALL BE CLEARED OUT AT 50% TRAP CAPACITY AND THE SEDIMENT SHALL BE DISPOSED OF BY SPREADING ON THE SITE OR IF NOT SUITABLE FOR FILL, HAULING AWAY AND DEPOSITING AT AN ACCEPTABLE DUMP SITE.
- 3. THE CONTRACTOR SHALL TAKE SPECIAL CARE TO PREVENT MUD AND/OR OTHER DEBRIS FROM BEING ENTERED ONTO EXISTING SWM/BMP FACILITIES OR DOWN STREAM WATER WAYS. SHOULD OFF SITE AREAS BECOME POLLUTED BY CONSTRUCTION ACTIVITIES, THE CONTRACTOR SHALL BE RESPONSIBLE FOR CLEANING THE EFFECTED AREAS TO THE SATISFACTION OF THE INSPECTOR.
- 4. AT THE COMPLETION OF CONSTRUCTION AND PRIOR TO BOND RELEASE, ALL TEMPORARY SEDIMENT CONTROLS SHALL BE REMOVED AND ANY REMAINING DENUDED AREAS SHALL BE STABILIZED. CERTAIN DEVICES MAY BE REMOVED PRIOR TO CONSTRUCTION COMPLETION BUT ONLY WITH THE APPROVAL OF THE COUNTY INSPECTOR.
- 5. AFTER CONSTRUCTION OPERATIONS HAVE ENDED, ALL DISTURBED AREAS SHALL BE STABILIZED. UPON APPROVAL OF THE COUNTY INSPECTOR, MECHANICAL SEDIMENT CONTROLS SHALL BE REMOVED AND THE GROUND PERMANENTLY STABILIZED WITH VEGETATION WITHIN 30 DAYS.

THIS SHEET IS FOR EROSION AND SEDIMENT CONTROL USE ONLY

FOR ALL DETAILS AND SPECIFICATIONS, SEE THE VIRGINIA

EROSION & SEDIMENT CONTROL HANDBOOK

TABLE 3.31-B (Revised June 2003) TEMPORARY SEEDING SPECIFICATIONS QUICK REFERENCE FOR ALL REGIONS

<u>SEED</u>					
APPLICATION DATES	SPECIES	APPLICATION RATES			
Sept. 1 - Feb. 15	50/50 Mix of Annual Ryegrass (Iolium multi- florum) & Cereal (Winter) Rye (Secale cereale)	50 -100 (lbs/acre)			
eb. 16 - Apr. 30	Annual Ryegrass (lolium multi-florum)	60 - 100 (lbs/acre)			
/lay 1 - Aug. 31	German Millet	50 (lbs/acre)			

FERTILIZER & LIME

- Apply 10-10-10 fertilizer at a rate of 450 lbs. / acre (or 10 lbs. / 1,000 sq. ft.)
- Apply Pulverized Agricultural Limestone at a rate of 2 tons/acre (or 90 lbs. / 1,000 sq. ft.)

 A soil test is necessary to determine the actual amount of lime required to adjust the soil pH of site. 2 - Incorporate the lime and fertilizer into the top 4 – 6 inches of the soil by disking or by other means.

3 - When applying Slowly Available Nitrogen, use rates available in Erosion & Sediment Control Technical Bulletin 4, 2003 Nutrient Management for Development Sites at http://www.dcr.state.va.us/sw/e&s.htm#pubs

TABLE 3.32-D (Revised June 2003) PERMANENT SEEDING SPECIFICATIONS FOR PIEDMONT AREA

SEED ¹						
LAND USE	SPECIES	APPLICATION PER ACRE				
Minimum Care Lawn Commercial or Residential)	Tall Fescue ¹ Perennial Ryegrass Kentucky Bluegrass ¹	95-100% 0-5% 0-5% TOTAL: 175-200 lbs.				
High-Maintenance Lawn	Tall Fescue ¹	TOTAL: 200-250 lbs.				
General Slope (3:1 or less)	Tall Fescue ¹ Red Top Grass or Creeping Red Fescue Seasonal Nurse Crop ²	128 lbs. 2 lbs. <u>20 lbs.</u> TOTAL: 150 lbs.				
ow-Maintenance Slope Steeper than 3:1)	Tall Fescue ¹ Red Top Grass or Creeping Red Fescue Seasonal Nurse Crop ² Crownvetch ³	108 lbs. 2 lbs. 20 lbs. 20 lbs. TOTAL: 150 lbs.				

1 - When selecting varieties of turfgrass, use the Virginia Crop Improvement Association (VCIA) recommended turfgrass variety list. Quality seed will bear a label indicating that they are approved by VCIA. A current turfgrass variety list is available at the local County Extension office or through VCIA at 804-746-4884 or at http://sudan.cses.vt.edu/html/Turf/turf/publications/publications2.html

2 - Use seasonal nurse crop in accordance with seeding dates as stated below:

February 16th - April Annual Rye May 1st - August 15th August 16th - October Annual Rye November - February 15th . Winter Rye

3 - Substitute Sericea lespedeza for Crownvetch east of Farmville, VA (May through September use hulled seed, all other periods, use unhulled Sericea). If Flatpea is used, increase rate to 30 lbs./acre. If Weeping Lovegrass is used, include in any slope or low maintenance mixture during warmer seeding periods, increase to 30 -40

FERTILIZER & LIME

Apply 10-20-10 fertilizer at a rate of 500 lbs. / acre (or 12 lbs. / 1,000 sq. ft.)

- A soil test is necessary to determine the actual amount of lime required to adjust the soil pH of site.

- Apply Pulverized Agricultural Limestone at a rate of 2 tons/acre (or 90 lbs. / 1,000 sq. ft.)
- Incorporate the lime and fertilizer into the top 4 6 inches of the soil by disking or by other means. When applying Slowly Available Nitrogen, use rates available in Erosion & Sediment Control Technical Bulletin # 4, 2003 Nutrient Management for Development Sites at http://www.dcr.state.va.us/sw/e&s.htm#pubs

Pre-Storm Erosion and Sediment Control Checklist

Per Erosion and Sediment Control General Note 6, the Contractor is responsible for the installation and maintenance of any additional erosion and sediment control (ESC) measures necessary to prevent erosion and sedimentation as determined by the County. These supplementary practices are in addition to those shown in an ESC plan. ESC practices shall be modified as needed to ensure only clear water is discharged from the site.

The following actions shall be taken prior to storm events with predicted heavy and/or large volume rainfall to prevent sediment discharges from a construction site. A typical summer thunderstorm is an example of a storm event with predicted heavy and/or large volume rainfall.

Perimeter controls

- Silt fence shall be checked for undermining, holes, or deterioration of the fabric. Fencing shall be replaced immediately if the fabric is damaged or worn. Silt fence must be trenched into the ground per state specifications (Std & Spec 3.09).
- ☐ Wooden stakes or steel posts shall be properly secured upright into the ground. Damaged posts or stakes must be replaced.
- ☐ Sediment that has accumulated against the silt fence should be removed. Accumulated sediment must be removed when the level reaches one-half the height of the fencing.
- ☐ Hay bales or a stone berm should be placed across the construction entrance to prevent sediment from leaving the construction site.

Exposed slopes and soil

- ☐ Exposed slopes not at the final stabilization phase shall be covered with tarps, plastic sheeting, or erosion control matting. Covering material shall be properly secured/anchored.
- ☐ Controls shall be installed to prevent concentrated flow down an exposed slope. Berms or diversion dikes shall be installed at the top of cut / exposed slopes to direct storm flow around the disturbed area.
- ☐ Exposed slopes at the final stabilization phase shall be stabilized using slope stabilization practices such as soil stabilization blankets or matting as specified in the Virginia Erosion and Sediment Control Handbook (VESCH) Std & Spec 3.36. Blankets or mats must be properly secured and anchored to the slope using staples, pins, or stakes.
- ☐ Seeded areas shall be checked and reseeded as necessary to cover exposed soil. Recently seeded areas shall be protected by straw or soil stabilization blankets to prevent seeding from being washed away.

Stockpiles

☐ Stockpiled soil and other loose materials that can be washed away shall be covered with a tarp, plastic sheeting, or other stabilization matting. The cover must be properly secured / anchored down to prevent it from being blown off and exposing materials to rain. Controls such as hay bales or booms should be placed along the perimeter of the stock pile (downhill side).

Inlet protection

☐ Inlet protection controls shall be inspected to ensure they are functioning properly and flooding will not occur. Clogged or damaged controls must be replaced immediately. Ensure controls allow for overflow / bypass of stormwater runoff during significant storm events

In addition to these pre-storm actions, all erosion and sediment control (ESC) measures must be checked daily and after each significant rainfall.

MA13 SEGMENT (PRE AND POST DEVELOPMENT LAND COVER CALCULATIONS


TOTAL PROJECT AREA

LIMITS OF WORK (LOW)				0.4798	20900	AC/SF	
IMITS OF DISTURBANCE (LOD)				0.3076	13400	AC/SF	
	PRE DE	/ [AC/SF]	POST DE	(AC/SF)	NET CHANG	E [AC/SF]	
(LOD) IMPERVIOUS AREA	0.2801	12200	0.2897	12620	0.0096	420	
(LOD) PERVIOUS AREA	0.0275	1200	0.0179	780	-0.0096	-420	

ARLINGTON VIRGINIA

DEPARTMENT OF **ENVIRONMENTAL SERVICES FACILITIES & ENGINEERING DIVISION ENGINEERING BUREAU** 2100 CLARENDON BOULEVARD, SUITE 813 ARLINGTON, VA 22201 PHONE: 703.228.3629 FAX: 703.228.3606

COPYRIGHT © 2016 ARLINGTON COUNTY VIRGINIA - ALL RIGHTS RESERVED



APPROVALS Kamal Taktak CONSTRUCTION MANAGEMENT SUPERVISOR WATER, SEWER, STREETS BUREAU CHIEF

Dennis M. Leach 03/17/21

PROJECT MANAGER **REVISIONS**

TRANSPORTATION DIRECTOR

Diana Isaza

 O NOI

SITWAY


DESIGNED: PB DRAWN: NS CHECKED: TL MISS UTILITY TRANSMITTAL #: N/A

TRANS<u>.</u>

FILENAME: MA13-224-E_AND_S_PLAN.DWG PATH:\\DES-CAD-S2\ENGINEERING_DATA\DA A\MA1 PLOTTED: AUGUST 4 2021

SCALE: N/A

PLOTTED BY:NSHARP



DEQ Virginia Runoff Reduction Method Re-Development Compliance Spreadsheet - Version 3.0

1
date

Qianqian Li, P.E.
ESC Program Administrator
Department of Environmental Sevices
2100 Clarendon Boulevard, Suite 813
Arlington, Virginia 22201

Re: Erosion and Sediment Control Permit Application for: MA13 - Crystal City Transitway Extension

Crystal Dr/18 St S & 12 St S/Long Bridge Dr

lot, block, section subdivision

permit number

Dear Mrs. Li:

I hereby certify that I accept the responsibilities of <u>Responsible Land Disturber</u> for the above referenced project. I understand that these responsibilities include:

- 1. Reviewing the erosion and sedimentation (E&S) plan for the project.
- Walking the site prior to construction to identify critical areas.
 Conducting a pre-construction briefing with earth moving and site contractors to present the E&S plan and highlight the presence of critical areas, the limits of clearing and the required E&S controls and tree protection
- measures to be installed. Call 703-228-0760 to schedule pre-construction meeting.

 4. Regularily inspecting the site during construction to ensure that all E&S controls are functioning and are
- adequate to address crosion and sedimentation. Inspect the site 48 hours after a runoff-generating storm, and provide a copy of the inspection findings to the county.
- 5. Reporting to the owner the presence inadequate or non functioning E&S controls when they are observed.
 6. Ensuring that temporary soil stabilization is applied within 7 days to areas denuded that will remain undisturbed for longer than 14 days. Permanent stabilization shall be applied to areas that are to be left dormant
- for more than one year.

 7. Calling (703) 228-0760 at least 80 hours before demolishing any structure.

I may be reached at 703-228-0596 with questions about this plan or my execution of the duties of telephone number

Responsible Land Disturber.

signed
TREVOR LANTLY
name printed
PE, 0402050508

professional registration (type and number)

STORMWATER POLLUTION PREVENTION PLAN MA13 – Crystal City Transitway Extension

STORMWATER POLLUTION PREVENTION PLAN (SWPPP) Arlington County Projects (Roadway Improvement)

For Construction Activities At:

MA13 – Crystal City Transitway Extension
Crystal Dr/18 St S and 12th St S/Long Bridge Dr Intersections

Arlington, VA 22202

Crystal Dr
Latitude: 38.8607 N (decimal degrees)
Longitude: 77.0493 W (decimal degrees)
12th St S
Latitude: 38.8630 N (decimal degrees)
Longitude: 77.0509 W (decimal degrees)

Construction Activity Operator:

Insert Company/Organization Name
Insert Name
Insert Address
Insert City, State, Zip Code
Insert Telephone Number
Insert Email Address
Insert 24-hour Emergency Contact

SWPPP Preparation Date:

August 01, 2018

CERTIFICATION

"I certify under penalty of law that I have read and understand this document and that this document and all attachments were prepared in accordance with a system designed to assure that qualified personnel properly gathered and evaluated the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations."

erator Nan	ne;		
Tit	le:		5
Signatu	re:		
Da	te:		

Arlington County SWPPP 12/2016

RESPONSIBLE LAND DISTURBER (RLD) NOTE

UPON AWARD OF COUNTY'S CONSTRUCTION CONTRACT, CONTRACTOR IS RESPONSIBLE FOR APPLYING AND TRANSFERRING THE OWNERSHIP OF RESPONSIBLE LAND DISTURBER PRIOR TO STARTING ANY LAND DISTURBANCE WITHIN THE PROJECT SITE. FOR THIS PERMIT APPLICATION, A SIGNED COPY OF THE RESPONSIBLE LAND DISTURBER WILL BE SUBMITTED SEPARATELY.

POLLUTION PREVENTION PLAN NOTES

ONLY THE FOLLOWING NON-STORMWATER DISCHARGES ARE AUTHORIZED BY ARLINGTON COUNTY'S MS4 PERMIT, UNLESS THE STATE WATER CONTROL BOARD, THE VIRGINIA SOIL AND WATER CONSERVATION BOARD (BOARD), OR ARLINGTON COUNTY DETERMINES THE DISCHARGE TO BE A SIGNIFICANT SOURCE OF POLLUTANTS TO SURFACE WATERS:

WATER LINE FLUSHING; LANDSCAPE IRRIGATION; DIVERTED STREAM FLOWS; RISING GROUND WATERS; UNCONTAMINATED GROUND WATER INFILTRATION (AS DEFINED AT 40 CFR 35.2005(20)); UNCONTAMINATED PUMPED GROUND WATER; DISCHARGES FROM POTABLE WATER SOURCES; FOUNDATION DRAINS; AIR CONDITIONING CONDENSATION; IRRIGATION WATER; SPRINGS; WATER FROM CRAWL SPACE PUMPS; FOOTING DRAINS; LAWN WATERING; INDIVIDUAL RESIDENTIAL CAR WASHING; FLOWS FROM RIPARIAN HABITATS AND WETLANDS; DECHLORINATED SWIMMING POOL DISCHARGES; DISCHARGES OR FLOWS FROM FIRE FIGHTING; AND, OTHER ACTIVITIES GENERATING DISCHARGES IDENTIFIED BY THE DEPARTMENT OF ENVIRONMENTAL QUALITY AS NOT REQUIRING VPDES AUTHORIZATION.

APPROPRIATE CONTROLS MUST BE IMPLEMENTED TO PREVENT ANY NON-STORMWATER DISCHARGES NOT INCLUDED ON THE ABOVE LIST (E.G., CONCRETE WASH WATER, PAINT WASH WATER, VEHICLE WASH WATER, DETERGENT WASH WATER, ETC.) FROM BEING DISCHARGED INTO ARLINGTON COUNTY'S MS4 SYSTEM, WHICH INCLUDES THE CURB AND GUTTER SYSTEM, AS WELL AS CATCH BASINS AND OTHER STORM DRAIN INLETS, OR STREAM NETWORK.

PER CHAPTER 26 OF THE ARLINGTON COUNTY CODE, IT SHALL BE UNLAWFUL FOR ANY PERSON TO DISCHARGE DIRECTLY OR INDIRECTLY INTO THE STORM SEWER SYSTEM OR STATE WATERS, ANY SUBSTANCE LIKELY, IN THE OPINION OF THE COUNTY MANAGER, TO HAVE AN ADVERSE EFFECT ON THE STORM SEWER SYSTEM OR STATE WATERS.

STORMWATER POLLUTION PREVENTION PLAN MA13 – Crystal City Transitway Extension

1.0 SWPPP Documents Located Onsite & Available for Review

SWPPP Document Type	Located Onsite & Available for R	Review?
Registration Statement	☐ Yes ☐ NA	
Notice of Coverage Letter	☐ Yes ☐ NA	
Construction General Permit	☐ Yes ☐ NA	
Pollution Prevention Plan		
Erosion & Sediment Control Plan		
Stormwater Management Plan	☐ Yes ☐ NA	
LDA Permit	☐ Yes ☐ NA	

Required documents must be kept at a centralized location on the project site (i.e. in a mail box or other container)

2.0 Authorized Non-Stormwater Discharges

Type of Authorized Non-Stormwater Discharges	Likely Prese	nt at Your Project Site?
Uncontaminated excavation dewatering Landscape irrigation Others [describe]	⊠ Yes □ Yes □ Yes	□ No □ No

3.0 Pollution Prevention Awareness

Employees will be given a "walk through" of the site identifying areas of possible pollution and will be shown Erosion and Sediment Controls and Pollution Prevention Practices (identified in Sections 4.0 and 5.0 of this SWPPP) that are applicable to their assigned job duties. A refresher meeting and "walk through" will be conducted on an as needed basis.

4.0 Erosion & Sediment Controls

Select all that apply	Erosion & Sediment Control	Estimated Installation Date	Estimated Removal Date	Responsible Party (Name, Contact Phone Number)
	Construction Entrance (Std. & Spec. 3.02)			
	Silt Fence (Std. & Spec. 3.05)			
	Culvert Inlet Protection (Std. & Spec. 3.08)			
	Outlet Protection (Std. & Spec. 3.18)	, v	NA	
\boxtimes	Temporary Seeding (Std. & Spec. 3.31)	As required	NA	
	Permanent Seeding (Std. & Spec. 3.32)		NA	
	Sodding (Std. & Spec. 3.33))	NA	
	Mulching (Std. & Spec. 3.35)		NA	
	Safety Fence (Std. & Spec 3.01)			
\boxtimes	Storm Drain Inlet Protection			

Arlington County SWPPP 12/2016

DEPARTMENT OF

ARLINGTON

VIRGINIA

ENVIRONMENTAL SERVICES

FACILITIES & ENGINEERING DIVISION
ENGINEERING BUREAU
2100 CLARENDON BOULEVARD, SUITE 813
ARLINGTON, VA 22201
PHONE: 703.228.3629
FAX: 703.228.3606

COPYRIGHT © 2016 ARLINGTON COUNTY VIRGINIA - ALL RIGHTS RESERVED

SEAL

TREVOR M. LANTZY

Lic. No. 0402050508

8/4/2021

APPROVALS

DATE

| 3/29/21 |
| QUALITY CONTROL ENGINEER |
| Amal Taktak |
| CONSTRUCTION MANAGEMENT SUPERVISOR

WATER, SEWER, STREETS BUREAU CHIEF

Dennis M. Leach 03/17/21

TRANSPORTATION DIRECTOR

Diana Isaza 3/2/21

PROJECT MANAGER

REVISIONS DA

EXTENSION TO SON CITY PREVENTION PLAN & 12TH ST S

TRANSITWAY EXTENS

PENTAGON CITY

SW POLLUTION PREVENT

CRYSTAL DR & 12TH

DRAWN: NS
CHECKED: TL
MISS UTILITY TRANSMITTAL #: N/A
FILENAME:
MA13-224-E_AND_S_PLAN.DWG
PATH:\\DES-CAD-S2\ENGINEERING_DATA\DATA\MA13

SCALE: N/A

PLOTTED: AUGUST 4 2021

CALE: N/A

HEET 14 OF 35

STORMWATER POLLUTION PREVENTION PLAN MA13 – Crystal City Transitway Extension

	(Std. & Spec 3.08 and/or Arlington County Std. & Spec from approved ESC plan)	
\boxtimes	Dewatering (Std. & Spec 3.26 and/or Arlington County Std. & Spec from approved ESC plan)	
	Turbidity Curtain (Std. & Spec 3.27 and/or Arlington County Std. & Spec from approved ESC plan)	
	Tree Protection (Arlington County Std. & Spec from approved ESC plan)	
	Stream Crossing / Cofferdams (Std. & Spec 3.25 or on plan)	
	Pump Around System (detail on approved plan)	
	Rip Rap (Std. & Spec. 3-19)	
	Other(s) [describe]	


Pre-Storm Erosion and Sediment Control Checklist

The following actions shall be taken <u>prior to storm events with predicted heavy and/or large volume rainfall</u> to prevent sediment discharges from a construction site. A typical summer thunderstorm is an example of a storm event with predicted heavy and/or large volume rainfall.

- Perimeter controls (silt fence, hay bales, stone berms) used to prevent sediment from leaving the site shall be checked for undermining, holes, or deterioration and repaired/replaced if needed.
- Sediment that has accumulated against perimeter controls shall be removed if the depth exceeds more than 1/2 of
- Exposed soil or slopes shall be covered with straw, tarps, plastic sheeting, or erosion control matting. Covering material shall be properly secured/anchored.
- Stockpiled soil and other loose materials that can be washed away shall be covered with a tarp, plastic sheeting, or other stabilization matting. The cover must be properly secured / anchored down to prevent it from being blown off and exposing materials to rain. Controls such as hay bales or booms should be placed along the perimeter of the stock pile (downhill side). Stockpiled materials should not obstruct flow along the curb line.
- Inlet protection controls shall be inspected to ensure they are installed per approved ESC plan, are functioning properly, and maintained as needed.

Arlington County SWPPP 12/2016

STORMWATER POLLUTION PREVENTION PLAN



- (4) Washing / cleaning Prevent the discharge of wash water to the storm drain system or surface waters.

 - Provide a suitable containment system for cleaning equipment such as a drum, prefabricated system, lined container, or portable wash pad.
 - ☐ The wash / containment area must be sized appropriately for the needs of the project.

 - Dewatering operations Construction site dewatering may not be discharged without treatment. Sediment laden or turbid water shall be filtered, settled or similarly treated prior to discharge.
 - □ Dewatering detail on approved ESC plan will be used.
 - □ Dewatering option from Planning & Field Guide for Pollution Prevention (P2):
 □ Filter Box
 - Straw Bale/Silt Fence Pit
 Portable Sediment Tank
 Filter Bag

Arlington County SWPPP 12/2016

STORMWATER POLLUTION PREVENTION PLAN

5.0 Potential Sources of Pollution & Pollution Prevention Practices

			1	Polluta	ants								
Pollutant-Generating Activity	Likely Present at your Project Site?	Sediment	Nutrients	Heavy Metals	pH (acids and bases)	Pesticides & Herbicides	Oil & Grease	Bacteria & Viruses	Trash, Debris, Solids	Other Toxic Chemicals	Pollution Prevention Practice	Responsible Party (Name, Contact Phone Number)	
Clearing, grading, excavating, and un-stabilized areas	⊠ Yes □ No	х	Х			3		:	х		(1)		
Paving and saw cutting operations	⊠ Yes □ No	Х					х		х		(2)		
Concrete operations, washout, and cement waste	⊠ Yes □ No			х	×				х		(3)		
Washing / cleaning	⊠ Yes □ No	Х	×	X	×		×		X	X	(4)		
Dewatering operations	⊠ Yes □ No	х	×						×		(5)		
Material / chemical use and storage	⊠ Yes □ No	х	X	х	×	х	X		x	x	(6)		
Equipment and vehicle maintenance	⊠ Yes □ No				×		X		х	×	(7)		
Waste management / disposal	☐ Yes ⊠ No			N					×	х	(8)		
Sanitary waste	⊠ Yes □ No		х		×			х			(9)	_	
Nutrient management	☐ Yes ⊠ No	х	х						х	х	(10)		

Arlington County SWPPP 11/2016

STORMWATER POLLUTION PREVENTION PLAN

(6) Material / chemical use and storage –Designate areas of the construction site for material delivery and storage. Locate these areas near construction entrances and away from waterways and storm drains. Enclose, cover or berm construction material storage areas if susceptible to stormwater.

Stockpiled soil and other loose materials that can be washed away shall be covered with a tarp, plastic sheeting, or other stabilization matting. The cover must be properly secured / anchored down to prevent it from being blown off and exposing materials to rain. Controls such as hay bales or booms should be placed along the perimeter of the stock pile (downhill side).

Stockpiled materials located on the edge of roadways should not obstruct flow along the curb line (gutter). Leave at least a one (1) foot space away from the curb to allow stormwater to flow along the curb line. Boards with cinder blocks and/or bricks may be used to create the flow through space.

Method used to ensure flow through:

- ☐ Provide secondary containment for paint, pesticides, cleaners, solvents, and/or other chemicals and keep these items secured and covered when not in use
- Regularly inspect containers.
- (7) Equipment and vehicle maintenance Use a designated area, away from storm drains and surface waters, to refuel vehicle or equipment or perform maintenance.
 - Regularly inspect vehicles and equipment for leaks. Clean up all spills and leaks upon discovery.
 - Use containment measures when conducting fueling (e.g. place spill pad, board, plastic sheeting on ground)
 - Regularly inspect fuel containers.
 - $\hfill \hfill \square$ Provide secondary containment and secure storage for fuel, oil, and/or lubricants
 - Keep drip pans, sheeting, and/or absorbent pads under heavy equipment when not in use (i.e. overnight) to capture leaks.
- (8) Waste management / disposal Designate a waste collection area on the construction site that does not receive a substantial amount of runoff from upland areas and does not drain directly to a waterway. Ensure that waste containers have lids so they can be covered before periods of rain. Schedule waste collection to prevent the containers from overfilling.
 - A sufficient number of waste containers must be kept on a site to handle the quantity of waste
 - ☐ Keep roll off containers covered and/or dumpster / trash lids closed.
 - ☐ Check waste containers frequently for damage / leaks and clean using DRY methods when necessary. Never clean out a dumpster by power washing or hosing it out.
 - ☐ Replace containers that are leaking, cracked, corroded, or otherwise deteriorating.
 - ☐ Do not bury waste material. Dispose of excess dry concrete, grout and mortar in the trash.

Arlington County SWPPP 12/2016

STORMWATER POLLUTION PREVENTION PLAN

Pollution Prevention Practices:

- Clearing, grading, excavating, and un-stabilized areas Maintain as much existing vegetation as practicable. Utilize erosion and sediment controls to prevent sediment from leaving the construction site. Dispose of clearing debris at acceptable disposal sites. Apply permanent or temporary stabilization, sodding and/or mulching to denuded areas in accordance with the erosion and sediment control specifications and the general VPDES permit for discharges of stormwater from construction activities. Plastic sheeting, tarps, 2" deep straw cover, and/or erosion matting can be used for temporary slope stabilization.
- (2) Paving and saw cutting operations Cover storm drain inlets during paving and saw cutting operations. Use pollution prevention materials such as drip pans and absorbent/oil dry for all paving machines to limit leaks and spills of paving materials and fluids. Slurry from saw cutting operations may not enter a storm drain; it must be captured and disposed of properly.

Temporary controls (i.e. tarp and block, sand berms, booms, and/or filter fabric) shall be used to cover storm drains during paving and saw cutting operations to prevent any discharges from entering the storm drain. These temporary controls SHALL BE REMOVED AT THE END OF EACH DAY. Inlet protection specified in the approved ESC plan shall be installed or reinstalled following the completion of paving or saw cutting work.

Method of covering / protecting storm drains:


Method for containment, collection, disposal of saw cut slurry:

- (3) Concrete operations, washout, and cement waste Direct concrete wash water into a leak-proof container or leak-proof settling basin that is designed so that no overflows can occur due to inadequate sizing or precipitation. Hardened concrete wastes shall be removed and disposed of in a manner consistent with the
- handling of other construction wastes.

 Washouts must be sized appropriately for the needs of the project.

 Do not locate washouts near storm drains. Concrete wash water is not allowed to enter a storm drain.
- Concrete washout areas cannot be used for the purpose of dewatering.
 Set up and operate small mixers on top of plywood that is covered by tarps or heavy plastic drop cloths.
- Set up and operate small finiters on top of plywood that is covered by tarps of heavy plastic drop cloths
 Wash out mixers and truck chutes in designated contained washout areas
 No tracking from washout areas may occur.
- Place plastic sheeting, boards, or tarps under concrete truck chutes during pouring

The selected concrete wash out facility will be used:



Arlington County SWPPP 12/2016

STORMWATER POLLUTION PREVENTION PLAN

- (9) Sanitary waste Prevent the discharge of sanitary waste by providing convenient and well-maintained portable sanitary facilities.
 - ☑ Locate portable lavatories away from storm drains and surface waters.

 - Regularly inspect facilities for leaks
- (10) Nutrient management Apply nutrients in accordance with manufacturer's recommendations. Do not apply during rainfall events or windy conditions. Provide secondary containment and keep fertilizer properly secured when not being used.

Additional information and details can be found in the Arlington County Planning & Field Guide for Pollution Prevention (P2).

6.0 Stormwater Management Controls

Select all that apply	Stormwater Management Control	Estimated Installation Date	Responsible Party	
	Exempted – stormwater management retrofit facility or stream restoration project	NA	NA NA	
	Linear development project per Arlington County Chesapeake Bay Total Maximum Daily Load (TMDL) Action Plan ¹	NA		
	Post-development Stormwater Management Controls provided by a Larger Common Plan of Development or Sale	NA	Common Plan Construction Activity Operator	
	Rooftop Disconnection		Construction Activity Operator	

¹ In accordance with Arlington County's Chesapeake Bay Total Maximum Daily Load (TMDL) Action Plan, approved by the Virginia Department of Environmental Quality (DEQ) on September 1, 2015, linear development projects conducted by the County are administered and tracked as follows consistent with 9VAC25-870-69.A.4, 9VAC25-870-76, and 9VAC25-870-92:

- Pollutant load changes will be computed as described in Section 3.A of the Action Plan.
 Petrofit opportunities will be evaluated for each project, using the screening and selection criteria applications.
- Retrofit opportunities will be evaluated for each project, using the screening and selection criteria applied and described in the adopted Stormwater Master Plan.
- Retrofit projects that meet the screening criteria and are determined by Arlington to be feasible and cost-effective will be implemented with specific linear development projects. Pollutant load reductions from retrofit projects will be
- omputed as described in Section 5 of the Action Plan.
 In cases where retrofit projects are not feasible and cost-effective for a particular linear project, any POC load increases that might occur for that project will be addressed by larger overall POC load reductions in place or added through TMDL action plan implementation.


In the above manner Arlington, as the MS4 operator and the construction site operator for its linear development projects, implements linear projects and retrofit projects in a manner that achieves the most TMDL POC reduction for the least cost, while fully accounting for load changes that occur with linear development project activity consistent with the DEQ Chesapeake Bay TMDL Special Condition Guidance.

Arlington County SWPPP 12/2016

ARLINGTON VIRGINIA

DEPARTMENT OF
ENVIRONMENTAL SERVICES
FACILITIES & ENGINEERING DIVISION
ENGINEERING BUREAU
2100 CLARENDON BOULEVARD, SUITE 813
ARLINGTON, VA 22201
PHONE: 703.228.3629
FAX: 703.228.3606

COPYRIGHT © 2016 ARLINGTON COUNTY VIRGINIA - ALL RIGHTS RESERVED



APPROVALS

DATE

3/29/21

QUALITY CONTROL ENGINEER

CONSTRUCTION MANAGEMENT SUPERVISOR

03.04.2021

WATER, SEWER, STREETS BUREAU CHIEF

Dennis W. Leach 03/17/21

TRANSPORTATION DIRECTOR

Diana Isaza PROJECT MANAGER

REVISIONS DA

AY EXTENSION TO TAGON CITY
N PREVENTION PLA
DR & 12TH ST S

TRANSITWAY E
PENTAGO
SW POLLUTION P

DESIGNED: PB
DRAWN: NS
CHECKED: TL
MISS UTILITY TRANSMITTAL #: N/A

FILENAME:
MA13-224-E_AND_S_PLAN.DWG
PATH:\\DES-CAD-S2\ENGINEERING_DATA\DATA\MA1

PLOTTED: AUGUST 4 2021 PLOTTED BY:NSHARP

SCALE: N/A

SHEET 15 OF 35

STORMWATER POLLUTION PREVENTION PLAN

Sheet flow to Vegetated Filter (1 or 2)	(See Cover of this SWF
Grass Channel	
Rainwater Harvesting	
Permeable Pavement (1 or 2)	
Infiltration (1 or 2)	
Bio-retention (1 or 2)	
Others [describe]	

Arlington County SWPPP 12/2016

STORMWATER POLLUTION PREVENTION PLAN

Are washout facilities (concrete, paint) available, labeled, and properly maintained?	☐ Yes ☐ No ☐ NA	
Are trash and waste materials properly managed and disposed of?	☐ Yes ☐ No ☐ NA	
Are trash receptacles covered and not leaking?	☐ Yes ☐ No ☐ NA	
Are non-stormwater discharges (i.e. wash water, saw cut slurry) properly managed?	☐ Yes ☐ No ☐ NA	
Are vehicle and equipment fueling, maintenance, and/or staging areas free of spills and leaks?	☐ Yes ☐ No ☐ NA	
Are materials that are potential stormwater contaminants stored properly (covered / have secondary containment)?	☐ Yes ☐ No ☐ NA	
Are portable lavatories level, in good condition, and located away from storm drains?	☐ Yes ☐ No ☐ NA	
Is a spill kit accessible onsite?	☐ Yes ☐ No ☐ NA	

Are there any unauthorized discharges at the time of this inspection?

Yes

No

If yes, describe:

Non - Compliance Issues

Describe any incidents of non-compliance not described above (use another page if necessary)

Certification

"I certify under penalty of law that I have read and understand this document and that this document and all attachments were prepared in accordance with a system designed to assure that qualified personnel properly gathered and evaluated the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations."

perator or Assigned Q	ualified Personnel Nar	me:	
ignature:		-	
ata.			

Arlington County SWPPP 12/2016

STORMWATER POLLUTION PREVENTION PLAN

7.0 Spill Prevention & Response

Most spills can be cleaned up using a spill kit. Absorbent/oil dry, sealable containers, plastic bags, and shovels/brooms are suggested minimum spill response items that should be available at the project site.

Protect all people

2nd Priority: Protect equipment and property Protect the environment

- 1. Check for hazards (flammable material, noxious fumes, cause of spill) if flammable liquid, turn off engines and nearby electrical equipment. If serious hazards are present leave the area and call 911. LARGE SPILLS
- ARE LIKELY TO PRESENT A HAZARD.
- 2. Ensure the spill area is safe to enter and that it does not pose an immediate threat to health or safety of any
- Stop the spill source. 4. Call co-workers and supervisor for assistance and to make them aware of the spill and potential dangers.
- 5. If possible, stop spill from spreading and/or entering storm drains (use absorbent or other materials as 6. If spilled material has entered a storm drain; contact Arlington County Fire Department and project manager.
- 7. Clean up spilled material according to manufacturer specifications, for liquid spills use absorbent materials and do not flush area with water.
- 8. Properly dispose of cleanup materials and used absorbent material according to manufacturer specifications.

703-558-2222

703-228-6555

703-750-1400

804-674-2400

Emergency Contacts:

Local Contacts Arlington County Fire & Police

24 Hour Reporting Service

DES Water, Sewer, Streets 24-Hour Emergency Washington Gas Emergency

Nights, Holidays & Weekends

Spill kit on site: Yes No

VA Dept. of Emergency Management

Location(s) of spill kit: _

Arlington County SWPPP 12/2016

STORMWATER POLLUTION PREVENTION PLAN

9.0 Grading & Stabilization Activities Log

Date Grading Activity Initiated	Description of the Grading Activity (including location)	Date Grading Activity Ceased	Date Stabilization Measures Initiated	Description of the Stabilization Measure (including location)
ii				

10.0 SWPPP Modification & Update Log

Modification Date	Description of the Modification / Update	Modification Prepared By (name & title)

Arlington County SWPPP 12/2016

STORMWATER POLLUTION PREVENTION PLAN

8.0 Self Inspection Report & Corrective Action Log (make additional copies as necessary)

Name of Inspector:		
Telephone Number:		

Inspection Schedule

Discharges to impaired waters, surface waters within a TMDL watershed, or exceptional waters:

Once every 4 business days

Inspection Date: _____

Describe phase of construction: ____

Is a copy of the SWPPP available on site?

Yes

No Is the SWPPP complete?

Yes

No

Erosion & Sediment Controls/ Pollution Prevention Practices	In Compliance?	Corrective Action Needed & Notes	Date Corrective Action Taken
Are controls in place to prevent sediment from being tracked off site or onto the street?	☐ Yes ☐ No ☐ NA		
Are perimeter controls adequately installed and properly maintained?	☐ Yes ☐ No ☐ NA		
Are storm drains properly protected / approved inlet protection is in place?	☐ Yes ☐ No ☐ NA		
Are all slopes and disturbed areas, including stockpiles, not actively being worked properly stabilized?	☐ Yes ☐ No ☐ NA		
Are dewatering operations working properly?	☐ Yes ☐ No ☐ NA		
Is construction dust properly controlled?	☐ Yes ☐ No ☐ NA		
Are mature trees and/or natural areas properly protected?	☐ Yes ☐ No ☐ NA		

Arlington County SWPPP 12/2016

INSTRUCTIONS for COMPLETING the SINGLE FAMILY RESIDENCE, COMMON PLAN of DEVELOPMENT or SALE STORMWATER POLLUTION PREVENTION PLAN (SWPPP)

A Stormwater Pollution Prevention Plan (SWPPP) must be developed prior to obtaining locality (e.g., City, County, Town) authorization

SWPPP Cover Page
For a construction activity, enter the project/site name and physical address (if available), including city (or town), state and zip code. Enter the latitude and longitude in decimal degrees of the construction activity.

Enter the Construction Activity Operator's company/organization name, the Operator's name and mailing address, including city (or

town), state, and zip code, telephone number, email address (if available), and a 24-hour emergency contact.

Enter the SWPPP preparation date.

The Construction Activity Operator identified on the cover page of the SWPPP is responsible for certifying the information contained therein. Please sign the certification in INK. Please note that state statues require the SWPPP to be signed as follows: (1) For a corporation: by a responsible corporate officer;

(2) For a partnership or sole proprietorship: by a general partner or the proprietor, respectively; (3) For a municipality, state, federal, or other public agency: by either a principal executive officer or ranking elected official.

Section 1.0 SWPPP Documents Located Onsite & Available for Review Utilize the provided checklist to ensure that the required SWPPP documents are located onsite and are available for review, if

Section 2.0 Authorized Non-Stormwater Discharges

Identify the authorized non-stormwater discharges likely to be present at the project site. If an unlisted authorized non-stormwater discharge is likely to be present at the project site, provide it here.

Section 3.0 Pollution Prevention Awareness Provide employees with a "walk through" of the project site and identify areas of possible pollution, erosion and sediment controls,

and pollution prevention practices which are applicable to their assigned job duties. Conduct refresher meetings and perform additional "walk throughs" on an as needed basis. Section 4.0 Erosion & Sediment Controls
Identify the erosion and sediment controls to be implemented at the project site. For each erosion and sediment control, enter the

estimated installation date and estimated removal date. If an unlisted erosion and sediment control will be implemented at the project site, provide the applicable information here.

Section 5.0 Potential Sources of Pollution & Pollution Prevention Practices Identify the pollutant-generating activities likely to be present at the project site; implement and maintain the corresponding pollution

prevention practices. If an unlisted pollutant-generating activity is likely to be present at the project site, describe it, identify the associated pollutant(s), and provide the corresponding pollution prevention practice(s) to be implemented and maintained. Section 6.0 Stormwater Management Controls

Identify the stormwater management controls to be implemented at the project site, if applicable. For each stormwater management control, enter the estimated installation date. If an unlisted stormwater management control will be implemented at the project site, provide the applicable information here.

Section 7.0 Spill Prevention & Response

Most spills can be cleaned up following manufacturer specifications. The priority should be to protect all people, equipment, property, and the environment. Enter the telephone number of your local fire and police departments.

Section 8.0 Inspections & Corrective Action Log

Enter the qualified inspector's company/organization name, the inspector's name, telephone number, and qualifications. Select the applicable inspection schedule, enter the construction activity inspection date, and enter the date and rainfall amount of the last measurable storm event (if applicable). Identify if the implemented best management practices are in compliance with the SWPPP. Enter corrective actions needed; the party responsible for implementing the corrective actions, and the date corrective actions were taken, if applicable. Make additional copies of the inspection and corrective action log as necessary.

Section 9.0 Grading & Stabilization Activities Log

Enter the date grading activities were initiated, a description of the grading activities including location, the date grading activities ceased, the date stabilization measures were initiated, and a description of the stabilization measures including location.

Section 10.0 SWPPP Modification & Update Log
Enter the SWPPP modification date, description of the SWPPP modification/update, and the name and title of the SWPPP modification preparer, if applicable.

Arlington County SWPPP 12/2016

ARLINGTON VIRGINIA

DEPARTMENT OF **ENVIRONMENTAL SERVICES FACILITIES & ENGINEERING DIVISION** ENGINEERING BUREAU 2100 CLARENDON BOULEVARD, SUITE 813 ARLINGTON, VA 22201 PHONE: 703.228.3629 FAX: 703.228.3606

COPYRIGHT © 2016 ARLINGTON COUNTY VIRGINIA - ALL RIGHTS RESERVED



APPROVALS Kamal Taktak

CONSTRUCTION MANAGEMENT SUPERVISOR WATER, SEWER, STREETS BUREAU CHIEF Dennis M. Leach 03/17/21 TRANSPORTATION DIRECTOR

Diana Isaza PROJECT MANAGER

REVISIONS

0 Δ

ON NOI: 7 \simeq

SITWAY OLLU **TRANS**


DESIGNED: PB DRAWN: NS CHECKED: TL MISS UTILITY TRANSMITTAL #: N/A


FILENAME: MA13-224-E_AND_S_PLAN.DWG PATH:\\DES-CAD-S2\ENGINEERING_DATA\DATA\MA1


PLOTTED: AUGUST 4 2021 PLOTTED BY:NSHARP


SCALE: N/A


16 OF 35
























NOTES VIEW



GEOMETRIC VIEW

- 1. FLAG STATION SIGN AND LCD MONITOR DETAILS WILL NOT BE INCLUDED ON THESE PLANS. ARLINGTON COUNTY SHALL PROVIDE SIGNED AND SEALED BUILDING PLANS TO THE CONTRACTOR FOR CONSTRUCTION.
- 2. CONTRACTOR TO CONFIRM LOCATION OF ALL STATION FURNISHINGS WITH ARLINGTON COUNTY PRIOR TO INSTALLATION.

CRYSTAL DR & 15TH ST STATION LAYOUT

1485 CRTSTAL DRIVE

1"=5'

ARLINGTON VIRGINIA DEPARTMENT OF **ENVIRONMENTAL SERVICES** FACILITIES & ENGINEERING DIVISION ENGINEERING BUREAU 2100 CLARENDON BOULEVARD, SUITE 813 ARLINGTON, VA 22201 PHONE: 703.228.3629 FAX: 703.228.3606 COPYRIGHT © 2016 ARLINGTON COUNTY VIRGINIA - ALL RIGHTS RESERVED **APPROVALS** QUALITY CONTROL ENGINEER Kamal Taktak CONSTRUCTION MANAGEMENT SUPERVISOR WATER, SEWER, STREETS BUREAU CHIEF Dennis M. Leach 03/17/21 TRANSPORTATION DIRECTOR Diana Isaza PROJECT MANAGER **REVISIONS** TRANSITWAY EXTENSION PENTAGON CITY DESIGNED: PB DRAWN: NS CHECKED: TL MISS UTILITY TRANSMITTAL #: N/A FILENAME: MA13-204-STATION_DETAIL.DWG PATH:Q:\DATA\MA13\CAD\ACTIVE PLOTTED: AUGUST 4 2021 PLOTTED BY:NSHARP SCALE:


AS SHOWN

21A OF 35


SHEET

DATE

COPYRIGHT © 2016 ARLINGTON COUNTY VIRGINIA - ALL RIGHTS RESERVED



NOTES VIEW



GEOMETRIC VIEW

- 1. FLAG STATION SIGN AND LCD MONITOR DETAILS WILL NOT BE INCLUDED ON THESE PLANS. ARLINGTON COUNTY SHALL PROVIDE SIGNED AND SEALED BUILDING PLANS TO THE CONTRACTOR FOR CONSTRUCTION.
- 2. CONTRACTOR TO CONFIRM LOCATION OF ALL STATION FURNISHINGS WITH ARLINGTON COUNTY PRIOR TO INSTALLATION.

12TH ST & LONG BRIDGE DR STATION LAYOUT

215 12TH ST S

1"=5'

ARLINGTON VIRGINIA DEPARTMENT OF **ENVIRONMENTAL SERVICES FACILITIES & ENGINEERING DIVISION** ENGINEERING BUREAU 2100 CLARENDON BOULEVARD, SUITE 813 ARLINGTON, VA 22201 PHONE: 703.228.3629 FAX: 703.228.3606 COPYRIGHT © 2016 ARLINGTON COUNTY VIRGINIA - ALL RIGHTS RESERVED APPROVALS QUALITY CONTROL ENGINEER Kamal Taktak CONSTRUCTION MANAGEMENT SUPERVISOR WATER, SEWER, STREETS BUREAU CHIEF Dennis M. Leach 03/17/21 TRANSPORTATION DIRECTOR Diana Isaza PROJECT MANAGER **REVISIONS** TRANSITWAY EXTENSION PENTAGON CITY DESIGNED: PB DRAWN: NS CHECKED: TL MISS UTILITY TRANSMITTAL #: N/A FILENAME: PLOTTED: AUGUST 4 2021

DATE

MA13-204-STATION_DETAIL.DWG PATH:Q:\DATA\MA13\CAD\ACTIVE


CRYSTAL


PLOTTED BY:NSHARP


SCALE:


AS SHOWN


SHEET 21B OF 35











LANDSCAPE REQUIREMENTS:

- BEFORE ANY GRADING, DEMOLITION, OR OTHER DISTURBANCE, TREE PROTECTION NEEDS TO BE INSTALLED PER PLAN, AND INSPECTED BY AN
 ARLINGTON COUNTY PARKS AND RECREATION URBAN FORESTER. EROSION AND SEDIMENT CONTROLS ARE INSPECTED BY THE DEPARTMENT OF
 ENVIRONMENTAL SERVICES.
- 2. PLANTS SHALL BE FURNISHED AND INSTALLED AS INDICATED, INCLUDING ALL PLANTS, MATERIALS, AND EQUIPMENT.
- 3. PLANTS SHALL BE TYPICAL OF THEIR SPECIES AND VARIETY; HAVE NORMAL GROWTH HABITS, WELL-DEVELOPED DENSELY FOLIATED BRANCHES, AND VIGOROUS ROOT SYSTEMS; AND BE FREE FROM DEFECTS AND INJURIES.
- 4. PLANTS SHALL BE PLANTED ON THE DAY OF DELIVERY IF/WHEN PRACTICAL. IN THE EVENT THAT THIS IS NOT POSSIBLE, THE CONTRACTOR SHALL PROTECT STOCK NOT PLANTED. PLANTS SHALL NOT REMAIN UNPLANTED FOR LONGER THAN A THREE-DAY PERIOD AFTER DELIVERY. ANY PLANTS NOT INSTALLED DURING THIS PERIOD SHALL BE REJECTED, UNLESS OWNER AND CONTRACTOR PROVIDE OTHERWISE BY WRITTEN AGREEMENT. ALL PLANTS KEPT ON SITE FOR ANY PERIOD OF TIME SHOULD BE WATERED AND CARED FOR USING ANSI A300 STANDARDS.
- 5. PLANTS SHALL NOT BE BOUND WITH WIRE OR ROPE AT ANY TIME SO AS TO DAMAGE THE BARK OR BREAK BRANCHES. PLANTS SHALL BE HANDLED FROM THE BOTTOM OF THE ROOT BALL ONLY.
- 6. PLANTING OPERATIONS SHALL BE PERFORMED DURING PERIODS WITHIN THE PLANTING SEASON WHEN WEATHER AND SOIL CONDITIONS ARE SUITABLE AND IN ACCORDANCE WITH ACCEPTED LOCAL PRACTICE. PLANTS SHALL NOT BE INSTALLED IN TOP SOIL THAT IS IN MUDDY OR FROZEN CONDITION. LAWNS, TREES AND SHRUBS SHALL BE INSTALLED BETWEEN 03/15 AND 06/15 OR BETWEEN 09/15 AND 12/01. IF A PROJECT COMPLETION IS OUTSIDE OF THIS PLANTING PERIOD, CONTACT THE ARLINGTON COUNTY URBAN FORESTER TO OBTAIN A DEFERRAL OR APPROVAL FOR PLANTING OUT OF SEASON.
- 7. NO PLANT, EXCEPT GROUNDCOVERS, SHALL BE PLANTED WITHIN TWO FEET OF A SIDEWALK.
- 8. TREES AND SHRUBS SHALL BE PLANTED IN HOLES TWO TO THREE TIMES AS WIDE AND TO THE DEPTH OF THE ROOT BALL.
- 9. PLANTS SHALL BE PLANTED IN IN SITU SOIL THAT IS THOROUGHLY WATERED.
- 10. SET ALL PLANTS PLUMB AND STRAIGHT SET AT SUCH LEVEL THAT NORMAL OR NATURAL RELATIONSHIP BETWEEN THE PLANT AND THE GROUND SURFACE WILL BE ESTABLISHED. LOCATE THE PLANT IN THE CENTER OF THE PIT.
- 11. INJURED ROOTS SHALL BE PRUNED TO CLEAN ENDS BEFORE PLANTING WITH CLEAN, SHARP TOOLS. THE LEADER OF TREES SHALL NOT BE CUT BACK.
- 12. PRESERVED AND PLANTED TREES MUST BE INSPECTED AND APPROVED BY A DEPARTMENT OF PARKS AND RECREATION URBAN FORESTER.
- 13. ALL DISTURBED AREAS SHALL BE TREATED WITH 4" TOP SOIL OR COMPOST AND SEEDED IN ACCORDANCE WTH PERMANENT STABILIZATION METHODS INDICATED ON SOIL EROSION AND SEDIMENT CONTROL SHEET AND/OR LANDSCAPE PLAN.

NOTES

I. A PERMIT IS REQUIRED WHEN TREES ARE PLANTED IN PUBLIC RIGHT-OF-WAY OR IN A PUBLIC EASEMENT. THE DEPARTMENT OF ENVIRONMENTAL SERVICES SHALL ISSUE THE PERMIT ACCORDING TO THE PROVISIONS OF THE CURRENT ARLINGTON COUNTY ADMINISTRATIVE REGULATION 4.3.

TREE SPECIES SHALL BE SELECTED FROM THE "ARLINGTON COUNTY STREET TREE LIST" OR PER SECTOR PLAN REQUIREMENTS.

3. TREES SHALL BE NURSERY GROWN SPECIMENS THAT MEET THE LATEST EDITION OF THE AMERICAN STANDARDS FOR NURSERY STOCK (ANSI Z60). BALLED AND BURLAPPED TREES SHALL BE SECURELY HELD IN PLACE BY UNTREATED BURLAP AND STOUT ROPE (NYLON ROPE IS NOT ACCEPTABLE). LOOSE, BROKEN OR MANUFACTURED BALLS ARE UNACCEPTABLE.

4. CALL MISS UTILITY AT (800) 552-7001 FOR UTILITY LOCATIONS PRIOR TO EXCAVATION.

 AT TIME OF PLANTING PRUNE ONLY CROSSING LIMBS, BROKEN OR DEAD BRANCHES, AND ANY BRANCHES THAT POSE A HAZARD TO PEDESTRIANS.
 DO NOT PRUNE INTO OLD WOOD ON EVERGREENS.

TREE PIT AND TREE STRIP PLANTING AREA DIMENSIONS:
 (A) 5' X I2' OR LARGER IS STANDARD
 (B) 4' X I5' MINIMUM IS ALLOWED PER SITE CONDITIONS AND COUNTY URBAN FORESTER'S APPROVAL.

7. SPACE TREES 25'-30' APART OR PER SECTOR PLAN REQUIREMENTS OR SITE CONDITIONS.

8. SITE CHARACTERISTICS, SUCH AS OVERHEAD POWER LINES, EXISTING VEGETATION, AND INFRASTRUCTURE ITEMS SUCH AS CURBS, SIDEWALKS AND UTILITIES SHALL BE CONSIDERED. TREES THAT GROW TALLER THAN 25 FEET SHOULD NOT BE PLANTED DIRECTLY UNDER POWER LINES. WHEN POSSIBLE THE TREE LEADER SHALL BE OFFSET FROM POWER LINES.

9. BACKFILL SOIL MIXTURE SHALL BE 3/4 EXISTING SOIL CLEANED OF DEBRIS (GRAVEL, ROCKS, STICKS, TRASH, ETC.) AND MIXED WITH I/4 ORGANIC MATERIAL (COMPOSTED BARK, LEAF MOLD, OR OTHER PLANT DEBRIS PROCESSED TO A POINT OF DECAY AND APPROVED BY THE COUNTY URBAN FORESTER. PEAT MOSS MAY NOT BE USED.

IO. IF THE QUANTITY OF ACCEPTABLE EXISTING SOIL IS INSUFFICIENT FOR THE PLANTING REQUIREMENTS, THE CONTRACTOR MAY USE TOPSOIL. SOIL TEST REPORT RESULTS FOR THE TOPSOIL WILL BE MADE AVAILABLE TO THE COUNTY URBAN FORESTER UPON REQUEST. CONTRACTOR SHALL SUBMIT TOPSOIL FOR APPROVAL TO COUNTY URBAN FORESTER THAT MEETS THE

TOPSOIL FOR APPROVAL TO COUNTY URBAN FORESTER THAT MEETS THE FOLLOWING SPECIFICATIONS:

(A.) TOPSOIL CONSISTS OF A SANDY LOAM WITH UNIFORM COMPOSITION

AND IS FREE OF STONES, LUMPS, PLANTS, ROOTS, AND OTHER DEBRIS

(B.) TOPSOIL HAS A PH RANGE OF 5.5 TO 6.5 AND A MINIMUM CONTENT OF 1.0% ORGANIC MATTER (C.) TOPSOIL DOES NOT CONTAIN TOXIC SUBSTANCES HARMFUL TO

PLANT GROWTH. SOLUBLE SALT LEVEL SHALL NOT EXCEED 3

II. TREES PLANTED WITHOUT THE TRUNK FLARE VISIBLE WILL BE REJECTED.

OVER 1/2" IN LENGTH.

MILLIOHMS PER CENTIMETER.

12. TREES MAY ONLY BE STAKED IF REQUIRED BY THE COUNTY URBAN FORESTER. REFER TO ARLINGTON COUNTY STANDARD STAKING DETAILS.

I3. MULCH SHALL BE CLEAN, SCREENED, DOUBLE-HAMMERED HARDWOOD BARK MULCH, UNIFORM IN SIZE AND FREE OF STONES, CLODS, NON-ORGANIC DEBRIS AND OTHER FOREIGN MATERIAL.

14. ALL PLANTS SHALL BE WATERED TWICE: ONCE AT INSTALLATION AND AGAIN WITHIN 48-HOURS OF INSTALLATION. EACH WATERING WILL CONSIST OF 20 GALLONS PER TREE.

I5. CONTRACTOR SHALL LEGALLY REMOVE EXCESS SOIL & DEBRIS FROM SITE.



GENERAL NOTES FOR STREET TREE PLANTINGS

FOR TREES PLANTED IN RIGHT-OF-WAY 329300.5 (2016) (02930.5)



ARLINGTON

VIRGINIA

DEPARTMENT OF

ENVIRONMENTAL SERVICES

FACILITIES & ENGINEERING DIVISION

ENGINEERING BUREAU

2100 CLARENDON BOULEVARD, SUITE 813

ARLINGTON, VA 22201

PHONE: 703.228.3629

FAX: 703.228.3606

COPYRIGHT © 2016 ARLINGTON COUNTY

VIRGINIA - ALL RIGHTS RESERVED

TREVŐR M. LANTZY

8/4/2021

CONSTRUCTION MANAGEMENT SUPERVISOR

WATER, SEWER, STREETS BUREAU CHIEF

Dennis M. Leach 03/17/21

APPROVALS

Kamal Taktak

TRANSPORTATION DIRECTOR

Diana Isaza
PROJECT MANAGER

REVISIONS

NOI:

SITWAY PENTA(

TRANS<u>.</u>

DESIGNED: PB DRAWN: NS CHECKED: TL

FILENAME:

SHEET

MISS UTILITY TRANSMITTAL #: N/A

MA13-260-LANDSCAPE_PLAN.DWG

PLOTTED: AUGUST 4 2021


PLOTTED BY:NSHARP

SCALE: N/A

PATH:\\DES-CAD-S2\ENGINEERING_DATA\DATA\MA1

24 OF 35

7



MA13 - Crystal City Transitway Extension TREE INVENTORY AND REPLACEMENT SCHEDULE

Ex Tree #	To Be Removed	DBH	Condi- tion	Species	Common name	Species Rating	Replace- ment value	Replace- ments	Comments
01		6"	70	Zelkova serrata	Japanese Zelkova	75			Protect
02		6"	70	Zelkova serrata	Japanese Zelkova	75			Protect
03	Х	8"	70	Zelkova serrata	Japanese Zelkova	75	1	1	
04	Х	8"	70	Zelkova serrata	Japanese Zelkova	75	1	1	
05	Х	8"	70	Zelkova serrata	Japanese Zelkova	75	1	1	
06		10"	60	Zelkova serrata	Japanese Zelkova	75			Protect
07		7"	30	Zelkova serrata	Japanese Zelkova	75			Protect
08	Х	5"	80	Zelkova serrata	Japanese Zelkova	75	1	1	
09	Х	7"	40	Zelkova serrata	Japanese Zelkova	75	1	1	
10	Х	12"	70	Zelkova serrata	Japanese Zelkova	75	6.3	2	
							Total:	7*	

*TREES REPLACEMENT TO BE INCLUDED IN CC08 CLARK-BELL EXTENSION TO 15TH STREET SOUTH PROJECT

MA13 - Crystal City Transitway Extension PLANT SCHEDULE

PLANT SCHEDULE


QTY KEY BOTANICAL NAME COMMON NAME SIZE SPACING REMARKS


SHRUBS


60 JY SHENANDOAH SWITCHGRASS PANICUM VIRGATUM 12"-18" Tall 3.0' O.C. CONTAINER

REVISED ON 11/08/2016

COPYRIGHT © 2016 ARLINGTON COUNTY VIRGINIA - ALL RIGHTS RESERVED










DATE

12TH

DR







APPROVALS QUALITY CONTROL ENGINEER

Ramal Taktak

3/29/21

3/29/21 CONSTRUCTION MANAGEMENT SUPERVISOR WATER, SEWER, STREETS BUREAU CHIEF Dennis M. Leach 03/17/21 TRANSPORTATION DIRECTOR Diana Isaza PROJECT MANAGER **REVISIONS** TRANSITWAY EXTENSION PENTAGON CITY CHECKED: TL MISS UTILITY TRANSMITTAL #: N/A MA13-234-CROSS_SECTIONS.DWG PATH:Q:\DATA\MA13\CAD\ACTIVE PLOTTED: AUGUST 4 2021 PLOTTED BY:NSHARP SCALE:

.2TH

VERTICAL: 1" = 5'

29A OF 35


SHEET


ARLINGTON VIRGINIA


DEPARTMENT OF **ENVIRONMENTAL SERVICES** FACILITIES & ENGINEERING DIVISION ENGINEERING BUREAU 2100 CLARENDON BOULEVARD, SUITE 813 ARLINGTON, VA 22201 PHONE: 703.228.3629 FAX: 703.228.3606 COPYRIGHT © 2016 ARLINGTON COUNTY VIRGINIA - ALL RIGHTS RESERVED


12TH ST S & CRYSTAL DRIVE TRANSITION

NOTE: PAVEMENT AND SIDEWALK SECTIONS ARE SHOWN ON THIS SHEET FOR INFORMATIONAL PURPOSES ONLY. SEE SHEET 04 FOR PAVEMENT AND SIDEWALK TYPICAL SECTIONS. SEE PLAN AND PROFILE SHEETS FOR EXTENTS OF PROPOSED PAVEMENT AND SIDEWALK.










- THE CONTRACTOR SHALL SUBMIT A DETAILED SCHEDULE WHICH INDICATES START AND FINISH DATES FOR EACH SEGMENT OF THE WORK. THE SCHEDULE SHALL INDICATE THE DURATION OF ALL LANE OR SHOULDER CLOSURES. THE CONTRACTOR SHALL NOTIFY THE PROJECT OFFICER A MINIMUM OF 3 BUSINESS DAYS IN ADVANCE OF PROCEEDING TO THE NEXT WORK SEGMENT.
- THE CONTRACTOR SHALL NOTIFY THE PROJECT OFFICER OF PARKING RESTRICTION NEEDS A MINIMUM OF 3 BUSINESS DAYS PRIOR TO COMMENCEMENT OF WORK FOR EACH SEGMENT. COUNTY PROJECT OFFICER SHALL RESTRICT PARKING BY CONTACTING DES - PERMITTING SECTION, 703-228-4798.
- DURING CONSTRUCTION, THE CONTRACTOR SHALL EITHER MAINTAIN APPROPRIATE SIGHT DISTANCE TO ALL TRAFFIC SIGNS OR PROVIDE FOR TEMPORARY SIGNAGE OR FLAGGERS TO GUIDE TRAFFIC THROUGH WORK ZONES.
- THE CONTRACTOR SHALL MINIMIZE THE DURATION OF ANY BLOCKAGE TO PRIVATE ENTRANCES AND DRIVEWAYS. THE CONTRACTOR SHALL SUBMIT A SCHEDULE OF DRIVEWAY CLOSURE FOR APPROVAL BY THE PROJECT OFFICER. THE PROJECT OFFICER SHALL BE NOTIFIED A MINIMUM OF 3 BUSINESS DAYS IN ADVANCE OF SUCH ACTIVITIES. THE CONTRACTOR SHALL NOTIFY THE PROPERTY OWNER AT LEAST 24 HOURS IN ADVANCE OF THE START OF ANY WORK THAT WIL REQUIRE TEMPORARY CLOSURE OF ACCESS TO THE PROPERTY. THE CONTRACTOR SHALL MAKE ALL PRIVATE ENTRANCES AND DRIVEWAYS ACCESSIBLE AT THE CONCLUSION OF EACH WORKDAY.
- ANY EXCAVATIONS WHICH ARE SPECIFICALLY APPROVED BY TH PROJECT OFFICER TO REMAIN OPEN PAST NORMAL WORKING HOURS SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR AND SHALL BE PROTECTED IN ACCORDANCE WITH THE VIRGINIA WORK AREA PROTECTION MANUAL AND AS APPROVED BY THE PROJECT OFFICER.
- PEDESTRIAN TRAFFIC SHALL BE MAINTAINED AT ALL TIMES, INCLUDING ACCESS TO BUS STOP SHELTERS, UNLESS OTHERWISE APPROVED IN THE PLANS.
- PEDESTRIAN TRAFFIC SHALL BE SEPARATED FROM WORK ZONES WITH APPROPRIATE MEASURES IN ACCORDANCE WITH MUTCD. ADEQUATE PROVISIONS FOR PERSONS WITH DISABILITIES
- SHALL BE PROVIDED AT ALL TIMES PER ADA REQUIREMENTS. WHEN NECESSARY, PEDESTRIANS SHALL BE APPROPRIATELY DIRECTED WITH ADVANCED WARNING SIGNS PLACED AT INTERSECTIONS, TO CROSS TO THE OPPOSITE SIDE OF THE ROADWAY IN ORDER TO PREVENT CONFLICT WITH MIDBLOCK
- PEDESTRIANS SHALL NOT BE LED INTO CONFLICT WITH WORK SITE EQUIPMENT, OPERATIONS, AND/OR VEHICLES MOVING THROUGH OR AROUND THE WORK SITE.
- ALL EXISTING FIRE HYDRANTS AND FIRE DEPARTMENT CONNECTIONS SHALL BE MAINTAINED UNOBSTRUCTED AND ACCESSIBLE AT ALL TIMES IN ACCORDANCE WITH SECTIONS 508.5.4 AND 508.5.5 OF THE ARLINGTON COUNTY FIRE PREVENTION CODE.
- ACCESS TO BUILDINGS FOR FIREFIGHTING SHALL BE MAINTAINED AT ALL TIMES. EXISTING FIRE APPARATUS ACCESS ROADS (FIRE LANES) SHALL BE KEPT CLEAR OF OBSTRUCTIONS IN ACCORDANCE WITH SECTION 503.4 OF THE ARLINGTON COUNTY FIRE PREVENTION CODE, ACCESS TO CONSTRUCTION SITES SHALL BE PROVIDED AND MAINTAINED IN ACCORDANCE WITH SECTION 1410 OF THE ARLINGTON COUNTY FIRE PREVENTION CODE.
- IN THE EVENT THAT EXISTING FIRE DEPARTMENT CONNECTIONS OR FIRE APPARATUS ACCESS ROADS (FIRE LANES) MUST BE OBSTRUCTED TO FACILITATE CONSTRUCTION ACTIVITIES, CONTACT THE ARLINGTON COUNTY FIRED DEPARTMENT FIRE PREVENTION OFFICE AT 703-228-4644 TO COORDINATE REVIEW AND APPROVAL OF TEMPORARY FIRE DEPARTMENT CONNECTIONS AND/OR FIRE APPARATUS ACCESS ROADS PRIOR TO CREATING THE OBSTRUCTION.
- THE CONTRACTOR SHALL NOTIFY ARI INGTON COUNTY TRANSIT BUREAU, 703-228-3049, A MINIMUM OF 4 WEEKS PRIOR TO COMMENCEMENT OF WORK, IF TRANSIT IS AFFECTED.
- AT SIGNALIZED INTERSECTIONS, THE CONTRACTOR SHALL BE RESPONSIBLE FOR MAINTAINING VEHICLE DETECTION AT ALL TIMES DURING THE PROJECT. TRAFFIC SENSORS SHALL BE RESTORED TO THEIR PRE-CONSTRUCTION STATE PRIOR TO THE
- COMPLETION OF THIS PROJECT. IN ARLINGTON COUNTY RIGHT-OF-WAY, WORK HOURS ARE RESTRICTED TO 9 AM TO 4 PM (MON-FRI).
- IN VDOT RIGHT-OF-WAY, WORK HOURS ARE RESTRICTED TO 9:30 AM TO 3 PM (MON-THUR.) AND 9:30 AM TO 2 PM (FRI.).
- ALL LANES SHALL BE FULLY OPEN TO TRAFFIC OUTSIDE THE ABOVE HOURS UNLESS SPECIFIED OTHERWISE IN THE MAINTENANCE OF TRAFFIC PLANS.
- CONTRACTOR SHALL COVER ANY EXISTING SIGNS WHICH ARE NOT APPLICABLE OR ARE IN CONFLICT WITH THIS MOT PLAN.
- CONTRACTOR SHALL ERADICATE AND RE-STRIPE AS NECESSARY ANY EXISTING PAVEMENT MARKINGS THAT ARE IN CONFLICT WITH OR DO NOT ALIGN WITH THE TEMPORARY PAVEMENT MARKINGS OR NEW TRAFFIC PATTERNS.
- CONTRACTOR SHALL ERADICATE ALL TEMPORARY PAVEMENT MARKING, INCLUDING TEMPORARY MARKED CROSSWALKS ONCE THE WORK AREA(S) ASSOCIATED WITH THE MARKINGS HAS BEEN COMPLETED.
- TEMPORARY SIGNS AND BARRIERS ARE NOT TO BE PLACED WHERE THEY WOULD OBSTRUCT PEDESTRIAN PASSAGE ON SIDEWALKS, UNLESS SUCH SIGNAGE OR BARRIER IS INTENDED TO CLOSE THE SIDEWALK SEGMENT.
- SIDEWALK AND BIKE LANE CLOSURES ARE TO BE COORDINATED WITH THE CONSTRUCTION MANAGER AND TE&O PRIOR TO IMPLEMENTATION.
- ACCESS TO LONG BRIDGE PARK ESPLANADE IS TO BE MAINTAINED AT ALL TIMES.

ALL AND ANY TEMPORARY STRIPING DUE TO MAINTENANCE OF TRAFFIC OPERATIONS PART OF THIS PROJECT SHALL BE INCLUDED AS PART OF THE PROJECT COST.

SEE SHEET 30-31A FOR CONSTRUCTION ZONES.

REVISED ON 11/08/2016

September 2019 Lane Closure Operation with Temporary Traffic Barrier ¹ (Figure TTC-20.2) 6" LINE BEGINNING AT ANGLE BREAK OF BARRIER



Typical Traffic Control

1. See Table 6H-5, page 6H-6, for recommended spacing of advance warning signs.

opportunity for disabled vehicles to pull off the roadway (see Figure TTC-6).

Location

Spacing

12. Eradication of existing pavement markings should be as shown in Figure TTC-55.

99 paragraph 12 and 13 for installation guidance and spacing.²

shoulder closure should be provided in feet or miles, as appropriate.

7. Group 2 channelizing device spacing shall be at the following:

20' 40' Travelway

Speed Limit

0 -35 | 36 +

10. End treatment of a barrier in order of preference:

Appendix A for clear zone values).

shoulder and lane² on a long-term project.

be used. Refer to L&D special design drawings.

Lane Closure Operation with Temporary Traffic Barrier

(Figure TTC-20.2)

2. SHOULDER CLOSED (W21-5a) signs should be used on Limited-Access Highways where there is no

4. If drivers cannot see a pull-off area beyond the closed shoulder, information regarding the length of the

5. An emergency pull-off area should be provided per Section 6G.18 and Temporary Traffic Control Figure

6. On divided highways having a median wider than 8', right and left sign assemblies shall be required.

Group 2 Channelizing Device Spacing

Construction access spacing may be increased to this distance, but shall not exceed one access per ¼ mile.

9. See Table 6H-6 for barrier transition flare rate.² When the barrier transition flare¹ is on a

a. Where guardrail exists, attach to barrier with appropriate fixed object attachment.

b. Where cut slope exists, bury barrier into cut slope and provide for drainage as needed.

horizontal alignment, the total offset shall be prorated around the curve in lieu of a straight-line

c. Extend end of barrier until it is beyond the established clear zone (see Figure 2 on Page A-4 of

d. When barrier end is inside the established clear zone, attenuator service Type I or Type II shall

and spaced on 40' centers along the transition or taper sections and spaced on 80' centers along the

parallel or tangent sections. Reflectorized surface shall be fluorescent orange prismatic lens

sheeting. The light at the beginning of the barrier run and at the breakpoint where the barrier becomes parallel to the roadway shall be a Type B flashing light. Barrier delinators shall be spaced

on 20' centers along the transition or taper sections and spaced on 80' centers and centered2 in-

between the barrier panels along the parallel or tangent sections² approximately 24 inches up from

13. The barrier shown in this typical application is an example of one method that may be used to close a

14. Long-term transvere rumble strips may be installed to enhance the work zone see Chapter 6F, Section 6F-

11. Barrier panels 8 inches in width and 12 inches in height shall be placed on top of the concrete barrier

Speed Limit

When closing a lane, a PCMS should be used in advance of the first warning sign if all of the left side

Page 6H-49

September 2019

Speed Limit

0 -35 | 36 +

1: Revision 1 – 4/1/2015 2: Revision 2 – 7/1/2018

signs cannot be installed.²

8. For taper lengths, see TTC-19.2

the roadway surface.

1: Revision 1 - 4/1/2015

2: Revision 2 - 7/1/2018

TTC-8.

Page 6H-48

Guidance:

(Figure TTC-35.1) CBO22 HEBE SEE NOTES RIGHT KEEb R4-V7L KEEP LEFT SIDEWALK CLOSED CROSS HERE SEE NOTES SIDEWALK DETOUR SIDEWALK DIVERSION TYPE 3 BARRICADE

Sidewalk Closure and Bypass Sidewalk Operation

Page 6H-79

September 2019

Typical Traffic Control Sidewalk Closure and Bypass Sidewalk Operation (Figure TTC-35.1) **NOTES**

Standard:

Page 6H-78

September 2019

1. When crosswalks or other pedestrian facilities are closed or relocated, temporary facilities shall be detectable and shall include accessibility features consistent with the features present in the existing pedestrian facility.

Guidance:

- 2. Where high speeds are anticipated, a temporary traffic barrier and, if necessary, a crash cushion should be used to separate the temporary sidewalks from vehicular traffic.
- 3. Audible information devices should be considered where midblock closings and changed crosswalk areas cause inadequate communication to be provided to pedestrians who have visual disabilities.
- 4. Temporary markings should be considered for operations exceeding three days in duration.
- Option:

2: Revision 2 – 9/1/2019

2: Revision 2 – 9/1/2019

- 5. Only the TTC devices related to pedestrians are shown. Other devices, such as lane closure signing or ROAD NARROWS (W5-1) signs, may be used to control vehicular traffic.
- 6. For nighttime closures, Type A Flashing warning lights may be used on barricades that support signs and
- 7. Signs, such as KEEP RIGHT (R4-V7R) and KEEP LEFT (R4-V7L), may be placed along a temporary sidewalk to guide or direct pedestrians.


Standard:

8. All sidewalk closures shall be closed with Type 3 Barricades. The SIDEWALK CLOSED (R9-9) sign and the SIDEWALK CROSS HERE (R9-11) sign shall be installed above the Type 3 barricade. The KEEP RIGHT sign can cover the top rail of the Type 3 Barricade.²

Page 6H-112

Typical Traffic Control Signing for Project Limits (Figure TTC-53.0) NOTES


- 1. This layout depicts signing requirements for notifying motorist when they are entering and exiting a potential construction/maintenance area with a duration equal to or greater than 60 days.
- 2. The ROAD WORK AHEAD (W20-1) sign or the ROAD WORK NEXT XX MILES (G20-1 (V)) sign shall be placed far enough in advance of the project limits so that other warning signs in a
- series may be adequately placed prior to the condition they are warning about. 3. The ROAD WORK NEXT XX MILES sign shall be used for projects with activity areas greater than 2 miles in length, or when multiple work activities (such as pavement patching, guardrail
- installations, shoulder restoration, etc.) occur along a highway. 4. The distance displayed on the ROAD WORK NEXT XX MILES sign shall be stated to the nearest whole mile from the point of installation to the END ROAD WORK (G20-2 (V)) sign.
- 5. On divided highways having a median wider than 8', right and left sign assemblies shall be required.
- 6. For projects with activity areas 2 miles or less in length, the ROAD WORK AHEAD sign should be the
- 7. Sign spacing should be 1300'-1500' for Limited Access highways. For all other roadways, the sign spacing should be 500'-800' where the posted speed limit is greater than 45 mph, and 350'-500' where the posted speed limit is 45 mph or less.
- 8. All connections within the project limits should be identified with signs indicating to motorist they are entering or exiting a potential construction/maintenance area.



ARLINGTON VIRGINIA

DEPARTMENT OF ENVIRONMENTAL SERVICES **FACILITIES & ENGINEERING DIVISION** ENGINEERING BUREAU 2100 CLARENDON BOULEVARD, SUITE 813 ARLINGTON, VA 22201 PHONE: 703.228.3629 FAX: 703.228.3606

COPYRIGHT © 2016 ARLINGTON COUNTY VIRGINIA - ALL RIGHTS RESERVED



APPROVALS DATE Kamal Taktak CONSTRUCTION MANAGEMENT SUPERVISO

WATER, SEWER, STREETS BUREAU CHIEF Dennis M. Leach 03/17/21 TRANSPORTATION DIRECTOR Diana Isaza

PROJECT MANAGER **REVISIONS**

DATE

0 TRANSITWAY EXTENSION PENTAGON CITY S 2TH **STAL**

DESIGNED: PB DRAWN: NS CHECKED: TL

MISS UTILITY TRANSMITTAL #: N/A FILENAME: MA13-286-MOT.DWG PATH:\\DES-CAD-S2\ENGINEERING_DATA\DATA\MA1

PLOTTED: AUGUST 4 2021 PLOTTED BY:NSHARP


SCALE: N/A

SHEET 32 OF 35

COPYRIGHT © 2016 ARLINGTON COUNTY VIRGINIA - ALL RIGHTS RESERVED

CRYSTAL CITY TRANSITWAY EXTENSION - CRYSTAL DR & 12TH ST S

August 2011



MID-ATLANTIC TEST HOLE FORM

State: VA

Material:

UTILITY INFORMATION

ADDITIONAL UTILITY INFORMATION

SITE CONDITIONS

FIRST & SECOND BENCHMARK INFORMATION

FIELD MARKER INFORMATION

PROFILE VIEW

Top of utility field measurement: 3.00'

Bottom of utility field measurement: None

Elevation: 35.93

1st Benchmark Description:

2nd Benchmark Description:

Project: M-0618-0201-5323 (Crystal City Trans.) Prepared By: Stephen Russell

City: Arlington

Utility Size:

Utility Type: None

1st Elevation: BM Check:

2nd Elevation: Elevation Datum:

Facing: North

REVISED ON 11/08/2016

Type set: Chiseled "X"

Field Condition: Brick Sidewalk


Ground Condition: Sand/ Concrete/ Brown Soil

Offset/Direction: Chiseled "X" is set C/L of the Utility.


Utility Width/Spacing:
PLAN VIEW

Utility Size: Clear Hole
Utility Type: None

General Location: 1501 Crystal Drive



MID-ATLANTIC UTILITY LOCATING, L.L.C.	TES	он та	LE FORM		
			378.0100 WWW.MIDATL	ANTICI OCATING CO	MID-ATLANTIC UTILITY LOCATIN
Project: M-0618-0201-5323 (Crystal City Trans.		By: Stephen R		Date: 2018-02-05	
City: Arlington	State: VA	(Test Hole: TH C5 of	
General Location: 1501 Crystal Dr					
		UTILITY IN	FORMATION		
Utility Size: Clear Hole	Material:			Good Condition: YES	3
Utility Type: None				Utility Owner:	
	Al	DDITIONAL UTI	LITY INFORMATION		
Utility Size:	Material:			See Test Hole No.:	
Utility Type: None				Utility Owner:	
		SITE CO	ONDITIONS		
Field Condition: Brick Sidewalk			Pavement thickness: 4"	Brick/ 4" Concrete	
Ground Condition: Sand/ Concrete/ Brown Soil/	Rock		!!		
	FIRST 8	SECOND BEN	ICHMARK INFORMATION		
1st Elevation:	1st Benc	hmark Descript	ion:		
BM Check:	53				
2nd Elevation:	2nd Bend	chmark Descrip	tion:		
Elevation Datum:					
		FIELD MARKE	R INFORMATION		
Type set: Chiseled "X"			Elevation: 35.72'		
Offset/Direction: Chiseled "X" is set C/L of the U	Itility.				
		PROF	LE VIEW		
		Top of utility f	ield measurement: <u>3.00'</u>	Elevatio	n: <u>32.72'</u>
V		Bottom of util	ity field measurement: No	one Elevatio	n: None
Facing: North Utility Width/Sp	acing:				
PLAN VIEW			11.	COORDINATES	
1 14	P _		Northing:	Easting	Ď.
Stal Drive	, , , , , , , , , , , , , , , , , , ,			COMMENTS/NOTE	<u>s</u>



	ARLI	NG RGI NIA	-	N
(FACILITIES & E ENGINE 2100 CLARENDON ARLING PHONE FAX: TO SEAL TREVE Lic. 1	NGINEERI ERING BU I BOULEVA TON, VA 2 : 703.228. 703.228.36	SERVIONG DIVISION REAU ARD, SUIT 22201 3629 506 GTON CO	ON E 813 UNTY
	APPROVALS	*****	D.	ATE
_	Com	zelf	/ 3/2	9/21
Ō	QUALITY CONTRO Kamal Ta	L ENGINE Etak	ER 3.24	4.21
	CONSTRUCTION M		03.04.	2021
	WATER, SEWER, S Dennis M.	Leach	03/1	
_	TRANSPORTATION Diana Isaza			2/21
-	PROJECT MANAGE REVISION		DA	TE
-				
	TRANSITWAY EXTENSION TO PENTAGON CITY	TEST HOLE PIT LOGS	CRYSTAL DR & 12TH ST S	MA13 - SEGMENT I
]] -]	DESIGNED: PB DRAWN: NS CHECKED: TL MISS UTILITY TRA FILENAME: MA13-229-TESTHO PATH: \\DES-CAD-	DLES.DWG	<u> </u>	ATA\D
	PLOTTED: AUGUST PLOTTED BY:NSH/			
	SCALE: N	/A		
	SHEET	3:	3 OF	35
				-

MOSATE WILL WILL HER WILL HE WILL HER WILL HE WILL HER WILL HE WILL HER WIL

Date: 2018-02-02

Test Hole: TH C4 of

Good Condition: YES

Utility Owner:

See Test Hole No.:

Elevation: 32.93

Elevation: None


COORDINATES


COMMENTS/NOTES


Utility Owner:

Pavement thickness: 4"/ 4" Concrete

NOTE: SEE SHEET 18 FOR TEST HOLE/PIT LOCATIONS








MID-ATLANTIC UTILITY LOCATING, L.L.C. 4501 DALY DRIVE LO	HANTILLY	MID-ATLÂLTIC UT LITY LOCATING MOBILE FIELD DATA REPORTING MOBILE FIELD DATA REPORTING
Project: M-0618-0201-5323 (Crystal City Trans.)		assin Aloumouati Date: 2018-02-12
City: Crystal City	State: V	Test Hole: TP-L5
General Location: 12 St. S. & S. Clark St.	•	,
		TILITY INFORMATION
Utility Size: N/A	Material:	pated Concrete Good Condition: YES
Utility Type: Top of Parking Garage	**	Utility Owner:
	Α	NAL UTILITY INFORMATION
Utility Size:	Material:	See Test Hole No.:
Utility Type: None		Utility Owner:
		SITE CONDITIONS
Field Condition: Brick		Pavement thickness: 3"
Ground Condition: Sand, Gravel		
	FIRST	OND BENCHMARK INFORMATION
1st Elevation: 28.37'	1st Bend	Description: 14034
BM Check: +-0.04'		
2nd Elevation: 27.99°	2nd Ben	Description: 13005
Elevation Datum:		
		MARKER INFORMATION
Type set: Mag Nail		Elevation: 29.05
Offset/Direction: Nail is set C/L of the Test Hole.		
		PROFILE VIEW
		of utility field measurement: 1.22' Elevation: 27.83' om of utility field measurement: None Elevation: None
Facing: West Utility Width/Spa	cing:	100 000 000 000 000 000 000 000 000 000
PLAN VIEW		COORDINATES
	20-20-	Northing: Easting:
Parking 22.45' 12th St. S. 43.05'	\(\frac{1}{2}\)\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\	COMMENTS/NOTES


450LD		ST HOLE F	WWW.MIDATLANTICLOCA	MIDENTE PIECE UTILITY REPORT
Project: M-0618-0201-5323 (Crysta	Christian of the contract of the State of th	By: Yassin Aloumouati	Date: 2018-	
City: Crystal City	State: V	1	Test Hole:	TH L3 of
General Location: 12 St. S. & S. C	ark St.			
		UTILITY INFORMATION	ON	
Utility Size: 32"	Material:	Smooth Pour Concrete	Good Cond	ition: YES
Utility Type: Communication Ductb	ank		Utility Owne	er:
	A	DDITIONAL UTILITY INFO	RMATION	
Utility Size: Notes	Material:		See Test Ho	le No.:
Utility Type: None	*		Utility Own	er:
		SITE CONDITIONS		
Field Condition: Brick		Pavemen	t thickness: 3"	
Ground Condition: Sand, Gravel, E	rown Soil	-		
	FIRST	& SECOND BENCHMARK	INFORMATION	
1st Elevation: 28.37	1st Bend	hmark Description: 14034	ĺ.	
BM Check: +-0.04'	,			
2nd Elevation: 27.99	2nd Ben	chmark Description: 1300	5	
Elevation Datum:	5			
		FIELD MARKER INFORM	IATION	
Type set: Mag Nail		Elevation	a: 28.80'	
Offset/Direction: Nail is set C/L of t	he Utility.	L2		
		PROFILE VIEW		
		Top of utility field measo	urement: <u>0.96'</u>	Elevation: <u>27.84'</u>
		Bottom of utility field me	easurement: 1.29'	Elevation: 27.51'
Facing: Northwest Util	ity Width/Spacing:			
P	LAN VIEW		COOR	DINATES
ľ	. i. A	Northing		Easting:
		Parking a		TS/NOTES arries an elevation of 27.80' Nail is s

UTILITY LOCATING, L.L.C.	TEST HOLE FORM	MODATE PIECUTALLY REPORTING
4501 DALY DRIVE (CH Project: M-0618-0201-5323 (Crystal City Trans.)	Prepared By: Yassin Aloumouati	Date: 2018-02-06
City: Crystal City	State: VA	Test Hole: TH L6 of
General Location: 12 St. S. & S Clark St.	•	-
	UTILITY INFORMATION	
Utility Size: 24"	Material: Rough Pour Concrete	Good Condition: YES
Utility Type: Electric Ductbank	•	Utility Owner:
	ADDITIONAL UTILITY INFORMATION	.
Utility Size:	Material:	See Test Hole No.:
Utility Type: None		Utility Owner:
	SITE CONDITIONS	
Field Condition: Brick	Pavement thickness:	3"
Ground Condition: Gravel, Brown Soil	The second of the first fig. An including all the control of the second	
	FIRST & SECOND BENCHMARK INFORMATIO	on'
1st Elevation: 28.37	1st Benchmark Description: 14034	
BM Check: +-0.04		
2nd Elevation: 27.99'	2nd Benchmark Description: 13005	
and allorations Erico		
Elevation Datum:		
	FIELD MARKER INFORMATION	
Elevation Datum:	FIELD MARKER INFORMATION Elevation: 28.57	
Elevation Datum: Type set: Mag Nail		
Elevation Datum: Type set: Mag Nail	PROFILE VIEW Top of utility field measurement: 3.53	
Elevation Datum: Type set: Mag Nail Offset/Direction: Nail is set C/L of the Utility.	PROFILE VIEW Top of utility field measurement: 3.53 Bottom of utility field measurement:	
Elevation Datum: Type set: Mag Nail Offset/Direction: Nail is set C/L of the Utility. Facing: East Utility Width/Spaci	PROFILE VIEW Top of utility field measurement: 3.53 Bottom of utility field measurement:	5.34' Elevation: 22.23'
Elevation Datum: Type set: Mag Nail Offset/Direction: Nail is set C/L of the Utility.	PROFILE VIEW Top of utility field measurement: 3.53 Bottom of utility field measurement: 9	Elevation: 22.23' COORDINATES
Elevation Datum: Type set: Mag Nail Offset/Direction: Nail is set C/L of the Utility. Facing: East Utility Width/Spaci	PROFILE VIEW Top of utility field measurement: 3.53 Bottom of utility field measurement:	5.34' Elevation: 22.23'


NOTE: SEE SHEET 18 FOR TEST HOLE/PIT LOCATIONS

210 COP	ACILITIES & ENGINEI O CLARENDON ARLINGT PHONE: FAX: 7 YRIGHT © 201 VIRGINIA - AL AL TREVO Lic. N	TMENT OF ENTAL SERV NGINEERING DIVERING BUREAU BOULEVARD, SUFON, VA 22201 703.228.3629 703.228.3606 6 ARLINGTON OLL RIGHTS RESER ALTHOUSE MALENTE SERVING TO MALENTE	ISION ITE 813 COUNTY
QUA CON WA- TRA Did PRO	Dufa	ANAGEMENT SUF 03.0 TREETS BUREAU Leach 03.0 DIRECTOR	4.2021
PROJECT NAME AND LOCATION	TRANSITWAY EXTENSION TO PENTAGON CITY	TEST HOLE PIT LOGS CRYSTAL DR & 12TH ST S	MA13 - SEGMENT I
DRA CHE MIS —— FILE MA1 PAT PLO PLO	ENAME: 3-229-TESTHO	52\ENGINEERING 4 2021 ARP	





MID-ATLANTIC UTILITY LOCATING, L.L.C.	TE	ST HO	LE FORM		MOSATE PIEC UZIATO RESORTINS
4501 DALY DRIVE Ch Project: M-0618-0201-5323 (Crystal City Trans.)		VA 20151 703. By: Tommy Lo	378.0100 WWW.MIDATL	Date: 2018-02-06	H
City: Crystal City	State: V		3,0373	Test Hole: TH L10 of	
General Location: 12 St. S. & S Clark St.					
Section By Control Section (Control Section Control Section Co		UTILITY II	FORMATION		
Utility Size: 2 1/2"	Material	: Steel	2	Good Condition: YES	
Utility Type: Electric Conduit				Utility Owner:	
	А	DDITIONAL UT	LITY INFORMATION		
Utility Size:	Material:			See Test Hole No.:	
Utility Type: None	200-1 (200-200-1 (100-200-1			Utility Owner:	
		SITE CO	ONDITIONS		
Field Condition: Brick			Pavement thickness: 3"	3	
Ground Condition: Sand, Gravel, Brown Soil		-	<u> </u>		
	FIRST	& SECOND BEN	CHMARK INFORMATION		
1st Elevation: 28.37	1st Bend	hmark Descrip	tion: 14034		
BM Check: +-0.04'		72			
2nd Elevation: 27,99°	2nd Ben	chmark Descrip	otion: 13005		
Elevation Datum:			100 A 100 C 100 C 100 A		
		FIELD MARKE	R INFORMATION		
Type set: Chiseled "X"			Elevation: 28.42'		
Offset/Direction: Nail is set C/L of the Utility.					
		PROF	ILE VIEW		
			field measurement: <u>2.44'</u>	Elevation	
		Bottom of util	ity field measurement: No	ne Elevation	n: None
Facing: East Utility Width/Spac	ing;		11	COORDWATES	
PLAN VIEW			Northing:	COORDINATES	
Ped Crossing 2.28' Sign 15.60'	_ ¹ _			Easting: COMMENTS/NOTES	





UTILITY LOCATING, L.L.C.			LE FORM	
4501 DALY DRIV Project: M-0618-0201-5323 (Crystal City Tra	- 11 - 1 - 1 - 1 - 1 - 1 - 1 - 1 - 1 -	VA 20151 703. d By: Stephen R	378.0100 WWW.MIDATL	Date: 2018-02-05
City: Arlington	State: V	23 17	3	Test Hole: TH L9 of
General Location: 12th St. and Long Bridge	- Introduction			TOTAL
		UTILITY IN	IFORMATION	
Utility Size: 8 1/2"	Material	Epoxy Coated 5	Steel	Good Condition: YES
Utility Type: Gas Line				Utility Owner: WGL
	A	DDITIONAL UTI	LITY INFORMATION	
Utility Size:	Material			See Test Hole No.:
Utility Type: None	*			Utility Owner:
		SITE CO	ONDITIONS	
Field Condition: Asphalt Road			Pavement thickness: 9"	
Ground Condition: Brown Soil/ Rock				
	FIRST	& SECOND BEN	ICHMARK INFORMATION	
1st Elevation: 14034	1st Bend	hmark Descript	tion: 28.37	
BM Check: +-0.04'	<u></u>	22 - 32-42 - 32-3	A200 1 (No. 60 2 20 4 4	
2nd Elevation: 27.99'	2nd Ben	chmark Descrip	tion: 13005	
Elevation Datum:		-		
		FIELD MARKE	R INFORMATION	
Type set: Mag Nail			Elevation: 27,77*	
Offset/Direction: Nail is set C/L of the Utility.		******		
		PROF	ILE VIEW	
Y		Top of utility t	field measurement: <u>4.39'</u>	Elevation: <u>23.38'</u>
		Bottom of util	ity field measurement: No	ne Elevation: None
Facing: East Utility Width	/Spacing:			
PLAN VIE	V	2	_	COORDINATES
19 65' 19 65' 35.25' 11.55' 0 15417			Northing:	Easting: COMMENTS/NOTES


T ASOL DALY DRIVE	CHANTILLY, VA 20151 703.	378 0100 LW/W/WIDATI	MOBILE PIELD DATA REPORTING
Project: M-0618-0201-5323 (Crystal City Trans			Date: 2018-02-08
City: Arlington	State: VA		Test Hole: TH L12 of
General Location: 12th St S. and S Clark St.			
1 (a) (b) (b) (b) (c) (c) (c) (c) (c) (c) (c) (c) (c) (c	UTILITY IN	FORMATION	
Utility Size: 24"	Material: Rough Pour Co	ncrete	Good Condition: YES
Utility Type: Communication Ductbank	1		Utility Owner:
	ADDITIONAL UTI	LITY INFORMATION	
Utility Size:	Material:		See Test Hole No.:
Utility Type: None			Utility Owner:
	SITE CO	ONDITIONS	
Field Condition: Brick Sidewalk		Pavement thickness: 3'	
Ground Condition: Sand, Gravel, Brown Soil		•)	
	FIRST & SECOND BEN	NCHMARK INFORMATION	·
1st Elevation: 28.37	1st Benchmark Descrip	tion: 14034	
BM Check: +-0.04			
2nd Elevation: 27.99'	2nd Benchmark Descrip	otion: 13005	
Elevation Datum:			
	FIELD MARKE	R INFORMATION	
Type set: Chiseled "X"		Elevation: 28.87	
Offset/Direction: Chiseled "X" is set C/L of the	Utility.		
	PROF	ILE VIEW	
	7 5		
~			
	Top of utility	field measurement: 3.35'	Elevation: 25.52'
1.			
	Bottom of util	ity field measurement: 3.	78' Elevation: <u>25.09'</u>
Facing: West Utility Width/S	pacing:		
PLAN VIEW			COORDINATES
Ped Crossing	10 2000	Northing:	Easting:
12.25'	1		COMMENTS/NOTES
□ S Sign	N		
25.20'	1,52		
Ò₁3005			
12	th St. S.		
		I I	


NOTE: SEE SHEET 18 FOR TEST HOLE/PIT LOCATIONS


'		NGTO	N
210 COP	ACILITIES & EI ENGINEI O CLARENDON ARLINGT PHONE: FAX: 7 YRIGHT © 201 VIRGINIA - AL TREVO Lic. N	RTMENT OF ENTAL SERVINGINEERING DIVERING BUREAU BOULEVARD, SUTON, VA 22201 703.228.3629 703.228.3606 6 ARLINGTON OLL RIGHTS RESERVALTHOLD AND AUGUSTO SUR M. LANTZY No. 0402050508 8/4/2021	ISION JITE 813 COUNTY
AP	PROVALS		DATE
TRA	TER, SEWER, S	L ENGINEER SANAGEMENT SUF 03.0 TREETS BUREAU Leach OS DIRECTOR	4.2021 CHIEF
 -			
-			
PROJECT NAME AND LOCATION	TRANSITWAY EXTENSION TO PENTAGON CITY	TEST HOLE PIT LOGS CRYSTAL DR & 12TH ST S	MA13 - SEGMENT I
DRA	GIGNED: PB AWN: NS ECKED: TL		
FILE MA1	ENAME: .3-229-TESTHC	NSMITTAL #: N/A DLES.DWG S2\ENGINEERING	
PLO PLO	TTED: AUGUST TTED BY:NSHA	⁻ 4 2021 ARP	
	HEET	35 O	F 35
VCT	AL DD (). 12TU C	T 6











ARLINGTON