

SPALDING COUNTY
SPALDING COUNTY CORRECTION INSTITUTE BAR SCREEN

FROM: PARAGON CONSULTING GROUP, INC.
350 AIRPORT ROAD
GRIFFIN, GA 30224

TO: ALL BIDDERS OF RECORD

RE: Addendum No. 1, dated February 18, 2020

This Addendum forms a part of the Contract Documents and modifies the original Bidding Documents dated January 2020.

This Addendum consists of two (2) pages, three (3) plan sheets, a revised Bid Tabulation, and revised Exhibit E.

CONTRACT DOCUMENTS AND SPECIFICATIONS

- Add. 1.1 Modification: The 'CONTRACTOR AFFIDAVIT AND AGREEMENT' form included in Book 1 of the Bid Documents contains incorrect text. A revised copy of the form is attached to this Addendum and becomes a part of the contract documents.
- Add. 1.2 Modification: Revised Plan Sheet 4 is attached to this addendum and becomes a part of the contract documents.
- Add. 1.3 Modification: Revised Plan Sheet 5 is attached to this addendum and becomes a part of the contract documents.
- Add. 1.4 Modification: Revised Plan Sheet 9 is attached to this addendum and becomes a part of the contract documents.
- Add. 1.5 Modification: The 1-inch water line described in Line Item 11 of the Bid Tabulation has been changed to a 1-1/2 inch schedule 40 PVC water service line. The length of the service line is approximately 190 linear feet. The contractor will connect the water service line to an existing 1 inch hose bibb service line in the location shown in Addendum Exhibit 1.1 included with this addendum. A revised Bid Tabulation is attached to this addendum and becomes a part of the contract documents.
- Add. 1.6 Modification: Addendum Exhibit 1.1 is attached to this addendum and becomes a part of the contract documents. The exhibit indicates the location of the water service line connection mentioned in Add. 1.5 above.
- Add. 1.7 Clarification: Spalding County will provide equipment and personnel to remove the existing Muffin Monster.

Add. 1.8 Clarification: It is acceptable for the contractor to pour the dumpster pad curb and dumpster pad slab separately. If this method is used the contractor must utilize #4 dowels at 24-inches on center to tie the two together.

End of Addendum No. 1