



**East Bay Park Improvements- Dog Park Fencing and Irrigation
Project #1218
RFB
Addendum #01
Date: 9-30-2019**

Answers to Questions and Clarifications

1. Will the City be supplying and/or installing the dog drinking fountains?

The City will be supplying the two (2) water fountains. The Contractor will be responsible to install the fountains. The exact location of these fountains is to be coordinated in the field with the City. Include the cost of installation under Item 1-General Conditions.

2. Water Service Size and Backflow Preventer

The City will be responsible to set the water meter in place. Depending upon the final irrigation system design, a 1-in. or 1 ½- in. service maybe needed. All City furnished 1-in. meters come with a back flow preventer in the meter box. Meters bigger than 1-in. will require a backflow preventer outside the meter. The contractor will be responsible to pipe up to the meter or backflow preventer, as needed.