

SUPPLEMENTS TO THE DES CONSTRUCTION STANDARDS AND SPECIFICATIONS

SECTION 01500 – TEMPORARY EROSION AND SEDIMENT CONTROL

PART 3 - EXECUTION

PARAGRAPH 3.1 Installation and Maintenance of Erosion and Sediment Controls

Delete

3.5.C The Contractor shall conduct dewatering operations in a manner to prevent sediment or other pollutants from discharging to the County's storm drain system, which includes the curb and gutter, or any surface water. Dewatering operations shall not create any erosion or flooding. Dewatering discharges that contain chemicals, hydrocarbons, or sewage shall not be discharged to the storm drain system. Any discharge from dewatering operations shall be properly filtered prior to being discharged. A dewatering plan with sufficient detail to ensure the proposed dewatering shall comply with applicable regulations must be included as part of the erosion and sediment control plan.

Add

3.5.C The Contractor shall conduct dewatering operations in a manner to prevent sediment or other pollutants from discharging to the County's storm drain system, which includes the curb and gutter, or any surface water. Dewatering operations shall not create any erosion or flooding. Dewatering discharges that contain chemicals, hydrocarbons, or sewage shall not be discharged to the storm drain system. Any discharge from dewatering operations shall be properly filtered prior to being discharged. The Contractor shall prepare a dewatering plan with sufficient detail to ensure the proposed dewatering complies with applicable regulations.

SECTION 02200 – EARTHWORK

PART 3 - EXECUTION

PARAGRAPH 3.5 Dewatering

Delete

3.5.C The Contractor shall conduct dewatering operations in a manner to prevent sediment or other pollutants from discharging to the County's storm drain system, which includes the curb and gutter, or any surface water. Dewatering operations shall not create any erosion or flooding. Dewatering discharges that contain chemicals, hydrocarbons, or sewage shall not be discharged to the storm drain system. A dewatering plan with sufficient detail to ensure the proposed dewatering shall comply with applicable regulations must be included as part of the erosion and sediment control plan.

Add

3.5.C The Contractor shall conduct dewatering operations in a manner to prevent sediment or other pollutants from discharging to the County's storm drain system, which includes the curb and gutter, or any surface water. Dewatering operations shall not

create any erosion or flooding. Dewatering discharges that contain chemicals, hydrocarbons, or sewage shall not be discharged to the storm drain system. Any discharge from dewatering operations shall be properly filtered prior to being discharged. The Contractor shall prepare a dewatering plan with sufficient detail to ensure the proposed dewatering complies with applicable regulations.

SECTION 02500 – GRAVITY SEWERS AND APPURTENANCES

PART 4 – MEASUREMENT AND PAYMENT

PARAGRAPH 4.1 Sewer

Delete

4.1.A Sewer pipe for the various materials, classes, and sizes shown on the plans shall be measured in linear feet along the center line of the pipe and shall be measured from inside wall of structure to inside wall of structures. Payment shall include the furnishing of all pipe and fittings, all necessary tests, excavation, removal and disposal of existing pipes, removal and disposal of unsuitable or surplus material, placement of bedding and backfill as shown in Standard M-3.0, restoration of roadways as shown in Standard M-6.1, all other restoration, and all other work required to providing a complete sewer installation in compliance with the Construction Documents.

Add

4.1.A Sewer pipe for the various materials, classes, and sizes shown on the plans shall be measured in linear feet along the center line of the pipe and shall be measured from inside wall of structure to inside wall of structures. Payment shall include the furnishing of all pipe and fittings, all necessary tests, excavation, abandonment and/or removal and disposal of existing pipes, removal and disposal of unsuitable or surplus material, placement of bedding and backfill as shown in Standard M-3.0, restoration of roadways as shown in Standard M-6.1, all other restoration, and all other work required to providing a complete sewer installation in compliance with the Construction Documents.

SECTION 02600 - BITUMINOUS ROADWAY PAVEMENTS

PART 4 – MEASUREMENT AND PAYMENT

Delete

4.2 Subbase shall be measured to the width and depths shown on the approved plans as verified in the field by the Project Officer or his designee. Payment shall be in cubic yards of material.

Add

4.2 Subbase shall be measured to the width and depths shown on the approved plans as verified in the field by the Project Officer or his designee. Payment shall be in cubic yards of material and shall include demolition, excavation, and the necessary preparation of the sub grade surface.

SECTION 02900 - PAVEMENT MARKINGS

24-DES-ITBPW-474

PART 3 - EXECUTION

PARAGRAPH 3.2 Provision for Temporary Markings

Add

B. All Type D pavement markings shall conform to the latest VDOT requirements.

PART 4 - MEASUREMENT AND PAYMENT

PARAGRAPH 4.4 Removal/Eradication of Existing Pavement Markings

Delete

A. Payment for pavement line markings (type, class, width) removal and/or eradication shall be paid by actual work performed as listed in the contract and shall include all labor, materials, tools, equipment, transportation, supplies, and incidentals required to remove and/or eradicate the line markings as specified.

Add

A. Payment for pavement line markings (type, class, width) removal and/or eradication shall be incidental to the work and no separate payment shall be made.

Add

PARAGRAPH 4.5 Pavement Message Marking

A. Measurement of pavement message markings (type, class, size) shall be in units of each furnished and installed.

B. Payment for pavement message markings (type, class, size) shall be in units of each and shall include all labor, materials, tools, equipment, transportation, supplies, and incidentals required to furnish and install the message markings as specified.

SECTION 329100 - PLANTING PREPARATION

PART 4 - MEASUREMENT AND PAYMENT

Add

4.10 The measurement of CONTINUOUS SOIL PANEL to be paid for shall be per CUBIC YARD of the amended soil in accordance with the plans, specifications and to the satisfaction of the Project Officer.

4.11 The unit price for CONTINUOUS SOIL PANEL shall include the cost of furnishing all labor, materials, equipment and incidental expenses, including but not limited to imported topsoil, vapor barrier, 4" UD-4 underdrain (per VDOT specification), bedding material per Continuous Soil Panel and Tree Pit Drainage Details, and connection to storm sewer system.

SUPPLEMENTS TO THE 2020 LIGHTING SPECIFICATIONS

Modify the listed sections as follows:

SECTION 14050 – LIGHTING CONDUCTORS

PART 4 MEASUREMENT AND PAYMENT

Delete

- (a) Furnish Conductor shall be measured and paid for on a linear foot basis.
- (b) Install Conductor will be measured and paid for on a linear foot basis. Several conductors pulled into a single conduit at the shall be measured by the length of the pull rather than the total length of the conductors installed. Cost for pulling conductors shall include all connectors, splice enclosures, or other appurtenances required for making the electrical connections.
 - 1. The cost of installing or replacing pull rope shall be incidental to the cost of pulling conductor.

Add

- (a) Furnishing and installing all conductor(s) and/or cable(s) for streetlights is included in a single price paid per linear foot measured by the length of conduit installed. The Unit Price shall include the cost of all conductors, fittings, connections, slack, securing terminals and other incidentals necessary for the Work as detailed in the County Lighting Specifications.
 - 1. The size, number and/or required slack length of the conductor(s) and/or cable(s) will not be assessed independently for payment.
 - 2. The cost of installing or replacing pull rope shall be incidental to the cost of the conductor(s).
- (b) THIS LINE INTENTIONALLY LEFT BLANK