

**CONSTRUCTION SERVICES FOR INSTALLATION OF
VINYL FLOORING AT CITY HALL-FIRE STATION 1**

SCOPE OF WORK

Construction Phase

- Contractors must use Safe Work Practice to installation, removal of existing carpet, existing base, remove, and cart away all materials from premises.
- Firms shall have three year experience in the installation of said product.
- Remove old existing floor material, vacuum, and prepare for new flooring.
- Level floor as needed for level installation.
- Install floating LVT Shaw Navigator Plank Vinyl Flooring
- Install 4" Black rubber cove base.

- Contractor is responsible for all City, County, or State license, permits and fees.

- Project duration shall be 7 day from the Notice to Proceed.

- Notice to Proceed will not be issued until contractor has required product and is ready to install.

- There will be no Payment or Performance bond for this project.

- There will be no bid bond for this project.

Submit all questions in writing to:

Tony McAbee
Facility Maintenance Manager
City of Spartanburg
tmcabee@cityofspartanburg.org