

# GROVECENTER ELEM. SCHOOL

775 N LARK ELLEN AVE. WEST COVINA, CA 91791

## COVID 19 - COVINA VALLEY DISTRICT HVAC REPLACEMENT

### 100% CONSTRUCTION DOCUMENTS

11/08/2022

DLR GROUP PROJECT NUMBER: 75-22605-00

DSA APPLICATION #  
A# 03-122225

#### SHEET INDEX

GENERAL		ELECTRICAL	
G0.1	COVER SHEET	E0.1	ELECTRICAL SYMBOLS, ABBREVIATIONS & NOTES
G1.1	GENERAL NOTES, SYMBOLS AND ABBREVIATIONS	E2.1	ELECTRICAL ROOF POWER PLAN
ARCHITECTURAL			
A1.1	ARCHITECTURAL SITE PLAN	E5.1	ELECTRICAL DIAGRAMS AND SCHEDULES
A1.1A	BUILDING BCD, AND BUILDING E FLOOR PLANS	E6.1	ELECTRICAL DETAILS
A1.1B	BUILDING F AND BUILDING G FLOOR PLANS	TOTAL: 32 SHEETS	
A1.3A	BUILDING BCD, AND BUILDING E ROOF PLANS		
A1.3B	BUILDING F AND BUILDING G ROOF PLANS		
A3.1A	BUILDING BCD, AND BUILDING E REFLECTED CEILING PLANS		
A3.1B	BUILDING F AND BUILDING G REFLECTED CEILING PLANS		
MECHANICAL			
M0.1	MECHANICAL SYMBOLS, ABBREVIATIONS & NOTES		
M0.2	TITLE 24 COMPLIANCE		
M0.4	TITLE 24 COMPLIANCE		
M0.3	TITLE 24 COMPLIANCE		
M0.5	TITLE 24 COMPLIANCE		
M0.6	TITLE 24 COMPLIANCE		
M1.1	OVERALL MECHANICAL SITE PLAN		
M1.1C	MECHANICAL FLOOR PLANS		
M1.3C	MECHANICAL ROOF PLANS		
M5.1	CONTROLS DIAGRAMS		
M5.2	CONTROLS DIAGRAMS		
M7.1	MECHANICAL DETAILS		
M7.2	MECHANICAL DETAILS		
M7.3	MECHANICAL DETAILS		
M7.4	MECHANICAL DETAILS		
M7.5	MECHANICAL DETAILS		
M8.1	MECHANICAL SCHEDULES		
MD1.1	MECHANICAL DEMOLITION PLANS		
MP1.1	MECHANICAL PLUMBING SITE PLAN		

#### VICINITY MAP



#### PROJECT DIRECTORY

**OWNER**  
COVINA VALLEY UNIFIED  
SCHOOL DISTRICT  
518 E BADILLO STREET  
COVINA, CA 91723  
CONTACT: BRIAN JOHNSON  
PH: 626.974.7000  
BJOHNSON@C-VUSD.ORG

**ARCHITECT**  
DLR GROUP  
1650 SPRUCE ST. #300  
RIVERSIDE, CA 92507  
CONTACT: JESSE MILLER  
PH: 951.882.0470  
JMILLER@DLRGROUP.COM

**MECHANICAL ENGINEER**  
DLR GROUP  
700 FLOWER ST 22ND FLOOR  
LOS ANGELES, CA 90017  
CONTACT: DONNA ZHAO  
PH: 213.800.9400  
NPATENA@DLRGROUP.COM

**STRUCTURAL ENGINEER**  
DLR GROUP  
700 FLOWER ST 22ND FLOOR  
LOS ANGELES, CA 90017  
CONTACT: DANIEL HAKHAM  
PH: 213.800.9400  
DAHAKHAM@DLRGROUP.COM

#### Statement of General Conformance

FOR ARCHITECTS/ENGINEERS WHO UTILIZE PLANS,  
INCLUDING BUT NOT LIMITED TO SHOP DRAWINGS, PREPARED BY OTHER  
LICENSED DESIGN PROFESSIONALS AND/OR CONSULTANTS

(Application No. 03-122225 File No. 19-25)

HAVE BEEN PREPARED BY OTHER DESIGN PROFESSIONALS OR CONSULTANTS  
WHO ARE LICENSED AND/OR AUTHORIZED TO PREPARE SUCH DRAWINGS IN THIS  
STATE. IT HAS BEEN EXAMINED BY ME FOR:

1) DESIGN INTENT AND APPEARS TO MEET THE APPROPRIATE REQUIREMENTS OF  
TITLE 24, CALIFORNIA CODE OF REGULATIONS, AND THE PROJECT  
SPECIFICATIONS PREPARED BY ME, AND

2) COORDINATION WITH MY PLANS AND SPECIFICATIONS, AND IS ACCEPTABLE  
FOR INCORPORATION INTO THE CONSTRUCTION OF THIS PROJECT.

THE STATEMENT OF GENERAL CONFORMANCE "SHALL NOT BE CONSTRUED AS  
RELIEVING ME OF MY RIGHTS, DUTIES, AND RESPONSIBILITIES UNDER SECTIONS  
17302 AND 81138 OF THE EDUCATION CODE AND SECTIONS 4-336, 4-341 AND 4-344"  
OF TITLE 24, PART 1, (TITLE 24, PART 1, SECTION 4-317(d)).

I FIND THAT:  ALL DRAWINGS OR SHEETS LISTED ON THE COVER OR INDEX SHEET  
FOR EACH DISCIPLINE (SEE SHEET INDEX FOR LIST OF DISCIPLINES)  
 THIS DRAWING OR PAGE

ARE IN GENERAL CONFORMANCE WITH  
THE PROJECT DESIGN,  
AND  
 HAVE BEEN COORDINATED WITH THE  
PROJECT PLANS AND SPECIFICATIONS.

ARE IN GENERAL CONFORMANCE WITH  
THE PROJECT DESIGN INTENT,  
AND  
 HAVE BEEN COORDINATED WITH THE  
PROJECT PLANS AND SPECIFICATIONS.

05/05/2022  
SIGNATURE DATE  
ARCHITECT OR ENGINEER DESIGNATED TO BE IN  
GENERAL RESPONSIBLE CHARGE  
JESSE MILLER

C-32306 10/31/2023  
LICENSE NUMBER EXPIRATION DATE

ARE IN GENERAL CONFORMANCE WITH  
THE PROJECT DESIGN INTENT,  
AND  
HAVE BEEN COORDINATED WITH THE  
PROJECT PLANS AND SPECIFICATIONS.

SIGNATURE DATE  
ARCHITECT OR ENGINEER DELEGATED  
RESPONSIBILITY FOR THIS PORTION OF THE  
WORK

PRINT NAME  
C-32306 10/31/2023  
LICENSE NUMBER EXPIRATION DATE

#### DESIGN ANALYSIS DATA

- WIND DESIGN CRITERIA (CBC 1603A.1.4) - STRUCTURAL DESIGN PARAMETERS  
- RISK CATEGORY: II  
- WIND DESIGN SPEED: V=110 MPH  
- WIND EXPOSURE CATEGORY: B (PER ASCE 7-16)
- EARTHQUAKE DESIGN CRITERIA (CBC 1603A.1.5)  
- SEISMIC DESIGN CATEGORY: D  
- SITE CLASS: D  
-  $S_s = 1.656$   
-  $S_1 = 0.911$   
-  $S_{m1} = 1.164$   
-  $S_{m2} = 1.039$   
-  $S_{m3} = 1.33$   
-  $S_{m4} = 0.992$   
-  $I_e$  (IMPORTANCE FACTOR) = 1.00  
-  $F_p$  (CONTROLLING HOR. SEISMIC FORCE) = 1711 LBS
- DESIGN LOAD BEARING VALUES OF SOILS (CBC 1603A.1.6)  
- ALLOWABLE SOIL BEARING PRESSURE: 1,500 PSF  
- ALLOWABLE LATERAL BEARING PRESSURE: 100 PSF MIN.

#### SCOPE OF WORK

SCOPE OF WORK SHALL BE AS FOLLOWS:

EXISTING HVAC SYSTEM REPLACEMENT TO BUILDINGS B, D, E, F, AND G

#### APPLICABLE CODES


2022 CALIFORNIA ADMINISTRATIVE CODE (CAC), PART 1, TITLE 24 CCR  
2022 CALIFORNIA BUILDING CODE (CBC), PART 2, TITLE 24 CCR  
(2021 INTERNATIONAL BUILDING CODE, VOL. 1 & 2 AND 2022 CALIFORNIA AMENDMENTS)  
2022 CALIFORNIA ELECTRICAL CODE (CEC), PART 3, TITLE 24 CCR  
(2021 NATIONAL ELECTRICAL CODE AND 2022 CALIFORNIA AMENDMENTS)  
2022 CALIFORNIA MECHANICAL CODE (CMC), PART 4, TITLE 24 CCR  
(2021 IAPMO UNIFORM MECHANICAL CODE AND 2022 CALIFORNIA AMENDMENTS)  
2022 CALIFORNIA PLUMBING CODE (CPC), PART 5, TITLE 24 CCR  
(2021 IAPMO UNIFORM PLUMBING CODE AND 2022 CALIFORNIA AMENDMENTS)  
2022 CALIFORNIA ENERGY CODE (CEC), PART 6, TITLE 24 CCR  
2022 CALIFORNIA FIRE CODE (CFC), PART 7, TITLE 24 CCR  
(2021 INTERNATIONAL FIRE CODE AND 2022 CALIFORNIA AMENDMENTS)  
2022 CALIFORNIA EXISTING BUILDING CODE (CEBC), PART 10, TITLE 24 CCR  
(2001 INTERNATIONAL EXISTING BUILDING CODE AND 2022 CALIFORNIA AMENDMENTS)  
2022 CALIFORNIA GREEN BUILDING STANDARDS CODE (CAL GREEN), PART 11, TITLE 24 CCR  
2022 CALIFORNIA REFERENCED STANDARDS CODE (CECS), PART 12, TITLE 24 CCR  
TITLE 19 CCR, PUBLIC SAFETY, STATE FIRE MARSHAL REGULATIONS  
2019 ASME A17.1/CSA B44-13 SAFETY CODE FOR ELEVATORS AND ESCALATORS  
(PER 2022 CBC PART 2 CH 35)  
NOTE: CALIFORNIA ELEVATOR UNIT ENFORCES CCR TITLE 8 AND USES THE 2004 ASME A17.1 BY  
ADOPTION  
2010 ADA STANDARDS FOR ACCESSIBLE DESIGN

NFPA 13	STANDARD FOR INSTALLATION OF SPRINKLERS SYSTEMS (CA AMENDED)	2016 ADDITION
NFPA 14	STANDARD FOR INSTALLATION OF SAND PIPE AND HOSE SYSTEMS (CA AMENDED)	2013 ADDITION
NFPA 17	STANDARD FOR DRY CHEMICAL EXTINGUISHING SYSTEMS	2016 ADDITION
NFPA 17A	STANDARD FOR WET CHEMICAL EXTINGUISHING SYSTEMS	2017 ADDITION
NFPA 20	STANDARD FOR INSTALLATION OF STATIONARY PUMPS FOR FIRE PROTECTION	2017 ADDITION
NFPA 22	STANDARD FOR WATER TANKS FOR PRIVATE FIRE PROTECTION	2013 ADDITION
NFPA 24	STANDARD FOR THE INSTALLATION OF PRIVATE FIRE SERVICE MAINS AND THEIR APPURTENANCES	2016 ADDITION
NFPA 72	NATIONAL FIRE ALARM AND SIGNALING CODE (CA AMENDED)	2016 ADDITION
NFPA 80	STANDARD FOR FIRE DOORS AND OTHER OPENINGS PROTECTIVE	2016 ADDITION
NFPA 2001	STANDARD ON CLEAN AGENT FIRE EXTINGUISHING SYSTEMS (CA AMENDED)	2016 ADDITION
UL 300	STANDARD FOR FIRE TESTING OF FIRE EXTINGUISHING SYSTEMS FOR PROTECTION OF COMMERCIAL COOKING EQUIPMENT	2005 (R2010)
UL 464	AUDIBLE SIGNALING DEVICES FOR FIRE ALARM AND SIGNALING SYSTEMS, INCLUDING ACCESSORIES	2005 (R2010)
UL 521	STANDARD FOR HEAT DETECTORS FOR FIRE PROTECTIVE SIGNALING SYSTEMS	2003 ADDITION
UL 1971	STANDARD FOR SIGNALING DEVICES FOR THE HEARING IMPAIRED	2002 (R2010)
ICC 300	STANDARD FOR BLEACHERS, FOLDING AND TELESCOPIC SEATING, AND GRANDSTANDS	2017 ADDITION

#### DSA GENERAL NOTES

- CHANGES TO THE APPROVED DRAWINGS AND SPECIFICATIONS SHALL BE MADE BY AN ADDENDUM OR A CONSTRUCTION CHANGE DOCUMENT APPROVED BY THE DIVISION OF THE STATE ARCHITECT (DSA), AS REQUIRED BY SECTION 4-338(B), PART 1, TITLE 24, CALIFORNIA CODE OF REGULATIONS (CCR), NOT WITH STANDING OTHER PROVISIONS OF THE PROJECT SPECIFICATIONS, COMPLY WITH ALL PROVISIONS OF THE CALIFORNIA BUILDING STANDARDS ADMINISTRATIVE CODE (PART 1, TITLE 24, CCR), SECTION 4-338, FOR ALL ADDENDUM AND CONSTRUCTION CHANGE DOCUMENTS.
- CONSTRUCTION CHANGE DOCUMENTS MUST BE SIGNED BY ALL THE FOLLOWING ARCHITECT OR ENGINEER HAVING GENERAL RESPONSIBLE CHARGE OF THE PROJECT, AND STRUCTURAL ENGINEER OF RECORD OR DELEGATED PROFESSIONAL ENGINEER (WHEN APPLICABLE).
- SUBSTITUTIONS AFFECTING DSA REGULATED ITEMS (ACCESSIBILITY, STRUCTURAL ENGINEER, AND FIRE/SAFETY) SHALL BE CONSIDERED AS A CONSTRUCTION CHANGE DOCUMENT, AND SHALL BE APPROVED BY DSA PRIOR TO FABRICATION AND INSTALLATION IN ACCORDANCE WITH DSA IR-A-6 AND SECTION 4-338(B), PART 1, TITLE 24, CCR. SUBSTITUTIONS SHALL BE FOR ANY MATERIALS, SYSTEMS OR PRODUCT THAT WOULD OTHERWISE BE REGULATED BY DSA.
- A DSA-CERTIFIED PROJECT INSPECTOR WITH CLASS 3 CERTIFICATION, EMPLOYED BY THE DISTRICT (OWNER) AND APPROVED BY THE ARCHITECT AND BY THE DIVISION OF THE STATE ARCHITECT, SHALL PROVIDE CONTINUOUS INSPECTION OF THE WORK. THE DUTIES OF THE PROJECT INSPECTOR ARE DEFINED IN SECTION 4-342, CALIFORNIA BUILDING ADMINISTRATIVE CODE (PART 1, TITLE 24, CCR).
- A DSA-ACCEPTED TESTING LAB, EMPLOYED BY THE DISTRICT (OWNER), SHALL CONDUCT ALL REQUIRED TESTS AND INSPECTIONS OF THE WORK.
- THE DSA-CERTIFIED PROJECT INSPECTOR AND DSA-ACCEPTED TESTING LAB SHALL BE EMPLOYED AND PAID BY THE OWNER (DISTRICT) AND APPROVED BY ALL OF THE FOLLOWING ARCHITECT OR ENGINEER HAVING GENERAL RESPONSIBLE CHARGE OF THE PROJECT, STRUCTURAL ENGINEER OF RECORD, AND DIVISION OF THE STATE ARCHITECT (DSA). THE INSPECTOR OF RECORD FOR THIS PROJECT SHALL BE CLASS 3 OR BETTER.
- ALL WORK SHALL CONFORM TO 2019 TITLE 24, CALIFORNIA CODE OF REGULATIONS (CCR).
- A DSA-ACCEPTED TESTING LABORATORY DIRECTLY EMPLOYED BY THE DISTRICT (OWNER) SHALL CONDUCT ALL THE REQUIRED TESTS AND INSPECTIONS FOR THE PROJECT.
- THE INTENT OF THESE DRAWINGS AND SPECIFICATIONS IS THAT THE WORK OF THE ALTERATION, REHABILITATION OR RECONSTRUCTION IS TO BE IN ACCORDANCE WITH TITLE 24, CCR. SHOULD ANY EXISTING CONDITIONS SUCH AS DETERIORATION OR NON-COMPLYING CONSTRUCTION BE DISCOVERED WHICH IS NOT COVERED BY THE CONTRACT DOCUMENTS WHEN THE FINISHED WORK WILL NOT COMPLY WITH TITLE 24, CCR, A CONSTRUCTION CHANGE DOCUMENT (CCD), OR A SEPARATE SET OF PLANS AND SPECIFICATIONS, DETAILING AND SPECIFYING THE REQUIRED WORK SHALL BE SUBMITTED TO AND APPROVED BY DSA BEFORE PROCEEDING WITH THE WORK. (SECTION 4-317(C), PART 1, TITLE 24, CCR)
- FABRICATION AND INSTALLATION OF DEFERRED SUBMITTAL ITEMS SHALL NOT BE STARTED UNTIL CONTRACTOR'S DRAWINGS, SPECIFICATIONS, AND ENGINEERING CALCULATIONS FOR THE ACTUAL SYSTEMS TO BE INSTALLED HAVE ACCEPTED AND SIGNED BY THE ARCHITECT OR STRUCTURAL ENGINEER AND APPROVED BY DSA. LIST DEFERRED SUBMITTAL ITEMS FOR THIS PROJECT. (IF THIS PROJECT HAS NO DEFERRED SUBMITTAL ITEMS, PLEASE INDICATE AS SUCH)
- GRADING PLANS, DRAINAGE IMPROVEMENTS, ROAD AND ACCESS REQUIREMENTS AND ENVIRONMENTAL HEALTH CONSIDERATIONS SHALL COMPLY WITH ALL LOCAL ORDINANCES.
- THE CALIFORNIA ENERGY CODE SECTION 10-103 REQUIRES ACCEPTANCE TESTING ON ALL NEWLY INSTALLED LIGHTING CONTROLS, MECHANICAL SYSTEMS, ENVELOPES, AND PROCESS EQUIPMENT AFTER INSTALLATION AND BEFORE PROJECT COMPLETION, AN ACCEPTANCE TEST IS A FUNCTIONAL PERFORMANCE TEST TO HELP ENSURE THAT NEWLY INSTALLED EQUIPMENT IS OPERATING AND IN COMPLIANCE WITH THE ENERGY CODE.
- LIGHTING CONTROLS ACCEPTANCE TESTS MUST BE PERFORMED BY CERTIFIED LIGHTING CONTROLS ACCEPTANCE TEST TECHNICIAN (ATT).
- MECHANICAL SYSTEM ACCEPTANCE TEST MUST BE PERFORMED BY A CERTIFIED MECHANICAL ATT FOR PROJECTS SUBMITTED ON OR AFTER OCTOBER 1, 2021.
- ENVELOPE AND PROCESS EQUIPMENT ACCEPTANCE TESTS SHALL BE PERFORMED BY THE INSTALLING CONTRACTOR, ENGINEER/ARCHITECT OR RECORD OR THE OWNER'S AGENT.
- A LISTING OF CERTIFIED ATT CAN BE FOUND AT [HTTPS://WWW.ENERGY.CA.GOV/PROGRAMS-AND-TOPICS/PROGRAMS/ACCEPTANCE-TESTING-TECHNICIAN-CERTIFICATION-PROVIDER-PROGRAM.HTM](https://www.energy.ca.gov/programs-and-topics/programs/acceptance-testing-technician-certification-provider-program.htm)
- THE ACCEPTANCE TESTING PROCEDURES MUST BE REPEATED, AND DEFICIENCIES MUST BE CORRECTED BY THE BUILDER OR INSTALLING CONTRACTOR UNTIL THE CONSTRUCTION/INSTALLATION OF THE SPECIFIED SYSTEMS CONFORM AND PASS THE REQUIRED ACCEPTANCE CRITERIA.
- PROJECT INSPECTORS WILL COLLECT THE FORMS TO CONFIRM THAT THE REQUIRED ACCEPTANCE TESTS HAVE BEEN COMPLETED.

DLR Group  
© DLR Group



GROVECENTER ELEM. SCHOOL  
COVID 19 - COVINA VALLEY DISTRICT HVAC REPLACEMENT  
775 N LARK ELLEN AVE. WEST COVINA, CA 91791

100%  
CONSTRUCTION  
DOCUMENTS  
11/08/2022  
REVISIONS

75-22605-00  
DSA A#03-122225  
DSA File #: 19-25  
COVER SHEET

G0.1



GENERAL ABBREVIATIONS

#	NUMBER
&	AND
@	AT
ADA	AMERICANS WITH DISABILITY ACT
ADDN	ADDITION OR ADDITIONAL
AFI	ABOVE FINISHED FLOOR
AFG	ABOVE FINISHED GRADE
AHJ	AUTHORITY HAVING JURISDICTION
ALT	ALTERNATE
ANSI	AMERICAN NATIONAL STANDARDS INSTITUTE
APPROX	APPROXIMATE
ARCH	ARCHITECTURAL
BLDG	BUILDING
BSMT	BASEMENT
CL	CENTER LINE
CLG	CENTRUM
CM	CENTIMETER
CONC	CONCRETE
CONNS	CONNECTIONS
CONST	CONSTRUCTION
CONT	CONTINUOUS
CONTR	CONTRACTOR
CTR	CENTER
D	DEPTH
DEG	DEGREE
DEMO	DEMOLISH OR DEMOLITION
DA	DIAMETER
DM	DIMENSION
DIV	SPECIFICATION DIVISION
DN	DOWN
DTL	DETAIL
DWG(S)	DRAWING(S)
E	EAST
EA	EACH
EC	ELECTRICAL CONTRACTOR
EL	ELEVATION
ELEC	ELECTRICAL
ENG	ENGINEER
EQ	EQUAL
EQUIP	EQUIPMENT
EQUIV	EQUIVALENT
EXT	EXISTING
EXTR	EXTERIOR
FN	FINISHED
FL	FLOOR
FT	FEET
FUT	FUTURE
GC	GENERAL CONTRACTOR
GOVT	GOVERNMENT
H	HEIGHT
HORIZ	HORIZONTAL
HT	HEIGHT
i.e.	THAT IS
IBC	INTERNATIONAL BUILDING CODE
IN	INCH
INT	INTERIOR
LB(S)	POUNDS(S)
M	THOUSAND
M	METER
MAX	MAXIMUM
MC	MECHANICAL CONTRACTOR
MECH	MECHANICAL
MEZZ	MEZZANINE
MFR	MANUFACTURER
MIN	MINIMUM
MISC	MISCELLANEOUS
MM	MILLIMETER
N	NORTH
N/A	NOT APPLICABLE
NIC	NOT IN CONTRACT
NTS	NOT TO SCALE
OC	ON CENTER
OPP	OPPOSITE
OVHD	OVERHEAD
PAR	PARALLEL
PENT	PENTHOUSE
PLYWD	PLYWOOD
QTY	QUANTITY
REQ(D)	REQUIRE(D)
REV	REVISION(S)
RM	ROOM
RND	ROUND
S	SOUTH
SCHED	SCHEDULE
SECT	SECTION
SHT	SHEET
SIM	SIMILAR
SPEC	SPECIFICATION(S)
STD	STANDARD
STL	STEEL
STOR	STORAGE
STRUCT	STRUCTURAL
SYM	SYMMETRICAL
TEMP	TEMPORARY
TYP	TYPICAL
UNEX	UNEXCAVATED
UNFN	UNFINISHED
UNO	UNLESS NOTED OTHERWISE
VERT	VERTICAL
VEST	VESTIBULE
VIF	VERIFY IN FIELD
W	WEST
WI	WITH
W/O	WITHOUT

ARCHITECTURAL ABBREVIATIONS

A/E	ARCHITECT/ENGINEER
AB	AIR BARRIER
ABS	ASBESTOS
ACC	ADA ACCESSIBLE
AGR	ACRYLIC WALL BOARD
ACT	ACOUSTIC CEILING TILE
AD	ACCESS DOOR
ADJ	ADJUSTABLE
ADJT	ADJACENT
ADMIN	ADMINISTRATION
AEC	AUTOMATED EXTERNAL DEFIBRILLATORS
AL	ALUMINUM
ALUM	ALUMINUM
APC	ACCESS PANEL
APF	ACOUSTIC PANEL CEILING
ASPH	ASPHALT
AUTO	AUTOMATIC
AVG	AVERAGE
A/W	ACOUSTIC WALL PANEL
B.O.	BOTTOM OF
BCS	BABY CHANGING STATION
BD	BOARD
BLF	BLOCK
BLK	BLOCKING
BLKHD	BULKHEAD
BM(S)	BEAM(S)
BOT	BOTTOM
BRG	BRIDGING
BRKT	BRACKET
BT	BATHTUB
BTWN	BETWEEN
CAB	CABINET
CBD	CHALKBOARD
CER	CERAMIC
CF	CUBIC FEET
CFI	CONTRACTOR FURNISHED CONTRACTOR INSTALLED
CFMF	COLD-FORMED METAL FRAMING
CG	CLEAR FLOAT GLASS
CI	CAST IRON
CIG	CLEAR INSULATING GLASS
CIP	CAST IN PLACE
CJ	CONTROL JOINT
CJA	CONTROL JOINT ABOVE
CLO	CLOSET
CLR	CLEAR
CMU	CONCRETE MASONRY UNIT
COL	COLUMN
COM	COMMON
COMB	COMBINATION
COMM	COMMUNICATIONS
COMPR	COMPRESSIBLE
CONF	CONFERENCE
CONFIG	CONFIGURATION
CORR	CORRIDOR
CP	COVER PLATE
CPT	CARPET
CR	CHAIR RAIL
CS	COUNTERSINK
CSTJ	CONSTRUCTION JOINT
CSSW	CASWORK
CT	CERAMIC TILE
CTG	CLEAR TEMPERED FLOAT GLASS
CU	COPPER
CU	COMBINATION UNIT
CV	CONDOM VENDOR
CY	CUBIC YARD
CYL	CYLINDER
DB	DECIBEL
DBL	DOUBLE
DC	DUST COLLECTOR
DEPR	DEPRESSION(ED)
DEPT	DEPARTMENT
DET	DETENTION
DF	DRINKING FOUNTAIN
DG	DOOR GRILLE
DNG	DIAGONAL DAMPROOFING
DR	DOOR
DSN	DOWNSPOUT NOZZLE
DW	DISHWASHER
DWL(S)	DOWEL(S)
DWR	DRAWER
EB	EXPANSION BOLT
EE	EACH END
EEW	EMERGENCY EYE WASH
EEWS	EMERGENCY EYE WASH SHOWER
EFF	EFFICIENCY
EJ	EXPANSION JOINT
ELAS	ELASTOMERIC
ELEV	ELEVATOR
EMER	EMERGENCY
ENCL	ENCLOSURE
ENTR	ENTRANCE
ERF	EPOXY RESIN FLOORING
ESH	EMERGENCY USE INTENSITY
EW	EACH WAY
EWC	ELECTRIC WATER COOLER
EXP	EXPANSION
EXP	EXPOSED
F	FABRIC
F.O.	FACE OF
FAB	FABRICATED(D)
FB	FACE BRICK
FD	FLOOR DRAIN
FDN	FOUNDATION
FE	FIRE EXTINGUISHER
FEC	FIRE EXTINGUISHER CABINET
FF	FINISH FLOOR
FH	FIRE HYDRANT
FHC	FIRE HOSE CABINET
FIG	FIGURE
FI	FIXTURE
FLASH	FLASHING
FLEX	FLEXIBLE
FLG	FLOORING
FLM	FULL LENGTH MIRROR
FLUOR	FLUORESCENT
FO	FINISH OPENING
FOC	FACE OF CONCRETE
FOF	FACE OF FINISH
FOM	FACE OF MASONRY
FOS	FACE OF STUD
FOW	FACE OF WALL
FP	FIREPROOFING
FR	FIRE RESISTANT
FRP	FIBERGLASS REINFORCED PANEL
FRT	FIRE RESISTANCE TREATED
FS	FLOOR SINK
FSS	FOLDING SHOWER SEAT
FTG	FOOTING
FVC	FIRE VALVE CABINET
FWC	FABRIC WALL COVERING
G	GROUT
GA	GAUGE
GAL	GALLON
GALV	GALVANIZED
GS	GRAB BAR
GO	GARBAGE DISPOSAL
GEN	GENERAL
GFA	GROSS FLOOR AREA
GL	GLUE LAMINATED
GLASS	GLASS
GMP	GUARANTEED MAXIMUM PRICE
GR	GUARD RAIL
GR	GRADE
GRS	GALVANIZED RIGID STEEL
GWB	GYPSPAN WALL BOARD
GYP	GYPSPUM
HC	HOLLOW CORE
HD	HAND DRYER
HDF	HIGH DENSITY FIBERBOARD
HDR	HEADER
HDWD	HARDWOOD
HDWR	HARDWARE
HM	HOLLOW METAL
HOUR	HOUR
HR	HANDRAIL
HS	HARDWARE SET
HSS	HOLLOW STRUCTURAL SHAPE
HVAC	HEATING VENTILATING AND AIR CONDITIONING
IAW	IN ACCORDANCE WITH
ID	INSIDE DIAMETER
IF	INSIDE FACE
IF	INSULATED INFILL PANEL GLASS
IP	ISOLATION JOINT
IS	IN JOIST SPACE
INC	INCLUDE(ING)
INSUL	INSULATION
JAN	JANITOR
JBE	JOIST BEARING ELEVATION
JCT	JUNCTION
JFB	JOINT FILLER BOARD
JOST	JOIST
JT	JOINT
KCJ	KEYED CONSTRUCTION JOINT
KD	KNOCKDOWN
KH	KITCHEN HOOD
KIT	KITCHEN
L	ANGLE
LBS	LABORATORY
LAM	LAMINATED
LAV	LAVATORY
LBR	LUMBER
LDG	LOADING
LF	LINEAR FOOT
LG	LENGTH (LONG)
LG	LAMINATED GLASS
LN	LINEAR
LNO	LINOLEUM
LKR	LOCKER
LOC	LOCATION
LONG	LONGITUDINAL
LSC	LIFE SAFETY CODE
LVT	LIGHTING
LV	COVER
LVT	LUXURY VINYL TILE
MAG	MAGNETIC
MAINT	MAINTENANCE
MAN	MANUAL
MAS	MASONRY
MATL	MATERIAL
MB	MOP BASIN
MBD	MARKER BOARD
MBH	MOP/BROOM HOLDER
MC	MEDICINE CABINET
MEMB	MEMBRANE
MH	MANHOLE
MHS	MIRROR WITH SHELF
MTD	MOUNTED
MTG	MOUNTING
MUL	MULLION
NC	NOISE CRITERIA
NFPA	NATIONAL FIRE PROTECTION ASSOCIATION
NOM	NOMINAL
O to O	OUT TO OUT
OK	OVERALL
OFCI	OWNER FURNISHED CONTRACTOR INSTALLED
OFF	OFFICE
OFOI	OWNER FURNISHED OWNER INSTALLED
OH	OPERATIONAL SITE HAND OPENING(S)
OPG(S)	OPERATIONAL SAFETY AND HEALTH ADMINISTRATION
OTB	OPEN TO BELOW
OVFL	OVERFLOW
P	PAINT
PAN B	PANIC BOLT
PB	PARTICLE BOARD
PC	PRECAST CONCRETE
PCD	PAPER DISPENSER
PCT	PORCELAIN CERAMIC TILE
PD	PANIC DEVICE
PERF	PERFORATED
PERP	PERPENDICULAR
PG	PATTERN GLASS
PIC	PORTABLE INSTRUMENT CONNECTION
PIG	PATTERN INSULATING GLASS
PL	PLATE
PL	PROFIC LINE
PLAM	PLASTIC LAMINATE
PLBG	PLUMBING
PR	PAIR
PREFAB	PREFABRICATED
PROJ	PROJECTOR (ICON)
PS	PROJECTION SCREEN
PT	POINT
PTD	POINT OF TANGENCY
PTD	PAPER TOWEL DISPENSER
PTDR	COMBINATION TOWEL DISPENSER/RECEPTACLE
PTN	PARTITION
PVC	POLYVINYL CHLORIDE
PWL	SOUND POWER LEVEL
QT	QUARRY TILE
QTR RND	QUARTER ROUND
R	RISER
RAD	RADIUS
RB	RUBBER BASE
RC	REMOTE CONTROL
RCP	REFLECTED CEILING PLAN
RD	ROOF DRAIN
REF	REFERENCE
REFL	REFLECTED
REM	REMOVABLE
RESIL	RESILIENT
RF	RESILIENT FLOORING
RF	RUBBER FLOOR
RFM	RECESSED FLOOR MAT
RH	ROBE HOOK
RKC	ROUGH IN AND CONNECT
S	SINK
SAT	SPRAYED ACOUSTIC TREATMENT
SAW	SOUND ABSORBING WALL UNITS
SB	SPRASH BLOCK
SC	SOLID CORE
SC	SHOWER CURTAIN
SCD	SEAT COVER DISPENSER
SCH	SHOWER CURTAIN HOOK
SCR	SHOWER CURTAIN ROD
SCT	STRUCTURAL CLAY TILE
SD	SOAP DISPENSER
SECY	SECRETARY
SF	SQUARE FEET
SG	SPANDREL GLASS
SGL	SINGLE
SH	SHOWER
SHM	SECURITY HOLLOW METAL
SLNT	SEALANT
SM	SHEET METAL
SND	SANITARY NAPKIN DISPOSAL
SNV	SANITARY NAPKIN VENDOR
SPL	SOUND PRESSURE LEVEL
SQ	SQUARE
SS	SOLID SURFACE
SSA	STORM SHELTER AREA
SST	STAINLESS STEEL SHELF
ST	STONE
ST	STAIR
STAGD	STAGGERED
STC	SOUND TRANSMISSION CLASS
STR	STRINGER
SUBFL	SUBFLOOR
SURF	SURFACE
SUSP	SUSPENDED
SVF	SHEET VINYL FLOORING
T	TREAD
T&G	TONGUE AND GROOVE
T.O.	TOP OF
TAN	TANGENT
TB	TOWEL BAR
TBD	TACK BOARD
TCP	TOILET COMPARTMENT PARTITION
TERR	TERRAZZO
TG	TINTED FLOAT GLASS
TH	TEMPERED GLASS
THRESH	THRESHOLD
THK	THICKNESS
TI	TEMP IMPROVEMENT
TIG	TINTED INSULATING GLASS
TMR	TILT MIRROR UNIT
TOIL	TOILET
TOP	TOP OF PAVING
TRANS	TRANSVERSE
TR	TERRAZZO TILE
TT	TOILET TISSUE DISPENSER
TTG	TINTED TEMPERED FLOAT GLASS
TTIG	TINTED TEMPERED INSULATING GLASS
TW	TACK WALL
UL	UNDERWRITERS LABORATORIES
UR	URNAL
US	UTILITY SHELF
UTIL	UTILITY
VB	VAPOR BARRIER
VB	VINYL BASE
VCB	VENTED COVE BASE
VFL	VINYL FLOOR
VOC	VOLATILE ORGANIC COMPOUND
VOL	VOLUME
VP	VENEER PLASTER
VNT	VINYL TILE
VWC	VINYL WALL COVERING
W	WIDE
WB	WALL BASE
WC	WATER CLOSET
WC	WALL COVERING
WCL	WATER CLOSET/LAVATORY COMBINATION
WD	WOOD
WDF	WOOD FLOORING
WIDW	WINDOW
WG	POLISHED WIRE GLASS
WI	WROUGHT IRON
WOM	WALK OFF MAT
WR	WASTE RECEPTACLE
WRB	WEATHER RESISTANT BARRIER
WW	WARM WHITE
WWF	WELDED WIRE FABRIC
YD	YARD

GL	GLUE LAMINATED
GLASS	GLASS
GMP	GUARANTEED MAXIMUM PRICE
GR	GUARD RAIL
GR	GRADE
GRS	GALVANIZED RIGID STEEL
GWB	GYPSPAN WALL BOARD
GYP	GYPSPUM
HC	HOLLOW CORE
HD	HAND DRYER
HDF	HIGH DENSITY FIBERBOARD
HDR	HEADER
HDWD	HARDWOOD
HDWR	HARDWARE
HM	HOLLOW METAL
HOUR	HOUR
HR	HANDRAIL
HS	HARDWARE SET
HSS	HOLLOW STRUCTURAL SHAPE
HVAC	HEATING VENTILATING AND AIR CONDITIONING
IAW	IN ACCORDANCE WITH
ID	INSIDE DIAMETER
IF	INSIDE FACE
IF	INSULATED INFILL PANEL GLASS
IP	ISOLATION JOINT
IS	IN JOIST SPACE
INC	INCLUDE(ING)
INSUL	INSULATION
JAN	JANITOR
JBE	JOIST BEARING ELEVATION
JCT	JUNCTION
JFB	JOINT FILLER BOARD
JOST	JOIST
JT	JOINT
KCJ	KEYED CONSTRUCTION JOINT
KD	KNOCKDOWN
KH	KITCHEN HOOD
KIT	KITCHEN
L	ANGLE
LBS	LABORATORY
LAM	LAMINATED
LAV	LAVATORY
LBR	LUMBER
LDG	LOADING
LF	LINEAR FOOT
LG	LENGTH (LONG)
LG	LAMINATED GLASS
LN	LINEAR
LNO	LINOLEUM
LKR	LOCKER
LOC	LOCATION
LONG	LONGITUDINAL
LSC	LIFE SAFETY CODE
LVT	LIGHTING
LV	COVER
LVT	LUXURY VINYL TILE
MAG	MAGNETIC
MAINT	MAINTENANCE
MAN	MANUAL
MAS	MASONRY
MATL	MATERIAL
MB	MOP BASIN
MBD	MARKER BOARD
MBH	MOP/BROOM HOLDER
MC	MEDICINE CABINET
MEMB	MEMBRANE
MH	MANHOLE
MHS	MIRROR WITH SHELF
MTD	MOUNTED
MTG	MOUNTING
MUL	MULLION
NC	NOISE CRITERIA
NFPA	NATIONAL FIRE PROTECTION ASSOCIATION
NOM	NOMINAL
O to O	OUT TO OUT
OK	OVERALL
OFCI	OWNER FURNISHED CONTRACTOR INSTALLED
OFF	OFFICE
OFOI	OWNER FURNISHED OWNER INSTALLED
OH	OPERATIONAL SITE HAND OPENING(S)
OPG(S)	OPERATIONAL SAFETY AND HEALTH ADMINISTRATION
OTB	OPEN TO BELOW
OVFL	OVERFLOW
P	PAINT
PAN B	PANIC BOLT
PB	PARTICLE BOARD
PC	PRECAST CONCRETE
PCD	PAPER DISPENSER
PCT	PORCELAIN CERAMIC TILE
PD	PANIC DEVICE
PERF	PERFORATED
PERP	PERPENDICULAR
PG	PATTERN GLASS
PIC	PORTABLE INSTRUMENT CONNECTION
PIG	PATTERN INSULATING GLASS
PL	PLATE
PL	PROFIC LINE
PLAM	PLASTIC LAMINATE
PLBG	PLUMBING
PR	PAIR
PREFAB	PREFABRICATED
PROJ	PROJECTOR (ICON)
PS	PROJECTION SCREEN
PT	POINT
PTD	POINT OF TANGENCY
PTD	PAPER TOWEL DISPENSER
PTDR	COMBINATION TOWEL DISPENSER/RECEPTACLE
PTN	PARTITION
PVC	POLYVINYL CHLORIDE
PWL	SOUND POWER LEVEL
QT	QUARRY TILE
QTR RND	QUARTER ROUND
R	RISER
RAD	RADIUS
RB	RUBBER BASE
RC	REMOTE CONTROL
RCP	REFLECTED CEILING PLAN
RD	ROOF DRAIN
REF	REFERENCE
REFL	REFLECTED
REM	REMOVABLE
RESIL	RESILIENT
RF	RESILIENT FLOORING
RF	RUBBER FLOOR
RFM	RECESSED FLOOR MAT
RH	ROBE HOOK
RKC	ROUGH IN AND CONNECT
S	SINK
SAT	SPRAYED ACOUSTIC TREATMENT
SAW	SOUND ABSORBING WALL UNITS
SB	SPRASH BLOCK
SC	SOLID CORE
SC	SHOWER CURTAIN
SCD	SEAT COVER DISPENSER
SCH	SHOWER CURTAIN HOOK
SCR	SHOWER CURTAIN ROD
SCT	STRUCTURAL CLAY TILE


GENERAL SYMBOLS

DETAIL NUMBER	DETAIL NUMBER	EARTH
CROSS REFERENCE SHEET NUMBER	CROSS REFERENCE SHEET NUMBER	GRAVEL
BUILDING ELEVATION	BUILDING ELEVATION	SAND
INTERIOR ELEVATION	INTERIOR ELEVATION	CONCRETE
WALL SECTION	WALL SECTION	PRECAST CONCRETE
DETAIL REFERENCE	DETAIL REFERENCE	STEEL
BUILDING SECTION	BUILDING SECTION	STONE
SHEET NOTE	SHEET NOTE	CONCRETE MASONRY UNIT
REFERENCE KEYNOTE	REFERENCE KEYNOTE	BRICK VENEER
COLUMN GRID LINE		












2 BUILDING B FLOOR PLAN  
SCALE: 1/8" = 1'-0"




3 BUILDING C FLOOR PLAN  
SCALE: 1/8" = 1'-0"




4 BUILDING D FLOOR PLAN  
SCALE: 1/8" = 1'-0"



5 BUILDING E FLOOR PLAN  
SCALE: 1/8" = 1'-0"



1 MECH. ANCHORAGE AT CONC. CURB  
SCALE: 3" = 1'-0"



6 TYPICAL MECH. EQUIPMENT CONCRETE PAD AT (E) SLAB-ON-GRADE  
SCALE: 1 1/2" = 1'-0"

REFERENCE KEYNOTES



KEYNOTES	DESCRIPTION
D104	REMOVE (E) MECHANICAL EQUIP., EQUIP. CONC. PAD, & ITS ASSOCIATED PARTS. SEE MECHANICAL & PLUMBING DWG.
E209	LINE OF (E) ROOF ABOVE SHOWN DASHED.
N158	NEW MECHANICAL EQUIPMENT ON NEW 6" THK. TOP LEVELED CONCRETE PAD & PLACED 6" FROM EDGE OF PAD. SEE MECH DWGS.
N212	REPLACE (E) INFILL PANEL AT CONDENSER UNIT PENETRATIONS WITH GLAZING TO MATCH ADJACENT. PAINT FRAME TO MATCH ADJACENT.

GENERAL ARCHITECTURAL NOTES

- ALL INTERIOR CMU WALLS SHALL REMAIN U.N.O. BEARING MASONRY WALLS.
- FURNISH AND INSTALL FIRE-TREATED WOOD BLOCKING OR METAL BACKING PLATE IN METAL STUD PARTITIONS FOR THE PROPER ANCHORAGE OF ALL WALL ATTACHED ITEMS, I.E. TOILET ACCESSORIES, CASEWORK, MILLWORK, WALL-MOUNTED FIXTURES, MARKER BOARDS, TACK BOARDS, DOOR STOPS, AUDIO VISUAL BRACKETS, AND OTHER WALL ATTACHED ITEMS WHERE OCCURS.
- GYPSON BOARD SURFACES SHALL BE ISOLATED WITH CONTROL JOINTS WHERE SHOWN ON DRAWINGS AND AS DESCRIBED IN THE SPECIFICATIONS.
- MASONRY CONTROL JOINTS (CJ) AND CONTROL JOINTS ABOVE (CA) SHALL BE LOCATED AS SHOWN ON THE FLOOR PLAN AND BUILDING ELEVATIONS, AND WHERE LARGE PLUMBING VENTS OR RISERS OCCUR IN SINGLE WYTHE MASONRY WALLS, AND WHERE MASONRY WALLS BEARING ON THE CONCRETE FLOOR SLAB ABUT MASONRY WALLS BEARING ON CONCRETE FOOTINGS OR AS INDICATED ON DRAWINGS.
- SCRIBE GYPSON WALL BOARD OF WALLS AND PARTITIONS TO IRREGULARITIES OF DECK ABOVE. SEAL TIGHTLY AROUND ALL PENETRATIONS.
- MAINTAIN (E) SEISMIC BRACING FOR SUSPENDED CEILING OR AS SHOWN ON THE DRAWINGS.

DEMOLITION GENERAL NOTES

- DEMOLITION NOTES APPLY TO ALL DEMOLITION SHEETS.
- THE CONTRACTOR SHALL:
- COORDINATE ALL DEMOLITION AND PHASING EFFORTS WITH THE ARCHITECT AND OWNER'S REPRESENTATIVE. EVERY EFFORT SHALL BE MADE TO MINIMIZE DISRUPTION OF OWNER'S OPERATIONS. EXCESSIVE NOISE OR VIBRATION SHALL BE PRE-APPROVED AND COORDINATED WITH THE OWNER'S REPRESENTATIVE. IN ALL CASES, PROVISIONS SHALL BE MADE FOR USER'S SAFETY.
  - COORDINATE ANY DISRUPTION OF UTILITY SERVICES WITH THE OWNER AND AS SPECIFIED.
  - CONSTRUCT TEMPORARY CONSTRUCTION PARTITIONS WITHIN THE EXISTING BUILDING WHICH OFFER A ONE-HOUR ENCLOSURE TO ISOLATE ANY DEMOLITION/CONSTRUCTION WORK FROM THE GENERAL PUBLIC AND AS DEEMED NECESSARY BY THE OWNER AND CODE OFFICIAL HAVING JURISDICTION. COORDINATE LOCATIONS WITH THE OWNER AND MAINTAIN MEANS OF EGRESS THROUGHOUT THE WORK.
  - MAINTAIN A SECURE, WEATHER-TIGHT ENCLOSURE AT ALL TIMES.
  - VERIFY ALL EXISTING CONDITIONS, DIMENSIONS AND ELEVATIONS AND NOTIFY THE ARCHITECT OF ANY DISCREPANCIES.
  - REMOVE IN THEIR ENTIRETY ALL EXISTING WALLS, DOORS, MILLWORK, PLUMBING FIXTURES, CEILING, SOFFITS, MARKERBOARDS, AND OTHER ITEMS, AS REQUIRED TO EXECUTE THE DEMOLITION/CONSTRUCTION WORK DESCRIBED BY THE DRAWINGS.
  - THE OWNER SHALL RESERVE THE RIGHT TO SALVAGE ANY MATERIALS.
  - PROVIDE PROTECTION FOR ALL EXISTING BUILDING MATERIALS AND EQUIPMENT FROM DAMAGE DUE TO ANY DEMOLITION OR CONSTRUCTION-RELATED INCIDENT PERFORMED UNDER THIS CONTRACT.
  - REPAIR OR REPLACE ITEMS THAT ARE DAMAGED AS A RESULT OF DEMOLITION OR CONSTRUCTION TO MATCH EXISTING FINISH AND/OR CONDITION.
  - EXISTING MATERIALS SHALL NOT BE REUSED UNLESS NOTED OTHERWISE OR AS AUTHORIZED BY ARCHITECT.
  - VERIFY AND MAINTAIN THE LOCATION OF EXISTING POWER, COMMUNICATION AND DATA CABLES TO PREVENT INTERRUPTION OF THEIR SERVICE.
  - PATCH FLOOR, WALL AND CEILING PENETRATIONS RESULTING FROM REMOVAL OR RE-ROUTING OF NEW OR EXISTING PIPING, DUCTWORK, CONDUIT, AND OTHER ITEMS, AS REQUIRED TO MAINTAIN FIRE-RESISTANCE-RATED SEPARATIONS. FINISH AS REQUIRED FOR NEW OR EXISTING ADJACENT SURFACES.
  - CAP ALL DISCONNECTED MECHANICAL PIPING LINES WITHIN THE WALL OR FLOOR. PATCH AND FINISH AS REQUIRED TO MATCH NEW OR EXISTING ADJACENT SURFACES.
  - SEE MECHANICAL AND ELECTRICAL DRAWINGS AND NOTES FOR FURTHER SEQUENCING AND SCOPE OF WORK.
  - AVOID ANY DISTURBANCE OF SOILS WITHIN THE ZONE OF INFLUENCE AROUND EXISTING FOOTINGS AND FLOOR SLABS AS DIRECTED BY GEOTECHNICAL ENGINEER.
  - WHERE CMU WALLS ARE INDICATED TO BE REMOVED, PREPARE ADJACENT WALLS TO RECEIVE NEW PATCH/FINISH BY REMOVING CMU IN TOOTH-IN PATTERN BOTH SIDES OF DEMOLITION FOR CONTRACTOR TO TOOTH-IN NEW CMU PATCHES.
  - WHERE PLASTER/STUD WALLS ARE INDICATED TO BE REMOVED, PREPARE ADJACENT WALLS TO RECEIVE NEW PATCH/FINISH BY SAWCUTTING ADJACENT PLASTER FINISH A MINIMUM OF 1'-0" BEYOND DEMOLITION.



GROVECENTER ELEM. SCHOOL  
COVID 19 - COVINA VALLEY DISTRICT HVAC REPLACEMENT  
775 N LARK ELLIEN AVE. WEST COVINA, CA 91791

100% CONSTRUCTION DOCUMENTS  
11/08/2022 REVISIONS


75-22605-00  
DSA A#03-122225  
DSA File #: 19-25

BUILDING BCD, AND BUILDING E FLOOR PLANS


A1.1A

Autodesk Docs/75-22605-00\_CVUSD - District Wide HVAC Replacement/75-22605-00\_CVUSD\_Grovecenter ES\_A1\_2022.rvt 11/22/2022 10:10:51 AM





1 BUILDING F FLOOR PLAN  
A1.1B SCALE: 1/8" = 1'-0"



2 BUILDING G FLOOR PLAN  
A1.1B SCALE: 1/8" = 1'-0"

REFERENCE KEYNOTES

KEYNOTES	
D104	REMOVE (E) MECHANICAL EQUIP., EQUIP. CONC. PAD, & ITS ASSOCIATED PARTS. SEE MECHANICAL & PLUMBING DWG.
E209	LINE OF (E) ROOF ABOVE SHOWN DASHED.
N212	REPLACE (E) INFILL PANEL AT CONDENSER UNIT PENETRATIONS WITH GLAZING TO MATCH ADJACENT. PAINT FRAME TO MATCH ADJACENT.

GENERAL ARCHITECTURAL NOTES

- ALL INTERIOR CMU WALLS SHALL REMAIN U.N.O. BEARING MASONRY WALLS.
- SEE STRUCTURAL DRAWINGS FOR BRACING OF NON-LOAD BEARING MASONRY WALLS.
- FURNISH AND INSTALL FIRE-TREATED WOOD BLOCKING OR METAL BACKING PLATE IN METAL STUD PARTITIONS FOR THE PROPER ANCHORAGE OF ALL WALL ATTACHED ITEMS, I.E. TOILET ACCESSORIES, CASEWORK, MILLWORK, WALL-MOUNTED FIXTURES, MARKER BOARDS, TACK BOARDS, DOOR STOPS, AUDIO VISUAL BRACKETS, AND OTHER WALL ATTACHED ITEMS WHERE OCCURS.
- GYPSON BOARD SURFACES SHALL BE ISOLATED WITH CONTROL JOINTS WHERE SHOWN ON DRAWINGS AND AS DESCRIBED IN THE SPECIFICATIONS.
- MASONRY CONTROL JOINTS (CJ) AND CONTROL JOINTS ABOVE (CA) SHALL BE LOCATED AS SHOWN ON THE FLOOR PLAN AND BUILDING ELEVATIONS, AND WHERE LARGE PLUMBING VENTS OR RISERS OCCUR IN SINGLE WYTHE MASONRY WALLS, AND WHERE MASONRY WALLS BEARING ON THE CONCRETE FLOOR SLAB ABUT MASONRY WALLS BEARING ON CONCRETE FOOTINGS OR AS INDICATED ON DRAWINGS.
- SCRIBE GYPSON WALL BOARD OF WALLS AND PARTITIONS TO IRREGULARITIES OF DECK ABOVE. SEAL TIGHTLY AROUND ALL PENETRATIONS.
- MAINTAIN (E) SEISMIC BRACING FOR SUSPENDED CEILINGS OR AS SHOWN ON THE DRAWINGS.

DEMOLITION GENERAL NOTES

- DEMOLITION NOTES APPLY TO ALL DEMOLITION SHEETS.
- THE CONTRACTOR SHALL:
- COORDINATE ALL DEMOLITION AND PHASING EFFORTS WITH THE ARCHITECT AND OWNER'S REPRESENTATIVE. EVERY EFFORT SHALL BE MADE TO MINIMIZE DISRUPTION OF OWNER'S OPERATIONS. EXCESSIVE NOISE OR VIBRATION SHALL BE PRE-APPROVED AND COORDINATED WITH THE OWNER'S REPRESENTATIVE. IN ALL CASES, PROVISIONS SHALL BE MADE FOR USER'S SAFETY.
  - COORDINATE ANY DISRUPTION OF UTILITY SERVICES WITH THE OWNER AND AS SPECIFIED.
  - CONSTRUCT TEMPORARY CONSTRUCTION PARTITIONS WITHIN THE EXISTING BUILDING WHICH OFFER A ONE-HOUR ENCLOSURE TO ISOLATE ANY DEMOLITION/CONSTRUCTION WORK FROM THE GENERAL PUBLIC AND AS DEEMED NECESSARY BY THE OWNER AND CODE OFFICIAL HAVING JURISDICTION. COORDINATE LOCATIONS WITH THE OWNER AND MAINTAIN MEANS OF EGRESS THROUGHOUT THE WORK.
  - MAINTAIN A SECURE, WEATHER-TIGHT ENCLOSURE AT ALL TIMES.
  - VERIFY ALL EXISTING CONDITIONS, DIMENSIONS AND ELEVATIONS AND NOTIFY THE ARCHITECT OF ANY DISCREPANCIES.
  - REMOVE IN THEIR ENTIRETY ALL EXISTING WALLS, DOORS, MILLWORK, PLUMBING FIXTURES, CEILINGS, SOFFITS, MARKERBOARDS, AND OTHER ITEMS, AS REQUIRED TO EXECUTE THE DEMOLITION/CONSTRUCTION WORK DESCRIBED BY THE DRAWINGS.
  - THE OWNER SHALL RESERVE THE RIGHT TO SALVAGE ANY MATERIALS.
  - PROVIDE PROTECTION FOR ALL EXISTING BUILDING MATERIALS AND EQUIPMENT FROM DAMAGE DUE TO ANY DEMOLITION OR CONSTRUCTION-RELATED INCIDENT PERFORMED UNDER THIS CONTRACT.
  - REPAIR OR REPLACE ITEMS THAT ARE DAMAGED AS A RESULT OF DEMOLITION OR CONSTRUCTION TO MATCH EXISTING FINISH AND/OR CONDITION.
  - EXISTING MATERIALS SHALL NOT BE REUSED UNLESS NOTED OTHERWISE OR AS AUTHORIZED BY ARCHITECT.
  - VERIFY AND MAINTAIN THE LOCATION OF EXISTING POWER, COMMUNICATION AND DATA CABLES TO PREVENT INTERRUPTION OF THEIR SERVICE.
  - PATCH FLOOR, WALL AND CEILING PENETRATIONS RESULTING FROM REMOVAL OR RE-ROUTING OF NEW OR EXISTING PIPING, DUCTWORK, CONDUIT, AND OTHER ITEMS, AS REQUIRED TO MAINTAIN FIRE-RESISTANCE-RATED SEPARATIONS. FINISH AS REQUIRED FOR NEW OR EXISTING ADJACENT SURFACES.
  - CAP ALL DISCONNECTED MECHANICAL PIPING LINES WITHIN THE WALL OR FLOOR. PATCH AND FINISH AS REQUIRED TO MATCH NEW OR EXISTING ADJACENT SURFACES.
  - SEE MECHANICAL AND ELECTRICAL DRAWINGS AND NOTES FOR FURTHER SEQUENCING AND SCOPE OF WORK.
  - AVOID ANY DISTURBANCE OF SOILS WITHIN THE ZONE OF INFLUENCE AROUND EXISTING FOOTINGS AND FLOOR SLABS AS DIRECTED BY GEOTECHNICAL ENGINEER.
  - WHERE CMU WALLS ARE INDICATED TO BE REMOVED, PREPARE ADJACENT WALLS TO RECEIVE NEW PATCH/FINISH BY REMOVING CMU IN TOOTH-IN PATTERN BOTH SIDES OF DEMOLITION FOR CONTRACTOR TO TOOTH-IN NEW CMU PATCHES.
  - WHERE PLASTER/STUD WALLS ARE INDICATED TO BE REMOVED, PREPARE ADJACENT WALLS TO RECEIVE NEW PATCH/FINISH BY SAWCUTTING ADJACENT PLASTER FINISH A MINIMUM OF 1'-0" BEYOND DEMOLITION.



GROVECENTER ELEM. SCHOOL  
COVID 19 - COVINA VALLEY DISTRICT HVAC REPLACEMENT  
775 N LARK ELLIEN AVE. WEST COVINA, CA 91791

100% CONSTRUCTION DOCUMENTS  
11/08/2022 REVISIONS


75-22605-00  
DSA A#03-122225  
DSA File #: 19-25

BUILDING F AND BUILDING G FLOOR PLANS


A1.1B

Autodesk Docs/75-22605-00\_CVUSD - District Wide HVAC Replacement/75-22605-00\_CVUSD\_Grovecenter ES\_A1\_2023.rvt 11/2/2022 10:10:51 AM







2 BUILDING B ROOF PLAN  
A1.3A SCALE: 1/8" = 1'-0"



3 BUILDING C ROOF PLAN  
A1.3A SCALE: 1/8" = 1'-0"



4 BUILDING D ROOF PLAN  
A1.3A SCALE: 1/8" = 1'-0"



5 BUILDING E ROOF PLAN  
A1.3A SCALE: 1/8" = 1'-0"

REFERENCE KEYNOTES

KEYNOTES	
E210	LINE OF (E) BLDG BELOW SHOWN DASHED
N400	NEW FREESTANDING METAL GUARDRAIL SYSTEM, SEE SUPPLIER FOR ANCHORAGE AND SPEC SECTION 07 22 00
N403	(N) MECHANICAL UNITS ATTACHED TO THE (E) UNIT CURB. SEE MECHANICAL DRAWING SHEET M1.3B & M1.3D

ROOF PLAN GENERAL NOTES

- A. (E) ROOF CURBS TO REMAIN U.N.O. SEE MECHANICAL DRAWINGS SHEET M1.3C FOR ADDITIONAL INFORMATION.
- B. COORDINATE THE SIZE AND LOCATION OF WALL PENETRATIONS FOR MECHANICAL AND ELECTRICAL EQUIPMENT. REFER TO MECHANICAL AND ELECTRICAL DRAWINGS FOR PENETRATIONS NOT SHOWN ON THIS DRAWING.
- C. (E) DRAINS, CURBS, VENTS AND STACKS TO REMAIN.

DEMOLITION GENERAL NOTES

- DEMOLITION NOTES APPLY TO ALL DEMOLITION SHEETS.
- THE CONTRACTOR SHALL:
- A. COORDINATE ALL DEMOLITION AND PHASING EFFORTS WITH THE ARCHITECT AND OWNER'S REPRESENTATIVE. EVERY EFFORT SHALL BE MADE TO MINIMIZE DISRUPTION OF OWNER'S OPERATIONS. EXCESSIVE NOISE OR VIBRATION SHALL BE PRE-APPROVED AND COORDINATED WITH THE OWNER'S REPRESENTATIVE. IN ALL CASES, PROVISIONS SHALL BE MADE FOR USER'S SAFETY.
  - B. COORDINATE ANY DISRUPTION OF UTILITY SERVICES WITH THE OWNER AND AS SPECIFIED.
  - C. CONSTRUCT TEMPORARY CONSTRUCTION PARTITIONS WITHIN THE EXISTING BUILDING WHICH OFFER A ONE-HOUR ENCLOSURE TO ISOLATE ANY DEMOLITION/CONSTRUCTION WORK FROM THE GENERAL PUBLIC AND AS DEEMED NECESSARY BY THE OWNER AND CODE OFFICIAL HAVING JURISDICTION. COORDINATE LOCATIONS WITH THE OWNER AND MAINTAIN MEANS OF EGRESS THROUGHOUT THE WORK.
  - D. MAINTAIN A SECURE, WEATHER-TIGHT ENCLOSURE AT ALL TIMES.
  - E. VERIFY ALL EXISTING CONDITIONS, DIMENSIONS AND ELEVATIONS AND NOTIFY THE ARCHITECT OF ANY DISCREPANCIES.
  - F. REMOVE IN THEIR ENTIRETY ALL EXISTING WALLS, DOORS, MILLWORK, PLUMBING FIXTURES, CEILING, SOFFITS, MARKERS/BARDS, AND OTHER ITEMS, AS REQUIRED TO EXECUTE THE DEMOLITION/CONSTRUCTION WORK DESCRIBED BY THE DRAWINGS.
  - G. THE OWNER SHALL RESERVE THE RIGHT TO SALVAGE ANY MATERIALS.
  - H. PROVIDE PROTECTION FOR ALL EXISTING BUILDING MATERIALS AND EQUIPMENT FROM DAMAGE DUE TO ANY DEMOLITION OR CONSTRUCTION-RELATED INCIDENT PERFORMED UNDER THIS CONTRACT.
  - I. REPAIR OR REPLACE ITEMS THAT ARE DAMAGED AS A RESULT OF DEMOLITION OR CONSTRUCTION TO MATCH EXISTING FINISH AND/OR CONDITION.
  - J. EXISTING MATERIALS SHALL NOT BE REUSED UNLESS NOTED OTHERWISE OR AS AUTHORIZED BY ARCHITECT.
  - K. VERIFY AND MAINTAIN THE LOCATION OF EXISTING POWER, COMMUNICATION AND DATA CABLES TO PREVENT INTERRUPTION OF THEIR SERVICE.
  - L. PATCH FLOOR, WALL AND CEILING PENETRATIONS RESULTING FROM REMOVAL OR RE-ROUTING OF NEW OR EXISTING PIPING, DUCTWORK, CONDUIT, AND OTHER ITEMS, AS REQUIRED TO MAINTAIN FIRE-RESISTANCE-RATED SEPARATIONS. FINISH AS REQUIRED FOR NEW OR EXISTING ADJACENT SURFACES.
  - M. CAP ALL DISCONNECTED MECHANICAL PIPING LINES WITHIN THE WALL OR FLOOR. PATCH AND FINISH AS REQUIRED TO MATCH NEW OR EXISTING ADJACENT SURFACES.
  - N. SEE MECHANICAL AND ELECTRICAL DRAWINGS AND NOTES FOR FURTHER SEQUENCING AND SCOPE OF WORK.
  - O. AVOID ANY DISTURBANCE OF SOILS WITHIN THE ZONE OF INFLUENCE AROUND EXISTING FOOTINGS AND FLOOR SLABS AS DIRECTED BY GEOTECHNICAL ENGINEER.
  - P. WHERE CMU WALLS ARE INDICATED TO BE REMOVED, PREPARE ADJACENT WALLS TO RECEIVE NEW PATCHFINISH BY REMOVING CMU IN TOOTH-IN PATTERN BOTH SIDES OF DEMOLITION FOR CONTRACTOR TO TOOTH-IN NEW CMU PATCHES.
  - Q. WHERE PLASTER/STUD WALLS ARE INDICATED TO BE REMOVED, PREPARE ADJACENT WALLS TO RECEIVE NEW PATCHFINISH BY SAWCUTTING ADJACENT PLASTER FINISH A MINIMUM OF 1'-0" BEYOND DEMOLITION.



GROVECENTER ELEM. SCHOOL  
COVID 19 - COVINA VALLEY DISTRICT HVAC REPLACEMENT  
775 N. LARK ELLIEN AVE. WEST COVINA, CA 91791


100% CONSTRUCTION DOCUMENTS  
11/08/2022 REVISIONS

75-22605-00  
DSA A#03-122225  
DSA File #: 19-25


BUILDING BCD, AND BUILDING E ROOF PLANS

A1.3A





2 BUILDING F ROOF PLAN  
A1.3B / SCALE: 1/8" = 1'-0"



1 BUILDING G ROOF PLAN  
A1.3B / SCALE: 1/8" = 1'-0"

**REFERENCE KEYNOTES**


E210	LINE OF (E) BLDG BELOW SHOWN DASHED
N400	NEW FREESTANDING METAL GUARDRAIL SYSTEM, SEE SUPPLIER FOR ANCHORAGE AND SPEC SECTION 07 72 00
N403	(N) MECHANICAL UNITS ATTACHED TO THE (E) UNIT CURB, SEE MECHANICAL DRAWING SHEET M1.3B & M1.3D

**ROOF PLAN GENERAL NOTES**

- A. (E) ROOF CURBS TO REMAIN U.N.O., SEE MECHANICAL DRAWINGS SHEET M1.3C FOR ADDITIONAL INFORMATION.
- B. COORDINATE THE SIZE AND LOCATION OF WALL PENETRATIONS FOR MECHANICAL AND ELECTRICAL EQUIPMENT, REFER TO MECHANICAL AND ELECTRICAL DRAWINGS FOR PENETRATIONS NOT SHOWN ON THIS DRAWING.
- C. (E) DRAINS, CURBS, VENTS AND STACKS TO REMAIN.

**DEMOLITION GENERAL NOTES**

- DEMOLITION NOTES APPLY TO ALL DEMOLITION SHEETS.
- THE CONTRACTOR SHALL:
- A. COORDINATE ALL DEMOLITION AND PHASING EFFORTS WITH THE ARCHITECT AND OWNER'S REPRESENTATIVE. EVERY EFFORT SHALL BE MADE TO MINIMIZE DISRUPTION OF OWNER'S OPERATIONS. EXCESSIVE NOISE OR VIBRATION SHALL BE PRE-APPROVED AND COORDINATED WITH THE OWNER'S REPRESENTATIVE. IN ALL CASES, PROVISIONS SHALL BE MADE FOR USER'S SAFETY.
  - B. COORDINATE ANY DISRUPTION OF UTILITY SERVICES WITH THE OWNER AND AS SPECIFIED.
  - C. CONSTRUCT TEMPORARY CONSTRUCTION PARTITIONS WITHIN THE EXISTING BUILDING WHICH OFFER A ONE-HOUR ENCLOSURE TO ISOLATE ANY DEMOLITION/CONSTRUCTION WORK FROM THE GENERAL PUBLIC AND AS DEEMED NECESSARY BY THE OWNER AND CODE OFFICIAL HAVING JURISDICTION. COORDINATE LOCATIONS WITH THE OWNER AND MAINTAIN MEANS OF EGRESS THROUGHOUT THE WORK.
  - D. MAINTAIN A SECURE, WEATHER-TIGHT ENCLOSURE AT ALL TIMES.
  - E. VERIFY ALL EXISTING CONDITIONS, DIMENSIONS AND ELEVATIONS AND NOTIFY THE ARCHITECT OF ANY DISCREPANCIES.
  - F. REMOVE IN THEIR ENTIRETY ALL EXISTING WALLS, DOORS, MILLWORK, PLUMBING FIXTURES, CEILING, SOFFITS, MARKERS/BARDS, AND OTHER ITEMS, AS REQUIRED TO EXECUTE THE DEMOLITION/CONSTRUCTION WORK DESCRIBED BY THE DRAWINGS.
  - G. THE OWNER SHALL RESERVE THE RIGHT TO SALVAGE ANY MATERIALS.
  - H. PROVIDE PROTECTION FOR ALL EXISTING BUILDING MATERIALS AND EQUIPMENT FROM DAMAGE DUE TO ANY DEMOLITION OR CONSTRUCTION-RELATED INCIDENT PERFORMED UNDER THIS CONTRACT.
  - I. REPAIR OR REPLACE ITEMS THAT ARE DAMAGED AS A RESULT OF DEMOLITION OR CONSTRUCTION TO MATCH EXISTING FINISH AND/OR CONDITION.
  - J. EXISTING MATERIALS SHALL NOT BE REUSED UNLESS NOTED OTHERWISE OR AS AUTHORIZED BY ARCHITECT.
  - K. VERIFY AND MAINTAIN THE LOCATION OF EXISTING POWER, COMMUNICATION AND DATA CABLES TO PREVENT INTERRUPTION OF THEIR SERVICE.
  - L. PATCH FLOOR, WALL AND CEILING PENETRATIONS RESULTING FROM REMOVAL OR RE-ROUTING OF NEW OR EXISTING PIPING, DUCTWORK, CONDUIT, AND OTHER ITEMS, AS REQUIRED TO MAINTAIN FIRE-RESISTANCE-RATED SEPARATIONS. FINISH AS REQUIRED FOR NEW OR EXISTING ADJACENT SURFACES.
  - M. CAP ALL DISCONNECTED MECHANICAL PIPING LINES WITHIN THE WALL OR FLOOR. PATCH AND FINISH AS REQUIRED TO MATCH NEW OR EXISTING ADJACENT SURFACES.
  - N. SEE MECHANICAL AND ELECTRICAL DRAWINGS AND NOTES FOR FURTHER SEQUENCING AND SCOPE OF WORK.
  - O. AVOID ANY DISTURBANCE OF SOILS WITHIN THE ZONE OF INFLUENCE AROUND EXISTING FOOTINGS AND FLOOR SLABS AS DIRECTED BY GEOTECHNICAL ENGINEER.
  - P. WHERE CMU WALLS ARE INDICATED TO BE REMOVED, PREPARE ADJACENT WALLS TO RECEIVE NEW PATCH/FINISH BY REMOVING CMU IN TOOTH-IN PATTERN BOTH SIDES OF DEMOLITION FOR CONTRACTOR TO TOOTH-IN NEW CMU PATCHES.
  - Q. WHERE PLASTER/STUD WALLS ARE INDICATED TO BE REMOVED, PREPARE ADJACENT WALLS TO RECEIVE NEW PATCH/FINISH BY SAWCUTTING ADJACENT PLASTER FINISH A MINIMUM OF 1'-0" BEYOND DEMOLITION.



3 HVAC ROOF GUARDRAIL - WD FRAMING  
A1.3B / SCALE: 1 1/2" = 1'-0"

**DLR Group**  
© DLR Group

**JESSIE MILLER**  
No. C-52306  
10/31/2023  
STATE OF CALIFORNIA

**USG**

**GROVECENTER ELEM. SCHOOL**  
COVID 19 - COVINA VALLEY DISTRICT HVAC REPLACEMENT  
775 N LARK ELLIEN AVE. WEST COVINA, CA 91791


100% CONSTRUCTION DOCUMENTS  
11/08/2022 REVISIONS

75-22605-00  
DSA A#03-122225  
DSA File #: 19-25


**BUILDING F AND BUILDING G ROOF PLANS**

**A1.3B**







2 BUILDING B REFLECTED CEILING PLAN  
A3.1A SCALE: 1/8" = 1'-0"



3 BUILDING C REFLECTED CEILING PLAN  
A3.1A SCALE: 1/8" = 1'-0"



4 BUILDING D REFLECTED CEILING PLAN  
A3.1A SCALE: 1/8" = 1'-0"



5 BUILDING E REFLECTED CEILING PLAN  
A3.1A SCALE: 1/8" = 1'-0"

**REFERENCE KEYNOTES**

D13	REMOVE (E) CEILING MOUNTED FAN COIL UNIT - SEE MECHANICAL DRAWINGS
N212	REPLACE (E) INFILL PANEL AT CONDENSER UNIT PENETRATIONS WITH GLAZING TO MATCH ADJACENT. PAINT FRAME TO MATCH ADJACENT

**REFLECTED CEILING PLAN GENERAL NOTES**

- A. REFLECTED CEILING PLAN GENERAL NOTES APPLY TO ALL REFLECTED CEILING PLAN SHEETS
- B. ALL CEILING GRIDS/PANELS SHALL BE CENTERED IN EACH ROOM UNLESS NOTED OTHERWISE.
- C. (E) CEILING HEIGHTS ARE TO REMAIN U.N.O. REFLECTED CEILING PLANS ARE MEASURED FROM THE FINISHED FLOOR OF THE ROOM.
- D. IN ACOUSTICAL CEILING PANELS WITH SCORE IN THE CENTER, CENTER DEVICES IN ONE HALF OF THE TILE. DO NOT LOCATE ON THE SCORE. FOR ACP WITH MULTIPLE SCORED PATTERNS, COORDINATE LOCATION WITH THE ARCHITECT.
- E. PROVIDE SUSPENSION SYSTEM AROUND ELECTRICAL FIXTURES, MECHANICAL GRILLES, DIFFUSERS, AND OTHER CEILING MOUNTED DEVICES AT ACOUSTICAL PANEL CEILINGS.
- F. ALL DIMENSIONS ON REFLECTED CEILING PLANS ARE ACTUAL AND ARE TO THE FOLLOWING UNLESS NOTED OTHERWISE.
  - a. FACE OF FINISHED WALL
  - b. FACE OF FINISHED BULKHEADS
  - c. CENTERLINE OF COLUMNS
  - d. CENTERLINE OF TEES
- G. IN AREAS WITH EXPOSED STRUCTURE CEILINGS, COORDINATE EXACT LOCATIONS OF MECHANICAL GRILLES, DIFFUSERS, DUCTWORK AND ELECTRICAL FIXTURES WITH EACH REPRESENTATIVE SUBCONTRACTOR.

**DEMOLITION GENERAL NOTES**

- DEMOLITION NOTES APPLY TO ALL DEMOLITION SHEETS.
- THE CONTRACTOR SHALL:
- A. COORDINATE ALL DEMOLITION AND PHASING EFFORTS WITH THE ARCHITECT AND OWNER'S REPRESENTATIVE. EVERY EFFORT SHALL BE MADE TO MINIMIZE DISRUPTION OF OWNER'S OPERATIONS. EXCESSIVE NOISE OR VIBRATION SHALL BE PRE-APPROVED AND COORDINATED WITH THE OWNER'S REPRESENTATIVE. IN ALL CASES, PROVISIONS SHALL BE MADE FOR USER'S SAFETY.
  - B. COORDINATE ANY DISRUPTION OF UTILITY SERVICES WITH THE OWNER AND AS SPECIFIED.
  - C. CONSTRUCT TEMPORARY CONSTRUCTION PARTITIONS WITHIN THE EXISTING BUILDING WHICH OFFER A ONE-HOUR ENCLOSURE TO ISOLATE ANY DEMOLITION/CONSTRUCTION WORK FROM THE GENERAL PUBLIC AND AS DEEMED NECESSARY BY THE OWNER AND CODE OFFICIAL HAVING JURISDICTION. COORDINATE LOCATIONS WITH THE OWNER AND MAINTAIN MEANS OF EGRESS THROUGHOUT THE WORK.
  - D. MAINTAIN A SECURE, WEATHER-TIGHT ENCLOSURE AT ALL TIMES.
  - E. VERIFY ALL EXISTING CONDITIONS, DIMENSIONS AND ELEVATIONS AND NOTIFY THE ARCHITECT OF ANY DISCREPANCIES.
  - F. REMOVE IN THEIR ENTIRETY ALL EXISTING WALLS, DOORS, MILLWORK, PLUMBING FIXTURES, CEILINGS, SOFFITS, MARKERS/BARDS, AND OTHER ITEMS, AS REQUIRED TO EXECUTE THE DEMOLITION/CONSTRUCTION WORK DESCRIBED BY THE DRAWINGS.
  - G. THE OWNER SHALL RESERVE THE RIGHT TO SALVAGE ANY MATERIALS.
  - H. PROVIDE PROTECTION FOR ALL EXISTING BUILDING MATERIALS AND EQUIPMENT FROM DAMAGE DUE TO ANY DEMOLITION OR CONSTRUCTION-RELATED INCIDENT PERFORMED UNDER THIS CONTRACT.
  - I. REPAIR OR REPLACE ITEMS THAT ARE DAMAGED AS A RESULT OF DEMOLITION OR CONSTRUCTION TO MATCH EXISTING FINISH AND/OR CONDITION.
  - J. EXISTING MATERIALS SHALL NOT BE REUSED UNLESS NOTED OTHERWISE OR AS AUTHORIZED BY ARCHITECT.
  - K. VERIFY AND MAINTAIN THE LOCATION OF EXISTING POWER, COMMUNICATION AND DATA CABLES TO PREVENT INTERRUPTION OF THEIR SERVICE.
  - L. PATCH FLOOR, WALL AND CEILING PENETRATIONS RESULTING FROM REMOVAL OR RE-ROUTING OF NEW OR EXISTING PIPING, DUCTWORK, CONDUIT, AND OTHER ITEMS, AS REQUIRED TO MAINTAIN FIRE-RESISTANCE-RATED SEPARATIONS. FINISH AS REQUIRED FOR NEW OR EXISTING ADJACENT SURFACES.
  - M. CAP ALL DISCONNECTED MECHANICAL PIPING LINES WITHIN THE WALL OR FLOOR. PATCH AND FINISH AS REQUIRED TO MATCH NEW OR EXISTING ADJACENT SURFACES.
  - N. SEE MECHANICAL AND ELECTRICAL DRAWINGS AND NOTES FOR FURTHER SEQUENCING AND SCOPE OF WORK.
  - O. AVOID ANY DISTURBANCE OF SOILS WITHIN THE ZONE OF INFLUENCE AROUND EXISTING FOOTINGS AND FLOOR SLABS AS DIRECTED BY GEOTECHNICAL ENGINEER.
  - P. WHERE CMU WALLS ARE INDICATED TO BE REMOVED, PREPARE ADJACENT WALLS TO RECEIVE NEW PATCH/FINISH BY REMOVING CMU IN TOOTH-IN PATTERN BOTH SIDES OF DEMOLITION FOR CONTRACTOR TO TOOTH-IN NEW CMU PATCHES.
  - Q. WHERE PLASTER/STUD WALLS ARE INDICATED TO BE REMOVED, PREPARE ADJACENT WALLS TO RECEIVE NEW PATCH/FINISH BY SAWCUTTING ADJACENT PLASTER FINISH A MINIMUM OF 1'-0" BEYOND DEMOLITION.

**DLR Group**  
© DLR Group

ARCHITECT  
JESSIE M. LEE  
No. C-52306  
10/31/2023  
STATE OF CALIFORNIA

USG

**GROVECENTER ELEM. SCHOOL**  
COVID 19 - COVINA VALLEY DISTRICT HVAC REPLACEMENT  
775 N. LARK ELLIEN AVE. WEST COVINA, CA 91791

100% CONSTRUCTION DOCUMENTS  
11/08/2022 REVISIONS


75-22605-00  
DSA A#03-122225  
DSA File #: 19-25

**BUILDING BCD, AND BUILDING E REFLECTED CEILING PLANS**


**A3.1A**

Autodesk Docs/75-22605-00\_CVUSD - District Wide HVAC Replacement/75-22605-00\_CVUSD - Grovescenter ES\_A3\_2023.rvt  
11/2/2022 10:10:53 AM





2 BUILDING F REFLECTED CEILING PLAN  
A3.1B SCALE: 1/8" = 1'-0"



1 BUILDING G REFLECTED CEILING PLAN  
A3.1B SCALE: 1/8" = 1'-0"

REFERENCE KEYNOTES

- D13 REMOVE (E) CEILING MOUNTED FAN COIL UNIT - SEE MECHANICAL DRAWINGS
- N212 REPLACE (E) IN-FILL PANEL AT CONDENSER UNIT PENETRATIONS WITH GLAZING TO MATCH ADJACENT. PAINT FRAME TO MATCH ADJACENT

REFLECTED CEILING PLAN GENERAL NOTES

- A. REFLECTED CEILING PLAN GENERAL NOTES APPLY TO ALL REFLECTED CEILING PLAN SHEETS
- B. ALL CEILING GRIDS/PANELS SHALL BE CENTERED IN EACH ROOM UNLESS NOTED OTHERWISE
- C. (E) CEILING HEIGHTS ARE TO REMAIN U.N.O. REFLECTED CEILING PLANS ARE MEASURED FROM THE FINISHED FLOOR OF THE ROOM
- D. IN ACOUSTICAL CEILING PANELS WITH SCORE IN THE CENTER CENTER DEVICES IN ONE HALF OF THE TILE. DO NOT LOCATE ON THE SCORE. FOR ACP WITH MULTIPLE SCORED PATTERNS, COORDINATE LOCATION WITH THE ARCHITECT
- E. PROVIDE SUSPENSION SYSTEM AROUND ELECTRICAL FIXTURES, MECHANICAL GRILLES, DIFFUSERS, AND OTHER CEILING MOUNTED DEVICES AT ACOUSTICAL PANEL CEILINGS
- F. ALL DIMENSIONS ON REFLECTED CEILING PLANS ARE ACTUAL AND ARE TO THE FOLLOWING UNLESS NOTED OTHERWISE:
  - a. FACE OF FINISHED WALL
  - b. FACE OF FINISHED BULKHEADS
  - c. CENTERLINE OF COLUMNS
  - d. CENTERLINE OF TEES
- G. IN AREAS WITH EXPOSED STRUCTURE CEILINGS, COORDINATE EXACT LOCATIONS OF MECHANICAL GRILLES, DIFFUSERS, DUCTWORK AND ELECTRICAL FIXTURES WITH EACH REPRESENTATIVE SUBCONTRACTOR.

DEMOLITION GENERAL NOTES

- DEMOLITION NOTES APPLY TO ALL DEMOLITION SHEETS.
- THE CONTRACTOR SHALL:
- A. COORDINATE ALL DEMOLITION AND PHASING EFFORTS WITH THE ARCHITECT AND OWNER'S REPRESENTATIVE. EVERY EFFORT SHALL BE MADE TO MINIMIZE DISRUPTION OF OWNER'S OPERATIONS. EXCESSIVE NOISE OR VIBRATION SHALL BE PRE-APPROVED AND COORDINATED WITH THE OWNER'S REPRESENTATIVE. IN ALL CASES, PROVISIONS SHALL BE MADE FOR USER'S SAFETY.
  - B. COORDINATE ANY DISRUPTION OF UTILITY SERVICES WITH THE OWNER AND AS SPECIFIED.
  - C. CONSTRUCT TEMPORARY CONSTRUCTION PARTITIONS WITHIN THE EXISTING BUILDING WHICH OFFER A ONE-HOUR ENCLOSURE TO ISOLATE ANY DEMOLITION/CONSTRUCTION WORK FROM THE GENERAL PUBLIC AND AS DEEMED NECESSARY BY THE OWNER AND CODE OFFICIAL HAVING JURISDICTION. COORDINATE LOCATIONS WITH THE OWNER AND MAINTAIN MEANS OF EGRESS THROUGHOUT THE WORK.
  - D. MAINTAIN A SECURE, WEATHER-TIGHT ENCLOSURE AT ALL TIMES.
  - E. VERIFY ALL EXISTING CONDITIONS, DIMENSIONS AND ELEVATIONS AND NOTIFY THE ARCHITECT OF ANY DISCREPANCIES.
  - F. REMOVE IN THEIR ENTIRETY ALL EXISTING WALLS, DOORS, MILLWORK, PLUMBING FIXTURES, CEILINGS, SOFFITS, MARKERS/BARDS, AND OTHER ITEMS, AS REQUIRED TO EXECUTE THE DEMOLITION/CONSTRUCTION WORK DESCRIBED BY THE DRAWINGS.
  - G. THE OWNER SHALL RESERVE THE RIGHT TO SALVAGE ANY MATERIALS.
  - H. PROVIDE PROTECTION FOR ALL EXISTING BUILDING MATERIALS AND EQUIPMENT FROM DAMAGE DUE TO ANY DEMOLITION OR CONSTRUCTION-RELATED INCIDENT PERFORMED UNDER THIS CONTRACT.
  - I. REPAIR OR REPLACE ITEMS THAT ARE DAMAGED AS A RESULT OF DEMOLITION OR CONSTRUCTION TO MATCH EXISTING FINISH AND/OR CONDITION.
  - J. EXISTING MATERIALS SHALL NOT BE REUSED UNLESS NOTED OTHERWISE OR AS AUTHORIZED BY ARCHITECT.
  - K. VERIFY AND MAINTAIN THE LOCATION OF EXISTING POWER, COMMUNICATION AND DATA CABLES TO PREVENT INTERRUPTION OF THEIR SERVICE.
  - L. PATCH FLOOR, WALL AND CEILING PENETRATIONS RESULTING FROM REMOVAL OR RE-ROUTING OF NEW OR EXISTING PIPING, DUCTWORK, CONDUIT, AND OTHER ITEMS, AS REQUIRED TO MAINTAIN FIRE-RESISTANCE-RATED SEPARATIONS. FINISH AS REQUIRED FOR NEW OR EXISTING ADJACENT SURFACES.
  - M. CAP ALL DISCONNECTED MECHANICAL PIPING LINES WITHIN THE WALL OR FLOOR. PATCH AND FINISH AS REQUIRED TO MATCH NEW OR EXISTING ADJACENT SURFACES.
  - N. SEE MECHANICAL AND ELECTRICAL DRAWINGS AND NOTES FOR FURTHER SEQUENCING AND SCOPE OF WORK.
  - O. AVOID ANY DISTURBANCE OF SOILS WITHIN THE ZONE OF INFLUENCE AROUND EXISTING FOOTINGS AND FLOOR SLABS AS DIRECTED BY GEOTECHNICAL ENGINEER.
  - P. WHERE CMU WALLS ARE INDICATED TO BE REMOVED, PREPARE ADJACENT WALLS TO RECEIVE NEW PATCH/FINISH BY REMOVING CMU IN TOOTH-IN PATTERN BOTH SIDES OF DEMOLITION FOR CONTRACTOR TO TOOTH-IN NEW CMU PATCHES.
  - Q. WHERE PLASTER/STUD WALLS ARE INDICATED TO BE REMOVED, PREPARE ADJACENT WALLS TO RECEIVE NEW PATCH/FINISH BY SAWCUTTING ADJACENT PLASTER FINISH A MINIMUM OF 1'-0" BEYOND DEMOLITION.



GROVECENTER ELEM. SCHOOL  
COVID 19 - COVINA VALLEY DISTRICT HVAC REPLACEMENT  
775 N LARK ELLIEN AVE WEST COVINA, CA 91791

100% CONSTRUCTION DOCUMENTS  
11/08/2022 REVISIONS

75-22605-00  
DSA A#03-122225  
DSA File #: 19-25

BUILDING F AND BUILDING G REFLECTED CEILING PLANS

A3.1B



ABBREVIATIONS

ABBREVIATIONS


SHEET INDEX

Table of abbreviations for mechanical symbols, including terms like DEMOLISHED, EXISTING, RELOCATED, etc.

Table of abbreviations for mechanical symbols, including terms like HIGH TEMPERATURE HOT WATER RETURN, HUMIDIFIER, HEATING VENTILATING UNIT, etc.

Table of sheet index, including Mechanical Symbols, Abbreviations & Notes, and Mechanical Demolition Plans.

GENERAL SYMBOLS



GENERAL NOTES

- 1 THE MECHANICAL CONTRACTOR SHALL BE RESPONSIBLE FOR FIELD VERIFYING... 2 WHERE FLOOR DRAINS OCCUR WITHIN THE LIMITS OF CONSTRUCTION...

GENERAL HVAC NOTES

- 1 CONDENSATE DRAINS SHALL BE SUPPLIED FOR ALL COOLING EQUIPMENT... 2 TEMPORARY, MOVABLE OR MOBILE EQUIPMENT THAT IS PERMANENTLY ATTACHED...

EQUIPMENT ANCHORAGE NOTE

MEP COMPONENT ANCHORAGE NOTE
ALL MECHANICAL, PLUMBING, AND ELECTRICAL COMPONENTS SHALL BE ANCHORED AND INSTALLED PER THE DETAILS ON THE DSA APPROVED CONSTRUCTION DOCUMENTS...

- 1. ALL PERMANENT EQUIPMENT AND COMPONENTS.
2. TEMPORARY, MOVABLE OR MOBILE EQUIPMENT THAT IS PERMANENTLY ATTACHED (E.G. HARD WIRED) TO THE BUILDING UTILITY SERVICES...

THE FOLLOWING MECHANICAL AND ELECTRICAL COMPONENTS SHALL BE POSITIVELY ATTACHED TO THE STRUCTURE BUT NEED NOT DEMONSTRATE DESIGN COMPLIANCE WITH THE REFERENCES NOTED ABOVE...

- A. COMPONENTS WEIGHING LESS THAN 400 POUNDS AND HAVING A CENTER OF MASS LOCATED 4 FEET OR LESS ABOVE THE ADJACENT FLOOR OR ROOF LEVEL... B. COMPONENTS WEIGHING LESS THAN 20 POUNDS...

THE ANCHORAGE OF ALL MECHANICAL, ELECTRICAL AND PLUMBING COMPONENTS SHALL BE SUBJECT TO THE APPROVAL OF THE DESIGN PROFESSIONAL IN GENERAL RESPONSIBLE CHARGE OR STRUCTURAL ENGINEER DELEGATED RESPONSIBILITY AND ACCEPTANCE BY DSA...

PIPING, DUCTWORK, AND ELECTRICAL DISTRIBUTION SYSTEM BRACING NOTE

PIPING, DUCTWORK, AND ELECTRICAL DISTRIBUTION SYSTEMS SHALL BE BRACED TO COMPLY WITH THE FORCES AND DISPLACEMENTS PRESCRIBED IN ASCE 7-16 SECTION 13.3 AS DEFINED IN ASCE 7-16 SECTIONS 13.6.5, 13.6.6, 13.6.7, 13.6.8, AND 2019 CBC, SECTIONS 1617A.1.24, 1617A.1.25 AND 1617A.1.26.

THE METHOD OF SHOWING BRACING AND ATTACHMENTS TO THE STRUCTURE FOR THE IDENTIFIED DISTRIBUTION SYSTEM ARE AS NOTED BELOW. WHEN BRACING AND ATTACHMENTS ARE BASED ON A PRE-APPROVED INSTALLATION GUIDE (E.G., OSHPD OPM FOR 2019 CBC OR LATER), COPIES OF THE BRACING SYSTEM INSTALLATION GUIDE OR MANUAL SHALL BE AVAILABLE ON THE JOBSITE PRIOR TO THE START OF AND DURING THE HANGING AND BRACING OF THE DISTRIBUTION SYSTEMS...

MECHANICAL PIPING (MP), MECHANICAL DUCTS (MD), PLUMBING PIPING (PP), ELECTRICAL DISTRIBUTION SYSTEMS (E).

- MP MD PP E OPTION 1: DETAILED ON THE APPROVED DRAWINGS WITH PROJECT SPECIFIC NOTES AND DETAILS.
MP MD PP E OPTION 2: SHALL COMPLY WITH THE APPLICABLE OSHPD PRE-APPROVAL (OPM) #0043-13.

ACCEPTANCE TESTING

MANDATORY ACCEPTANCE TESTING PER TITLE 24, PART 6 SHALL BE AS FOLLOWS: AN ABC AGENCY SHALL ACT AS THE ACCEPTANCE AGENT AND PERFORM WORK REQUIRED IN THE FOLLOWING ACCEPTANCE TESTS AS DESCRIBED IN CHAPTER 13 OF THE 2019 NONRESIDENTIAL COMPLIANCE MANUAL...

- NRCA-MCH-02-A - OUTDOOR AIR ACCEPTANCE
NRCA-MCH-03-A - CONSTANT VOLUME, SINGLE ZONE, UNITARY AIR CONDITIONER AND HEAT PUMP SYSTEMS
NRCA-MCH-04-A - AIR DISTRIBUTION SYSTEMS ACCEPTANCE

MECHANICAL MANDATORY MEASURES

EQUIPMENT AND SYSTEMS EFFICIENCY

ANY APPLIANCE FOR WHICH THERE IS A CALIFORNIA STANDARD ESTABLISHED IN THE APPLIANCE EFFICIENCY STANDARDS SHALL COMPLY WITH THAT STANDARD.

EXCEPT THOSE CONVEYING FLUIDS WITH A DESIGN OPERATING TEMPERATURE BETWEEN 60°F AND 105°F, OR WITHIN SPACE-CONDITIONING EQUIPMENT CERTIFIED UNDER §110.1 OR §110.2, SHALL BE INSULATED IN ACCORDANCE WITH §12.3.

ALL AIR DISTRIBUTION SYSTEM DUCTS AND PLENUMS ARE REQUIRED TO BE INSTALLED, SEALED, AND INSULATED IN ACCORDANCE WITH THE CALIFORNIA MECHANICAL CODE (CMC) SECTIONS 601, 602, 603, 604, 605, AND ANSIS/MCA-006-2006 HVAC DUCT CONSTRUCTION STANDARDS METAL AND FLEXIBLE 3RD EDITION.

VENTILATION

CONTROLS SHALL BE PROVIDED TO ALLOW OUTSIDE AIR DAMPERS OR DEVICES TO BE OPERATED AT THE VENTILATION RATES AS SPECIFIED IN THESE PLANS.

ALL GRAVITY VENTILATING SYSTEMS SHALL BE PROVIDED WITH AUTOMATIC OR READILY ACCESSIBLE MANUALLY OPERATED DAMPERS IN ALL OPENINGS TO THE OUTSIDE.

AR BALANCING: ALL SPACE CONDITIONING AND VENTILATION SYSTEMS SHALL BE BALANCED TO THE QUANTITIES SPECIFIED IN THESE PLANS, IN ACCORDANCE WITH THE ASSOCIATED AIR BALANCE MANUAL (AABM) NATIONAL STANDARDS.

GRAVITY OR AUTOMATIC DAMPERS INTERLOCKED AND CLOSED ON FAN SHUTDOWN SHALL BE PROVIDED ON THE OUTSIDE AIR INTAKES AND DISCHARGES OF ALL SPACE CONDITIONING AND EXHAUST SYSTEMS.

FANS USED FOR VENTILATION SHALL OPERATE CONTINUOUSLY DURING OCCUPIED HOURS.

THE MINIMUM OUTDOOR AIR LISTED OR THREE COMPLETE AIR CHANGES SHALL BE SUPPLIED TO THE ENTIRE BLDG. DURING THE ONE HOUR PERIOD IMMEDIATELY BEFORE THE BLDG. IS NORMALLY OCCUPIED.

CONTROLS

EACH SPACE CONDITIONING ZONE SHALL BE CONTROLLED BY AN INDIVIDUAL THERMOSTATIC CONTROL THAT RESPONDS TO THE SUPPLY OF HEATING AND COOLING ENERGY WITHIN THAT ZONE (§120.2(a)). WHEN USED TO CONTROL HEATING, THE THERMOSTATIC CONTROL MUST BE ADJUSTABLE UP TO 55°F OR LOWER. FOR COOLING, THE THERMOSTATIC CONTROL MUST BE ADJUSTABLE UP TO 85°F OR HIGHER. WHEN USED TO CONTROL BOTH HEATING AND COOLING, THE THERMOSTATIC CONTROL MUST BE ADJUSTABLE FROM 55°F TO 85°F AND ALSO PROVIDE A DEAD BAND OF AT LEAST 5°F WITHIN WHICH THE SUPPLY OF HEATING AND COOLING IS SHUT OFF OR REDUCED TO A MINIMUM.

EACH SPACE CONDITIONING SYSTEM SERVING BUILDING TYPES SUCH AS OFFICES AND MANUFACTURING FACILITIES (AND ALL OTHERS NOT EXPLICITLY EXEMPT FROM THE REQUIREMENTS OF SECTION 112 (D)) SHALL BE INSTALLED WITH AN AUTOMATIC TIME SWITCH WITH AN ACCESSIBLE MANUAL OVERRIDE THAT ALLOWS OPERATION OF THE SYSTEM DURING OFF-HOURS FOR UP TO 4 HOURS. THE TIME SWITCH SHALL BE CAPABLE OF PROGRAMMING DIFFERENT SCHEDULES FOR WEEKDAYS OR WEEKENDS. INCORPORATE AN AUTOMATIC HOLIDAY "SHUTOFF" FEATURE THAT TURNS OFF ALL LOADS FOR AT LEAST 24 HOURS, THEN RESUMES THE NORMALLY SCHEDULED OPERATION AND HAS PROGRAM BACKUP CAPABILITIES THAT PREVENT THE LOSS OF THE DEVICES PROGRAM AND TIME SETTING FOR AT LEAST 10 HOURS IF POWER IS INTERRUPTED.

SYSTEM WITH DDC TO THE §110.2(a) ARE ALSO REQUIRED TO HAVE AUTOMATIC DEMAND SHED CONTROLS.

EACH SPACE CONDITIONING SYSTEM MUST BE PROVIDED WITH CONTROLS THAT CAN AUTOMATICALLY SHUT OFF THE EQUIPMENT DURING OCCUPIED HOURS. WHEN SHUT DOWN, THE CONTROLS SHALL BE CAPABLE OF AUTOMATICALLY RESTART THE SYSTEM TO MAINTAIN A SETBACK HEATING THERMOSTAT SETPOINT, IF THE SYSTEM PROVIDES MECHANICAL HEATING AND SETUP COOLING THERMOSTAT SETPOINT, IF THE SYSTEM PROVIDES MECHANICAL COOLING.

THERMOSTATS SHALL HAVE NUMERIC SETPOINTS IN DEGREES FAHRENHEIT (°F) AND ADJUSTABLE STOPS ACCESSIBLE ONLY BY AUTHORIZED PERSONNEL.


HVAC SYMBOLS

Table of HVAC symbols including Schematic, 3D, and Description for various components like Gas Flue Exhaust Air, General Exhaust Air, Grease Exhaust Air, etc.

PIPING VALVES AND FITTINGS

Table of piping valves and fittings including Schematic, 3D, and Description for components like Pipe Drop, Pipe Rise, Pipe Tee Down, etc.

NOTE: ALL NOTES ON THIS SHEET ARE APPLICABLE TO ALL OTHER SHEETS IN THIS SET. THE SYMBOLS AND ABBREVIATIONS SHOWN ON THIS SHEET MAY OR MAY NOT BE APPLICABLE IN THIS SET OF DRAWINGS.



Grovecenter Elementary School
COVINA VALLEY USD
775 N. LARK ELLIEN AVE. WEST COVINA, CA 91791

100% CONSTRUCTION DOCUMENTS
11/08/2022 REVISIONS

77-22605-00

MECHANICAL SYMBOLS, ABBREVIATIONS & NOTES

MO.1



STATE OF CALIFORNIA  
**Mechanical Systems**  
 NRC-MCH-E CALIFORNIA ENERGY COMMISSION

**CERTIFICATE OF COMPLIANCE** NRC-MCH-E  
 This document is used to demonstrate compliance for mechanical systems that are within the scope of the permit application and are demonstrating compliance using the prescriptive path outlined in §140.4, or §141.0(b)(2) for alterations.

Project Name: CVUSD Grovescenter Report Page: (Page 1 of 42)  
 Project Address: 775 N Lark Ellen Ave Date Prepared: 7/27/2022

**A. GENERAL INFORMATION**

01 Project Location (city)	West Covina	04 Total Conditioned Floor Area	20370
02 Climate Zone	10	05 Total Unconditioned Floor Area	0
03 Occupancy Types Within Project:		06 # of Stories (Habitable Above Grade)	1
<input type="checkbox"/> Office (B)	<input type="checkbox"/> Retail (M)	<input type="checkbox"/> Non-refrigerated Warehouse (S)	
<input type="checkbox"/> Hotel/ Motel Guest Rooms (R-1)	<input type="checkbox"/> School (E)	<input type="checkbox"/> Healthcare Facility (I)	
<input type="checkbox"/> High-Rise Residential (R-2/R-3)	<input type="checkbox"/> Relocatable Class Bldg (E)	<input checked="" type="checkbox"/> Other (write in)	See Table J

**B. PROJECT SCOPE**  
 This table includes mechanical systems or components that are within the scope of the permit application and are demonstrating compliance using the prescriptive path outlined in §140.4, or §141.0(b)(2) for alterations.

01 Air System(s)	02 Wet System Components	03 Dry System Components
<input checked="" type="checkbox"/> Heating Air System	<input type="checkbox"/> Water Economizer	<input checked="" type="checkbox"/> Air Economizer
<input checked="" type="checkbox"/> Cooling Air System	<input type="checkbox"/> Pumps	<input type="checkbox"/> Electric Resistance Heat
<input type="checkbox"/> Mechanical Controls	<input type="checkbox"/> System Piping	<input checked="" type="checkbox"/> Fan Systems
<input checked="" type="checkbox"/> Mechanical Controls (existing to remain, altered or new)	<input type="checkbox"/> Cooling Towers	<input checked="" type="checkbox"/> Ductwork (existing to remain, altered or new)
	<input type="checkbox"/> Chillers	<input checked="" type="checkbox"/> Ventilation
	<input type="checkbox"/> Boilers	<input type="checkbox"/> Zonal Systems/ Terminal Boxes

Registration Number: Registration Date/Time: Registration Provider: Energysoft  
 CA Building Energy Efficiency Standards - 2019 Nonresidential Compliance Report Version: 2019.1.003 Report Generated: 2022-07-27 11:06:19  
 Schema Version: rev 20200601

STATE OF CALIFORNIA  
**Mechanical Systems**  
 NRC-MCH-E CALIFORNIA ENERGY COMMISSION

**CERTIFICATE OF COMPLIANCE** NRC-MCH-E  
 Project Name: CVUSD Grovescenter Report Page: (Page 4 of 42)  
 Project Address: 775 N Lark Ellen Ave Date Prepared: 7/27/2022

**F. HVAC SYSTEM SUMMARY (DRY & WET SYSTEMS)**  
 Dry System Equipment Sizing (includes air conditioners, condensers, heat pumps, VRF, furnaces and unit heaters)

01	02	03	04	05	06	07	08	09	10	11
RTU-E3	Unitary Heat Pumps	Air-cooled, pkg (3 phase)	NA: Load Controls	20.14	34.1	0	28.98	26.15	29.43	29.68
RTU-E4	Unitary Heat Pumps	Air-cooled, pkg (3 phase)	NA: Load Controls	20.14	34.1	0	28.98	26.15	31.54	29.58
RTU-F1	Unitary Heat Pumps	Air-cooled, pkg (3 phase)	NA: Load Controls	20.14	34.1	0	28.99	26.15	31.68	30.28
RTU-F2	Unitary Heat Pumps	Air-cooled, pkg (3 phase)	NA: Load Controls	20.14	34.1	0	28.98	26.15	29.43	29.68
RTU-F3	Unitary Heat Pumps	Air-cooled, pkg (3 phase)	NA: Load Controls	20.14	34.1	0	28.98	26.15	29.43	29.68
RTU-F4	Unitary Heat Pumps	Air-cooled, pkg (3 phase)	NA: Load Controls	20.14	34.1	0	28.98	26.15	31.54	29.58
RTU-G1	Unitary Heat Pumps	Air-cooled, pkg (3 phase)	NA: Load Controls	20.14	34.1	0	28.99	26.15	31.68	30.28
RTU-G2	Unitary Heat Pumps	Air-cooled, pkg (3 phase)	NA: Load Controls	20.14	34.1	0	28.98	26.15	29.43	29.68
RTU-G3	Unitary Heat Pumps	Air-cooled, pkg (3 phase)	NA: Load Controls	20.14	34.1	0	28.98	26.15	29.43	29.68
RTU-G4	Unitary Heat Pumps	Air-cooled, pkg (3 phase)	NA: Load Controls	20.14	34.1	0	28.98	26.15	31.54	29.58

**FOOTNOTES:** Equipment shall be the smallest size, within the available options of the desired equipment line, necessary to meet the design heating and cooling loads of the building per §140.4(a). Healthcare facilities are exempt.  
 \*It is common practice to show rated output capacity on the equipment schedule. Sensible cooling output comes from specification sheet tables.  
 † If equipment is heating only, leave cooling output and load blank. If equipment is cooling only, leave heating output and load blank.  
 ‡ Authority Having Jurisdiction may ask for load calculations used for compliance per §140.4(b).

Registration Number: Registration Date/Time: Registration Provider: Energysoft  
 CA Building Energy Efficiency Standards - 2019 Nonresidential Compliance Report Version: 2019.1.003 Report Generated: 2022-07-27 11:06:19  
 Schema Version: rev 20200601

STATE OF CALIFORNIA  
**Mechanical Systems**  
 NRC-MCH-E CALIFORNIA ENERGY COMMISSION

**CERTIFICATE OF COMPLIANCE** NRC-MCH-E  
 Project Name: CVUSD Grovescenter Report Page: (Page 7 of 40)  
 Project Address: 775 N Lark Ellen Ave Date Prepared: 5/4/2022

**H. FAN SYSTEMS & AIR ECONOMIZERS**

System Name:	RTU-D2	Economizer:	NA: <=54 kBTU/h cooling	Economizer Controls:	Designed per §140.4(e) and (m)	System Fan Type:	Constant Volume
01	02	03	04	05	06	07	08
Fan Name or Item Tag	Fan Function	Qty	Maximum Design Supply Airflow (CFM)	HP Unit <sup>2</sup>	Design HP	Fan Power Pressure Drop Adjustment - Table 140.4-B Device	Design Airflow through Device (CFM)
SF	Supply	1	1200	BHP	0.91		
Total System Design Supply Airflow (CFM):			1200	Total System Design (BHP):		0.91	Maximum System Fan Power (BHP):

System Name:	RTU-D3	Economizer:	NA: <=54 kBTU/h cooling	Economizer Controls:	Designed per §140.4(e) and (m)	System Fan Type:	Constant Volume
01	02	03	04	05	06	07	08
Fan Name or Item Tag	Fan Function	Qty	Maximum Design Supply Airflow (CFM)	HP Unit <sup>2</sup>	Design HP	Fan Power Pressure Drop Adjustment - Table 140.4-B Device	Design Airflow through Device (CFM)
SF	Supply	1	1200	BHP	0.91		
Total System Design Supply Airflow (CFM):			1200	Total System Design (BHP):		0.91	Maximum System Fan Power (BHP):

Registration Number: Registration Date/Time: Registration Provider: Energysoft  
 CA Building Energy Efficiency Standards - 2019 Nonresidential Compliance Report Version: 2019.1.003 Report Generated: 2022-05-04 08:27:25  
 Schema Version: rev 20200601

STATE OF CALIFORNIA  
**Mechanical Systems**  
 NRC-MCH-E CALIFORNIA ENERGY COMMISSION

**CERTIFICATE OF COMPLIANCE** NRC-MCH-E  
 Project Name: CVUSD Grovescenter Report Page: (Page 2 of 42)  
 Project Address: 775 N Lark Ellen Ave Date Prepared: 7/27/2022

**C. COMPLIANCE RESULTS**  
 Table C will indicate if the project data input into the compliance document is compliant with mechanical requirements. This table is not editable by the user. If this table says "DOES NOT COMPLY" or "COMPLIES with Exceptional Conditions" refer to Table D., or the table indicated as not compliant for guidance.

01	02	03	04	05	06	07	08	09
System Summary §110.1, §140.4	Pumps §140.4(b)(2)	Fans/Economizers §140.4(c), §140.4(e)	System Controls §110.2, §120.2, §140.4(f)	Ventilation §120.1	Terminal Box Controls §140.4(d)	Distribution §120.3, §140.4(i)	Cooling Towers §110.2(e)(2)	Compliance Results
(See Table F)	(See Table G)	(See Table H)	(See Table I)	(See Table J)	(See Table K)	(See Table L)	(See Table M)	COMPLIES
Mandatory Measures Compliance (See Table Q for Details)								COMPLIES

**D. EXCEPTIONAL CONDITIONS**  
 This table is auto-filled with uneditable comments because of selections made or data entered in tables throughout the form.

**E. ADDITIONAL REMARKS**  
 This table includes remarks made by the permit applicant to the Authority Having Jurisdiction.

Registration Number: Registration Date/Time: Registration Provider: Energysoft  
 CA Building Energy Efficiency Standards - 2019 Nonresidential Compliance Report Version: 2019.1.003 Report Generated: 2022-07-27 11:06:19  
 Schema Version: rev 20200601

STATE OF CALIFORNIA  
**Mechanical Systems**  
 NRC-MCH-E CALIFORNIA ENERGY COMMISSION

**CERTIFICATE OF COMPLIANCE** NRC-MCH-E  
 Project Name: CVUSD Grovescenter Report Page: (Page 5 of 42)  
 Project Address: 775 N Lark Ellen Ave Date Prepared: 7/27/2022

**F. HVAC SYSTEM SUMMARY (DRY & WET SYSTEMS)**  
 Dry System Equipment Efficiency (other than Package Terminal Air Conditioners (PTAC) and Package Terminal Heat Pumps (PTHP))

01	02	03	04	05	06	07	08	09
Name or Item Tag	Size Category (Btu/h)	Rating Condition (°F)	Efficiency Unit	Minimum Efficiency Required per Tables 110.2 / Table 20	Design Efficiency	Efficiency Unit	Minimum Efficiency Required per Tables 110.2 / Table 20	Design Efficiency
FCU/CU-B1	>=135,000 and <240,000		COP	3.2	3.5	EER	10.6	10.6
RTU-C1	<=65,000		HSPF	7.7	13	SEER	13.0	14.3
RTU-C2	<=65,000		HSPF	7.7	13	SEER	13.0	14.3
RTU-D1	<=65,000		HSPF	7.7	13	SEER	13.0	14.3
RTU-D2	<=65,000		HSPF	7.7	13	SEER	13.0	14.3
RTU-D3	<=65,000		HSPF	7.7	13	SEER	13.0	14.3
RTU-D4	<=65,000		HSPF	7.7	13	SEER	13.0	14.3
RTU-E1	<=65,000		HSPF	7.7	13	SEER	13.0	14.3
RTU-E2	<=65,000		HSPF	7.7	13	SEER	13.0	14.3
RTU-E3	<=65,000		HSPF	7.7	13	SEER	13.0	14.3
RTU-E4	<=65,000		HSPF	7.7	13	SEER	13.0	14.3
RTU-F1	<=65,000		HSPF	7.7	13	SEER	13.0	14.3
RTU-F2	<=65,000		HSPF	7.7	13	SEER	13.0	14.3
RTU-F3	<=65,000		HSPF	7.7	13	SEER	13.0	14.3
RTU-F4	<=65,000		HSPF	7.7	13	SEER	13.0	14.3
RTU-G1	<=65,000		HSPF	7.7	13	SEER	13.0	14.3
RTU-G2	<=65,000		HSPF	7.7	13	SEER	13.0	14.3
RTU-G3	<=65,000		HSPF	7.7	13	SEER	13.0	14.3
RTU-G4	<=65,000		HSPF	7.7	13	SEER	13.0	14.3

Registration Number: Registration Date/Time: Registration Provider: Energysoft  
 CA Building Energy Efficiency Standards - 2019 Nonresidential Compliance Report Version: 2019.1.003 Report Generated: 2022-07-27 11:06:19  
 Schema Version: rev 20200601

STATE OF CALIFORNIA  
**Mechanical Systems**  
 NRC-MCH-E CALIFORNIA ENERGY COMMISSION

**CERTIFICATE OF COMPLIANCE** NRC-MCH-E  
 Project Name: CVUSD Grovescenter Report Page: (Page 8 of 42)  
 Project Address: 775 N Lark Ellen Ave Date Prepared: 7/27/2022

**H. FAN SYSTEMS & AIR ECONOMIZERS**

System Name:	RTU-D3	Economizer:	NA: <=54 kBTU/h cooling	Economizer Controls:	Designed per §140.4(e) and (m)	System Fan Type:	Constant Volume
01	02	03	04	05	06	07	08
Fan Name or Item Tag	Fan Function	Qty	Maximum Design Supply Airflow (CFM)	HP Unit <sup>2</sup>	Design HP	Fan Power Pressure Drop Adjustment - Table 140.4-B Device	Design Airflow through Device (CFM)
SF	Supply	1	1200	BHP	0.61		
Total System Design Supply Airflow (CFM):			1200	Total System Design (BHP):		0.61	Maximum System Fan Power (BHP):

System Name:	RTU-D4	Economizer:	NA: <=54 kBTU/h cooling	Economizer Controls:	Designed per §140.4(e) and (m)	System Fan Type:	Constant Volume
01	02	03	04	05	06	07	08
Fan Name or Item Tag	Fan Function	Qty	Maximum Design Supply Airflow (CFM)	HP Unit <sup>2</sup>	Design HP	Fan Power Pressure Drop Adjustment - Table 140.4-B Device	Design Airflow through Device (CFM)
SF	Supply	1	1200	BHP	0.61		
Total System Design Supply Airflow (CFM):			1200	Total System Design (BHP):		0.61	Maximum System Fan Power (BHP):

Registration Number: Registration Date/Time: Registration Provider: Energysoft  
 CA Building Energy Efficiency Standards - 2019 Nonresidential Compliance Report Version: 2019.1.003 Report Generated: 2022-07-27 11:06:19  
 Schema Version: rev 20200601

STATE OF CALIFORNIA  
**Mechanical Systems**  
 NRC-MCH-E CALIFORNIA ENERGY COMMISSION

**CERTIFICATE OF COMPLIANCE** NRC-MCH-E  
 Project Name: CVUSD Grovescenter Report Page: (Page 3 of 42)  
 Project Address: 775 N Lark Ellen Ave Date Prepared: 7/27/2022

**F. HVAC SYSTEM SUMMARY (DRY & WET SYSTEMS)**  
 This table is used to demonstrate compliance for mechanical equipment with mandatory requirements found in §110.1 and §110.2(a) and prescriptive requirements found in §140.4(a), §140.4(b) and §140.4(c) or §141.0(b)(2) for alterations.

**Dry System Equipment Sizing (includes air conditioners, condensers, heat pumps, VRF, furnaces and unit heaters)**

01	02	03	04	05	06	07	08	09	10	11
Name or Item Tag	Equipment Category per Tables 110.2	Equipment Type per Tables 110.2 / Title 20	Smallest Size Available <sup>2</sup> §140.4(a)	Equipment Sizing per Mechanical Schedule §140.4(a)(8)			Compliance Results			
				Heating Output <sup>2,3</sup>		Cooling Output <sup>2,3</sup>		Load Calculations <sup>2,4</sup>		
				Per Design (kBtu/h)	Rated (kBtu/h)	Supp. Heating Output (kBtu/h)	Sensible Per Design (kBtu/h)	Rated (kBtu/h)	Total Heating Load (kBtu/h)	Total Sensible Cooling Load (kBtu/h)
FCU/CU-B1	Unitary Heat Pumps	Air-cooled, split (3 phase)	NA: Load Controls	98.05	166	0	156.69	129	192.74	158.1
RTU-C1	Unitary Heat Pumps	Air-cooled, pkg (3 phase)	NA: Load Controls	20.14	34.1	0	29.19	26.15	35.73	36.53
RTU-C2	Unitary Heat Pumps	Air-cooled, pkg (3 phase)	NA: Load Controls	20.14	34.1	0	29.2	26.15	35.73	37.13
RTU-D1	Unitary Heat Pumps	Air-cooled, pkg (3 phase)	NA: Load Controls	20.14	34.1	0	28.99	26.15	31.68	30.28
RTU-D2	Unitary Heat Pumps	Air-cooled, pkg (3 phase)	NA: Load Controls	20.14	34.1	0	28.98	26.15	29.43	29.68
RTU-D3	Unitary Heat Pumps	Air-cooled, pkg (3 phase)	NA: Load Controls	20.14	34.1	0	28.98	26.15	29.43	29.68
RTU-D4	Unitary Heat Pumps	Air-cooled, pkg (3 phase)	NA: Load Controls	20.14	34.1	0	28.98	26.15	31.54	29.58
RTU-E1	Unitary Heat Pumps	Air-cooled, pkg (3 phase)	NA: Load Controls	20.14	34.1	0	28.99	26.15	31.68	30.28
RTU-E2	Unitary Heat Pumps	Air-cooled, pkg (3 phase)	NA: Load Controls	20.14	34.1	0	28.98	26.15	29.43	29.68

Registration Number: Registration Date/Time: Registration Provider: Energysoft  
 CA Building Energy Efficiency Standards - 2019 Nonresidential Compliance Report Version: 2019.1.003 Report Generated: 2022-07-27 11:06:19  
 Schema Version: rev 20200601

STATE OF CALIFORNIA  
**Mechanical Systems**  
 NRC-MCH-E CALIFORNIA ENERGY COMMISSION

**CERTIFICATE OF COMPLIANCE** NRC-MCH-E  
 Project Name: CVUSD Grovescenter Report Page: (Page 6 of 42)  
 Project Address: 775 N Lark Ellen Ave Date Prepared: 7/27/2022

**G. PUMPS**  
 This section does not apply to this project.

**H. FAN SYSTEMS & AIR ECONOMIZERS**  
 This table is used to demonstrate compliance with prescriptive requirements found in §140.4(c), §140.4(e) and §140.4(m) for fan systems. Fan systems serving only process loads are exempt from these requirements and do not need to be included in Table H.

System Name:	FCU/CU-B1	Economizer:	NA: Special OA filtration	Economizer Controls:	Designed per §140.4(e) and (m)	System Fan Type:	Constant Volume
01	02	03	04	05	06	07	08
Fan Name or Item Tag	Fan Function	Qty	Maximum Design Supply Airflow (CFM)	HP Unit <sup>2</sup>	Design HP	Fan Power Pressure Drop Adjustment - Table 140.4-B Device	Design Airflow through Device (CFM)
SF	Supply	1	4800	BHP	3.04		
Total System Design Supply Airflow (CFM):			4800	Total System Design (BHP):		3.04	Maximum System Fan Power (BHP):

Registration Number: Registration Date/Time: Registration Provider: Energysoft  
 CA Building Energy Efficiency Standards - 2019 Nonresidential Compliance Report Version: 2019.1.003 Report Generated: 2022-07-27 11:06:19  
 Schema Version: rev 20200601

STATE OF CALIFORNIA  
**Mechanical Systems**  
 NRC-MCH-E CALIFORNIA ENERGY COMMISSION

**CERTIFICATE OF COMPLIANCE** NRC-MCH-E  
 Project Name: CVUSD Grovescenter Report Page: (Page 9 of 42)  
 Project Address: 775 N Lark Ellen Ave Date Prepared: 7/27/2022

**H. FAN SYSTEMS & AIR ECONOMIZERS**

System Name:	RTU-E2	Economizer:	NA: <=54 kBTU/h cooling	Economizer Controls:	Designed per §140.4(e) and (m)	System Fan Type:	Constant Volume
01	02	03	04	05	06	07	08
Fan Name or Item Tag	Fan Function	Qty	Maximum Design Supply Airflow (CFM)	HP Unit <sup>2</sup>	Design HP	Fan Power Pressure Drop Adjustment - Table 140.4-B Device	Design Airflow through Device (CFM)
SF	Supply	1	1200	BHP	0.61		
Total System Design Supply Airflow (CFM):			1200	Total System Design (BHP):		0.61	Maximum System Fan Power (BHP):

System Name:	RTU-E3	Economizer:	NA: <=54 kBTU/h cooling	Economizer Controls:	Designed per §140.4(e) and (m)	System Fan Type:	Constant Volume
01	02	03	04	05	06	07	08
Fan Name or Item Tag	Fan Function	Qty	Maximum Design Supply Airflow (CFM)	HP Unit <sup>2</sup>	Design HP	Fan Power Pressure Drop Adjustment - Table 140.4-B Device	Design Airflow through Device (CFM)
SF	Supply	1	1200	BHP	0.61		
Total System Design Supply Airflow (CFM):			1200	Total System Design (BHP):		0.61	Maximum System Fan Power (BHP):

Registration Number: Registration Date/Time: Registration Provider: Energysoft  
 CA Building Energy Efficiency Standards - 2019 Nonresidential Compliance Report Version: 2019.1.003 Report Generated: 2022-07-27 11:06:19  
 Schema Version: rev 20200601



STATE OF CALIFORNIA  
**Mechanical Systems**  
 NRCC-MCH-4 CALIFORNIA ENERGY COMMISSION  
**CERTIFICATE OF COMPLIANCE**  
 Project Name: CVUSD Grovescenter Report Page: NRCC-MCH-4 (Page 10 of 42)  
 Project Address: 775 N Lark Ellen Ave Date Prepared: 7/27/2022

H. FAN SYSTEMS & AIR ECONOMIZERS									
System Name:	RTU-F1	Economizer: <sup>1</sup>	NA: <=54 kBtu/h cooling	Economizer Controls:	Designed per §140.4(e) and (m)	System Fan Type:	Constant Volume		
O1	O2	O3	O4	O5	O6	O7	O8	O9	O10
Fan Name or Item Tag	Fan Function	Qty	Maximum Design Supply Airflow (CFM)	HP Unit <sup>2</sup>	Design HP	Fan Power Pressure Drop Adjustment - Table 140.4-B	Design Airflow through Device (CFM)		
SF	Supply	1	1200	BHP	0.61	Maximum System Fan Power (BHP):			
Total System Design Supply Airflow (CFM):			1200	Total System Design (BHP):		0.61			

Registration Number: Registration Date/Time: Registration Provider: Energysoft  
 CA Building Energy Efficiency Standards - 2019 Nonresidential Compliance Report Version: 2019.1.003 Schema Version: rev 20200601 Report Generated: 2022-07-27 11:06:19

STATE OF CALIFORNIA  
**Mechanical Systems**  
 NRCC-MCH-4 CALIFORNIA ENERGY COMMISSION  
**CERTIFICATE OF COMPLIANCE**  
 Project Name: CVUSD Grovescenter Report Page: NRCC-MCH-4 (Page 13 of 42)  
 Project Address: 775 N Lark Ellen Ave Date Prepared: 7/27/2022

I. SYSTEM CONTROLS									
This table is used to demonstrate compliance with mandatory controls in §110.2 and §120.2 and prescriptive controls in §140.4(f) and (n) or requirements in §141.0(b)(2) for altered space conditioning systems.									
O1	O2	O3	O4	O5	O6	O7	O8	O9	O10
System Name	System Zoning	Conditioned Floor Area Being Served (ft <sup>2</sup> )	Thermostats §110.2(b) & (c) <sup>1</sup> , §120.2(a)(or §141.0(b)(2)) <sup>2</sup>	Shut-Off Controls §120.2(e)	Isolation Zone Controls §120.2(a)	Demand Response §110.12 and §120.2(b)	Supply Air Temp. Reset §140.4(f)	Window Interlocks per §140.4(n)	
FCU/CU-B1	Single zone	<= 25,000 ft <sup>2</sup>	Setback	Auto Timer Switch	4 Hour Timer	EMCS	Included	Provided	
RTU-C1	Single zone	<= 25,000 ft <sup>2</sup>	Setback	Auto Timer Switch	4 Hour Timer	EMCS	Included	Provided	
RTU-C2	Single zone	<= 25,000 ft <sup>2</sup>	Setback	Auto Timer Switch	4 Hour Timer	EMCS	Included	Provided	
RTU-D1	Single zone	<= 25,000 ft <sup>2</sup>	Setback	Auto Timer Switch	4 Hour Timer	EMCS	Included	Provided	
RTU-D2	Single zone	<= 25,000 ft <sup>2</sup>	Setback	Auto Timer Switch	4 Hour Timer	EMCS	Included	Provided	
RTU-D3	Single zone	<= 25,000 ft <sup>2</sup>	Setback	Auto Timer Switch	4 Hour Timer	EMCS	Included	Provided	
RTU-D4	Single zone	<= 25,000 ft <sup>2</sup>	Setback	Auto Timer Switch	4 Hour Timer	EMCS	Included	Provided	
RTU-E1	Single zone	<= 25,000 ft <sup>2</sup>	Setback	Auto Timer Switch	4 Hour Timer	EMCS	Included	Provided	
RTU-E2	Single zone	<= 25,000 ft <sup>2</sup>	Setback	Auto Timer Switch	4 Hour Timer	EMCS	Included	Provided	
RTU-E3	Single zone	<= 25,000 ft <sup>2</sup>	Setback	Auto Timer Switch	4 Hour Timer	EMCS	Included	Provided	
RTU-E4	Single zone	<= 25,000 ft <sup>2</sup>	Setback	Auto Timer Switch	4 Hour Timer	EMCS	Included	Provided	
RTU-F1	Single zone	<= 25,000 ft <sup>2</sup>	Setback	Auto Timer Switch	4 Hour Timer	EMCS	Included	Provided	

Registration Number: Registration Date/Time: Registration Provider: Energysoft  
 CA Building Energy Efficiency Standards - 2019 Nonresidential Compliance Report Version: 2019.1.003 Schema Version: rev 20200601 Report Generated: 2022-07-27 11:06:19

STATE OF CALIFORNIA  
**Mechanical Systems**  
 NRCC-MCH-4 CALIFORNIA ENERGY COMMISSION  
**CERTIFICATE OF COMPLIANCE**  
 Project Name: CVUSD Grovescenter Report Page: NRCC-MCH-4 (Page 16 of 42)  
 Project Address: 775 N Lark Ellen Ave Date Prepared: 7/27/2022

J. VENTILATION AND INDOOR AIR QUALITY									
System Name	RTU-C2	System Design OA CFM Airflow <sup>1</sup>	225	System Design Transfer Air CFM	0	Air Filtration per §120.1(c) and §141.0(b)(2) <sup>2</sup> Provided per §120.1(c) (NR and Hotel/Motel)			
O8	O9	10	11	12	13	14	15	16	
Space Name of Item Tag	Occupancy Type <sup>4</sup>	Conditioned Floor Area (ft <sup>2</sup> )	# of Shower heads/ toilets	# of people <sup>5</sup>	Required Min OA CFM	Required Min CFM	Provided per Design CFM	DCV or Sensor Controls per §120.1(d)(3), §120.1(d)(5), and §120.1(e)(3) <sup>6</sup>	
Classroom	Lecture/ postsecondary classroom	1230		15	225	0	0	DCV	Provided per §120.1(d)(4)
								Occ Sensor	NA: Not required space type
17 Total System Required Min OA CFM					225	18	Ventilation for this System Complies? Yes		

Registration Number: Registration Date/Time: Registration Provider: Energysoft  
 CA Building Energy Efficiency Standards - 2019 Nonresidential Compliance Report Version: 2019.1.003 Schema Version: rev 20200601 Report Generated: 2022-07-27 11:06:19

STATE OF CALIFORNIA  
**Mechanical Systems**  
 NRCC-MCH-4 CALIFORNIA ENERGY COMMISSION  
**CERTIFICATE OF COMPLIANCE**  
 Project Name: CVUSD Grovescenter Report Page: NRCC-MCH-4 (Page 11 of 42)  
 Project Address: 775 N Lark Ellen Ave Date Prepared: 7/27/2022

H. FAN SYSTEMS & AIR ECONOMIZERS									
System Name:	RTU-F4	Economizer: <sup>1</sup>	NA: <=54 kBtu/h cooling	Economizer Controls:	Designed per §140.4(e) and (m)	System Fan Type:	Constant Volume		
O1	O2	O3	O4	O5	O6	O7	O8	O9	O10
Fan Name or Item Tag	Fan Function	Qty	Maximum Design Supply Airflow (CFM)	HP Unit <sup>2</sup>	Design HP	Fan Power Pressure Drop Adjustment - Table 140.4-B	Design Airflow through Device (CFM)		
SF	Supply	1	1200	BHP	0.61	Maximum System Fan Power (BHP):			
Total System Design Supply Airflow (CFM):			1200	Total System Design (BHP):		0.61			

Registration Number: Registration Date/Time: Registration Provider: Energysoft  
 CA Building Energy Efficiency Standards - 2019 Nonresidential Compliance Report Version: 2019.1.003 Schema Version: rev 20200601 Report Generated: 2022-07-27 11:06:19

STATE OF CALIFORNIA  
**Mechanical Systems**  
 NRCC-MCH-4 CALIFORNIA ENERGY COMMISSION  
**CERTIFICATE OF COMPLIANCE**  
 Project Name: CVUSD Grovescenter Report Page: NRCC-MCH-4 (Page 14 of 42)  
 Project Address: 775 N Lark Ellen Ave Date Prepared: 7/27/2022

I. SYSTEM CONTROLS									
RTU-F2	Single zone	<= 25,000 ft <sup>2</sup>	Setback	Auto Timer Switch	4 Hour Timer	EMCS	Included	Provided	
RTU-F3	Single zone	<= 25,000 ft <sup>2</sup>	Setback	Auto Timer Switch	4 Hour Timer	EMCS	Included	Provided	
RTU-F4	Single zone	<= 25,000 ft <sup>2</sup>	Setback	Auto Timer Switch	4 Hour Timer	EMCS	Included	Provided	
RTU-G1	Single zone	<= 25,000 ft <sup>2</sup>	Setback	Auto Timer Switch	4 Hour Timer	EMCS	Included	Provided	
RTU-G2	Single zone	<= 25,000 ft <sup>2</sup>	Setback	Auto Timer Switch	4 Hour Timer	EMCS	Included	Provided	
RTU-G3	Single zone	<= 25,000 ft <sup>2</sup>	Setback	Auto Timer Switch	4 Hour Timer	EMCS	Included	Provided	
RTU-G4	Single zone	<= 25,000 ft <sup>2</sup>	Setback	Auto Timer Switch	4 Hour Timer	EMCS	Included	Provided	

<sup>2</sup>FOOTNOTES: Gravity gas wall heaters, gravity floor heaters, gravity room heaters, non-central electric heaters, fireplaces or decorative gas appliances, wood stoves are not required to have setback thermostats.  
 \*Notes: Controls with a \* require a note in the space below explaining how compliance is achieved. EX: system 1: SA Temp Reset: Exempt because zones compliant with §140.4(f); EXCEPTION 1 to §140.4(f)

J. VENTILATION AND INDOOR AIR QUALITY									
This table is used to demonstrate compliance with mandatory ventilation requirements in §120.1 and §120.2(d)(3) for all nonresidential, high-rise residential and hotel/motel occupancies. For alterations, only ventilation systems being altered within the scope of the permit application need to be documented in this table. In lieu of this table, the required outdoor ventilation rates and airflow may be shown on the plans or the calculations can be presented in a spreadsheet.									
O1	<input type="checkbox"/>	Check this box if the project is showing ventilation calculations on the plans, or attaching the calculations instead of completing this table.							
O2	<input checked="" type="checkbox"/>	Check this box if the project included Nonresidential or Hotel/Motel spaces							
O3	<input type="checkbox"/>	Check this box if the project included new or altered high-rise residential dwelling units.							
O3	<input type="checkbox"/>	Check this box if the project is using natural ventilation in any nonresidential or hotel/motel spaces to meet required ventilation rates per §120.1(c)(2).							
Nonresidential and Hotel/ Motel Ventilation Systems									

Registration Number: Registration Date/Time: Registration Provider: Energysoft  
 CA Building Energy Efficiency Standards - 2019 Nonresidential Compliance Report Version: 2019.1.003 Schema Version: rev 20200601 Report Generated: 2022-07-27 11:06:19

STATE OF CALIFORNIA  
**Mechanical Systems**  
 NRCC-MCH-4 CALIFORNIA ENERGY COMMISSION  
**CERTIFICATE OF COMPLIANCE**  
 Project Name: CVUSD Grovescenter Report Page: NRCC-MCH-4 (Page 17 of 42)  
 Project Address: 775 N Lark Ellen Ave Date Prepared: 7/27/2022

J. VENTILATION AND INDOOR AIR QUALITY									
System Name	RTU-D2	System Design OA CFM Airflow <sup>1</sup>	225	System Design Transfer Air CFM	0	Air Filtration per §120.1(c) and §141.0(b)(2) <sup>2</sup> Provided per §120.1(c) (NR and Hotel/Motel)			
O8	O9	10	11	12	13	14	15	16	
Space Name of Item Tag	Occupancy Type <sup>4</sup>	Conditioned Floor Area (ft <sup>2</sup> )	# of Shower heads/ toilets	# of people <sup>5</sup>	Required Min OA CFM	Required Min CFM	Provided per Design CFM	DCV or Sensor Controls per §120.1(d)(3), §120.1(d)(5), and §120.1(e)(3) <sup>6</sup>	
Classroom	Lecture/ postsecondary classroom	895		15	225	0	0	DCV	Provided per §120.1(d)(4)
								Occ Sensor	NA: Not required space type
17 Total System Required Min OA CFM					225	18	Ventilation for this System Complies? Yes		

Registration Number: Registration Date/Time: Registration Provider: Energysoft  
 CA Building Energy Efficiency Standards - 2019 Nonresidential Compliance Report Version: 2019.1.003 Schema Version: rev 20200601 Report Generated: 2022-07-27 11:06:19

STATE OF CALIFORNIA  
**Mechanical Systems**  
 NRCC-MCH-4 CALIFORNIA ENERGY COMMISSION  
**CERTIFICATE OF COMPLIANCE**  
 Project Name: CVUSD Grovescenter Report Page: NRCC-MCH-4 (Page 12 of 42)  
 Project Address: 775 N Lark Ellen Ave Date Prepared: 7/27/2022

H. FAN SYSTEMS & AIR ECONOMIZERS									
System Name:	RTU-G3	Economizer: <sup>1</sup>	NA: <=54 kBtu/h cooling	Economizer Controls:	Designed per §140.4(e) and (m)	System Fan Type:	Constant Volume		
O1	O2	O3	O4	O5	O6	O7	O8	O9	O10
Fan Name or Item Tag	Fan Function	Qty	Maximum Design Supply Airflow (CFM)	HP Unit <sup>2</sup>	Design HP	Fan Power Pressure Drop Adjustment - Table 140.4-B	Design Airflow through Device (CFM)		
SF	Supply	1	1200	BHP	0.61	Maximum System Fan Power (BHP):			
Total System Design Supply Airflow (CFM):			1200	Total System Design (BHP):		0.61			

<sup>1</sup> FOOTNOTES: Computer room economizers must meet requirements of §140.9(a) and will be documented on the NRCC-PRC-E document.  
<sup>2</sup> The unit used for HP must be consistent for all fans within a system.

Registration Number: Registration Date/Time: Registration Provider: Energysoft  
 CA Building Energy Efficiency Standards - 2019 Nonresidential Compliance Report Version: 2019.1.003 Schema Version: rev 20200601 Report Generated: 2022-07-27 11:06:19

STATE OF CALIFORNIA  
**Mechanical Systems**  
 NRCC-MCH-4 CALIFORNIA ENERGY COMMISSION  
**CERTIFICATE OF COMPLIANCE**  
 Project Name: CVUSD Grovescenter Report Page: NRCC-MCH-4 (Page 15 of 42)  
 Project Address: 775 N Lark Ellen Ave Date Prepared: 7/27/2022

J. VENTILATION AND INDOOR AIR QUALITY									
System Name	FCU/CU-B1	System Design OA CFM Airflow <sup>1</sup>	2250	System Design Transfer Air CFM	0	Air Filtration per §120.1(c) and §141.0(b)(2) <sup>2</sup> Provided per §120.1(c) (NR and Hotel/Motel)			
O8	O9	10	11	12	13	14	15	16	
Space Name of Item Tag	Occupancy Type <sup>4</sup>	Conditioned Floor Area (ft <sup>2</sup> )	# of Shower heads/ toilets	# of people <sup>5</sup>	Required Min OA CFM	Required Min CFM	Provided per Design CFM	DCV or Sensor Controls per §120.1(d)(3), §120.1(d)(5), and §120.1(e)(3) <sup>6</sup>	
MPR	Assembly-multituse	3550		150	2250	0	0	DCV	Provided per §120.1(d)(4)
								Occ Sensor	NA: Not required space type
17 Total System Required Min OA CFM					2250	18	Ventilation for this System Complies? Yes		

Registration Number: Registration Date/Time: Registration Provider: Energysoft  
 CA Building Energy Efficiency Standards - 2019 Nonresidential Compliance Report Version: 2019.1.003 Schema Version: rev 20200601 Report Generated: 2022-07-27 11:06:19

STATE OF CALIFORNIA  
**Mechanical Systems**  
 NRCC-MCH-4 CALIFORNIA ENERGY COMMISSION  
**CERTIFICATE OF COMPLIANCE**  
 Project Name: CVUSD Grovescenter Report Page: NRCC-MCH-4 (Page 18 of 42)  
 Project Address: 775 N Lark Ellen Ave Date Prepared: 7/27/2022

J. VENTILATION AND INDOOR AIR QUALITY									
System Name	RTU-D4	System Design OA CFM Airflow <sup>1</sup>	225	System Design Transfer Air CFM	0	Air Filtration per §120.1(c) and §141.0(b)(2) <sup>2</sup> Provided per §120.1(c) (NR and Hotel/Motel)			
O8	O9	10	11	12	13	14	15	16	
Space Name of Item Tag	Occupancy Type <sup>4</sup>	Conditioned Floor Area (ft <sup>2</sup> )	# of Shower heads/ toilets	# of people <sup>5</sup>	Required Min OA CFM	Required Min CFM	Provided per Design CFM	DCV or Sensor Controls per §120.1(d)(3), §120.1(d)(5), and §120.1(e)(3) <sup>6</sup>	
Classroom	Lecture/ postsecondary classroom	895		15	225	0	0	DCV	Provided per §120.1(d)(4)
								Occ Sensor	NA: Not required space type
17 Total System Required Min OA CFM					225	18	Ventilation for this System Complies? Yes		

Registration Number: Registration Date/Time: Registration Provider: Energysoft  
 CA Building Energy Efficiency Standards - 2019 Nonresidential Compliance Report Version: 2019.1.003 Schema Version: rev 20200601 Report Generated: 2022-07-27 11:06:19

1  
2  
3  
4  
5



Grovescenter Elementary School  
 COVINA VALLEY USD  
 775 N LARK ELLEN AVE, WEST COVINA, CA 91791

100% CONSTRUCTION DOCUMENTS  
 11/08/2022 REVISIONS

77-22605-00  
 TITLE 24 COMPLIANCE

M0.3

10/21/2022 4:45:33 PM  
 Autodesk Docs/775-22605-00\_CVUSD - District Wide HVAC Replacement/75-22605-00\_CVUSD\_Grovescenter\_ES MEP\_2022.rvt



J. VENTILATION AND INDOOR AIR QUALITY															
04				05				06				07			
System Name	RTU-E2	System Design OA CFM Airflow <sup>1</sup>	225	System Design Transfer Air CFM	0	Air Filtration per §120.1(c) and §141.0(b)2 <sup>2</sup>	Provided per §120.1(c) (NR and Hotel/Motel)								
08	09	10	11	12	13	14	15	16	Mechanical Ventilation Required per §120.1(c)3 <sup>3</sup>						
Space Name of Item Tag	Occupancy Type <sup>4</sup>	Conditioned Floor Area (ft <sup>2</sup> )	# of Shower heads/ toilets	# of people <sup>5</sup>	Required Min OA CFM	Required Min CFM	Provided per Design CFM	DCV or Sensor Controls per §120.1(d)3, §120.1(d)5, and §120.1(e)3 <sup>6</sup>	Exh. Vent per §120.1(c)4						
Classroom	Lecture/ postsecondary classroom	895		15	225	0	0	DCV	Provided per §120.1(d)4	Occ Sensor NA: Not required space type					
17	Total System Required Min OA CFM 225 18 Ventilation for this System Complies? Yes														

Registration Number: CA Building Energy Efficiency Standards - 2019 Nonresidential Compliance  
Registration Date/Time: Report Version: 2019.1.003  
Registration Provider: Energysoft Schema Version: rev 20200601  
Report Generated: 2022-07-27 11:06:19

J. VENTILATION AND INDOOR AIR QUALITY															
04				05				06				07			
System Name	RTU-F4	System Design OA CFM Airflow <sup>1</sup>	225	System Design Transfer Air CFM	0	Air Filtration per §120.1(c) and §141.0(b)2 <sup>2</sup>	Provided per §120.1(c) (NR and Hotel/Motel)								
08	09	10	11	12	13	14	15	16	Mechanical Ventilation Required per §120.1(c)3 <sup>3</sup>						
Space Name of Item Tag	Occupancy Type <sup>4</sup>	Conditioned Floor Area (ft <sup>2</sup> )	# of Shower heads/ toilets	# of people <sup>5</sup>	Required Min OA CFM	Required Min CFM	Provided per Design CFM	DCV or Sensor Controls per §120.1(d)3, §120.1(d)5, and §120.1(e)3 <sup>6</sup>	Exh. Vent per §120.1(c)4						
Classroom	Lecture/ postsecondary classroom	895		15	225	0	0	DCV	Provided per §120.1(d)4	Occ Sensor NA: Not required space type					
17	Total System Required Min OA CFM 225 18 Ventilation for this System Complies? Yes														

Registration Number: CA Building Energy Efficiency Standards - 2019 Nonresidential Compliance  
Registration Date/Time: Report Version: 2019.1.003  
Registration Provider: Energysoft Schema Version: rev 20200601  
Report Generated: 2022-07-27 11:06:19

L. DISTRIBUTION (DUCTWORK AND PIPING)		
This table is used to show compliance with mandatory pipe insulation requirements found in §140.3 and prescriptive requirements found in §140.4(f) for duct leakage testing.		
Duct Leakage Sealing		
The answers to the questions below apply to the following duct systems: FCU/CU-B1 Duct leakage testing triggered for these systems? No		
11	No	The scope of the project includes only duct systems serving healthcare facilities
12	Yes	Duct system provides conditioned air to an occupiable space for a constant volume, single zone, space-conditioning system.
13	Yes	The space conditioning system serves less than 5,000 ft <sup>2</sup> of conditioned floor area.
14	No	The combined surface area of the ducts in the following locations is more than 25% of the total surface area of the entire duct system: Outdoors <input type="checkbox"/> In a space directly under a roof that has a U-factor greater than the u-factor of the ceiling, or if the roof does not meet the requirements of §140.3(a)18 or if the roof has fixed vents or openings to the outside/unconditioned spaces <input type="checkbox"/> In an unconditioned crawl space <input type="checkbox"/> In other unconditioned spaces
15		The scope of the project includes extending an existing duct system, which is constructed, insulated or sealed with asbestos.
16		The scope of the project includes an existing duct system that is documented to have been previously sealed as confirmed through field verification and diagnostic testing in accordance with procedures in the Reference Nonresidential Appendix NA2.
17	Yes	Duct system shall be sealed in accordance with the California Mechanical Code
The answers to the questions below apply to the following duct systems: RTU-C1 Duct leakage testing triggered for these systems? No		
11	No	The scope of the project includes only duct systems serving healthcare facilities
12	Yes	Duct system provides conditioned air to an occupiable space for a constant volume, single zone, space-conditioning system.
13	Yes	The space conditioning system serves less than 5,000 ft <sup>2</sup> of conditioned floor area.
14	No	The combined surface area of the ducts in the following locations is more than 25% of the total surface area of the entire duct system: Outdoors <input type="checkbox"/> In a space directly under a roof that has a U-factor greater than the u-factor of the ceiling, or if the roof does not meet the requirements of §140.3(a)18 or if the roof has fixed vents or openings to the outside/unconditioned spaces <input type="checkbox"/> In an unconditioned crawl space

Registration Number: CA Building Energy Efficiency Standards - 2019 Nonresidential Compliance  
Registration Date/Time: Report Version: 2019.1.003  
Registration Provider: Energysoft Schema Version: rev 20200601  
Report Generated: 2022-07-27 11:06:19

J. VENTILATION AND INDOOR AIR QUALITY															
04				05				06				07			
System Name	RTU-E4	System Design OA CFM Airflow <sup>1</sup>	225	System Design Transfer Air CFM	0	Air Filtration per §120.1(c) and §141.0(b)2 <sup>2</sup>	Provided per §120.1(c) (NR and Hotel/Motel)								
08	09	10	11	12	13	14	15	16	Mechanical Ventilation Required per §120.1(c)3 <sup>3</sup>						
Space Name of Item Tag	Occupancy Type <sup>4</sup>	Conditioned Floor Area (ft <sup>2</sup> )	# of Shower heads/ toilets	# of people <sup>5</sup>	Required Min OA CFM	Required Min CFM	Provided per Design CFM	DCV or Sensor Controls per §120.1(d)3, §120.1(d)5, and §120.1(e)3 <sup>6</sup>	Exh. Vent per §120.1(c)4						
Classroom	Lecture/ postsecondary classroom	895		15	225	0	0	DCV	Provided per §120.1(d)4	Occ Sensor NA: Not required space type					
17	Total System Required Min OA CFM 225 18 Ventilation for this System Complies? Yes														

Registration Number: CA Building Energy Efficiency Standards - 2019 Nonresidential Compliance  
Registration Date/Time: Report Version: 2019.1.003  
Registration Provider: Energysoft Schema Version: rev 20200601  
Report Generated: 2022-07-27 11:06:19

J. VENTILATION AND INDOOR AIR QUALITY															
04				05				06				07			
System Name	RTU-G2	System Design OA CFM Airflow <sup>1</sup>	225	System Design Transfer Air CFM	0	Air Filtration per §120.1(c) and §141.0(b)2 <sup>2</sup>	Provided per §120.1(c) (NR and Hotel/Motel)								
08	09	10	11	12	13	14	15	16	Mechanical Ventilation Required per §120.1(c)3 <sup>3</sup>						
Space Name of Item Tag	Occupancy Type <sup>4</sup>	Conditioned Floor Area (ft <sup>2</sup> )	# of Shower heads/ toilets	# of people <sup>5</sup>	Required Min OA CFM	Required Min CFM	Provided per Design CFM	DCV or Sensor Controls per §120.1(d)3, §120.1(d)5, and §120.1(e)3 <sup>6</sup>	Exh. Vent per §120.1(c)4						
Classroom	Lecture/ postsecondary classroom	895		15	225	0	0	DCV	Provided per §120.1(d)4	Occ Sensor NA: Not required space type					
17	Total System Required Min OA CFM 225 18 Ventilation for this System Complies? Yes														

Registration Number: CA Building Energy Efficiency Standards - 2019 Nonresidential Compliance  
Registration Date/Time: Report Version: 2019.1.003  
Registration Provider: Energysoft Schema Version: rev 20200601  
Report Generated: 2022-07-27 11:06:19

L. DISTRIBUTION (DUCTWORK AND PIPING)		
This table is used to show compliance with mandatory pipe insulation requirements found in §140.3 and prescriptive requirements found in §140.4(f) for duct leakage testing.		
Duct Leakage Sealing		
The answers to the questions below apply to the following duct systems: RTU-C2 Duct leakage testing triggered for these systems? No		
11	No	The scope of the project includes only duct systems serving healthcare facilities
12	Yes	Duct system provides conditioned air to an occupiable space for a constant volume, single zone, space-conditioning system.
13	Yes	The space conditioning system serves less than 5,000 ft <sup>2</sup> of conditioned floor area.
14	No	The combined surface area of the ducts in the following locations is more than 25% of the total surface area of the entire duct system: Outdoors <input type="checkbox"/> In a space directly under a roof that has a U-factor greater than the u-factor of the ceiling, or if the roof does not meet the requirements of §140.3(a)18 or if the roof has fixed vents or openings to the outside/unconditioned spaces <input type="checkbox"/> In an unconditioned crawl space
15		The scope of the project includes extending an existing duct system, which is constructed, insulated or sealed with asbestos.
16		The scope of the project includes an existing duct system that is documented to have been previously sealed as confirmed through field verification and diagnostic testing in accordance with procedures in the Reference Nonresidential Appendix NA2.
17	Yes	Duct system shall be sealed in accordance with the California Mechanical Code
The answers to the questions below apply to the following duct systems: RTU-D1 Duct leakage testing triggered for these systems? No		
11	No	The scope of the project includes only duct systems serving healthcare facilities
12	Yes	Duct system provides conditioned air to an occupiable space for a constant volume, single zone, space-conditioning system.
13	Yes	The space conditioning system serves less than 5,000 ft <sup>2</sup> of conditioned floor area.
14	No	The combined surface area of the ducts in the following locations is more than 25% of the total surface area of the entire duct system: Outdoors <input type="checkbox"/> In a space directly under a roof that has a U-factor greater than the u-factor of the ceiling, or if the roof does not meet the requirements of §140.3(a)18 or if the roof has fixed vents or openings to the outside/unconditioned spaces <input type="checkbox"/> In an unconditioned crawl space

Registration Number: CA Building Energy Efficiency Standards - 2019 Nonresidential Compliance  
Registration Date/Time: Report Version: 2019.1.003  
Registration Provider: Energysoft Schema Version: rev 20200601  
Report Generated: 2022-07-27 11:06:19

J. VENTILATION AND INDOOR AIR QUALITY															
04				05				06				07			
System Name	RTU-F2	System Design OA CFM Airflow <sup>1</sup>	225	System Design Transfer Air CFM	0	Air Filtration per §120.1(c) and §141.0(b)2 <sup>2</sup>	Provided per §120.1(c) (NR and Hotel/Motel)								
08	09	10	11	12	13	14	15	16	Mechanical Ventilation Required per §120.1(c)3 <sup>3</sup>						
Space Name of Item Tag	Occupancy Type <sup>4</sup>	Conditioned Floor Area (ft <sup>2</sup> )	# of Shower heads/ toilets	# of people <sup>5</sup>	Required Min OA CFM	Required Min CFM	Provided per Design CFM	DCV or Sensor Controls per §120.1(d)3, §120.1(d)5, and §120.1(e)3 <sup>6</sup>	Exh. Vent per §120.1(c)4						
Classroom	Lecture/ postsecondary classroom	895		15	225	0	0	DCV	Provided per §120.1(d)4	Occ Sensor NA: Not required space type					
17	Total System Required Min OA CFM 225 18 Ventilation for this System Complies? Yes														

Registration Number: CA Building Energy Efficiency Standards - 2019 Nonresidential Compliance  
Registration Date/Time: Report Version: 2019.1.003  
Registration Provider: Energysoft Schema Version: rev 20200601  
Report Generated: 2022-07-27 11:06:19

J. VENTILATION AND INDOOR AIR QUALITY															
04				05				06				07			
System Name	RTU-G4	System Design OA CFM Airflow <sup>1</sup>	225	System Design Transfer Air CFM	0	Air Filtration per §120.1(c) and §141.0(b)2 <sup>2</sup>	Provided per §120.1(c) (NR and Hotel/Motel)								
08	09	10	11	12	13	14	15	16	Mechanical Ventilation Required per §120.1(c)3 <sup>3</sup>						
Space Name of Item Tag	Occupancy Type <sup>4</sup>	Conditioned Floor Area (ft <sup>2</sup> )	# of Shower heads/ toilets	# of people <sup>5</sup>	Required Min OA CFM	Required Min CFM	Provided per Design CFM	DCV or Sensor Controls per §120.1(d)3, §120.1(d)5, and §120.1(e)3 <sup>6</sup>	Exh. Vent per §120.1(c)4						
Classroom	Lecture/ postsecondary classroom	895		15	225	0	0	DCV	Provided per §120.1(d)4	Occ Sensor NA: Not required space type					
17	Total System Required Min OA CFM 225 18 Ventilation for this System Complies? Yes														

Registration Number: CA Building Energy Efficiency Standards - 2019 Nonresidential Compliance  
Registration Date/Time: Report Version: 2019.1.003  
Registration Provider: Energysoft Schema Version: rev 20200601  
Report Generated: 2022-07-27 11:06:19

L. DISTRIBUTION (DUCTWORK AND PIPING)		
This table is used to show compliance with mandatory pipe insulation requirements found in §140.3 and prescriptive requirements found in §140.4(f) for duct leakage testing.		
Duct Leakage Sealing		
The answers to the questions below apply to the following duct systems: RTU-D2 Duct leakage testing triggered for these systems? No		
11	No	The scope of the project includes only duct systems serving healthcare facilities
12	Yes	Duct system provides conditioned air to an occupiable space for a constant volume, single zone, space-conditioning system.
13	Yes	The space conditioning system serves less than 5,000 ft <sup>2</sup> of conditioned floor area.
14	No	The combined surface area of the ducts in the following locations is more than 25% of the total surface area of the entire duct system: Outdoors <input type="checkbox"/> In a space directly under a roof that has a U-factor greater than the u-factor of the ceiling, or if the roof does not meet the requirements of §140.3(a)18 or if the roof has fixed vents or openings to the outside/unconditioned spaces <input type="checkbox"/> In an unconditioned crawl space
15		The scope of the project includes extending an existing duct system, which is constructed, insulated or sealed with asbestos.
16		The scope of the project includes an existing duct system that is documented to have been previously sealed as confirmed through field verification and diagnostic testing in accordance with procedures in the Reference Nonresidential Appendix NA2.
17	Yes	Duct system shall be sealed in accordance with the California Mechanical Code
The answers to the questions below apply to the following duct systems: RTU-D3 Duct leakage testing triggered for these systems? No		
11	No	The scope of the project includes only duct systems serving healthcare facilities
12	Yes	Duct system provides conditioned air to an occupiable space for a constant volume, single zone, space-conditioning system.
13	Yes	The space conditioning system serves less than 5,000 ft <sup>2</sup> of conditioned floor area.
14	No	The combined surface area of the ducts in the following locations is more than 25% of the total surface area of the entire duct system: Outdoors <input type="checkbox"/> In a space directly under a roof that has a U-factor greater than the u-factor of the ceiling, or if the roof does not meet the requirements of §140.3(a)18 or if the roof has fixed vents or openings to the outside/unconditioned spaces <input type="checkbox"/> In an unconditioned crawl space

Registration Number: CA Building Energy Efficiency Standards - 2019 Nonresidential Compliance  
Registration Date/Time: Report Version: 2019.1.003  
Registration Provider: Energysoft Schema Version: rev 20200601  
Report Generated: 2022-07-27 11:06:19

1

2

3

4

5







STATE OF CALIFORNIA  
**Mechanical Systems**  
 NRCC-MCH-E CALIFORNIA ENERGY COMMISSION

**CERTIFICATE OF COMPLIANCE** NRCC-MCH-E  
 Project Name: CVUSD Grovescenter Report Page: (Page 37 of 42)  
 Project Address: 775 N Lark Ellen Ave Date Prepared: 7/27/2022

**D. DECLARATION OF REQUIRED CERTIFICATES OF ACCEPTANCE**  
 Selections have been made based on information provided in previous tables of this document. If any selection needs to be changed, please explain why in Table E Additional Remarks. These documents must be provided to the building inspector during construction and can be found online at https://www.energy.ca.gov/title24/2019standards/2019\_compliance\_documents/Nonresidential\_Documents/NRCA/

Form/Title	Systems/Spaces To Be Field Verified	Field Inspector	
		Pass	Fail
NRCA-MCH-05-A - Air Economizer Controls	RTU-C1 CARRIER 3-TON; RTU-C2 CARRIER 3-TON;	<input type="checkbox"/>	<input type="checkbox"/>
NRCA-MCH-06-A Demand Control Ventilation Systems must be submitted for all systems required to employ demand controlled ventilation (refer to §120.1(c)(3) can vary outside ventilation flow rates based on maintaining interior carbon dioxide (CO <sub>2</sub> ) concentration setpoints.	FCU/CLU-B1A & B1B; RTU-C1 CARRIER 3-TON; RTU-C2 CARRIER 3-TON; RTU-D1 CARRIER 3-TON; RTU-D2 CARRIER 3-TON; RTU-D3 CARRIER 3-TON; RTU-D4 CARRIER 3-TON; RTU-E1 CARRIER 3-TON; RTU-E2 CARRIER 3-TON; RTU-E3 CARRIER 3-TON; RTU-E4 CARRIER 3-TON; RTU-F1 CARRIER 3-TON; RTU-F2 CARRIER 3-TON; RTU-F3 CARRIER 3-TON; RTU-F4 CARRIER 3-TON; RTU-G1 CARRIER 3-TON; RTU-G2 CARRIER 3-TON; RTU-G3 CARRIER 3-TON; RTU-G4 CARRIER 3-TON;	<input type="checkbox"/>	<input type="checkbox"/>

Registration Number: CA Building Energy Efficiency Standards - 2019 Nonresidential Compliance  
 Registration Date/Time: Report Version: 2019.1.003 Schema Version: rev 20200601  
 Registration Provider: Energysoft  
 Report Generated: 2022-07-27 11:06:19

STATE OF CALIFORNIA  
**Mechanical Systems**  
 NRCC-MCH-E CALIFORNIA ENERGY COMMISSION

**CERTIFICATE OF COMPLIANCE** NRCC-MCH-E  
 Project Name: CVUSD Grovescenter Report Page: (Page 40 of 42)  
 Project Address: 775 N Lark Ellen Ave Date Prepared: 7/27/2022

**O. DECLARATION OF REQUIRED CERTIFICATES OF ACCEPTANCE**  
 Selections have been made based on information provided in previous tables of this document. If any selection needs to be changed, please explain why in Table E Additional Remarks. These documents must be provided to the building inspector during construction and can be found online at https://www.energy.ca.gov/title24/2019standards/2019\_compliance\_documents/Nonresidential\_Documents/NRCA/

Form/Title	Systems/Spaces To Be Field Verified	Field Inspector	
		Pass	Fail
NRCA-MCH-18-A Energy Management Control Systems	FCU/CLU-B1A & B1B; RTU-C1 CARRIER 3-TON; RTU-C2 CARRIER 3-TON; RTU-D1 CARRIER 3-TON; RTU-D2 CARRIER 3-TON; RTU-D3 CARRIER 3-TON; RTU-D4 CARRIER 3-TON; RTU-E1 CARRIER 3-TON; RTU-E2 CARRIER 3-TON; RTU-E3 CARRIER 3-TON; RTU-E4 CARRIER 3-TON; RTU-F1 CARRIER 3-TON; RTU-F2 CARRIER 3-TON; RTU-F3 CARRIER 3-TON; RTU-F4 CARRIER 3-TON; RTU-G1 CARRIER 3-TON; RTU-G2 CARRIER 3-TON; RTU-G3 CARRIER 3-TON; RTU-G4 CARRIER 3-TON;	<input type="checkbox"/>	<input type="checkbox"/>

**P. DECLARATION OF REQUIRED CERTIFICATES OF VERIFICATION**  
 There are no NRCV forms required for this project.

Registration Number: CA Building Energy Efficiency Standards - 2019 Nonresidential Compliance  
 Registration Date/Time: Report Version: 2019.1.003 Schema Version: rev 20200601  
 Registration Provider: Energysoft  
 Report Generated: 2022-07-27 11:06:19

STATE OF CALIFORNIA  
**Mechanical Systems**  
 NRCC-MCH-E CALIFORNIA ENERGY COMMISSION

**CERTIFICATE OF COMPLIANCE** NRCC-MCH-E  
 Project Name: CVUSD Grovescenter Report Page: (Page 38 of 42)  
 Project Address: 775 N Lark Ellen Ave Date Prepared: 7/27/2022

**D. DECLARATION OF REQUIRED CERTIFICATES OF ACCEPTANCE**  
 Selections have been made based on information provided in previous tables of this document. If any selection needs to be changed, please explain why in Table E Additional Remarks. These documents must be provided to the building inspector during construction and can be found online at https://www.energy.ca.gov/title24/2019standards/2019\_compliance\_documents/Nonresidential\_Documents/NRCA/

Form/Title	Systems/Spaces To Be Field Verified	Field Inspector	
		Pass	Fail
NRCA-MCH-11-A Automatic Demand Shed Controls	FCU/CLU-B1A & B1B; RTU-C1 CARRIER 3-TON; RTU-C2 CARRIER 3-TON; RTU-D1 CARRIER 3-TON; RTU-D2 CARRIER 3-TON; RTU-D3 CARRIER 3-TON; RTU-D4 CARRIER 3-TON; RTU-E1 CARRIER 3-TON; RTU-E2 CARRIER 3-TON; RTU-E3 CARRIER 3-TON; RTU-E4 CARRIER 3-TON; RTU-F1 CARRIER 3-TON; RTU-F2 CARRIER 3-TON; RTU-F3 CARRIER 3-TON; RTU-F4 CARRIER 3-TON; RTU-G1 CARRIER 3-TON; RTU-G2 CARRIER 3-TON; RTU-G3 CARRIER 3-TON; RTU-G4 CARRIER 3-TON;	<input type="checkbox"/>	<input type="checkbox"/>

Registration Number: CA Building Energy Efficiency Standards - 2019 Nonresidential Compliance  
 Registration Date/Time: Report Version: 2019.1.003 Schema Version: rev 20200601  
 Registration Provider: Energysoft  
 Report Generated: 2022-07-27 11:06:19

STATE OF CALIFORNIA  
**Mechanical Systems**  
 NRCC-MCH-E CALIFORNIA ENERGY COMMISSION

**CERTIFICATE OF COMPLIANCE** NRCC-MCH-E  
 Project Name: CVUSD Grovescenter Report Page: (Page 41 of 42)  
 Project Address: 775 N Lark Ellen Ave Date Prepared: 7/27/2022

**Q. MANDATORY MEASURES DOCUMENTATION LOCATION**  
 This table is used to indicate where mandatory measures are documented in the plan set or construction documentation.

01	02
Compliance with Mandatory Measures documented through MCH	Yes
Mandatory Measures Note Block	M-Sheets

Registration Number: CA Building Energy Efficiency Standards - 2019 Nonresidential Compliance  
 Registration Date/Time: Report Version: 2019.1.003 Schema Version: rev 20200601  
 Registration Provider: Energysoft  
 Report Generated: 2022-07-27 11:06:19

STATE OF CALIFORNIA  
**Mechanical Systems**  
 NRCC-MCH-E CALIFORNIA ENERGY COMMISSION

**CERTIFICATE OF COMPLIANCE** NRCC-MCH-E  
 Project Name: CVUSD Grovescenter Report Page: (Page 39 of 42)  
 Project Address: 775 N Lark Ellen Ave Date Prepared: 7/27/2022

**D. DECLARATION OF REQUIRED CERTIFICATES OF ACCEPTANCE**  
 Selections have been made based on information provided in previous tables of this document. If any selection needs to be changed, please explain why in Table E Additional Remarks. These documents must be provided to the building inspector during construction and can be found online at https://www.energy.ca.gov/title24/2019standards/2019\_compliance\_documents/Nonresidential\_Documents/NRCA/

Form/Title	Systems/Spaces To Be Field Verified	Field Inspector	
		Pass	Fail
NRCA-MCH-16-A Supply Air Temperature Reset Controls	FCU/CLU-B1A & B1B; RTU-C1 CARRIER 3-TON; RTU-C2 CARRIER 3-TON; RTU-D1 CARRIER 3-TON; RTU-D2 CARRIER 3-TON; RTU-D3 CARRIER 3-TON; RTU-D4 CARRIER 3-TON; RTU-E1 CARRIER 3-TON; RTU-E2 CARRIER 3-TON; RTU-E3 CARRIER 3-TON; RTU-E4 CARRIER 3-TON; RTU-F1 CARRIER 3-TON; RTU-F2 CARRIER 3-TON; RTU-F3 CARRIER 3-TON; RTU-F4 CARRIER 3-TON; RTU-G1 CARRIER 3-TON; RTU-G2 CARRIER 3-TON; RTU-G3 CARRIER 3-TON; RTU-G4 CARRIER 3-TON;	<input type="checkbox"/>	<input type="checkbox"/>

Registration Number: CA Building Energy Efficiency Standards - 2019 Nonresidential Compliance  
 Registration Date/Time: Report Version: 2019.1.003 Schema Version: rev 20200601  
 Registration Provider: Energysoft  
 Report Generated: 2022-07-27 11:06:19

STATE OF CALIFORNIA  
**Mechanical Systems**  
 NRCC-MCH-E CALIFORNIA ENERGY COMMISSION

**CERTIFICATE OF COMPLIANCE** NRCC-MCH-E  
 Project Name: CVUSD Grovescenter Report Page: (Page 42 of 42)  
 Project Address: 775 N Lark Ellen Ave Date Prepared: 7/27/2022

**DOCUMENTATION AUTHOR'S DECLARATION STATEMENT**  
 I certify that this Certificate of Compliance documentation is accurate and complete.

Documentation Author Name: Tong Fang Zhao  
 Signature Date: 2022-07-27  
 Company: DLR Group  
 Address: 700 FLOWER STREET, LOS ANGELES CA 90017  
 City/State/Zip: LOS ANGELES CA 90017

**RESPONSIBLE PERSON'S DECLARATION STATEMENT**  
 I certify the following under penalty of perjury under the laws of the State of California:  
 1. The information provided on this Certificate of Compliance is true and correct.  
 2. I am eligible under Division 3 of the Business and Professions Code to accept responsibility for the building design or system design identified on this Certificate of Compliance (responsible designer).  
 3. The energy features and performance specifications, materials, components, and manufactured devices for the building design or system design identified on this Certificate of Compliance conform to the requirements of Title 24, Part 1 and Part 6 of the California Code of Regulations.  
 4. The building design features or system design features identified on this Certificate of Compliance are consistent with the information provided on other applicable compliance documents, worksheets, calculations, plans and specifications submitted to the enforcement agency for approval with this building permit application.  
 5. I will ensure that a completed signed copy of this Certificate of Compliance shall be made available with the building permit(s) issued for the building, and made available to the enforcement agency for all applicable inspections. I understand that a completed signed copy of this Certificate of Compliance is required to be included with the documentation the builder provides to the building owner at occupancy.

Responsible Designer Name: Tong Fang Zhao  
 Signature Date: 2022-07-27  
 Company: DLR GROUP  
 Address: 700 FLOWER STREET, LOS ANGELES CA 90017  
 City/State/Zip: LOS ANGELES CA 90017

Registration Number: CA Building Energy Efficiency Standards - 2019 Nonresidential Compliance  
 Registration Date/Time: Report Version: 2019.1.003 Schema Version: rev 20200601  
 Registration Provider: Energysoft  
 Report Generated: 2022-07-27 11:06:19



Grovescenter Elementary School  
 COVINA VALLEY USD  
 775 N LARK ELLEN AVE, WEST COVINA, CA 91791

100% CONSTRUCTION DOCUMENTS  
 11/08/2022 REVISIONS

TITLE 24 COMPLIANCE

M0.6

Autodesk Docs/775-22605-00 CVUSD - District Wide HVAC Replacement/75-22605-00 CVUSD\_Grovescenter\_ES MEP\_2022.rvt  
 10/21/2022 4:45:38 PM



A

B

C

D

E

F

1

2

3

4



5



**MECHANICAL OVERALL PLAN**  
 SCALE: 1" = 20'-0"

**GENERAL NOTES**  
 A FOR SYMBOLS AND ABBREVIATIONS SEE DRAWING M0.1

**SITE LEGEND**

-  EXISTING BUILDING - SCOPE OF WORK UNDER THIS DSA APPLICATION
-  (E) RESTROOMS - NOT IN SCOPE



**Groves Center Elementary School**  
 COVINA VALLEY USD  
 775 N LARK ELLER AVE, WEST COVINA, CA 91791

100%  
 CONSTRUCTION  
 DOCUMENTS  
 11/08/2022  
 REVISIONS


77-22605-00

OVERALL  
 MECHANICAL  
 SITE PLAN


**M1.1**

Autodesk Docs://75-22605-00\_CVUSD - District Wide HVAC Replacement/75-22605-00\_CVUSD\_GrovesCenter ES MEP\_2022.rvt  
 10/21/2022 4:55:37 PM







1 LEVEL 01 - AREA B - HVAC PLAN  
M1.1C / SCALE: 1/8" = 1'-0"




2 BUILDING C MECHANICAL FLOOR PLAN  
M1.1C / SCALE: 1/8" = 1'-0"




3 BUILDING D MECHANICAL FLOOR PLAN  
M1.1C / SCALE: 1/8" = 1'-0"



4 BUILDING E MECHANICAL FLOOR PLAN  
M1.1C / SCALE: 1/8" = 1'-0"



5 BUILDING F MECHANICAL FLOOR PLAN  
M1.1C / SCALE: 1/8" = 1'-0"



6 BUILDING G MECHANICAL FLOOR PLAN  
M1.1C / SCALE: 1/8" = 1'-0"

DEMO NOTES

- A. DEMOLISH EXISTING OUTDOOR CONDENSING UNIT AND INDOOR FAN/CL. UNITS, ALONG WITH RELATED CONCRETE PADS, PIPING, CONDUIT, FENCE, SUPPORTS AND OTHER APPURTENANCES. REFER TO ARCH PLANS OR SPECS FOR FILLING HOLES AND MATCHING WALL TYP.

GENERAL NOTES

- 1. SCOPE OF WORK IS CLASSROOMS & MPR ONLY.
- 2. DIFFUSERS AND GRILLES TO MATCH (E) CEILING TILES. REFER TO RCP.



Grovecenter Elementary School  
COVINA VALLEY USD  
775 N. LARK ELLIEN AVE. WEST COVINA, CA 91791

100% CONSTRUCTION DOCUMENTS  
11/08/2022 REVISIONS


77-22605-00

MECHANICAL FLOOR PLANS

M1.1C


Autodesk Docs/775-22605-00\_CVUSD - District Wide HVAC Replacement/75-22605-00\_CVUSD\_Grovecenter ES MEP\_2022.rvt 10/21/2022 4:55:41 PM





Autodesk Docs/775-22605-00\_CVUSD - District Wide HVAC Replacement/75-22605-00\_CVUSD\_Grovecenter ES MEP\_2022.rvt  
 10/21/2022 4:35:44 PM

- GENERAL HVAC NOTES**
- INSTALL NEW RTU ON PLATFORM.
  - ALL ROOFTOP UNITS SHALL BE PROVIDED WITH UNPOWERED CONVENIENCE OUTLET.
  - DISCONNECTING MEANS TO BE NEMA 3R RATED. FURNISHED BY HVAC EQUIPMENT MANUFACTURER AND INSTALLED UNDER DIVISION 26.
  - NEW OPENINGS FOR SUPPLY AND RETURN DUCTS SHOULD BE MADE BETWEEN THE ROOF JOISTS. DO NOT CUT THE JOISTS.
  - PROVIDE FLEXIBLE DUCT AT UNIT CONNECTION FOR SA & RA DUCT.
- KEY NOTES**
- PROVIDE POWER EXHAUST ON RETURN DUCT WITH LEG LENGTH TO FIT THE ROOF SLOPE. CONTRACTOR TO VERIFY ON SITE. TYP.
  - RTU TO BE 16'-0" MIN. FROM ROOF EDGE. CONTRACTOR TO VERIFY ON SITE. TYP.
  - RTU IS LESS THAN 10'-0" FROM ROOF EDGE. ARCH TO PROVIDE PROTECTION GUARDS. TYP.



**Grovecenter Elementary School**  
 COVINA VALLEY USD  
 775 N LARK ELLIEN AVE. WEST COVINA, CA 91791

100% CONSTRUCTION DOCUMENTS  
 11/08/2022 REVISIONS

77-22605-00  
 MECHANICAL ROOF PLANS

**M1.3C**



1  
2  
3  
4  
5

A


B

C

D

E

F



1 BACS RISER DIAGRAM  
 M5.1 NO SCALE



**Grovecenter Elementary School**  
 COVINA VALLEY USD  
 775 N LARK ELLERAYE, WEST COVINA, CA 91791

100% CONSTRUCTION DOCUMENTS  
 11/08/2022  
 REVISIONS

77-22605-00

CONTROLS DIAGRAMS

M5.1

Autodesk Docs://75-22605-00\_CVUSD - District Wide HVAC Replacement/75-22605-00\_CVUSD\_Grovecenter ES MEP\_2022.rvt  
 10/21/2022 4:55:44 PM



**SEQUENCES OF OPERATION**

**SEQUENCE OF OPERATION FOR CVUSD GROVECENTER ES**

**HEAT PUMP RTU CONTROLLER (RTU-C1 THRU RTU-C4, RTU- D1 THRU RTU-D4, RTU-E1 THRU RTU-E4, RTU-F1 THRU RTU-F4, AND RTU-G1 THRU RTU-G4)**

**INDOOR FAN**

THE FAN OPERATES AT A VARIABLE SPEED TO MEET THE LOAD CONDITIONS AND SAT SAFETY REQUIREMENTS TO PROVIDE MAXIMUM ENERGY SAVINGS BY MINIMIZING FAN HORSEPOWER CONSUMPTION. FAN SPEED IS NOT CONTROLLED BY STATIC PRESSURE.

**HEATING MODE**

WHEN SPACE TEMPERATURE IS BELOW THE OCCUPIED HEATING SETPOINT, UNIT SHALL OPERATE IN THE HEATING MODE. UNIT SHALL STAGE AVAILABLE HEAT STAGES TO SATISFY DEMAND IN THE OCCUPIED SPACE.

**COOLING MODE**


WHEN SPACE TEMPERATURE IS ABOVE OCCUPIED COOLING SETPOINT, UNIT SHALL OPERATE IN THE COOLING MODE. UNIT SHALL ENABLE AVAILABLE COOLING STAGES TO SATISFY DEMAND IN THE OCCUPIED SPACE.

**CO2 CONTROL**

UNIT SHALL MONITOR SPACE CO2 WHEN THE SUPPLY FAN IS ENERGIZED. WHEN CO2 IS ABOVE SETPOINT OF 1000 PPM, AN ALARM SHALL BE ENABLED THROUGH THE EMS.

**POWER EXHAUST**


THE EXHAUST FAN SHALL RUN WHEN THE UNIT IS OCCUPIED



50FCQ HEAT PUMP DETAIL (RTU-C1 THRU RTU-C4, RTU- D1 THRU RTU-D4, RTU-E1 THRU RTU-E4, RTU-F1 THRU RTU-F4, AND RTU-G1 THRU RTU-G4)

SCALE	1
NONE	


2  
M5.2  
DETAIL  
NO SCALE



SPLIT SYSTEM DETAIL (FCU/CU-B1)

SCALE	2
NONE	

1  
M5.2  
DETAILS  
NO SCALE



Grovecenter Elementary School  
COVINA VALLEY USD  
775 N LARK ELLER AVE, WEST COVINA, CA 91791

100%  
CONSTRUCTION  
DOCUMENTS  
11/08/2022  
REVISIONS


77-22605-00

CONTROLS  
DIAGRAMS


M5.2




1  
2  
3  
4  
5




5 DUCT THRU ROOF PENETRATION  
M7.1 NO SCALE




9 CONDENSATE DRAIN CONNECTION DETAIL  
M7.1 NO SCALE




2 DUCT SUPPORT ON ROOF DETAIL  
M7.1 NO SCALE




6 PIPE SUPPORT ON ROOF DETAIL  
M7.1 NO SCALE




8 RECTANGULAR ELBOW W/ TURNING VANES DETAIL  
M7.1 NO SCALE




3 ECONOMIZER AND POWER EXHAUST DETAIL - HORIZONTAL DISCHARGE RTU (LESS THAN 15 TONS)  
M7.1 NO SCALE




11 RECTANGULAR VOLUME DAMPER DETAIL  
M7.1 NO SCALE




4 ROUND VOLUME DAMPER (LARGER THAN 14\"/>



1 THERMOSTAT MOUNTING  
M7.1 NO SCALE



7 ACOUSTICAL DUCT LINING INSTALLATION DETAIL  
M7.1 NO SCALE







10 FLEXIBLE DUCT CONNECTION  
M7.1 NO SCALE

Autodesk Docs/175-22605-00\_CVUSD - District Wide HVAC Replacement/175-22605-00\_CVUSD\_Grovercenter ES MEP\_2022.rvt  
 10/21/2022 4:55:45 PM



1  
2  
3  
4  
5  
9







1 CEILING SUPPLY DIFFUSER CONNECTION DETAIL  
M7.2 NO SCALE

2 ROUND DUCT BRANCH TO MAIN RECT. CONNECTION  
M7.2 NO SCALE

3 RECTANGULAR DUCT BRANCH TO RECTANGULAR DUCT  
M7.2 NO SCALE

4 ROUND DUCT BRANCH TO ROUND MAIN CONNECTION  
M7.2 NO SCALE






5 DRY WELL DETAIL  
M7.2 NO SCALE

6 BOWDEN TYPE CABLE CONTROL (YOUNG'S REGULATOR)  
M7.2 NO SCALE

7 ROUND DUCT FITTINGS  
M7.2 NO SCALE

8 ROUND SUPPLY DUCT BRANCH TO RECTANGULAR DUCT  
M7.2 NO SCALE



9 DUCT SUPPORT IN CEILING SPACE  
M7.2 NO SCALE

10 DUCT SUPPORTS  
M7.2 NO SCALE

11 PIPE THRU WALL PENETRATION DETAIL  
M7.2 NO SCALE

Autodesk Docs/175-22605-00\_CVUSD - District Wide HVAC Replacement/175-22605-00\_CVUSD\_Grovecenter ES MEP\_2022.rvt  
11/21/2022 4:55:48 PM



MARK	MAKE	MODEL	STEEL FRAME
FCU-B1	CARRIER	4GRUAQ-16	ASTM A36, L 3 X 3 X 1/4

### DETAIL-1

UNIT OUTLINE

TE-DOWN STRAPS AS SHOWN

LEVELLING BOLT 3/8 DIA. & ATTACHMENT OF STEEL BASE TO SPRING ISOLATOR, SEE DETAIL-2

**NOTES:**  
 1. APPROX. STEEL WEIGHT INCLUDING ISOLATORS.: 200 LBS.  
 2. — INDICATES TIE-DOWN STRAP. SEE DETAIL 3.  
 3. ALL DIMENSIONS REQUIRE FINAL REVIEW AT COMMENCEMENT OF PROJECT.

### DETAIL-3

ATTACHMENT OF SPRING ISOLATORS TO CONCRETE PAD ON GRADE

9/16" DIA. HOLE (2) PLACES  
 USE 1/2" DIA. HILTI KB T22 ANCHORS IN 3000 PSI HR CONCRETE, MIN 3" NORMAL EMBEDMENT, MIN 6" CONCRETE THICKNESS & MIN 6" EDGE DISTANCE. INSTALL ANCHORS WITH SPECIAL INSPECTION PER ICC ESR-4266.

MAX. ALLOW. LOADS: HORIZ. 1100 lbs. VERT. (UP) 1400 lbs.

~~REV-02-22-1~~

TIE DOWN STRAP DETAIL

ATTACHMENT OF UNIT TO STEEL BASE

### DETAIL-2

VIEW A-A

VIEW B-B

LEVELLING BOLT 3/8 DIA. & ATTACHMENT OF STEEL BASE TO SPRING ISOLATOR

APPROX. OPER. HT. 1 1/2 - 3 - 3/4

ASTM A36, L 3 X 3 X 1/4

NOTCH @ EA ISOLATOR LOCATION

<b>M. W. SAUSSE &amp; CO., INC.</b> 28744 Whitherspoon Pkwy, Valencia, CA 91355 Phone: (661) 257-3311 Fax: (661) 257-7673 	<b>JOB NAME:</b> COVINA USD - GROVECENTER	<b>REVISIONS:</b>	<b>DRN:</b> TDT
	<b>CUST.:</b>	<b>A:</b> CALL OUT ALL ATTACHMENTS (9-2-22)	<b>DATE:</b> 7-25-22
	<b>CUST. P.O.:</b>	<b>B:</b> SPECS ANGLE (9-20-22)	<b>DRAWING NO.:</b>
	<b>MECH. ENGR.:</b> DLRG <b>MARK:</b> FCU-B1 (HORIZONTAL)	<b>C:</b> <b>D:</b>	-2B

1 FCU-B1  
M7.3 NO SCALE



<b>MARK</b> CU-B1	<b>MAKE</b> TOSHIBA	<b>MODEL</b> MMY-AP1925	<b>STEEL FRAME</b> ASTM A36, L 4 X 3 X 1/4	<b>DETAIL-1</b>		<b>MTG</b> 1-6	<b>SPRING CO.</b> 4"	<b>DEFL.</b> 2"
----------------------	------------------------	----------------------------	---	-----------------	--	-------------------	-------------------------	--------------------

**DETAIL-1**

ASTM A36, L 4 X 3 X 1/4

9/16" DIA. HOLE (8)  
USE 1/2" DIA. NR. A-307

LEVELLING BOLT 1/2" DIA.  
& ATTACHMENT OF STEEL BASE  
TO SPRING ISOLATOR, SEE DETAIL-2

**NOTES:**

- APPROX. STEEL WEIGHT INCLUDING ISOLATORS: 450 LBS.
- FOR ISOLATORS. SEE DETAIL 3.
- M.W. SAUSSE & CO. INC. IS NOT RESPONSIBLE FOR THE STRUCTURAL INTEGRITY OF THE EQUIPMENT WHEN ANCHORED AS SHOWN.
- NOT FOR CONSTRUCTION, ALL DIMENSIONS REQUIRE FINAL REVIEW AT COMMENCEMENT OF PROJECT.

**DETAIL-3**

ATTACHMENT OF SPRING ISOLATORS TO CONCRETE PAD ON GRADE

1 1/8" DIA. HOLE (2) PLATES  
USE 5/8" DIA. STAINLESS HILTI HB 122 ANCHORS IN MIN 3000 PSI HR CONCRETE,  
MIN 3-1/4" NOMINAL EMBEDMENT, MIN 4" CONCRETE THICKNESS & MIN  
6" EDGE DISTANCE. INSTALL ANCHORS WITH SPECIAL INSPECTION PER ICC ESR-1286.

MAX. ALLOW. LOADS: HORIZ: 2200 LBS      VERT. (UP): 2820 LBS

**DETAIL-2**

LEVELLING BOLT 1/2" DIA.  
& ATTACHMENT OF STEEL BASE  
TO SPRING ISOLATOR

9/16" DIA. HOLE

ASTM A36, L 4 X 3 X 1/4

5-7/8 OPER. HT.

VIEW A-A      VIEW B-B

<b>M. W. SAUSSE &amp; CO., INC.</b> 28744 Whitherspoon Pkwy. Valencia, CA 91355 Phone: (661) 257-3311 Fax: (661) 257-7673	<b>JOB NAME:</b> COVINA USD - GROVECENTER ES	<b>REVISIONS:</b>	<b>DRN:</b> TDT
	<b>CUST.:</b>	<b>A:</b> CALL OUT ALL ATTACHMENT (9-2-22)	<b>DATE:</b> 9-7-22
	<b>CUST. P.O.:</b>	<b>B:</b> CHANGED UNIT (9-6-22)	<b>DRAWING NO.:</b>
	<b>MECH. ENGR.:</b> DLR	<b>C:</b> SPECS ANGLE (9-20-22)	-1C
<b>MARK:</b> CU-B1	<b>D:</b>		

1 CU-B1  
M7.4 NO SCALE



**DETAIL-1**

**DETAIL-2**

**DETAIL-3**

MARK	MAKE	TYPE	SIZE	CURB WT.
3 TON	CARRIER	50FCQA	04	275#

**SRC TOP VIEW**

A	B	C	D	E	F	G	H	I	J	K	L	M
36-15/16	67-1/8	40-7/8	70-5/8	20-1/4	13-11/16	13-7/8	15-3/16	32-1/16				

**SRC FOOTPRINT**

**SECTION A-A**

**NOTES:**

- FOR ANCHOR REQUIREMENTS AND SEISMIC STRAPS, SEE DETAIL 2, 3.
- ROOF SLOPE TO BE VERIFIED BY CONTRACTOR BEFORE FABRICATION & ROOF CURB HEIGHT ARE APPROXIMATE.
- NOT FOR CONSTRUCTION, ALL DIMENSIONS REQUIRE FINAL REVIEW AT COMMENCEMENT OF PROJECT

**NOTES:**

- L & M DIMENSIONS ARE CENTERLINES OF ANCHOR HOLES IN CURB BOTTOM FLANGE.
- FOR ANCHORAGE, USE 3/8" DIA. LAG BOLT MIN. 3" LONG INTO MIN. 4 x 4 DOUGLAS FIR, MIN 1-1/2" EDGE DISTANCE, & MIN 2-5/8" END DISTANCE. (3) ON LONG SIDES & (2) ON SHORT SIDES.

**M. W. SAUSSÉ & CO., INC.**  
26744 Whitherspoon Pkwy, Valencia, CA 91355  
Phone: (861) 257-3311 Fax: (861) 257-7873

**Vibrex SRC**

<b>JOB NAME:</b> COVINA USD	<b>REGISTERED PROFESSIONAL ENGINEER</b> M. W. SAUSSÉ No. 56487 STATE OF CALIFORNIA	<b>REVISIONS:</b>	<b>DRN:</b> TDT
<b>CUST. P.O.:</b> 10/19/2022		A	<b>DATE:</b> 7-25-22
<b>MECH. ENGR.:</b> DLR		B	<b>DRAWING NO.:</b>
<b>MARK:</b> 3 TON		C	-3
		D	

1 RTU CURB  
M7.5 NO SCALE

Autodesk Docs/775-22605-00\_COVUSD - District Wide HVAC Replacement/775-22605-00\_COVUSD\_Grovecenter ES MEP\_2022.rvt 10/21/2022 4:56:47 PM






1

2


3

4

5



1 DEMO HVAC PLAN MECHANICAL ROOM - BUILDING B  
 MD1.1 SCALE: 1/4" = 1'-0"



2 DEMO HVAC SECTION MECHANICAL ROOM - BUILDING B  
 MD1.1 SCALE: 1/4" = 1'-0"

DEMO NOTES  
 A. DEMO (E) EQUIPMENT AND SA & RA DUCTWORK IN THE SCOPE AREA UP TO POD, ALONG WITH ALL THE SUPPORTS, PIPING, OTHER COMPONENTS.



Grovescenter Elementary School  
 COVINA VALLEY USD  
 775 N LARK ELLIEN AVE, WEST COVINA, CA 91791

100% CONSTRUCTION DOCUMENTS  
 11/08/2022 REVISIONS

77-22605-00

MECHANICAL DEMOLITION PLANS

MD1.1

A

B

C

D

E

F

1

2

3

4

5



**GENERAL NOTE:**  
 1. ALL CONDENSATE WATER PIPING FOR MFR ROOM TO DRAIN TO CLOSEST EXISTING FLOOR SINK.

**SITE LEGEND**

	EXISTING BUILDING NOT IN SCOPE
	EXISTING BUILDING - SCOPE OF WORK UNDER THIS ESA APPLICATION
	(E) RESTROOMS - NOT IN SCOPE




**Grovescenter Elementary School**  
 COVINA VALLEY USD  
 775 N LARK ELLERAY AVE, WEST COVINA, CA 91791

100%  
 CONSTRUCTION  
 DOCUMENTS  
 11/08/2022  
 REVISIONS

77-22605-00

MECHANICAL  
 PLUMBING SITE  
 PLAN

MP1.1



**MECHANICAL PLUMBING SITE PLAN**  
 SCALE: 1" = 20'-0"

Autodesk Docs/775-22605-00\_CVUSD - District Wide HVAC Replacement/775-22605-00\_CVUSD\_Grovescenter ES MEP\_2022.rvt  
 10/21/2022 4:55:48 PM




**SHEET INDEX**

E0.1	ELECTRICAL SYMBOLS, ABBREVIATIONS & NOTES
E.2.1	ELECTRICAL ROOF POWER PLAN
E.5.1	ELECTRICAL DIAGRAMS AND SCHEDULES
E.6.1	ELECTRICAL DETAILS

**GENERAL NOTES**

- PENETRATIONS IN WALLS REQUIRING PROTECTED OPENINGS MUST BE FIRESTOPPED WITH AN APPROVED MATERIAL.
- UNLESS SPECIFICALLY SHOWN ON THESE DRAWINGS, NO STRUCTURAL MEMBER SHALL BE CUT, DRILLED, OR NOTCHED WITHOUT PRIOR AUTHORIZATION IN WRITING BY THE STRUCTURAL ENGINEER OF RECORD AND DSA.



**POWER**

- CIRCUIT HOME RUN
- CONDUIT TURNING UP
- CONDUIT TURNING DOWN
- CONDUIT STUB-UP
- CONDUIT SLEEVE
- CONDUIT SEAL
- CONDUIT CONCEALED IN CEILING OR WALLS, POWER
- CONDUIT CONCEALED IN CEILING OR WALLS, OTHER (\* = SEE ABBREVIATIONS)
- CONDUIT CONCEALED IN FLOOR OR UNDERGROUND, POWER
- CONDUIT CONCEALED IN FLOOR OR UNDERGROUND, OTHER (\* = SEE ABBREVIATIONS)
- EXPOSED CONDUIT, POWER
- EXPOSED CONDUIT, OTHER (\* = SEE ABBREVIATIONS)
- FIRE RATED SLEEVE
- TRANSFORMER
- BRANCH CIRCUIT PANELBOARD MOUNT 72-INCHES TO TOP
- DISTRIBUTION PANELBOARD MOUNT 72-INCHES TO TOP
- EQUIPMENT CABINET, AS NOTED
- SWITCHBOARD
- MOTOR STARTER OR DRIVE
- DISCONNECT SWITCH
- COMBINATION STARTER / DISCONNECT SWITCH
- CURRENT TRANSFORMER ENCLOSURE
- METER
- GENERATOR
- AUTOMATIC TRANSFER SWITCH
- SYSTEM GROUND ELECTRODE
- THERMOSTAT
- MUSHROOM SWITCH
- ELECTRICAL MANHOLE
- ELECTRICAL HAND HOLE
- MOTOR CONNECTION, HORSEPOWER AS INDICATED
- FUSE AND SWITCH ASSEMBLY
- MANUAL CONTROLLER WITH THERMAL OVERLOAD
- MANUAL CONTROLLER W/O THERMAL OVERLOAD
- CIRCUIT BREAKER ENCLOSURE
- PULL BOX
- EQUIPMENT CONNECTION
- CABLE TRAY, LADDER TYPE OR RUNWAY
- CABLE TRAY
- MULTI-OUTLET ASSEMBLIES MOUNT 18-INCHES AFF, UNO WHERE DENOTED 'AC', MOUNT ABOVE COUNTER
- DIVIDED SURFACE RACEWAY MOUNT 18-INCHES AFF, UNO WHERE DENOTED 'AC', MOUNT ABOVE COUNTER
- PUSHBUTTON STATION: MOUNT 42-INCHES AFF UNO
  - SWITCH, PUSH BUTTON, SINGLE
  - SWITCH, PUSH BUTTON, DOUBLE
  - SWITCH, PUSH BUTTON, TRIPLE

**RECEPTACLES: MOUNT 18-INCHES AFF, UNO**

- DIAGONAL LINE THROUGH SYMBOL OR DENOTED 'AC' INDICATES MOUNT DEVICE ABOVE COUNTER WHERE INDICATED AS 'MOUNT ABOVE COUNTER' MOUNT BOTTOM OF BOX 2-INCHES ABOVE TOP OF BACKSPLASH OR 6-INCHES ABOVE COUNTER TOP IF NO BACKSPLASH EXISTS.
- LABELS SHALL BE MACHINE PRINTED, UNO
- SIMPLEX RECEPTACLE
- DUPLEX RECEPTACLE
- DUPLEX RECEPTACLE, GFI TYPE
- DUPLEX RECEPTACLE, MOUNT ABOVE COUNTER
- DUPLEX RECEPTACLE, GFI TYPE, MOUNT ABOVE COUNTER
- FOURPLEX RECEPTACLE
- FOURPLEX RECEPTACLE, GFI TYPE
- FOURPLEX RECEPTACLE, MOUNT ABOVE COUNTER
- FOURPLEX RECEPTACLE, GFI TYPE, MOUNT ABOVE COUNTER
- DUPLEX RECEPTACLE, FLUSH IN CEILING
- FOURPLEX RECEPTACLE, FLUSH IN CEILING
- DUPLEX RECEPTACLE, HORIZONTALLY MOUNTED
- DUPLEX RECEPTACLE, HORIZ. MTD, GFI TYPE
- DUPLEX RECEPTACLE, HORIZ. MTD, ABOVE COUNTER
- DUPLEX RECEPTACLE, HORIZ. MTD, GFI TYPE, MOUNT ABOVE COUNTER
- WEATHER RESISTANT GFI DUPLEX RECEPTACLE, ROOF MOUNT 18-INCHES ABOVE ADJACENT STRUCTURE WITH A WEATHERPROOF, IN-USE COVER
- WEATHER RESISTANT GFI DUPLEX RECEPTACLE, MOUNT 18-INCHES AFF WITH A WEATHERPROOF, IN-USE COVER
- STD DUPLEX RECEPTACLE TO SERVE ELECTRIC WATER COOLER, MOUNT AT HEIGHT PER EWG EQUIPMENT MANUFACTURERS INSTALLATION GUIDELINES: WIRE TO GFCI BAR IN PANELBOARD, DUPLEX RECEPTACLE TO SERVE TELEVISION, MOUNT AT SAME HEIGHT AND WITHIN 8-INCHES OF ADJACENT TV OUTLET
- DUPLEX RECEPTACLE, EMERGENCY
- FOURPLEX RECEPTACLE, EMERGENCY
- DUPLEX RECEPTACLE, LOWER SWITCH
- DUPLEX RECEPTACLE, SWITCHED
- RANGE RECEPTACLE, MOUNT 8-INCHES AFF
- SPECIAL RECEPTACLE, DEEP WELL BOX
- FLUSH FLOOR OUTLET BOX UNO
- FLUSH FLOOR BOX WITH DUPLEX RECEPTACLE UNO
- MULTI-DEVICE FLOOR BOX WITH DUPLEX RECEPTACLE AND TELECOMMUNICATIONS OUTLETS
- USB ONLY RECEPTACLE
- RECEPTACLE WITH USB PORTS
- FLUSH JUNCTION BOX, CEILING MOUNTED
- JUNCTION BOX FOR FUTURE PROJECTOR POWER MOUNT 24-INCHES ABOVE SUSPENDED CEILING MOUNT TIGHT TO CEILING AT EXPOSED STRUCTURE LABEL BOX COVER: PROJECTOR POWER
- JUNCTION BOX ABOVE SUSPENDED CEILING WITH FLEX CONNECTION
- FLUSH JUNCTION BOX, WALL MOUNTED
- SURFACE JUNCTION BOX, WALL MOUNTED
- SURFACE JUNCTION BOX, CEILING MOUNTED
- HAND DRYER, INSTALL HAND DRYER SPECIFIED IN DIV. 11

**ABBREVIATIONS**

(D)	DEMOLISHED
(E)	EXISTING
(R)	RELOCATED
Ø	PHASE
A	AMPERE
AC	ABOVE COUNTER
AF	AMP FRAME (CIRCUIT BREAKER)
AC	AMPERE INTERRUPTING CAPACITY
AL	ALUMINUM
AMP	AMPERE
AP	WIRELESS ACCESS POINT
AT	AMP TRIP (CIRCUIT BREAKER OR FUSE)
ATS	AUTOMATIC TRANSFER SWITCH
AV	AUDIO-VIDEO AUDIO/VISUAL
AWG	AMERICAN WIRE GAUGE
BAS	BUILDING AUTOMATION SYSTEM
SJ	BONDING JUMPER BREAKER
BKR	BREAKER
BMS	BUILDING MANAGEMENT SYSTEM
C	CONDUIT
CAV	CABLE TELEVISION
CB	CIRCUIT BREAKER
CCTV	CLOSED CIRCUIT TELEVISION
CFCI	CONTRACTOR FURNISHED CONTRACTOR INSTALLED
CKT	CIRCUIT
CTL	CONTROL
CU	COPPER
DB	DECBEL
DC	DIRECT CURRENT
DISC	DISCONNECT
DP	DISTRIBUTION PANELBOARD
DW	DISHWASHER
EC5	EMERGENCY COMMUNICATION SYSTEM
EG8	ELECTRICAL GROUNDING BUSBAR
EMD	ESTIMATED MAXIMUM DEMAND
EMGB	ELECTRICAL MAIN GROUNDING BUSBAR
EP	EXPL. OSHN PROOF
ER	EXISTING (TO BE) RELOCATED
ERMS	ENERGY REDUCTION MAINTENANCE SWITCH
EW	ELECTRIC WATER COOLER
FA	FIRE ALARM
FAA	FIRE ALARM ANNUNCIATOR
FAFP	FIRE ALARM CONTROL PANEL
FC	FOOT CANDLE
FLA	FULL LOAD AMPS
FS	FLOW SWITCH
FSD	FIRE SMOKE DAMPER
G	EQUIPMENT GROUNDING CONDUCTOR
GEN	GENERATOR
GFI, GFCI	GROUND FAULT CIRCUIT INTERRUPTER
GFFE	GROUND FAULT PROTECTION OF EQUIPMENT
GND	EQUIPMENT GROUNDING CONDUCTOR
HH	HANDHOLE
HQA	HAND-OFF-AUTOMATIC
HP	HORSE POWER
IC	INTERCOM
IG	ISOLATED GROUND
JB	JUNCTION BOX
KAIC	THOUSAND AMPERE INTERRUPTING CIRCUIT
KV	KILOVOLT
KVA	KILOVOLT AMPERES
KW	KILOWATT
LT	LIGHT
LTG	LIGHTING
MCA	MINIMUM CIRCUIT AMPACITY
MCB	MAIN CIRCUIT BREAKER
MCC	MOTOR CONTROL CENTER
MH	MANHOLE
MLO	MAIN LUGS ONLY
MOCP	MAXIMUM OVERCURRENT PROTECTION
MRTS	MOTOR RATED TOGGLE SWITCH
MSB	MAIN SWITCHBOARD
MTD	MOUNTED
MTG	MOUNTING
MTS	MAIN TRANSFER SWITCH
N	NEUTRAL
N.C.	NORMALLY CLOSED
N.O.	NORMALLY OPEN
NF	NON-FUSED
NL	NIGHT LIGHT
OFCI	OWNER FURNISHED CONTRACTOR INSTALLED
OS&Y	OUTSIDE SCREW AND YOKE
P	POLE(S)
PA	PUBLIC ADDRESS
PB	PULL BOX
PH	PHASE
PV	POST INDICATOR VALVE
PNL	PANEL
PWR	POWER
RCP	REFLECTED CEILING PLAN
RECP	RECEPTACLE
REF	REFERENCE
RESP	RESPONSIVE
SCCR	SHORT CIRCUIT CURRENT RATING
SD	SMOKE DAMPER
SEC	SECONDARY
SPD	SURGE PROTECTION DEVICE
SWBD	SWITCHBOARD
TBB	TELECOMMUNICATIONS BONDING BACKBONE
TC	TIME CLOCK
TGB	TELECOMMUNICATIONS GROUNDING BUSBAR
TMGB	TELECOMMUNICATIONS MAIN GROUNDING BUSBAR
TO	TELECOMMUNICATIONS OUTLET
TR	TELECOMMUNICATIONS ROOM
TS	TAMPER SWITCH
TV	TELEVISION
UG	UNDERGROUND
UPS	UNINTERRUPTIBLE POWER SUPPLY
V	VOLT
VA	VOLT-AMPERE
VFD	VARIABLE FREQUENCY DRIVE
W	WIRE
WA	TELECOMMUNICATIONS WORK AREA
WG	WIRE GUARD
WP	WEATHER-PROOF (NEMA 3R)
XFMR	TRANSFORMER

APPLICABLE CODE: 2019 CBC 02/02/2020 REVISED: 02/14/2020  
 MEP COMPONENT ANCHORAGE NOTE

ALL MECHANICAL, PLUMBING AND ELECTRICAL COMPONENTS SHALL BE ANCHORED AND INSTALLED PER THE DETAILS ON THE DSA-APPROVED CONSTRUCTION DOCUMENTS. THE FOLLOWING COMPONENTS SHALL BE ANCHORED OR BRACED TO MEET THE FORCE AND DISPLACEMENT REQUIREMENTS PRESCRIBED IN THE 2019 CBC SECTIONS 1617A.1.18 THROUGH 1617A.1.26 AND ASCE 7-16 CHAPTERS 13, 26, AND 30:

- ALL PERMANENT EQUIPMENT AND COMPONENTS.
- TEMPORARY, MOVABLE OR MOBILE EQUIPMENT THAT IS PERMANENTLY ATTACHED (E.G. HARD WIRED) TO THE BUILDING UTILITY SERVICES SUCH AS ELECTRICITY, GAS OR WATER. "PERMANENTLY ATTACHED" SHALL INCLUDE ALL ELECTRICAL CONNECTIONS EXCEPT PLUGS FOR 110/220 VOLT RECEPTACLES HAVING A FLEXIBLE CABLE.
- TEMPORARY, MOVABLE OR MOBILE EQUIPMENT WHICH IS HEAVIER THAN 400 POUNDS OR HAS A CENTER OF MASS LOCATED 4 FEET OR MORE ABOVE THE ADJACENT FLOOR OR ROOF LEVEL. THAT DIRECTLY SUPPORT THE COMPONENT IS REQUIRED TO BE RESTRAINED IN A MANNER APPROVED BY DSA.

THE FOLLOWING MECHANICAL AND ELECTRICAL COMPONENTS SHALL BE POSITIVELY ATTACHED TO THE STRUCTURE BUT NEED NOT DEMONSTRATE DESIGN COMPLIANCE WITH THE REFERENCES NOTED ABOVE. THESE COMPONENTS SHALL HAVE FLEXIBLE CONNECTIONS PROVIDED BETWEEN THE COMPONENT AND ASSOCIATED DUCTWORK, PIPING, AND CONDUIT. FLEXIBLE CONNECTIONS MUST ALLOW MOVEMENT IN BOTH TRANSVERSE AND LONGITUDINAL DIRECTIONS:

- COMPONENTS WEIGHING LESS THAN 400 POUNDS AND HAVING A CENTER OF MASS LOCATED 4 FEET OR LESS ABOVE THE ADJACENT FLOOR OR ROOF LEVEL THAT DIRECTLY SUPPORT THE COMPONENT.
- COMPONENTS WEIGHING LESS THAN 20 POUNDS, OR IN THE CASE OF DISTRIBUTED SYSTEMS, LESS THAN 5 POUNDS PER FOOT, WHICH ARE SUSPENDED FROM A ROOF OR FLOOR OR HUNG FROM A WALL.

THE ANCHORAGE OF ALL MECHANICAL, ELECTRICAL AND PLUMBING COMPONENTS SHALL BE SUBJECT TO THE APPROVAL OF THE DESIGN PROFESSIONAL. IN GENERAL RESPONSIBLE CHARGE OR STRUCTURAL ENGINEER DELEGATED RESPONSIBILITY AND ACCEPTANCE BY DSA. THE PROJECT INSPECTOR WILL VERIFY THAT ALL COMPONENTS AND EQUIPMENT HAVE BEEN ANCHORED IN ACCORDANCE WITH THE ABOVE REQUIREMENTS.

PIPING, DUCTWORK AND ELECTRICAL DISTRIBUTION SYSTEM BRACING NOTE

PIPING, DUCTWORK AND ELECTRICAL DISTRIBUTION SYSTEMS SHALL BE BRACED TO COMPLY WITH THE FORCES AND DISPLACEMENTS PRESCRIBED IN ASCE 7-16 SECTION 13.3 AS DEFINED IN ASCE 7-16 SECTIONS 13.6.5, 13.6.6, 13.6.7, 13.6.8, AND 2019 CBC, SECTIONS 1617A.1.24, 1617A.1.25 AND 1617A.1.26.

THE METHOD OF SHOWING BRACING AND ATTACHMENTS TO THE STRUCTURE FOR THE IDENTIFIED DISTRIBUTION SYSTEM ARE AS NOTED BELOW. WHEN BRACING AND ATTACHMENTS ARE BASED ON A PREAPPROVED INSTALLATION GUIDE (E.G. OSHPD OPM FOR 2013 CBC OR LATER), COPIES OF THE BRACING SYSTEM INSTALLATION GUIDE OR MANUAL SHALL BE AVAILABLE ON THE JOBSITE PRIOR TO THE START OF AND DURING THE HANGING AND BRACING OF THE DISTRIBUTION SYSTEMS. THE STRUCTURAL ENGINEER OF RECORD SHALL VERIFY THE ADEQUACY OF THE STRUCTURE TO SUPPORT THE HANGER AND BRACE LOADS.

MECHANICAL PIPING (MP), MECHANICAL DUCTS (MD), PLUMBING PIPING (PP), ELECTRICAL DISTRIBUTION SYSTEMS (E):

MP	MD	PP	E	OPTION 1: DETAILED ON THE APPROVED DRAWINGS WITH PROJECT SPECIFIC NOTES AND DETAILS.
MP	MD	PP	(E)	OPTION 2: SHALL COMPLY WITH THE APPLICABLE OSHPD PRE-APPROVAL (OPM) # 00043-13

**\*NOTE\***

ALL NOTES ON THIS SHEET ARE APPLICABLE TO ALL OTHER SHEETS IN THIS SET.

THE SYMBOLS AND ABBREVIATIONS SHOWN ON THIS SHEET MAY OR MAY NOT BE APPLICABLE IN THIS SET OF DRAWINGS.



**Grovescenter Elementary School**  
 COVINA VALLEY USD  
 775 N LARK ELLIEN AVE, WEST COVINA, CA 91791

100% CONSTRUCTION DOCUMENTS  
 11/08/2022 REVISIONS

77-22605-00

ELECTRICAL SYMBOLS, ABBREVIATIONS & NOTES

E0.1



1  
2  
3  
4  
5

A

B

C

D

E


F

**GENERAL NOTES**

- A WORK TO INCLUDE REMOVAL OF EXISTING FEEDER TO EXISTING HVAC EQUIPMENT THAT ARE TO BE REMOVED AND REPLACED. FEEDER TO EXISTING INDOOR FAN COIL UNIT TO BE REMOVED IN ITS ENTIRETY.
- B DISCONNECTING MEANS TO BE NEMA 3R RATED, FURNISHED AND INSTALLED BY DIVISION 26. ELECTRIC HEATING IS BEING PROVIDED.
- C CARBON MONOXIDE DETECTION SYSTEM NOT REQUIRED. SEE SCHEDULE ON SHEET ES.1 FOR ADDITIONAL INFORMATION.
- D FUSES SHALL BE PROVIDED PER EQUIPMENT NAMEPLATE RATING.
- E ELECTRICAL PANELS LOCATED AT GRADE LEVEL DIRECTLY BELOW WHERE SHOWN.
- F ENERGY MANAGEMENT SYSTEM (EMS) / BUILDING AUTOMATION SYSTEM (BAS) IS A DELEGATED DESIGN SCOPE BY CONTRACTOR. CONTRACTOR TO FIELD COORDINATE WITH SCHOOL DISTRICT FOR LOCATIONS OF EMS ROUTER AND EMS PANEL AS WELL AS CONDUIT ROUTING.
- G CARBON MONOXIDE DETECTION SYSTEM WILL NOT BE PROVIDED AT THIS TIME UNDER CEBC 503.15.1. EXCEPTION 2: THE GROUP BUILDING WAS CONSTRUCTED BEFORE THE ADOPTION OF THE 2016 CALIFORNIA BUILDING STANDARDS CODE.
- H EXISTING HVAC UNITS ARE BEING REPLACED IN KIND THROUGHOUT.
- J CONTRACTOR TO PROVIDE CONNECTION FROM LOAD SIDE OF HVAC EQUIPMENT DISCONNECT SWITCH TO FEED POWER EXHAUST DISCONNECT SWITCH. PROVIDE SAME SIZE FEEDER. PROVIDE FUSES PER EQUIPMENT NAMEPLATE RATING.

**KEYNOTES**

- 1 EXISTING HVAC EQUIPMENT AT GRADE TO BE DISCONNECTED AND REPLACED AS PART OF THIS SCOPE OF WORK WITH ROOF-TOP EQUIPMENT. EXTEND EXISTING FEEDER AS REQUIRED. SEE TABLE ON SHEET ES.1 FOR OTHER INFORMATION. PROVIDE ALL REQUIRED CONNECTION.
- 2 EXISTING HVAC EQUIPMENT AT GRADE TO BE DISCONNECTED AND REPLACED AS PART OF THIS SCOPE OF WORK. PROVIDE NEW FEEDER PER TABLE ON SHEET ES.1. PROVIDE ALL REQUIRED CONNECTION.
- 3 NEW HVAC EQUIPMENT AT GRADE. PROVIDE NEW FEEDER PER TABLE ON SHEET ES.1. PROVIDE ALL REQUIRED CONNECTION.
- 4 DUCT SMOKE DETECTOR FOR COMPLIANCE TO CALIFORNIA MECHANICAL CODE SECTION 908 IS NOT REQUIRED PER CODE EXCEPTION NO. 2. ROOM HAVE DIRECT EXIT TO EXTERIOR AND TRAVEL DISTANCE DOES NOT EXCEED 100 FEET.
- 5 EXISTING ELECTRICAL EQUIPMENT TO REMAIN AND TO BE PROTECTED IN PLACE.
- 6 PROVIDE 120 VOLT CIRCUIT FROM SPARE BREAKER. PROVIDE TANDEM BREAKER AS REQUIRED.
- 7 (N) PANELBOARD 5 AT GRADE LEVEL. 277/480 VOLTS, 3-PHASE, W-WIRE, 225 AMP BUS. ROUTE CONDUIT UNDERGROUND FROM EXISTING MSB TO PANEL. LOCATION FIELD COORDINATE WITH SCHOOL DISTRICT EXACT CONDUIT ROUTING AND TRENCHING. REFER TO SHEET ES.1 FOR PANELBOARD MOUNTING DETAIL.
- 8 GFCI TYPE RECEPTACLE PROVIDED BY HVAC EQUIPMENT MANUFACTURER. SEE TABLE PROVIDED ON SHEET ES.1. GENERAL NOTE NO. 2 FOR CIRCUITING OF OUTLETS. PROVIDE WEATHERPROOF COVER.
- 9 FUSED DISCONNECT SIZE PER TABLE SHOWN ON ES.1.
- 10 PROVIDE 120V CIRCUIT FOR EMS ROUTER AND EMS PANEL. FIELD VERIFY EXACT LOCATION OF EMS ROUTER AND EMS PANEL.



**OVERALL ELECTRICAL POWER PLAN**  
SCALE: 1" = 20'-0"



**Grovescenter Elementary School**  
COVINA VALLEY USD  
775 N LARK ELLIEN AVE, WEST COVINA, CA 91791

100%  
CONSTRUCTION  
DOCUMENTS  
11/08/2022  
REVISIONS

77-22605-00

ELECTRICAL  
ROOF POWER  
PLAN

E2.1




1  
2  
3  
4  
5

GENERAL SINGLE LINE NOTES

- OVERCURRENT DEVICES OF ENTIRE DISTRIBUTION SYSTEM SHALL MEET STATED FAULT CURRENT VALUES WITH FULLY RATED EQUIPMENT.
- CONDUCTOR LENGTHS INDICATED ON THE SINGLE LINE DIAGRAM ARE FOR FAULT CURRENT CALCULATIONS ONLY. ACTUAL LENGTH SHALL BE DETERMINED BY FIELD CONDITIONS AND ACTUAL ROUTES OF FEEDERS.
- REFER TO SWITCHBOARD SCHEDULES AND DISTRIBUTION PANEL SCHEDULES FOR ADDITIONAL REQUIREMENTS. WHERE A DISCREPANCY EXISTS BETWEEN EQUIPMENT ON THE SINGLE LINE DIAGRAM AND THE DETAILED SCHEDULES, THE ITEM OR ARRANGEMENT WITH BETTER QUALITY, GREATER QUANTITY, OR HIGHER COST SHALL BE USED.
- ALL DISCREPANCIES SHALL BE BROUGHT TO THE ATTENTION OF THE ENGINEER.
- REFER TO THE MOTOR AND SPECIAL CONNECTION SCHEDULE FOR ALL FEEDERS DESIGNATED "EQ".

KEYNOTES

- FUSED DISCONNECT TO BE PROVIDED BY CONTRACTOR.
- VARIABLE FREQUENCY DRIVE WITH ON/OFF SWITCH TO BE PROVIDED UNDER DIVISION 23.
- CONTRACTOR TO MATCH EXISTING BREAKER.



ELECTRICAL CALCULATION:  
 ELECTRICAL METER DEMAND FOR PAST 12 MONTHS = 144KW  
 ELECTRICAL METER DEMAND IN AMPS @0.8 PF = 216.51  
 125% OF MAX. DEMAND PER CEC 220.67 = 270.63  
 (N) CU-B1A = 23  
 (N) CU-B1B = 12.9  
 (N) FCU-B1 = 7.0  
 (N) SWITCHBOARD TOTAL LOAD = 313.53  
 % UTILIZATION = 313.53 / 800 X 100% = 39.19%

One-Line Diagram  
 SCALE: 12" = 1'-0"

EXISTING PANEL: B														
LOCATION: MECHANICAL B115 BUS RATING: 225.0 A MAIN BREAKER: 225					VOLTS: 480Y/277 PHASES: 3 WIRES: 4 SCCR:					MOUNTING: SURFACE FED FROM: INTEGRAL SPD: Type 1 LUG ACCESSORIES: SEE ONE-LINE				
CKT	CIRCUIT DESCRIPTION	BKR TRIP	P	BKR TYPE	LOAD TYPE	PHASE A (VA)	PHASE B (VA)	PHASE C (VA)	LOAD TYPE	BKR TRIP	P	BKR TYPE	CIRCUIT DESCRIPTION	CKT
1						6.374	0		Spare	1	20	SPARE		2
3	CU-B1A	30	3	M		6.374	0	6.374	0	1	20	SPARE		4
5						3.575	0		0	1	20	SPARE		6
7										1	20	SPARE		8
9	CU-B1B	20	3	M		3.575	0	3.575	0	1	20	SPARE		10
11						1.550	0		0	1	20	SPARE		12
13								1.550	0	1	20	SPARE		14
15	FCU-B1	20	3	M		1.550	0	1.550	0	1	20	SPARE		16
17										1	20	SPARE		18
19										1	20	SPARE		20
21														22
23														24
25														26
27														28
29														30
TOTAL LOAD:						11469 VA	11469 VA	11469 VA						
TOTAL AMPS:						41.5 A	41.5 A	41.5 A						

FEEDER SCHEDULE - COPPER

MARK (AMPS)	# SETS	Ø & N	GND	CONDUIT SIZE		
				#W	MARK SUFFIX	CONDUIT SIZE
15	1	12	12	3/4"	3/4"	3/4"
20	1	12	12	3/4"	3/4"	3/4"
25	1	10	10	3/4"	3/4"	3/4"
30	1	10	10	3/4"	3/4"	3/4"
35	1	8	10	3/4"	3/4"	3/4"
40	1	8	10	3/4"	3/4"	3/4"
45	1	6	10	1"	3/4"	3/4"
50	1	6	10	1"	3/4"	3/4"
60	1	4	10	1-1/4"	1"	3/4"
70	1	4	8	1-1/4"	1"	3/4"
80	1	3	8	1-1/4"	1-1/4"	1"
90	1	2	8	1-1/4"	1-1/4"	1"
100	1	1	8	1-1/2"	1-1/2"	1-1/4"
110	1	1	6	1-1/2"	1-1/2"	1-1/4"
125	1	1	6	1-1/2"	1-1/2"	1-1/4"
150	1	10	6	2"	1-1/2"	1-1/4"
175	1	20	6	2"	1-1/2"	1-1/4"
200	1	30	6	2"	1-1/2"	1-1/2"
225	1	40	4	2-1/2"	2"	1-1/2"
250	1	250	4	2-1/2"	2"	1-1/2"
300	1	350	4	3"	2-1/2"	2"
350	1	500	3	3-1/2"	3"	2-1/2"
400	1	600	3	3-1/2"	3"	2-1/2"
400	2	30	3	2"	2"	1-1/2"
450	2	40	2	2-1/2"	2"	1-1/2"
500	2	250	2	2-1/2"	2-1/2"	2"
600	2	350	1	3"	2-1/2"	2"
700	2	500	10	3-1/2"	3"	2-1/2"
800	2	600	10	3-1/2"	3"	2-1/2"
1000	3	400	20	3"	3"	2-1/2"
1200	3	600	30	3-1/2"	3-1/2"	3"
1600	4	600	40	3-1/2"	3-1/2"	3"
2000	5	600	250	4"	3-1/2"	3"
2500	6	600	350	4"	3-1/2"	3"
3000	8	500	400	3-1/2"	3"	2-1/2"
4000	10	600	500	4"	3-1/2"	3"

ABBREVIATIONS:  
 Ø PHASE  
 N NEUTRAL  
 GND EQUIPMENT GROUNDING CONDUCTOR  
 -4W FOUR WIRE + GROUND (3Ø GND)  
 -3W THREE WIRE + GROUND (3Ø GND OR 2Ø N GND)  
 -2W TWO WIRE + GROUND

NOTES:  
 1. CONDUCTOR AMPACITIES ARE BASED ON NEC TABLE 310.15(B)(16).  
 2. CONDUIT SIZES ARE BASED ON A MAXIMUM FILL RATIO OF 40%.  
 3. SCHEDULE SHALL BE USED FOR FEEDERS AND BRANCH CIRCUITS WHERE APPLICABLE.  
 4. ALL FEEDERS AND BRANCH CIRCUITS SHALL INCLUDE AN EQUIPMENT GROUNDING CONDUCTOR.  
 5. SCHEDULE IS VALID FOR TYPE THHN, THWN-2, AND XHHW-2 CONDUCTORS. SEE SPECIFICATIONS FOR CONDUCTOR TYPES REQUIRED.  
 6. SCHEDULE IS VALID FOR TYPE EMT, IMC, FMC, LMC, HDPE, AND RMC-40 RACEWAYS. SEE SPECIFICATIONS FOR RACEWAY APPLICATIONS.  
 7. OPTIONAL CONFIGURATIONS (1 OR 2 SETS) ARE GIVEN FOR SOME SIZES.  
 8. NOT ALL SIZES USED.

Grove Center AC UNIT REPLACEMENT																			
EXISTING UNIT								NEW UNIT											
TAGS	ELECTRICAL				DISCONNECT	TAGS	DIRECT REPLACEMENT? Y/N	CFM	ELECTRICAL				POWER EXHAUST			NOTES			
	VIPH	MCA	FLA	MOCPP					PANEL/ CKTR	FEEDER SIZE	V-PH	MCA	MOCPP	PANEL/ CKTR#	DISCONNECT		REQUIRED?	Model#	MCA
NA	NA	NA	NA	NA	NA	CU-B1A	NO		480/3	23	30	B-1,3,5	30A (30A FUSE)	NO					
NA	NA	NA	NA	NA	NA	CU-B1B	NO		480/3	12.9	20	B-7,9,11	30A (20A FUSE)	NO					
NA	NA	NA	NA	NA	NA	FCU-B1	NO	4.800	480/3	7	20	B-13,15,17	30A (20A FUSE)	NO					
CU/FCU-C1 (BLDG C)	240/1	22.875	18.3	30	LC-8,10	2#10, 1#10GND-0.75°C	Y	1,200	240/1	26	30	LC-8,10	30A (30A FUSE)	YES	PCD-SRT12CA	7.1	12.8	2#10, 1#10GND-0.75°C	20A (15A FUSE)
CU/FCU-C2 (BLDG C)	240/1	22.875	18.3	30	LC-12,14	2#10, 1#10GND-0.75°C	Y	1,200	240/1	26	30	LC-12,14	30A (30A FUSE)	YES	PCD-SRT12CA	7.1	12.8	2#10, 1#10GND-0.75°C	20A (15A FUSE)
CU/FCU-D1 (BLDG D)	240/1	22.875	18.3	30	H-2,4	2#10, 1#10GND-0.75°C	Y	1,200	240/1	26	30	H-2,4	30A (30A FUSE)	YES	PCD-SRT12CA	7.1	12.8	2#10, 1#10GND-0.75°C	20A (15A FUSE)
CU/FCU-D2 (BLDG D)	240/1	22.875	18.3	30	H-6,8	2#10, 1#10GND-0.75°C	Y	1,200	240/1	26	30	H-6,8	30A (30A FUSE)	YES	PCD-SRT12CA	7.1	12.8	2#10, 1#10GND-0.75°C	20A (15A FUSE)
CU/FCU-D3 (BLDG D)	240/1	22.875	18.3	30	H-10,12	2#10, 1#10GND-0.75°C	Y	1,200	240/1	26	30	H-10,12	30A (30A FUSE)	YES	PCD-SRT12CA	7.1	12.8	2#10, 1#10GND-0.75°C	20A (15A FUSE)
CU/FCU-D4 (BLDG D)	240/1	22.875	18.3	30	H-14,16	2#10, 1#10GND-0.75°C	Y	1,200	240/1	26	30	H-14,16	30A (30A FUSE)	YES	PCD-SRT12CA	7.1	12.8	2#10, 1#10GND-0.75°C	20A (15A FUSE)
CU/FCU-E1 (BLDG E)	240/1	22.875	18.3	30	H-1,3	2#10, 1#10GND-0.75°C	Y	1,200	240/1	26	30	H-1,3	30A (30A FUSE)	YES	PCD-SRT12CA	7.1	12.8	2#10, 1#10GND-0.75°C	20A (15A FUSE)
CU/FCU-E2 (BLDG E)	240/1	22.875	18.3	30	H-5,7	2#10, 1#10GND-0.75°C	Y	1,200	240/1	26	30	H-5,7	30A (30A FUSE)	YES	PCD-SRT12CA	7.1	12.8	2#10, 1#10GND-0.75°C	20A (15A FUSE)
CU/FCU-E3 (BLDG E)	240/1	22.875	18.3	30	H-9,11	2#10, 1#10GND-0.75°C	Y	1,200	240/1	26	30	H-9,11	30A (30A FUSE)	YES	PCD-SRT12CA	7.1	12.8	2#10, 1#10GND-0.75°C	20A (15A FUSE)
CU/FCU-E4 (BLDG E)	240/1	22.875	18.3	30	H-13,15	2#10, 1#10GND-0.75°C	Y	1,200	240/1	26	30	H-13,15	30A (30A FUSE)	YES	PCD-SRT12CA	7.1	12.8	2#10, 1#10GND-0.75°C	20A (15A FUSE)
CU/FCU-F1 (BLDG F)	240/1	22.875	18.3	30	J-2,4	2#10, 1#10GND-0.75°C	Y	1,200	240/1	26	30	J-2,4	30A (30A FUSE)	YES	PCD-SRT12CA	7.1	12.8	2#10, 1#10GND-0.75°C	20A (15A FUSE)
CU/FCU-F2 (BLDG F)	240/1	22.875	18.3	30	J-6,8	2#10, 1#10GND-0.75°C	Y	1,200	240/1	26	30	J-6,8	30A (30A FUSE)	YES	PCD-SRT12CA	7.1	12.8	2#10, 1#10GND-0.75°C	20A (15A FUSE)
CU/FCU-F3 (BLDG F)	240/1	22.875	18.3	30	J-10,12	2#10, 1#10GND-0.75°C	Y	1,200	240/1	26	30	J-10,12	30A (30A FUSE)	YES	PCD-SRT12CA	7.1	12.8	2#10, 1#10GND-0.75°C	20A (15A FUSE)
CU/FCU-F4 (BLDG F)	240/1	22.875	18.3	30	J-14,16	2#10, 1#10GND-0.75°C	Y	1,200	240/1	26	30	J-14,16	30A (30A FUSE)	YES	PCD-SRT12CA	7.1	12.8	2#10, 1#10GND-0.75°C	20A (15A FUSE)
CU/FCU-G1 (BLDG G)	240/1	22.875	18.3	30	J-1,3	2#10, 1#10GND-0.75°C	Y	1,200	240/1	26	30	J-1,3	30A (30A FUSE)	YES	PCD-SRT12CA	7.1	12.8	2#10, 1#10GND-0.75°C	20A (15A FUSE)
CU/FCU-G2 (BLDG G)	240/1	22.875	18.3	30	J-5,7	2#10, 1#10GND-0.75°C	Y	1,200	240/1	26	30	J-5,7	30A (30A FUSE)	YES	PCD-SRT12CA	7.1	12.8	2#10, 1#10GND-0.75°C	20A (15A FUSE)
CU/FCU-G3 (BLDG G)	240/1	22.875	18.3	30	J-9,11	2#10, 1#10GND-0.75°C	Y	1,200	240/1	26	30	J-9,11	30A (30A FUSE)	YES	PCD-SRT12CA	7.1	12.8	2#10, 1#10GND-0.75°C	20A (15A FUSE)
CU/FCU-G4 (BLDG G)	240/1	22.875	18.3	30	J-13,15	2#10, 1#10GND-0.75°C	Y	1,200	240/1	26	30	J-13,15	30A (30A FUSE)	YES	PCD-SRT12CA	7.1	12.8	2#10, 1#10GND-0.75°C	20A (15A FUSE)

- GENERAL NOTES:  
 1. CONTRACTOR TO FIELD VERIFY CIRCUITING AND FEEDER INFORMATION PRIOR TO EQUIPMENT REMOVAL. CONTRACTOR TO PROVIDE REQUIRED ADJUSTMENTS AS NEEDED.  
 2. PROVIDE MECHANICAL UNIT WITH INTEGRAL CONVENIENCE RECEPTACLE. FEED FROM SPARE 20A/1P BREAKER IN NEAREST PANEL. ROUTE 2#12+1#12GND IN 1/2" EMT CONDUIT FROM PANEL TO RECEPTACLE.  
 3. POWER NO MORE THAN 10 RECEPTACLES ON ONE CIRCUIT. FIELD VERIFY EXACT LOCATION OF NEAREST PANEL AND ROUTE OF NEW CIRCUIT FROM PANEL TO UNIT RECEPTACLE.  
 4. CONTRACTOR TO DEMOLISH POWER CONNECTION FROM CONDENSING UNITS, FAN COIL UNITS AND CONDENSATE PUMPS. DEMOLITION TO CONSIST OF REMOVAL OF POWER CONNECTION, CABLING, AND CONDUIT BACK TO SOURCE UNLESS NOTED OTHERWISE. FIELD COORDINATE EQUIPMENT MANUFACTURER FOR FAULT CURRENT LIMITING FUSE TYPES



Groves Center Elementary School  
 COVINA VALLEY USD  
 775 N LARK ELLIEN AVE, WEST COVINA, CA 91791

100% CONSTRUCTION DOCUMENTS  
 11/08/2022 REVISIONS

77-22605-00  
 ELECTRICAL DIAGRAMS AND SCHEDULES

E5.1

Autodesk Docs // 77-22605-00\_CVUSD - District Wide HVAC Replacement // 77-22605-00\_CVUSD - Grovescenter ES MEP\_2022.rvt  
 8/29/2022 2:56:38 PM



### ALTERNATE ARRANGEMENT OF SEISMIC BRACES FOR CONDUITS ON TRAPEZE

**ELEVATION VIEW**  
SOLID BRACE INSTALLED IN-BETWEEN HANGERS (TRANSVERSE OR ALL-DIRECTIONAL BRACE)

**ELEVATION VIEW**  
CABLE BRACE INSTALLED IN-BETWEEN HANGERS

**ELEVATION VIEW**  
CABLE BRACE INSTALLED AT SINGLE HANGER (TRANSVERSE BRACES ONLY)

**PLAN VIEW**  
LONGITUDINAL SOLID BRACES INSTALLED IN ALTERNATING DIRECTIONS

**PLAN VIEW**  
ALL-DIRECTIONAL SOLID BRACES INSTALLED IN ALTERNATING DIRECTIONS

**PLAN VIEW**  
CABLE X-PATTERN BRACE INSTALLED IN-BETWEEN HANGERS

NOTES:  
1) REFER TO APPROPRIATE DETAIL F PAGES FOR DIMENSIONS AND NOTATIONS NOT SHOWN.

**MASON WEST, INC.**  
1601 E. Miraloma Ave. Placentia, CA 92870  
TEL (714) 630 - 0701, www.masonwest.com

**Jiefu "Jeff" Zhang, SE**  
California SE No. 55270

PAGE **A25.1**

08/16/2019 OPM-0043-13: Reviewed for Code Compliance by Jeffrey Kikumoto Page 130 of 812

### SEISMIC BRACKET ATTACHMENT TO STRUCTURAL TIMBER WITH (1) THRU BOLT OR THREADED ROD

**SEISMIC BRACE BRACKET PERPENDICULAR TO JOIST**

**SEISMIC BRACE BRACKET PARALLEL TO JOIST**

MIN. 2x MEMBER, TYP. (MIN. SPECIES SPECIFIC GRAVITY G=0.42 AND WITH 2x2x1/2 PLATE WASHER ON BACK SIDE OF 4x6)

ASTM A307 BOLT OR ASTM A36 THREADED ROD, SNUG TIGHT TYP.

ASTM A307 BOLT OR ASTM A36 THREADED ROD, WITH STANDARD WASHER ON BACK SIDE OF JOIST, SNUG TIGHT TYP.

MAX. 4x JOIST, TYP. (MIN. SPECIES SPECIFIC GRAVITY G=0.42 AND GRADE NO.2)

4x6 MIN. SPECIES SPECIFIC GRAVITY G=0.42 AND GRADE NO.2

ADDITIONAL BLOCKING OF WOOD JOIST TO BE DESIGNED BY THE STRUCTURAL ENGINEER OF RECORD.

3" MIN. 15" MAX. 24" MAX.

2x2x1/2 PLATE WASHER

MIN. 1/2" MAX. 1/2" WEB THICKNESS (MIN. SPECIES SPECIFIC GRAVITY G=0.42), TYP.

ASTM A307 BOLTS OR ASTM A36 THREADED ROD

BRACE BRACKET ATTACHMENT TYPE	ALLOWABLE LATERAL LOAD Fp LBS	MAX. BRACE RANGE INCH	MIN. EDGE DIA. INCH
38A TO 38D	250	30"-45"	1/2"
38A TO 38B	150	46"-60"	1/2"
50A TO 50D	300	30"-45"	1/2"
50A TO 50B	170	46"-60"	1/2"
63A TO 63D	340	30"-45"	1/2"
63A TO 63C	200	46"-60"	1/2"

SEE DETAIL NO.09 FOR SECTION NOTES

**MASON WEST, INC.**  
1601 E. Miraloma Ave. Placentia, CA 92870  
TEL (714) 630 - 0701, www.masonwest.com

**Jiefu "Jeff" Zhang, SE**  
California SE No. 55270

PAGE **N4.10**

08/16/2019 OPM-0043-13: Reviewed for Code Compliance by Jeffrey Kikumoto Page 697 of 812

### SEISMIC BRACKET ATTACHMENT TO WOOD I-JOISTS WITH (1) THRU BOLT OR THREADED ROD

**PERPENDICULAR TO JOIST**

**PARALLEL TO JOIST**

2x6x1-0" (MIN. SPECIES SPECIFIC GRAVITY G=0.42 AND GRADE NO. 2) WITH 2x2x1/2 PLATE WASHER ON BACK SIDE OF JOIST

ASTM A307 BOLT OR ASTM A36 THREADED ROD, WITH STANDARD WASHER ON BACK SIDE OF JOIST, SNUG TIGHT TYP.

12-12x (3/16") COMMON NAIL, CLINCH NAILS AT I-JOIST WEB TYP.

MASON IND. N.Y. SEISMIC BRACKET FOR CABLE OR SOLID BRACING.

4x8 MIN. SPECIES SPECIFIC GRAVITY G=0.42 AND GRADE NO.2

NAIL THROUGH JOIST TO END OF 4x8 WITH 6-12x COMMON NAILS FOR 4x JOISTS WITH MIN. EDGE 4D

MIN. 1/2" MAX. 1/2" WEB THICKNESS (MIN. SPECIES SPECIFIC GRAVITY G=0.42), TYP.

ADDITIONAL BLOCKING OF WOOD JOIST TO BE DESIGNED BY THE STRUCTURAL ENGINEER OF RECORD.

3" MIN. 15" MAX. 24" MAX.

2x2x1/2 PLATE WASHER

BRACE BRACKET ATTACHMENT TYPE	ALLOWABLE LATERAL LOAD Fp LBS	MAX. BRACE RANGE INCH	MIN. EDGE DIA. INCH
38A TO 38B	150	30"-45"	1/2"
38A TO 38A	80	46"-60"	1/2"
50A TO 50C	100	30"-45"	1/2"
50A TO 50A	100	46"-60"	1/2"
63A TO 63C	210	30"-45"	1/2"
63A TO 63A	120	46"-60"	1/2"

SEE DETAIL NO.09 FOR SECTION NOTES

**MASON WEST, INC.**  
1601 E. Miraloma Ave. Placentia, CA 92870  
TEL (714) 630 - 0701, www.masonwest.com

**Jiefu "Jeff" Zhang, SE**  
California SE No. 55270

PAGE **N4.11**

08/16/2019 OPM-0043-13: Reviewed for Code Compliance by Jeffrey Kikumoto Page 698 of 812

### SEISMIC BRACKET ATTACHMENT TO WOOD JOIST

**AT JOIST**

**VIEW A-A**

2x3x1/2 PLATE WASHER

MIN. 2x (MIN. SPECIES SPECIFIC GRAVITY G=0.42 AND GRADE NO. 2), TYP.

3/8" DIA. ASTM A307 BOLT OR ASTM A36 THREADED ROD THROUGH 1/2" DIA. HOLE, WITH STANDARD WASHER ON BACK SIDE OF JOIST, SNUG TIGHT TYP.

L3x3x1/2, 5" L.G.

MASON IND. N.Y. SEISMIC BRACKET FOR SOLID OR CABLE BRACING. BRACE BRACKET MAY BE ROTATED TO ANY ANGLE AROUND BOLT.

ADDITIONAL BLOCKING OF WOOD JOIST TO BE DESIGNED BY THE STRUCTURAL ENGINEER OF RECORD.

1/2" DIA. HOLE, TYP. HOLE SIZE, 1/8" LARGER THAN ATR HANGER

BRACE BRACKET ATTACHMENT TYPE	ALLOWABLE LATERAL LOAD Fp LBS	MAX. BRACE RANGE INCH	MIN. EDGE DIA. INCH
38A TO 38E	420	30"-45"	1/2"
38A TO 38D	300	46"-60"	1/2"
50A TO 50E	420	30"-45"	1/2"
50A TO 50D	300	46"-60"	1/2"
63A TO 63E	420	30"-45"	1/2"
63A TO 63D	300	46"-60"	1/2"

SEE DETAIL NO.09 FOR SECTION NOTES

**MASON WEST, INC.**  
1601 E. Miraloma Ave. Placentia, CA 92870  
TEL (714) 630 - 0701, www.masonwest.com

**Jiefu "Jeff" Zhang, SE**  
California SE No. 55270

PAGE **N4.13**

08/16/2019 OPM-0043-13: Reviewed for Code Compliance by Jeffrey Kikumoto Page 700 of 812

### CONDUIT ELECTRICAL METALLIC TUBING (EMT) MAXIMUM SEISMIC BRACE SPACINGS

VERTICAL FORCE Fpv = 0.375g (ASD)

TRADE SIZE	MAX WEIGHT PER FOOT (LBS/FT)	MAX GRAVITY SUPPORT SPACING (FT)	MAX TRANSVERSE BRACE SPACING BASED ON TRADE SIZE AND g FORCE (FT)						
			0.25	0.375	0.5	0.625	0.75	0.875	1
3	8.26	10	45	41	38	36	35	33	31
3.5	10.98	10	48	44	41	39	37	35	33
4	13.64	10	50	45	42	40	38	36	34

NOTES:  
1. MAXIMUM BRACE SPACING IS BASED ON ASCE 7-10 SECTION 13.6.3, NOTE 9, 75 PERCENT OF THE MATERIAL MINIMUM SPECIFIED TENSILE STRENGTH FOR STEEL TUBING.  
2. EMT CONSIDERED FULL OF CONDUCTORS WHEN DETERMINING WEIGHT (REFER TO APPENDIX).  
3. FOR LONGITUDINAL AND ALL-DIRECTIONAL BRACE SPACING, MULTIPLY THE TABULATED VALUES BY 3. BRACE AND OR CONNECTION CAPACITY MAY GOVERN MAXIMUM BRACING IN SOME CASES.  
4. BRACE SPACINGS ARE BASED ON EMT STEEL TUBING CONSTRUCTED TO UL-778 OR ANSI C-80.3 WITH A MINIMUM YIELD STRENGTH OF 30,000 PSI.  
5. COUPLERS FOR LW TO 2 1/2" EMT TO MEET PRODUCT SPECIFICATIONS HOWEVER, CONNECTION COUPLERS OR COUPLERS WITH MIN. (2) BOLTS AT EACH END, E.G., CONDUIT CAN BE PUSHED INTO CONDUIT "X" AND SET WITH MIN. (2) SCREWS. SHALL BE USED FOR 3", 3 1/2", AND 4" EMT.

**MASON WEST, INC.**  
1601 E. Miraloma Ave. Placentia, CA 92870  
TEL (714) 630 - 0701, www.masonwest.com

**Jiefu "Jeff" Zhang, SE**  
California SE No. 55270

PAGE **S2.0**

08/16/2019 OPM-0043-13: Reviewed for Code Compliance by Jeffrey Kikumoto Page 715 of 812

### ELECTRICAL CONDUIT WEIGHT TABLES



CONDUIT DIAMETER (IN)	PIPE TYPE	PIPE WEIGHT PER FOOT (LBS)	
		PIPE CONDUCTORS	TOTAL
ELECTRICAL METALLIC TUBING (EMT) WEIGHT	1/2	0.29	0.22
	3/4	0.44	0.40
	1	0.64	0.66
	1 1/2	0.95	1.17
	2	1.10	1.60
	2 1/2	1.49	2.62
INTERMEDIATE METAL CONDUIT (IMC) WEIGHT	1	2.05	3.74
	1 1/2	2.42	3.63
	2	4.28	3.47
	3	5.26	5.43
	3 1/2	6.12	7.34
	4	6.82	9.80
RIGID METAL CONDUIT (RMC) WEIGHT	1	1.53	0.66
	1 1/2	2.01	1.17
	2	2.48	1.61
	2 1/2	3.32	2.62
	3	5.27	3.74
	3 1/2	6.82	5.77
RIGID METAL CONDUIT (RMC) WEIGHT	4	8.31	7.73
	5	9.72	9.95
	6	13.14	15.62
	8	17.45	22.58

**MASON WEST, INC.**  
1601 E. Miraloma Ave. Placentia, CA 92870  
TEL (714) 630 - 0701, www.masonwest.com

**Jiefu "Jeff" Zhang, SE**  
California SE No. 55270

PAGE **APP3.0**

08/16/2019 Page 811 of 812



NOTES:  
1. MAXIMUM WEIGHT OF EQUIPMENT UNIT NOT TO EXCEED 500 LBS.  
2. COORDINATE EXACT LOCATIONS WITH MECHANICAL, ELECTRICAL AND ARCHITECTURAL DRAWINGS.