



- REV. 10-26-03; ADDED EROSION CONTROL SYMBOL.
- REV. 5-27-04; CORRECTED DIMENSION IN SECTION A-A.
- REV. 4-15-06; ADDED CONNECTION SLEEVE AND OPTIONAL LIFTING STRAPS. REFORMATTED SHEET, REVISED NOTES, MISC. EDITS TO DRAWING.
- REV. 4-1-08; REMOVED TEMPORARY REFERENCE. REVISED GENERAL NOTES, AND DRAFTING EDITS.
- REV. 2-28-01; CORRECTED PAY ITEM NUMBER IN PLAN VIEW.
- REV. 5-27-01; CHANGED ITEM NOS. 209-08 TO 209-08.03, 209-08.10 TO 209-09.02 AND 303-15.01 TO 303-10.01. CHANGED DESCRIPTION IN ITEM NO. 209-20.03.
- REV. 12-18-02; CHANGED SILT FENCE (WITHOUT BACKING) TO SILT FENCE (WITH BACKING) IN PLAN AND SECTIONAL VIEW. CHANGED PAY ITEM FROM 209-08.03 TO 209-08.02 FOR SILT FENCE.



SECTION A-A

SEDIMENT FILTER BAG GENERAL NOTES

- (A) SPECIAL PROVISION 209B IS TO BE USED FOR SEDIMENT FILTER BAGS. ALL REFERENCES IN SPECIAL PROVISION 209B TO PUMPING FROM SEDIMENT TRAPS ALSO APPLIES TO PUMPING FROM COFFER DAMS.
- (B) SEDIMENT FILTER BAGS SHOULD NOT BE PLACED WITHIN A JURISDICTIONAL WETLAND OR WITHIN 20 FEET OF A STABILIZED OUTLET, STREAM, OR OTHER NATURAL WATER RESOURCE.
- (C) CONTRACTOR SHALL EXERCISE CAUTION NOT TO BURST OR DAMAGE THE SEDIMENT FILTER BAG WHEN PUMPING.
- (D) THE LENGTH AND WIDTH OF THE SEDIMENT BAG SHOWN ON THIS DRAWING MAY VARY PER VENDOR SPECIFICATIONS. THE MINIMUM "FOOTPRINT" OF THE BAG SHALL BE 150 SQUARE FEET.
- (E) SEDIMENT FILTER BAGS MAY BE EQUIPPED WITH A SEWN-IN SLEEVE OF SUFFICIENT SIZE TO ACCEPT A MINIMUM FOUR-INCH DIAMETER PUMP DISCHARGE HOSE. A HOSE CONNECTION THROUGH A SLIT IN THE BAG IS ALSO ACCEPTABLE. THE DISCHARGE HOSE SHOULD BE EXTENDED INTO THIS SLEEVE A MINIMUM OF SIX INCHES AND BE TIGHTLY SECURED WITH A HOSE CLAMP OR OTHER SUITABLE MEANS TO PREVENT LEAKAGE.
- (F) THE PUMP DISCHARGE HOSE CONNECTION SLEEVE, OR SLIT, SHALL BE SECURELY TIED OFF DURING DISPOSAL OF THE SEDIMENT FILTER BAG IN ORDER TO PREVENT LEAKAGE OF COLLECTED SEDIMENTS.
- (G) ONLY GEOTEXTILE FABRIC (TYPE III) LISTED ON THE QUALIFIED PRODUCTS LIST SHALL BE USED.
- (H) SURROUND SEDIMENT FILTER BAG ASSEMBLY WITH SILT FENCE WITH WIRE BACKING. SEE STANDARD DRAWING EC-STR-3C AND EC-STR-3E FOR INSTALLATION DETAILS.
- (I) EXISTING VEGETATIVE BUFFER TO REMAIN BETWEEN SILT FENCE WITH WIRE BACKING AND STABILIZED OUTLET, STREAM OR OTHER NATURAL WATER RESOURCE.
- (J) SEDIMENT TUBES OR FILTER SOCKS MAY BE USED AS AN ALTERNATIVE TO SILT FENCE WITH WIRE BACKING. SEE STANDARD DRAWINGS EC-STR-37 AND EC-STR-8 FOR INSTALLATION DETAILS. FILTER SOCKS MAY NOT REQUIRE STAKING WHEN APPROVED BY THE ENGINEER.
- (K) SEDIMENT FILTER BAGS SHALL BE PAID FOR UNDER THE FOLLOWING ITEM NUMBERS:
 209-09.03 SEDIMENT FILTER BAG (15' X 15') PER EACH
 209-09.04 SEDIMENT FILTER BAG (15' X 10') PER EACH
 303-10.01 MINERAL AGGREGATE (SIZE 57) PER TON
 740-10.03 GEOTEXTILE (TYPE III) (EROSION CONTROL) PER SQUARE YARD
 SILT FENCE WITH BACKING, SEDIMENT TUBES, AND FILTER SOCKS SHALL BE PAID FOR ACCORDING TO ITS RESPECTIVE STANDARD DRAWING.
 PAYMENT SHALL INCLUDE ALL MATERIALS AND LABOR NECESSARY FOR CONSTRUCTION, MAINTENANCE, AND REMOVAL OF SEDIMENT FILTER BAGS.
- (L) WHEN SEDIMENT FILTER BAGS ARE REPLACED ONLY THE REPLACEMENT BAG SHALL BE PAID FOR. MAINTENANCE ON ALL OTHER PARTS OF THE SEDIMENT FILTER BAG ASSEMBLY SHALL BE INCLUDED IN THE INITIAL PAYMENT.
- (M) ONLY SEDIMENT FILTER BAGS LISTED ON THE QUALIFIED PRODUCTS LIST MAY BE USED.
- (N) SEDIMENT FILTER BAGS SHALL BE REPLACED WHEN SEDIMENT HAS ACCUMULATED TO 1/2 OF THE BAGS CAPACITY OR IN ACCORDANCE WITH THE MANUFACTURER'S RECOMMENDATIONS.

EROSION CONTROL PLAN LEGEND: SEDIMENT FILTER BAG

MINOR REVISION -- FHWA APPROVAL NOT REQUIRED.

STATE OF TENNESSEE
DEPARTMENT OF TRANSPORTATION

SEDIMENT
FILTER BAG