

Qty: 1 **G14.2L Caterpillar Generator**

- Natural Gas Unit
- Rated at 200Kw, 277/480 volts, 3 phase, 4 wire, 350 amps, 60Hz at 1800 rpm
- L2 sound attenuated enclosure
- UL2200 listed
- 600 amp mainline circuit breaker
- 20 amp battery charger
- Engine coolant heater
- Battery disconnect switch
- EMCP4.2B control panel
- Remote emergency stop switch
- 16 light local annunciator
- Gen run/alarm relay
- 20 amp GFCI receptacle
- Freight to the job site
- 2 hour on site load bank test
- Startup inspection
- Building load test
- Customer training 2 sound attenuated enclosure

Qty: 1 **G100 Caterpillar Generator**

- Natural Gas Unit
- Rated at 100Kw, 120/208 volts, 3 phase, 4 wire, 347 amps, 60Hz at 1800rpm
- L2 sound attenuated enclosure
- UL2200 listed
- 400 amp mainline circuit breaker
- 10 amp battery charger
- Engine coolant heater
- Battery disconnect switch
- Gccp1.2 control panel
- Remote emergency stop switch
- 16 light remote annunciator
- Gen run/alarm relay
- 20 amp GFCI receptacle
- Coolant reservoir
- Freight to the job site
- 2 hour on site load bank test
- Startup inspection
- Building load test
- Customer training
- The unit will also be equipped with an 18" sub base frame in order to fit on the pad and to be able to reuse the existing conduit.
- The automatic transfer switch will be rated at 400 amps, 120/208 volts, 3 phase, 3 pole, 4 wire in a Nema 1 enclosure