

CITY OF AZTEC, NEW MEXICO
Rio de Animas Park, and Riverside Park River Access and Bank Stabilization Project Animas
River, City of Aztec, New Mexico
BACKGROUND AND SPECIFICATIONS
July 27, 2021

BACKGROUND INFORMATION

The City of Aztec, New Mexico (City) proposes to install river rock and sand along the banks of Rio de Animas Park and Riverside Park. This installation needs to be completed by October 22, 2021. Rock and sand is provided by city of Aztec.

SPECIFICATIONS

A Scope of Work

1. The construction contractor (Contractor) is required to provide the necessary and appropriately sized equipment to implement work proposed by the Animas de Rio Park, and Riverside Park Site Construction plans for the duration of the project. Included in the bid will be fuel, and maintenance costs for operation.

(See attachments #1,#2).

2. The Contractor shall mobilize and stage all necessary equipment within a reasonable distance of the work site. (See4.c.)

3. The Contractor is required to employ a highly skilled & experienced equipment operator(s), especially the excavator operator, as Basin Hydrology Inc. will be working closely with, and in close proximity to the excavator.

4. It is the Contractor's responsibility to:
 - a. Power wash all equipment prior to site delivery.
 - b. Inspect their equipment daily for fluid leaks, prevent fuel and fluid leaks, and
 - c. Store service equipment at least 100 ft. from the river and irrigation ditch, monitor and prevent any fuel leaks from equipment and fuel storage tanks.
 - d. Properly dispose of all Contractor- generated refuse (i.e., trash, lube cans, etc.)

B Utilities Statement

The Contractor may be liable for any damage to utilities during construction. The City and Basin Hydrology Inc. makes no representation that any utilities, if any, shown are exactly located or that all utilities present are shown in the plan. Call New Mexico 811 in advance of any digging, grading or excavation for the marking of underground utilities.

C Permitting

The Contractor is required to comply with all issued Federal State and City of Aztec (City) permit requirements as well as any NEPA requirements; all of which will be provided to Contractors during the Bidding process.

D Soil and Vegetationon Disturbance

The Contractor is required to implement the appropriate measures to avoid unnecessary soil and vegetation disturbances (I.e. / the Contractor is to minimize site disturbances) and is required to restore the grades and elevations of disturbed areas.

E Contractor is requiredto Review before Pre-bid Meeting

1. Construction Plans for the Rio de Animas Park River Access and Bank Stabilization Project Animas River, City of Aztec, New Mexico, (See attachment #1)
2. Construction Plans for the Riverside Park River Access and Bank Stabilization Project Animas River, City of Aztec, New Mexico, (See attachment #2)
3. J-Hook Specifications
4. Rock Specifications (City will provide Rock)
5. Basin Hydrology, Inc. Role
6. Contractor's Responsibility
7. General Notes
8. Debris Removal & Revegetation
9. Review: Contractor Procurement and Construction Schedule

Contractor Procurement and Construction Schedule

Phase	Responsible Party	Date/Days to be Completed
Procurement		
a. Release Request for Proposals	City	8/6/2021
b. Mandatory Pre-Bid Site Tour	Bidders, City	8/11/2021
c. Deadline for Written Questions	Bidders	8/19/2021
d. Responses to Written Questions	City	8/23/2021
e. Proposal Submission Deadline	Bidders	8/30/2021
f. Proposal Evaluation	City, SJWG, BHI	8/31/2021
g. Contractor Selection	City	9/2/2021
h. Finalize Contract/PO	City, BHI	9/13/2021
Staging and Construction		
a. Staging Rock and Sand	City	8/16/2021-8/20/2021
b. Construction	BHI	9/20/2021-10/22/2021
Monitoring		
a. As Built Survey	BHI	End of Construction
b. Year 1 Survey	BHI, SJWG	September 2022

City = City of Aztec

SJWG = San Juan Watershed Group

BHI = Basin Hydrology Inc.