

TOWN OF BLUFFTON

JASON STREET SEWER EXTENSION TO 5 LOTS ON MAY RIVER ROAD

DATE: 10/17/2019

Item #	Description	Qty	Unit	Unit Price	Total
General					
1	Clearing and Grubbing, including street R/W, easement & other areas as shown on the plans	1	LS		
2	Grading and Project Miscellaneous shall include all grading, including off-site removal and replacement of unsuitable material, to meet the finished grades shown in the plans, and project staking, testing, insurance and bonds & all miscellaneous items not included elsewhere in this bid schedule to complete the project in accordance with the plans & specifications	1	LS		
3	Saw and Replace Existing Asphalt Paving, fill with flowable fill	30	SY		
4	Silt Fence - Type "Sd1-NS"	875	LF		
Sanitary Sewer System					
1	4" PVC Service Lateral (Direct Bury)	20	LF		
2	6" PVC Service Lateral (Direct Bury)	100	LF		
3	4" PVC Service Lateral (Horizontal Directional Drill)	40	LF		
4	8" x 4" Service Wye	2	EA		
5	8" x 6" Service Wye	4	EA		
6	4" Clean Out for Future Connection	1	EA		
7	8" PVC Sewer Pipe 0'-6'	215	LF		
8	8" PVC Sewer Pipe 6'-8'	464	LF		
9	8" PVC Sewer Pipe 8'-10'	0	LF		
10	8" PVC Sewer Pipe 10'-12'	0	LF		
11	Standard Manhole 0'-6'	1	EA		
12	Standard Manhole 6'-8'	2	EA		
13	Standard Manhole 8'-10'	0	EA		
14	Standard Manhole 10'-12'	0	EA		
15	Cut-in Manhole	1	EA		
16	Abandon Existing 6" PVC Sewer Service	1	LS		
JASON STREET SEWER EXTENSION TO 5 LOTS ON MAY RIVER ROAD - TOTAL					