

GEOTECHNICAL ENGINEERING REPORT

PROPOSED VINEYARD VILLAGE CRESTVIEW, FLORIDA

PREPARED FOR:

ALDAY HOWELL ENGINEERING, INC. 4100 S. FERDON BOULEVARD, SUITE B2 CRESTVIEW, FLORIDA 32536

> 429 FLORIDA AVENUE LYNN HAVEN, FLORIDA 32444 TELEPHONE (850) 258.0994



August 21, 2022

Alday Howell Engineering, Inc. ATTN: John Feeney, P.E. 4100 S. Ferdon Boulevard Suite B2 Crestview, FL 32536

SUBJECT: Proposed Vineyard Village Development – Geotechnical Services Crestview, Florida MEI Project No. M122-105-052

Dear Mr. Feeney:

This letter forwards the results of our Geotechnical exploration for the proposed development. Our exploration consisted of Five (5) 25-feet deep Standard Penetration (SPT) borings in the proposed building footprint, six (6) 5-feet deep hand auger borings in the proposed pavement areas and stormwater management area, and One (1) Double Ring Infiltrometer (DRI) test in the proposed stormwater retention area.

The subsurface exploration was conducted to provide information needed in the design of an effective foundation system, stormwater area(s), and pavement area(s) for the referenced development. The following report presents the results of our study as well as our evaluation and recommendations pertaining to the geotechnical aspects of the project.

Project Information

The subject site is located northeast of W. Field Avenue and southwest of W. Bowers Avenue in Crestview, Florida. At the time of our exploration, the site was currently undeveloped and covered with surficial grasses and light to medium dense undergrowth. The site previously had single story residences that were razed prior to our mobilization. Based upon visual observations, the site appeared relatively level with less than 3 feet of grade change. At the time of writing this report, no structural or grading information was available, however; we anticipate less than 3 feet of cut/fill will be required to obtain finished floor elevation. Additionally, for engineering purposes, we have estimated max wall loads to be less than 2 kips per linear feet and column loads to be less than 30 kips.

If any of the above information is incorrect, please inform Magnum Engineering, Inc. (MEI) so that we can review and update our recommendations, as needed.

Proposed Vineyard Village – Geotechnical Services Crestview, Florida Page 2 of 6

Subsurface Conditions

Figure #1 show the Boring Location Plan and Figure #2 shows the Logs of Borings for Standard Penetration Test borings B-1 through B-5 and hand auger borings HA-1 through HA-6. The test locations were established in the field using the provided site plan with LAT/LONG coordinates and our hand-held GPS unit. Therefore, the borings should be considered only as accurate as the GPS unit (+/- 9 feet).

Upon completion of our field testing, the samples were brought back to the office for visual inspection, classification, and analysis by our engineering staff.

The building borings (B-1 through B-5) generally encountered very loose to loose slightly silty fine sands and silty fine sands from the existing ground surface to roughly 4 feet to 6 feet below existing grade underlain by loose to medium dense clayey fine sands to depth of 13 feet to 18 feet below existing grade underlain by medium dense to dense slightly silty fine sands to the boring termination depth of 25 feet below existing grade.

The pavement and stormwater borings generally encountered slightly silty, silty, and clayey fine sands throughout the depth of the 5 feet deep augers.

The above subsurface descriptions are of a generalized nature, provided to highlight the major soil strata encountered. The Logs of Boring should be reviewed for specific subsurface conditions at each boring location. The stratifications shown on the Logs of Boring represent the subsurface conditions at the actual boring locations only, and variations in the subsurface conditions can and may occur between boring locations and should therefore be expected. The stratifications represent the approximate boundary between subsurface materials, and the transitions between strata may be gradual.

Please refer to the attached logs of borings presented as Figure #2 for a more detailed description of the soils encountered in each borings.

Groundwater Conditions

Groundwater was encountered at approximately 18.0 feet below existing grade at the time of drilling (August 10, 2022), which was during a period of normal seasonal rainfall. Groundwater levels will fluctuate with rainfall and could vary several feet during typical seasonal fluctuations. Larger fluctuations are possible under severe weather conditions. We recommend that the Contractor verify the actual groundwater levels at the time of construction to determine potential impacts groundwater will have on construction procedures.

CONCLUSIONS AND RECOMMENDATIONS

<u>General</u>

The following geotechnical related design recommendations have been developed on the basis of the previously described project characteristics and subsurface conditions encountered. If there are any changes in these project criteria, including project location on the site, a review should be made by MEI to determine if modifications to the recommendations are warranted.

Once final design plans and specifications are available, a general review by MEI is recommended as a means to check that the evaluations made in preparation of this report are correct and that earthwork and foundation recommendations are properly interpreted and implemented

Site Preparation

The site should be cleared and grubbed of surface vegetation. As a minimum, it is recommended the clearing operations extend at least five feet beyond the development perimeters.

Proposed Vineyard Village – Geotechnical Services Crestview, Florida Page 3 of 6

The subgrade soils should be compacted to at least 95 percent of the Modified Proctor (ASTM D-1557) maximum dry density to a depth of 24 inches below footing and floor slab bottoms.

Engineered Fill

All fill used to raise the building area and pavement areas to final grades should consist of sandy soils with less than 15 percent passing the No. 200 sieve. These soils should be free of rubble, organics, clay, debris and other unsuitable material. Fill should be placed in lifts on the order of 12 inches or less (in loose thickness) and compacted to 95 percent of the soil's Modified Proctor maximum dry density, per ASTM D-1557.

Foundations

With proper subgrade preparation and compaction/densification as described herein, the site soils should be capable of supporting the proposed structure on shallow foundations. The existing near surface soils and fill soils should be prepared as previously recommended to improve foundation support and reduce total and differential settlements.

Based on the anticipated construction and site preparation requirements recommended herein, it is our opinion that the building can be supported on shallow foundations designed for a net maximum allowable bearing pressure of 2,000 pounds per square foot (psf). The following geotechnical related recommendations should be used for design and construction of the foundations.

- The foundation and floor slab should bear on properly improved existing subgrade or on properly placed and compacted cohesionless (sand) fill.
- The soils to a depth of one foot below the footings and floor slabs and all new fill should be compacted to 95 percent of the soil's Modified Proctor (ASTM D-1557) density.
- Exterior footings should be embedded so that the bottom of the foundation is a minimum of 18 inches below the adjacent compacted grades.
- Strip or wall footings should be a minimum of 18 inches wide and pad or column footings should be a minimum of three feet wide. The minimum footing sizes should be used regardless of whether or not the foundation loads and allowable bearing pressures dictate a smaller size.
- All footings should be constructed in a "dry" fashion.
- Structural elements should be centered on the footings such that the load is transferred evenly unless the footings are proportioned for eccentric loads.

Settlement

The settlement of shallow foundations supported on sandy soils should occur rapidly after loading. The majority of expected settlement should occur during construction as dead loads are imposed. Total settlements of footings are estimated to be less than 1 inch, with differential settlement on the order of 50 percent of the total settlements. Total and differential settlements of these magnitudes are usually considered tolerable for the anticipated construction; however, the tolerance of the proposed structures to the predicted total and differential settlements should be confirmed by the structural engineer.

Pavements

Initially, the pavement areas should be cleared, grubbed, and stripped of topsoil and other deleterious material (i.e. concrete pavement, previous building foundation remnants). Special care should be taken to insure that all stumps, root systems, and peaty soils are removed from beneath the proposed pavement areas.

Prior to placing fill soils, where applicable, the top of the ground surface should be compacted to a minimum soil density of 95% of the Modified Proctor Test (ASTM D1557). Structural fill soils should be placed in maximum 12-inch lifts and compacted to a minimum soil density of 95% of the Modified Proctor Test (ASTM D1557). The top 12 inches of subgrade should be compacted to a minimum soil density of 98% of the Modified Proctor Test (ASTM D1557). The top 12 inches of subgrade should be compacted to a minimum soil density of 98% of the Modified Proctor Test (ASTM D1557). The top 12 inches of subgrade should be compacted should have a minimum LBR value of 40. We recommend that structural fill soils, where planned, have a minimum LBR of 40.

Based on the subsurface conditions encountered in the test borings, we recommend using a graded aggregate base (i.e. limerock or crushed concrete). The base course should be compacted to a minimum soil density of 98% of the Modified Proctor Test (ASTM D1557) and have a minimum LBR of 100.

Without benefit of traffic loads, volumes, and serviceability parameters, a pavement section cannot be designed. However, typical parking lots in the local area generally consist of a minimum of 1½ inches of FDOT Superpave Mix SP-12.5 or SP-9.5 asphaltic concrete and a minimum of 6 inches of base. Moderate duty traffic areas (e.g. main entrance areas) typically have a minimum pavement section consisting of 2 inches of FDOT Superpave Mix SP-12.5 asphaltic concrete and 8 inches of base.

Preparation of the subgrade soils for the parking and drive lanes should be prepared in general accordance with the site soil preparation recommendations described for the building area. While specific traffic loads and volumes for the project have not been provided, we are providing recommended light-duty and medium-duty pavement sections, which have been successfully utilized for this type of commercial development in the Northwest Florida area with similar traffic loadings.

Light Duty (Automobile Parking)

- 1 ½ inches Asphalt Concrete (FDOT Superpave Mix SP-12.5 or SP-9.5)
- 6 inches Crushed Limerock or Graded Aggregate Base (minimum LBR 100)
- 12 inches stabilized subgrade (minimum LBR 40)

Medium Duty (Entrance Lanes)

- 2 inches Asphaltic Concrete (FDOT Superpave Mix SP-12.5)
- 8 inches Crushed Limerock or Graded Aggregate Base (minimum LBR 100)
- 12 inches Stabilized Subgrade (minimum LBR 40)

A rigid pavement section merits consideration for areas to receive relatively high concentrated sustained loads such as dumpsters and loading/storage areas. A rigid concrete pavement of 6 inches in minimum thickness will distribute concentrated loads over a greater area, hence reducing the possibility of high stress concentrations to the subgrade. The concrete used for rigid pavement should have a minimum 28-day flexural strength of 650 psi and a maximum slump of 4 inches. The subgrade should consist of a near uniform soil of equivalent moisture content and density. Pavement joints, reinforcing, and details should be designed in accordance with applicable American Concrete Institute (ACI) standards.

Proposed Vineyard Village – Geotechnical Services Crestview, Florida Page 5 of 6

The above recommended pavement sections represent minimum design thicknesses and, as such, periodic maintenance should be anticipated. Also, these recommended pavement sections should be confirmed or modified by your Civil Engineer, based on actual traffic and the owner's requirements. The pavement section materials and construction should comply with the Florida DOT and local municipality requirements.

Double Ring Infiltrometer Test

One (1) Double Ring Infiltrometer (DRI) test was performed in the field in general accordance with the procedures outlined in ASTM D-3385, ``Infiltration Rate of Soils in Field using Double Ring Infiltrometers". Testing consisted of initially clearing all surface vegetation and topsoil from within the test area. The Infiltration test was performed approximately 2-feet below existing grade at test location DRI-1. The outer ring, which is approximately 24 inches in diameter, was then driven to a depth of 6 inches below the exposed ground surface. The inner ring, approximately 12 inches in diameter, was then centrally located within the outer ring and driven to a depth of 2 inches. The two rings were then simultaneously filled with water to a height of 4 inches above the exposed ground surface test soils. The water level was maintained at this height throughout the test period, with the required amount of water added to maintain this level in both rings recorded at time intervals of ten minutes. After reaching a stabilized inflow of water, the test was continued in order to verify that a sustained infiltration rate has been achieved. The infiltration rate for the inner ring and the annular space between the rings is determined by dividing (a) the water volume used (within each specific area) during the stabilized flow period of the test, by (b) the specific area and (c) the time interval. Infiltration rates are generally converted to units of inches per hour. The infiltration rate for the inner ring, if different than the infiltration rate of the annular area between the rings, according to ASTM, should be used as the infiltration rate for the soils. The test yielded a measured sustained infiltration rate of 10.4 in/hr.

DESCRIPTION	LOCATION	DESIGN PARAMTER
SUSTAINED INFILTRATION RATE	DRI-1	10.4 IN/HR*
TEST DEPTH	DRI-1	2 FT BELOW EXISTING GRADE
FILLABLE POROSITY	DRI-1	30%
DEPTH TO EXISTING GROUNDWATER TABLE	DRI-1	18 FT BELOW EXISTING GRADE
DEPTH TO ESTIMATED SEASONAL HIGH GROUNDWATER TABLE	DRI-1	16 FT BELOW EXISTING GRADE

Environmental Resource Permitting (ERP) Design Parameters

* The above infiltration rate has not been factored and it is up to the designer to apply an appropriate factor of safety. We recommend using a transformation ratio of 1 horizontal to 1 vertical.

Proposed Vineyard Village – Geotechnical Services Crestview, Florida Page 6 of 6

Warranty and Limitations of Study

Our professional services have been performed, our findings obtained, and our recommendations prepared in accordance with generally accepted geotechnical engineering principles and practices. This warranty is in lieu of all other warranties, either expressed or implied. MEI is not responsible for the independent conclusions, opinions or recommendations made by others based on the field exploration and laboratory test data presented in this report.

Soil conditions at other locations may differ from those encountered in the test borings, and the passage of time may cause the soils conditions to change from those described in this report.

This report is intended for use by the designers of this project. While we have no objections to it being provided for review by parties to this project, it is not a specification document and is not to be used as a part of the specifications. If desired, we can assist in the development of specifications for this project based upon our exploration.

The nature and extent of variation and change in the subsurface conditions at the site may not become evident until the course of construction. Construction monitoring by the geotechnical engineer or his representative is therefore considered necessary to verify the subsurface conditions and to check that the soils connected construction phases are properly carried out. If significant variations or changes are in evidence, it may be necessary to reevaluate the recommendations in this report.

Furthermore, if the project characteristics are altered significantly from those discussed in this report, if the project information contained in this report is incorrect or if additional information becomes available. a review must be made by this office to determine if any modifications in the recommendations will be necessary.


We hope this letter provides sufficient information for the present. If you have any questions or

Sincerely, MAGNUM ENGINEERING. INC. J. J. LICENS No. 56813 110000000 PRO. STATE OF JAMES **#**. VICKERS, P.E. Sr. Geotechnical Engineer Florida Registration # 56813 Attachments: Figure #1 – Boring Location Riam Figure #3 – Double Ring Infiltrometer Test Results



BORING LOCATION PLAN

FIGURE #1



PHONE (850) 634-6084 * FAX (850) 526-4740 E-MAIL : info@aldayhowell.com FLORIDA CERTIFICATE OF AUTHORIZATION. NO. 26105

VINEYARD VILLAGE

SITE PLAN

SITE DATA:

PARCEL ID NUMBERS: 17-3N-23-2490-0133-017B 17-3N-23-2490-0133-0160 17-3N-23-2490-0133-014A 17-3N-23-2490-0133-014B 17-3N-23-2490-0133-014D

ZONING: MIXED USE (MU) PARKING REQUIREMENTS:

17-3N-23-2490-0133-0150 17-3N-23-2490-0133-006A 17-3N-23-2490-0133-006C 17-3N-23-2490-0133-014E TOTAL SITE AREA: 1.43 AC = 62,494 SF FUTURE LAND USE: MIXED USE (MU)

34 SPACES TOTAL PARKING REQUIRED FOR 30 UNITS 38 SPACES TOTAL PARKING REQUIRED FOR 34 UNITS PARKING SPACE REQUIREMENTS PER ITE PARKING GENERATION MANUAL (5TH) EDITION LAND USE CODE 220 LOW RISE APARTMENT

TOTAL PARKING PROVIDED: 45 SPACES

IMPERVIOUS SURFACE RATIO (ISR): MAXIMUM ALLOWED ISR: 0.80 PROPOSED ISR: 0.71

FLOOR AREA RATIO (FAR): MAXIMUM ALLOWED FAR: 2.0 PROPOSED FAR: 0.37

OPEN SPACE RATIO (OSR): MINIMUM ALLOWED OSR: 0.20 PROPOSED OSR: 0.29

LANDSCAPE BUFFER DIMENSIONS: FRONT (R/W) = 10'SIDE = 7.5'REAR = 7.5'

BUILDING SETBACK DIMENSIONS: FRONT (R/W) = 20'SIDE = 7.5'REAR = 15'

LEGEND:

PROPOSED BUILDING FOOTPRINT



LANDSCAPE BUFFER



PROPOSED CONCRETE SIDEWALK



PROPOSED ASPHALT PAVEMENT



OPEN SPACE AREA



BUILDING SETBACK

CONSTRUCTION PHASE LINE

2022-02 T.O. NO. NMM, NCS DRAWN BY JSF CHECKED BY_ 08/01/22 DATE



LOGS OF BORING

FIGURE # 2

TATI	026 Pierson Drive ynn Haven, Florida 32444 Telephone: 8502658332									PAGI	E 1 C	DF	
	Howell Engineering, Inc.	PROJECT I	NAME	Viney	/ard Village	9							
PROJECT NUMB	BER	PROJECT I			Okaloosa (County	/, Flori	da					
DATE STARTED	<u>8/10/22</u> COMPLETED <u>8/10/22</u>	GROUND ELEVATION HOLE SIZE											
DRILLING CONT	RACTOR _ GeoDrill Tech, LLC	GROUND V	VATEF	R LEVE	LS:								
DRILLING METH	OD <u>Standard Penetration Test (SPT)</u>	$ar{2}$ dept	тн то	GROU	NDWATER	R AT TI	ME O	F DRIL	LING	18.0	ft		
LOGGED BY J.	Governale CHECKED BY J. Vickers	ESTI	MATE	D SEAS	SONAL HIC	GH GW	/т						
NOTES		AFTE	R DRI	LLING									
			Й	%		ż	Т.	(9)	ATT	LIMIT:		NT	
DEPTH (ft) (ft) CRAPHIC LOG			SAMPLE TYPE NUMBER	RECOVERY (RQD)	BLOW COUNTS (N VALUE)	POCKET PEN. (tsf)	DRY UNIT WT. (pcf)	MOISTURE CONTENT (%)				FINES CONTENT	
DEPTH (ft) sRAPHIC LOG	MATERIAL DESCRIPTION		JMB MB	R		(tsf)	Def	ISTI	LIQUID	PLASTIC LIMIT	PLASTICITY INDEX	00	
			AMF	U U U U U U U	що́х	0CI	Ϋ́	0 M N O	lg ∃	LIV	AST	U L L S L L	
0			S S	R.		<u>م</u>		0		ш	Ч	Ľ	
В	Brown Slightly Silty Fine SAND (SP-SM)	\mathbb{N}	ss		2-2-2-2								
		/	1		(4)								
B	Brown/Orange Silty Fine SAND with Trace of Clay (SM)			1									
-1111		X	SS 2		1-1-2-2 (3)								
			}	-		-							
5		$ \rangle$	ss		3-3-3-3								
		/\	3		(6)								
В	Brown/Orange Clayey Fine SAND (SC)		ss]	4-5-5-5]							
		X	4		(10)								
		\leftarrow	}	-		-							
		ΙX	SS 5		4-5-7-9								
10		\square	5		(12)								
B	Brown/Orange Slightly Silty to Silty Fine SAND (SP-SM)	\square	ss]	7-10-12	1							
15		\square	6		(22)								
-													
В	Brown Slightly Silty Fine SAND (SP-SM)	\square	SS 7]	12-14-17								
20		Ľ	7		(31)								
			_										
L	ight Orange Fine SAND (SP)	\neg	ss		11-15-19								
25	Daving Transienties Drath at 05 0.5	<u> </u> /`	8	-	(34)								
	Boring Termination Depth at 25.0 feet.												

PROJECT NAME Vineyard Village PROJECT LOCATION Okaloosa County, Florida							
PROJECT LOCATION Okaloosa County Florida							
Chalobba County, Flohau							
GROUND ELEVATION HOLE SIZE							
GROUND WATER LEVELS:							
DEPTH TO GROUNDWATER AT TIME OF DRILLING 18.0 ft							
ESTIMATED SEASONAL HIGH GWT AFTER DRILLING							
SAMPLE TYPE NUMBER RECOVERY % (RQD) BLOW COUNTS (N VALUE) POCKET PEN. (1sf) DRY UNIT WT. (sf) DRY UNIT WT. (sf) DRY UNIT WT. LIMIT LIMIT PLASTIC LIMIT PLASTIC LIMIT PLASTIC INDEX CONTENT							
SS 1-1-1-1 (2)							
SS 1-1-1-1 (2)							
SS 2-2-2-2 (4)							
SS 2-2-3-3 (5)							
SS 3-4-5-5 5 (9)							
$\begin{array}{ c c c c c } \hline \\ \hline $							
SS 7 11-11-12 (23)							
SS 8 11-10-10 (20)							

ME	Magnum Engineering, Inc. 1026 Pierson Drive Lynn Haven, Florida 32444 Telephone: 8502658332				BO	RIN	IG N	NUN		R E E 1 C			
	day-Howell Engineering, Inc.	PROJECT NAME	Vine	yard Village	е								
	UMBER <u>M122-105-052</u>	PROJECT LOCA				/, Flori	ida						
DATE STAR	TED _ 8/10/22 COMPLETED _ 8/10/22	GROUND ELEVA				HOLE	E SIZE						
DRILLING C	ONTRACTOR GeoDrill Tech, LLC	GROUND WATE	R LEVE	LS:									
DRILLING M	ETHOD Standard Penetration Test (SPT)	$ arrow arrow black Depth to groundwater at time of drilling 18.0 ext{ ft}$							ft				
LOGGED BY	J. Governale CHECKED BY J. Vickers	ers ESTIMATED SEASONAL HIGH GWT											
NOTES		AFTER DR	ILLING										
		ц	%		Ż	Т.	()	AT	LIMIT:		NT		
o DEPTH (ft) GRAPHIC LOG	MATERIAL DESCRIPTION	SAMPLE TYPE NUMBER	RECOVERY (RQD)	BLOW COUNTS (N VALUE)	POCKET PEN. (tsf)	DRY UNIT WT. (pcf)	MOISTURE CONTENT (%)	LIQUID	PLASTIC LIMIT	~	FINES CONTENT		
	Tan Silty Fine SAND (SM)	ss 1		1-2-1-2 (3)									
	Brown/Orange Silty Fine SAND (SM)	ss 2		2-2-2-2 (4)									
5	Brown/Orange Clayey Fine SAND (SC)	ss 3		3-2-3-3 (5)									
			-	4-4-5-6									
				(9) 4-6-6-8									
10		5	_	(12)									
<u>15</u>	Brown/Orange Slightly Silty Fine SAND (SP-SM)	SS 6	_	8-10-13 (23)	-								
20	∑	SS 7	_	30-50	_								
25	Boring Termination Depth at 25.0 feet.	SS 8	_	15-17-18 (35)	-								

1026 Pierson Drive Lynn Haven, Florida 32444 Telephone: 8502658332					BO	KIN	IGN	NUIV	PAGE			
ay-Howell Engineering, Inc.	PROJEC	T NAME	Viney	/ard Village	9							
ED <u>8/10/22</u> COMPLETED <u>8/10/22</u>	GROUNI) ELEVA				HOLE	SIZE					
NTRACTOR _ GeoDrill Tech, LLC	_											
THOD Standard Penetration Test (SPT)	$ar{ abla}$ de	PTH TO	GROU	NDWATER	AT TI	ME O	F DRIL	LING	18.0	ft		
					SH GW	π						
	AF	ter dri	LLING									
MATERIAL DESCRIPTION		PLE TYPE JMBER	OVERY % (RQD)	BLOW OUNTS VALUE)	KET PEN. (tsf)	UNIT WT. (pcf)	ISTURE ITENT (%)			5	FINES CONTENT	
		SAMI	REC.	ΞŬΖ	POC	DRY	CON	LIN	PLA:	PLAS ⁻ IND	FINES	
Brown Slightly Silty Fine SAND (SP-SM)		ss 1		2-3-4-3 (7)								
Brown/Orange Silty Fine SAND with Trace of Clay (SM)		SS 2		3-4-3-3 (7)								
		ss 3		3-2-3-3 (5)								
Brown/Orange Clayey Fine SAND (SC)		ss 4		3-3-4-6 (7)	-							
		ss 5	-	3-4-6-7 (10)	-							
Brown/Orange Slightly Silty to Silty Fine SAND (SP-SM)		SS 6	-	4-6-7 (13)	-							
Brown/Orange Slightly Silty Fine SAND (SP-SM)		SS 7	-	13-15-17 (32)	-							
Light Orange Slightly Silty Fine SAND (SP-SM) Boring Termination Depth at 25.0 feet.		SS 8	-	8-10-11 (21)	-							
	wy-Howell Engineering, Inc. MBER M122-105-052 ED 8/10/22 COMPLETED 8/10/22 NTRACTOR GeoDrill Tech, LLC THOD Standard Penetration Test (SPT) J. Governale CHECKED BY J. Vickers MATERIAL DESCRIPTION Brown Slightly Silty Fine SAND (SP-SM) Brown/Orange Silty Fine SAND with Trace of Clay (SM) Brown/Orange Clayey Fine SAND (SC) Brown/Orange Slightly Silty to Silty Fine SAND (SP-SM) Brown/Orange Slightly Silty Fine SAND (SP-SM) Light Orange Slightly Silty Fine SAND (SP-SM)	my-Howell Engineering, Inc. PROJEC MBER_M122-105-052 PROJEC ED_8/10/22 COMPLETED_8/10/22 GROUND NTRACTOR_GeoDrill Tech, LLC GROUND J. Governale CHECKED BY J. Vickers J. Governale CHECKED BY J. Vickers MATERIAL DESCRIPTION Image: Silightly Sility Fine SAND (SP-SM) Brown/Orange Silightly Sility Fine SAND (SC) Image: Silightly Sility Fine SAND (SC) Brown/Orange Slightly Sility to Sility Fine SAND (SP-SM) Image: Silightly Sility Fine SAND (SP-SM) Brown/Orange Slightly Sility Fine SAND (SP-SM) Image: Silightly Sility Fine SAND (SP-SM) Image: Slightly Sility Fine SAND (SP-SM) Image: Slightly Sility Fine SAND (SP-SM) Image: Slightly Sility Fine SAND (SP-SM) Image: Slightly Sility Fine SAND (SP-SM)	wy-Howell Engineering, Inc. PROJECT NAME MBER_M122-105-052 PROJECT LOCAT ED_8/10/22 COMPLETED_8/10/22 GROUND ELEVA INTRACTOR_GeoDrill Tech, LLC GROUND WATEF THOD_Standard Penetration Test (SPT) Image: CHECKED BY_J_Vickers ESTIMATEI J_Governale CHECKED BY_J_Vickers ESTIMATEI MATERIAL DESCRIPTION Image: CHECKED BY_J_Vickers SS Brown/Orange Silty Fine SAND (SP-SM) Image: SS SS Brown/Orange Clayey Fine SAND (SC) Image: SS SS Brown/Orange Silghtly Silty Fine SAND (SP-SM) Image: SS SS Brown/Orange Silghtly Silty Fine SAND (SP-SM) Image: SS SS Brown/Orange Silghtly Silty Fine SAND (SP-SM) Image: SS SS Brown/Orange Silghtly Silty Fine SAND (SP-SM) Image: SS SS Brown/Orange Silghtly Silty Fine SAND (SP-SM) Image: SS SS Brown/Orange Silghtly Silty Fine SAND (SP-SM) Image: SS SS Brown/Orange Silghtly Silty Fine SAND (SP-SM) Image: SS SS Brown/Orange Silghtly Silty Fine SAND (SP-SM) Image: SS SS Brown/Orange Silghtly Silty Fine SAND (SP-SM) Image: SS	wy-howell Engineering, Inc. PROJECT NAME Vince MBER_M122-105-052 PROJECT LOCATION GROUND ELEVATION ED_8/10/22 COMPLETED_8/10/22 GROUND WATER LEVE THOD_Standard Penetration Test (SPT) GROUND WATER LEVE Formation J_Governale CHECKED BY J_Vickers GROUND WATER LEVE MATERIAL DESCRIPTION MATERIAL DESCRIPTION SS 1 Brown Slightly Slity Fine SAND (SP-SM) SS 2 SS 3 Brown/Orange Slightly Slity Fine SAND (SP-SM) SS 4 SS 5 Brown/Orange Slightly Slity Fine SAND (SP-SM) SS 6 SS 7 Brown/Orange Slightly Slity Fine SAND (SP-SM) SS 7 SS 8 Brown/Orange Slightly Slity Fine SAND (SP-SM) SS 8 SS 8	y-bowell Engineering, Inc. PROJECT NAME Vineyard Village PROJECT LOCATION Okaloosa (Colored a) MBER M122-105-052 GROUND ELEVATION GROUND WATER GROUND WATER EVELS: Intractor GeoDrill Tech, LLC GROUND WATER LEVELS: Important of the colored and th	Product Engineering, Inc. PROJECT NAME Vineyard Village MBER M122-105-052 PROJECT LOCATION Otalocas County ED Ø/10/22 COMPLETED Ø/10/22 GROUND ELEVATION IDD Standard Penetration Test (SPT) GROUND WATER LEVELS: GROUND WATER LEVELS: J. Governale CHECKED BY J. Vickers Standard Penetration Test (SPT) J. Governale CHECKED BY J. Vickers Standard Penetration Test (SPT) J. Governale CHECKED BY J. Vickers Standard Penetration Test (SPT) MATERIAL DESCRIPTION MATERIAL DESCRIPTION SS <	where PROJECT NAME Vinevard Village MBER M122-105-062 PROJECT LOCATION Okalocsa County, Flori ED 9/10/22 COMPLETED 9/10/22 GROUND ELEVATION HOLE CadeDrift Tech, LLC GROUND WATER LEVELS: Image: CheckEd BY J. Covernale CHECKED BY J. Vickers Image: CheckEd BY J. Vickers Image: CheckEd BY J. Vickers Image: CheckEd BY J. Covernale Image: CheckEd BY J. Vickers Image: CheckEd BY J. Vickers Image: CheckEd BY J. Vickers Image: CheckEd BY J. Vickers Image: CheckEd BY J. Vickers Image: CheckEd BY J. Vickers Image: CheckEd BY J. Vickers Image: CheckEd BY J. Vickers Image: CheckEd BY J. Vickers Image: CheckEd BY J. Vickers Brown/Orange Silghtly Silty Fine SAND (SP-SM) Image: Sightly Silty F	Webwell Engineering, Inc. PROJECT NAME_Vineyard Village MBER_M122-105-052 PROJECT LOCATION_Okaloosa County, Florida OBJU1022 COMPLETED_0/10/22 COMPLETED_0/10/22 NTRACTOR_GeoDrill Tech, LLC GROUND ELEVATION	Provedil Engineering, Inc. PROJECT NAME Vineyard Village MBERM122-105-052 PROJECT LOCATION_Okalosa County, Florida ROUE SIZE MRATCRIAL_GOUND LETED8/10/22 GROUND ELEVATION	PROJECT NAME Vineyard Village MBER_M122-105-052 PROJECT LOCATION Okaloosa County, Florida GROUND ELEVATION HOLE SIZE PROJECT LOCATION HOLE SIZE GROUND MATER LEVELS: GROUND WATER AT TIME OF DRILLING J. Governale CHECKED BY J. Vickers MATERIAL DESCRIPTION Standard Panetration Test (SPT) Ground Standard Panetration Test (SPT) MATERIAL DESCRIPTION Standard Panetration Test (SPT) ATTERNER Brown/Orange Sitightity Sitity Fine SAND (SP-SM) SS SS Brown/Orange Slightity Silty Fine SAND (SP-SM) SS 4-6-7 Brown/Orange Slightity Silty Fine SAND (SP-SM) SS SS Brown/Orange Slightity Silty Fine SAND (SP-SM) SS 13-15-17 Brown/Orange Slightity Silty Fine SAND (SP-SM) SS SS Srown/Orange Slightity Silty Fine SAND (SP-SM) SS 13-15-17 Light Orange Slightity Silty Fine SAND (SP-SM) SS 8 Brown/Orange Slightity Silty Fine SAND (SP-SM) SS 8 Brown/Orange Slightity Silty Fine SAND (SP-SM) SS 8 Brown/Orange Slightity Silty Fine SAND (SP-SM) SS 8	Wheele Engineering. Inc. PROJECT NAME Vineyard Village MBER_M122-105-062 PROJECT LOCATION Okaloosa County, Florida D0_01022	

MEL 1026 Lynn	um Engineering, Inc. Pierson Drive Haven, Florida 32444				BO	RIN	IG N	IUN		R E E 1 C		
Telep	hone: 8502658332 Il Engineering, Inc.	PROJECT NAME	Vine	yard Village	Ð							
PROJECT NUMBER	M122-105-052	PROJECT LOCA		Okaloosa	County	/, Flori	da					
DATE STARTED 8/1	0/22 COMPLETED 8/10/22	GROUND ELEVATION HOLE SIZE										
ORILLING CONTRAC	TORGeoDrill Tech, LLC		R LEVE	ELS:								
ORILLING METHOD	Standard Penetration Test (SPT)	🛛 🗠 🔤 СЕРТН ТО	GROU	INDWATEF			F DRIL	LING	18.0	ft		
OGGED BY J. Gov	ernale CHECKED BY J. Vickers	ESTIMATE	D SEA	SONAL HIC	SH GW	л						
		AFTER DR	LLING	i								
		ш	%			<u> </u>		ATT	LIMIT:	ERG	L	
_ ♀		SAMPLE TYPE NUMBER	2	s⊆	POCKET PEN. (tsf)	DRY UNIT WT. (pcf)	MOISTURE CONTENT (%)				FINES CONTENT	
(ff) (ff) LOG	MATERIAL DESCRIPTION	HE	RECOVERY (RQD)	BLOW COUNTS (N VALUE)	ET (jst)	pcf)	STU EN	≘⊢	PLASTIC LIMIT	l E X C	0	
2 8		MUN	Ю. ПО ПО ПО		S S S S		100 L	LIQUID	LIM LIM	NDE	S U U	
0		S	R		۲ ۲	Ľ۵	20		료	PLASTICITY INDEX	EIN	
	ilty Fine SAND (SM)	V ss		2-3-3-2								
				(6)								
			-		-							
		$ \rangle $ ss		2-2-2-2								
		2		(4)								
5 Brown	n/Orange Clayey Fine SAND (SC)	V ss		2-3-2-3								
				(5)								
			-		-							
				3-4-6-7								
		4		(10)								
		V ss		4-6-7-9								
				(13)								
10		<u> </u>	-		-							
			4		-							
	n/Orange Silty Fine SAND (SM)			7-11-12 (23)								
<u>15</u>			-	(23)	-							
			1									
			1									
			1									
	n/Orange Slightly Silty Fine SAND (SP-SM)	SS 7	1	18-19-22								
20			-	(41)	-							
			1									
			1									
		V ss	1	16-17-19								
25	Device Territoria Device 105.01	8	4	(36)	-							
	Boring Termination Depth at 25.0 feet.		1									
			1									
			1									
			1									
			1									
			1		1				1			

Magnum Engineering, Inc. 1026 Pierson Drive Lynn Haven, Florida 32444 Telephone: 8502658332	BORING NUMBER HA-1 PAGE 1 OF 1
CLIENT Alday-Howell Engineering, Inc.	PROJECT NAME Vineyard Village
	PROJECT LOCATION Okaloosa County, Florida
	GROUND ELEVATION HOLE SIZE
DRILLING CONTRACTOR GeoDrill Tech, LLC	
DRILLING METHOD Hand Auger Boring	
LOGGED BY J. Governale CHECKED BY J. Vickers NOTES	
HL HL HL HC HC HC HC HC HC HC HC HC HC HC HC HC	SAMPLE TYPE NUMBER RECOVERY % (RQD) BLOW COUNTS (N VALUE) POCKET PEN. (15f) DRY UNIT WT. (15f) DRY UNIT WT. (15f) DRY UNIT WT. (15f) DRY UNIT WT. (15f) DRY UNIT WT. (15f) DRY UNIT WT. (1001) LIMIT LIMIT PLASTIC TY DRATICITY SONTENT CONTENT FINES CONTENT
Brown/Orange Silty Fine SAND (SM) 2.5 2.5 5.0 Brown/Orange Clayey Fine SAND (SC) 5.0 Boring Termination Depth at 5.0 feet.	

Magnum Engineering, Inc. 1026 Pierson Drive Lynn Haven, Florida 32444 Telephone: 8502658332	BORING NUMBER HA-2 PAGE 1 OF 1
CLIENT Alday-Howell Engineering, Inc.	PROJECT NAME _ Vineyard Village
	PROJECT LOCATION Okaloosa County, Florida
	GROUND ELEVATION HOLE SIZE
DRILLING CONTRACTOR _ GeoDrill Tech, LLC	
DRILLING METHOD Hand Auger Boring	
LOGGED BY J. Governale CHECKED BY J. Vickers	
NOTES	
H H H H H H H H H H H H H H H H H H H	SAMPLE TYPE NUMBER RECOVERY % (ROD) (ROD) (SOUNTS (N VALUE) (SOUNTS) (SOUNTS) (SOUNTS) (SONTENT PLASTICITY (%) (%)
2.5 Brown/Orange Silty Fine SAND (SP-SM) 5.0 Brown/Orange Silty Fine SAND (SM)	

\mathbb{N}	Æ	Magnum Engineering, Inc. 1026 Pierson Drive Lynn Haven, Florida 32444 Telephone: 8502658332	BORING NUMBER HA PAGE 1 OF										
CLIE	ENT Ald	day-Howell Engineering, Inc.											
		UMBER <u>M122-105-052</u>											
DAT	E STAR	TED _8/10/22 COMPLETED _8/10/22	GROUN	D ELEVA				HOLE	SIZE				
DRII	LING C	ONTRACTOR GeoDrill Tech, LLC	GROUN	D WATER	LEVE	LS:							
DRII	LING M	ETHOD Hand Auger Boring	DEPTH TO GROUNDWATER AT TIME OF DRILLING										
LOG	GED B	J. Governale CHECKED BY J. Vickers	E\$	TIMATE) SEA	SONAL HIG	SH GW	т					
NOT	'ES		AF	TER DRI	LLING		,						
0.0 (#)		MATERIAL DESCRIPTION		SAMPLE TYPE NUMBER	RECOVERY % (RQD)	BLOW COUNTS (N VALUE)	POCKET PEN. (tsf)	DRY UNIT WT. (pcf)	MOISTURE CONTENT (%)	<u> </u>			FINES CONTENT (%)
GEOTECH BH COLUMNS VINEYARD VILLAGE.GPJ GINT STD US LAB.GDT 8/16/22		Brown/Orange Silty Fine SAND (SM) Brown/Orange Clayey Fine SAND (SC) Boring Termination Depth at 5.0 feet.		AU									
GEOTECH BH COLU													

ME	Magnum Engineering, Inc. 1026 Pierson Drive Lynn Haven, Florida 32444 Telephone: 8502658332				E	BOR	ING	6 NU			₩ 1 0	
CLIENT A	Iday-Howell Engineering, Inc.	PROJEC	T NAME	Vine	/ard Village	e						
	NUMBER				Okaloosa (, Flori	da				
DATE STAI		22 GROUND ELEVATION HOLE SIZE										
DRILLING	CONTRACTOR GeoDrill Tech, LLC	GROUN	D WATER	LEVE	LS:							
	METHOD Hand Auger Boring				NDWATER							
	Y J. Governale CHECKED BY J. Vickers				Sonal Hig							
NOTES		_ AF		LLING				1		ERBE		
DEPTH (ft) GRAPHIC LOG	MATERIAL DESCRIPTION		SAMPLE TYPE NUMBER	RECOVERY % (RQD)	BLOW COUNTS (N VALUE)	POCKET PEN. (tsf)	DRY UNIT WT. (pcf)	MOISTURE CONTENT (%)				FINES CONTENT (%)
	Brown/Orange Silty Fine SAND (SM) Brown/Orange Clayey Fine SAND (SC) Boring Termination Depth at 5.0 feet.		AU									

ME	Magnum Engineering, Inc. 1026 Pierson Drive Lynn Haven, Florida 32444 Telephone: 8502658332				E	BOR	ING	6 NU			₩ ■ 1 0	
	day-Howell Engineering, Inc.	PROJEC	T NAME	Viney	/ard Village	e						
	NUMBER <u>M122-105-052</u>				Okaloosa (, Flori	da				
DATE STA	RTED8/10/22 COMPLETED8/10/22	GROUN	D ELEVA				HOLE	SIZE				
	CONTRACTOR GeoDrill Tech, LLC											
	METHOD Hand Auger Boring	_			NDWATER							
	Y _J. Governale CHECKED BY _J. Vickers				SONAL HIC							
		_ ^						1	ATT	ERBE	RG	Г
DEPTH DEPTH (ft) (ft) GRAPHIC LOG	MATERIAL DESCRIPTION		SAMPLE TYPE NUMBER	RECOVERY % (RQD)	BLOW COUNTS (N VALUE)	POCKET PEN. (tsf)	DRY UNIT WT. (pcf)	MOISTURE CONTENT (%)	<u> </u>			FINES CONTENT (%)
	Brown/Orange Silty Fine SAND (SM) Brown/Orange Clayey Fine SAND (SC) Boring Termination Depth at 5.0 feet.		AU									

ME	Magnum Engineering, Inc. 1026 Pierson Drive Lynn Haven, Florida 32444 Telephone: 8502658332	BORING NUMBER HA-6 PAGE 1 OF 1										
	lday-Howell Engineering, Inc.	_ PROJECT I	NAME	Viney	ard Village	•						
	NUMBERM122-105-052											
	RTED 8/10/22 COMPLETED 8/10/22						HOLE	SIZE				
	CONTRACTOR GeoDrill Tech, LLC											
	METHOD Hand Auger Boring											
	Y _J. Governale CHECKED BY _J. Vickers				Sonal Hig							
						r	1		ATT	ERBE	RG	— ⊢
DEPTH (ft) GRAPHIC LOG	MATERIAL DESCRIPTION		SAMPLE TYPE NUMBER	RECOVERY % (RQD)	BLOW COUNTS (N VALUE)	POCKET PEN. (tsf)	DRY UNIT WT. (pcf)	MOISTURE CONTENT (%)	LIQUID	IMITS	PLASTICITY INDEX	FINES CONTENT (%)
	Tan Silty Fine SAND (SM) Tan Slightly Silty Fine SAND (SP-SM) Boring Termination Depth at 5.0 feet.		AU								PL	



DOUBLE RING INFILTROMETER TEST RESULTS


FIGURE # 3



Double-Ring Field Infiltration Test

Test Location:	DRI-1	
Project Name:	Vineyard Village	
Project Location:	Okaloosa County	
Test Depth:	>10.0 ft	
Depth to GWT:	8.5 ft	
Inner Ring Diameter:	12 in	0.3048 m
Outer Ring Diameter:	24 in	0.6096 m
Pre-Saturation	30 min	
Area Outer Ring:	3.1416 ft^2	0.00202683 m^2
Area Inner Ring:	0.7854 ft^2	0.00050671 m^2
Net Outer Ring Area:	2.3562 ft^2	0.00152013 m ²

	Inner Ring		
Cycle	ElapTime	Vol Used	Infiltration
	(sec)	(in^3)	Rate (ft/sec)
1	300	103	2.53E-04
2	300	103	2.53E-04
3	300	103	2.53E-04
4	300	103	2.53E-04
5	300	100	2.46E-04
6	300	100	2.46E-04
7	300	100	2.46E-04
8	300	100	2.46E-04
9	300	95	2.33E-04
10	300	95	2.33E-04
11	300	95	2.33E-04
12	300	95	2.33E-04
13	300	95	2.33E-04
14	300	95	2.33E-04
15	300	95	2.33E-04
16	300	95	2.33E-04
17	300	95	2.33E-04
18	300	95	2.33E-04
Results	Sustained Rate	98	2.40E-04



APPENDIX A