ARLINGTON VIRGINIA

Construction Drawings For: Marcey Road Park Improvements

(By Right) 2722 Marcey Road, Arlington, VA 22207

SHEET LIST TABLE

	Sheet List Table
SHEET	Sheet Title
Number C-01	Cover Sheet
1 OF 3	Signed Topographic Survey
2 OF 3	SIGNED TOPOGRAPHIC SURVEY
3 OF 3	SIGNED TOPOGRAPHIC SURVEY
C-03	EXISTING CONDITIONS PLAN
LF-01	TREE PRESERVATION PLAN - PHASE I
LF-02	TREE PRESERVATION PLAN - PHASE 2
LF-03	TREE PRESERVATION DETAILS
LF-04	EXISTING TREE TABLE - TREE CONDITION SUMMARY
C-04	DEMOLITION PLAN
C-05	EROSION AND SEDIMENT CONTROL - PHASE I
C-06	EROSION AND SEDIMENT CONTROL - PHASE I
C-07	EROSION AND SEDIMENT CONTROL NOTES
C-08	EROSION AND SEDIMENT CONTROL DETAILS
C-00 C-09	SITE PLAN
C-10	MATERIALS PLAN
C-11	GRADING PLAN
C-12	UTILITY PLAN
C-13	ADA Access Plan
C-14	Layout Plan
C-15	JOINT LAYOUT PLAN
C-16	UTILITY DETAILS
C-17	STORM SEWER PROFILES AND DETAILS
C-18	PRE- DEVELOPMENT WATER QUALITY MAP
C-19	Post- Development Water Quality Map
C-20	Stormwater Management Plan
C-21	STORMWATER MANAGEMENT NARRATIVE & CALCULATIONS
C-22	Stormwater Management Notes and Details
C-23	Stormwater Management Details
C-24	Soil Boring Logs
C-25	WATER QUALITY IMPACT ASSESSMENT AND POLLUTION PREVENTIO PLAN
E-0.1	Electrical Symbols List, Details, & Diagrams
EI.I	Electrical Site Plan
E5.0	ELECTRICAL DETAILS
E5.I	ILLUMINATON SUMMARY & EQUIPMENT LAYOUT
E5.2	Control System Summary
L-01	SITE DETAILS - FLATWORK
L-02	SITE DETAILS - FLATWORK
L-03	Site Details - Walls
L-03B	Site Details - Walls
L-03C	SITE DETAILS - WALLS
L-04	SITE DETAILS - SIGNAGE
L-05	SITE DETAILS - FURNISHINGS
L-06	SITE DETAILS - FURNISHINGS AND TENNIS & BASKETBALL DETAIL
L-07	SITE DETAILS - TENNIS & BASKETBALL DETAILS SITE DETAILS - TENNIS & BASKETBALL DETAILS
L-08 L-09	SITE DETAILS - TENNIS & BASKETBALL DETAILS SITE DETAILS - DRINKING FOUNTAIN
L-09 A-01	PICNIC SHELTER
A-01 A-02	PICNIC SHELTER
A-02	SHADE STRUCTURE FOOTING & STEEL FRAME
LP-01	PLANTING PLAN
LP-02	Planting Plan - Plaza Area
LP-03	PLANTING DETAILS
REF-01	REFORESTATION PLAN
ALT-01	BID ALTERNATES

GENERAL NOTES

- THE CONTRACTOR SHALL FULLY ACQUAINT HIMSELF WITH THE CONDITIONS OF THE SITE. THE CONTRACTOR SHALL THOROUGHLY EXAMINE AND BE FAMILIAR WITH THE DRAWINGS AND SPECIFICATIONS. SHOULD THE CONTRACTOR FIND ANY DISCREPANCIES, OMISSIONS, AMBIGUITIES, OR CONFLICTS IN OR AMONG THE CONTRACT DOCUMENTS OR BE IN DOUBT AS TO THEIR MEANING, HE SHALL BRING THESE ITEMS TO THE ATTENTION OF THE PROJECT OFFICER FOR DIRECTION BEFORE PROCEEDING WITH WORK.
- 2. THE CONTRACTOR SHALL OBTAIN ALL NECESSARY PERMITS AND BE RESPONSIBLE FOR ADHERENCE TO ALL ORDINANCES, REGULATIONS, LAWS AND CODES HAVING JURISDICTION OVER THE PROPERTY.
- 5. THE CONTRACTOR SHALL SUBMIT A REQUIRED "RESPONSIBLE LAND DISTURBER" CERTIFICATION LETTER AS PART OF OBTAINING A BUILDING (OR DISTURBANCE) PERMIT.
- 4. THE CONTRACTOR IS RESPONSIBLE FOR LICENSING AS REQUIRED BY APPLICABLE REGULATORY AGENCIES.
- 5. THE CONTRACTOR IS RESPONSIBLE FOR ALL SALES, USE AND CAPITAL GAINS TAXES.
- 6. UTILITY LOCATIONS SHOWN ON THIS PLAN ARE APPROXIMATE LOCATIONS DETERMINED FROM VISIBLE EVIDENCE AND AVAILABLE RECORDS. ADDITIONAL UNDERGROUND UTILITY LINES MAY BE PRESENT THAT ARE NOT SHOWN. IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO LOCATE AND PRESERVE EXISTING UTILITIES.
- 7. CONTRACTOR SHALL NOT SUBSTITUTE PRODUCTS OR MATERIALS WITHOUT PRIOR APPROVAL BY THE PROJECT OFFICER.
- 8. THE CONTRACTOR SHALL IDENTIFY ALL STAGING AREAS AND LIMITS OF WORK FOR APPROVAL BY THE PROJECT OFFICER PRIOR TO THE START OF WORK. AREAS OUTSIDE LIMITS OF WORK SHALL NOT BE USED FOR STORAGE OR MOVEMENT OF MATERIALS, MACHINERY OR DEBRIS.
- 9. THE CONTRACTOR SHALL OBTAIN THE PROJECT OFFICER'S APPROVAL FOR TIMES OF DAY DURING WHICH CONSTRUCTION OPERATIONS MAY OCCUR. ALL CONSTRUCTION OPERATIONS SHALL OCCUR WITHIN TIMES SPECIFIED BY LOCAL ORDINANCES.
- 10. CONSTRUCTION ACTIVITIES FOR THIS PROJECT OCCUR ENTIRELY ON PARK PROPERTY, THEREFORE, A MAINTENANCE OF TRAFFIC (MOT) PLAN IS NOT EXPECTED TO BE REQUIRED. HOWEVER, IF THE ARLINGTON DEPARTMENT OF ENVIRONMENTAL SERVICES (DES) DETERMINES THAT AN MOT PLAN IS REQUIRED, THE CONTRACTOR SHALL BE RESPONSIBLE FOR PROVIDING THE PLAN TO DES FOR THEIR REVIEW AND APPROVAL.
- II. THE CONTRACTOR SHALL BE ON SITE AT TIME OF ALL MATERIALS DELIVERIES.
- 12. THE CONTRACTOR SHALL KEEP THE SITE CLEAN AND FREE OF TRASH AT ALL TIMES DURING CONSTRUCTION. THE CONTRACTOR SHALL PROVIDE A TRASH RECEPTACLE TO BE USED ON SITE DURING CONSTRUCTION AND SHALL REMOVE TRASH FROM THE SITE ON A DAILY BASIS.
- 13. THE CONTRACTOR SHALL KEEP VEHICULAR ACCESS AREAS CLEAN DURING CONSTRUCTION. VEHICULAR AND OTHER PAVED AREAS SHALL BE WASHED FREE OF MUD ON A WEEKLY BASIS DURING CONSTRUCTION.
- 14. THE CONTRACTOR SHALL SECURE THE CONSTRUCTION AREA WITH FENCING AT END OF WORKDAY AND WHEN CONTRACTOR IS NOT ON SITE.
- 15. THE CONTRACTOR SHALL DISTRIBUTE ALL PROJECT MATERIALS AND EQUIPMENT AND DISTRIBUTE ANY STOCKPILES IN SUCH A MANNER AS TO PROTECT EXISTING CONDITIONS, SUCH AS UTILITIES, PAVING, VEGETATION, ETC. THE CONTRACTOR SHALL NOT STOCKPILE SOIL OR CONSTRUCTION MATERIALS, OR DRIVE VEHICLES WITHIN THE CRITICAL ROOT ZONE OF EXISTING TREES TO REMAIN. THE CONTRACTOR SHALL OBTAIN THE PROJECT OFFICER'S APPROVAL FOR ALL CONSTRUCTION ACCESS AREAS, STAGING AND STOCKPILE AREAS PRIOR TO CONSTRUCTION.
- 16. THE CONTRACTOR SHALL NOT BLOCK STREETS, PARKING AREAS, HOUSE OR DRIVEWAY ENTRANCES DURING CONSTRUCTION WITHOUT THE PROJECT OFFICER'S PERMISSION AND APPROVAL OF ANY RIGHT-OF-WAY PERMITS IF REQUIRED.
- 17. THE CONTRACTOR SHALL STAKE THE ALIGNMENT OF ALL PAVEMENT, WALLS, CURBING, SAFETY SURFACING AND SITE FEATURES IN THE FIELD FOR APPROVAL BY THE PROJECT OFFICER PRIOR TO CONSTRUCTION.
- 18. THE CONTRACTOR SHALL PROMPTLY REPAIR ALL DAMAGE TO EXISTING PAVEMENT, DRIVEWAYS, AND ADJACENT FACILITIES CAUSED BY CONSTRUCTION OPERATIONS. COST OF REPAIRS SHALL BE AT CONTRACTOR'S EXPENSE.
- 19. CONTRACTOR SHALL REMOVE ALL EXCESS SOIL, TEMPORARY FENCING, EROSION CONTROL MEASURES, STABILIZATION MATERIALS, AND OTHER DEBRIS AND SHALL DISPOSE OF LEGALLY UPON COMPLETION OF THE PROJECT. CONTRACTOR SHALL THOROUGHLY WASH AND CLEAN ALL PAVED AREAS, WALLS, SITE FURNISHINGS AND FEATURES, ETC. UPON COMPLETION OF THE PROJECT.
- 20. REFER TO INDIVIDUAL DRAWINGS FOR ADDITIONAL NOTES.

DEPARTMENT OF PARKS AND RECREATION

PARK DEVELOPMENT DIVISION

2100 CLARENDON BOULEVARD, SUITE 414, ARLINGTON, VA 22201 PHONE: 703.228.3332 FAX: 703.228.3328 WWW.ARLINGTONVA.US

100% CONSTRUCTION DRAWINGS

ARLINGTON COUNTY DEPARTMENT OF ENVIRONMENTAL SERVICES WATER-SEWER CONSTRUCTION REQUIREMENTS (REVISED MARCH 2005)

- ALL MATERIALS AND CONSTRUCTION SHALL BE IN ACCORDANCE WITH ARLINGTON COUNTY DEPARTMENT OF ENVIRONMENTAL SERVICES CONSTRUCTION STANDARDS & SPECIFICATIONS (LATEST EDITION) AND SHALL BE APPROVED BY THE DEPARTMENT OF ENVIRONMENTAL SERVICES. UPON PHYSICAL INSPECTION, THE COUNTY RESERVES THE RIGHT TO REJECT THE USE OF ANY MATERIAL FOUND TO BE DEFECTIVE OR NOT CONFORMING TO THE STANDARDS AND SPECIFICATIONS.
- 2. BEFORE START OF CONSTRUCTION, THE CONTRACTOR SHALL FURNISH THE FOLLOWING INFORMATION AND/OR EVIDENCE OF COMPLIANCE WITH ALL APPLICABLE REGULATIONS AND LAWS, TO THE ARLINGTON COUNTY DEPARTMENT OF ENVIRONMENTAL SERVICES:
- 2.A. THE NAME AND ADDRESS OF THE CONTRACTOR HIRED TO WORK ON THE PROJECT. THE CONTRACTOR SHALL BE REGISTERED IN THE COMMONWEALTH OF VIRGINIA. SATISFACTORY EVIDENCE SHALL BE FURNISHED OF THE CONTRACTOR'S PRIOR EXPERIENCE AS PRIME CONTRACTOR IN THE CONSTRUCTION OF WATER MAINS AND/OR SANITARY SEWER INSTALLATIONS. FURTHER, THE CONTRACTOR SHALL FURNISH A LETTER WITH A LIST OF MATERIALS AND SUPPLIERS FOR PROPOSED PROJECT.
- 2.B. A RIGHT OF WAY PERMIT IS REQUIRED TO WORK IN ARLINGTON COUNTY STREETS. IN INSTANCES OF EXCAVATIONS IN STATE RIGHT OF WAY, THE DATE AND NUMBER OF ALL PERMITS REQUIRED BY THE VIRGINIA DEPARTMENT OF TRANSPORTATION (VDOT) SHALL BE FURNISHED.
- 2.C. IF ANY OTHER EASEMENT IS NEEDED, TWO (2) COPIES OF THE DESCRIPTION OF SUCH EASEMENT, AS ACTUALLY RECORDED, SHALL BE FURNISHED, INCLUDING THE PLACE, DATE AND REFERENCE OF SUCH RECORDATION.
- 2.D. WRITTEN NOTICE OF TENTATIVE STARTING DATE OF CONSTRUCTION, WHICH SHALL BE A MINIMUM OF ONE (I) WEEK FOLLOWING THE DATE OF NOTICE. IN ADDITION, THE CONTRACTOR SHALL FURNISH THE NAMES AND TELEPHONE NUMBERS OF TWO (2) RESPONSIBLE PERSONS WHO CAN BE CONTACTED IN CASE OF EMERGENCY.
- 2.E. ACTUAL CONSTRUCTION SHALL NOT BEGIN UNTIL THE ABOVE ITEMS HAVE BEEN COMPLETED AND THE ARLINGTON COUNTY DEPARTMENT OF ENVIRONMENTAL SERVICES APPROVED THE STARTING DATE AND ARRANGEMENTS HAVE BEEN MADE FOR THE REQUIRED INSPECTION SERVICE.
- 3. ALL CONSTRUCTION SHALL BE ACCOMPLISHED FROM APPROVED PLANS, SPECIFICATIONS AND CUT SHEETS SUBMITTED BY A REGISTERED ENGINEER AND APPROVED BY THE COUNTY. TO AVOID CONSTRUCTION DELAYS ALL NECESSARY TEST HOLE INFORMATION SHALL BE OBTAINED PRIOR TO MOBILIZATION AND CONSTRUCTION PLANS SHALL BE REVISED ACCORDINGLY.
- 4. NO EXISTING WATER MAINS, FIRE HYDRANTS, OR SANITARY SEWERS MAY BE TAKEN OUT OF SERVICE OR MADE INACCESSIBLE BY THE CONTRACTOR WITHOUT THE PRIOR APPROVAL FROM THE DEPARTMENT OF ENVIRONMENTAL SERVICES.
- 5. UPON COMPLETION OF CONSTRUCTION, ALL FINAL TESTS, AS REQUIRED, SHALL BE PERFORMED IN THE PRESENCE OF THE COUNTY'S REPRESENTATIVE. WATER AND SEWER SERVICE CONNECTIONS SHALL NOT BE MADE UNTIL THE WATER AND/OR SEWER MAINS AND APPURTENANCES HAVE BEEN APPROVED AND ACCEPTED BY ARLINGTON COUNTY DEPARTMENT OF ENVIRONMENTAL SERVICES.
- 6. EXISTING WATER SERVICES MAY BE ALLOWED FOR CONSTRUCTION PURPOSES ONLY FOR WHICH CONTRACTOR SHALL REQUEST TO THE ARLINGTON COUNTY'S UTILITY SERVICES BY CALLING 703-228-3636. PRIOR TO THE FINAL ACCEPTANCE OF THE PROJECT, THE DEVELOPER SHALL REQUEST TO THE UTILITY SERVICES IN WRITING FOR THE DISCONTINUATION OF ALL EXISTING WATER SERVICES. ALSO, THE CONTRACTOR IS RESPONSIBLE FOR REMOVING ALL EXISTING METER BOXES RELATED TO THE SERVICES BEING DISCONTINUED.
- 7. THE CONTRACTOR SHALL MAINTAIN BACKFILL FOR UTILITY EXCAVATIONS UNTIL ARLINGTON COUNTY HAS FINALLY ACCEPTED THE PROPOSED WATER AND/OR SEWER MAIN. ALSO, ALL SURFACES OVER THE UTILITY EXCAVATIONS SHALL EITHER BE RESTORED TO THE ORIGINAL CONDITION OR FINISHED AS PER THE PROPOSED DESIGN BEFORE THE ACCEPTANCE OF THE PROJECT. PAVEMENT PATCHING FOR UTILITY CUTS IN THE PUBLIC STREETS SHALL BE PERFORMED IN ACCORDANCE WITH ARLINGTON COUNTY DEPARTMENT OF ENVIRONMENTAL SERVICES CONSTRUCTION STANDARDS AND SPECIFICATIONS OR AS PER VDOT ROAD AND BRIDGE STANDARDS AND SPECIFICATIONS DEPENDING UPON THE STREET JURISDICTION. PRIOR TO FINAL PAVING, THE CONTRACTOR SHALL ADJUST ALL EXISTING VALVE BOXES AND SANITARY SEWER MANHOLE FRAME AND COVERS AS PER COUNTY STANDARDS, REMOVE ALL ABANDONED SANITARY MANHOLES AND VALVE BOXES OVER THE ABANDONED WATER MAINS, AND COMPLETE ALL NECESSARY WATER MAIN "CUT AND CAPS".
- 8. UPON COMPLETION, APPROVAL, AND ACCEPTANCE OF WATER AND/OR SEWER MAINS AND APPURTENANCES, THE DEVELOPER'S REGISTERED ENGINEER SHALL SUBMIT TO ARLINGTON COUNTY DEPARTMENT OF ENVIRONMENTAL SERVICES, A SET OF MYLAR TRACINGS INDICATING THE AS-BUILT CONDITIONS AND A SIGNED STATEMENT CONFIRMING THAT THE WORK, AS INDICATED, IS ACCEPTABLE TO THE ENGINEER. SUCH SUBMITTALS SHALL BE MADE BEFORE REQUESTING REDUCTION AND/OR RELEASE OF THE SURETY BOND.

CONTRACTOR: TO BE DETERMINED

LANDSCAPE ARCHITECT/ENGINEER:

A. MORTON THOMAS
& ASSOCIATES, INC.
14555 Avion Parkway, Suite 150
Chantilly, VA 20151
Phone: 703.817.1373
WWW.AMTENGINEERING.COM



TRAFFIC CONTROL

- CONTRACTOR SHALL NOTIFY THE PROJECT OFFICER AT LEAST 3 WORKING DAYS PRIOR TO DISTURBING ANY EXISTING, OR INSTALLING ANY NEW, TRAFFIC SIGNS SIGNALS, OR OTHER TRAFFIC CONTROL DEVICES.
- 2. THE CONTRACTOR SHALL PREMARK THE LAYOUT OF ANY PERMANENT TRAFFIC CONTROL STRIPING, INDICATING THE PROPOSED LOCATION AND TYPE OF MARKING TO BE INSTALLED. THE PREMARKING MAY CONSIST OF TYPE D TAPE CHALK, OR LUMBER CRAYONS. THE CONTRACTOR SHALL ALLOW 3 WORKING DAYS FOR THE INSPECTION AND APPROVAL OF THE PREMARKINGS PRIOR TO PLACING THE PERMANENT MARKINGS.
- 3. THE CONTRACTOR SHALL SUBMIT ANY REQUESTS FOR TEMPORARY " NO PARKING RESTRICTIONS TO THE PROJECT OFFICER AT LEAST 3 WORKING DAYS PRIOR TO THE DESIRED ONSET OF RESTRICTIONS.
- 4. THE CONTRACTOR SHALL PRESERVE ALL BUS STOPS, INCLUDING MAINTAINING ADEQUATE ACCESSIBILITY THROUGH AND ADJACENT TO THE CONSTRUCTION FOR BUSES AND THEIR PASSENGERS. THE CONTRACTOR SHALL NOT CLOSE RELOCATE, OR OTHERWISE MODIFY A BUS STOP WITHOUT PRIOR REQUEST OF THE PROJECT OFFICER. TYPICALLY ANY RELOCATION OR CLOSURE OF A BUS STOF WILL REQUIRE AT LEAST TWO WEEKS ADVANCE NOTICE FOR COORDINATION WITH THE COUNTY'S BUS STOP COORDINATOR AT 703-228-3049. ALL TEMPORARY AND FINAL BUS TRAVEL LANES MUST BE AT MINIMUM II' WIDE.
- 5. WHEN CONDITIONS WARRANT DUE TO TRAFFIC VOLUMES, PATTERNS, OR SPECIAL EVENTS, THE COUNTY MAY SUSPEND OR OTHERWISE DIRECT THE CONTRACTOR'S ACTIVITIES TO PROTECT THE PUBLIC AND OR THE COUNTY'S TRANSPORTATION NETWORK.

ARLINGTON COUNTY DEPARTMENT OF ENVIRONMENTAL SERVICES NOTES:

. ALL CONSTRUCTION SHALL CONFORM TO THE CURRENT ARLINGTON COUNTY DES STANDARDS AND SPECIFICATIONS.

- 2. THE CONTRACTOR SHALL REMOVE AND REPLACE, TO THE CURRENT ARLINGTON COUNTY DES STANDARDS AND SPECIFICATIONS, ANY EXISTING ENTRANCES, CURB AND GUTTER OR SIDEWALK ALONG THE FRONTAGE OF THIS SITE IN POOR CONDITION, OR DAMAGED DURING CONSTRUCTION.
- 3. THE CONTRACTOR SHALL BE RESPONSIBLE FOR REMOVING AND CLOSING, TO ARLINGTON COUNTY STANDARDS, ANY EXISTING ENTRANCES NOT BEING USED IN CONJUNCTION WITH THIS DEVELOPMENT.
- 4. THE CONTRACTOR SHALL OBTAIN ARLINGTON COUNTY PERMITS FOR EACH SITE.
- 5. THERE MAY BE UNDERGROUND CONDUIT, CABLES AND TRAFFIC DETECTION DEVICES IN THIS AREA, THE CONTRACTOR SHALL BE RESPONSIBLE FOR REPLACING ANY TRAFFIC CONTROLS THAT ARE DISTURBED DURING CONSTRUCTION. NOTIFY THE TRANSPORTATION ENGINEERING & OPERATIONS BUREAU AT (703) 228-3575, 24 HOURS PRIOR TO STARTING WORK.
- 6. THE CONTRACTOR SHALL NOT DISTURB OR REMOVE ANY TRAFFIC CONTROL SIGNS, PARKING METERS OR ANY OTHER TRAFFIC CONTROL DEVICE WITHOUT PRIOR PERMISSION FROM THE TRANSPORTATION ENGINEERING & OPERATIONS BUREAU. CONTACT TRANSPORTATION ENGINEERING AT (703) 228-3575.
- 7. THE CONTRACTOR SHALL OBTAIN A PERMIT FROM THE TRANSPORTATION ENGINEERING & OPERATIONS BUREAU, PRIOR TO PLACING ANY OBSTRUCTION WITHIN THE PUBLIC RIGHT OF WAY, OR ON SIDEWALKS ALONG THE FRONTAGE OF THIS DEVELOPMENT.
- 8. THE CONTRACTOR SHALL OBTAIN PERMITS FROM THE INSPECTION SERVICES DIVISION PRIOR TO ANY DEMOLITION, EXCAVATION OR CONSTRUCTION OF ON-SITE FACILITIES. FOR INFORMATION AND PERMIT REQUIREMENTS TELEPHONE (703) 228-3800.

UTILITY MARKING REQUIREMENTS:

- 9. THE CONTRACTOR SHALL NOTIFY "MISS UTILITY" AT 811, 72 HOURS PRIOR TO THE START OF ANY EXCAVATION OR CONSTRUCTION, FOR THE MARKING OF UNDERGROUND UTILITIES IN THE RIGHT-OF-WAY.
- 10. UTILITY LOCATIONS SHOWN ON THIS PLAN ARE APPROXIMATE LOCATIONS DETERMINED FROM A TOPOGRAPHIC SURVEY AND AVAILABLE RECORDS. ADDITIONAL UNDERGROUND UTILITY LINES MAY BE PRESENT THAT ARE NOT SHOWN. THE CONTRACTOR SHALL LOCATE AND PRESERVE ALL EXISTING UTILITIES.

HORIZONTAL DATUM:


HE SITE SHOWN HEREON IS REFERENCED TO THE VIRGINIA COORDINATE SYSTEM 83 (NORTH ZONE) AS COMPUTED FROM A FIELD RUN BOUNDARY AND HORIZONTAL CONTROL SURVEY.

VERTICAL DATUM:

THE SITE SHOWN HEREON IS REFERENCED TO THE NORTH AMERICAN VERTICAL DATUM OF 1988 (NAVD88) AS COMPUTED FROM A FIELD RUN VERTICAL CONTROL SURVEY.

QUANTITIES NOTE:

ANY QUANTITIES SPECIFIED IN THE BID TAB AND ON THE CONSTRUCTION DOCUMENTS ARE ESTIMATES ONLY. CONTRACTOR SHALL VERIFY ALL QUANTITIES PER DRAWINGS AND SPECIFICATIONS. ANY QUANTITIES SHOWN ON THE DRAWINGS AND SPECIFICATIONS DO NOT GUARANTEE A SPECIFIC QUANTITY OR DOLLAR AMOUNT. ADDITIONALLY, EVERY ITEM REQUIRED TO BUILD THE PROJECT MAY NOT BE LISTED ON THE BID SHEET.



VICINITY MAP - 1" = 500'

GLOSSARY OF ABBREVIATIONS

ABBREVIATION:	REFERENCE:	ITB KSI
AC (A.C.) AC (AC.)	ARLINGTON COUNTY ACRES	L#
ADA (A.D.A.)	AMERICANS WITH DISABILITIES ACT	LA LB (LB.)
AL ANSI	ALLOWANCE AMERICAN NATIONAL STANDARDS	LDA LF
		LOD
APPROX. ASTM	APPROXIMATE, APPROXIMATELY AMERICAN SOCIETY FOR TESTING AND	LP LS (L.S.)
B&B	MATERIALS BALL & BURLAP	MANUF.
B/T	BETWEEN	MAX (MA
BL BMP	BASELINE BEST MANAGEMENT PRACTICES	MD
BP (B.P.)	POINT OF BEGINNING	MECH. MH
BS	BOTTOM STEP	MIN (MIN
BW C#	BOTTOM WALL CURVE NUMBER (LAYOUT)	MM (MM.
C&G	CURB AND GUTTER	MON (MO MOT (M.)
CE	CONSTRUCTION ENTRANCE	MS4
CAL (CAL.) CF (C.F.)	CALIPER CUBIC FEET	
CFR	CODE OF FEDERAL REGULATIONS	NA (N/A) NAD 83
CFS	CUBIC FEET PER SECOND	NAD 00
CIP (C.I.P.) CJ	CAST IN PLACE CONTROL JOINT	NAVD 88
CL	CENTER LINE	NIC (N.I. NTO
CLA (C.L.A.) CM (CM.)	CERTIFIED LANDSCAPE ARCHITECT CENTIMETER	NTS (N.T
CN (CM.)	CURVE NUMBER	0C (0.C.
CO	CLEANOUT	OFF (OFF PC
CONC (CONC.) CONT (CONT.)	CONCRETE CONTAINER (PLANTING), OR	PCC
	CONTINUOUS	PDD PE (P.E.)
CRZ CY	CRITICAL ROOT ZONE	PERF (PE
DA	CUBIC YARD DRAINAGE AREA	PL
DBH	DIAMETER AT BREAST HEIGHT	PO POC (P.O
DC (D.C.) DCR	DISTRICT OF COLUMBIA DEPT. OF CONSERVATION AND	
	RECREATION	PRC PSI (P.S.
DEMO DEQ	DEMOLITION DEPT. OF ENVIRONMENTAL QUALITY	PT (P.T.)
DES	DEPT. OF ENVIRONMENTAL SERVICES	
DIA (DIA.)	DIAMETER DEPARTMENT OF JUSTICE	PVC (P.V Q
DOJ DPR	DEPARTMENT OF PARKS & RECREATION	QTY (QT
DS	DEWATERING STRUCTURE	RAD. RCP
DSWC	DIVISION OF SOIL AND WATER CONSERVATION	REQ.
E&S	EROSION AND SEDIMENT CONTROL	RET. RLA (R.L
E.G. EA	EXEMPLI GRATIA (FOR EXAMPLE) EACH	ROW (R.(
EC (E.C.)	EPOXY COATED	RPA
EJ EJD	EXPANSION JOINT EXPANSION JOINT WITH DOWEL	RV SCH (SCH
FLEC (FLEC)	ELECTRIC	SCHD
ELEV (ELEV.)		SF (S.F., SFF
EP (E.P.) EQ (EQ.)	END POINT EQUAL	SPEC.
ESC	EROSION AND SEDIMENT CONTROL	SS STA (STA
ESD ETC.	ENVIRONMENTAL SITE DESIGN ET CETERA	STD (STI
EW (E.W.)	EACH WAY	SWM
EX. EX. JOINT	EXISTING EXPANSION JOINT	T&B TAN (TAI
FG	FINISH GRADE	TEMP.
FP	FLOODPLAIN	TP TS
FT (FT.) FT/S	FEET FEET PER SECOND	ΤW
GAL (GAL.)	GALLONS	TYP (TYF UGE
GALV (GALV.) GPM	GALVANIZED GALLONS PER MINUTE	UGE UON (U.C
HORIZ (HORIZ.)		VA
HP	HIGH POINT HOLLOW STRUCTURAL STEEL	VERT. VPDES
HSS I.E.	ID EST (IN OTHER WORDS)	
I.P.F.	IRON PIPE FOUND	W/ WSE
I.P.S. ID (I.D.)	IRON PIN SET IDENTIFICATION	WWF
INFO	INFORMATION	YR XING
INV (INV.)	INVERT	

	INLET PROTECTION
	INVITATION TO BID
	KILOPOUND PER SQUARE INCH LINE NUMBER (LAYOUT)
	LANDSCAPE ARCHITECT
.)	POUNDS
	LAND DISTURBING ACTIVITY LINEAR FEET (FOOT)
	LIMEAR FEET (FOOT) LIMITS OF DISTURBANCE
	LOW POINT
S.)	PROFESSIONAL LAND SURVEYOR,
- -	OR LUMP SUM MANUFACTURER
1AX.)	MAXIMUM
	MARYLAND
	MECHANICAL MANHOLE
IN.)	MINIMUM
M.)	MILLIMETER
10N.)	MONUMENT
4.0.T.)	MAINTENANCE OF TRAFFIC MUNICIPAL SEPARATE STORM
	SEWER SYSTEM PERMIT PROGRAM
A)	NOT APPLICABLE
3	NORTH AMERICAN HORIZONTAL
38	DATUM83 NORTH AMERICAN VERTICAL DATUM8
.I.C.)	NOT IN CONTRACT
·	NEW TO OLD (JOINT)
I.T.S.)	NOT TO SCALE
C.))FF.)	ON CENTER OFFSET
///./	POINT OF CURVATURE
	POINT OF COMPOUND CURVATURE
- \	PARK DEVELOPMENT DIVISION
E.) PERF.)	PROFESSIONAL ENGINEER PERFORATED
	PLATE
	PROJECT OFFICER
.0.C.)	POINT OF CONNECTION (IRRIGATION), POINT OF CURVATURE (LAYOUT)
	POINT OF CORVATORE (LATOUT)
S.I.)	POUNDS PER SQUARE INCH
T.)	PRESSURE TREATED (LUMBER), OR
.V.C.)	POINT OF TANGENCY (LAYOUT) POLYVINYL CHLORIDE
.v.c.)	CAPACITY
ATY.)	QUANTITY
	RADIUS
	REINFORCED CONCRETE PIPE REQUIRED
	RETAINING
R.L.A.)	REGISTERED LANDSCAPE ARCHITECT
R.O.W.)	RIGHT-OF-WAY RESOURCE PROTECTION AREA
	VOLUMETRIC RUNOFF COEFFICIENT
SCH.)	SCHEDULE
- 00 57)	SCHEDULE
, SQ. FT.)	SQUARE FOOT (FEET) SUPER SILT FENCE
	SPECIFICATION, OR SPECIFIED
	STAINLESS STEEL
STA.)	STATION
TD.)	STANDARD STORMWATER MANAGEMENT
	TOP AND BOTTOM
AN.)	TANGENT
	TEMPORARY TREE PROTECTION
	TOP STEP
	TOP WALL
YP.)	
J.O.N.)	UNDERGROUND ELECTRIC LINE UNLESS OTHERWISE NOTED
	VIRGINIA
	VERTICAL
	VIRGINIA POLLUTANT DISCHARGE
	ELIMINATION SYSTEM WITH
	WATER SURFACE ELEVATION
	WELDED WIRE FABRIC
	YEAR CROSSING



LTS NNE SFS EF S

NOTES: 1. PROPERTY LINES SHOWN ON THIS SURVEY ARE A COMPILATION FROM DEEDS, PLATS, SURVEYS BY OTHERS, OR COMBINATION THEREOF FROM LAND RECORDS; AND LIMITED MONUMENT TIES, AND DOES NOT REPRESENT THE RESULTS OF A FIELD RUN BOUNDARY SURVEY.

2. NO TITLE REPORTS HAVE BEEN FURNISHED AND NOT ALL EASEMENTS AND/OR ENCUMBRANCES ARE SHOWN ON THE SURVEY.

3. THIS SURVEY WAS PREPARED FOR ARLINGTON COUNTY DEPARTMENT OF PARKS, RECREATION AND CULTURAL RESOURCES.

4. THE HORIZONTAL DATUM IS VIRGINIA COORDINATE SYSTEM 83(NORTH ZONE), AND THE VERTICAL DATUM IS NAVD88, BOTH ESTABLISHED BY GPS OBSERVATIONS. THE FOOT DEFINITION USED IS THE U.S. SURVEY FOOT.

5. THE CONTOUR INTERVAL IS ONE (1) FOOT.

6. NO CEMETERY SITES WERE OBSERVED ON THE SUBJECT PROPERTY, HOWEVER THIS DOES NOT PRECLUDE THEIR EXISTENCE.

7. THIS SURVEY WAS FORWARDED ELECTRONICALLY IN READ ONLY FORMAT. ANY ATTEMPT AT ALTERATION INVALIDATES THE SEAL AND SIGNATURE. AN ORIGINAL HARD COPY REMAINS ON FILE AT RICE ASSOCIATES.

8. THE PHYSICAL FEATURES SHOWN HEREON ARE DERIVED BY CONVENTIONAL SURVEY METHODS.

- 9. THE SUBJECT PROPERTY IS IDENTIFIED AS RPC #04-011-239.
- 10. AREA IS 130,680 SQ. FT. PER ARLINGTON COUNTY TAX RECORDS. AREA IS 130,710 SQ. FT. PER DEEDS AND PLATS RECORDED AT D.B.1406 PG. 269 AND D.B. 1438 PG. 651.
- 11. RESOURCE PROTECTION BUFFER OBTAINED FROM AVAILABLE ARLINGTON COUNTY G.I.S. DATA.
- 12. THE SUBJECT PROPERTY LIES WITHIN ZONE X, AREAS DETERMINED TO BE OUTSIDE THE 0.290 ANNUAL CHANGE FLOODPLAIN AS DEPICTED ON THE FLOOD INSURANCE RATE MAP NUMBER 51013C0036C, EFFECTIVE 08/19/2013.

13. SEE SHEET 3 FOR SUBSURFACE DESIGNATIONS, CRITICAL ROOT ZONES AND RPA LIMITS.

UTILITY CONTACTS:

UTILITY NOTES:

ARLINGTON COUNTY WATER & SEWER DARYL SMITH

ENGINEER 4200 28TH STREET ARLINGTON, VA 22206 (703) 228–8797

DOMINION POWER

JULIA MATHERS ELECTRIC COORDINATOR 3072 CENTREVILLE ROAD HERNDON, VA 20171 (571)203–5324

VERIZON COMMUNICATION LENWOOD TURNER SUPERVISOR OF NETWORK 502 E PIEDMONT STREET CULPEPER, VA 22701

WASHINGTON GAS DEBBIE BUNYEA RECORDS CLERK 6802 INDUSTRIAL ROAD SPRINGFIELD, VA 22151 (703)750-4403

(540)829–2640

- 1. UTILITIES SHOWN HEREIN ARE ACCORDANCE WITH AMERICAN SOCIETY OF CIVIL ENGINEER'S DOCUMENT ASCE 38-02, "STANDARD GUIDELINE FOR THE COLLECTION AND DEPICTION OF EXISTING SUBSURFACE UTILITY DATA."
- 2. ALL UTILITIES DEPICTED IN THIS FILE ARE QUALITY LEVEL "B" UNLESS OTHERWISE NOTED
- 3. UTILITIES DEPICTED ACCORDING TO UTILITY RECORDS (DATUR) ARE QUALITY LEVEL "d" and labeled "ql-d datur".
- 4. UTILITY SIZE AND TYPE FOR QUALITY LEVEL "B" DEPICTIONS ARE DETERMINED THROUGH AVAILABLE UTILITY OWNER INFORMATION. UTILITIES LABELED AS UNKNOWN HAVE NO CORRELATED RECORDS OR VISIBLE APPURTENANCES TO DETERMINE FUNCTION OR TYPE.
- 5. UTILITY MAPPING WAS COMPLETED ON 02/11/2019. THERE MAY EXIST UTILITES THAT ARE UNABLE TO BE ELECTROMAGNETICLY TONED OR DETECTED BY SUBSURFACE UTILITY EQUIPMENT OR GEOPHYSICAL METHODS. UTILITIES MAY HAVE BEEN CHANGED OR ADDED AFTER THIS DATE.
- 6. RELIANCE UPON THIS DATA FOR RISK MANAGEMENT PURPOSES DURING BIDDING DOES NOT RELIEVE THE EXCAVATOR OR UTILITY OWNER FROM FOLLOWING ALL APPLICABLE UTILITY DAMAGE PREVENTION STATUTES, POLICIES, AND/OR PROCEDURES DURING EXCAVATION.
- 7. ALL UTILITIES SHOWN HERE IN WERE PERFORMED UNDER THE DIRECTION OF TIMOTHY EDWARD PAYNE, LS. 403003090.

	SYMBOL LEGEND
A	TRAVERSE STATION
×	WATER VALVE
*	FIRE HYDRANT
8	WATER METER
TCAN	TRASH CAN
cv N	GAS VALVE
GTS	GAS TEST STATION
GWP	GAS WITNESS POST
പ	UTILITY POLE
Ĕ	HANDICAP RAMP
¢	LIGHT POLE
	SIGN
Ø	POST
8	BOLLARD
0	PROPERTY CORNER
0	CRITICAL ROOT ZONE
+0.00	SPOT ELEVATION
	BENCHMARK


	ARLINGTON
CONTROL TABLE	VIRGINIA
# NORTHING EASTING ELEV. DESCRIPTION I 7017946.42 II879003.87 264.42' ROD & CAP 2 7017977.12 II878731.49 238.51' ROD & CAP 3 7017791.28 II878859.39 246.17' ROD & CAP 5 7017869.32 II878601.18 257.93' ROD & CAP	DEPARTMENT OF PARKS, RECREATION AND CULTURAL RESOURCES
9 7018054.86 II878598.84 242.43' ROD & CAP	Park Development Division 2100 Clarendon Boulevard, Suite 414 Arlington, VA 22201 Phone: 703.228.7928
LINE TYPE LEGEND	Fax: 703.228.3328
	Project Name and Location
OHW OVERHEAD WIRES	PLAT SHOWING
Uge UNDERGROUND ELECTRIC LINE UNDERGROUND WATER LINE UNDERGROUND WATER LINE	TOPOGRAPHIC SURVEY THE PROPERTY OF
	COUNTY BOARD OF ARLINGTON, VIRGINIA
I INTERMEDIATE CONTOUR	MARCEY PARK
	2722 NORTH MARCEY ROAD
# INCH ITTPE FEET FEET I I2 DECIDUOUS 36 I2 TWIN	
2 8 POPLAR 36 8 3 12 MAPLE 30 12 4 4 BOXWOOD 20 8 TRIPLE	Arlington, Virginia
5 6 SYCAMORE 20 8 6 4 OAK 10 8	Sheet Title
7 7 HOLLY 24 8 TRIPLE 8 4 DECIDUOUS 12 8	Base Plan Prepared by
I0 4 REDBUD I0 8 II 3 MAPLE I0 8 I2 4 POPLAR I2 8 I3 3 POPLAR 8 8	RICE ASSOCIATES LAND SURVEYING · MAPPING CONSULTANTS
I4 4 POPLAR I0 8 I5 6 ELM I8 8 I6 6 ELM I8 8	10661 GASKINS WAY MANASSAS, VIRGINIA 20109 (703) 968-3200
I7 20 HOLLY 30 20 I8 4 MAPLE I0 8	RICE FAX (703) 968-2705 ASSOCIATES WWW.RICESURVEYS.COM
19 30 CATALPA 40 30 20 27 CATALPA 40 27 21 42 OAK 70 42	Seal
22 30 MAPLE 60 30 23 I5 PINE 32 I5 24 42 MAPLE 80 42	STATEALTHOR LER T
25 48 MAPLE 100 48 26 6 REDBUD 16 8	SWILLIAM CLIPPY, JR
27 5 REDBUD 16 8 28 6 REDBUD 16 8 29 6 OAK 16 8	WILLIAM G. LIPPY, JR WILLIAM G. LIPPY, JR Lic. No. 2887 10-21-2020 Manage Manage Management Managem
30 5 OAK I6 8 31 10 OAK 20 10	ANDSURVEYOR
32 10 PINE 24 10 33 8 LOCUST 24 8 34 15 PINE 36 15	
35 9 DECIDUOUS 22 9 36 6 DECIDUOUS 22 8 TWIN 37 7 DECIDUOUS 24 8 TRIPLE	Approvals Date
38 16 HEMLOCK 24 16 TRIPLE 39 24 LOCUST 36 24	DEPARTMENT DIRECTOR
40 4 BEECH 16 8 41 10 CHERRY 20 10 42 10 LOCUST 20 10	PLANNING AND DESIGN DIVISION CHIEF
43 2 DECIDUOUS 6 8 44 4 CHERRY 10 8 45 3 SASSAFRAS 8 8	
46 2 DECIDUOUS 6 8 47 6 CHERRY 12 8	DESIGN TEAM SUPERVISOR
48 6 OAK I2 8 49 I6 POPLAR 30 I6 50 4 CHERRY I2 8	PARK SERVICE AREA MANAGER
51 18 POPLAR 30 18 52 4 BOXWOOD 12 8 53 3 BOXWOOD 10 8	URBAN FORESTRY
54 20 POPLAR 44 20 TWIN 55 6 DECIDUOUS 20 8	
	Revisions Date
ARLINGTON COUNTY, VIRGINIA	Added Trees #40-5512/18/19Added Ulitiy mapping at water meter10/21/20
DEPARTMENT OF ENVIRONMENTAL SERVICES	
MARCEY PARK EXISTING CONDITIONS PLAN	
BY-RIGHT (COUNTY PROJECT)	
SCALE: DESIGNED: CHECKED: COVER SUBMITTED DATE: APPROVED DATE: APPROVED DATE:	
CHIEF TRANSP. PLANNING BUREAU CHIEF TRANSP. ENGINEERING BUREAU	Designed:
APPROVED DATE: APPROVED DATE: APPROVED DATE:	Drawn: KRM Checked: LS / WGL
CHIEF WATER, SEWER, & STR. BUREAU CHIEF ENGINEERING BUREAU DIRECTOR OF ENV. SERVICES	Filename: AC150014-TOPO 2D UPDATE 10-21-2
SHEET OF	Path: S:\project\AC150014 Marcey Rd Park\DWG\
SURVEYOR'S CERTIFICATION	$\frac{\text{Plotted:} \text{Oct 21, 2020}}{\text{Scale:} 1" = 25'}$
I. THIS PLAT DEPICTING A TOPOGRAPHIC SURVEY OF MARCEY ROAD PARK, IDENTIFIED AS RPC	Scale: 1" = 25' Date: April 11, 2019
NUMBER 04-011-239, WAS COMPLETED UNDER THE DIRECT AND RESPONSIBLE CHARGE OF WILLIAM G. LIPPY JR. FROM AN ACTUAL GROUND SURVEY MADE UNDER MY SUPERVISION; THE DATA WAS OBTAINED BETWEEN THE DATES OF 01-16-2019, 03-01-2019, AND 12-13-19, THAT THIS PLAT, MAP OR	Sheet
DIGITAL GEOSPATIAL DATA MEETS MINIMUM ACCURACY STANDARDS UNLESS OTHERWISE NOTED. 2. REVISION ON 10-21-20 ONLY APPLIES TO UPDATED UTILITY MAPPING AT THE WATER METER.	1 OF 3


			ARLINGTON
CONTROL TABLE			VIRGINIA
# NORTHING EASTING EL I 7017946.42 II879003.87 264 2 7017977.12 II878731.49 238 3 7017791.28 II878859.39 246 5 7017869.32 II878601.18 257	.42' ROD & CAP .51' ROD & CAP .17' ROD & CAP .93' ROD & CAP		DEPARTMENT OF PARKS, RECREATION AND CULTURAL RESOURCES
9 7018054.86 11878598.84 242	.43' ROD & CAP		Park Development Division 2100 Clarendon Boulevard, Suite 414 Arlington, VA 22201 Phone: 703.228.7928
LINE TYPE LEGEN			Fax: 703.228.3328
X X FENCE / HAN			Project Name and Location
OVERHEAD W	REELINE CANOPY RES		PLAT SHOWING
			TOPOGRAPHIC SURVEY THE PROPERTY OF
			COUNTY BOARD OF ARLINGTON, VIRGINIA
I INTERMEDIAT			
TREE			MARCEY PARK
# DIA TYPE	DRIP CRZ FEET FEET NOTE		2722 NORTH MARCEY ROAD
I I2 DECIDUOUS 2 8 POPLAR	36 12 TWIN 36 8		Arlington, Virginia
3 I2 MAPLE 4 4 BOXWOOD	30 I2 20 8 TRIPLE		Sheet Title
5 6 SYCAMORE 6 4 OAK 7 7 HOLLY	20 8 10 8 24 8 TRIPLE		
7 7 HOLLY 8 4 DECIDUOUS 9 4 MAPLE	24 8 IRIPLE 12 8 12		Base Plan Prepared by
I04REDBUDII3MAPLEI24POPLARI33POPLAR	I0 8 I0 8 I2 8 8 8		RICE ASSOCIATES
I4 4 POPLAR I5 6 ELM	IO 8 I8 8		10661 GASKINS WAY MANASSAS, VIRGINIA 20109 (703) 968-3200
I6 6 ELM I7 20 HOLLY I8 4 MAPLE	18 8 30 20 10 8		RICE FAX (703) 968-2705 ASSOCIATES WWW.RICESURVEYS.COM
I9 30 CATALPA 20 27 CATALPA	40 30 40 27		Seal
21 42 OAK 22 30 MAPLE	70 42 60 30		EALTHOR
23 I5 PINE 24 42 MAPLE 25 48 MAPLE	32 15 80 42 100 48		
23 48 MAPLE 26 6 REDBUD 27 5 REDBUD	16 8 16 8		WILLIAM C. LIPPY, JR Lic. No. 2887
28 6 REDBUD 29 6 OAK	I6 8 I6 8		10.21.2020
30 5 OAK 31 10 OAK	16 8 20 10		$\frac{10 \cdot 21 \cdot 2000}{\sqrt{2}}$
32 10 PINE 33 8 LOCUST 34 15 PINE	24 I0 24 8 36 I5		
35 9 DECIDUOUS 36 6 DECIDUOUS	22 9 22 8 TWIN		Approvals Date
377DECIDUOUS3816HEMLOCK	24 8 TRIPLE 24 16 TRIPLE		DEPARTMENT DIRECTOR
39 24 LOCUST 40 4 BEECH 41 10 CHERRY	36 24 16 8 20 10		
4110CHERRY4210LOCUST432DECIDUOUS	20 10 20 10 6 8		PLANNING AND DESIGN DIVISION CHIEF
444CHERRY453SASSAFRAS	10 8 8 8		DESIGN TEAM SUPERVISOR
46 2 DECIDUOUS 47 6 CHERRY 48 6 OAK	6 8 12 8 12 8		
48 6 OAK 49 I6 POPLAR 50 4 CHERRY	12 8 30 16 12 8		PARK SERVICE AREA MANAGER
5118POPLAR524BOXWOOD	30 18 12 8		
533BOXWOOD5420POPLAR556DECIDUOUS	10 8 44 20 TWIN 20 8		URBAN FORESTRY
55 6 DECIDUOUS			Revisions Date
			Added Trees #40-55 12/18/19
	GTON COUNTY, V nt of environment		Added Ulitiy mapping at water meter 10/21/20
	MARCEY PARK	AL SERVICES	
	EXISTING CONDITIONS PLA		
	BY-RIGHT (COUNTY PROJEC	ст)	
SCALE: DESIG	····	ECKED:	
SUBMITTED DATE:	APPROVED DATE:	APPROVED DATE:	
APPROVED DATE:	CHIEF TRANSP. PLANNING BUREAU APPROVED DATE:	CHIEF TRANSP. ENGINEERING BUREAU APPROVED DATE:	Designed: Drawn: KRM Checked: LS / WGL
CHIEF WATER, SEWER, & STR. BURE	AU CHIEF ENGINEERING BUREAU	DIRECTOR OF ENV. SERVICES	Filename: AC150014-TOPO 2D UPDATE 10-21-2
	SHEET	SHEET OF	Path: S:\project\AC150014 Marcey Rd Park\DWG\
			Plotted: Oct 21, 2020
<u>S</u>	URVEYOR'S CERTIFICATION		Scale: $1'' = 25'$
NUMBER 04-011-239, W	A TOPOGRAPHIC SURVEY OF MARCEY ROAD AS COMPLETED UNDER THE DIRECT AND RE	ESPONSIBLE CHARGE OF WILLIAM	Date: April 11, 2019
OBTAINED BETWEEN T	ACTUAL GROUND SURVEY MADE UNDER MY HE DATES OF 01-16-2019, 03-01-2019, AND 12 DATA MEETS MINIMUM ACCURACY STANDAR	2-13-19, THAT THIS PLAT, MAP OR	Sheet $1 \cap \Gamma 2$
	DATA MEETS MINIMUM ACCURACY STANDAR ONLY APPLIES TO UPDATED UTILITY MAPPII		1 OF 3

	ABBREVIATION LEGEND			
ASPH.	ASPHALT			
BLDR	BOULDER			
CONC.	CONCRETE			
CMP	CORRUGATED METAL PIPE			
CRZ	CRITICAL ROOT ZONE			
DB. PG. DEED BOOK PAGE				
EX.	EXISTING			
GRND GROUND				
IPF	IRON PIPE FOUND			
RTW	RETAINING WALL			
TRV	TRAVERSE			
TW	TOP OF WALL			
(TYP)	TYPICAL			


			ARLINGTON
CONTROL TABLE	. DESCRIPTION		VIRGINIA
II879003.87 264.42 II878731.49 238.51 II878859.39 246.17 II878601.18 257.93 II878598.84 242.43	2' ROD & CAP I' ROD & CAP 7' ROD & CAP 3' ROD & CAP		DEPARTMENT OF PARKS, RECREATION AND CULTURAL RESOURCES
LINE TYPE LEGEND			Park Development Division 2100 Clarendon Boulevard, Suite 414 Arlington, VA 22201 Phone: 703.228.7928 Fax: 703.228.3328
FENCE / HANDRA			Project Name and Location
TREELINE /TREE OVERHEAD WIRE	ES		PLAT SHOWING TOPOGRAPHIC SURVEY
UNDERGROUND E UNDERGROUND V UNDERGROUND V UNDERGROUND V	WATER LINE		THE PROPERTY OF COUNTY BOARD OF ARLINGTON, VIRGINIA
TREE TA			MARCEY PARK
# DIA TYPE	DRIP CRZ FEET FEET NOTE		2722 NORTH MARCEY ROAD
II2DECIDUOUS28POPLAR3I2MAPLE44BOXWOOD	36 I2 TWIN 36 8		Arlington, Virginia
4 4 BOXWOOD 5 6 SYCAMORE 6 4 OAK 7 7 HOLLY	20 8 10 8 24 8		Sheet Title Base Plan
84DECIDUOUS94MAPLE104REDBUD	I2 8 I2 8 I0 8		Prepared by
II3MAPLEI24POPLARI33POPLAR	10 8 12 8 8 8		RICE ASSOCIATES
I4 4 POPLAR I5 6 ELM I6 6 ELM I7 20 HOLLY	I0 8 I8 8 I8 8 30 20		10661 GASKINS WAY MANASSAS, VIRGINIA 20109 (703) 968-3200 RICE FAX (703) 968-2705
17 20 HOLL 1 18 4 MAPLE 19 30 CATALPA 20 27 CATALPA	30 20 10 8 40 30 40 27		ASSOCIATES WWW.RICESÚRVEYS.COM
2I 42 OAK 22 30 MAPLE 23 I5 PINE	70 42 60 30 32 15		ON EALTHOR LA
24 42 MAPLE 25 48 MAPLE 26 6 REDBUD	80 42 100 48 16 8		WILLIAM C. LIPPY, JR Lic. No. 2887
27 5 REDBUD 28 6 REDBUD 29 6 OAK	16 8 16 8 16 8		⁴ ⁴ ⁴ ⁴ ⁴ ⁴ ⁴ ⁴ ⁴ ⁴
30 5 OAK 31 10 OAK 32 10 PINE 33 8 LOCUST	16 8 20 10 24 10 24 8		A D SURVEY OF
33 8 LOCUST 34 15 PINE 35 9 DECIDUOUS 36 6 DECIDUOUS	24 6 36 15 22 9 22 8		Approvals Date
37 7 DECIDUOUS 38 16 HEMLOCK 39 24 LOCUST	24 8 TRIPLE 24 16 TRIPLE 36 24		DEPARTMENT DIRECTOR
40 4 BEECH 41 10 CHERRY 42 10 LOCUST	I6 8 20 10 20 10		PLANNING AND DESIGN DIVISION CHIEF
432DECIDUOUS444CHERRY453SASSAFRAS	6 8 10 8 8 8		DESIGN TEAM SUPERVISOR
46 2 DECIDUOUS 47 6 CHERRY 48 6 OAK	6 8 12 8 12 8		
49 16 POPLAR 50 4 CHERRY 51 18 POPLAR	30 16 12 8 30 18		PARK SERVICE AREA MANAGER
52 4 BOXWOOD 53 3 BOXWOOD 54 20 POPLAR 55 6 DECIDUOUS	12 8 10 8 44 20 20 8		URBAN FORESTRY
			Revisions Date
	TON COUNTY, V		Added Trees #40-55 12/18/19 Added Ulitiy mapping at water meter 10/21/20
DEPARTMEN	IT OF ENVIRONMENTA MARCEY PARK	AL SERVICES	
	EXISTING CONDITIONS PLA		
: DESIGNED	CHE	ECKED: COVER	
ITED DATE:	APPROVED DATE: CHIEF TRANSP. PLANNING BUREAU	APPROVED DATE: CHIEF TRANSP. ENGINEERING BUREAU	Designed:
/ED DATE:	APPROVED DATE:	APPROVED DATE:	Drawn: KRM Checked: LS / WGL
WATER, SEWER, & STR. BUREAU	CHIEF ENGINEERING BUREAU	DIRECTOR OF ENV. SERVICES	Filename: AC150014-TOPO 2D UPDATE 10-21-2 Path:
		SHEET OF	S:\project\AC150014 Marcey Rd Park\DWG\ Plotted: Oct 21, 2020
a	RVEYOR'S CERTIFICATION		Scale: 1" = 25' Date: April 11, 2019
NUMBER 04-011-239, WAS G. LIPPY JR. FROM AN AG	TOPOGRAPHIC SURVEY OF MARCEY ROAD S COMPLETED UNDER THE DIRECT AND RE CTUAL GROUND SURVEY MADE UNDER MY	ESPONSIBLE CHARGE OF WILLIAM (SUPERVISION; THE DATA WAS	Sheet
DIGITAL GEOSPATIAL DA	E DATES OF 01-16-2019, 03-01-2019, AND 12 TA MEETS MINIMUM ACCURACY STANDAR ILY APPLIES TO UPDATED UTILITY MAPPIN	RDS UNLESS OTHERWISE NOTED.	1 OF 3

			T
			ARLINGTON
CONTROL TABLE	/. DESCRIPTION		
RTHING EASTING ELLV 7946.42 II879003.87 264.4 7977.12 II878731.49 238.5 7791.28 II878859.39 246.1 7869.32 II878601.18 257.9 8054.86 II878598.84 242.4	ROD & CAP 61' ROD & CAP 7' ROD & CAP 3' ROD & CAP		DEPARTMENT OF PARKS, RECREATION AND CULTURAL RESOURCES
107034.00 11070390.04 242.4			Park Development Division 2100 Clarendon Boulevard, Suite 414 Arlington, VA 22201 Phone: 703.228.7928 Fax: 703.228.3328
LINE TYPE LEGEND			T ax. 703.220.3320
X FENCE / HANDR TREELINE /TRE			Project Name and Location
OVERHEAD WIRE			PLAT SHOWING TOPOGRAPHIC SURVEY
UNDERGROUND			THE PROPERTY OF COUNTY BOARD OF ARLINGTON,
			VIRGINIA
I INTERMEDIATE			MARCEY PARK
TREE TA	DRIP CRZ NOTE		2722 NORTH MARCEY ROAD
#INCHI YPEII2DECIDUOUS28POPLAR	FEET FEET NOTE 36 12 TWIN 36 8		Arlington, Virginia
3I2MAPLE44BOXWOOD	30 I2 20 8 TRIPLE		Sheet Title
5 6 SYCAMORE 6 4 OAK 7 7 HOLLY	20 8 10 8 24 8 TRIPLE		Base Plan
84DECIDUOUS94MAPLE104REDBUD	12 8 12 8 10 8		Prepared by
II3MAPLEI24POPLARI33POPLAR	I0 8 I2 8 8 8		RICE ASSOCIATES
I4 4 POPLAR I5 6 ELM I6 6 ELM	10 8 18 8 18 8		10661 GASKINS WAY MANASSAS, VIRGINIA 20109 (703) 968-3200
17 20 HOLLY 18 4 MAPLE	30 20 10 8 40 30		RICE FAX (703) 968-2705 ASSOCIATES WWW.RICESURVEYS.COM
20 27 CATALPA 21 42 OAK	40 27 70 42		
22 30 MAPLE 23 15 PINE 24 42 MAPLE	60 30 32 15 80 42		
25 48 MAPLE 26 6 REDBUD	100 48 16 8		OWILLIAM C. LIPPY, JR A Lic. No. 2887
27 5 REDBUD 28 6 REDBUD 29 6 OAK	16 8 16 8 16 8		Lic. No. 2887
29 6 OAK 30 5 OAK 31 10 OAK 32 10 PINE	10 0 16 8 20 10 24 10		10-21-2020
33 8 LOCUST 34 15 PINE	24 8 36 I5		
35 9 DECIDUOUS 36 6 DECIDUOUS 37 7 DECIDUOUS	22 9 22 8 TWIN 24 8 TRIPLE		Approvals Date
38 16 HEMLOCK 39 24 LOCUST	24 I6 TRIPLE 36 24		DEPARTMENT DIRECTOR
40 4 BEECH 41 10 CHERRY 42 10 LOCUST	16 8 20 10 20 10		PLANNING AND DESIGN DIVISION CHIEF
432DECIDUOUS444CHERRY453SASSAFRAS	6 8 10 8		
453SASSAFRAS462DECIDUOUS476CHERRY	8 8 6 8 12 8		DESIGN TEAM SUPERVISOR
48 6 OAK 49 I6 POPLAR 50 4 CHERRY	I2 8 30 I6 I2 8		PARK SERVICE AREA MANAGER
5118POPLAR524BOXWOOD	12 8 30 18 12 8		URBAN FORESTRY
533BOXWOOD5420POPLAR556DECIDUOUS	10 8 44 20 TWIN 20 8		URBAN FORESTRY
			Revisions Date
ARI ING	TON COUNTY, V	IRGINIA	Added Trees #40-55 Added Ulitiy mapping at water meter 10/21/20
	IT OF ENVIRONMENTA		
	MARCEY PARK		
	EXISTING CONDITIONS PLA Y-RIGHT (COUNTY PROJEC		
SCALE: DESIGNE	1	ECKED: COVER	
SUBMITTED DATE:	APPROVED DATE:	APPROVED DATE:	
APPROVED DATE:	CHIEF TRANSP. PLANNING BUREAU APPROVED DATE:	CHIEF TRANSP. ENGINEERING BUREAU APPROVED DATE:	Designed: Drawn: KRM Checked: LS / WGL
CHIEF WATER, SEWER, & STR. BUREAU	CHIEF ENGINEERING BUREAU	DIRECTOR OF ENV. SERVICES	Filename: AC150014-TOPO 2D UPDATE 10-21-2
	SHEET	SHEET OF	Path: S:\project\AC150014 Marcey Rd Park\DWG\
			$\frac{\text{Plotted:} \text{Oct 21, 2020}}{\text{C} = 1 = 25'}$
I. THIS PLAT DEPICTING A	RVEYOR'S CERTIFICATION TOPOGRAPHIC SURVEY OF MARCEY ROAD		Scale: 1" = 25' Date: April 11, 2019
NUMBER 04-011-239, WAS G. LIPPY JR. FROM AN A	S COMPLETED UNDER THE DIRECT AND RE ACTUAL GROUND SURVEY MADE UNDER MY	ESPONSIBLE CHARGE OF WILLIAM ' SUPERVISION; THE DATA WAS	Sheet
DIGITAL GEOSPATIAL DA	E DATES OF 01-16-2019, 03-01-2019, AND 13 ATA MEETS MINIMUM ACCURACY STANDAR NLY APPLIES TO UPDATED UTILITY MAPPI1	DS UNLESS OTHERWISE NOTED.	1 OF 3





	The
	ARLINGTON VIRGINIA
	DEPARTMENT OF PARKS, RECREATION AND CULTURAL RESOURCES
	Park Development Division 2100 Clarendon Boulevard, Suite 414 Arlington, VA 22201 Phone: 703.228.7928 Fax: 703.228.3328
	Project Name and Location
	PLAT SHOWING TOPOGRAPHIC SURVEY THE PROPERTY OF COUNTY BOARD OF ARLINGTON, VIRGINIA
	MARCEY PARK
	2722 NORTH MARCEY ROAD
	Arlington, Virginia
	Sheet Title
	Base Plan Prepared by
	RICE ASSOCIATES LAND SURVEYING · MAPPING CONSULTANTS
	10661 GASKINS WAY MANASSAS, VIRGINIA 20109 (703) 968-3200 FAX (703) 968-2705
	RICE FAX (703) 968-2705 ASSOCIATES WWW.RICESURVEYS.COM
150	ALTHON
a Hadron and a start and a start a sta	WILLIAM G. LIPPY, JR Lic. No. 2887
	Lic. No. 2887
	LAND SURVEY OF
	Approvals Date
	DEPARTMENT DIRECTOR
	PLANNING AND DESIGN DIVISION CHIEF
	DESIGN TEAM SUPERVISOR
	PARK SERVICE AREA MANAGER
STORM GRATE C (FULL OF DEBRIS)	URBAN FORESTRY
251.98	RevisionsDateAdded Trees #40-5512/18/19
	Added Ulitiy mapping at water meter 10/21/20
	Designed: Drawn: KRM
	Checked: LS / WGL
	Path: S:\project\AC150014 Marcey Rd Park\DWG\
	$\frac{\text{Plotted:} \text{Oct 21, 2020}}{\text{Scale:} 1" = 25'}$
	Date: April 11, 2019
	^{Sheet} 3 OF 3



Path: X:\Rockville\15-0396.024 - Marcey Road Park\05-CAD

				AB	BREVIATION L	EGEND	
		SPH.		ASPHA			
		MP			JGATED METAL PIP	È	
		RZ			CAL ROOT ZONE		
		B. PG. X.		DEED EXIST	BOOK PAGE		
		RND		GROU			
		٣F			PIPE FOUND		
		TW			NING WALL		
		RV W		TRAVE	F WALL		
		TYP)		TYPIC			
(NTROL TABL		
	#		NORTHING		EASTING	L ELEV.	DESCRIPTION
			7017946.42		11879003.87	264.42'	ROD & CAP
	2 3		7017977.12 7017791.28		ll878731.49 ll878859.39	238.51' 246.17'	ROD & CAP ROD & CAP
_	5 9		7017869.32		87860 . 8 878598.84	257.93' 242.43'	ROD & CAP ROD & CAP
			LI	NE T	YPE LEGEND		
	— X -		- X		FENCE / HANDF	RAIL	
~~~~	~~~~	~~~~~ 	~~~~~~	<u>`</u>	TREELINE /TRE	ELINE CANC	)PY
	OH\	V			OVERHEAD WIRI		
					UNDERGROUND		
			W				
					INDEX CONTOUR		
						CONTOUR	
					SYME	BOL LEGE	 -ND
	DRIP FEET		NOTE		•	RSE STATIC	
IS	36 36	12 8	TWIN			R VALVE	
	30 20	12 8	TRIPLE			HYDRANT	
E	20	8				R METER	
	10 24	8 8	TRIPLE	<del> </del> T			
S	12 12	8 8			GAS V		
	10 10	8 8			010	EST STATIO	)N
	10 12 8	8				ITNESS POS	ST T
	10	8 8			ک UTILIT	Y POLE	
	18 18	8 8			ڈ HANDI	CAP RAMP	
	30 10	20 8			☆ LIGHT	POLE	
	40	30 27			- SIGN		
	70	42			⊙ POST		
	60 32	30 15			⊗ BOLLA		
	80	42 48			•	RTY CORNE	R
	16 16	8 8		+0		ELEVATION	
	16	8			BENCH	IMARK	
	16 16	8 8			⊕ B-# BORIN	G TEST LOC	ATION
	20 24	10 10			⊕ IT-# INFILT	RATION TES	ST LOCATION
	24 36	8 15					
JS JS	22	9 8	TWIN				
JS	24	8	TRIPLE				
	24 36	16 24	TRIPLE				
	16 20	8 10					
IS	20 6	10 8					
	10	8					
AS JS	8	8 8					
	2  2	8 8					
	30	16					
	12 30	8 18					
	12	8 8					
)	0		TWIN				
	10	20		ļ			
S		8					

The ARLINGTON VIRGINIA DEPARTMENT OF PARKS AND RECREATION Park Development Division 2100 Clarendon Boulevard, Suite 414 Arlington, VA 22201 Phone: 703.228.3332 Fax: 703.228.3328 21-DPR-ITB-646 Project Name and Location Marcey Road Park Improvements (By Right) (County Project) 2722 MARCEY ROAD ARLINGTON, VA 22207 Sheet Title EXISTING CONDITIONS PLAN 100% Construction Drawings Date Approval Design Manager Date Revisions Designed: AW Drawn: AMT Checked: SDT, JKS, MMW, CMB Filename: c-03-150396024 existing conditions plan.dwg Plotted: 2021-06-02 Scale: |" = 20' Date: JUNE 2, 2021 Seal -----MATTHEW M. WEIR Cert. No. 04060019 Jan SCAPEAK JUNE 2, 2021 Sheet

C-03

- 2. ALL UTILITIES DEPICTED IN THIS FILE ARE QUALITY LEVEL "B" UNLESS OTHERWISE NOTED
- 3. UTILITIES DEPICTED ACCORDING TO UTILITY RECORDS (DATUR) ARE QUALITY LEVEL "D" AND LABELED "QL-D DATUR".
- 4. UTILITY SIZE AND TYPE FOR QUALITY LEVEL "B" DEPICTIONS ARE DETERMINED THROUGH AVAILABLE UTILITY OWNER INFORMATION. UTILITIES LABELED AS UNKNOWN HAVE NO CORRELATED RECORDS OR VISIBLE APPURTENANCES TO DETERMINE FUNCTION OR TYPE.
- 5. UTILITY MAPPING WAS COMPLETED ON 02/II/2019. THERE MAY EXIST UTILITES THAT ARE UNABLE TO BE ELECTROMAGNETICLY TONED OR DETECTED BY SUBSURFACE UTILITY EQUIPMENT OR GEOPHYSICAL METHODS. UTILITIES MAY HAVE BEEN CHANGED OR ADDED AFTER THIS DATE.
- 6. RELIANCE UPON THIS DATA FOR RISK MANAGEMENT PURPOSES DURING BIDDING DOES NOT RELIEVE THE EXCAVATOR OR UTILITY OWNER FROM FOLLOWING ALL APPLICABLE UTILITY DAMAGE PREVENTION STATUTES, POLICIES, AND/OR PROCEDURES DURING EXCAVATION.
- 7. ALL UTILITIES SHOWN HERE IN WERE PERFORMED UNDER THE DIRECTION OF TIMOTHY EDWARD PAYNE, LS. 403003090.

VERIZON COMMUNICATION LENWOOD TURNER SUPERVISOR OF NETWORK 502 E PIEDMONT STREET CULPEPER, VA 22701

MAP

MAP

MAP

RED

RED RED

OAM

DEC

LOC

CHE

LOCI

CHE

DEC

ΟΔŀ


POPL

CHE

POPL

BOX

WASHINGTON GAS DEBBIE BUNYEA RECORDS CLERK 6802 INDUSTRIAL ROAD SPRINGFIELD, VA 22151



DEMOLITION	SCHEDULE

YMBOL	DESCRIPTION
D-104	TREE TO BE REMOVED (AND STUMP GROUND) BY ARLINGTON
	COUNTY PRIOR TO CONSTRUCTION. THIS TREE HAS BEEN SLATED
	FOR REMOVAL BY ARLINGTON COUNTY LIDRAN FORESTER REFORE

FOR REMOVAL BY ARLINGTON COUNTY URBAN FORESTER BEFORE THE DESIGN PROCESS BEGAN.

IREE PRO	DTECTION SCHEDULE	
SYMBOL	DESCRIPTION	DETAIL
$\bigcirc$	TREE TRUNK & LIMB PROTECTION WRAP	I/LF-03
$\otimes$	REMOVE TREE & GRIND STUMP	
SYMBOL	DESCRIPTION	DETAIL
	DEMOLITION AS DIRECTED BY THIRD PARTY ARBORIST OR ARLINGTON COUNTY ARBORIST	
	DEMOLITION BY HAND REMOVAL	
	MULCH MATTING	8/LF-03
	TEMPORARY ROOT PROTECTION MATTING	3/LF-03
TPF	$$ INTERIOR TREE PROTECTION FENCING $\begin{pmatrix} 4 \\ LF-03 \end{pmatrix}$	
LOD/TP	EXTERIOR TREE PROTECTION FENCING/ CONSTRUCTION FENCE	
LOW	LIMIT OF WORK	

-RP ------ ROOT PRUNING 2/LF-03

APPLIES TO PHASE I AND PHASE 2):
ITH THE EXCEPTION OF THOSE THAT ARE SPECIFICALLY MARKED ON THE PLAN FOR REMOVAL, O
HE ARLINGTON COUNTY URBAN FORESTER.
NCE IS LOCATED AT THE LIMIT OF DISTURBANCE. THEREFORE, THE LAYOUT OF LINES DEPICTIN
AMMATIC, AND FOR REFERENCE ONLY. PLEASE REFER TO THE TREE PRESERVATION DETAILS FO

CONTRACTOR TO NOTIFY ARLINGTON COUNTY URBAN FORESTER 72 HOURS PRIOR TO INSTALLATION OF ANY TREE PRESERVATION MEASURES SHOWN ON PLANS AND ARLINGTON COUNTY URBAN FORESTER SHALL APPROVE THE LAYOUT OF TREE PRESERVATION

ARLINGTON COUNTY URBAN FORESTER RESERVES THE RIGHT TO MAKE ADJUSTMENTS TO TREE PROTECTION MEASURES BASED O

ALL ADJUSTMENTS TO THIS PLAN SHALL BE APPROVED BY URBAN FORESTER PRIOR TO SITE WORK. CONTRACTOR SHALL COORDINATE TREATMENT (I.E., RADIAL TRENCHING, SUPERSONIC AIR TOOL DECOMPACTION, SOIL COMPOST AMENDMENT, ROOT PRUNING) OF EXISTING TREES WITH COUNTY AS DEEMED NECESSARY. 4' WOOD G. IF TREE PROTECTION MEASURES PROVIDED ON THE PLANS AND SPECIFICATIONS ARE NOT FOLLOWED DURING ANY PART OF THE CONSTRUCTION PROCESS, THE URBAN FORESTER MAY ASK FOR THE REMOVAL AND REPLACEMENT OF ANY DAMAGED TREES AT THE CONTRACTOR'S EXPENSE. THIS WILL BE COORDINATED WITH THE CONSTRUCTION MANAGER AND LANDSCAPE ARCHITECT. PER SECTION 61-10.C.3 OF THE CHESAPEAKE BAY PRESERVATION ORDINANCE, THE PROPOSED USE OF THIS PROJECT IS EXEMPT FORM

SEE TREE PROTECTION DETAILS ON LF-03. SEE GRADING PLAN, SITE PLAN, LAYOUT PLAN AND CONSTRUCTION DETAILS FOR

(FULL OF DEBRIS) K. SEE TREE SCHEDULE AND PRESERVATION SUMMARY ON LF-04 FOR TREE-BY-TREE LIST OF PROPOSED TREE PRERVATION MEASURES.

. AN INDEPENDENT ARBORIST, HIRED BY THE GENERAL CONTRACTOR, SHALL BE ON-SITE DURING DEMOLITION OF EXISTING SIT ELEMENTS AS INDICATED ON THE LEGEND TO MONITOR TREE PRESERVATION MEASURES. INDEPENDENT ARBORIST SHALL OVERSE DEMOLITION WITHIN CRITICAL ROOT ZONES AND REPORT TO DPR FORESTRY STAFF WITH REGULAR COMMUNICATION AND MONTHLY WRITTEN REPORT, INCLUDING PHOTOGRAPHS, NOTES, PRESERVATION UPDATES AND CONSTRUCTION PROGRESS. 2. CONTRACTOR SHALL COORDINATE AND ARRANGE AN ON-SITE PRE-CONSTRUCTION MEETING WITH ARLINGTON COUNTY ARBORIST

ARLINGTON COUNTY LANDSCAPE ARCHITECT, CONSULTANT LANDSCAPE ARCHITECT, COUNTY THIRD PARTY ARBORIST AND ARLINGTON COUNTY CONSTRUCTION MANAGER PRIOR TO COMMENCEMENT OF ANY SITE WORK. 3. INSTALL PERIMETER CONSTRUCTION FENCE / TREE PROTECTION FENCE AS INDICATED IN THE DRAWINGS.

4. BEFORE ANY GRADING, DEMOLITION, OR OTHER DISTURBANCE IS PERFORMED (ASIDE FROM THE INSTALLATION OF THE TREE PROTECTION FENCE AND EROSION/SEDIMENT CONTROLS), TREE PROTECTION MEASURES SHALL BE INSTALLED PER PLAN AND INSPECTED/APPROVE

5. AS AGREED UPON AT THE FORESTRY PRE-CONSTRUCTION MEETING, AND AS SHOWN ON THESE DRAWINGS, INSTALL ALL INTERIOR TREA PROTECTION MEASURES (INCLUDING BUT NOT LIMITED TO THE TRUNK/LIMB PROTECTION, MULCH MAT, INTERIOR FENCING, ROOT

6. OF PARTICULAR IMPORTANCE IS THE LAYOUT AND INSTALLATION OF THE TEMPORARY ROOT PROTECTION MATTING AND INTERIOR TREE PROTECTION FENCING. THESE ARE SHOWN ON LF-0I BUT ARE SUBJECT TO FIELD LAYOUT MODIFICATIONS AS DEEMED APPROPRIATE B THE ARLINGTON COUNTY ARBORIST. THERE SHALL BE NO CUT OR EXCAVATION WITHIN TEMPORARY ROOT PROTECTION MATTING AREAS INTERIOR TREE PROTECTION FENCING, THE ACCESS ROUTE, OR THE MULCH MATTING AREAS.

7. THIS TEMPORARY "TREE PROTECTION ACCESS PATH" PROVIDES HEAVY EQUIPMENT ACCESS TO THE NORTH END OF THE SITE FOR THE 7.I. REFORESTATION PLANTING, PERMANENT REFORESTATION FENCING/SIGNAGE AND MULCH PATH;

DEMOLITION OF THE EXISTING BASKETBALL COURT & ASSOCIATED ELEMENTS; 7.3. CONSTRUCTION OF THE NEW BASKETBALL COURT, FENCING, CONCRETE WALKWAY, STORM DRAIN, GRADING, & ASSOCIATED NEARBY

8. MAINTAIN THE "TREE PROTECTION ACCESS PATH" UNTIL DEMOLITION/CONSTRUCTION IN THAT AREA IS COMPLETE, OR UNTIL THE TEMPORARY PATH MUST BE REMOVED IN ORDER TO PROPERLY INSTALL PROPOSED ELEMENTS SUCH AS THE PICNIC SHELTER AND PLAZA REPLENISH MULCH TO MAINTAIN 6" MINIMUM DEPTH, OR AS REQUIRED BY ARLINGTON COUNTY ARBORIST OR THIRD-PARTY ARBORIST, FOR AL LONG AS CONSTRUCTION VEHICLE ACTIVITY IS OCCURRING IN THE AREA.

8.2. ACCESS PATH SHALL ALIGN WITH STABILIZED CONSTRUCTION ENTRANCE AS SHOWN ON C-05 & C-06. 9. INSTALL TEMPORARY ROOT PROTECTION MATTING OR MULCH MATTING ATOP CRITICAL ROOT ZONES INSIDE THE LOD THAT ARE NOT PROTECTED BY TREE PROTECTION FENCING. LIKE THE ACCESS PATH, THE TEMPORARY MATTING:

9.1. SHALL NOT BE REMOVED UNTIL ABSOLUTELY NECESSARY TO CONSTRUCT PROPOSED SITE ELEMENTS.


9.2. SHALL BE USED TO PROTECT THE EXISTING GROUND AND CRITICAL ROOT ZONES FROM SOIL COMPACTION. 9.3. SHALL REMAIN IN PLACE UNTIL FINAL CONSTRUCTION OR FINAL GRADING NEEDS TO OCCUR, AT WHICH POINT CONSTRUCTION

EQUIPMENT SHALL NOT PASS OVER CRITICAL ROOT ZONES WHERE THE PROTECTIVE MATTING ONCE WAS PRESENT. 10. ROOT PRUNE ONLY IN CUT AND EXCAVATED AREAS PER LF-02 AND WHERE INSTRUCTED BY ARLINGTON COUNTY URBAN FORESTER.


II. REMOVE, DEMOLISH OR ABANDON OTHER EXISTING PARK ITEMS, MATERIALS AND HARDSCAPE PER DEMOLITION PLAN C-04. ANY O THESE ITEMS THAT ARE ALSO WITHIN THE CRITICAL ROOT ZONES SHALL BE REMOVED BY HAND AND/OR UNDER SUPERVISION O COUNTY OR THIRD-PARTY ARBORIST, AS INDICATED ON THE DRAWINGS. THIS WORK SHALL BE COMPLETED WITHOUT MOVING TREE


12. IN AREAS WHERE EXISTING FULL DEPTH PAVEMENT IS REMOVED BUT NOT REPLACED WITH NEW PAVEMENT ON THE PROPOSED SIT PLAN, THE CONTRACTOR SHALL PROVIDE FILL TO BRING GRADES BACK TO EXISTING CONDITIONS AND IMMEDIATELY STABILIZE UPON COMPLETION. FILLED GRADES SHALL BE A MINIMUM OF 2% TO PROMOTE PROPER DRAINAGE.

T
A R L I N G T O N
DEPARTMENT OF PARKS AND RECREATION
Park Development Division 2100 Clarendon Boulevard, Suite 414 Arlington, VA 22201 Phone: 703.228.3332 Fax: 703.228.3328
21-DPR-ITB-646
Project Name and Location Marcey
Road Park
Improvements (By Right)
(County Project) 2722 MARCEY ROAD
ARLINGTON, VA 22207
Sheet Title TREE
PRESERVATION PLAN - PHASE I
100% Construction Drawings
Approval Date
Approval Date
Design Manager
Design Manager
Design Manager   Revisions Date   Image: Date Image: Date   Image: Date
Design Manager   Revisions Date
Design Manager         Revisions       Date
Design ManagerRevisionsDate
Design Manager         Revisions       Date
Design Manager         Revisions       Date
Design Manager         Revisions       Date
Design Manager     Revisions     Date     Date     Designed: AW   Drawn:   Matchecked:   SDT, JKS, MMW, CMB     Filename:   If-01-150396024 site:   plan.dwg   Plotted:   2021-06-02   Scale: I" = 20' Date:     JUNE 2, 2021     Matchew M. WEIR   Cer, No. 0406001961     JUNE 2, 2021




TREE PR	OTECTION SCHEDULE		
	<u>DESCRIPTION</u> TREE TRUNK & LIMB PROTECTION WRAP	DETAIL I/LF-03	
	MULCH MATTING	8/LF-03	A R L I N G T O N
	TEMPORARY ROOT PROTECTION MATTING	3/LF-03	DEPARTMENT OF PARKS AND RECREATION
TPF	INTERIOR TREE PROTECTION FENCING		Park Development Division 2100 Clarendon Boulevard, Suite 414
LOD/TP	EXTERIOR TREE PROTECTION FENCING/ CONSTRUCTION FENCE	<b>/</b>	Arlington, VA 22201 Phone: 703.228.3332
LOW	LIMIT OF WORK		Fax: 703.228.3328
RP	ROOT PRUNING 2/LF-03		21-DPR-ITB-646
			Project Name and Location
			Marcey
			Marcey Road Park
			Improvements
			(By Right)
			(County Project)
			2722 MARCEY ROAD
			ARLINGTON, VA 22207
			Sheet Title
			TREE
			PRESERVATION
			PLAN - PHASE 2
			100% Construction Drawings
			Approval Date
			Design Manager
SEQUENCE:	<u>-</u>		
~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~	~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~	~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~	Revisions   I   Date     ADDENDUM 2   7/28/21
E NO CUT OR EX G, CONSTRUCTIO ITILITIES. COOR	MEASURES AS SHOWN ON LF-02 AND AS REQUIRED E CAVATION WITHIN TEMPORARY ROOT PROTECTION M ON ACCESS ROUTE, OR THE MULCH MATTING AREA DINATE ANY CUT REQUIRED IN THESE AREAS R AND LANDSCAPE ARCHITECT PRIOR TO COMMENCIN	ATTING AREAS, THE INTERIOR AS, UNLESS AS REQUIRED TO WITH ARLINGTON COUNTY'S	
	NOT DESCRIBED ON LF-01 FOR CONSTRUCTION REA, COVER THE AREA THAT WILL EVENTUALLY R		Designed: AW Drawn: AMT
S WILL PROTECT O BE PLACED.	TREE #25'S CRITICAL ROOT ZONE FROM COMPACTION	ON AND OTHER DISTURBANCES	Checked: SDT, JKS, MMW, CMB
CE FILL AND PC	A AND SHELTER, REMOVE MULCH MATTING FROM OUR CONCRETE AS SHOWN ON THE PLANS. MAKE AD PROTECT T25 AT NO ADDITIONAL EXPENSE TO T	JUSTMENTS AS REQUIRED BY	Filename: ^{If-01-150396024 site} plan.dwg Plotted: 2021-07-28
	VEMENT FOR VEHICLE/MACHINE ACCESS TO THE B E EXISTING TENNIS COURT PAVEMENT PROTECTS		Scale: 1" = 20'
	TAINING WALL AND BIORETENTION, KEEPING HEAVY TAIN PROTECTION MEASURES AND EXISTING PAVEN		Date: JUNE 2, 2021
BE REMOVED II CT OFFICER AND	N ORDER TO PROPERLY INSTALL THE PROPOSED E URBAN FORESTER. SSOCIATED ELEMENTS, SUCH AS FENCING, TRENCH D	LEMENTS. COORDINATE WITH	Seal
THE PARK'S CO THE ACCESS WAI	ONSTRUCTION, WHICH IS LARGELY OUTSIDE OF C LKWAYS TO THE TENNIS COURT AND PLAZA AREA,	RITICAL ROOT ZONES. THIS DRINKING FOUNTAIN/POTABLE	COMP
HALL MEET EXIS	WITH SUPER SONIC AIR TOOL EXCAVATION WHERE SH STING GRADE UNIFORMLY TO ENSURE A SMOOTH TR, F THERE ARE ANY EDGE CONDITIONS THAT CREAT	ANSITION. NOTIFY ARLINGTON	MATTHEW M. WEIR Cert, No. 0406001961
OMPLETE, AND V MEASURES FROM	WHEN DIRECTED BY ARLINGTON COUNTY PROJECT OF 1 SITE.	FICER AND URBAN FORESTER,	JUNE 2, 2021
			Sheet
			LF-02





NOT USED

6



			1					COLUMNS WILL BE (I), AND PRESERVATION	RE SUBMISSION.
Tree #	SCIENTIFIC NAME	COMMON NAME	DBH (INCHES)	CRITICAL ROOT ZONE (RADIUS)	AMT Condition Rating	NOTES:	TREE TO BE REMOVED BY CONTRACTOR	% CRZ WITHIN LIMITS OF DISTURBANCE	PRESERVATION MEASURES (PHASE I)	PRESERVATION MEASURES (PHAS 2)
ΤI	Malus sp.	CRABAPPLE SP.	23.00	23.00	53.13	WINTER ID; EROSION AT BASE OF THE TREE FROM TENNIS COURT RUNOFF; WOUND IN TRUNK; POSSIBLE HEART ROT; EPICORMIC GROWTH IN CANOPY	REMOVE	100%		
Т2	Liriodendron tulipifera	YELLOW POPLAR	9.00	9.00	75.00	SLIGHT LEAN, CROWDED BY ADJACENT MAPLE. ROOTS IN COMPACTED DIRT TRAIL		100%		
Т3	ACER SACCHARINUM	SILVER MAPLE	14.00	14.00	71.88	NARROW CANOPY; ROOTS IN COMPACTED DIRT TRAIL		100%		
Τ4	Buxus sempervirens	ENGLISH BOXWOOD	8.50	8.50	62.50	MULTI-TRUNK (3", 4", 4", 5.5"); ROOTS IN COMPACTED DIRT TRAIL; ONE OF THE MULTI-STEM TRUNKS HAS A BROKEN LEADER; ONE MULTI-STEM TRUNK PREVIOUSLY REMOVED		100%		
Τ5	PLATANUS X ACERIFOLIA	LONDON PLANE TREE	8.50	8.50	81.25	SLIGHT LEAN		26%	TPF	TPF, RP
Τ6	QUERCUS RUBRA	NORTHERN RED OAK	5.50	8.00	81.25	PLANTED TREE; VINES CLIMBING BASE AND INTO CANOPY; WIRE DEAR CAGE AROUND TRUNK		33%	TPF	TPF
Τ7	ILEX OPACA	AMERICAN HOLLY	14.00	14.00	59.38	TRIPLE TRUNK (6", 9", 9"); IN TREE WELL/TREE WALL; INASIVES AT BASE AND CLIMBING TRUNK		0%		
T8	LIRIODENDRON TULIPIFERA	YELLOW POPLAR	5.00	8.00	70.31	Wounds in Trunk		0%		
T9	ACER SACCHARUM	SUGAR MAPLE	4.50	8.00	81.25	ON SLOPE; MINOR ROOT DAMAGE		0%		
T10 T11	CERCIS CANADENSIS	REDBUD RED MAPLE	4.50	8.00	75.00	N/A SIGNIFICANT DAMAGE TO TRUNK		0%		
TI2	LIRIODENDRON TULIPIFERA	YELLOW POPLAR	5.50	8.00	70.31	LEANING; POOR FORM; TWO LEADERS; ON STEEP SLOPE		0%		
TI3	LIRIODENDRON TULIPIFERA	YELLOW POPLAR	4.50	8.00	73.44	Two leaders (one larger and one smaller); included bark		0%		
TI4	LIRIODENDRON TULIPIFERA	YELLOW POPLAR	5.00	8.00	73.44	SLIGHT LEAN; MINOR DAMAGE AT BASE		0%		
TI5	ULMUS AMERICANA	AMERICAN ELM	8.50	8.50	79.69	N/A		0%		
T16	Ulmus Americana	American elm	6.50	8.00	71.88	ON STEEP SLOPE		0%		
T17	ILEX OPACA	AMERICAN HOLLY	21.50	21.50	71.88	TRIPLE LEADERS IN CANOPY. VINES CLIMBING TRUNK		32%	TPF, RP	TPF
T18	ACER SACCHARUM	SUGAR MAPLE	4.00	8.00	82.81	N/A		54%	TPF, TP, RP	TPF, TP
T19	CATALPA SPECIOSA	NORTHERN CATALPA	37.00	37.00	43.75	MAJOR WOUND BASE; LEANING; HEART ROT; EPICORMIC GROWTH; OVERHEAD LINES; HAZARD TREE; ROOTS UNDER PAVEMENT		12%	TPF	TPF
T20	CATALPA SPECIOSA	NORTHERN CATALPA	31.50	31.50	40.63	MAJOR WOUND BASE; LEANING; HEART ROT; EPICORMIC GROWTH; OVERHEAD LINES; HAZARD TREE; ROOTS UNDER PAVEMENT		0.2%	TPF, HAND REMOVAL	TPF
T2I	ACER SACCHARINUM	SILVER MAPLE	42.00	42.00	43.75	ROOTS UNDER PAVEMENT; WOUNDS AT BASE; HEART ROT; VINES AT BASE AND CLIMBING; BROKEN LIMBS; HAZARD TREE; OVERHEAD LINES		0%	HAND REMOVAL	
T22	ACER RUBRUM	RED MAPLE	37.50	37.50	73.44	VINES CLIMBING		37%	TPF, RP	TPF
T23	PICEA ABIES	NORWAY SPRUCE	21.50	21.50	71.88	N/A		100%	TPF, TRPM	TPF, TRPM
T24	ACER SACCHARINUM	SILVER MAPLE	49.00	49.00	71.88	POSSIBLE HEART ROT IN TRUNK AND LEADER; BROKEN AND ROTTEN LOWER LIMB IS A HAZARD	REMOVAL BY COUNTY, NOT GC	98%		
T25	ACER SACCHARINUM	SILVER MAPLE	56.00	56.00	75.00	A FEW BROKEN LIMBS IN CANOPY		100%	TPF, TP, RP, TRPM, MM, HAND REMOVAL, DEMO AS DIRECTED	TPF, RP, TP, MM TRPM
T26	CERCIS CANADENSIS	REDBUD	6.50	8.00	71.88	N/A	REMOVE	100%		
T27	CERCIS CANADENSIS	REDBUD	6.00	8.00	71.88	N/A	REMOVE	100%		
T28	CERCIS CANADENSIS	REDBUD	7.50	8.00	68.75	EPICORMIC GROWTH AT BASE	REMOVE	100%		
Т29	QUERCUS RUBRA	NORTHERN RED OAK	7.50	8.00	73.44	TWO LEADERS IN CANOPY; ROOTS UNDER ROAD		1%	TPF, HAND REMOVAL	TPF
T30	QUERCUS RUBRA	NORTHERN RED OAK	5.50	8.00	81.25	N/A		0%		
T3I	QUERCUS RUBRA	NORTHERN RED OAK	11.50	11.50	81.25	N/A		0.2%	TPF	TPF
T32	PINUS STROBUS	EASTERN WHITE PINE	16.50	16.50	53.13	MAJOR LEAN; MAJOR WOUND; ROOTS UNDER ROAD		0%	HAND REMOVAL	
T34	ROBINIA PSEUDOACACIA ROBINIA PSEUDOACACIA	BLACK LOCUST	10.00	10.00	68.75 73.44	ON SLOPE; LEANING; VINES IN CANOPY A FEW BROKEN LIMBS		0%		
T35	MAGNOLIA X SOULANGEANA	BLACK LOCUST CHINESE MAGNOLIA	9.00	9.00	64.06	WOUND AT BASE		43%	TPF, HAND REMOVAL	TPF
Т36	MAGNOLIA X SOULANGEANA	CHINESE MAGNOLIA	10.00	10.00	73.44	DOUBLE TRUNK (6", 8")		10%	TPF	TPF
Т37	Magnolia x soulangeana	CHINESE MAGNOLIA	13.00	13.00	73.44	TRIPLE TRUNK (7", 7.5", 8")		40%	TPF, HAND	TPF
T38	Tsuga canadensis	EASTERN HEMLOCK	34.50	34.50	67.19	TRIPLE TRUNK (15", 20", 24"); SHALLOW SURFACE ROOTS; VINES AT BASE		18%	REMOVAL TPF, HAND REMOVAL	TPF
Т39	ROBINIA PSEUDOACACIA	BLACK LOCUST	30.00	30.00	29.69	ON BANK; LEANING; HEART ROT; VINES; HAZARD TREE; PREVIOUSLY REMOVED LEADER		0%		
T40	FAGUS GRANDIFOLIA	AMERICAN BEECH	4.00	8.00	82.81	VINES CLIMBING		0%		
T41	PRUNUS SEROTINA	BLACK CHERRY	11.00	11.00	73.44	SLIGHT LEAN; VINES		2%	TPF	TPF
T42	ROBINIA PSEUDOACACIA	BLACK LOCUST	10.50	10.50	78.13	MAJOR VINES		0%		
T43	BETULA LENTA	BLACK BIRCH	2.00	8.00	70.31	THIN CANOPY		0%		
T44	PRUNUS SEROTINA	BLACK CHERRY	4.00	8.00	65.63	VINES TAKING OVER CANOPY		0%		
T45	ROBINIA PSEUDOACACIA	BLACK LOCUST	2.50	8.00	71.88	THIN CANOPY; CROWDED		0%		
T46 T47		STANDING DEAD	0.00	0.00	0.00	STANDING DEAD		0%		
T47	PRUNUS SEROTINA QUERCUS PRINUS	BLACK CHERRY CHESTNUT OAK	6.00	8.00	75.00	MAJOR LEAN OVER TENNIS COURT; VINES VINES ON TRUNK AND IN CANOPY		0%		
T48 T49	LIRIODENDRON TULIPIFERA	YELLOW POPLAR	16.00	16.00	85.94	VINES ON TRUNK AND IN CANOPY VINES ON TRUNK AND IN CANOPY		0%		
T50	PRUNUS SEROTINA	BLACK CHERRY	4.00	8.00	60.94	VINES ON TRUNK AND IN CANOPY; MAJOR LEAN; CROWDED		0%		
T51	LIRIODENDRON TULIPIFERA	YELLOW POPLAR	18.00	18.00	79.69	VINES ON TRUNK AND IN CANOPY		0.5%	TPF	TPF
T52	ACER NEGUNDO	BOX ELDER	5.00	8.00	71.88	SPROUTS AT BASE; VINES AT BASE; CROWDED		1%	TPF, RP	TPF
	LIRIODENDRON TULIPIFERA	YELLOW POPLAR	35.50	35.50	70.31	DOUBLE TRUNK (22", 28"); MAJOR VINES ON TRUNK AND IN CANOPY;		24%	TPF, RP	TPF
T53			1			INCLUDED BARK		1		1
T53	LIRIODENDRON TULIPIFERA	YELLOW POPLAR	17.00	17.00	79.69	CROWDED; THIN CANOPY		0%		

CONTRACTOR SHALL REFER TO THE TREE PRESERVATION PLANS FOR SPECIFIC PROTECTION MEASURES. IN THE EVENT OF A DISCREPANCY BETWEEN THE PRESERVATION MEASURES (PHASE | & II) LISTED IN THIS TREE TABLE AND THE TREE PRESERVATION PLANS, THE PLANS SHALL GOVERN.

TPF = TREE PROTECTION FENCE TP = TRUNK PROTECTION TRPM = TEMPORARY ROOT PROTECTION MATTING RP = ROOT PRUNING MM = MULCH MATTING

RAM = ROOT AERATION MATTING HAND REMOVAL = HAND DEMO OF EXISTING INFRASTRUCTURE WITHIN CRITICAL ROOT ZONE (THE TREE ITSELF IS NOT TO BE REMOVED) DEMO AS DIRECTED = DEMOLITION AS DIRECTED BY THIRD PARTY ARBORIST OR ARLINGTON COUNTY ARBORIST (THE TREE ITSELF IS NOT TO BE REMOVED)

TREE IDENTIFICATION, CONDITIONS AND RETENTION POTENTIAL: NOTE I: TREE SPECIES NAMED REPRESENT THE PROFESSIONAL JUDGMENT OF THE PREPARER. THERE ARE A VARIETY OF REASONS IDENTIFICATION CAN BE INCONCLUSIVE: WINTER IDENTIFICATION IS LESS RELIABLE THAN DURING THE GROWING SEASON. PROPER IDENTIFICATION CAN ONLY BE MADE ON THE BASIS OF FLOWERING PARTS, WHICH ARE OFTEN ABSENT. WHILE THE NAMED GENERA ARE FELT TO BE RELIABLE, SOME SPECIES AND HYBRIDS ARE LESS CERTAIN. ONE EXAMPLE IS THE DISTINCTION BETWEEN QUERCUS SPECIES. Q. RUBRA, Q. BOREALIS, Q. PALUSTRIS AND Q. FALCATA ARE ALL CLASSIFIED AS "RED OAKS", AND THEY ARE NOTABLE FOR FREELY HYBRIDIZING. EVEN EXAMINATION OF FLORAL PARTS IS OFTEN INCONCLUSIVE. THE GENERA MALUS AND CRATAEGUS POSE A SIMILAR CHALLENGE.

NOTE 2: NO WARRANTY, EXPRESSED OR IMPLIED, CAN BE MADE WITH RESPECT TO TREE SAFETY, FITNESS OR SURVIVAL. THE COMMENTARY ABOUT INDIVIDUAL TREES NOTES SOME ACTUAL OR POTENTIAL DEFECTS TO BE CONSIDERED. HOWEVER, HIDDEN FACTORS AND UNFORESEEABLE EVENTS MAY BE HIGHLY SIGNIFICANT, WHILE SOME OF THE POTENTIAL PROBLEMS NOTED MAY NOT. THE PROPOSED DISTURBANCES WILL HAVE SOME ADVERSE IMPACT UPON THE REMAINING TREES. OTHER STRESSES SUCH AS DISEASE, WIND, SUNSCALD, AIR POLLUTION, REFLECTED HEAT AND LIGHT, INSUFFICIENT OR EXCESS RAINFALL CAN COMBINE TO CAUSE ADDITIONAL DAMAGE OR DEATH TO A TREE. ANY RECOMMENDED ACTIONS ARE INTENDED TO PARTIALLY OFFSET FORESEEABLE DAMAGE. HOWEVER, TREES SHOULD BE MONITORED AND ADDITIONAL CORRECTIVE MEASURES OR REMOVAL MAY BE NECESSARY.


NOTE: PER SECTION 61-10.C.3 OF THE CHESAPEAKE BAY PRESERVATION ORDINANCE, THE PROPOSED USE OF THIS PROJECT IS EXEMPT FROM THE TREE CANOPY COVERAGE REQUIREMENTS OF THE ORDINANCE.

NOTE: THIS PLAN IS FOR TREE PROTECTION/ FOREST CONSERVATION PURPOSES ONLY.

TREE REPLACEMENTS							
SPECIES	TREE ID NUMBER	NUMBER OF TREES REMOVED	DBH (INCHES)	CONDITION	SPECIES RATING	TOTAL SCORE	REPLACEMENTS REQUIRED
MALUS SP.	ΤI	I	23	0.5313	0.5	6.11	2
Acer saccharum	Т24	I	49				REPLACEMENT NOT INCLUDED IN THIS CONTRACT
Cercis canadensis	T26	I	6.5		-		I
Cercis canadensis	T27	I	6		-		I
Cercis canadensis	T28		7.5		-		I
TOTAL 5							
*SHADED CELLS INDICATE TREES WITH 10" DBH AND SMALLER, WHICH ARE AUTOMATICALLY							

REPLACED AT A RATE OF ONE-FOR-ONE ACCORDING TO THE POLICY. SEE PLANTING PLAN FOR TREE REPLACEMENTS.

T ARLINGTON VIRGINIA DEPARTMENT OF PARKS AND RECREATION Park Development Division 2100 Clarendon Boulevard, Suite 414 Arlington, VA 22201 Phone: 703.228.3332 Fax: 703.228.3328 21-DPR-ITB-646 Project Name and Location Marcey Road Park Improvements (By Right) (County Project) 2722 MARCEY ROAD ARLINGTON, VA 22207 Sheet Title EXISTING TREE TABLE - TREE CONDITION SUMMARY 100% Construction Drawings Date Approval Design Manager Date Revisions Designed: AW Drawn: AMT Checked: SDT, JKS, MMW, CMB Filename: If-01-150396024 site plan.dwg Plotted: 2021-06-02 Scale: N.T.S. Date: JUNE 2, 2021 Seal ____ MATTHEW M. WEIR ****** JUNE 2, 2021 Sheet LF-04




DEMOLITION NOTES:

LOCATION OF ALL UTILITIES SHOWN ARE APPROXIMATE. IT IS THE RESPONSIBILITY OF M THE CONTRACTOR TO FIELD VERIFY AND DETERMINE THE EXACT LOCATION AND DEPTH OF ALL UTILITIES WITHIN THE LIMIT OF DISTURBANCE PRIOR TO COMMENCING WORK. REPORT ANY DISCREPANCY TO THE PROJECT OFFICER. THE CONTRACTOR SHALL CONTACT MISS UTILITY AT 811 A MINIMUM OF 72 HOURS PRIOR TO ANY EXCAVATION TO DETERMINE THE EXACT ARLINGTON LOCATION OF ALL EXISTING UTILITIES AND SHALL BE FULLY RESPONSIBLE FOR ANY AND AL DAMAGES WHICH MAY BE OCCASIONED BY THE CONTRACTOR'S FAILURE TO EXACTLY VIRGINIA LOCATE AND PRESERVE ANY AND ALL EXISTING UTILITIES. 2. THE DEMOLITION PLAN IS A GENERAL GUIDE OF WHAT ITEMS NEED TO DEMOLISHED. IT SHALL B THE CONTRACTOR'S RESPONSIBILITY TO IDENTIFY ALL ITEMS THAT REQUIRED DEMOLITION TO COMPLETE THE PROPOSED CONSTRUCTION. DEPARTMENT OF PARKS . CONTRACTOR SHALL PROTECT AND PRESERVE ALL EXISTING SITE STRUCTURES AND FEATURES AND RECREATION NOT SCHEDULED FOR DEMOLITION AND/ OR CONSTRUCTION FROM DAMAGE DUE TO DEMOLITION PROCEDURES. ANY RESULTING DAMAGE SHALL BE THE CONTRACTOR'S RESPONSIBILITY AND Park Development Division SHALL BE RESTORED AT THE CONTRACTOR'S EXPENSE TO THE SATISFACTION OF THE PROJECT 2100 Clarendon Boulevard, Suite 414 OFFICER. Arlington, VA 22201 4. TEMPORARY CONSTRUCTION FENCING SHALL BE ERECTED AS SHOWN ON THE PLANS PRIOR T Phone: 703.228.3332 BEGINNING CONSTRUCTION OPERATIONS AND MAINTAINED UNTIL COMPLETION OF PROJECT. TREE Fax: 703.228.3328 PROTECTION AND CONSTRUCTION FENCE SHALL BE THE SAME WHEREVER THEY OVERLAP. 5. THE CONTRACTOR SHALL BE FULLY RESPONSIBLE FOR SAFETY AND SECURITY AT THE PROJECT SITE FOR THE DURATION OF THE CONTRACT. 6. CONTRACTOR SHALL COORDINATE WITH THE PROJECT OFFICER TO IDENTIFY ANY 21-DPR-ITB-646 NECESSARY STAGING/STORAGE AREAS. PROPOSED STAGING AND STORAGE AREAS SHALL BE REVIEWED AND APPROVED BY THE PROJECT OFFICER, AND THE LIMITS OF WORK WILL BE ADJUSTED ACCORDINGLY. 7. ANY STOCKPILING, REGARDLESS OF LOCATION ON SITE, SHALL BE STABILIZED IMMEDIATEL **Project Name and Location** AFTER ITS ESTABLISHMENT AND FOR THE DURATION OF THE PROJECT. STOCKPILES SHALL E CONTAINED BY STRAW BALES OR EROSION CONTROL FENCING AND COVERED WITH PLASTIC OR Marcey CANVAS AT THE END OF EACH WORK DAY FOR THE DURATION OF THE PROJECT. 8. WHERE ITEMS TO BE REMOVED OCCUR WITHIN TREE PROTECTION ZONES, THE CONTRACTOR SHALL REMOVE THE ITEMS WORKING WITH A COUNTY ARBORIST (PROVIDED BY COUNTY) ON-SITE Road Park TO OBSERVE AND MINIMIZE TREE DAMAGE. CONTRACTOR SHALL NOTIFY THE LANDSCAPE ARCHITECT FIVE BUSINESS DAYS PRIOR TO THESE REMOVALS. 9. CARE SHALL BE TAKEN TO PRESERVE EXISTING TREES AND THEIR ROOT SYSTEMS. TREES Improvements INCURRING ROOT DAMAGE DUE TO CONSTRUCTION SHALL BE PRUNED AND FERTILIZED PER THE SPECIFICATIONS. 10. NO MATERIALS OR EQUIPMENT SHALL BE PERMITTED WITHIN THE TREE PROTECTION AREA (By Right) ANY VIOLATION OF THIS REQUIREMENT WILL RESULT IN A FINE OF \$500 PER DAY OF VIOLATION. II. UNAUTHORIZED TREE REMOVALS, TREE DEATH OR SEVERE DAMAGE DUE TO THE CONTRACTOR'S FAILURE TO EXERCISE PROPER CARE WHEN WORKING NEAR TREES, SHALL RESULT IN A FINE (County Project) EQUAL TO THE LANDSCAPE VALUE OF THE TREE AS PUBLISHED IN THE LATEST EDITION OF THE COUNCIL OF TREE AND LANDSCAPE APPRAISERS GUIDE FOR PLANT APPRAISALS PUBLISHED BY TH 2722 MARCEY ROAD INTERNATIONAL SOCIETY OF ARBORICULTURE. ARLINGTON, VA 22207 COUNTY ARBORIST INSPECTION IS REQUIRED PRIOR TO ANY SITE LAND DISTURBANCE ACTIVITY. 13. DEMOLITION STAGE EROSION AND SEDIMENT CONTROLS AND TREE PROTECTION MEASURES SHALL BE INSTALLED PRIOR TO DEMOLITION 14. ALL MATERIAL FROM DEMOLITION NOT IDENTIFIED FOR REUSE SHALL BE REMOVED FROM THE SITE AND DISPOSED OF IN ACCORDANCE WITH APPROPRIATE REGULATIONS. Sheet Title 15. ALL PAVEMENT REMOVED SHALL BE DONE SUCH THAT REMAINING PAVEMENT IS LEFT WITH CLEAN STRAIGHT EDGE. CONCRETE PAVEMENT/ CURBING SHALL BE REMOVED TO THE NEAREST JOINT DEMOLITION 16. EXISTING PAVEMENT SHALL BE SAW CUT WHEN NEXT TO REMAINING PAVEMENT BEFORE REMOVAL. ALL SAW CUTS SHALL BE STRAIGHT, EVEN CUTS; JAGGED CUTS WILL NOT BE PLAN PERMITTED 17. CHAIN LINK FENCE REMOVED: INCLUDES ALL FENCE POSTS AND CONCRETE FOOTINGS. 18. CONCRETE REMOVAL: SHALL INCLUDE CONCRETE, STEEL REINFORCEMENT, AND GRAVEL BASE WHERE NO PROPOSED CONCRETE WILL BE INSTALLED. 19. ASPHALT REMOVAL: SHALL INCLUDE SURFACE, BASE AND SUBBASE MATERIALS. 20. CONTRACTOR SHALL REMOVE AND DISPOSE OF ANY SITE FURNISHINGS WITHIN THE LIMITS OF DISTURBANCE NOT REMOVED FROM SITE PRIOR TO COMMENCEMENT OF CONSTRUCTION (IE SIGNAGE, BENCHES, TRASH RECEPTACLES, ETC). 21. CONTRACTOR SHALL PROVIDE EXISTING DAMAGE PHOTOS PRIOR TO MOBILIZING OR PERFORMING ANY WORK. LOCATIONS OF PICTURES TO BE RECORDED ON THIS SHEET 100% Construction Drawings 22. TO PREVENT DAMAGES OUTSIDE THE LIMITS OF DISTURBANCE, NO PARK AREAS OUTSIDE THE LOD SHALL BE USED FOR STAGING OR STORAGE 23. UPON COMPLETION OF THE PROJECT, ALL EXCESS SOIL, SAND, MULCH, TEMPORARY FENCING EROSION CONTROL MEASURES, STABILIZATION MATERIALS, AND OTHER DEBRIS SHALL BE REMOVED FROM THE SITE AND DISPOSED OF LEGALLY. ALL PAVED AREAS, WALLS, ETC. SHALL BE THOROUGHLY WASHED AND CLEANED UPON COMPLETION OF THE PROJECT. 24. REFER TO SITE CLEARING, DEMOLITION, & REMOVALS SPECIFICATION FOR ADDITIONAL REQUIREMENTS. 25. THE GENERAL CONTRACTOR SHALL INITIATE OUTREACH TO UTILITY COMPANIES FOR SHUTOFF CAPPING AND CONTINUATION OF UTILITY SERVICES AS REQUIRED. IF UTILITY COMPANIES REQUIRE THE UTILITY ACCOUNT OWNER (I.E., ARLINGTON COUNTY) TO REQUEST THE UTILITY SHUTOFF THE GENERAL CONTRACTOR SHALL NOTIFY ARLINGTON COUNTY OF THIS REQUIREMENT. THI GENERAL CONTRACTOR SHALL COORDINATE TIMING OF SHUTOFF AND ASSOCIATED UTILITY WORK WITH ARLINGTON COUNTY AND THE RESPECTIVE UTILITY COMPANY. THE GENERAL CONTRACTO Approval IS RESPONSIBLE FOR PROVIDING APPROPRIATE TIME IN THE CONSTRUCTION SCHEDULE TO ALLOW FOR UTILITY COMPANIES TO PROCESS THE WORK ORDER REQUEST WITHOUT A DELAY TO TH CONSTRUCTION SCHEDULE. THE GENERAL CONTRACTOR IS RESPONSIBLE FOR THE CAPPING AND CONTINUATION OF UTILITY SERVICES AS NEEDED Design Manager 26. THE CONTRACTOR IS RESPONSIBLE FOR ANY DAMAGE THAT OCCURS TO ANY EXISTING SITE ELEMENT THAT IS NOT MARKED FOR DEMOLITION DURING CONSTRUCTION AND MUST REPLACE AT NO COST TO ARLINGTON COUNTY IF DAMAGED. Revisions 27. CONTRACTOR SHALL INFORM LANDSCAPE ARCHITECT AND PROJECT OFFICER IF ANY ADDENDUM 2 ITEMS/INFORMATION IS NOT LISTED OR CALLED OUT, SO AN APPROPRIATE SOLUTION CAN BE DISCUSSED. CONTRACTOR SHALL HAVE WRITTEN APPROVAL FROM LANDSCAPE ARCHITECT AND PROJECT OFFICER PRIOR TO ANY FURTHER SITE WORK 28. CONTRACTOR SHALL PERFORM UTILITY TEST HOLE TO DETERMINE EXACT LOCATION AND CONDITION OF THE EXISTING ON-SITE WATERLINE. COORDINATE TEST HOLE WITH ARLINGTON COUNTY PROJECT OFFICER. IN CONSULTATION AND AGREEMENT WITH ARLINGTON COUNTY PROJECT OFFICER, IF THE EXISTING ON-SITE WATER LINE IS IN GOOD WORKING CONDITION CONTRACTOR SHALL CUT THE EXISTING WATERLINE FOR NEW WATERLINE CONNECTION AT THE TEST HOLE LOCATION. OTHERWISE, CONTRACTOR SHALL REMOVE ADDITIONAL EXISTING WATERLINE AS NEEDED UP TO THE PRIVATE SIDE OF THE 5/8" WATER METER AND MAKE NEW WATERLINE CONNECTION AT NO ADDITIONAL EXPENSE TO ARLINGTON COUNTY. Designed: AW RESTORATION NOTE Drawn: AMT IN AREAS WHERE FULL DEPTH PAVEMENT IS DEMOLISHED, CONTRACTOR SHALL PROVIDE FILL TO Checked: SDT, JKS, MMW, CMB BRING GRADES BACK TO EXISTING CONDITIONS AND IMMEDIATELY STABILIZE UPON COMPLETION. FINAL GRADES SHALL BE A MINIMUM OF 2% TO PROMOTE PROPER DRAINAGE. Filename: c-04-150396024 demo plan.dwg TREE PROTECTION NOTE SEE TREE PRESERVATION SHEETS AND DETAILS FOR ADDITIONAL REQUIREMENTS BEFORE Plotted: 2021-07-28 DURING AND AFTER DEMOLITION PHASE. Scale: |" = 20' EXISTING WALL TO BE DEMOLISHED AND Date: JUNE 2, 2021 REMOVED. DEMOLISH FULL DEPTH, INCLUDING ANY SUBBASE AND AGGREGATE Seal _**__** $\overline{\bigcirc}$ EXISTING GAZEBO TO BE DEMOLISHED AND arDelta REMOVED. DEMOLISH FULL DEPTH, INCLUDING ANY PAVEMENT, SUBBASE, AGGREGATE AND FOOTERS. MATTHEW M. WEIR EXISTING CHAIN LINK FENCE, RAILING, AND rt No. 04060019 · GATES TO BE DEMOLISHED AND REMOVED, ||| |-|| ŀ// INCLUDING FOOTERS. EXISTING UTILITY TO BE REMOVED OR ABANDONED (AS • // /4 /4 // • DIRECTED BY ARLINGTON COUNTY PROJECT OFFICER) ****** JUNE 2, 2021 LOD/TP ------ LIMIT OF DISTURBANCE/TREE PROTECTION FENCE ----- LOW ------ LIMIT OF WORK Sheet C-04

Date

Date

7/28/21



EROSION AND SEDIMENT CONTROL LEGEND

١0.	KEY	SYMBOL
		RPA
3.38	TP	LOD/TP
		LOW
3.02	CE	
.05	SSF	SSF
.04	FL	FL-15

DESCRIPTION

PROPERTY LINE

RESOURCE PROTECTION AREA LIMITS OF DISTURBANCE/TREE PROTECTION FENCE (DETAIL 4/LF-03) LIMITS OF WORK

10'x40' MODIFIED CONSTRUCTION ENTRANCE WITH WASH RACK

SUPER SILT FENCE

15" FILTER LOG



- FENCE ARE SHOWN, THE FILTER FABRIC SHALL BE ADHERED TO THE TREE PROTECTION FENCE.2. WHERE FILTER LOG IS SHOWN ADJACENT TO TREE
- 2. WHERE THEFTER LOG IS SHOWN ADDACENT TO TREE PROTECTION FENCE.
 3. SEE LF-01 FOR INSTRUCTIONS ON PHASING/SEQUENCING OF
- TEMPORARY TREE PROTECTION FENCE NEAR REFORESTATION AREA. 4. CONTRACTOR SHALL PROVIDE SUPER SILT FENCE
- 4. CONTRACTOR SHALL PROVIDE SUPER SILT PENCE PROTECTION AROUND PROPOSED BIORETENTION PRIOR TO CONSTRUCTION ACTIVITIES TO PROTECT THE SOILS IN THAT AREA FROM COMPACTION.

TREE PROTECTION NOTES:

- I. REFER TO LF-0I TO LF-04 FOR TREE PROTECTION REQUIREMENTS, SEQUENCING, PLACEMENT, DETAILS, NOTES AND TREE TABLE.
- CONTRACTOR SHALL NOTIFY ARLINGTON COUNTY URBAN FORESTER 72 HOURS PRIOR TO INSTALLATION OF ANY TREE PRESERVATION MEASURES.
- 3. TREE PROTECTION MEASURES SHALL BE INSTALLED CONCURRENTLY, OR PRIOR TO, THE INSTALLATION OF THE E&S MEASURES. TREE PROTECTION SHALL BE INSPECTED/APPROVED BY ARLINGTON COUNTY ARBORIST.



A R L I N G T O N

DEPARTMENT OF PARKS AND RECREATION

Park Development Division 2100 Clarendon Boulevard, Suite 414 Arlington, VA 22201 Phone: 703.228.3332 Fax: 703.228.3328

21-DPR-ITB-646

Project Name and Location

Marcey Road Park Improvements (By Right)

(County Project)

2722 MARCEY ROAD ARLINGTON, VA 22207

Sheet Title

EROSION AND SEDIMENT CONTROL -PHASE I

100% Construction Drawings

Approval

Design Manager

Revisions

_____ _

Date


Date

Designed: AW Drawn: AMT Checked: SDT, JKS, MMW, CMB

Filename: c-05-150396024 erosion and sediment control phase i.dwg

Scale: I" = 20' Date: JUNE 2, 2021


Seal CHELSEA M. BISHOP Lic. No. 50030 JUNE 2, 2021 Sheet C - 05



EROSION AND SEDIMENT CONTROL LEGEND

10.	KEY	SYMBOL
		RPA
5.38	TP	LOD/TP
		LOW
5.02	CE	
.05	SSF	SSF
.05	SF	SF
.04	FL	FL-15
.07	IP	IP
.18	OP	

DESCRIPTION PROPERTY LINE RESOURCE PROTECTION AREA LIMITS OF DISTURBANCE/TREE PROTECTION FENCE (DETAIL 4/LF-03) LIMITS OF WORK 10'x40' MODIFIED CONSTRUCTION ENTRANCE WITH WASH RACK SUPER SILT FENCE



15" FILTER LOG

INLET PROTECTION

OUTLET PROTECTION (SEE SHEET C-I6)

DRAINAGE DIVIDE

- EROSION AND SEDIMENT CONTROL NOTES: WHERE SUPER SILT FENCE IS SHOWN ADJACNT TO TREE
- PROTECTION FENCE, THE FILTER FABRIC SHALL BE ADHERED TO THE TREE PROTECTION FENCE. 2. WHERE FILTER LOG IS SHOWN ADJACENT TO TREE
- PROTECTION FENCE, STAKE FILTER LOG DIRECTLY NEXT TO TREE PROTECTION FENCE.
- 3. TREE PROTECTION FENCE PROPOSED ALONG THE TENNIS COURT FENCE SHALL BE A SEPARATE TEMPORARY FENCE. 4. SEE LF-0I FOR INSTRUCTIONS ON PHASING/SEQUENCING OF TEMPORARY TREE PROTECTION FENCE NEAR
- REFORESTATION AREA. 5. CONTRACTOR SHALL MAINTAIN SUPER SILT FENCE PROTECTION AROUND PROPOSED BIORETENTION UNTIL UPSTREAM AREAS ARE STABILIZED AND FACILITY

TREE PROTECTION NOTES:

INSTALLATION BEGINS.

- REFER TO LF-0I TO LF-04 FOR TREE PROTECTION REQUIREMENTS, SEQUENCING, PLACEMENT, DETAILS, NOTES AND TREE TABLE.
- CONTRACTOR SHALL NOTIFY ARLINGTON COUNTY URBAN FORESTER 72 HOURS PRIOR TO INSTALLATION OF ANY TREE PRESERVATION MEASURES.
- TREE PROTECTION MEASURES SHALL BE INSTALLED CONCURRENTLY, OR PRIOR TO, THE INSTALLATION OF THE E&S MEASURES. TREE PROTECTION SHALL BE
- INSPECTED/APPROVED BY ARLINGTON COUNTY ARBORIST.



DEPARTMENT OF PARKS AND RECREATION

Park Development Division 2100 Clarendon Boulevard, Suite 414 Arlington, VA 22201 Phone: 703.228.3332 Fax: 703.228.3328

21-DPR-ITB-646

Project Name and Location

Marcey Road Park Improvements (By Right)

(County Project)

2722 MARCEY ROAD ARLINGTON, VA 22207

Sheet Title

EROSION AND SEDIMENT CONTROL -PHASE II

100% Construction Drawings

Approval

Design Manager

Revisions

Date

Date

Designed: AW Drawn: AMT Checked: SDT, JKS, MMW, CMB c-06-150396024 erosion and

Filename: sediment control phase ii.dwg Plotted: 2021-06-02

Scale: |" = 20' Date: JUNE 2, 2021

Seal CHELSEA M. BISHO UNAL JUNE 2, 2021 Sheet

C-06

EROSION AND SEDIMENT CONTROL NARRATIVE

PROJECT DESCRIPTION

TYPE OF DEVELOPMENT: RENOVATION OF A TENNIS COURT, BASKETBALL COURT, PARKING AND PATHS. THERE WILL BE AN INCREASE IN IMPERVIOUS AREA THEREFORE, A LEVEL I BIORETENTION FACILITY AND REFORESTATION WILL PROVIDE STORMWATER QUALITY AND QUANTITY MANAGEMENT IN ACCORDANCE WITH THE JANUARY 2013 DRAFT VERSION 2.0 SPECIFICATION 9 OF THE VIRGINIA DEQ DESIGN SPECIFICATIONS AND SUPPLEMENTED BY THE MARCH 2020 ARLINGTON COUNTY STORMWATER MANUAL

TOTAL AREA OF DISTURBANCE: 1.3056 ACRES

EXISTING SITE CONDITIONS

EXISTING SLOPES: 1-72%

OVERALL, IN BOTH THE PRE-DEVELOPED AND POST-DEVELOPED CONDITIONS, THE SITE DRAINS TO THE NORTHWEST

ADJACENT PROPERTIES NORTH: POTOMAC OVERLOOK REGIONAL PARK

EAST: POTOMAC OVERLOOK REGIONAL PARK SOUTH: DONALDSON RUN RECREATION ASSOCIATION WEST: POTOMAC OVERLOOK REGIONAL PARK

THERE IS NO PROPOSED CONSTRUCTION ON ADJACENT PROPERTIES.

GLENELG LOAM, 8 TO 15 PERCENT SLOPES; GLENELG-MANOR COMPLEX, 15 TO 35 PERCENT SLOPES;

THE SITE CONSISTS OF MOSTLY GLENELG LOAM AT VARYING SLOPES WITH GLENELG-MANOR COMPLEX SOIL IN THE NORTHERN PART OF THE SITE. GLENELG LOAM AND GLENELG-MANOR ARE HYDROLIGIC GROUP B SOILS.

CRITICAL EROSION AREAS

THERE IS A RESOURCE PROTECTION AREA WITHIN THE LIMITS OF DISTURBANCE. REFER TO THE WQIA NARRATIVE ON SHEET C-25 FOR A DETAILED DESCRIPTION OF THE PROPOSED EROSION AND SEDIMENT CONTROL MEASURES AND OTHER MITIGATION STRATEGIES.

EROSION AND SEDIMENT CONTROL MEASURES

PERMANENT OR TEMPORARY SOIL STABILIZATION MUST BE APPLIED TO DENUDED AREAS WITHIN 7 DAYS AFTER FINAL GRADE IS REACHED ON ANY PORTION OF THE SITE. SOIL STABILIZATION MUST BE APPLIED WITHIN 7 DAYS TO DENUDED AREAS WHICH MAY NOT BE AT FINAL GRADE BUT WILL REMAIN DORMANT (UNDISTURBED) FOR LONGER THAN 14 DAYS. ANY STOCKPILES MUST BE MULCHED AND SEEDED IMMEDIATELY AS DIRECTED BY THE COUNTY INSPECTOR. THERE ARE CRITICAL EROSION AREAS WITHIN THE LIMITS OF DISTURBANCE. SEDIMENT CONTROL WILL BE EXECUTED THROUGH THE INSTALLATION OF SILT FENCE, TREE PROTECTION AND INLET PROTECTION WITHIN THE LIMITS OF DISTURBANCE.

ALL TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES SHALL BE REMOVED WITHIN 30 DAYS AFTER FINAL SITE STABILIZATION OR AFTER TEMPORARY MEASURES ARE NO LONGER NEEDED.

STRUCTURAL PRACTICES

CONSTRUCTION ENTRANCE - 3.02

INSTALL A TEMPORARY CONSTRUCTION ENTRANCE WITH A WASH RACK OVERTOP THE EXISTING TRAIL AS SHOWN. THE EXISTING TRAIL SURFACE WILL REMAIN IN PLACE THROUGHOUT CONSTRUCTION. WASH ALL CONSTRUCTION VEHICLES LEAVING THE SITE AS NECESSARY TO ENSURE THAT SEDIMENT WILL NOT LEAVE THE SITE. DIRECT WASH WATER TO NEAREST SEDIMENT CONTROL DEVICE.

INSTALL SUPER SILT FENCE AND SILT FENCE BARRIER DOWNSLOPE OF AREAS WITH MINIMAL GRADES TO FILTER SEDIMENT-LADEN RUNOFF FROM SHEET FLOW. WHERE SUPER SILT FENCE IS SHOWN ADJACENT TO TREE PROTECTION FENCE, ADHERE SUPER SILT FABRIC DIRECTLY TO TREE PROTECTION FENCE.

TREE PRESERVAION & PROTECTION - 3.38 INSTALL TREE PROTECTION FENCING TO PROTECT TREES FROM MECHANICAL AND OTHER INJURY DURING LAND DISTURBING AND CONSTRUCTION ACTIVITY.

FILTER LOG - 3.04

INSTALL A 15" FILTER LOG BARRIER DOWNSLOPE OF AREA WITH MINIMAL GRADES TO FILTER SEDIMENT-LADEN RUNOFF FROM SHEET FLOW.

INLET PROTECTION - 3.07

INSTALL SEDIMENT FILTER OR AN EXCAVATED IMPOUNDING AREA AROUND A STORM DRAIN DROP INLET OR CURB INLET.

VEGETATIVE MEASURES

TOPSOILING (STOCKPILE) TOPSOIL WILL BE STRIPPED FROM AREAS TO BE GRADED AND STOCKPILED FOR LATER USE. STOCKPILE LOCATIONS ARE TO BE STABILIZED WITH TEMPORARY VEGETATION WITHIN 14 DAYS.

TEMPORARY SEEDING

DISTURBED AREAS THAT WILL NOT BE BROUGHT TO FINAL GRADE WITHIN A PERIOD OF 14 DAYS WILL HAVE TEMPORARY VEGETATION ESTABLISHED. TEMPORARY VEGETATION WILL REDUCE DAMAGE FROM SEDIMENT AND RUNOFF TO DOWNSTREAM AND OFF-SITE AREAS. TEMPORARY SEEDING PLANT MATERIAL SHALL BE RAPIDLY GROWING PLANTS SELECTED FROM VESCH STANDARD AND SPEC. 3.3I AND TABLE 3.3I-A&B. AREAS WHICH FAIL TO ESTABLISH VEGETATIVE COVER ADEQUATE TO PREVENT RILL EROSION ARE TO BE RESEEDED AS SOON AS POSSIBLE. FERTILIZER SHALL BE APPLIED AT A RATE OF 600 LBS. PER ACRE. FERTILIZER SHALL BE INCORPORATED INTO TOP 2-4 INCHES OF SOIL. SEED SHALL BE BE EVENLY APPLIED AND SMALL GRAINS SHALL BE PLANTED NO MORE THAN 1.5 INCHES DEEP. SEEDING MADE IN FALL FOR WINTER COVER AND DURING HOT AND DRY SUMMER MONTHS SHALL BE MULCHED ACCORDING TO SPEC 3.35.

3. <u>PERMANENT SEEDING</u>

IF SEEDING IS BEING USED, ALL AREAS DISTURBED BY CONSTRUCTION SHALL BE STABILIZED WITH PERMANENT SEEDING IMMEDIATELY FOLLOWING FINISHED GRADING. SEEDING SHALL BE DONE WITH KENTUCKY 3I TALL FESCUE ACCORDING TO MINIMUM STANDARD #3, VESCH SPEC. 3.32-A&B. EROSION CONTROL BLANKETS ARE TO BE INSTALLED OVER FILL SLOPES, WHICH HAVE BEEN BROUGHT TO FINAL GRADE AND HAVE BEEN SEEDED. THIS WILL PROTECT THE SLOPES FROM RILL AND GULLY EROSION AND ALLOW THE SEED TO GERMINATE PROPERLY. MULCH (STRAW OR FIBER) WILL BE USED ON RELATIVELY FLAT AREAS ACCORDING TO SPEC. 3.35. IN ALL SEEDING OPERATIONS, SEED, FERTILIZER AND LIME WILL BE APPLIED PRIOR TO MULCHING. SOIL TESTS SHOULD BE USED TO DETERMINE THE EXACT REQUIREMENTS FOR LIME AND FERTILIZER. THE PLANTING SOIL MUST HAVE ENOUGH FINE GRAINED SOIL, SUFFICIENT PORE SPACE, SUFFICIENT DEPTH AND BE FREE FROM TOXIC OR EXCESSIVE QUANTITIES OF ROOTS AND SHALL BE APPLIED IN ACCORDANCE WITH STD. 3.30.

5. SODDING

IF SOD IS BEING USED, AREAS THAT ARE TO BE SODDED SHALL BE BROUGHT TO FINAL GRADE IN ACCORDANCE WITH THE PLANS. SOIL TESTS SHOULD BE USED TO DETERMINE THE EXACT REQUIREMENTS FOR LIME AND FERTILIZER. PRIOR TO LAYING SOD, SOIL SURFACE SHALL BE CLEAR OF TRASH, DEBRIS, AND LARGE OBJECTS. QUALITY OF SOD SHALL BE STATE CERTIFIED AND ENSURE GENETIC PURITY AND HIGH QUALITY. SOD SHALL NOT BE LAID IN EXCESSIVELY WET OR DRY WEATHER AND BE DELIVERED AND INSTALLED WITHIN 36 HOURS. SOD SHOULD NOT BE LAID ON FROZEN SOIL SURFACE AND SHALL BE INSTALLED PER PLATE 3.33-I OF THE VESCH.

6. DUST CONTROL DUST SHALL BE MINIMIZED AS MUCH AS PRACTICABLE.

SEDIMENT CONTROL - SEQUENCE OF CONSTRUCTION NARRATIVE

SEQUENCE OF CONSTRUCTION - PHASE I

A. CONTRACTOR TO HAVE CONSTRUCTION WORKER PARKING, HAUL ROUTE, AND EXCAVATION PROTECTION PLAN

APPROVED BY ARLINGTON COUNTY. B. CONTRACTOR TO SUBMIT SEDIMENT DISPOSAL PLAN TO ARLINGTON COUNTY INSPECTOR FOR APPROVAL

INSTALL SUPER SILT FENCE (SSF), TREE PROTECTION (TP), FILTER LOG (FL), AND CONSTRUCTION ENTRANCE (CE). REFER TO LF SERIES SHEETS FOR TREE PROTECTION LOCATIONS, NOTES AND DETAILS. D. DEMOLISH AND REMOVE EXISTING CONCRETE, ASPHALT, BRICK, AND GAZEBO AS INDICATED ON THE DEMOLITION PLAN.

SEQUENCE OF CONSTRUCTION - PHASE 2

ALL SEDIMENT AND EROSION CONTROL DEVICES INSTALLED AS PART OF PHASE I SHALL REMAIN IN PLACE AND FUNCTIONING, UNLESS OTHERWISE DIRECTED BY THE INSPECTOR.

F. INSTALL TREES FOR REFORESTED AREA; REFER TO LF SERIES SHEETS FOR INSTALLATION DETAIL.

G. INSTALL SITE IMPROVEMENTS INCLUDING INSTALLATION OF LEVEL I BIORETENTION FACILITY, UTILITIES, UNDERDRAINS, STORM PIPES AND STRUCTURES, RETAINING WALLS, WALKS, ASPHALT PAVING, AND SITE FURNISHINGS. PERFORM FINAL GRADING. INSTALLATION OF THE BIORETENTION STONE, FILTER MEDIA AND MULCH SHALL BE

- COMPLETED AFTER ADJACENT AREAS HAVE BEEN PERMANENTLY STABILIZED.
- RESTORE AND STABILIZE DISTURBED AREAS.

REMOVE EROSION AND SEDIMENT CONTROL MEASURES WITH THE APPROVAL OF SITE INSPECTOR.

MAINTENANCE

A. ALL CONTROLS ARE TO BE INSPECTED ON A DAILY BASIS BY THE SITE SUPERINTENDENT OR HIS REPRESENTATIVE, ANY DAMAGED CONTROLS ARE TO BE REPAIRED BY THE END OF THE WORKING DAY. B. ALL CONSTRUCTION VEHICLES LEAVING THE SITE SHALL BE WASHED AS NECESSARY TO INSURE THAT SEDIMENT WILL NOT BE REMOVED FROM THE SITE. WASH WATER TO BE TRUCKED INTO THE SITE OR OBTAINED FROM A METERED WATER CONNECTION. WASH WATER TO BE DIRECTED TO A SEDIMENT TRAPPING DEVICE.

C. TO PREVENT CLOGGING, BLOCK AND GRAVEL INLET IS TO BE PROTECTED FROM DEBRIS AND CONSTRUCTION MATERIAL. CONTRACTOR TO COORDINATE WITH SITE INSPECTOR TO DETERMINE METHODOLOGY OF PROTECTION.

GENERAL EROSION AND SEDIMENT CONTROL NOTES

ES-I: UNLESS OTHERWISE INDICATED, ALL VEGETATIVE AND STRUCTURAL EROSION AND SEDIMENT CONTROL PRACTICES WILL BE CONSTRUCTED AND MAINTAINED ACCORDING TO THE MINIMUM STANDARDS AND SPECIFICATIONS OF THE VIRGINIA EROSION AND SEDIMENT CONTROL HANDBOOK AND VIRGINIA ADMINISTRATIVE CODE 9VAC25-840-40 EROSION AND SEDIMENT CONTROL REGULATIONS, MINIMUM STANDARDS.

PRIOR TO THE FINAL INSPECTION. IN CLEARING.

AT ALL TIMES. ES-5: PRIOR TO COMMENCING LAND DISTURBING ACTIVITIES IN AREAS OTHER THAN INDICATED ON THESE PLANS (INCLUDING, BUT NOT LIMITED TO, OFF-SITE BORROW OR WASTE AREAS), THE CONTRACTOR SHALL SUBMIT A SUPPLEMENTARY EROSION CONTROL PLAN TO THE OWNER FOR REVIEW AND APPROVAL BY THE

PLAN APPROVING AUTHORITY. AUTHORITY.

ES-7: ALL DISTURBED AREAS ARE TO DRAIN TO APPROVED SEDIMENT CONTROL MEASURES AT ALL TIMES DURING LAND DISTURBING ACTIVITIES AND DURING SITE DEVELOPMENT UNTIL FINAL STABILIZATION IS ACHIEVED.

ES-8: DURING DEWATERING OPERATIONS, WATER WILL BE PUMPED INTO AN APPROVED FILTERING DEVICE. ES-9: THE CONTRACTOR SHALL INSPECT ALL EROSION CONTROL MEASURES PERIODICALLY AND AFTER EACH RUNOFF-PRODUCING RAINFALL EVENT. ANY NECESSARY REPAIRS OR CLEANUP TO MAINTAIN THE EFFECTIVENESS OF THE EROSION CONTROL DEVICES SHALL BE MADE IMMEDIATELY.

PRE-STORM EROSION AND SEDIMENT CONTROL CHECKLIST PER EROSION AND SEDIMENT CONTROL GENERAL NOTE 6, THE CONTRACTOR IS RESPONSIBLE FOR THE INSTALLATION AND MAINTENANCE OF ANY ADDITIONAL EROSION AND SEDIMENT CONTROL (ESC) MEASURES NECESSARY TO PREVENT EROSION AND SEDIMENTATION AS DETERMINED BY THE COUNTY. THESE SUPPLEMENTARY PRACTICES ARE IN ADDITION TO THOSE SHOWN IN AN ESC PLAN. ESC PRACTICES SHALL BE MODIFIED AS NEEDED TO ENSURE ONLY CLEAR WATER IS DISCHARGED FROM THE SITE.

THE FOLLOWING ACTIONS SHALL BE TAKEN PRIOR TO STORM EVENTS WITH PREDICTED HEAVY AND/OR LARGE VOLUME RAINFALL TO PREVENT SEDIMENT DISCHARGES FROM A CONSTRUCTION SITE. A TYPICAL SUMMER THUNDERSTORM IS AN EXAMPLE OF A STORM EVENT WITH PREDICTED HEAVY AND/OR LARGE VOLUME RAINFALL.

PERIMETER CONTROLS POSTS OR STAKES MUST BE REPLACED. SEDIMENT FROM LEAVING THE CONSTRUCTION SITE.

EXPOSED SLOPES AND SOII AROUND THE DISTURBED AREA.

EXPOSED SLOPES AT THE FINAL STABILIZATION PHASE SHALL BE STABILIZED USING SLOPE STABILIZATION PRACTICES SUCH AS SOIL STABILIZATION BLANKETS OR MATTING AS SPECIFIED IN THE VIRGINIA EROSION AND SEDIMENT CONTROL HANDBOOK (VESCH) STD & SPEC 3.36. BLANKETS OR MATS MUST BE PROPERLY SECURED AND ANCHORED TO THE SLOPE USING STAPLES, PINS, OR STAKES SEEDED AREAS SHALL BE CHECKED AND RESEEDED AS NECESSARY TO COVER EXPOSED SOIL. RECENTLY SEEDED AREAS SHALL BE PROTECTED BY STRAW OR SOIL STABILIZATION BLANKETS TO PREVENT SEEDING FROM BEING WASHED AWAY.

STOCKPILES

STOCKPILED SOIL AND OTHER LOOSE MATERIALS THAT CAN BE WASHED AWAY SHALL BE COVERED WITH A TARP, PLASTIC SHEETING, OR OTHER STABILIZATION MATTING. THE COVER MUST BE PROPERLY SECURED / ANCHORED DOWN TO PREVENT IT FROM BEING BLOWN OFF AND EXPOSING MATERIALS TO RAIN. CONTROLS SUCH AS HAY BALES OR BOOMS SHOULD BE PLACED ALONG THE PERIMETER OF THE STOCK PILE (DOWNHILL SIDE).

INLET PROTECTION

INLET PROTECTION CONTROLS SHALL BE INSPECTED TO ENSURE THEY ARE FUNCTIONING PROPERLY AND FLOODING WILL NOT OCCUR. CLOGGED OR DAMAGED CONTROLS MUST BE REPLACED IMMEDIATELY. ENSURE CONTROLS ALLOW FOR OVERFLOW / BYPASS OF STORMWATER RUNOFF DURING SIGNIFICANT STORM EVENTS. IN ADDITION TO THESE PRE-STORM ACTIONS, ALL EROSION AND SEDIMENT CONTROL (ESC) MEASURES MUST BE CHECKED DAILY AND AFTER EACH SIGNIFICANT RAINFALL.

GENERAL LAND CONSERVATION NOTES AUTHORIZED BY THE DIRECTOR OR HIS AGENT. CONTROLS.

3. ALL STORM AND SANITARY SEWER LINES NOT IN STREETS ARE TO BE MULCHED AND SEEDED WITHIN 5 DAYS AFTER BACKFILL. NO MORE THAN 500 FEET ARE TO BE OPEN AT ANY ONE TIME. 4. ELECTRIC POWER, TELEPHONE AND GAS SUPPLY TRENCHES ARE TO BE COMPACTED, SEEDED AND MULCHED WITHIN 5 DAYS OF BACKFLLL

REQUIRED. THE SAME APPLIES TO ALL SOIL STOCKPILES.

AT THE COMPLETION OF THE CONSTRUCTION PROJECT AND PRIOR TO BOND RELEASE, ALL TEMPORARY SEDIMENT CONTROLS SHALL BE REMOVED AND ALL DENUDED AREAS SHALL BE STABILIZED. ARLINGTON COUNTY INSPECTOR TO APPROVE REMOVAL OF ALL TEMPORARY SILTATION MEASURES.

ES-2: THE PLAN APPROVING AUTHORITY MUST BE NOTIFIED ONE WEEK PRIOR TO THE PRE-CONSRTRUCTION CONFERENCE, ONE WEEK PRIOR TO THE COMMENCEMENT OF LAND DISTURBING ACTIVITY, AND ONE WEEK

ES-3: ALL EROSION AND SEDIMENT CONTROL MEASURES ARE TO BE PLACED PRIOR TO OR AS THE FIRST STEP ES-4: A COPY OF THE APPROVED EROSION AND SEDIMENT CONTROL PLAN SHALL BE MAINTAINED ON THE SITE

ES-6: THE CONTRACTOR IS RESPONSIBLE FOR THE INSTALLATION OF ANY ADDITIONAL EROSION CONTROL MEASURES NECESSARY TO PREVENT EROSION AND SEDIMENTATION AS DETERMINED BY THE PLAN APPROVING

□ SILT FENCE AND SUPER SILT FENCE SHALL BE CHECKED FOR UNDERMINING, HOLES, OR DETERIORATION OF THE FABRIC. FENCING SHALL BE REPLACED IMMEDIATELY IF THE FABRIC IS DAMAGED OR WORN. SILT FENCE MUST BE TRENCHED INTO THE GROUND PER STATE SPECIFICATIONS (STD & SPEC 3.09). WOODEN STAKES OR STEEL POSTS SHALL BE PROPERLY SECURED UPRIGHT INTO THE GROUND. DAMAGED

□ SEDIMENT THAT HAS ACCUMULATED AGAINST THE SILT FENCE SHOULD BE REMOVED. ACCUMULATED SEDIMENT MUST BE REMOVED WHEN THE LEVEL REACHES ONE-HALF THE HEIGHT OF THE FENCING. HAY BALES OR A STONE BERM SHOULD BE PLACED ACROSS THE CONSTRUCTION ENTRANCE TO PREVENT

EXPOSED SLOPES NOT AT THE FINAL STABILIZATION PHASE SHALL BE COVERED WITH TARPS, PLASTIC SHEETING, OR EROSION CONTROL MATTING. COVERING MATERIAL SHALL BE PROPERLY SECURED/ANCHORED □ CONTROLS SHALL BE INSTALLED TO PREVENT CONCENTRATED FLOW DOWN AN EXPOSED SLOPE. BERMS OR DIVERSION DIKES SHALL BE INSTALLED AT THE TOP OF CUT / EXPOSED SLOPES TO DIRECT STORM FLOW

NO DISTURBED AREA WILL REMAIN DENUDED FOR MORE THAN 7 CALENDAR DAYS UNLESS OTHERWISE 2. ALL EROSION AND SEDIMENT CONTROL MEASURES ARE TO BE PLACED PRIOR TO OR AS THE FIRST

STEP IN GRADING. FIRST AREAS TO BE CLEARED ARE TO BE THOSE REQUIRED FOR THE PERIMETER

5. ALL TEMPORARY EARTH BERMS, DIVERSIONS AND SEDIMENT CONTROL DAMS ARE TO BE MULCHED AND SEEDED FOR TEMPORARY VEGETATIVE COVER IMMEDIATELY AFTER GRADING. STRAW OR HAY MULCH IS

6. DURING CONSTRUCTION, ALL STORM SEWER INLETS WILL BE PROTECTED BY INLET PROTECTION DEVICES, MAINTAINED AND MODIFIED AS REQUIRED BY CONSTRUCTION PROGRESS.

7. ANY DISTURBED AREA NOT COVERED BY NOTE # I ABOVE AND NOT PAVED, SODDED OR BUILT UPON BY NOVEMBER IST, OR DISTURBED AFTER THAT DATE, SHALL BE MULCHED WITH HAY OR STRAW AT THE RATE OF 2 TONS PER ACRE AND OVER-SEEDED NO LATER THAN MAY 15TH.

TABLE 3.31-B (Revised June 2003) **TEMPORARY SEEDING SPECIFICATIONS** QUICK REFERENCE FOR ALL REGIONS

	SEED	
APPLICATION DATES	SPECIES	APPLICATIO
Sept. 1 - Feb. 15	50/50 Mix of Annual Ryegrass (lolium multi- florum) & Cereal (Winter) Rye (Secale cereale)	50 -100 (lb
Feb. 16 - Apr. 30	Annual Ryegrass (Iolium multi-florum)	60 - 100 (lk
May 1 - Aug. 31	German Millet	50 (Ibs/a

FERTILIZER & LIME

• Apply 10-10-10 fertilizer at a rate of 450 lbs. / acre (or 10 lbs. / 1,000 sq. ft.) • Apply **Pulverized Agricultural Limestone** at a rate of 2 tons/acre (or 90 lbs. / 1,000 sq. ft.)

NOTE:

1 - A soil test is necessary to determine the actual amount of lime required to adjust the soil pH of site. 2 - Incorporate the lime and fertilizer into the top 4 - 6 inches of the soil by disking or by other means. 3 - When applying Slowly Available Nitrogen, use rates available in Erosion & Sediment Control Technical Bulletin # 4, 2003 Nutrient Management for Development Sites at http://www.dcr.state.va.us/sw/e&s.htm#pubs

PERM	TABLE 3.32-D(Revised June 2003)ANENT SEEDING SPECIFICATIONS FOR PIED	DMONT AREA
	SEED ¹	
LAND USE	SPECIES	
<u>Minimum Care Lawn</u> (Commercial or Residential)	Tall Fescue ¹ Perennial Ryegrass Kentucky Bluegrass ¹ PEARL'S PREMIUM DEEP-ROOTED MIX ⁴	TOTAL: 1
High-Maintenance Lawn	Tall Fescue ¹	TOTAL: 20
General Slope (3:1 or less)	Tall Fescue ¹ Red Top Grass or Seasonal Nurse Crop ²	τοτα
I ow-Maintenance Slope	Tall Fescue ¹ Red Top Grass or Creeping Red Fescue	

Low-Maintenance Slope Seasonal Nurse Crop² (Steeper than 3:1) Crownvetch 1 - When selecting varieties of turfgrass, use the Virginia Crop Improvement Association (VCIA) recommended

turfgrass variety list. Quality seed will bear a label indicating that they are approved by VCIA. A current turfgrass variety list is available at the local County Extension office or through VCIA at 804-746-4884 or at http://sudan.cses.vt.edu/html/Turf/turf/publications/publications2.html

2 - Use seasonal nurse crop in accordance with seeding dates as stated belo	W:
February 16 th - April	Annual Rye
May 1 st - August 15 th	Foxtail Millet
August 16 th - October	Annual Rye
November - February 15 th	Winter Rye

B- Substitue Sericea lespedeza for Crownvetch east of Farmville, VA (May through September use hulled Sericea, all other periods, use unhulled Sericea). If Flat pea is used in lieu of Crown vetch, increase rate to 30lbs./acre. All legume seed must be properly inoculated. Weeping lovegrass may be added to any slope or low-maintenance mix during warmer seeding periods; add 10-20 lbs./acre in mixes.

FERTILIZER & LIME

• Apply 10-20-10 fertilizer at a rate of 500 lbs. / acre (or 12 lbs. / 1,000 sq. ft.) • Apply **Pulverized Agricultural Limestone** at a rate of 2 tons/acre (or 90 lbs. / 1,000 sq. ft.)

NOTE:


- A soil test is necessary to determine the actual amount of lime required to adjust the soil pH of site. - Incorporate the lime and fertilizer into the top 4-6 inches of the soil by disking or by other means. - When applying Slowly Available Nitrogen, use rates available in Erosion & Sediment Control Technical Bulletin # 4, 2003 Nutrient Management for Development Sites at http://www.dcr.state.va.us/sw/e&s.htm#pubs


TABLE 3.35-A

ORGANIC MULCH MATERIALS AND APPLICATION RATES


	RA	TES:	
MULCHES:	Per Acre	Per 1000 sq. ft.	NOTES:
Straw or Hay	1 ¹ / ₂ - 2 tons (Minimum 2 tons for winter cover)	70 - 90 lbs.	Free from weeds and coa matter. Must be anchore Spread with mulch blowe or by hand.
Fiber Mulch	Minimum 1500 lbs.	35 lbs.	Do not use as mulch for winter cover or during ho dry periods.* Apply as slurry.
Corn Stalks	4 - 6 tons	185 - 275 lbs.	Cut or shredded in 4-6" lengths. Air-dried. Do r use in fine turf areas. Ay with mulch blower or by hand.
Wood Chips	4 - 6 tons	185 - 275 lbs.	Free of coarse matter. A dried. Treat with 12 lbs nitrogen per ton. Do no use in fine turf areas. A with mulch blower, chip handler, or by hand.
Bark Chips or Shredded Bark	50 - 70 cu. yds.	1-2 cu. yds.	Free of coarse matter. A dried. Do not use in fine turf areas. Apply with mulch blower, chip hand or by hand.


* When fiber mulch is the only available mulch during periods when straw should be used, apply at a minimum rate of 2000 lbs./ac. or 45 lbs./1000 sq. ft.





SOURCE: Adapted from Installation of Straw and Fabric Filter Barriers for Sediment Control, PLATE. 3.05-1 Sherwood & Wyant





7-27-20

Department of Environmental Sevices 2100 Clarendon Boulevard, Suite 813

2722 Marcey Road

04-011-239

LDA-16261

-fter of

Aaron Wohler

Re: Erosion and Sediment Control Permit Application for:

I hereby certify that I accept the responsibilities of <u>Responsible Land Disturber</u> for the above referenced project. I understand

Reviewing the erosion and sedimentation (E&S) plan for the project.


- Walking the site prior to construction to identify critical areas. 3. Conducting a pre-construction briefing with earth moving and site contractors to present the E&S plan and
- highlight the presence of critical areas, the limits of clearing and the required E&S controls and tree protection measures to be installed. Call 703-228-0760 to schedule pre-construction meeting.
- 4. Regularily inspecting the site during construction to ensure that all E&S controls are functioning and are
- adequate to address erosion and sedimentation. Inspect the site 48 hours after a runoff-generating storm, and provide a copy of the inspection findings to the county.
- 5. Reporting to the owner the presence inadequate or non functioning E&S controls when they are observed. 6. Ensuring that temporary soil stabilization is applied within 7 days to areas denuded that will remain
- undisturbed for longer than 14 days. Permanent stabilization shall be applied to areas that are to be left dormant

for more than one year. 7. Calling (703) 228-0760 at least 80 hours before demolishing any structure.

_____ with questions about this plan or my execution of the duties of

Landscape Architect 1615 professional registration (type and number)

telephone number



PRIOR TO INSTALLATION, CLEAR ALL OBSTRUCTIONS INCLUDING ROCKS, CLODS, AND DEBRIS GREATER THAN ONE INCH THAT MAY INTERFERE WITH PROPER FUNCTION OF COIR FILTER LOG.


FILL LOG NETTING UNIFORMLY WITH COMPOST (IN ACCORDANCE WITH VIRGINIA DEQ MATERIALS SPECIFICATIONS), OR OTHER APPROVED BIODEGRADABLE MATERIAL TO DESIRED LENGTH SUCH THAT LOGS DO NOT DEFORM. . INSTALL COIR FILTER LOGS PERPENDICULAR TO THE FLOW DIRECTION AND PARALLEL TO THE SLOPE WITH THE BEGINNING


AND END OF THE INSTALLATION POINTING SLIGHTLY UP THE SLOPE CREATING A "J" SHAPE AT EACH END TO PREVENT 4. FOR UNTRENCHED INSTALLATION BLOW OR HAND PLACE MULCH OR COMPOST ON UPHILL SIDE OF THE SLOPE ALONG LOG.

5. STAKE FILTER LOG EVERY 4 FEET OR CLOSER ALONG ENTIRE LENGTH OF LOG OR TRENCH LOG INTO GROUND A MINIMUM OF 4 INCHES AND STAKE LOG EVERY 8 FEET OR CLOSER.


6. USE STAKES WITH A MINIMUM NOMINAL CROSS SECTION OF 2X2 INCH AND OF SUFFICIENT LENGTH TO ATTAIN A MINIMUM OF 12 INCHES INTO THE GROUND AND 3 INCHES PROTRUDING ABOVE LOG. WHEN MORE THAN ONE LOG IS NEEDED, OVERLAP ENDS 12 INCHES MINIMUM AND STAKE.

. REMOVE SEDIMENT WHEN IT HAS ACCUMULATED TO A DEPTH OF $\frac{1}{2}$ THE EXPOSED HEIGHT OF LOG AND REPLACE MULCH. REPLACE COIR FILTER LOG IF TORN. REINSTALL COIR LOG IF UNDERMINING OR DISLODGING OCCURS. REPLACE CLOGGED COIR LOGS. FOR PERMANENT APPLICATIONS, ESTABLISH AND CONTINUOUSLY MEET REQUIREMENTS FOR ADEQUATE VEGETATIVE ESTABLISHMENT IN ACCORDANCE WITH VIRGINIA VEGETATIVE STABILIZATION.






	TP	FENCE & GATES 4/L- PARKING SPACE 1/L-0.	NCE 4/LF-03
		AISLE 6/L-02 SHADE STRUCTURE A-01 - A-03	
		NATURE / PARK ACCES TRAIL - 3" NATURAL SHREDDED HARDWOOD STEPPER BLOCK STEPS TENNIS COURT PRACTICE WALL STORM DRAIN INFRAST SEE C-12, C-16 & I/L-0	MULCH
SITE FI		IINGS SCHEDULE	
SYMBOL			DETAIL
		ORLD`S FAIR BENCH	6/L-05
-	BIKE RACK (SURFACE MOUNT)		3/L-05
®	RECYCL	E RECEPTACLE	2/L-05
T	TRASH	RECEPTACLE	I/L-05
	PICNIC -	TABLE	4/L-05
ADA ADA	ADA PIC	NIC TABLE	4/L-05
		INKING FOUNTAIN DTTLE FILLER, VAULT PMENT	2/L-09
	1964 WC (BACKLE		I/L-06
		URTS SCHEDULE	
<u>SYMBOL</u>	SPORT (FIXTURE POLES T REPLAC HALIDE TOP FIT COMPON LED FIX ELECTR PLANS F	COURT LIGHT E RETROFIT. EXISTING FO REMAIN IN PLACE. E CURRENT METAL LIGHTS WITH NEW TER, ELECTRICAL IENTS, DRIVER AND TURES. SEE ICAL & LIGHTING FOR ADDITIONAL EMENTS.	<u>DETAIL</u> SHEETS E-0.1 THROUGH E5.2
⊜	SPORT (ELECTR	JTTON PEDESTAL FOR COURT LIGHTING. SEE ICAL PLANS FOR NAL INFORMATION.	2/E5.0 I/E5.0
	BASKET	BALL HOOP	4/L-06
0— · — · — · —0	TENNIS	COURT EQUIPMENT	3 L-06



N	4/L-04
	2/L-04
	I/L-04
	5/L-04
	6/L-04

DETAIL



		IREE PROTECTION FE LIMIT OF WORK (NO GROUND DISTURBANCE REFORESTATION AREA SEE SHEET REF-OI PARKING LOT FLUSH CURB L-02 CONCRETE PAVEMENT & SCORE JOINTS TENNIS SEGMENTAL BLOCK WALL CHAIN LINK FENCE ON CONCRETE CURB CHAIN LINK FENCE ON CONCRETE CURB CHAIN LINK FENCE & GATES PARKING SPACE BLOCK WALL	NCE 4/LF-03 E) A 7/L-05 6 L-02 1/L-01 2/L-01 6/L-01 3/L-01 1 L-07 -07 5/L-07 -07 2/L-08 02 2/L-02 02 6/L-02 SS MULCH	ARLENGTON, VA 22201 Project Name and Location Marcey Road Park By Right, County Project
	SITE F	URNISHINGS SCHEDULE		Sheet Title MATERIALS PLAN
	SYMBOL		DETAIL	
		1964 WORLD`S FAIR BENCH	6/L-05	100% Construction Drawings
		BIKE RACK (SURFACE MOUNT)	3/L-05	
	R	RECYCLE RECEPTACLE	2/L-05	
	\mathbf{T}	TRASH RECEPTACLE	I/L-05	
		PICNIC TABLE	4/L-05	
		ADA PICNIC TABLE	4/L-05	Approval Date
		ADA DRINKING FOUNTAIN WITH BOTTLE FILLER, VAULT & EQUIPMENT	2/L-09	Design Manager
		1964 WORLD`S FAIR BENCH (BACKLESS)	I/L-06	Revisions Date
		TIC COURTS SCHEDULE		
<u>DETAIL</u> 6/L-06 I/L-01	<u>SYMBOL</u>	DESCRIPTION SPORT COURT LIGHT FIXTURE RETROFIT. EXISTING POLES TO REMAIN IN PLACE. REPLACE CURRENT METAL HALIDE LIGHTS WITH NEW TOP FITTER, ELECTRICAL COMPONENTS, DRIVER AND LED FIXTURES. SEE ELECTRICAL & LIGHTING PLANS FOR ADDITIONAL REQUIREMENTS.	DETAIL SHEETS E-0.1 THROUGH E5.2	Designed: AW Drawn: AMT Checked: SDT, JKS, MMW, CMB Filename: c-10-150396024 materials plan.dwg
5/L-0I	⊜	PUSH BUTTON PEDESTAL FOR SPORT COURT LIGHTING. SEE ELECTRICAL PLANS FOR ADDITIONAL INFORMATION.	2/E5.0 I/E5.0	Plotted: 2021-06-02 Scale: I" = 20' Date: JUNE 2, 2021
		BASKETBALL HOOP	4/L-06	Seal
6/L-02	I o · · ·(• TENNIS COURT EQUIPMENT	3 L-06	MATTHEW M. WEIR Cert, No. 0406001961
4/L-02				JUNE 2, 2021


Sheet


C-10

	DETAIL
SIGN	4/L-04
	2/L-04
	I/L-04
١	5/L-04
Ν	6/L-04

CHEDULE	


4/L-02





		The
UTIL SYMBOL	ITY LEGEND DESCRIPTION	A R L I N G T O N
- RPA	 PROPERTY LINE RESOURCE PROTECTION AREA 	DEPARTMENT OF PARKS
LOD/TP	 LIMITS OF DISTURBANCE/TREE PROTECTION FENCE LIMIT OF WORK DEPOPOPOPULATE ELEPTRIC LARE (SEE ELOLITUDA ELO) 	AND RECREATION
- UGE	 PROPOSED UNDERGROUND ELECTRIC LINE (SEE E-0.1 THRU E5.2) EXISTING UNDERGROUND ELECTRIC LINE TO BE REUSED (SEE E-0.1 THRU E5.2) 	Park Development Division 2100 Clarendon Boulevard, Suite 414 Arlington, VA 22201
W	 WATER LINE 4" PERFORATED SCHD 40 PVC UNDERDRAIN 	Phone: 703.228.3332 Fax: 703.228.3328
0	4" SOLID SCHD 40 PVC UNDERDRAINMITERED DRAIN (SEE DETAILS 2 & 4/C-16)	21-DPR-ITB-646
•	6" CLEANOUT (SEE DETAIL I/C-I6) OUTLET PROTECTION (SEE DETAILS 2 & 4/C-I6)	Project Name and Location
•	OBSERVATION WELL (SEE DETAIL 5/C-16)	Marcey
•		Road Park
		Improvements
·		(By Right)
_	PARKING LOT 4 6 FLUSH CURB L-02 L-02	(County Project)
	CONCRETE PAVEMENT I/L-01 2/L-01 & SCORE JOINTS 6/L-01 3/L-01	2722 MARCEY ROAD ARLINGTON, VA 22207
۰ ــــــــــــــــــــــــــــــــــــ	TENNIS SEGMENTAL	Sheet Title
	ON CONCRETE CURB L-07 CHAIN LINK 3/L-07 5/L-07 FENCE & GATES 4/L-07 2/L-08	UTILITY PLAN
	PARKING SPACE 1/L-02 2/L-02 STRIPING WITH 4/L-02 6/L-02 WHEEL STOP	
	ADA ACCESS I/L-02 AISLE 6/L-02	
御 (1) (1) (1)	SHADE STRUCTURE A-0I - A-03	
	NATURE / PARK ACCESS TRAIL - 3" NATURAL	100% Construction Drawings
	SHREDDED HARDWOOD MULCH	
xxxxx	BLOCK STEPS L-02 TENNIS COURT 2 PRACTICE WALL L-03	
	STORM DRAIN INFRASTRUCTURE, SEE C-12, C-16 & I/L-03C	
		Approval Date
	IOTES:	Design Manager
	 TRENCH DRAIN CLEANING AND MAINTENANCE IS THE RESPONSIBILITY OF THE PARK AREA MANAGER, NOT OSEM. A MINIMUM OF 5 FEET COPPER LINE AND FITTINGS IS REQUIRED FROM THE METER TO THE DOMESTIC LINE 	Revisions Date
	CONNECTION. NO OTHER PIPE OR FITTING TYPES SHALL BE CONNECTED WITHIN THIS LOCATION.	· ·
		Designed: AW
		Drawn: AMT Checked: SDT, JKS, MMW, CMB
		Filename: c-12-150396024 utility plan.dwg Plotted: 2021-06-02
		Scale: " = 20' Date: JUNE 2, 2021
		Seal
		NOTWEALTH OF VIR
		CHELSEA M. BISHOP
		Lic. No. 50030
		JUNE 2, 2021
		Sheet
		C-12

_ _ _



		PROPOSE	DS	ITE LE	GEND	
					TATION AREA ET REF <u>-01</u>	7/L-05
				PARKING FLUSH C	LOT 4 URB L-02 L	$\frac{6}{1-02}$
				CONCRE ⁻ & SCORE		/L-0 2\L-0 6/L-0 3/L-0
		• • •			SEGMENTAL	$\left(\frac{1}{L-03}\right)$
			•	CHAIN LI	NK FENCE	
				CHAIN LI	NK 3/L-	07 07 5/L-07
				FENCE &	SPACE 1/1-02	07 2/L-08 2 2/L-02
				STRIPING WHEEL S	STOP 4/2 02	2 6/L-02
				ADA ACC AISLE	ESS 1/L-02 6/L-02	
				SHADE STRUCTI	IRF	
				A-01 - A-		
				TRAIL -	/ PARK ACCES 3" NATURAL	
				SHREDDE	5 HARDWOOD	MULCH
				BLOCK S	TEPS L-02	
			******	TENNIS (PRACTIC	E WALL L-03	
			Ċ,		PRAIN INFRAST , C-16 & 1/L-0	
		STIE FUR			CHEDULE	DETAIL
					IR BENCH	6/L-05
			KE RA DUNT)	.CK (SURF	ACE	3/L-05
		® RE	CYCLI	E RECEPT	ACLE	2/L-05
		TF	RASH F	RECEPTAC	CLE	I/L-05
			CNIC 1	TABLE		4/L-05
			DA PIC	NIC TABL	E	4/L-05
		W		OTTLE FIL	UNTAIN LER, VAULT	2/L-09
			64 WC ACKLE		IR BENCH	I/L-06
		GRADING	LE(GEND		
					D MINOR CON D MAJOR CON	
		ADA SCH	EDU	<u>LE</u>		
				ADA ACO ENTRY F	CESSIBLE PARP OINT	Κ
				ADA ACC	CESSIBLE SEAT	ΓING
		>		ADA ACC	CESSIBLE ROUT	TE
				END OF	ADA ACCESSIE	BLE ROUTE
				ADA ACC	CESSIBLE LANI	DING
Ī	THAT ALL E VERSION OF OF JUSTICE INSTALLATIO	LEMENTS ARE ADA STANDAF E. SHOULD A DN, OR IF ANY ACT THE PRO	CONS RDS FO ANY CLAF JECT	STRUCTED OR ACCES QUESTION RIFICATIO OFFICER.	IN ACCORDAN SIBLE DESIGN, IS ARISE DU NS ARE NEED	NSIBLE FOR ENSURING ICE WITH THE LATEST , BY THE DEPARTMENT RING CONSTRUCTION, ED, THE CONTRACTOR S.
	PARK AG	CESSIBIL	ITY	TABUL	ATION	
	ACCESSIBLE QUANTITY	TOTAL QUANTITY	ACC	% ESSIBLE	NOTES	
	8	12		66%		
,	4	4		100%		
Ν	I	I		100%		
	I	I		100%		
	I ACCESSIBLE					
	(WITH I ADA TABLE EXTENSION/ PAD)	3 tables		33%		

FEATURE/ COMPONENT/ ELEMENT

BENCHES

TRASH/RECYCLING (PAIRS)

DRINKING FOUNTAIN (DOUBLE)

PICNIC SHELTER

PICNIC TABLES

SPORT COURTS

SPORTS COURT LIGHTING PUSH BUTTON 2

2


2

2


100%

100%

DEPARTMENT OF PARKS AND RECREATIONDEPARTMENT OF PARKS AND RECREATIONPark Development Division 2100 Clarendon Boulevard, Suite 414 Arlington, VA 22201 Phone: 703.228.3332 Eax: 703.228.3328
21-DPR-ITB-646 Project Name and Location Marcey Road Park Improvements (By Right) (County Project) 2722 MARCEY ROAD ARLINGTON, VA 22207
Sheet Title ADA ACCESS PLAN 100% Construction Drawings
Approval Date
Design Manager
Design Manager
Design Manager Revisions Date
Design Manager Revisions Date




	001
TA:	STATI
FF:	OFFSE
_#:	BASEL
#:	LINE 7
#:	CURVE
Q:	EQUAL
R:	POB:
ON:	UNLES
P:	END P
₽:	BEGIN



Path: X:\Rockville\15-0396.024 - Marcey Road Park\05-CAD\

Filename: C-14-150396024 Layout Plan.dwg



P = 6.74' H = 0.25' Q = 2.78 CFS


H = 0.25'

Q = 4.53 CFS

$$P = 8.61^{\circ}$$


 $H = 0.25^{\circ}$

Q = 3.55 CFS



```
Path: X:\Rockville\15-0396.024 - Marcey Road Park\05-CAD\
```


Filename: C-17-150396024.dwg



		EXIS
		MATERIAL
PRE-DEVELOF	MENT WATER QUALITY LEGEND	CONCRETE PAVING
LOD/TP	LIMITS OF DISTURBANCE/TREE PROTECTION FENCE - 56,871 SF (1.3056 AC)	WALL
RPA	RESOURCE PROTECTION AREA	ASPHALT
	PROPERTY LINE	TOTAL AREA
LOW	LIMITS OF WORK	
	MANAGED TURF - 29,671 SF (0.6812 AC)	

IST	ING IMPERVIOUS	AREAS
	SURFACE AREA (SF)	LEGEND
ING	1,170	
	230	
	25,800	
	27,200 (0.6244 AC)	


	0.11
A R L I N G T	U N
DEPARTMENT OF PA AND RECREATIO	N
Park Development Divisio 2100 Clarendon Boulevard, Sui Arlington, VA 22201 Phone: 703.228.3332 Fax: 703.228.3328	
21-DPR-ITB-	646
Project Name and Locat	ion
Road Park	
Improvem	ents
(By Right) (County Project)	
2722 MARCEY ROA ARLINGTON, VA 22	
Sheet Title	
PRE-	
DEVELOPM WATER	ENT
QUALITY M	AP
100% Construction Dra	wings
Approval	Date
Approval Design Manager	Date
	Date Date
Design Manager	
Design Manager	
Designed: AW Drawn: AMT Checked: SDT, JKS, MMW,	Date
Designed: AW Drawn: AMT	Date
Design Manager Revisions Designed: AW Drawn: AMT Checked: SDT, JKS, MMW,	Date
Design Manager Revisions Designed: AW Drawn: AMT Checked: SDT, JKS, MMW, c-18-150396024 Filename: pre-development Plotted: 2021-06-02 Scale: 1" = 20'	Date
Design Manager Revisions Designed: AW Drawn: AMT Checked: SDT, JKS, MMW, C-18-150396024 Filename: pre-development Plotted: 2021-06-02 Scale: 1" = 20' Date: JUNE 2, 2021 Seal CHELSEA M. BISHOP Lic. No. 50030 CHELSEA M. BISHOP	Date
Design Manager Revisions Designed: AW Drawn: AMT Checked: SDT, JKS, MMW, <u>c-18-150396024</u> Filename: pre-development guality map.dwg Plotted: 2021-06-02 Scale: 1" = 20' Date: JUNE 2, 2021 Seal CHELSEA M. BISHOP	Date




POST-DEVELC	PMENT WATER QUALITY LEGEND	
LOD/TP	LIMITS OF DISTURBANCE/TREE PROTECTION FENCE - 56,871 SF (1.3056 AC)	
RPA	RESOURCE PROTECTION AREA	
	PROPERTY LINE	
LOW	LIMITS OF WORK	
	MANAGED TURF - 19,505 SF (0.4478) AC)	

PROPOSED IMPERVIOUS AREAS					
MATERIAL	<u>SURFACE AREA (SF)</u>	<u>LEGEND</u>			
CONCRETE PAVING	4,892				
WALL	269				
ASPHALT PAVING	25,675				
TOTAL AREA	30,836 (0.7079 AC)				

A R L I N G T O N
DEPARTMENT OF PARKS
AND RECREATION Park Development Division 2100 Clarendon Boulevard, Suite 414
Arlington, VA 22201 Phone: 703.228.3332 Fax: 703.228.3328
21-DPR-ITB-646
Project Name and Location Marcey
Road Park Improvements
(By Right)
(County Project) 2722 MARCEY ROAD ARLINGTON, VA 22207
Sheet Title
POST- DEVELOPMENT
WATER QUALITY MAP
100% Construction Drawings
Approval Date
Design Manager
Design Manager
Design Manager Revisions Date
Design Manager Revisions Date
Design Manager Revisions Date
Design Manager Revisions Date
Design Manager Revisions Date
Design Manager Revisions Date
Design Manager Revisions Date



STORMWATER MANAGMENT LEGEND



DESCRIPTION PROPERTY LINE RESOURCE PROTECTION AREA

LIMITS OF DISTURBANCE/TREE PROTECTION FENCE

BMP DRAINAGE DIVIDE

REFORESTED AREA - 6,530 SF (0.1499 AC)

BIORETENTION FACILITY (LEVEL I)



A R L I N G T O N

DEPARTMENT OF PARKS AND RECREATION

Park Development Division 2100 Clarendon Boulevard, Suite 414 Arlington, VA 22201 Phone: 703.228.3332 Fax: 703.228.3328

21-DPR-ITB-646

Project Name and Location

Marcey Road Park Improvements (By Right)

(County Project)

2722 MARCEY ROAD ARLINGTON, VA 22207

Sheet Title

STORMWATER MANAGEMENT PLAN

100% Construction Drawings

Approval

Design Manager

Revisions

Date

Date

Designed: AW Drawn: AMT Checked: SDT, JKS, MMW, CMB

Filename: c-20-150396024 swm plan.dwg Plotted: 2021-06-02

Scale: |" = 20' Date: JUNE 2, 2021

Seal



C-20

WATER QUALITY NARRATIVE THE SITE IS DEFINED BY THE TOTAL APPLICABLE AREA WITHIN THE LIMITS OF DISTURBANCE OF 1.3056 ACRES. THE IMPERVIOUS AREA FOR THE EXISTING CONDITION IS 0.6244 ACRES (47.8%) AND 0.7079 ACRES (54.2%) FOR THE PROPOSED CONDITION. DUE TO THE INCREASE IN IMPERVIOUS AREA THERE IS A 0.4137 LB/YEAR PHOSPHOROUS LOAD REDUCTION REQUIRED. TO MEET COUNTY AND STATE REQUIREMENTS FOR WATER QUALITY, THE PLANS PROPOSE A LEVEL I BIORETENTION FACILITY AND REFORESTATION. REFER TO SHEET REF-01 FOR REFORESTATION INFORMATION. THE PROPOSED STORMWATER MANAGEMENT FACILITY PROVIDES A TOTAL OF 0.5716 LB/YR. THE TOTAL PHOSPHORUS REDUCTION PROVIDED IS MET AND EXCEEDED BY 0.1579 LB/YR. THE FACILITY IS DESIGNED IN ACCORDANCE TO THE JANUARY 2013 DRAFT VERSION 2.0 SPEC 9 OF THE VIRGINIA DEQ DESIGN SPECIFICATIONS SUPPLEMENTED BY THE MARCH 2020 ARLINGTON COUNTY STORMWATER MANUAL.

Project Name:	Marcy Road Park	CLEAR ALL	data input cells
Date:	10/13/2020	(Ctrl+Shift+R)	constant values
	Linear Development Project? No		calculation cells
Site Information			final results

Post-Development Project (Treatment Volume and Loads)

					r	3	
		Enter	Total Disturbed	Area (acres) →	1.3056	Check:	
						BMP Design Specifications List:	2013 D
			Maximum r	eduction required:	20%	Linear project?	No
	Т	he site's net inc	rease in impervio	us cover (acres) is:	0.0835	Land cover areas entered correctly?	~
				ion for Site (lb/yr):		Total disturbed area entered?	~
Pre-ReDevelopment Land Cover (a	acres)						
	A Soils	B Soils	C Soils	D Soils	Totals]	
Forest/Open Space (acres) undisturbed					0.0000		
forest/open space					0.0000		
Managed Turf (acres) disturbed, graded					0.6812		
for yards or other turf to be		0.6812			0.0012		
Impervious Cover (acres)		0.6244			0.6244		
					1.3056	I	
Post-Development Land Cover (ac	res)					-	
	A Soils	B Soils	C Soils	D Soils	Totals	1	
Forest/Open Space (acres) undisturbed,					0.1499]*	
protected forest/open space or reforested		0.1499			0.1499		
Managed Turf (acres) disturbed graded							

* Forest/Open Space areas must be protected in accordance with the Virginia Runoff Reduction Method					
Area Check	OK.	OK.	OK.	OK.	1.3056
Impervious Cover (acres)		0.7079			0.7079
for yards or other turf to be		0.4478			0.4478
Managed Turf (acres) disturbed, graded					
protected forest/open space or reforested		0.1499			

С	C	or	15	t	a	n	t	s	
					0			6 11	1

Annual Rainfall (inches)	43
Target Rainfall Event (inches)	1.00
Total Phosphorus (TP) EMC (mg/L)	0.26
Total Nitrogen (TN) EMC (mg/L)	1.86
Target TP Load (Ib/acre/yr)	0.41
Pj (unitless correction factor)	0.90

	A Soils	B Soils	C Soils	D Soils
Forest/Open Space	0.02	0.03	0.04	0.05
Managed Turf	0.15	0.20	0.22	0.25
Impervious Cover	0.95	0.95	0.95	0.95

LAND COVER SUMMARY -- PRE-REDEVELOPMENT

Land Cover Summary-Pre				
Pre-Re Development	Listed	Adjusted ¹		
Forest/Open Space Cover (acres)	0.0000	0.0000		
Weighted Rv(forest)	0.0000	0.0000		
% Forest	0%	0%		
Managed Turf Cover (acres)	0.6812	0.5977		
Weighted Rv(turf)	0.2000	0.2000		
% Managed Turf	52%	49%		
Impervious Cover (acres)	0.6244	0.6244		
Rv(impervious)	0.9500	0.9500		
% Impervious	48%	51%		
Total Site Area (acres)	1.3056	1.2221		
Site Rv	0.5587	0.5832		
Treatment Volume and Nutrient Load				

reautient volume and Nutient Load				
Pre-ReDevelopment Treatment Volume (acre-ft)	0.0608	0.0594		
Pre-ReDevelopment Treatment Volume (cubic feet)	2,647.7946	2,587.1736		
Pre-ReDevelopment TP Load (lb/yr)	1.6636	1.6255		
Pre-ReDevelopment TP Load per acre (lb/acre/yr)	1.3300			
Baseline TP Load (lb/yr) (0.41 lbs/acre/yr applied to pre-redevelopmen	0.5011			

Land Cover Summa	ry-Post (Final)		Land Cover Sum	mary-Post		Land Cover Sum	nary-P
Post ReDev. & New	w Impervious		Post-Re Deve	lopment		Post-Development No	ew Imp
Forest/Open Space Cover (acres)	0.1499		Forest/Open Space Cover (acres)	0.1499			
Weighted Rv(forest)	0.0300		Weighted Rv(forest)	0.0300	1		
% Forest	11%		% Forest	12%			
Managed Turf Cover (acres)	0.4478		Managed Turf Cover (acres)	0.4478			
Weighted Rv (turf)	0.2000		Weighted Rv (turf)	0.2000			
% Managed Turf	34%		% Managed Turf	3 7 %			
Impervious Cover (acres)	0.7079		ReDev. Impervious Cover (acres)	0.6244		New Impervious Cover (acres)	0
Rv(impervious)	0.9500		Rv(impervious)	0.9500	1	Rv(impervious)	0
% Impervious	54%		% Impervious	51%			
Final Site Area (acres)	1.3056		Total ReDev. Site Area (acres)	1.2221			
Final Post Dev Site Rv	0.5871		Re Dev Site Rv	0.5623			
		Treatr	nent Volume and	d Nutrient Lo	ad		
Final Post- Development Treatment Volume (acre-ft)	0.0639		Post-ReDevelopment Treatment Volume (acre-ft)	0.0573		Post-Development Treatment Volume (acre-ft)	0
Final Post- Development Treatment Volume (cubic feet)	2,782.6201		Post-ReDevelopment Treatment Volume (cubic feet)	2,494.6703		Post-Development Treatment Volume (cubic feet)	28
Final Post- Development TP Load (lb/yr)	1.7483		Post-ReDevelopment Load (TP) (Ib/yr)*	1.5674		Post-Development TP Load (lb/yr)	0
Final Post-Development TP Load per acre (lb/acre/yr)	1.3400		Post-ReDevelopment TP Load per acre (Ib/acre/yr)	1.2800			
			Max. Reduction Required (Below Pre- ReDevelopment Load)	20%			
			TP Load Reduction Required for Redeveloped Area	0.2670		TP Load Reduction Required for New Impervious Area	0.

(lb/yr)

LAND COVER SUMMARY – POST DEVELOPMENT

Check: BMP Design Specifications List: 2013 Draft Stds & Specs Linear project? No

¹Adjusted Land Cover Summary:

Pre ReDevelopment land cover minus pervious land cover (forest/open space or managed turf) acreage proposed for new impervious cover.

Adjusted total acreage is consistent with Post-ReDevelopment acreage (minus acreage of new impervious cover).

Column I shows load reduction requriement for new impervious cover (based on new development load limit, 0.41 lbs/acre/year).

	TP Load	Reduction Required (lb/yr)	0.4137		
	Nit	rogen Loads (Informational Pur	poses Only)		
Pre-ReDevelopment TN Load	11.9012		Final Post-Development TN Load (Post-Re Development & New	12.5072	
(lb/yr)			Impervious) (lb/yr)		
					Facility Type**
				l	Facility Type
					BIORETENTION #1

Drainage Area A Drainage Area A Land Cover (acres)			CLEAR BMP ARI	AS		WATER QU	ANTITY N	ARRATIVE		
Forest/Open Space (acres)	0.1499	D Soils Totals Land Cover Rv 0.1499 0.0300			×	PROVIDED BY THE BIO	ORETENTION FACILI	TY. PER THE ARLING	MPLISHED BY THE RUNOFF TON COUNTY CODE, CHAPT	ER 60,
Manage d'Turf (acres) Impervious Cover (acres)	0.4478 0.7079	0.4478 0.2000 0.7079 0.9500 Total 1.3056		e for Removal in D.A. A (lb/yr) eatment Volume in D.A. A (ft³)	1.7381 2,766.2960	DEVELOPED SITE SHA 10-YEAR 24-HOUR PEA			UFFICIENT TO PASS THE I- BALANCE METHOD.	-YEAR
Stormwater Best Manage	ment Practices (RR = Runoff Reduction		Phosphorus	Intreated	-Select from dropdown lists	THE TOTAL APPLICAE	BLE AREA (LIMITS (F DISTURBANCE) IS I.	.3056 ACRES.	
Practice	s i	ostream Reduction Runoff Tre	eatment Removal Upstream Load	hosphorus	Remaining Phosphorus Load (lb)	RUNOFF COMPUTATIC	ONS FOR THE SITE N	VERE DEVELOPED TO	DSHEET, PRE- AND POST-D ESTABLISH ALLOWABLE RE	ELEASE
6. Bioretention (RR) 6.a. Bioretention #1 or Micro-Bioretention # or Urban Bioretention (Spec #9)	^{#1} 40 0.1978 0.4386 0	0.0000 662.4460 993.6689 1,	656.1149 25 0.0000	1.0394 0.5716	0.4677) 4.48 CFS, RESPECTFULLY LESS THAN THE ALLOWAE	
	Si	te Results (Water Qu	uality Compliance)	I I	, i	BASED ON CHAPTER			OOK AND THE ARLINGTON	ENERG
	Area Chec			D.A. E	AREA CHECK	WORKSHEET, SHOWN) BE PROVIDED. OPOSED WITH THIS APPLIC.	ΔΤΙΟΝ
	FOREST/OPEN SPACE (IMPERVIOUS COVER (0.0000	<u>ок.</u> ок.	NO ADVERSE IMPACT	TO THE ADJACENT			
	IMPERVIOUS COVER TREATED (MANAGED TURF AREA (0.0000	ок. ок.	SWM Water Quantity Energy Balan				
	MANAGED TURF AREA TREATED (AREA CHEC		0.0000 0.0000 OK. OK.	0.0000 OK.	ОК.	SITE AREA (acre)	1.3056 1 PRE	-year POST (adjusted)	10-year PRE	POST
	Site Treatment Volume (f	(t³) 2,782.6201				P CN	2.62 79	2.62 77	4.87	1001
Runoff Reduction	Volume and TP By Drainage Ar	rea				S=1000/CN-10 0.2S	2.66 0.53	2.99 0.60	2.66 0.53	
RI	UNOFF REDUCTION VOLUME ACHIEVED (D.A. A D.A. B (ft³) 662.4460 0.0000		D.A. E 0.0000	TOTAL 662.4460	RV=(P-0.2S) ² /(P-0.2S)+S	0.92	0.82	2.69	
	TP LOAD AVAILABLE FOR REMOVAL (Ib/ TP LOAD REDUCTION ACHIEVED (Ib/	/yr) 1.7381 0.0000	0.0000 0.0000	0.0000	1.7381 0.5716			pre-development* RVpre-de	evelopment)/RVDeveloped)	
	TP LOAD REMAINING (Ib/		0.0000 0.0000	0.0000	1.1664	I.F CHANNEL PRO			FLOOD CONTI	ROL
NITR	OGEN LOAD REDUCTION ACHIEVED (Ib/	/yr) 4.7586 0.0000	0.0000 0.0000	0.0000	4.7586	Qpre-development QPost Development RVPost Development (with	1.49 1.31	From TR55 From TR55	Qpre-development QPost Development RVPost Development (with	
F	Total Phosphoru INAL POST-DEVELOPMENT TP LOAD (Ib/					runoff reduction) Qallowable	0.8330 1.31	From RRM	runoff reduction) Qallowable	2
	TP LOAD REDUCTION REQUIRED (Ib/ TP LOAD REDUCTION ACHIEVED (Ib/	/yr) 0.5716				Qallowable/QPost Development	1.00	Fig 11.7 of DEQ Manual	Qallowable/QPost Development	
REMAINI	TP LOAD REMAINING (Ib/ NG TP LOAD REDUCTION REQUIRED (Ib/	201, 22				Vs/Vr Vs Storage required (cf)	0.00		Vs/Vr Vs Storage required (cf)	
	Rur	noff Volume and Curve								
		Enter design storm rair								
		1-year storm 2-year sto 2.62 3.17	rm 10-year storm 4.87							
		Use NOAA Atlas 14 (http://hdsc.r	nws.noaa.gov/hdsc/pfds/)							
	rs and runoff volumes computed in this spreads		in their applicability for determining and de	monstrating compliance with	water quantity					
	RRM User's Guide and Documentation for additi V) for pre- and post-development drainage area		e-feet or cubic feet) when using the Energy I	Balance Equation. Runoff mea	asured in watershed-					
	the spreadsheet as RV(watershed-inch) can onl lied by the drainage area.	y be used in the Energy Balance Equation	on when the pre- and post-development dra	nage areas are equal. Otherv	wise RV(watershed-					
[3] Adjusted CNs are	based on runoff reduction volumes as calculate	d in D.A. tabs. An alternative CN adjust:	ment calculation for Vegetated Roofs is inc	uded in BMP specification No	p. 5.					
	Dra	ainage Area Curve Numbe	rs and Runoff Depths*							
			are computed with and without i	eduction practices.						
Forest/Open Spa	ainage Area A ace undisturbed, protected Area (acre	A Soils B Soils res) 0.0000 0.1499	C Soils D Soils 0.0000 0.0000	Total Area (acre Runoff Reductio	on					
Managed Turf dis	space or reforested land CN turbed, graded for yards or other Area (acre be mowed/managed CN	30 55 es) 0.0000 0.4478 39 61	70 77 0.0000 0.0000 74 80	Volume (ft	³): 662.4460					
	npervious Cover CN CN		74 80 0.0000 0.0000 98 98							
			CN _(D.A. A) 80	Ι						
RV _{Developed}	(watershed-inch) with no Runoff Reduct	1-year storm 2-year storm tion* 0.9728 1.3789	m 10-year storm 2.7798							
	_{oped} (watershed-inch) with Runoff Reduct Adjusted C	tion* 0.8330 1.2391 CN* 77 78	2.6400 78							
	*See Notes al	ove								
			Site Inf	ormation - Revis	sed 9/19/2017					
		Pre- Post- TP loa						Runoff		
		Develop Develop reduct ment TP ment TP n	tio Develop Develop reduct ment TN ment TN n	tio Pre-		Post- Post- Forest Post-Turf Impervio		Volume Site	Site	

				Distance	/011C-	///////////////////////////////////////	mene n	inche in		inche in			Total Site	TUICSE	i i c-i uni pi	mpervio	TOICSL	I Ost-Turi	mpervio		1031-	neudeati	Latituac	LOUBILU			
		Project	LDA	d Area	Impervio	Impervio	load	load	achieved	load	load a	achieved	Area	Area	Area	us Area	Area	Area	us Area	Runoff	Runoff	on	(Decimal	(Decim	al ed Start		
		SWM #	Permit #	(acres)	us	us	(lb/yr)	(lb/yr)	(lb/yr)	(lb/yr)	(lb/yr)	(lb/yr)	(acres)	(acres)	(acres)	(acres)	(acres)	(acres)	(acres)	Volume	Volume	Achieved	Degrees)	Degree	s) Date		
		20-0172	LDA20158	1.3056	47.8	54.2	1.66	1.75	0.57	11.90	12.51	4.76	1.3056	0.0000	0.6812	0.6244	0.1499	0.4478	0.7079	2647.7946	2782.6201	662.4460	38.911102	-77.1087	81 TBD		
										·			·		·	·		•		·				-			
								-			12				/												
		-			-			S	tormwa	ter Man	agement	Facility	Informa	ition-Re	vised 5/3	31/2018	<u> </u>			<u> </u>	<u> </u>			.			
						BMP d	lownstream	n of Upst	ream					Runo	ff Volum	ne Treate	ed Fore	est								TP load	TN load
		LDA	Project	Buildin	g	ano	ther BMP (in (Prir	mary) Ch	e sapeake				Treate	d Treate	d Area	a Are	a Turf A	rea Imp	ervious		Phosphoru	s Nitro	ogen	Sediment	removed	removed
Description	Location	Permit #	SWM#	Permit	# Facility	ID	Series)?	B	MP Ba	y Segment	Watershe	ed HUC	6 Soils	s (in)	(ft ³)	(acres	s) (acr	es) (acre	es) Area	a (acres)	RPC	Efficiency (%	6) Efficier	ncy (%) E	fficiency (%)	(lbs)	(lbs)
	North of						•												-				-				
	Tennis										Donaldsor	n															
		LDA 2015	8 20-0172	2	20-017	2A	No		PO	TTF VA	Run	PL2	4 A/B	1.00	1656.	1 0.636	64 0.00	000 0.19	78 0	.4386 0	4011239	55.00	64.	.00	75.00	0.57	4.76
		20112010		-				I					. ,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,	1.00	2000.	- 0.000	0.00	0.10			.011100	23.00				0.07	

0.146

(lb/yr)

T ARLINGTON VIRGINIA

DEPARTMENT OF PARKS AND RECREATION

Park Development Division 2100 Clarendon Boulevard, Suite 414 Arlington, VA 22201 Phone: 703.228.3332 Fax: 703.228.3328

21-DPR-ITB-646

Project Name and Location

Marcey Road Park Improvements (By Right)

(County Project)

2722 MARCEY ROAD ARLINGTON, VA 22207

Sheet Title

STORMWATER MANAGEMENT NARRATIVE & CALCULATIONS

100% Construction Drawings

<u>۸</u> –	- r	~	<i>(</i> -)
Ap	РΓ	0	/ CII

Design Manager

Revisions

Date


Date

Designed: AW Drawn: AMT Checked: SDT, JKS, MMW, CMB


Filename: c-20-150396024 swm plan.dwg Plotted: 2021-06-02

Scale: N.T.S. Date: JUNE 2, 2021





									· · · · · · · · · · · · · · · · · · ·													
				Pre-	Post-	TP load	Pre-	Post-	TN load										Runoff			
				Develop	Develop	reductio	Develop	Develop	reductio		Pre-		Pre-	Post-		Post-			Volume	Site	Site	
	Disturbe	% Pre-	% Post-	ment TP	ment TP	n	ment TN	ment TN	n	Total Site	Forest	Pre-Turf	Impervio	Forest	Post-Turf	Impervio	Pre-	Post-	Reducati	Latitude	Longitude	Anticipat
	d Area	Impervio	Impervio	load	load	achieved	load	load	achieved	Area	Area	Area	us Area	Area	Area	us Area	Runoff	Runoff	on	(Decimal	(Decimal	ed Start
#	(acres)	us	us	(lb/yr)	(lb/yr)	(lb/yr)	(lb/yr)	(lb/yr)	(lb/yr)	(acres)	(acres)	(acres)	(acres)	(acres)	(acres)	(acres)	Volume	Volume	Achieved	Degrees)	Degrees)	Date
58	1.3056	47.8	54.2	1.66	1.75	0.57	11.90	12.51	4.76	1.3056	0.0000	0.6812	0.6244	0.1499	0.4478	0.7079	2647.7946	2782.6201	662.4460	38.911102	-77.108781	TBD



NTLEMAN' 3 RY HOLLY
NTLEMAN [*] 3 RY HOLLY
NTLEMAN ¹ 3 RRY HOLLY
NTLEMAN [°] 3 RRY HOLLY
RY HOLLY
3
(
1
CIFOLIA I
1
1
1
1
1
N.
NNERS`TM
(
(
4

Facility name/type	Design Level	Impervious Area to Facility	Pervious Area to Facility	Total Drainage Area	Total Drainage Area	Rainfall Depth (P)	Rv	Target storage (WQv)	Ponding depth	Filter depth	Gravel depth	Filter : Gravel Depth Ratio	Gravel Sump below underdrain Required for Level 2 Designs that include an underdrain (No storage credit provided)	
		(SF)	(SF)	(SF)	(acre)	(in)		(CF)	(in)	(in)	in	Level 1: ≥ 2:1 Level 2: ≥ 3:1	(in)	(SF
Bioretention #1	Level 1	19107	8614	27721	0.6364	1.00	0.72	1670.56	6	40	12	3.33	N/A	1096

Construction Inspection Checklist: Bioretention	LOTION	Certification of Excavation Inspection: Inspector certifies the successful completion of the excavation		PRETREATMENT AND PLANT INSTALLATION	DATE
Address/ Building	INIA GINIA	steps listed above.		Riser, overflow weir, or other outflow structure is set to the proper elevation, receive the proper compaction and are functional.	
Location: Permit #: LDA Permit #: SWM#:		 Photos required include: Excavated area prior to installation of stone, including measurements (L x W x D); Non-woven geotextile fabric installed on sides of excavated subgrade only. 		Placement of energy dissipaters and pretreatment practices (forebays, gravel diaphragms, etc.) are installed in accordance with the approved plans.	
Contractor: Telephone:					+
Certifying Professional*: Telephone:		Material delivery ticket include: o Geotextile installed on sides		Appropriate number and spacing of plants are installed in accordance with the approved plans. Microbioretentions use the appropriate number of plants from VA DEQ Table 9.4, bioretentions follow the approved landscape plan.	
Date Started: Final Inspection Date:		FILTER LAYER, UNDERDRAIN, AND STONE RESERVOIR PLACEMENT	DATE	Ponding depth verification after plant and mulch placement.	1
*Certifying professional must be a licensed Professional Engineer (PE), Landscape Architect (LA), or Land Surveyor (LS).			DATE		
		All aggregates conform to specifications as certified by quarry.		Certification of Pretreatment and Plant Installation: Inspector certifies the successful completion of any pretreatment measures, plants and mulch as listed above.	
The following checklist provides a basic outline of the anticipated items for the construction inspection		Underdrain size and perforations meet the specifications (if applicable).			
bioretention facilities. This checklist does not necessarily distinguish between all the design variation differences in construction between the family of practices. Inspectors should review the plans care	fully, and	If the underdrain is directly tied into the public storm sewer system, the connection has been witnessed by DES inspector.		 Photos/Elevations required for this step include: Overall photos of showing mulch and plants installed; Location of inflow and appropriate energy dissipation; 	
adjust these items and the timing of inspection verification as needed to ensure the intent of the des The standard for design of this practice is based on Virginia Stormwater BMP Clearinghouse and Arling	Contraction of the second s	For Level 2 installations: placement of filter layer and initial lift of stone reservoir layer aggregates with underdrain or infiltration sump, spread (not dumped) to avoid aggregate segregation		 Microbioretention with sheetflow as the inflow: string line measurement showing the swale. 	
Stormwater Guidance Manual.		Placement of underdrain, observation wells, and underdrain fittings are in accordance with the approved plans.		 Bioretention with sheetflow as the inflow: survey of the swale. Any pretreatment measures required per the approved plans; Distance from the top of the mulch to the top of the overflow (either pipe or berm). 	
All items should be checked when completed. Items labeled "Certification of" must be crosse dated and initialed by certifying inspector.	d off,	Elevations of underdrain and outlet structure are in accordance with approved plans, or as adjusted to meet field conditions and denoted in Comments section.		 Microbioretention: string line measurement showing the surface of the microbioretention is level and has the appropriate ponding depth over the entire surface. 	
PRE-CONSTRUCTION MEETING	DATE	Placement of remaining lift of stone reservoir layer as needed to achieve the required reservoir depth.		 Bioretention: as-built survey that captures the top of mulch and top of overflow to achieve the proper ponding depth. 	
 Identify the tentative schedule for construction and verify the requirements and schedule for interim inspections. All pervious areas of the contributing drainage areas have been adequately stabilized with a thick layer 		Certification of Filter Layer and Underdrain Placement Inspection: Inspector certifies the successful completion of the filter layer and underdrain placement steps listed above. Photos and material delivery tickets for these items are attached.		Material delivery tickets required for this step include: Approved plants listing number and species; Shredded hardwood mulch. 	
of vegetation or erosion control measures are still in place and stormwater has been diverted around the area.		 Photos required include: Perforated underdrain pipe (if applicable) with a solid vertical overflow pipe; 			
Area of bioretention practice has not been impacted during construction.		Depth of #57 stone;		BIORETENTION TESTING	DAT
Conduct a pre-construction meeting with the contractor designated to install the bioretention, the person completing this checklist, and the County DES Stormwater Specialist inspector (schedule via		 Depth of choker stone (pea gravel or #8); Underdrain connection to public storm sewer system (if applicable). 		A bioretention that uses infiltration to drain (i.e., it has no underdrain) must be tested for infiltration rate upon completion and must function as designed.	
stormwaterreview@arlingtonva.us).		Material delivery tickets required include: o 57 stone;		COMMENTS (CLARIFICATION, DEVIATIONS, ETC.)	DAT
		 Choker stone (pea gravel or #8). 			
EXCAVATION	DATE				
Area of bioretention excavation is marked and the size and location conforms to plan.		BIORETENTION SOIL MEDIA PLACEMENT	DATE		
If the excavation area has been used as a sediment trap: verify that the bottom elevation of the proposed stone reservoir is lower than the bottom elevation of the existing trap.		Soil media is certified by supplier or contractor as meeting the project specifications and comes from an approved soil media vendor.		All items checked above have been inspected by me (or by an individual under my responsible charge	le) and
For Level 2 bioretention, ensure the bottom of the excavation is scarified prior to placement of stone.		Soil media is placed in 12-inch lifts to the design top elevation of the bioretention area, and lifts have been lightly watered Elevation has been verified after settlement (2 to 4 days after initial placement).		have been completed to my satisfaction and meet the approved plans (or deviations are noted here)	
Subgrade surface is free of rocks and roots, and large voids. Any voids should be refilled with the base aggregate to create a level surface for the placement of aggregates and underdrain (if required).		Side slopes of ponding area are feathered back at the required slope (no steeper than 3H:1V).		Signature: Date:	
No groundwater seepage or standing water is present. Any standing water is dewatered to an acceptable dewatering device.		Certification of Soil Media Placement Inspection: Inspector certifies the successful completion of the soil media steps listed above and any necessary photos are attached.			
Excavation of the bioretention practice has achieved proper grades and the required geometry and		Photo required of a measurement of the soil media installed.		Certifying Professional's License Number (or Seal):	200202-020
elevations without compacting the bottom of the excavation.			1	 See attached sealed final location survey with the installed stormwater management facilities appropriate 	Vaheloo
Constructed dimensions:		Material delivery ticket required from an approved soil media vendor.		 See attached sealed final location survey with the installed stormwater management facilities appropriate and certification letter 	ly labele

Bioretention | March 2020

Bioretention Maintenance Schedule Maintena

- Maintenanc
 Spot weeding, erosion repair, trash
 Add reinforcement planting to main vegetation density
 Remove invasive plants using recording Stabilize the contributing drainage at Spring inspection and cleanup
 Supplement mulch to maintain a 2-Prune trees and shrubs
 Remove sediment in pre-treatment
 Replace the mulch layer
 Inspected and certified by a profess of Virginia

Bioretention | March 2020

Bioretention | March 2020

ance	Frequency
ash removal, and mulch raking	Twice during growing season
naintain the desired	As needed
ecommended control methods ge area to prevent erosion	
a 2-3 inch layer	Annually
ent cells and inflow points	Once every 2 to 3 years
	Every 3 years
fessional licensed in the State	Once every 5 years

Bioretention	Basin	Material	Specifications
--------------	-------	----------	----------------

Material	Specification	Notes				
Filter Media Composition	 Filter Media to contain: 80%-90% sand with >75% being coarse to very coarse 10%-20% soil fines 3%-5% organic matter in the form of plant based compost meeting Clearinghouse Design Specification #4, Section 6.5 	The volume of filter media based on 110% of the plan volume, to account for settling or compaction.				
Filter Media Testing	Plant available P within Low+ (L+) to Medium (M) per DCR 2014 Nutrient Management Criteria (18- 40 mg/kg P for the Mehlich III procedure) and CEC >5	The media can be procured from approved filter media vendors or mixed onsite with testing results meeting standard for both texture and nutrient composition.				
Mulch Layer	Use aged, shredded hardwood bark mulch	Lay a 2 to 3 inch layer on the surface of the filter bed.				
Geotextile/Liner	Use a non-woven geotextile fabric with a flow rate of > 110 gal./min./sq. ft. (e.g., Geotex 351 or equivalent)	Apply only to the vertical sides and 2' on each side of the underdrain. Do not install at the bottom or between layers.				
Choking Layer	3 inch layer of pea gravel or VDOT underdrain stone.	#8 stone which is laid over the				
Stone Jacket for Underdrain and/or Storage Layer	1 inch stone should be double- washed and clean and free of all fines (e.g., VDOT #57 stone).	12 inches for the underdrain; 12 to 18 inches for the stone storage layer, if needed				
Underdrains, Cleanouts, and Observation Wells	Use 6 inch rigid schedule 40 PVC pipe for bioretention basins, with 3/8-inch perforations at 6 inches on center, maximum of 3 rows of perforations; position each underdrain on a 1% or 2% slope located nor more than 20 feet from the next pipe.	All bioretentions are to have an observation well, cleanout or overflow pipe. Lay the perforated pipe under the length of the bioretention cell, and install non-perforated pipe as needed to connect with the storm drain system Install T's and Y's as needed, depending on the underdrain				

A R L I N G T VIRGINIA DEPARTMENT OF PAR AND RECREATION Park Development Division 2100 Clarendon Boulevard, Suite Arlington, VA 22201 Phone: 703.228.3332	RKS
Fax: 703.228.3328	on ents
DETAILS 100% Construction Drav	vings
Approval Design Manager	Date
Design Manager	Date Date

Subsurface Exploration and Geotech

HC

3.4 In-Situ Infiltration Test Results

The individual infiltration test results are included as an attach (Appendix V) and summarized in the Table 2 below:

	Table 1 - Summary of Infiltration	Test Results
Infiltration	Depth of Boring from	Estimate
Boring no.	Existing ground level (ft.)	(in
IT-1	6.0	. NG
IT-2	6.0	

All in-situ infiltration test rates were found to be higher than the infiltration rate of 0.5 in/hr.

HILLIS-CARNES ENGINEERING ASSOCIATES

HILLIS - CARNES ENGINEERING ASSOCIATES, INC. RECORD OF SOIL EXPLORATION

Project	Name		Marcey Road Park												
Lo	ocatior	۱	2722 Marcey Rd, Arlington, VA 22207												
Surf. Elev. <u>+</u>		OGL ft. 5/7/2020	Hammer Drop		30)	_ lbs. _ in.	Rock	Diame Core	Diameter _			Insp		
Elev (ft)	Depth (ft)	Descriptio	n	Soil Sym	Sar No	mple Rec (in)	NM (%)	PI (%)	LL (%)	SPT blows per 6"			h		
-0.6	0				1	13				7-4-4		 			
-2.5		Brown, moist, mediu			2	18				6-5-8	13	 			
	5	Brown, moist, mediu sand (SM)	m dense silty		3	18	13.0%	NP	NP	4-6-9	15				
-10.0	10				4	18				6-9-13	22				
	15														
	20														
	25														
	30														
PT - Pre	plit Spo ssed Sh ntinuous	oon unless otherwise noted nelby Tube s Flight Auger	SAMPLE C D - Disinteg I - Intact U - Undistu L - Lost	grate.	d	NS	At Comp After 24 After	Hrs.		Dry	CAVE DEPT a. 8.5 aa				

STANDARD PENETRATION TEST-DRIVING 2" O.D. SAMPLER 1' WITH 140# HAMMER FALLING 30": COUNT MADE AT 6" INTERVALS.

Marcey Road park Engineering Services		KEY TO S	SYMBOLS	8		
oject Number: C20043	Symbol Descripti	ion				
nt to this report	Strata symbols			Soil Samplers		
nt to this report	Paving			Auger		
nfiltration Rate	Topsoil					
es/hour) 2.62	Topsoil Silt (ML)					
0.51						
required minimum	Silty sand	1 (SM)				
	Low plasti	icity				
	Elastic si					
	Sand (ML/S	3M)				
	Notes:					
		orings were drilled on ight power auger.	5/7/2020 us	ing a 4-inches diam	eter	
	2. No groundwate:	r was encountered at th	he time of d	rilling or when re-		
	checked the for	ollowing day. ons were staked from ex	xisting feat	ures from the desig	n	
	schematic plan	n.				
		e subject to the limitans in this report.	ations, conc	lusions, and		
	5. Results of tea	sts conducted on sample	es recovered	are reported on the	e logs.	
PAGE 11 OF 21						
PAGE 11 OF 21 Page 1			•		Page 1	
	Project Name	ENGINEERING A				
Page 1		ENGINEERING A RECORD OF SOI Marcey Road Park 2722 Marcey Rd, Arlington,	SSOCIATES, IN		- -	
Page 1 pring No. <u>B1</u> Job # <u>C20043</u> n. Foreman <u>James Burrowbridge</u>	Location DatumOGL	ENGINEERING A RECORD OF SOI Marcey Road Park 2722 Marcey Rd, Arlington, SAM Hammer Wt. 140 lbs.	SSOCIATES, IN IL EXPLORATION VA 22207 PLER Hole Diameter	Boring No B2 Job #C2004 in. Foreman <u>James Bur</u>	13 rrowbridge	
Page 1 pring No <u>B1</u> _ Job # <u>C20043</u>	Location DatumOGL Surf. Elev. <u>+</u>	ENGINEERING A RECORD OF SOI Marcey Road Park 2722 Marcey Rd, Arlington, SAM Hammer Wt. 140 lbs.	SSOCIATES, IN IL EXPLORATION VA 22207 PLER Hole Diameter Rock Core Diameter	Boring No B2 Job #C2004 in. Foreman <u>James Bur</u> InspectorF	13 rrowbridge Y	
Page 1 pring NoB1Job #C20043 n. Foreman James BurrowbridgeInspectorFYDate Completed5/7/2020 otBoring and Sampling Notes	Location DatumOGL Surf. Elev. <u>+</u> Date Started <u>5/7/2020</u>	ENGINEERING A RECORD OF SOI Marcey Road Park 2722 Marcey Rd, Arlington, SAM Hammer Wt. 140 lbs. ft. Hammer Drop 30 in. Pipe Size 2 in.	SSOCIATES, IN IL EXPLORATION VA 22207 PLER Hole Diameter Rock Core Diameter	Boring NoB2 Job #C2004 in. Foreman James Bur InspectorF ISA-SPTDate Completed5, SPTBlows/footBoring ar Sampling N	13 rrowbridge Y 17/2020	
Page 1 Dring NoB1Job #C20043 n. Foreman James BurrowbridgeInspectorFYDate Completed5/7/2020 Date Completed5/7/2020 Date Completed3" Asphalt 3" base	Location DatumOGL Surf. Elev. \pm Date Started5/7/2020 $\begin{array}{c} \textcircled{\bar{e}} & \hline \bar{e} & $	ENGINEERING A RECORD OF SOI Marcey Road Park 2722 Marcey Rd, Arlington, SAM 140 Ibs. Hammer Wt. 140 Ibs. ft. Hammer Drop 30 in. I o Pipe Size 2 in. I escription E Sample Root Rec (in) NM (%) Rec (in) 1 6	SSOCIATES, IN IL EXPLORATION VA 22207 PLER Hole Diameter Rock Core Diameter Boring Method H	Boring No. B2 Job # C2004 Job # C2004 in. Foreman James Bur Inspector FilsA-SPT Date Completed 5. SPT Blows/foot Boring ar Sampling No.	13 rrowbridge Y /7/2020 nd lotes	
Page 1 Dring NoB1Job #C20043 n. Foreman James BurrowbridgeInspectorFYDate Completed5/7/2020 OtBoring and Sampling Notes 3 8	Location DatumOGL Surf. Elev. \pm Date Started5/7/2020 $\begin{array}{c} \underbrace{} \\ \underbrace{\underbrace{} \\ \underbrace{ \\ \underbrace{} \\ \\ \underbrace{ \\ \\ \underbrace{ \\ \\ \underbrace{ \\ \\ \\ \underbrace{ \\ \\ \underbrace{ \\ \\ \\ \underbrace{ \\ \\ \\ \underbrace{ \\ \\ \\ \\ \underbrace{ \\ \\ \\ \\ \underbrace{ \\ $	ENGINEERING A RECORD OF SOI Marcey Road Park 2722 Marcey Rd, Arlington, SAM 140 Ibs. Hammer Wt. 140 Ibs.	SSOCIATES, IN IL EXPLORATION VA 22207 PLER Hole Diameter Rock Core Diameter Boring Method H PI LL SPT blows per 6" 2-0-1	Boring No. B2 Job # C2004 Job # C2004 Inspector F Inspector F ISA-SPT Date Completed 5 Blows/foot Boring ar SPT Boring n SPT Boring ar Sampling N 2" Topso 1 1 1	13 rrowbridge Y /7/2020 Ind lotes	
Page 1 Dring NoB1Job #C20043 n. Foreman James BurrowbridgeInspectorFYDate Completed5/7/2020 Date Completed5/7/2020 Date CompletedSampling Notes3 & g3 & g	Location DatumOGL Surf. Elev. \pm Date Started5/7/2020 $\begin{array}{c} \hline \hline$	ENGINEERING A RECORD OF SOI Marcey Road Park 2722 Marcey Rd, Arlington, SAM 140 Ibs. Ibs. 140 Ibs. In. E In. E In. Ibs. Ibs. Ibs. Ibs. <th c<="" td=""><td>SSOCIATES, IN IL EXPLORATION</td><td>Boring No. B2 Job # C2004 </td><td>13 rrowbridge Y /7/2020 Ind lotes</td></th>	<td>SSOCIATES, IN IL EXPLORATION</td> <td>Boring No. B2 Job # C2004 </td> <td>13 rrowbridge Y /7/2020 Ind lotes</td>	SSOCIATES, IN IL EXPLORATION	Boring No. B2 Job # C2004	13 rrowbridge Y /7/2020 Ind lotes
Page 1 pring No. <u>B1</u> Job # <u>C20043</u> n. Foreman <u>James Burrowbridge</u> Inspector <u>FY</u> Date Completed <u>5/7/2020</u> t Boring and Sampling Notes Boring and Bor	Location DatumOGL Surf. Elev. \pm Date Started $\underbrace{\textcircled{(t)}}_{=}$ $\underbrace{\textcircled{(t)}}_{=}$ De $\underbrace{\textcircled{(t)}}_{=}$ $\underbrace{\textcircled{(t)}}_{=}$ $\underbrace{\textcircled{(t)}}_{=}$ De $\underbrace{\textcircled{(t)}}_{=}$ $\underbrace{\textcircled{(t)}}_{=}$ $\underbrace{(t)}_{=}$ $\underbrace{(t)}_{$	ENGINEERING A RECORD OF SOI Marcey Road Park 2722 Marcey Rd, Arlington, SAM 140 Ibs. Ibs. 140 Ibs. 140 Ibs. 140 Ibs. In. I Ibs. Ibs. Ibs. Ibs. Ibs. Ibs. Ibs. Ibs. Ibs. Ibs. Ibs. Ibs. Ibs. Ibs. Ibs. Ibs. Ibs. Ibs. Ibs. Ibs. Ibs. Ibs. Ibs. <thi< td=""><td>SSOCIATES, IN IL EXPLORATION VA 22207 PLER Hole Diameter Rock Core Diameter Boring Method H PI LL SPT blows per 6" 2-0-1</td><td>Boring No. B2 Job # C2004 </td><td>13 rrowbridge Y /7/2020 Ind lotes</td></thi<>	SSOCIATES, IN IL EXPLORATION VA 22207 PLER Hole Diameter Rock Core Diameter Boring Method H PI LL SPT blows per 6" 2-0-1	Boring No. B2 Job # C2004	13 rrowbridge Y /7/2020 Ind lotes	
Page 1 ring NoB1 Job #C20043 a. Foreman James Burrowbridge InspectorFY Date Completed5/7/2020 b. Boring and ph Sampling Notes T3" Asphalt 3" base Probable fill	Location DatumOGL Surf. Elev. \pm Date Started $\begin{array}{c} \hline \hline$	ENGINEERING A RECORD OF SOI Marcey Road Park 2722 Marcey Rd, Arlington, SAM 140 Ibs. Ibs. 140 Ibs. In. E In. E In. Ibs. Ibs. Ibs. Ibs. <th c<="" td=""><td>SSOCIATES, IN IL EXPLORATION</td><td>Boring No. B2 Job # C2004 in. Foreman James Bur in. Inspector inspector Fill ISA-SPT Date Completed Blows/foot Boring ar SPT Boring ar SPT Boring ar Sampling N 2" Topso 1 1 <t< td=""><td>13 rrowbridge Y /7/2020 Ind lotes</td></t<></td></th>	<td>SSOCIATES, IN IL EXPLORATION</td> <td>Boring No. B2 Job # C2004 in. Foreman James Bur in. Inspector inspector Fill ISA-SPT Date Completed Blows/foot Boring ar SPT Boring ar SPT Boring ar Sampling N 2" Topso 1 1 <t< td=""><td>13 rrowbridge Y /7/2020 Ind lotes</td></t<></td>	SSOCIATES, IN IL EXPLORATION	Boring No. B2 Job # C2004 in. Foreman James Bur in. Inspector inspector Fill ISA-SPT Date Completed Blows/foot Boring ar SPT Boring ar SPT Boring ar Sampling N 2" Topso 1 1 <t< td=""><td>13 rrowbridge Y /7/2020 Ind lotes</td></t<>	13 rrowbridge Y /7/2020 Ind lotes
Page 1 pring NoB1 Job #C20043 The Foreman James BurrowbridgeFYDate Completed5/7/2020 The Boring and Sampling Notes The Boring terminated @10ft.	Location DatumOGL Surf. Elev. \pm Date Started5/7/2020 $\begin{array}{c} \hline \hline$	ENGINEERING A RECORD OF SOI Marcey Road Park 2722 Marcey Rd, Arlington, SAM 140 Ibs. Ibs. 140 Ibs. In. Ibs. The many of the many	SSOCIATES, IN IL EXPLORATION	Boring No. B2 Job # C2004	rowbridge Y /7/2020 Ind lotes Dil	
Page 1 pring No. <u>B1</u> Job # <u>C20043</u> A. Foreman <u>James Burrowbridge</u> Inspector <u>FY</u> Date Completed <u>5/7/2020</u> bt Boring and Sampling Notes 3" Asphalt 3" base Probable fill	Location DatumOGL Surf. Elev. \pm Date Started5/7/2020 $\begin{array}{c c} \hline \hline$	ENGINEERING A RECORD OF SOI Marcey Road Park 2722 Marcey Rd, Arlington, SAM 140 Ibs. Ibs. 140 Ibs. In. Ibs. The many of the many	SSOCIATES, IN IL EXPLORATION	Boring No. B2 Job # C2004 in. Foreman James Bur Inspector F ISA-SPT Date Completed 5 Blows/foot Boring ar SPT Boring no 1 Image: Second for the second formed formed for the second formed formed for the second formed formed formed formed for the second formed	rowbridge Y /7/2020 Ind lotes Dil	
Page 1 pring No. B1 Job # C20043 n. Foreman James Burrowbridge Inspector FY Date Completed 5/7/2020 ot Boring and Sampling Notes 3 3" Asphalt 3" base Probable fill 0 Boring terminated @10ft. 0 Boring terminated @10ft. 0 Boring terminated @10ft.	Location DatumOGL Surf. Elev. \pm Date Started5/7/2020 $\begin{array}{c c} \hline \hline$	ENGINEERING A RECORD OF SOI Marcey Road Park 2722 Marcey Rd, Arlington, SAM 140 Ibs. Ibs. 140 Ibs. In. Ibs. The many of the many	SSOCIATES, IN IL EXPLORATION	Boring No B2 Job # C2004 in. Foreman James Bur Inspector F ISA-SPT Date Completed 5 Blows/foot Boring ar Sampling N 1 IIIIIIIIIIIIIIIIIIIIIIIIIIIIIIIIIIII	rowbridge Y /7/2020 Ind lotes Dil	
Page 1 pring No. B1 Job # C20043 n. Foreman James Burrowbridge Inspector FY Date Completed 5/7/2020 ot Boring and aph Sampling Notes a 3" Asphalt 3" base Probable fill Boring terminated @10ft. a a	Location DatumOGL Surf. Elev. \pm Date Started5/7/2020 $\begin{array}{c c} \hline \hline$	ENGINEERING A RECORD OF SOI Marcey Road Park 2722 Marcey Rd, Arlington, SAM 140 Ibs. Ibs. 140 Ibs. In. Ibs. The many of the many	SSOCIATES, IN IL EXPLORATION	Boring No. B2 Job # C2004	rowbridge Y /7/2020 Ind lotes Dil	
Page 1 pring No. B1 Job # C20043 n. Foreman James Burrowbridge Inspector FY Date Completed 5/7/2020 ot Boring and Sampling Notes Sampling Notes Sampling Notes Sampling Notes Sampling Notes Sampling Notes Boring terminated @10ft. Horing terminated @10ft. Inspector Gate Completed @10ft.	Location DatumOGL Surf. Elev. \pm Date Started5/7/2020 $\begin{array}{c c} \hline \hline$	ENGINEERING A RECORD OF SOI Marcey Road Park 2722 Marcey Rd, Arlington, SAM 140 Ibs. Ibs. 140 Ibs. In. Ibs. The many of the many	SSOCIATES, IN IL EXPLORATION	Boring No. B2 Job # C2004	rowbridge Y /7/2020 Ind lotes Dil	
Page 1 pring No. B1 Job # C20043 n. Foreman James Burrowbridge Inspector FY Date Completed 5/7/2020 ot Boring and Sampling Notes Sampling Notes Sampling Notes Sampling Notes Sampling Notes Sampling Notes Boring terminated @10ft. Horing terminated @10ft. Inspector Gate Completed @10ft.	Location DatumOGL Surf. Elev. \pm Date Started5/7/2020 $\begin{array}{c c} \hline \hline$	ENGINEERING A RECORD OF SOI Marcey Road Park 2722 Marcey Rd, Arlington, SAM 140 Ibs. Ibs. 140 Ibs. In. Ibs. The many of the many	SSOCIATES, IN IL EXPLORATION	Boring No. B2 Job # C2004	rowbridge Y /7/2020 Ind lotes Dil	
Page 1 ing No. <u>B1</u> Job # <u>C20043</u> Foreman <u>James Burrowbridge</u> Inspector <u>FY</u> Date Completed <u>5/7/2020</u> boring and Sampling Notes 3" Asphalt 3" base Probable fill	Location Datum Surf. Elev. \pm Date Started $\hline \hline \hline$	ENGINEERING A RECORD OF SOI Marcey Road Park SAM 2 Marcey Rd, Arlington, SAM 140 Ibs. 140 Ibs. 140 Ibs. 140 Ibs. In. Ibs. Ibs. Ibs. Ibs. Ibs. Ibs. Ibs. Ibs. Ibs. Ibs. Ibs. Ibs. Ibs. Ibs. Ibs.	SSOCIATES, IN IL EXPLORATION	Boring No. B2 Job # C2004	rowbridge Y /7/2020 Ind lotes Dil	
Page 1 g No. <u>B1</u> ob # <u>C20043</u> Foreman <u>James Burrowbridge</u> Inspector <u>FY</u> Date Completed <u>5/7/2020</u> Boring and Sampling Notes 3" Asphalt 3" base Probable fill Boring terminated @10ft. depth.	Location DatumOGL Surf. Elev. \pm Date Started5/7/2020 $\begin{array}{c c} \hline \hline$	ENGINEERING A RECORD OF SOI Marcey Road Park SAM 2 Marcey Rd, Arlington, SAM 140 Ibs. 140 Ibs. 140 Ibs. 140 Ibs. In. Ibs. Ibs. Ibs. Ibs. Ibs. Ibs. Ibs. Ibs. Ibs. Ibs. Ibs. Ibs. Ibs. Ibs. Ibs.	SSOCIATES, IN IL EXPLORATION	Boring No. B2 Job # C2004	rowbridge Y /7/2020 Ind lotes Dil	

BORING METHOD HSA - Hollow Stem Augers 5 ft. ft. CFA - Continuous Flight Augers ft. DC - Driving Casing MD - Mud Drilling

30							_
SAMPLER TYPE	SAMPLE CONDITION	s	GROUND WATI	R	CAVE IN DEPTH		BORING METHOD
SAMPLER TYPE Driven Split Spoon unless otherwise noted	SAMPLE CONDITION D - Disintegrated	S At Completion		ERft.		ft.	BORING METHOD HSA - Hollow Stem Augers
		-	DEPTH		DEPTH	_ ft. _ ft.	HSA - Hollow Stem Augers
Driven Split Spoon unless otherwise noted	D - Disintegrated	At Completion	DEPTH Dry Dry	_ fl.	DEPTH	-	

SAMPLER TYPE Driven Split Spoon u PT - Pressed Shelby CA - Continuous Flig

30

RC - Rock Core

REFERENCE NOTES FOR BORING LOGS

ing and Sampling Symbols:

plit Spoon Sampler	RB	Rock Bit Drilling
helby Tube Sampler	BS	Bulk Sample of Cuttings
ock Core; NX, BX, AX	PA	Power Auger (no sample)
rassuremeter	HSA	Hollow Stem Auger
utch Cone Penetrometer	WS	Wash Sample

ard Penetration Test (SPT) resistance refers to the blows per foot (bpf) of a 140 lb hammer failing 30 on a 2 in. O.D. split-spoon sampler as specified in ASTM D-1586. The blow count is commonly referred e N-value.

visition of Penetration Resistances to Soli Properties:

ve Dens	ity of Cohesionless Soils	Consistency of Cohesive Soils				
(bof)	Relative Density	<u>SPT-N (bof)</u>	Consistency			
	Very Loose	0-1	Very Soft			
	Loose	2-4	Soft			
9	Medium Dense	5-8	Firm			
0	Dense	9-15	Stiff			
	Very Dense	16 - 30	Very Stiff			
	12 5	31 - 50	Hard			
		>51	Very Hard			

ared Rock (WR) may be defined as SPT-N values exceeding 60 bpf depending on site specific ons. Refer carefully to boring logs.

regments, gravel, cobbles, boulders, or debris may produce N-values that are not representative of soil properties.

led Soil Classification Symbols:

y Graded Gravel	
Graded Gravel	
Gravel	
y Gravels	
Graded Sands	
Graded Sands	
Sands	
y Sands	

orstory Testing and Water Level Symbols

IQUID LIMIT (%)	
PLASTIC INDEX (%)	
MOISTURE CONTENT (%)	
DRY DENSITY (PCF)	
NON PLASTIC	
PERCENT PASSING NO. 200 SIEVE	
POCKET PENETROMETER (TSF)	

¥	Water Level at Time Drilling, or as Shown
¥	Water Level at End of Drilling, or as Shown

Water Level After 24 Hours, or as Shown

ML – Low Plasticity Silts MH – High Plasticity Silts CL – Low Plasticity Clays CH – High Plasticity Clays OL – Low Plasticity Organics OH – High Plasticity Organics CL-ML – Dual Classification (Typical)

			١E	ERI		ISS	OCI	ES ATES, II ORATION				Page 1
			_		l Park							NoB3
	2722 Mar	сеу	Rd	, Arl	ington	, VA	22207	7			Job	# C20043
					_ lbs.		Diame					oreman <u>James Burrowbridg</u> spectorFY
5/7/2020	Pipe Size		2		in.	Borii	ng Met	hod H	ISA-SF	νŢ	_ Da	ate Completed 5/7/2020
Descriptic	n	5		mple Rec (in)		Pl (%)	LL (%)	SPT blows per 6"	BI	SPT ows/fool Grap ₽ 8	h	Boring and Sampling Notes
Brown, moist, mediui	m stiff silty clay		1	10				2-2-4	6			2" Topsoil Probable fill
(CL)			2	10	28.7%	NP	NP	14-13-5	18			
Brown, moist, loose t dense silty sand (SM			3	12				2-2-3	5			
Brown, moist, very st sand (ML/SM)	tiff silt with		4	18				13-9-13	22			Boring terminated @10ft.
: n unless otherwise noted elby Tube Flight Auger	SAMPLE (D - Disinte <u>;</u> I - Intact U - Undistu L - Lost	grated	b	NS	At Comp After 24 After	Hrs.		Dry	DI	f	t. t.	BORING METHOD HSA - Hollow Stem Augers CFA - Continuous Flight Augers DC - Driving Casing MD - Mud Drilling



DEPARTMENT OF PARKS AND RECREATION

Park Development Division 2100 Clarendon Boulevard, Suite 414 Arlington, VA 22201 Phone: 703.228.3332 Fax: 703.228.3328

21-DPR-ITB-646

Project Name and Location

Marcey Road Park Improvements (By Right)

(County Project)

2722 MARCEY ROAD ARLINGTON, VA 22207

Sheet Title SOIL BORING LOGS

100% Construction Drawings

Approval	Date
Design Manager	
Revisions	Date
Designed: AW Drawn: AMT Checked: SDT, JKS, MMW, C	СMB
Filename: c-23-150396024.c Plotted: 2021-06-02	lwg
Scale: 1" = 25' Date: JUNE 2, 2021	
Seal	
MATTHEW M. WEIR Cert. No. 0406001961	
Sheet C-24	

POLLUTION PREVENTION NOTES

- I. ONLY THE FOLLOWING NON-STORMWATER DISCHARGES ARE AUTHORIZED BY ARLINGTON COUNTY'S MS4 PERMIT. UNLESS THE STATE WATER CONTROL BOARD, THE VIRGINIA SOIL AND WATER CONSERVATION BOARD (BOARD), OR ARLINGTON COUNTY DETERMINES THE DISCHARGE TO BE A SIGNIFICANT SOURCE OF POLLUTANTS TO SURFACE WATERS: WATER LINE FLUSHING; LANDSCAPE IRRIGATION; DIVERTED STREAM FLOWS; RISING GROUND WATERS; UNCONTAMINATED GROUND WATER INFILTRATION (AS DEFINED AT 40 CFR 35.2005(20)); UNCONTAMINATED PUMPED GROUND WATER; DISCHARGES FROM POTABLE WATER SOURCES; FOUNDATION DRAINS; AIR CONDITIONING CONDENSATION; IRRIGATION WATER; SPRINGS; WATER FROM CRAWL SPACE PUMPS; FOOTING DRAINS; LAWN WATERING; INDIVIDUAL RESIDENTIAL CAR WASHING; FLOWS FROM RIPARIAN HABITATS AND WETLANDS; DECHLORINATED SWIMMING POOL DISCHARGES; DISCHARGES OR FLOWS FROM FIRE FIGHTING; AND, OTHER ACTIVITIES GENERATING DISCHARGES IDENTIFIED BY THE DEPARTMENT OF ENVIRONMENTAL QUALITY AS NOT REQUIRING VPDES AUTHORIZATION.
- 2. APPROPRIATE CONTROLS MUST BE IMPLEMENTED TO PREVENT ANY NON-STORMWATER DISCHARGES NOT INCLUDED ON THE ABOVE LIST (E.G., CONCRETE WASH WATER, PAINT WASH WATER, VEHICLE WASH WATER, DETERGENT WASH WATER, ETC.) FROM BEING DISCHARGED INTO ARLINGTON COUNTY'S MS4 SYSTEM, WHICH INCLUDES THE CURB AND GUTTER SYSTEM, AS WELL AS CATCH BASINS AND OTHER STORM DRAIN INLETS, OR STREAM NETWORK. 3. PER CHAPTER 26 OF THE ARLINGTON COUNTY CODE, IT SHALL BE UNLAWFUL FOR ANY PERSON TO DISCHARGE DIRECTLY OR INDIRECTLY INTO THE STORM
- SEWER SYSTEM OR STATE WATERS, ANY SUBSTANCE LIKELY, IN THE OPINION OF THE COUNTY MANAGER, TO HAVE AN ADVERSE EFFECT ON THE STORM SEWER SYSTEM OR STATE WATERS.

2.0 Authorized Non-Stormwater Discharges

Type of Authorized Non-Stormwater Discharge	Likely Pre
External buildings wash down Uncontaminated foundation or footing drains Uncontaminated excavation dewatering Landscape irrigation Others [describe]	☐ Yes ⊠ Yes ⊠ Yes ☐ Yes ☐ Yes

5.0 Potential Sources of Pollution & Pollution Prevention Practices

			1	Polluta	ants							
Pollutant-Generating Activity	Likely Present at your Project Site?	Sediment	Nutrients	Heavy Metals	pH (acids and bases)	Pesticides & Herbicides	Oil & Grease	Bacteria & Viruses	Trash, Debris, Solids	Other Toxic Chemicals	Pollution Prevention Practice	Responsible Party
Clearing, grading, excavating, and un-stabilized areas	🕅 Yes 🔲 No	x							х		(1)	
Paving operations	🛛 Yes 🔲 No	x					х		х		(2)	
Concrete washout and cement waste	🛛 Yes 🔲 No			х	x				x		(3)	
Structure construction, stucco, painting, and cleaning	🗌 Yes 🕅 No			х	х				x	х	(4)	
Dewatering operations	🛛 Yes 🗖 No	x	х						х		(5)	
Material delivery and storage	🗶 Yes 🔲 No	x	х	х	х		х		x	х	(6)	Construction Activity Operator (See Cover Page of this SWPPP)
Material use during building process	🗌 Yes 🕅 No		х	х	х		х		x	х	(7)	
Solid waste disposal	🕅 Yes 🔲 No								x	х	(8)	
Sanitary waste	Yes 🕅 No		х		х			х			(9)	
Landscaping operations	🕅 Yes 🔲 No	x	х			x	J		х	х	(10)	
Others [describe]	🗌 Yes 🕅 No	[X]	[X]	[X]	[X]	[X]	[X]	[X]	[X]	[X]	(11)	

Appendix C. Water Quality Impact Assessment Data Sheet

Project Address 2722 MAR			Date:					
	CEY ROAD		10/23/2020					
Applicant Name//				Applicant Contact Information (phone and email):				
AARON W	OHLER/DPR		703-228-7928; AWOHLER@ARLINGTONVA.US					
Owner/Client Nar			Owner/Client Contact Information (phone and email):					
				703-228-7928; AWOHLER@ARLINGTONVA.US				
	NT OF PARKS AND RECF Type of activity prop							
Activity type (che			1					
·	ion (residential, commercial, put	olic, etc.)		atio, or retaining wall				
	on-residential structure	,		aping (includes tree removal) ork				
□ Residential ad			K) Utility w	CONNECTION AND				
 Detached resi 			Fence					
			K) Other (p	lease describe): REFORESTATION.				
Section 2:	Key details of the pro	posed act	ivity					
Complete all tha	at apply			Explanation				
Complete all the								
Total area of dist	urbance on parcel (sf)	56,871 SF		Includes building footprint plus a 10 foot buffer. Also includes all soil disturbance, ingress/egress areas, stockpiling areas, etc.				
Area of disturbar	nce within RPA (sf)	5,538 SF		Includes removal of trees ≥ 3" in diameter				
	ice on slopes greater than or ent located adjacent to pundary (sf)	0 SF		Does not apply to RPA parcels along Chain Bridge Road (15 percent and greater slopes are included as part of RPA)				
Complete all fiel	ds	Existing	Proposed condition	Explanation				
	Left third of parcel or site	129	128	The distance (in feet) from the existing or				
RPA encroachment	Middle third of parcel or site	138	124	proposed structure to the designated RPA feature (edge of stream or open channel, wetland, etc.).				
(ft)	Right third of parcel or site	174	160	Encroachments of zero (0) indicate the project wi impact the stream or other RPA feature.				
Total development	nt footprint in RPA (sf)	0	0	The existing footprint includes the area of any existing structures, patios, decks, walkways, etc. Proposed foorprint is the anticipated post-project area of all structures, additions, decks, walkways regraded area behind a retaining wall, etc.				
			0	Total area of impervious surfaces within the RPA				
Impervious footpi	rint in RPA (sf)	0	0	(rooftops, pavement, etc.)				
Impervious footp	rint in RPA (sf)	-	U U VER)	(rooftops, pavement, etc.)				
		-		(rooftops, pavement, etc.)				
		-		(rooftops, pavement, etc.)				
STAFF USE ((0		(rooftops, pavement, etc.)				
STAFF USE (Building/demolitic	ONLY	(0		(rooftops, pavement, etc.)				
STAFF USE (Building/demolitic Major WQIA requ	ONLY on/LDA/Fence permit number(s)	(0		(rooftops, pavement, etc.)				

PROJECT CONSISTS OF PARK AND ATHLETIC IMPROVEMENTS LOCATED AT 2722 MARCEY ROAD. IMPROVEMENTS INCLUDE NEW HARDSCAPE, FENCING, VEGETATION, DRINKING FOUNTAIN, A LEVEL | BIORETENTION FACITILTY, REFORESTATION AND ALL ASSOCIATED UTILITIES. REFER TO SHEET REF-01 FOR REFORESTATION PLAN INFORMATION. NO TREES ARE TO BE REMOVED WITHIN THE RESOURCE PROTECTION AREA (RPA) AND NO GRADING IS PROPOSED AROUND THEM, THEREFORE, THERE WILL BE NO IMPACTS TO TREES OR CRITICAL ROOT ZONES (CRZS) WITHIN THE RPA. CRZ PROTECTION MEASURES FOR TREES OUTSIDE OF THE RPA LIMITS INCLUDE LIMITS OF DISTURBANCE, FILTER LOGS AND TREE PROTECTION FENCE SET IN A MANNER TO LIMIT DISTURBANCE AND STANDARD TREE PROTECTION NOTES HAVE BEEN INCLUDED ON THE TREE PRESERVATION PLAN TO FURTHER HIGHLIGHT THE IMPORTANCE OF PROTECTING THE EXISTING TREES. SITE RESTORATION INCLUDES INVASIVE/NON-NATIVE UNDERSTORY REMOVAL AND PLANTING OF NEW TREES AS SHOWN ON SHEET LP-01. STORMWATER RUNOFF FROM THE SITE IS IN THE FORM OF SHEET FLOW TO THE NORTHWEST INTO DONALDSON RUN. RUNOFF COLLECTED AND TREATED BY THE PROPOSED BIORETENTION FACILITY WILL SHEET FLOW TO THE NORTHWEST. STORMWATER QUALITY AND QUANTITY CONTROL TREATMENT REQUIREMENTS ARE MET BY THE ADDITION OF FORESTED AREA AND THE INSTALLATION OF THE BIORETENTION FACILITY. EROSION AND SEDIMENT CONTROL MEASURES HAVE BEEN PROVIDED FOR BOTH THE DEMOLITION AND PROPOSED PHASES OF WORK.

Path: X:\Rockville\15-0396.024 - Marcey Road Park\05-CAD

issued in Permits Plus:

Likely Present at Your Project Site?



Section 3: Plan and Narrative

Provide a plan showing the location of the proposed activity, along with the RPA boundary Briefly describe the proposed project, including any potential water quality impacts and mitigation measuresproposed. The narrative must address three impact categories 1. Tree/vegetation impacts, 2. Stormwater and runoff 3. Erosion and sediment control. Please refer to the WQIA plan/narrative checklist for additional information.

I. REFER TO SHEETS LF-01, LF-02, LF-03 AND LF-04 FOR TREE INVENTORY AND TREE PRESERVATION PLANS. 2. REFER TO SHEET C-20 FOR STORMWATER MANAGEMENT PLAN AND SHEET C-21 FOR RUNOFF INFORMATION.

3. REFER TO SHEETS C-05, C-06, C-07 AND C-08 FOR EROSION AND SEDIMENT CONTROL PLAN, NARRATIVE, NOTES AND DETAILS.

PROJECT NARRATIVE:

Additional Water Quality Impact Assessment Information

The information supplied on this form satisfies the minimum requirements for a Minor Water Quality Impact Assessment. For projects that disturb over 2500 square feet, elements of a Major Water Quality Impact Assessment may also be required, depending on the nature and extent of the proposed RPA encroachment, as outlined in Section 61-12 of the ordinance.

Pollution Prevention Practices:

- (1) Clearing, grading, excavating and un-stabilized areas Utilize erosion and sediment cor sediment laden or turbid runoff from leaving the construction site. Dispose of clearing debi disposal sites. Apply permanent or temporary stabilization, sodding and/or mulching to de accordance with the erosion and sediment control specifications and the general VPDES perm
- of stormwater from construction activities. (2) Paving operations – Cover storm drain inlets during paving operations and utilize pollution prev such as drip pans and absorbent/oil dry for all paving machines to limit leaks and spills of pavi
- fluids. (3) Concrete washout and cement waste - Direct concrete wash water into a leak-proof contain settling basin that is designed so that no overflows can occur due to inadequate sizing or precipi concrete wastes shall be removed and disposed of in a manner consistent with the h
- construction wastes. Structure construction, stucco, painting and cleaning - Enclose, cover or berm building (4) areas if susceptible to contaminated stormwater runoff. Conduct painting operations consist quality and OSHA regulations. Mix paint indoors, in a containment area or in a flat unpaved discharge of soaps, solvents, detergents and wash water from construction materials, including
- stucco paint, form release oils and curing compounds. Dewatering operations - Construction site dewatering from building footings or other source (5) discharged without treatment. Sediment laden or turbid water shall be filtered, settled or similar to discharge.
- Material delivery and storage Designate areas of the construction site for material delivery (6) Place near construction entrances, away from waterways, and avoid transport near dra waterways.
- (7) Material use during building process Use materials only where and when needed t construction activity. Follow manufacturer's instructions regarding uses, protective equipm flammability and mixing of chemicals.
- Solid waste disposal Designate a waste collection area on the construction site that do (8) substantial amount of runoff from upland areas and does not drain directly to a waterwa containers have lids so they can be covered before periods of rain, and keep containers in whenever possible. Schedule waste collection to prevent the containers from overfilling.
- (9) Sanitary waste - Prevent the discharge of sanitary waste by providing convenient and well-ma sanitary facilities. Locate sanitary facilities in a convenient location away from waterways.
- (10) Landscaping operations Maintain as much existing vegetation as practicable. Appl temporary stabilization, sodding and/or mulching to denuded areas in accordance with the erosi
- control specifications and the general VPDES permit for discharges of stormwater from constr Apply nutrients in accordance with manufacturer's recommendations and not during rainfall ev (11) Others – If applicable, describe your Pollution Prevention Practice.

7.0 Spill Prevention & Response

Most spills can be cleaned up following manufacturer specifications. Absorbent/oil dry, sealable of bags, and shovels/brooms are suggested minimum spill response items that should be available at the

1st Priority: Protect all people

2nd Priority: Protect equipment and property 3rd Priority: Protect the environment


- 1. Check for hazards (flammable material, noxious fumes, cause of spill) if flammable liquid,
- and nearby electrical equipment. If serious hazards are present leave the area and call 911 ARE LIKELY TO PRESENT A HAZARE
- 2. Make Sure the spill area is safe to enter and that it does not pose an immediate threat to he any person.
- 3. Stop the spill source.
- Call co-workers and supervisor for assistance and to make them aware of the spill and poten If possible, stop spill from entering drains (use absorbent or other material as necessary).
- Stop spill from spreading (use absorbent or other material) If spilled material has entered a storm sewer; contact locality's storm water department.
- 8. Clean up spilled material according to manufacturer specifications, for liquid spills use abso and do not flush area with water.
- 9. Properly dispose of cleaning materials and used absorbent material according to manufacture Emergency Contacts:


Normal Working Hours	
DEQ Northern Regional Office	703-583-3800
Nights, Holidays & Weekends	
VA Dept. of Emergency Management 24 Hour Reporting Service	804-674-2400
Local Contacts	
Arlington County Fire & Police DES Water, Sewer, Streets 24-Hour Emergency Washington Gas Emergency	703-558-2222 703-228-6555 703-750-1400

Appendix D. Exception Request Form

Applicant:	Project address:
AARON WOHLER/DPR	2722 Marcey Road, Arlington, VA 22207
Section 1: Brief description of ex	xception request
N/A	
Section 2: Parcel, structure, and	ownership information
Date parcel ownership began: <u>JANUARY</u> 190 Date existing principal structure built: <u>N/A</u> Will existing principal structure remain intact? Xi Yes □ No	0 Date(s) of construction of any prior work by <u>current</u> owner (alterations additions, decks, patios, etc.)—list individually: <u>DateType of prior work</u> 1. 2. 3. 4.
STAFF USE ONLY	
 Allowable development in RPA (§ 61-7.A) Allowable modification in RPA (§ 61-7.B) Allowable encroachment in RPA (§ 61-7.C) 	 New development in the RPA, redevelopment that increases imperviou area in the RPA or encroaches further into the RPA, or any other proposed disturbance of any RPA component (exception request required) Exempted activity in RPA (§ 61-15)
Expansion of nonconforming structure or use in RPA (§ 61-14) (exception request required)	 Proposed development in RMA on 15 percent slopes adjacent to RPA Other RMA activity
CBORC hearing required? □ Yes □ No	
Date public notification sent certified mail:	
Hearing date: CBORC decision:	d
Date of final approval letter:	

ontrols to prevent oris at acceptable lenuded areas in mit for discharges	ARLING	- TON
evention materials ing materials and	V I R G I N I	
iner or leak-proof itation. Hardened nandling of other	DEPARTMENT OF AND RECREA	
rmaterial storage tent with local air area. Prevent the ng the clean-up of	Park Development 2100 Clarendon Bouleva	rd, Suite 414
irces may not be ilarly treated prior	Arlington, VA 22 Phone: 703.228.3 Fax: 703.228.3	3332
very and storage. ainage paths or		
to complete the ment, ventilation,	21-DPR-IT	B-646
bes not receive a ay. Ensure that n a covered area	Project Name and Lo	ocation
aintained portable ly permanent or	Marcey	
sion and sediment truction activities. vents.	Road Par	·k
	Improver	
ontainers, plastic	-	
his location.	(By Right	.)
	(County Project)	
I, turn off engines . LARGE SPILLS	2722 MARCEY R ARLINGTON, VA	
nealth or safety of		
ntial dangers.	Sheet Title	
sorbent materials rer specifications.	WATER QUA	
	AND POLLU	
	PREVENTION	
	100% Construction	Drawings
	Approval	Date
	Design Manager	
	Revisions	Date
	Designed: AW	
	Drawn: AMT Checked: SDT, JKS, MI	NW, CMB
	Filename: c-24-150396	024.dwg
	Plotted: 2021-06-02	
	Scale: 1" = 25' Date: JUNE 2, 2021	
	Seal	
	CHELSEA M. BIS Lic. No. 5003	
	JUNE 2, 20	(G) 121
	Sheet C-2	5





ELECTRICAL SYMBOLS AND ABBREVIATIONS

WIRING

HOMERUN TO PANELBOARD. NUMBER OR ARROWS INDICATES NUMBER OF CIRCUITS UNLESS -###---- OTHERWISE NOTED. NUMBER OF HASH MARKS INDICATES NUMBER OF PHASE AND NEUTRAL CONDUCTORS PLUS GROUND UNLESS OTHERWISE NOTED. WHERE NO HASH MARKS APPEAR, TWO (2) CONDUCTORS PLUS GROUND ARE IMPLIED. PROVIDE GROUND CONDUCTOR WITH ALL FEEDERS AND BRANCH CIRCUITS. REFER TO PANEL SCHEDULES FOR CONDUCTOR QUANTITY, CONDUCTOR SIZE, AND CONDUIT SIZE UNLESS OTHERWISE NOTED.

> GROUNDING TERMINATION POINT. PROVIDE EQUIPMENT GROUNDING CONDUCTORS AND GROUNDING ELECTRODE CONDUCTORS IN COMPLIANCE WITH NATIONAL ELECTRICAL CODE REQUIREMENTS.

> > DEMOLITION

DISCONNECT AND REMOVE EXISTING LIGHT POLE FIXTURE.

EXISTING TO REMAIN

EXISTING TO REMAIN ELECTRIC PANELBOARD (120/240V), SURFACE MOUNTED.

POWER

2P-3W-20A-125V DUPLEX GROUNDING-TYPE CONVENIENCE RECEPTACLE, NEMA CONFIGURATION 5-20R WITH WEATHER-RESISTANT (WR) RECEPTACLE CONSTRUCTION, GROUND FAULT CIRCUIT INTERRUPTER (GFCI) FUNCTION, AND WEATHER-PROTECTIVE (WP) IN-USE COVER, RECESSED MOUNTED 18" ABOVE GRADE TO TOP OF BOX, UNLESS OTHERWISE NOTED.

ELECTRICAL CONNECTION TO LIGHT POLE FIXTURE (PROVIDED BY OTHERS)

ΕΝΤ	ER S	SCH	IEDI	JLE	"A"	(MODIFIED)			
	20	0 AN	1P B	US		SURFACE MC	UNTED		
KVA	\/Ø			CIR-	POLE	DESCRIPTION	WIRE/	BREA	KER
В	Ø	С	Ø	CUIT			CONDUIT	POLE	AMP
				2	2	REC (ABOVE PANEL)	ETR	1	20
1.5	0.7			4	4	LTG - BASKETBALL B1	NOTE 1	2	30
		1.5	0.7	-	6		NOTET	2	30
				8	8	LTG - BASKETBALL B2	NOTE 1	2	30
1.5	0.7			-	10		NOTET	2	30
		1.5	0.8	12	12	REC - GAZEBO	NOTE 1	1	20
				14	14	REC - GAZEBO	NOTE 1	1	20
1.5	-			16	16	SPACE & PROVISIONS		-	-
		0.1	-	18	18	SPACE & PROVISIONS		-	-
				20	20	SPACE & PROVISIONS		-	-
-	-			22	22	SPACE & PROVISIONS		-	-
		-	-	24	24	SPACE & PROVISIONS		-	-
				26	26	SPACE & PROVISIONS		-	-
-	-			28	28	SPACE & PROVISIONS		-	-
		-	-	30	30	SPACE & PROVISIONS		-	-
4.5	1.4	3.1	1.5						
5.	9	4	.6						
				-		MAIN BREAKER	200	AMPS	

LOCATION ELEC SERVICE CABINET



VIRGINIA

DEPARTMENT OF PARKS AND RECREATION

Park Development Division 2100 Clarendon Boulevard, Suite 414 Arlington, VA 22201 Phone: 703.228.3332 Fax: 703.228.3328

20-###-ITB

Project Name and Location

Marcey Road Park Improvements (By Right)

(County Project)

2722 MARCEY ROAD ARLINGTON, VA 22207

Sheet Title

ELECTRICAL SYMBOLS LIST, DETAILS, & DIAGRAMS

100% Construction Drawings

Ap	pr	ov	'al
· 1	P .		· · ·

Date

Date

Design Manager


Revisions

Designed: MLG Drawn: MLG

Checked: вмм Filename: e0.1.dwg


Plotted: 2021-04-26

Scale: AS INDICATED Date: APRIL 26, 2021



E0.1

Sheet



GENERAL NOTES:

- INFORMATION SHOWN ON THIS DRAWING PERTAINING TO EXISTING Α. CONDITIONS HAS BEEN OBTAINED FROM AVAILABLE DRAWINGS OR GENERAL FIELD OBSERVATIONS AND MAY NOT INDICATE EXISTING CONDITIONS IN DETAIL OR DIMENSION. DETERMINE EXISTING CONDITIONS PRIOR TO FABRICATION OR PERFORMANCE OF ANY WORK. SHOULD CONDITIONS BE DISCOVERED THAT PREVENT EXECUTION OF THE WORK AS INDICATED, IMMEDIATELY NOTIFY THE OWNER IN WRITING AND AWAIT DIRECTION BEFORE PROCEEDING WITH THE WORK.
- WHERE EQUIPMENT IS NOTED AS "DISCONNECT" OR "REMOVE", REMOVE ALL ASSOCIATED CONDUIT AND WIRE BACK TO SOURCE. UNDERGROUND CONDUIT THAT DOES NOT IMPACT NEW WORK MAY BE ABANDONED IN PLACE. UNDERGROUND CONDUIT THAT DOES IMPACT NEW WORK SHALL BE DEMOLISHED.
- C. FOR CONDUIT INSTALLED UNDER SIDEWALKS AND UNPAVED SURFACES: PROVIDE DIRECTLY-BURIED CONDUIT.
- D. REFER TO CIVIL UTILITY PLAN C-12 FOR SPECIFIC CONDUIT ROUTING. REFER TO TREE PRESERVATION PLANS AND DETAILS (LF-01 THROUGH LF-04) FOR TREE PROTECTION MEASURE REQUIRED DURING DEMOLITION AND CONSTRUCTION.

SPECIFIC NOTES:

- EXISTING TO REMAIN LOAD CENTER "A": 200A MCB-120/240V-1Ø; MANUFACTURED BY SQUARE D, TYPE QO.
- PROVIDE TWO BRANCH CIRCUITS CONSISTING OF (4#10+#10G) IN 1" DIRECTLY BURIED CONDUIT.
- (3) MOUNT WIRING DEVICES TO COLUMNS. SEE LANDSCAPE ARCHITECTURE DETAILS FOR COLUMNS FOR ADDITIONAL INFORMATION. TYPICAL OF 8.
- (4) LIGHTING CONTROL PUSHBUTTON (FURNISHED BY LIGHTING FIXTURE MANUFACTURER, INSTALLED BY CONTRACTOR). PROVIDE 1" DIRECTLY BURIED CONDUIT AND WIRING AS REQUIRED BY LIGHTING FIXTURE MANUFACTURER FOR PUSHBUTTON CONTROL.
- (5) DISCONNECT AND REMOVE EXISTING LIGHTING FIXTURE HEADS. LEAVE INTACT EXISTING CONDUIT, WIRING, POLE BASE, AND POLE FOR REUSE. NEW LIGHTING FIXTURE HEAD AND ACCESSORIES SHALL BE FURNISHED BY THE LIGHTING MANUFACTURER AND INSTALLED BY THE CONTRACTOR.
- 6 CONNECT NEW POLE MOUNTED LIGHTING FIXTURE TO EXISTING WIRING. PROVIDE ADDITIONAL WIRING, MATCHING EXISTING CONDUCTOR SIZE AND QUANTITY, AS NECESSARY FOR INSTALLATION
- $\overline{7}$ LIGHTING POLE FIXTURE CONTROL PANEL (FURNISHED BY LIGHTING FIXTURE MANUFACTURER, INSTALLED BY CONTRACTOR). PROVIDE 3#12 WIRE FROM EXISTING LOAD CENTER "A" TO LIGHTING POLE FIXTURE CONTROL PANEL. REUSE EXISTING RACEWAY.



DEPARTMENT OF PARKS

AND RECREATION

Park Development Division 2100 Clarendon Boulevard, Suite 414 Arlington, VA 22201 Phone: 703.228.3332 Fax: 703.228.3328

20-###-ITB

Project Name and Location

Marcey Road Park Improvements (By Right)

(County Project)

2722 MARCEY ROAD ARLINGTON, VA 22207

Sheet Title ELECTRICAL SITE PLAN

100% Construction Drawings

Approval

Design Manager

Revisions


Date

Date

Designed: MLG Drawn: MLG Checked: вмм


Filename: e1.1.dwg Plotted: 2021-04-26

Scale: AS INDICATED Date: APRIL 26, 2021




Sheet

E1.1



Mir	
A R L I N G T C) N
DEPARTMENT OF PAR	KS
Park Development Division 2100 Clarendon Boulevard, Suite Arlington, VA 22201 Phone: 703.228.3332 Fax: 703.228.3328	414
21-DPR-ITB-6	646
Project Name and Location	'n
Road Park	
Improveme (By Right)	ents
(County Project) 2722 MARCEY ROAD ARLINGTON, VA 222	
Sheet Title ELECTRICAL DETAILS	
100% Construction Draw	ings
100% Construction Draw	ings Date
Approval	
Approval Design Manager	Date
Approval Design Manager Revisions Designed: AW Drawn: AMT Checked: SDT, JKS, MMW, CM	Date
Approval Design Manager Revisions	Date
Approval Design Manager Revisions	Date Date
Approval Design Manager Revisions	Date



SIGNED AND SEALE A VIRGINIA PROFES ARE REQUIRED BY CONTRACTOR SHAL SUBMISSION OF THE

20 1

29

28

-26


25

		TUR	
minaíres JIRE 017/ THIS 014ER JIRE 017/ 000 0000	Arlington County Marcey Road Park Tennis and Basketbal Arlington, VA	A R L I N G T O N	1
Impairement Impairement Impairement Impairement Impairement Impairement	<text></text>	DEPARTMENT OF PARKS AND RECREATION Park Development Division 2100 Clarendon Boulevard, Suite 414 Arlington, VA 22201 Phone: 703.228.3332 Fax: 703.228.3328 DEPARTMENT OF PARKS AND RECREATION Phone: 703.228.3328 Department of the second second second Project Name and Location Marcey Road Park Inport State Second Secon	ts
ED SHOP DRAWINGS (BY SSIONAL ENGINEER) THE MANUFACTURER. L COORDINATE THE E SHOP DRAWINGS.	ILLUMINATION SUMMARY	Design Manager	

Designed: AW Drawn: AMT Checked: SDT, JKS, MMW, CMB

Filename: e-01-150396024 electrical.dwg Plotted: 2021-06-02

Scale: 1" = 25' Date: JUNE 2, 2021





Project Specific Notes: This service will include a Push Button Strobe assembly for Tennis & Basketball.

Materials Checklist

- Contractor/Customer Supplied: A dedicated control circuit must be supplied
- per distribution panel location - If the control voltage is NOT available, a control transformer is required Electrical distribution panel to provide overcurrent protection for circuits
- per full load amps on Circuit Summary by Zone Chart 🗖 Wiring
- Equipment grounding conductor and splices must be insulated (per circuit) Lightning ground protection (per pole), if not Musco supplied
- Electrical conduit wireway system — Entrance hubs rated NEMA 4, must be die-cast zinc, PVC, or copper-free die-cast aluminum
- Mounting hardware for cabinets Breaker lock-on device to prevent unauthorized power interruption to control power and powerline connection (if present)
- wire, if necessary
- at 877/347-3319 to schedule activation of the control system upon completion of the installation.
- Note: Activation may take up to 1 1/2 hours.



T:\203\203076P1V3-0707142732.pdf


T:\203\203076P1V3-0707142732.pdf

SWITCHING SCHEDULE Field/Zone Description Tennis 1-3 Zones Basketball

	CIRCUIT S	UMMAF	RY BY Z	ZONE			
POLE	CIRCUIT DESCRIPTION	# OF FIXTURES	# OF DRIVERS	*FULL LOAD AMPS	CONTACTOR SIZE (AMPS)	CONTACTOR ID	ZONE
T1	Tennis 1-3	2	2	7.5	30	C1	1
T2	Tennis 1-3	2	2	7.5	30	C2	1
Т3	Tennis 1-3	2	2	7.5	30	C3	1
T4	Tennis 1-3	2	2	7.5	30	C4	1
B1	Basketball	2	1	4.0	30	C5	2
B2	Basketball	2	1	4.0	30	C6	2
*Full Load Amps b	ased on amps per driver.						

Control System Summary

Project Information



additional equipment may be required. Contact your Musco sales representative. 5. A single control circuit must be supplied per control system. 6. Size overcurrent devices using the full load amps column of the Circuit Summary By Zone chart- Minimum power factor is 0.9.

NOTE: Refer to Installation Instructions for more details on equipment information and the installation requirements.

> ©1999,2020 Musco Sports Lighting,LLC Form: T-5030-1

Control System Summary

Arlington County Marcey Road Park Tennis And Basketball Relight / 203076 - 203076D Service 1 - Page 3 of 4


CONTROL PC	WER CONSUMPTION
120V Single P	hase
VA loading	INRUSH: 2043.0
of Musco	
011010300	
Supplied	SEALED: 231.8



Control Syster

Arlington County Marcey Road Park Tennis And Basketball Reliable

Control • Link . **Control and Monitoring System**



ID	Description	Wires	(AWG)	(in)	Length (fi
1	Line power to contactors, and equipment grounding conductor	*A	*В	*C	N/A
1	Power-line Communication Connection (dedicated, 20A)	*A	12	*C	N/A
2	Load power to lighting circuits, and equipment grounding conductor	*A	*В	*C	N/A
3	Control power (dedicated, 20A)	3	12	*C	N/A

* Notes:

T:\203\203076P1V3-0707142732.pdf

T:\203\203076P1V3-0707142732.pdf

- A. See voltage and phasing per the notes on cover page. B. Calculate per load and voltage drop.
- C. All conduit diameters should be per code unless otherwise specified to allow for connector size.
- D. Equipment grounding conductor and any splices must be insulated.
- E. Refer to control and monitoring system installation instructions for more details on equipment information and the installation r

IMPORTANT: Control wires (3) must be in separate conduit from line and load power wires (1, 2).

MŬŠCO


Control Syster

Arlington County Marcey Road Park Tennis And Basketball Rel

		PANEL SUMMARY				
CABINET #	CONTROL MODULE LOCATION	CONTACTOR ID	CIRCUIT DESCRIPTION	FULL LOAD AMPS	DIS PA	
1	1	C1	Pole T1	7.53		
1	1	C2	Pole T2	7.53		
1	1	C3	Pole T3	7.53		
1	1	C4	Pole T4	7.53		
1	1	C5	Pole B1	4.00		
1	1	C6	Pole B2	4.00		

		ZONE SCHEDULE		
			CIRCUIT	DES
ZONE	SELECTOR SWITCH	ZONE DESCRIPTION	POLE ID	
Zone 1	1	Tennis 1-3	T1	
			T2	
			Т3	
			Τ4	
Zone 2	2	Basketball	B1	
			B2	

		T
n Summary		ARLINGTON
ight / 203076 - 203076D Service 1 - Page 2 of 4		V I R G I N I A
		DEPARTMENT OF PARKS AND RECREATION
		Park Development Division 2100 Clarendon Boulevard, Suite 414 Arlington, VA 22201 Phone: 703.228.3332 Fax: 703.228.3328
		21-DPR-ITB-646 Project Name and Location
		Marcey Road Park
		Improvements (By Right)
MUSCO Supplied Notes No A-E		(County Project)
No A-E No A-E No C,E		2722 MARCEY ROAD ARLINGTON, VA 22207
R60-100-00_A		Sheet Title CONTROL
requirements.		SYSTEM
requirements.		SUMMARY
		100% Construction Drawings
n Summary		
ight / 203076 - 203076D Service 1 - Page 4 of 4		
		Approval Date
NEL ID (BY BREAKER OTHERS) POSITION (BY OTHERS)		Design Manager
		Revisions Date
CONTACTOR ID C1 C2 C3		
C4 C5 C6		Designed: AW Drawn: AMT Checked: SDT, JKS, MMW, CMB
		Filename: e-01-150396024 electrical.dwg Plotted: 2021-06-02
		Scale: 1" = 25' Date: JUNE 2, 2021
	SIGNED AND SEALED SHOP DRAWINGS (BY	Seal
	A VIRGINIA PROFESSIONAL ENGINEER) ARE REQUIRED BY THE MANUFACTURER. CONTRACTOR SHALL COORDINATE THE SUBMISSION OF THE SHOP DRAWINGS.	MATTHEW M. WEIR Cert. No. 0406001961
		Sheet E5.2



SITE DETAILS - FLATWORK
100% Construction Drawings
Approval Date
Revisions Date
Designed: AW Drawn: AMT Checked: SDT, JKS, MMW, CMB Filename: ^{I-01-150396024 site details - flatwork.dwg Plotted: 2021-06-02 Scale: AS SHOWN Date: JUNE 2, 2021}
Seal MATTHEW M. WEIR Cert. No. 0406001961
Sheet L-01

T

ARLINGTON

VIRGINIA

DEPARTMENT OF PARKS

AND RECREATION

Park Development Division

2100 Clarendon Boulevard, Suite 414

Arlington, VA 22201

Phone: 703.228.3332 Fax: 703.228.3328

21-DPR-ITB-646

Improvements

Project Name and Location

Marcey


Road Park


(By Right)


(County Project)


2722 MARCEY ROAD


ARLINGTON, VA 22207















Path: X:\Rockville\15-0396.024 - Marcey Road Park\05-CAD\















LIVE' & SCH. 80 FVC INSIDE 4' & SCH 40 FVC SLEEVE. THE TO POP-UP DRAIN EMITTER (4/L-09), SEE UTILITY PLANS.		DRINKING FOUNTAIN	2-09
SCH 40 PVC SLEEVE. TIE TO POP-UP DRAIN EMITTER (4/L-09). SEE UTILITY PLANS. 6' 95 COUR SOLID GASKET SEAL COVER #I480 BY EAST JORDAN IRON WORKS (OR APPROVED EQUAL) WATERTITE BASE FLANGE #IA80 BY EAST JORDAN IRON WORKS (OR APPROVED EQUAL) WATERTITE BASE FLANGE #IA80 BY EAST JORDAN IRON WORKS (OR APPROVED EQUAL) DRAIN-BACK WATER (TO DRAIN HUB WITHIN DRINKING FOUNTAIN) WATER SUPPLY LINES TO DRINKING FOUNTAIN. WATERR SUPPLY LINES TO DRINKING FOUNTAIN. WATERRATIONS (TYP) UTILITY VAULT MODEL 444-CUS BY SMITH-MIDLAND PCC (OR APPROVED			
SCH 40 PVC SLEEVE. THE TO POP-UP DRAIN EMITTER (4/L-09). SEE UTILITY PLANS. 6° 95 COUR			
SCH 40 PVC SLEEVE. TIE TO POP-UP DRAIN EMITTER (4/L-09). SEE UTILITY PLANS. 6' 95 COUR SOLID GASKET SEAL COVER #I480 BY EAST JORDAN IRON WORKS (OR APPROVED EQUAL) WATERTITE BASE FLANGE #IA80 BY EAST JORDAN IRON WORKS (OR APPROVED EQUAL) WATERTITE BASE FLANGE #IA80 BY EAST JORDAN IRON WORKS (OR APPROVED EQUAL) DRAIN-BACK WATER (TO DRAIN HUB WITHIN DRINKING FOUNTAIN) WATER SUPPLY LINES TO DRINKING FOUNTAIN. WATERR SUPPLY LINES TO DRINKING FOUNTAIN. WATERRATIONS (TYP) UTILITY VAULT MODEL 444-CUS BY SMITH-MIDLAND PCC (OR APPROVED			
VILLITY VAULT MODEL 444-CUS BY SMITH-MIDLAND PCC (OR APPROVED		SCH 40 PVC SLEEVE. TIE T POP-UP DRAIN EMITTER	-0 LANS. 6" 95
JORDAN IRON WORKS (OR APPROVED EQUAL) WATERTITE BASE FLANGE #1480 BY EAST JORDAN IRON WORKS (OR APPROVED EQUAL) DRAIN-BACK WATER (TO DRAIN HUB WITHIN DRINKING FOUNTAIN) WATER SUPPLY LINES TO DRINKING FOUNTAIN. WATERPROOF ALL PENETRATIONS (TYP) UTILITY VAULT MODEL 444-CUS BY SMITH-MIDLAND PCC (OR APPROVED			MBLY (W
WATERTITE BASE FLANGE #IL40 BY EAST JORDAN IRON WORKS (OR APPROVED EQUAL) DRAIN-BACK WATER (TO DRAIN HUB WITHIN DRINKING FOUNTAIN) WATER SUPPLY LINES TO DRINKING FOUNTAIN. WATERRROOF ALL PENETRATIONS (TYP) UTILITY VAULT MODEL 444-CUS BY SMITH-MIDLAND PCC (OR APPROVED		(OR APPROVED EQUAL)	'-I0 "
DRAIN HUB WITHIN DRINKING FOUNTAIN) WATER SUPPLY LINES TO DRINKING FOUNTAIN. WATERPROOF ALL PENETRATIONS (TYP) UTILITY VAULT MODEL 444-CUS BY SMITH-MIDLAND PCC (OR APPROVED	FLANGE #1480 BY EAS JORDAN IRON WORKS	ST (OR	
WATER SUPPLY LINES TO DRINKING FOUNTAIN. WATERPROOF ALL PENETRATIONS (TYP) 42 UTILITY VAULT MODEL 444-CUS BY SMITH-MIDLAND PCC (OR APPROVED	DRAIN HUB WITHIN		PREVENTOR INSTALL PER ARLINGTON C
UTILITY VAULT MODEL 444-CUS BY	TO DRINKING FOUNTAI WATERPROOF ALL		
	SMITH-MIDLAND P	DDEL 444-CUS BY CC (OR APPROVED	۵.



DRINKING FOUNTAIN VALVES & VAULT




LY (WITH VAULT DRAIN LINE)



2

DRINKING F 3/4" = |'-0"





A-SI-21


4

POP-UP DRA |" = |'-0"

REMOVEABLE SS CAP PLAQUE WITH ¹³ %" HIGH LETTERING: "WATER FOUNTAIN" QUICK CLOSE VALVE %" FLOW REDUCER 9"x8" SS ACCESS DOOR ON OPPOSITE SIDE 1'-6" 9"x8" SS ACCESS DOOR ON OPPOSITE SIDE 10" SS PIPE 8"x7" SS ACCESS DOOR 2-3" OPEN DRAIN HUB 10" STAINLESS STEEL CARRIER ½" PVC DRAIN LINE ³ " WATER CONNECTION	 I. THE FOUNTAIN TO BE MODEL 10145SMSS FR SAN (FREEZE FLOW SANITARY DRINKING FOUNTAIN), WITH OPTIONAL RECESSED HOSE BIB AND LOCK DOOR, FROM MOST DEPENDABLE FOUNTAINS, INC. (MDF) OR APPROVED EQUAL. 2. COLOR: PER SPECIFICATIONS 3. THE FOUNTAIN SHALL INCLUDE FREEZE RESISTANT SANITARY VALVES BYSAME MANUFACTURER. SEE3L-8.1L-09 4. FOUNTAIN TO BE FROST FREE. 5. PLAQUE TO BE PROVIDED BY MANUFACTURER. 6. STAINLESS STEEL PIPE AND ACCESS DOORS (SS; 304 SCHEDULE 10) TO BE POWDER COATED; COLOR TO BE SELECTED FROM FOUNTAIN MANUFACTURER'S FULL LINE OF COLORS BY LANDSCAPE ARCHITECT. 7. ACCESS DOORS CONNECTED TO FOUNTAIN WITH VANDAL RESISTANT BOLTS PROVIDED BY MANUFACTURER. 8. INSTALLATION TO BE COMPLETED IN ACCORDANCE WITH MANUFACTURER'S SPECIFICATIONS. 	DEPARTMENT OF PARKS AND RECREATION Park Development Division 2100 Clarendon Boulevard, Suite 414 Arlington, VA 22201 Phone: 703.228.3322 Fax: 703.228.3328 21-DPR-ITB-6466 Project Name and Location Marcey Road Park Improvements (By Right) (County Project) 2722 MARCEY ROAD ARLINGTON, VA 22207
OUNTAIN	PLAN VIEW A-127	^{Sheet Title} SITE DETAILS – DRINKING FOUNTAIN
4" Ø GRAD - 1% SLOPE MIN. - INVERT ELE	PROVED EQUAL. SH GRADE PVC DRAIN PIPE TYPE-I, DE-I, HIGH DENSITY PVC NOTE: POP-UP EMITTER SHALL BE MODEL NO. 421 BY EVATION NDS, INC. (OR APPROVED EQUAL.).	100% Construction Drawings Approval Date Design Manager
END CONDITION	OLE	Revisions Date
		Designed: AW Drawn: AMT Checked: SDT, JKS, MMW, CMB Filename: ^{LO9-150396024 site details- drinking fountain.dwg Plotted: 2021-06-02 Scale: AS SHOWN Date: JUNE 2, 2021 Seal MATTHEW M. WEIR Cer. No. 0406001961 MATTHEW M. WEIR Cer. No. 0406001961 JUNE 2, 2021}

NOTES:

T A R L I N G T O N



N	CRITERIA
20	NSTRUCTION COD

CONSTRUCTI	ON CODE	
	0.00	
		psf + Structure Dead Weight
	25.00	pst
	1.00	
	1.00	
	1.20	
	1.00	
	21.00	•
	21.00	psf
't =	25.00	psf
	20.00	psf
	115.00	mph
	90.00	mph
	D	
	Steel Ordinary	/ Cantilever Column System
, S _S =	0.119	
r, S ₁ =	0.051	
	В	
	1.00	
=	1.25	
	1.00	
	1.25	
	1.600	
	2.400	
ramenter, S _{MS} =	0.190	
aramenter, S _{M1} =	0.122	
ameter, S _{DS} =	0.127	

	0.102	
	3857.81 lbs	
	391.75 lbs	
	391.75 lbs	
, E _m =	489.69 lbs	


CÓVERWORX


GENERAL:

- 1. PROPER BRACING OF MEMBERS DURING INSTALLATION MUST BE PERFORMED UNTIL COMPLETE.
- 2. ANY MODIFICATIONS TO THE PROPOSED SHELTER NEED TO HAVE PRIOR CONSENT FROM A LICENSED ENGINEER.
- 3. THE INSTALLATION OF THE SHELTER SHALL BE PERFORMED BY SOMEONE OF EXPERIENCE AND COMPETENCE. IT SHALL BE THE RESPONSIBILITY OF THE INSTALLER TO PROPERLY ASSEMBLE THE SHELTER AS SHOWN IN THIS DOCUMENT AND TO CONSTRUCT SHELTER FOUNDATIONS AS SPECIFIED IN SUPPLEMENTAL ENGINEERING DOCUMENTS.
- 4. READ AND UNDERSTAND INSTALLATION INSTRUCTIONS THOROUGHLY BEFORE PROCEEDING WITH THE INSTALLATION PROCESS.
- 5. ALWAYS USE THE INSTALLATION INSTRUCTIONS THAT HAVE SHIPPED WITH THE SHELTER AS THESE ARE THE MOST CURRENT. POSSIBLE CHANGES IN MATERIAL QUANTITIES, LENGTHS, PART LABELS, ETC. MAY HAVE BEEN NECESSARY DURING FINAL SHOP DRAWINGS, EVEN AFTER SEALED ENGINEERING.
- 6. SHOULD THERE BE ANY ERROR IN MANUFACTURING OR INSTALLATION, COVERWORX SHOULD BE NOTIFIED AS SOON AS POSSIBLE. ABSOLUTELY NO FIELD REPAIRS WILL BE HONORED WITHOUT PRIOR AUTHORIZATION OF PROCESS AND COST BY COVERWORX MANAGEMENT.

STEEL & HARDWARE SHOP NOTES:

- 1. ALL STEEL IS TO BE ASTM A-36 EXCEPT STEEL TUBES.
- 2. STEEL TUBES SHALL BE ASTM A-500 GRADE B.
- 3. ALL WELDING IS TO BE DONE IN ACCORDANCE WITH THE LATEST AWS STANDARDS AND ALL WELDS ARE TO DEVELOP FULL STRENGTH OF COMPONENT PARTS. (E7018 ELECTRODES). 4. ALL BOLTS TO BE ASTM A-325.
- 5. ALL BOLTED CONNECTIONS SHOULD FOLLOW THE "TURN-OF-NUT PRETENSIONING" METHOD AS OUTLINED IN THE AISC SPECIFICATIONS. IT SHALL BE THE RESPONSIBILITY OF THE INSTALLER TO MAKE SURE ALL AISC REQUIREMENTS ARE MET.
- 6. ALL STEEL FRAMEWORK WILL RECEIVE A CORROSION PROTECTIVE ZINC-RICH EXPOXY PRIMER FOLLOWED BY A TGIC POLYESTER POWDER COAT, ELECTRO-STATICALLY APPLIED AND CURED AT 400°F.







PAGE 3

FOUNDATION		
Item	Size	Quantity
ANCHOR BOLT BRACING TEMPLATE	12" x 12"	4
F1554 ANCHOR BOLT	3/4-10 x 16"	16
F436 FLAT WASHER	3/4"	16
A563 HEX NUT	3/4-10	32
FRAMING		
Item	Size	Quantity
COLUMN (C 1)	6" x 6" x 3/16" x 8'-11 7/8"	2
COLUMN (C 2)	6" x 6" x 3/16" x 10'-11 1/4"	2
RAFTER BEAM (RA 1)	8" x 6" x 3/16" x 16'-0 1/4"	2
PURLIN (P 1)	8" x 6" x 3/16" x 25'-6"	4
PURLIN (P 2)	8" x 6" x 3/16" x 1'-9"	8
A325 HEX HEAD BOLT	3/4-10 x 1 1/2"	32
A325 HEX HEAD BOLT	3/4-10 x 2"	16
FLAT WASHER	3/4"	48
ROOFING		
Item	Size	Quantity
ROOF PANEL	24 Ga. MULTI-RIB x 16'-2"	10
EAVE TRIM	2" x 2" x 10'-4"	6
RAKE TRIM	2 1/2" x 2" x 10'-4"	4
1 1/4" TEK SCREW	12-24 x 1 1/4" TEK 5	140
7/8" TEK SCREW	1/4-14 x 7/8" TEK 1	225
FINISHING		
Item	Size	Quantity
TOUCH-UP PAINT	-	1

COLORS:

FRAME: ROOF:



PART 2: FRAMING


PAGE 7

COLUMNS (C1) & (C2):

1. LOWER EACH COLUMN ONTO THE ANCHOR BOLTS WITH THE HIGH POINT ORIENTATED CORRECTLY (REFER TO FRAMING PLAN & SECTION FOR LOCATIONS OF COLUMN). PLUMB COLUMNS AND SECURE TO ANCHOR BOLTS WITH 3/4" A563 HEX NUTS AND 3/4" F436 FLAT WASHERS.

RAFTER BEAMS (RA1):

1. RAISE AND BRACE THE RAFTER BEAMS ONTO THE COLUMNS. ATTACH RAFTER BEAMS TO COLUMNS USING (4) 3/4" x 2" HEX BOLTS AND FLAT WASHERS. LEVEL AND BRACE.




A R L I N G T O N
DEPARTMENT OF PARKS AND RECREATION
Park Development Division 2100 Clarendon Boulevard, Suite 414 Arlington, VA 22201 Phone: 703.228.3332 Fax: 703.228.3328
20-###-ITB
Project Name and Location
Marcey
Road Park
Improvements
(By Right)
(County Project)
2722 MARCEY ROAD ARLINGTON, VA 22207
Sheet Title
100% Construction Drawings
Approval Date
Design Manager
Revisions Date
Designed: RH Drawn: RH Checked: BR
Filename: full size sheets.dwg Plotted: 2021-04-26
Scale: Date: APRIL 26, 2021
Seal
A DUNCE AND
JASON M. CONN Lic. No. 40642
🚡 LIC. NO. 40042 👗
LIC. NO. 40042
LLC. No. 40042
A THOMAS IN A LEW CLUB AND A THOMAS AND A TH



PART 2: FRAMING

PURLINS (P1) & (P2):


- 1. RAISE PURLINS INTO PLACE BY ALIGNING THE HOLES IN THE ENDS OF THE PURLINS WITH THE HOLES IN THE SIDES OF THE RAFTER BEAMS.
- 2. ATTACH PURLINS USING (2) 3/4" x 1 1/2" HEX BOLTS AND FLAT WASHERS (FINGER TIGHT ONLY). LEVEL AND BRACE.
- 3. BEFORE TIGHTENING ALL CONNECTIONS VERIFY THE SHELTER IS PROPERLY ALIGNED, LEVEL AND PLUMB.
- 4. TIGHTEN ALL BOLTED CONNECTIONS THROUGHOUT THE ENTIRE STRUCTURE AND DOUBLE CHECK EACH CONNECTION AGAIN AFTER ALL OTHER CONNECTIONS HAVE BEEN TIGHTENED.
- 5. SUPPORTS AND BRACING MAY NOW BE REMOVED.



PURLIN INSTALLATION SCALE: 3/4" = 1'-0"



ROOF PANELS:






PART 4: FINISHING

PAGE 11

MAINTENANCE:

- 1. DURING THE ASSEMBLY PROCESS SOME SCRAPES AND SCRATCHES MAY HAVE OCCURRED. THESE WILL REQUIRE TOUCHING UP. ALSO, OVER TIME, NORMAL USE MAY CREATE MORE SCRATCHES. FOLLOW THE STANDARD PAINT PROCEDURES LISTED ON ANY SPRAY PAINT CAN. HOWEVER, IT IS IMPORTANT TO REMOVE ALL LOOSE PAINT, GREASE, OIL AND/OR RUST BEFORE LIGHTLY SANDING SURROUNDING PAINT FOR GOOD ADHESION. ADDITIONAL MATCHING TOUCH-UP PAINT IS AVAILABLE UPON REQUEST AT AN ADDITIONAL COST.
- 2. CLEAN THE STEEL SURFACES PERIODICALLY USING A MILD CLEANING SOLUTION, AND HAND-WIPE TO MAINTAIN "LIKE NEW" APPEARANCE.
- 3. PERIODICALLY CHECK FOR DEBRIS THAT MAY HAVE GOTTEN STUCK WITHIN THE ROOF TRIM AND REMOVE.



T

ARLINGTON VIRGINIA

DEPARTMENT OF PARKS


AND RECREATION

Park Development Division


2100 Clarendon Boulevard, Suite 414

Arlington, VA 22201

Phone: 703.228.3332







		PROPOSED S	I IMITS OF DISTUPRANCE/	,	The
		LOD/TP	TREE PROTECTION FENCE	4/LF-03	
		LOW	LIMIT OF WORK (NO GROUND DISTURBANCE)		ARLINGTON
_DED WIRE F " MESH OPEN	ENCE (TYP.), IING;		REFORESTATION AREA	7/L-05	VIRGINIA
_VANIZED LANDSCAPE			PARKING LOT 4 6		
"H GALV. WIR	ECT RE TIES 2		FLUSH CURB L-02 L-02 CONCRETE PAVEMENT I/L & SCORE JOINTS 6/		DEPARTMENT OF PARKS AND RECREATION
			TENNIS SEGMENTAL BLOCK WALL	$\left(\begin{array}{c} I\\ L-03\end{array}\right)$	Park Development Division
		0 ô 0	CHAIN LINK FENCE		2100 Clarendon Boulevard, Suite 414 Arlington, VA 22201
			ON CONCRETE CURB L-0 CHAIN LINK 3/L-07 FENCE & GATES 4/L-07		Phone: 703.228.3332 Fax: 703.228.3328
	D D				
			STRIPING WITH 4/L-02 6 WHEEL STOP	/L-02 /L-02	
			ADA ACCESS 1/L-02		21-DPR-ITB-646
	80000000				Project Name and Location
			SHADE STRUCTURE		-
		a fa	A-01 - A-03		Marcey
			NATURE / PARK ACCESS TRAIL - 3" NATURAL		Road Park
			SHREDDED HARDWOOD MU	JLCH	-
			STEPPER 5 BLOCK STEPS L-02		Improvements
N FENC	CE		TENNIS COURT 2		(By Right)
	A-130		PRACTICE WALL L-03 STORM DRAIN INFRASTRU	ICTURE,	(County Project)
			SEE C-12, C-16 & 1/L-03C		
					2722 MARCEY ROAD
					ARLINGTON, VA 22207
		GRADING LEC	GEND		
			PROPOSED MINOR CONTOL PROPOSED MAJOR CONTO		Sheet Title
		43	FROFUSED MAJOR CONTO	UK	PLANTING PLAN
HIS SHEE	T ONLY) - EXCLUDE	S BIORETENTI	ON, LP-02 AND REF	ORESTATION	
QTY	BOTANICAL / COMMON NA	ME	C	CONT SPACING	
1,139 SF	MULCH TRAIL 3" SHREDDED HARDWOOD N	MULCH. ALIGNMENT F		AREA	
268 SF	ARCHITECT NATIVE SEED MIX FOR STE			SEED	
200 31	OR APPROVED EQUAL				
13,542 SF	TURFGRASS SOD / TURF P	PER SPECIFICATIONS	A	AREA	100% Construction Drawings
					Approval Date
					Design Manager
					Revisions Date
					Designed: AW
					Drawn: AMT
					Checked: SDT, JKS, MMW, CMB
					Filename: lp-01-150396024 planting plan.dwg
					Plotted: 2021-06-02
					Scale: 1" = 20' Date: JUNE 2, 2021
					Seal
					ATON' REEL
					MATTHEW M. WEIR Cert. No. 0406001961
					stattal up
					VOSCAPEARCHTE
					JUNE 2, 2021
					Sheet

LP-01



 $Path: L \blue here a constraint the set of the set of$

5


Filename: Planting Plan_Revised 4-28-21 dwg


DETERMINED IN THE FIELD BY THE URBAN FORESTER AND LANDSCAPE ARCHITECT, PRIOR TO INSTALLATION.


PLANT LEGEND	

	PLANT	LEGEND		
Symbol	Scientific Name	Common Name	Size / Notes	Quantity (This Sheet)
Trees				
	Platanus occidentalis	American Sycamore	8-10'	5
Grasses				
	Panicum virgatum 'North Wind'	Blue Switchgrass	1Gal	120
	Panicum virgatum 'Shanandoah'	Switchgrass	1Gal	112
Perennials				
	Coreopsis verticillata	Threadleaf Coreopsis	1Gal	28
	Penstemon digitalis	Beardtongue	1Gal	50

REFER TO STORMWATER MANAGEMENT AND REFORESTATION PLANS FOR FURTHER PLANTING INFORMATION. REFORESTATION PLANT PLACEMENT SHALL BE







THE REFORESTATION PLOT AT MARCEY ROAD PARK IS ON PUBLIC LAND MANAGED BY ARLINGTON COUNTY DEPARTMENT OF PARKS AND RECREATION (DPR). HOWEVER, ARLINGTON COUNTY'S PARKS AND NATURAL RESOURCES AGREES TO MAINTAIN THE REFORESTATION PLOT, IN A MANNER CONSISTENT WITH THE PROVISIONS OF THE VSMP REGULATIONS, FOR A LENGTH OF 5 YEARS AFTER ARLINGTON COUNTY'S DEPARTMENT OF ENVRONMENTAL SERVICES (DES) CERTIFIES THE REFORESTATION PLOT AS A STORMWATER

THE PARK, TRAIL AND TENNIS/BASKETBALL COURT AREAS WILL BE MAINTAINED TO PROVIDE CONTROL OF SEDIMENT RUNOFF AND/OR EROSIVE AREAS. A PLANTING LIST IS PROVIDED ON THIS SHEET (SEE CHART BELOW). INVASIVE PLANT MANAGEMENT/REMOVAL FOR THIS REFORESTATION AREA WILL BE PROVIDED VIA AN AGREEMENT BETWEEN ARLINGTON COUNTY PNR AND ARLINGTON COUNTY DPR. THE GENERAL CONTRACTOR IS

ANNUAL INSPECTIONS ARE REQUIRED AND SHOULD BE CONDUCTED IN THE NON-GROWING SEASON TO MAKE IT EASIER TO SEE THE FLOW PATH. THE INSPECTIONS SHOULD CHECK

- SCOUR AND EROSION DO NOT OCCUR WITHIN THE REFORESTATION AREA.
- VEGETATED DENSITY EXCEEDS AN 90% COVER IN THE REFORESTATION AREA AT
- NO MOWING IS PERMITTED IN THE REFORESTATION AREA AND EDUCATIONAL SIGNAGE AND PHYSICAL DEMARCATION OF THE AREA TO PREVENT ACCIDENTAL

CONSTRUCTION NARRATIVE

- THE ENTIRE CONSTRUCTION SEQUENCE CAN BE FOUND ON THE "SEQUENCE OF CONSTRUCTION NARRATIVE" ON THE EROSION AND SEDIMENT CONTROL PLANS. ADDITIONAL NOTES:
- ONLY VEHICULAR TRAFFIC NECESSARY FOR THE REFORESTATION AREA CONSTRUCTION SHOULD BE ALLOWED WITHIN 10 FEET OF THE REFORESTATION AREA.
- CONSTRUCTION ENTRANCE SHOWN ON THE EROSION AND SEDIMENT CONTROL PLANS. THE SCE IS ACCESSIBLE FROM MARCEY ROAD. • IF EXISTING TOPSOIL IS STRIPPED DURING GRADING, IT SHALL BE STOCKPILED AND STABILIZED FOR LATER USE.
- PRESERVATION PLANS) AROUND THE PERIMETER.

REFORESTATION NOTES:

REFORESTATION IN MARCEY ROAD PARK REFORESTATION AREA: 6,650 SQUARE FEET = 0.15 ACRES RPA DELINEATION: DETERMINATION IS 100' FROM STREAM BANK, PLUS ANY ADJACENT >25% SLOPES.

- REFORESTATION PLANTING NOTES CONTRACTOR TO CONTACT ARLINGTON COUNTY URBAN FORESTER 72 HOURS PRIOR TO PLANTING TO SCHEDULE INSPECTION OF THE TREE STOCK. REMAINING TURF GRASS IN SEED BANK RETURNS.
- 3. ACCESS TO THE REFORESTED PLANTING AREA WILL BE FROM MARCEY ROAD. THIS ACCESS LOCATION WILL BE VERIFIED AT THE PRE-CONSTRUCTION MEETING.
- CONTRACTOR WITH COUNTY STAFF ON-SITE. CARE SHALL BE TAKEN TO AVOID ROOTS OF EXISTING TREES.
- MAINTENANCE. THIS SPACING WILL BE DETERMINED IN THE FIELD. DO NOT STAKE NEWLY PLANTED TREES.
- AND GRASSES SHALL BE PLANTED WITHIN SMALLER X-SHAPED CUTS.
- 9. AFTER PLANTING TREES, SHRUBS, PERENNIALS AND GRASSES, THE CONTRACTOR SHALL OVERSEED WITH ERNST SEED MIX ERNMX-140 "PARTIALLY SHADED AREA ROADSIDE MIX (OR APPROVED EQUAL). SEE SEED MIX BELOW. 10. NEWLY PLANTED TREES TO BE WATERED FOR TWO YEARS AFTER INSTALLATION (UNDER A SEPARATE CONTRACTOR FROM THE GENERAL CONTRACTOR).

COVER GOALS

- WHEN CONSTRUCTION IS COMPLETE, NO BARE SOIL AND 80% NON-TURF COVER SHALL BE PROVIDED.
- NO BARE SOIL OR TURF COVER WITH (GROUND LAYER TO BE VEGETATED OR WITH NATURAL MATERIALS SUCH AS LEAF LITTER AND MULCH) 90% DENSITY WITHIN 5 YEARS. COMPLETION.

PLAN NARRATIVE

THE PURPOSE OF THIS PROJECT IS TO REFOREST A 0.15 ACRE AREA ON THE NORTH SIDE OF THE RENOVATED MARCEY ROAD PARK. THE REFORESTATION AREA ITSELF IS ALSO WITHIN THE RPA. THE PROPOSED REFORESTATION AREA INCLUDES A SECTION OF RPA THAT IS NOT CURRENTLY FORESTED, BUT RATHER MOWED TURF GRASS. AS PART OF THE MARCEY ROAD PARK IMPROVEMENTS, THE EXISTING TURF WILL BE REMOVED. THE REMAINING GROUND SURFACE AND ANY SURROUNDING TURF GRASS/INVASIVE SPECIES THAT ARE WITHIN THE LIMITS OF DISTURBANCE SHALL UNDERGO TWO FOLIAR HERBICIDE APPLICATIONS TO KILL THE REMAINING UNDESIRED VEGETATION. THE AREA WILL BE DENSELY PLANTED WITH NATIVE TREES, SHRUBS AND UNDERSTORY PLANTS AND OVERSEEDED WITH A NATIVE GRASS/PERENNIAL SEED MIX. THE REFORESTATION GOALS INCLUDE ESTABLISHING 90% NATIVE COVER BY THE END OF 5 YEARS AFTER PLANTING.

FUNDING FOR 5 YEARS OF MAINTENANCE WILL NOT BE INCLUDED IN THE GENERAL CONTRACTOR'S CONSTRUCTION COST. MAINTENANCE AND OVERALL MANAGEMENT RESPONSIBILITY SHALL BE BY PNR. INFORMATIONAL SIGNAGE AND PERIMETER FENCING IS INCLUDED IN THE PROJECT. THE GENERAL CONTRACTOR IS NOT RESPONSIBLE FOR INVASIVE SPECIES REMOVAL.

BOTANICAL/COMMON	QTY	CONTAINER	CALIPER/ SIZE	SPACING
OVERSTORY/CANOPY TREES			1	1
QUERCUS BICOLOR / SWAMP WHITE OAK	2	B & B	1.5 - 2" CAL	I5' O.C.
NYSSA SYLVATICA / BLACK GUM	2	B&B	1.5 - 2" CAL	I5' O.C.
LIQUIDAMBAR STYRACIFLUA / SWEETGUM	2	B & B	1.5 - 2" CAL	I5' O.C.
CARYA TOMENTOSA / MOCKERNUT HICKORY	2	B & B	1.5 - 2" CAL	I5' O.C.
PLATANUS OCCIDENTALIS / AMERICAN SYCAMORE	3	B & B	1.5 - 2" CAL	I5' O.C.
QUERCUS FALCATA / SOUTHERN RED OAK	2	B & B	1.5 - 2" CAL	15' O.C.
QUERCUS RUBRA / NORTHERN RED OAK	2	B & B	1.5 - 2" CAL	15' O.C.
	TOTAL 15			
UNDERSTORY/ORNAMENTAL TREES				
AMELANCHIER CANADENSIS / CANADIAN SERVICEBERRY	7	B & B	6-7' HEIGHT	I0-I2' O.C.
SASSAFRAS ALBIDUM / SASSAFRAS	7	B & B	6-7' HEIGHT	10-12' O.C.
CERCIS CANADENSIS / EASTERN REDBUD (SINGLE STEM)	8	B & B	6-7' HEIGHT	10-12' O.C.
CORNUS FLORIDA / FLOWERING DOGWOOD	8	B & B	6-7' HEIGHT	10-12' 0.C
	TOTAL 30			
SHRUBS	I _	7.6.1		
HAMAMELIS VIRGINIANA / COMMON WITCH HAZEL	21	3 GAL	15-18"	10' O.C.
SAMBUCUS CANADENSIS / AMERICAN BLACK ELDERBERRY	21	3 GAL	15-18"	8' O.C.
ILEX VERTICILLATA / WINTERBERRY	20	3 GAL	15-18"	8' O.C.
PHYSOCARPUS OPULIFOLIUS / NINEBARK	20	3 GAL	15-18"	4-6' O.C.
LINDERA BENZOIN / SPICEBUSH	21	3 GAL	15-18"	8' O.C.
VACCINIUM ANGUSTIFOLIUM / LOWBUSH BLUEBERRY	20	3 GAL	15-18"	4-6' O.C.
VACCINIUM CORYMBOSUM / HIGHBUSH BLUEBERRY	20	3 GAL	15-18"	8' O.C.
VIBURNUM DENTATUM / VIBURNUM	21	3 GAL	15-18"	5-7' O.C.
TOTAL	164			
н	IERBACEOUS PERENNIALS AN	ID GRASSES		
ANDROPOGON VIRGINUCUS / BROOMSEDGE BLUESTEM	75		NUART	18-20" 0.0
AQUILEGIA CANADENSIS	75	QUART		18-20" O.C
ASCLEPIAS INCARNATA	50	(QUART	18-20" O.C
ASCLEPIAS SYRIACA	50	(QUART	18-20" O.C
ASCLEPIAS TUBEROSA	50	(QUART	18-20" O.C
ASCLEPIAS VERTICILLATA	50	QUART		18-20" O.C
ASTER NOVI-BELGII / NEW YORK ASTER	50	QUART		18-20" O.C
SCHIZACHYRIUM SCOPARIUM	50	QUART		18-20" O.C
SORGHASTRUM NUTANS	50		QUART	18-20" 0.C
ELYMUS VIRGINICUS / VIRGINIA WILD RYE	50		QUART	18-20" O.C
ERAGRAGROSTIS SPECTACTABOLIS	75		QUART	18-20" O.C
PYCNANTHEMUM MUTICUM	75		QUART	18-20" O.C
RUDBECKIA FULGIDA / BLACK-EYED SUSAN	50		QUART	18-20" O.C.
SCHIZACHYRIUM SCOPARIUM	75			18-20" O.C.
	50			18-20" O.C.
SOLIDAGO CAESIA				10-20 0.0
SOLIDAGO CAESIA SYMPHYOTRICHUM NOVAE-ANGLIAE / NEW ENGLAND ASTER	75		QUART	18-20" O.C.

• VEHICULAR ACCESS FOR THE PLANT INSTALLATION SHALL OCCUR FROM ROOT PROTECTION MATTING SHOWN ON TREE PRESERVATION PLAN - PHASE I (LF-0I) AND THE STABLIZED

• THE PROPOSED REFORESTATION AREA SHALL HAVE FILTER LOGS/SILT FENCE (SEE EROSION & SEDIMENT CONTROL PLANS) AND TREE PROTECTION FENCE (SEE TREE

2. INVASIVE PLANT MANAGEMENT (IMP) IS CURRENTLY BEING CARRIED OUT UNDER A SEPARATE CONTRACT AND WILL BE EXPANDED TO INCLUDE THIS NEWLY REFORESTED AREA. ANY INVASIVE VEGETATION THAT REMAINS IN THE REFORESTATION AREA SHALL BE TREATED WITH A FOLIAR APPLICATION OF HERBICIDE AND TREATED A SECOND TIME AFTER ANY

.. REFORESTATION PLANTING AND ASSOCIATED SITE WORK (SUCH AS SOIL IMPROVEMENTS) ARE THE RESPONSIBILITY OF THE MARCEY ROAD PARK GENERAL CONTRACTOR. 5. THE EXISTING SOILS WHERE REFORESTATION OCCURS SHALL BE AMENDED WITH LEAF COMPOST & TOPSOIL AND SHALL BE THOROUGHLY WATERED. SEE SPECS.

. PRIOR TO PLANTING OF THE REFORESTATION AREA, CONTRACTOR SHALL INSTALL BIODEGRADABLE AND 100% ALL-NATURAL ORGANIC STRAW EROSION CONTROL MAT (BY GEI WORKS, OR APPROVED EQUAL) ATOP THE AMENDED SOILS WITHIN THE ENTIRE PROPOSED REFORESTATION AREA. THE MATTING SHALL NOT INCLUDE ANY SYNTHETIC MATERIALS OR PLASTICS. SECURE MATTING TO THE GROUND WITH BIODEGRABLE STAKES ON A 3' x 3' GRID IN ACCORDANCE WITH MANUFACTURER'S RECOMMENDATIONS. THE PURPOSE OF THE MATTING IS TO SUPPRESS COMPETING VEGETATION GROWTH, RETAIN SOIL MOISTURE AND REDUCE EROSION. REFORESTATION PLANTINGS SHALL BE LAID OUT IN THE FIELD BY

7. TREES MAY BE SPACED SLIGHTLY CLOSER THAN OPTIMAL SPACING FOR STREET TREES AS IS NOTED ON PLANTING LIST TO ENCOURAGE LESS VEGETATION COMPETITION AND 8. WHEN PLANTING PROPOSED TREES AND SHRUBS, CONTRACTOR SHALL MAKE AN X-SHAPED CUT IN THE MATTING IN ORDER TO DIG A HOLE TO RECEIVE THE PLANT. PERENNIAL

• WHEN CONSTRUCTION IS COMPLETE, DPR AND/OR THEIR THIRD PARTY INSPECTOR SHALL PROVIDE A SIGNED LETTER CERTIFYING THAT: I) THE COVERAGE REQUIREMENT IS MET AND 2) THE PLANT STOCK, LOCATIONS, QUANTITIES, SPECIES, NATIVE SEEDING, ETC. MEETS THE REQUIREMENTS OF THIS PLAN. THIS LETTER SHALL BE ADDRESSED TO CHRISTIN JOLICOEUR, WATERSHED PLANNER, ARLINGTON COUNTY DEPARTMENT OF ENVIRONMENTAL SERVICES (DES) CHESAPEAKE BAY DEPT

• ARLINGTON COUNTY PARKS AND NATURAL RESOURCES DIVISION (PNR) TO PROVIDE ASSESSMENT AND MANAGEMENT OF REFORESTED AREA FOR 5 YEARS AFTER PROJECT



DEPARTMENT OF PARKS AND RECREATION

Park Development Division 2100 Clarendon Boulevard, Suite 414 Arlington, VA 22201 Phone: 703.228.3332 Fax: 703.228.3328

21-DPR-ITB-646

Project Name and Location


Marcey Road Park Improvements (By Right)

(County Project)

2722 MARCEY ROAD ARLINGTON, VA 22207

Sheet Title

REFORESTAT	ION
100% Construction Drawi	ngs
Approval Design Manager	Date
Revisions	Date
Designed: AW Drawn: AMT Checked: SDT, JKS, MMW, CM	IB
Filename: ref-01-150396024 reforestation plan.de Plotted: 2021-06-02 Scale: 1" = 10' Date: JUNE 2, 2021	
Seal MATTHEW M. WEIR Cert. No. 0406001961	
sheet REF-01	



Path: X:\Rockville\15-0396.024 - Marcey Road Park\05-CAD\

N	D

T CONCRETE	(3)
ALL	L-02

DETAIL

2/L-04

I/L-04

PROPOSED SITE LEGEND

LOD/TP	LIMITS OF DISTURBANCE/ TREE PROTECTION FENCE 4/LF-03
LOW	LIMIT OF WORK (NO GROUND DISTURBANCE)
<u>===</u>	REFORESTATION AREA 7/L-05 SEE SHEET REF-01
	PARKING LOT 4 6 FLUSH CURB L-02 L-02
	CONCRETE PAVEMENT I/L-01 2/L-01 & SCORE JOINTS 6/L-01 3/L-01
· · · · · · · · · · · · · · · · · · ·	TENNIS SEGMENTAL
ee	CHAIN LINK FENCE
	CHAIN LINK 3/L-07 5/L-07 FENCE & GATES 4/L-07 2/L-08
	PARKING SPACE I/L-02 2/L-02 STRIPING WITH 4/L-02 6/L-02 WHEEL STOP
	ADA ACCESS 1/L-02 AISLE 6/L-02
	SHADE STRUCTURE A-01 - A-03
	NATURE / PARK ACCESS TRAIL - 3" NATURAL SHREDDED HARDWOOD MULCH
	STEPPER 5 BLOCK STEPS L-02
······	TENNIS COURT

MULCH PRACTICE WALL U-03 STORM DRAIN INFRASTRUCTURE, SEE C-12, C-16 & I/L-03C

SITE FURNISHINGS SCHEDULE

<u>SYMBOL</u>	DESCRIPTION	DETAIL		
	1964 WORLD'S FAIR BENCH	6/L-05		
-	BIKE RACK (SURFACE MOUNT)	3/L-05		
R	RECYCLE RECEPTACLE	2/L-05		
\bigcirc	TRASH RECEPTACLE	I/L-05		
	PICNIC TABLE	4/L-05		
ADA ADA	ADA PICNIC TABLE	4/L-05		
	ADA DRINKING FOUNTAIN WITH BOTTLE FILLER, VAULT & EQUIPMENT	2/L-09		
	1964 WORLD`S FAIR BENCH (BACKLESS)	I/L-06		
ATHLETIC COURTS SCHEDULE				
SYMBOL	DESCRIPTION	DETAIL		

SPORT COURT LIGHT SHEETS FIXTURE RETROFIT. EXISTING E-0.1 POLES TO REMAIN IN PLACE. THROUGH E5.2 REPLACE CURRENT METAL HALIDE LIGHTS WITH NEW TOP FITTER, ELECTRICAL COMPONENTS, DRIVER AND LED FIXTURES. SEE ELECTRICAL & LIGHTING PLANS FOR ADDITIONAL REQUIREMENTS. PUSH BUTTON PEDESTAL FOR 2/E5.0 SPORT COURT LIGHTING. SEE 1/E5.0 ⊜ ELECTRICAL PLANS FOR ADDITIONAL INFORMATION. BASKETBALL HOOP 4/L-06





DEPARTMENT OF PARKS AND RECREATION

Park Development Division 2100 Clarendon Boulevard, Suite 414 Arlington, VA 22201 Phone: 703.228.3332 Fax: 703.228.3328

21-DPR-ITB-646

Project Name and Location

Marcey Road Park Improvements (By Right)

(County Project)

2722 MARCEY ROAD ARLINGTON, VA 22207

Sheet Title BID ALTERNATES

100% Construction Drav	vinas
	5
Approval	Date
Design Manager	
Revisions	Date
Designed: AW Drawn: AMT Checked: SDT, JKS, MMW, C	СMB
Filename: c-09-150396024 s plan.dwg Plotted: 2021-06-02	ite
Scale: " = 20' Date: JUNE 2, 2021	
Seal MATTHEW M. WEIR Cert. No. 0406001961	A
Sheet ALT-O	