



Front Street UG System Upgrade Project #1919
Materials – Phase 1
ADDENDUM 2
Clarification of material requirements.

The following are answers to questions received:

For Material Items 7 & 8, wall supports, 1-5/8" x 7/8" in 12 gauge is an acceptable alternative to the listed 1-5/8" x 13/16" in 12 gauge. The wall supports shall be stainless steel with no finish.

Material Item 26, 15 kV URD Cable 1/0 AWG AL, shall be 175 mil as noted in Section 16124, 3.2 CABLE:

“Insulation rating shall equal or exceed 100 percent of the rated system voltage class.”

For Material Items 27 & 28, 350 and 500 kcmil AL Single Conductor Secondary UD cable, standard XLP is acceptable.