

RFP 18-0002 Questions and Answers #2

1. On the walk you stated that you would provide the estimated footages for the Wire mold/Panduit for the classrooms or per site, Will you be able to provide these numbers?

WIRE MOLD ESTIMATES PER ROOM WILL BE AS FOLLOWS:

16' PER ROOM, 1 Elbow, 1 T, 2 Caps, 5 Device Brackets, 5 Dual Port Data Plates, 5 Receptacle

2. Will you allow Riser cable or do you require Plenum? **RISER**
3. Your specifications call out for “10Gb up to 100 meters” which is CAT6A, is this required for all cabling/drops and ports that we will be installing? **ALL CABLING REQUIREMENTS ARE THE SAME FOR ALL DROPS.**
4. Are patch cords required? **NO**