

LaGRANGE THREAD PHASE 7B- CLOCKTOWER_KEX MILL TO HUNNICUTT ST - BID FORM PROPOSAL

Section A: Roadway / Trail					
Item Number	Quantity	Units	Item Description	Unit Price	Cost
140-1000	1	LS	MOBILIZATION		
150-1000	1	LS	TRAFFIC CONTROL		
210-0100	1	LS	GRADING COMPLETE (INCLUDING DEMOLITION, STORM SEWER REMOVAL, STORM SEWER SYSTEM CLEANOUT, & TREE REMOVAL)		
310-5060	10000	SY	GR AGGR SUBBASE CRS, 6 IN, INCL MATL		
402-1802	1	LS	ASPHALT PAVEMENT, CUT & PATCH, PER GDOT STD. 1401		
402-3910	300	SY	RECYCLED ASPH CONC 12.5MM SUPERPAVE GP 2 ONLY, INCL BITUM MTL & H LIME, PER PAVEMENT OVER GUTTER DETAIL. DEPTH VARIES		
441-0018	22	SY	CONC DRIVEWAY APRON, 8 IN PER GDOT STD. A2 (Labor, form, finish only) Materials furnished by city		
441-0105	10000	SY	CONCRETE TRAIL, SIDEWALK, CL 3000 PSI, 5 IN, 10-12 FT, INCL ADA RAMPS, POCKET PARKS, & BOARDWALK OVERLOOK SLAB (Labor,form,finish only) Concrete finished by City		
444-1000	7,850	LF	SAWED JOINTS IN EXISTING PAVEMENTS, (Space btw joint to equal trail width)		
441-5002	30	LF	CONCRETE HEADER CURB, 6 IN, TP. 2 (Labor, form, finish only) Concrete furnished by City		
441-6012	500	LF	CONC CURB & GUTTER, 6 IN X 24 IN, TP 2. (Labor, form, finish only) Concrete furnished by City		
432-0200	300	SY	MILL EXISTING ASPHALT SURFACE, PER PAVEMENT OVER GUTTER DETAIL, MILL DEPTH VARIES		
643-1462	4,500	LF	CHAIN LINK FENCE, 6' TO 8' HT PER PLANS, BLACK		
643-8400	500	LF	2 PANEL WOOD FENCE (INC. POST AND RAILS)		
999-5200	700	SF	4"X8" DETECTABLE ADA PAVERS (RED)		
900-0526	18	EA	FIXED STEEL BOLLARDS		
900-0527	9	EA	STEEL REMOVABLE BOLLARDS		
999-3800	2	EA	RECTANGULAR RAPID FLASHING BEACON SYSTEM (SPUR STA 205+00, MAINLINE STA 47+50). EACH RRFB SYSTEM IS COMPRISED OF (2) DOUBLE-SIDED POLE ARRANGEMENTS PER DETAIL 3/CD-03		
611-8120		EA	ADJUST UTILITY TO GRADE (WATER, GAS, ELECTRIC, ETC.)		not in contract- city responsibility
		EA	ADJUST/RELOCATE EXISTING AMENITIES (MAIL BOXES, SIGNS ETC.)		not in contract- city responsibility
754-1050		EA	BENCH		not in contract- city responsibility
754-4000		EA	WASTE RECEPTACLE UNIT		not in contract- city responsibility
Section A Sub Total					

Section B: MUTCD Signs and Pavement Markings					
636-1014	28	SF	MUTCD HIGHWAY SIGNS		
636-3010	100	LF	MUTCD HIGHWAY SQUARE POSTS, 14 FT PER GDOT		
635-1000	40	LF	PERMANENT TIMBER TYPE BARRICADE		
652-5301	1000	LF	THERMO SOLID TRAFFIC STRIPE, 8 IN WHITE, 10'-12' WIDE (GDOT CROSSWALKS)		
653-1500	125	LF	THERMO SOLID TRAFFIC STRIPE, 4 IN, WHITE (CROSS HATCH)		
653-1704	30	LF	THERMO SOLID TRAFFIC STRIPE, 24 IN, WHITE (STOP BARS)		
652-6501	7,850	LF	MMA SKIP STRIPING (YELLOW) (TRAIL CL) , 4 IN, STRIPE LENGTH AND GAP TO EQUAL TRAIL WIDTH		
636-1042		SF	THREAD TRAIL SQUARE MATL 0.125 ALUM. DIRECT PRINT		not in contract- city responsibility
636-1043		LF	THREAD TRAIL SQUARE 3"X3" POST		not in contract- city responsibility
Section B Sub Total					

Section C: Structural Slabs/Retaining Walls					
Item Number	Quantity	Units	Item Description	Unit Price	Cost
445-1003	2	LS	10' X 12' CONC. STRUCTURAL SLAB, INCL REINF & POST & CABLE HANDRAIL (STA 43+75)		
502-1200	1	LS	SPCL DESIGN BOARDWALK OVERLOOK, INCL REINF, HANDRAIL, & TURNDOWN WALL ABUTMENT (STA 7+00)		
Section C Sub Total					

Section D: Tree Protection					
Item Number	Quantity	Units	Item Description	Unit Price	Cost
643-8200	3,500	LF	ORANGE CONSTRUCTION LIMITS/TREE FENCE, 4 FT		
222-1002	250	SY	#57 STONE (CLEAN), 6 IN, (ROOT BRIDGING AREAS AND GRAVEL DRIVE AT STA 5+50)		
603-7000	250	SY	PLASTIC FILTER FABRIC (ROOT BRIDGING AREAS)		
Section D Sub Total					

Section E: Erosion Control / Storm Drainage					
Item Number	Quantity	Units	Item Description	Unit Price	Cost
163-0300	11	EA	CONSTRUCTION EXIT		
163-0301	1	LS	EROSION CONTROL INSPECTIONS, WEEKLY AND MONTHLY		
	1	LS	TEMPORARY REFUELING AREA		
	1	LS	TEMPORARY CONC. WASHDOWN		
	175	LF	CONSTRUCT, MAINTAIN, & REMOVE 18" FILTER MEDIA SOCK CHECK DAMS		
163-0529	11500	LF	CONSTRUCT AND REMOVE TEMPORARY SEDIMENT BARRIER, TYPE NS		
	5000	LF	CONSTRUCT AND REMOVE TEMPORARY SEDIMENT BARRIER, TYPE S		
	275	LF	CONSTRUCT, MAINTAIN, & REMOVE TEMPORARY SEDIMENT BARRIER J-HOOKS		
163-0550A	7	EA	CONSTRUCT AND REMOVE INLET SEDIMENT TRAP, TYPE F		
165-0105	1	LS	MAINTENANCE OF INLET SEDIMENT TRAP		
165-0010	1	LS	MAINTENANCE OF TEMPORARY SEDIMENT BARRIER		
165-0101	1	LS	MAINT OF CONSTRUCTION EXIT		
167-1000	1	LS	WATER QUALITY MONITORING AND SAMPLING		
441-0105	250	SY	CONCRETE SPILLWAY, CL 3000 PSI, 5 IN, (Labor,form,finish only) Concrete finished by City		
611-8020	5	EA	ADJUST DRAIN TO GRADE		
	2	EA	TIE PROPOSED 24" HDPE TO EXISTING STRUCTURE		
	3	EA	TIE PROPOSED 18" HDPE TO EXISTING STRUCTURE		
	1	EA	TIE PROPOSED 24" RCP TO EXIST. 24" RCP		
	2	EA	18" FLARED END SECTION		
	2	EA	24" FLARED END SECTION		
	1	EA	18" ENERGY DISSIPATING HEADWALL		
	1	EA	HEADWALL W/ CONC. APRON FOR CONCRETE BOX CULVERT		
	12	LF	CONCRETE BOX CULVERT EXTENSION		
550-1180	80	LF	STORM DRAIN PIPE, 18 IN, HDPE, H 1-10		
550-1240	140	LF	STORM DRAIN PIPE, 24 IN, HDPE, H 1-10		
550-1240	36	LF	STORM DRAIN PIPE, 24 IN, RCP, H 1-10		
603-1012A	175	SY	ROCK RIPRAP, GADOT TYPE 3 EQUIVALENT RIVER ROCK (12" THICK)		
603-1012B	115	SY	ROCK RIPRAP, GADOT TYPE 3 (12" THICK)		
603-1012C	30	SY	ROCK RIPRAP, GADOT TYPE 1		
603-1224	80	SY	GROUTED ROCK RIPRAP, GDOT TYPE 1		
603-2997	400	SY	FILTER BLANKET		
700-6910	6.5	AC	PERMANENT GRASSING		
700-8000	6.5	AC	FERTILIZER MIX GRADE		
716-2000	8500	SY	EROSION CONTROL MATS, SLOPES		
Section E Sub Total					

Section F: Allowances					
Item Number	Quantity	Units	Item Description	Unit Price	Cost
700-9900		ALLOW	LANDSCAPE (TREES, PLANTS, +1 YR MAINT)		not in contract- city responsibility
999-1000	1	ALLOW	MISCELLANEOUS CONSTRUCTION	\$100,000.00	\$100,000.00
Section F Sub Total					\$100,000.00

Section A Sub Total					\$0.00
Section B Sub Total					\$0.00
Section C Sub Total					\$0.00
Section D Sub Total					\$0.00
Section E Sub Total					\$0.00
Section F Sub Total					\$100,000.00
TOTAL ESTIMATED CONSTRUCTION COST					

LS	LUMP SUM
SY	SQUARE YARD
CY	CUBIC YARD
LF	LINEAR FOOT
EA	EACH
ALLOW	ALLOWANCE
SF	SQUARE FOOT
GLF	GALLON PER LINEAR FOOT