



St. Johns River Water Management District

Ann B. Shortelle, Ph.D., Executive Director

4049 Reid Street • P.O. Box 1429 • Palatka, FL 32178-1429 • 386-329-4500
On the internet at www.sjrwmd.com.

DATE: May 17, 2019
TO: Prospective Respondents
FROM: Pam Paulk, Contracts Administrator
SUBJECT: Addendum #1 to Invitation for Bids 34470 Lake Apopka North Shore Internal Levee Improvements

As a result of inquiries, the following clarifications/changes are provided for your information. Please make all appropriate changes to your bid documents. Note: changes are reflected with original language shown with strike-through and new language is underlined.

MODIFICATION

1. Attachment F, ST. Johns River Water Management District Upper Ocklawaha River Basin/Lake Apopka North Shore Internal Levee Improvements Plans, April 30, 2019; Sheet C-2 – Notes Section LIMEROCK ROADWAY #1 – GENERAL FILL LANGUAGE shall be deleted and replaced with the following:

GENERAL FILL: FILL SHALL CONSIST OF SOILS CLASSIFIED AS FINE SAND (SP), SLIGHTLY SILTY SAND (SP-SM), SLIGHTLY CLAYEY SAND (SP-SC), SILTY SAND (SM), AND CLAYEY SAND (SC). SOILS WITH FINES CONTENT GREATER THAN 20 PERCENT SHALL BE TO BE APPROVED BY THE DISTRICT IN ADVANCE. MORE MOISTURE SENSITIVE SOILS WILL BE DIFFICULT TO PLACE AND COMPACT.

THE CONTRACTOR SHALL PROVIDE A SUBMITTAL FOR THE GENERAL FILL MATERIAL TO THE DISTRICT WITH THE FOLLOWING INFORMATION:

USCS SOIL CLASSIFICATION
MOISTURE CONTENT
PERCENT PASSING NO. 200 SEIVE
LIQUID AND PLASTIC LIMITS

QUESTIONS AND ANSWERS

- Q.1. Attachment J, FDEP Permit references pump station, ditch block and temporary cofferdam work. Is this work to be included as part of bid no. 34470? This work is not referenced in Attachment F, Improvement Plan Sheets C-1 through C-5. Please clarify this work is not to be included as part of bid No. 34470.
- A.1. The FDEP and Army Corps permits were broader permits that covered more work than is included in bid No 34470 Attachment F. In particular the pump station, ditch blocks and temporary coffer dams shown in the permits are not part of bid 34470. However, some of the work included in Attachment F is regulated and addressed in the permits. Specifically, any fill and associated wetland impacts within the existing canals that results from the levee improvements. Therefore, the contractor should be aware of the conditions of the permits as they may apply.

- Q.2. The Cost Schedule shows 4500 SF of sodding. Should the Unit be SY instead of SF?
A.2. No the unit is square feet as shown on the Cost Schedule

NOTE: The Bid Opening remains on June 6, 2019, 2:00 PM.

Please acknowledge receipt of this Addendum on the BID FORM provided in the bid package.

If you have any questions, please call me at (386) 329-4469 or e-mail ppaulk@sjrwmd.com.