





ENGINEER DEPARTMENT OF ENVIRONMENTAL SERVICES

FACILITIES & ENGINEERING DIVISION ENGINEERING BUREAU 2100 CLARENDON BOULEVARD, SUITE 813 ARLINGTON, VA 22201 PHONE: 703.228.3629 FAX: 703.228.3606 WWW.ARLINGTONVA.US

OWNER DES/DTD/PLAN

CONTRACTOR TO BE DETERMINED


LOCATION MAP



DEPARTMENT OF ENVIRONMENTAL SERVICES FACILITIES & ENGINEERING DIVISION ENGINEERING BUREAU 2100 CLARENDON BOULEVARD, SUITE 813 ARLINGTON, VA 22201 PHONE: 703.228.3629 FAX: 703.228.3606

COPYRIGHT © 2021 ARLINGTON COUNTY VIRGINIA - ALL RIGHTS RESERVED

SEAL



APPROVALS DATE

Table with columns for Approvals and Date, listing Amy Plawn, Edward Sanders, and other project managers with their respective dates.

REVISIONS DATE

CONSTRUCTION DRAWINGS FOR: 14TH ST N. & N. VEITCH ST. 14TH ST N. @ N. VEITCH ST. PROJECT NUMBER: P31D

GENERAL NOTES:

GENERAL CONSTRUCTION NOTES

- 1. ALL CONSTRUCTION WORK FOR THIS PROJECT SHALL CONFORM TO THE ARLINGTON COUNTY DEPARTMENT OF ENVIRONMENTAL SERVICES, CONSTRUCTION STANDARDS AND SPECIFICATIONS... 2. ALL CONSTRUCTION AND WORK ACTIVITIES SHALL COMPLY WITH THE VIRGINIA WORK AREA PROTECTION MANUAL... 3. THE CONTRACTOR SHALL IMMEDIATELY NOTIFY THE PROJECT OFFICER OF ANY DISCREPANCIES BETWEEN ACTUAL FIELD CONDITIONS AND THE APPROVED PLANS... 4. THE CONTRACTOR SHALL CONTACT "MISS UTILITY" AT 811 FOR MARKING THE LOCATIONS OF EXISTING UNDERGROUND UTILITIES... 5. THE CONTRACTOR SHALL BE RESPONSIBLE FOR LAYING OUT THE WORK AND SHALL RETAIN A PROFESSIONAL LAND SURVEYOR LICENSED IN THE COMMONWEALTH OF VIRGINIA TO PROVIDE ALL NECESSARY CONSTRUCTION LAYOUTS AND ESTABLISH ALL CONTROL LINES, GRADES, AND ELEVATION DURING CONSTRUCTION... 6. THE LOCATION OF ALL EXISTING UTILITIES SHOWN ON THESE PLANS ARE FROM BEST AVAILABLE RECORDS AND SHALL BE CONSIDERED TO BE APPROXIMATE... 7. EXISTING MANHOLE FRAMES, COVERS, VALVE BOXES, AND OTHER APPURTENANCES SHALL BE ADJUSTED TO THE FINAL GRADE OR REPLACED, AS NECESSARY... 8. THE CONTRACTOR SHALL PROVIDE ADA COMPLIANT ACCESS THROUGH OR AROUND THE SITE AT ALL TIMES AND SHALL ENSURE THE SAFETY OF ALL THOSE PASSING THROUGH OR ADJACENT TO THE SITE... 9. ALL SIDEWALK AND CURB AND GUTTER DEMOLITION SHALL BEGIN AND END AT THE CONSTRUCTION JOINT NEAREST TO THE DEPICTED DEMOLITION EXTENTS WITH A NEAT SAWCUT LINE TO FULL DEPTH OF PAVEMENT SECTION.

STORMWATER AND ENVIRONMENTAL PROTECTION

- 10. THE CONTRACTOR SHALL CONFINE ALL ACTIVITIES AT THE SITE ASSOCIATED WITH CONSTRUCTION ACTIVITIES, TO INCLUDE STORAGE OF EQUIPMENT AND OR MATERIALS, ACCESS TO THE WORK, FORMWORK, ETC. TO WITHIN THE DESIGNATED LIMITS OF DISTURBANCE (LOD).

TREE PROTECTION

- 11. TREES SHALL BE PROTECTED PER THE REQUIREMENTS OF ARLINGTON PARKS & RECREATION STANDARD.

TRAFFIC CONTROL

- 12. CONTRACTOR SHALL NOTIFY THE PROJECT OFFICER AT LEAST 3 WORKING DAYS PRIOR TO DISTURBING ANY EXISTING, OR INSTALLING ANY NEW, TRAFFIC SIGNS, SIGNALS, OR OTHER TRAFFIC CONTROL DEVICES... 13. THE CONTRACTOR SHALL PREMARK THE LAYOUT OF ANY PERMANENT TRAFFIC CONTROL STRIPING, INDICATING THE PROPOSED LOCATION AND TYPE OF MARKING TO BE INSTALLED... 14. THE CONTRACTOR SHALL SUBMIT ANY REQUESTS FOR TEMPORARY "NO PARKING" RESTRICTIONS TO THE PROJECT OFFICER AT LEAST 5 BUSINESS DAYS PRIOR TO THE DESIRED ONSET OF RESTRICTIONS... 15. WHEN THE APPROVED PLAN CALLS FOR THE REMOVAL OF ANY PARKING METER THE CONTRACTOR MUST MAKE A REQUEST TO THE PROJECT OFFICER AT LEAST ONE WEEK IN ADVANCE OF THE DESIRED REMOVAL... 16. THE CONTRACTOR SHALL PRESERVE ALL BUS STOPS, INCLUDING MAINTAINING ADEQUATE ACCESSIBILITY THROUGH AND ADJACENT TO THE CONSTRUCTION FOR BUSES AND THEIR PASSENGERS... 17. WHEN CONDITIONS WARRANT DUE TO TRAFFIC VOLUMES, PATTERNS, OR SPECIAL EVENTS, THE COUNTY MAY SUSPEND OR OTHERWISE DIRECT THE CONTRACTOR'S ACTIVITIES TO PROTECT THE PUBLIC AND OR THE COUNTY'S TRANSPORTATION NETWORK.

WATER DISTRIBUTION, STORM AND SANITARY SEWER SYSTEMS

- 18. UNLESS OTHERWISE DIRECTED, CONTRACTORS ARE EXPRESSLY PROHIBITED FROM OPERATING ANY WATER VALVES OR APPURTENANCES... 19. IN THE EVENT OF A WATER OR SEWER EMERGENCY, THE CONTRACTOR SHALL IMMEDIATELY NOTIFY THE COUNTY'S WATER CONTROL CENTER AT 703-228-6555 AND THE PROJECT OFFICER... 20. THE CONTRACTOR SHALL COORDINATE ALL UTILITY SHUTOFFS, DISCONNECTS, AND/OR ABANDONMENT WITH UTILITY OWNER AND PROJECT OFFICER AT LEAST 1 WEEK IN ADVANCE OF THE REQUIRED INTERRUPTION.

FIRE DEPARTMENT NOTES:

- 21. ALL EXISTING FIRE HYDRANTS AND FIRE DEPARTMENT CONNECTIONS SHALL BE MAINTAINED UNOBSERVED AND ACCESSIBLE AT ALL TIMES IN ACCORDANCE WITH SECTIONS 507.5.4 AND 507.5.5 OF THE ARLINGTON COUNTY FIRE PREVENTION CODE... 22. ACCESS TO BUILDINGS FOR FIREFIGHTING SHALL BE MAINTAINED AT ALL TIMES... 23. IN THE EVENT THAT EXISTING FIRE DEPARTMENT CONNECTIONS OR FIRE APPARATUS ACCESS ROADS (FIRE LANES) MUST BE OBSTRUCTED TO FACILITATE CONSTRUCTION ACTIVITIES, CONTACT THE ARLINGTON COUNTY FIRE DEPARTMENT FIRE PREVENTION OFFICE AT 703-228-4644 TO COORDINATE REVIEW AND APPROVAL OF TEMPORARY FIRE DEPARTMENT CONNECTIONS AND/OR FIRE APPARATUS ACCESS ROADS PRIOR TO CREATING THE OBSTRUCTION.

Table of Contents

Table with columns for SHEET NUMBER and SHEET TITLE, listing various plan details like COVER, VDOT COVER, DETAILS, TYPICAL SECTIONS, etc.

VDOT PROJECT # EN18-000-880

UPC # 113868

LOCALITY PROJECT # P31D

SWM# 22-0200 LDA # 51482

ADT

3,300 - 14TH STREET NORTH (FROM N BARTON ST TO N COURT HOUSE RD.) - 2020 - TE & O N/A - VEITCH ST NORTH (FROM 14TH ST. N. TO 13TH ST. N.)

STREET CLASSIFICATION

14TH ST. N. - NEIGHBORHOOD PRINCIPAL N. VEITCH ST. - NEIGHBORHOOD MINOR MAINTAINING AGENCY : ARLINGTON COUNTY

POSTED SPEED

14TH ST. N. - 25 MPH N. VEITCH ST. - 25 MPH 2011 AASHTO CITY BUS

14TH ST N. & N. VEITCH ST. P31D

14TH ST N. @ N. VEITCH ST.

COVER

DESIGNED: K. PATEL DRAWN: K.PATEL CHECKED: Z. DRAGACEVAC

PLOTTED: MARCH 8 2023

SCALE:

C000.1

REVISED ON 11/19/2021



THIS PROJECT WAS DEVELOPED UTILIZING THE ARLINGTON COUNTY DES DESIGN PACKAGE (AUTOCAD CIVIL3D 2020).
PROJECT UPC: 113868
ARLINGTON COUNTY STORMWATER MANAGEMENT #: SWM 22-0200
ARLINGTON COUNTY LAND DEVELOPMENT APPLICATION #: LDA51482
ARLINGTON COUNTY BOARD APPROVAL DATE: N/A
ARLINGTON COUNTY PROGRAM OWNER: Transportation Planning Bureau

ARLINGTON VIRGINIA

CONSTRUCTION DRAWINGS FOR: 14TH ST. N. & N. VEITCH ST. 14TH ST N. @ N. VEITCH ST.

PROJECT NUMBER: P31D
UPC NUMBER: 113868

LOCATION MAP



POPULATION: ARLINGTON COUNTY 207,627 (2010 CENSUS)

STATE PROJECT NO.	SECTION	FEDERAL AID PROJECT NO.	TYPE CODE	UPC NO.	LENGTH INCLUDING BRIDGE(S)		LENGTH EXCLUDING BRIDGE(S)		BRIDGE PLAN NO.	TYPE PROJECT	DESCRIPTION
					FEET	MILES	FEET	MILES			
EN18-000-880	P101	FHWA-5B01(074)	PENG	113868	450	0.085	450	0.085		PRELIMINARY ENGINEERING	INTERSECTION IMPROVEMENTS

NOTE: PROJECT LENGTH BASED ON ROADWAY CENTERLINE

FHWA 534 DATA: 43128

STATE	FEDERAL AID		STATE		SHEET NO.
	PROJECT	ROUTE	PROJECT		
VA	FHWA-5B01 (074)	N/A	EN18-000-880		1

FUNCTIONAL CLASSIFICATION AND TRAFFIC DATA

ROADWAY	NEIGHBORHOOD PRINCIPAL	NEIGHBORHOOD MINOR	
	14TH ST. N	N. VEITCH ST.	NAME
POSTED V (MPH)	25	25	
ADT (2020)	3,300	N/A	

MAINTAINING AGENCY : ARLINGTON COUNTY

Sheet List Table

SHEET NUMBER	SHEET TITLE
C000.2	VDOT COVER
C002.1	DETAILS
C004.1	TYPICAL SECTIONS
C011.1	EXISTING CONDITIONS PLAN
C006.1	LEGEND
C021.1	DEMOLITION PLAN
C031.1	EROSION_AND_SEDIMENT CONTROL PLAN
C032.1	EROSION_AND_SEDIMENT_CONTROL NOTES AND DETAILS
C032.2	EROSION AND SEDIMENT CONTROL NOTES AND DETAILS
C032.3	EROSION AND SEDIMENT CONTROL NOTES AND DETAILS
C032.4	EROSION AND SEDIMENT CONTROL NOTES AND DETAILS
C035.1	STORMWATER POLLUTION PREVENTION PLAN
C035.2	STORMWATER POLLUTION PREVENTION PLAN
C041.1	PLAN AND PROFILE
C042.1	RAMP DETAILS
C042.2	RAMP DETAILS
C042.3	RAMP DETAILS
C042.4	RAMP DETAILS
C043.1	CURB RETURN PROFILES
C044.1	CROSS-SECTIONS
C044.2	CROSS-SECTIONS
C044.3	CROSS-SECTIONS
C044.4	CROSS-SECTIONS
C045.1	GEOMETRIC CONTROL PLAN
C101.1	SIGNAGE_AND_STRIPING
C121.1	MAINTENANCE OF TRAFFIC PLAN
C122.1	MAINTENANCE OF TRAFFIC NOTES & DETAILS
C122.2	MAINTENANCE OF TRAFFIC NOTES & DETAILS

THE COMPLETE ELECTRONIC PDF VERSION OF THE PLAN ASSEMBLY AS AWARDED, INCLUDING ALL SUBSEQUENT REVISIONS, WILL BE THE OFFICIAL CONSTRUCTION PLANS. FOR INFORMATION RELATIVE TO ELECTRONIC FILES AND LAYERED PLANS, SEE GENERAL NOTES.


DESIGN FEATURES RELATING TO CONSTRUCTION OR TO REGULATION AND CONTROL OF TRAFFIC MAY BE SUBJECT TO CHANGE AS DEEMED NECESSARY BY THE DEPARTMENT.

THIS PROJECT IS TO BE CONSTRUCTED IN ACCORDANCE WITH THE DEPARTMENT'S 2020 ROAD AND BRIDGE SPECIFICATIONS, 2016 ROAD AND BRIDGE STANDARDS, 2009 MUTCD, 2011 VIRGINIA SUPPLEMENT TO THE MUTCD, 2011 VIRGINIA WORK AREA PROTECTION MANUAL REV 2 (2019), ARLINGTON COUNTY STANDARDS AND SPECIFICATIONS, AND AS AMENDED BY CONTRACT PROVISIONS AND THE COMPLETE ELECTRONIC PDF VERSION OF THE PLAN ASSEMBLY.

THE ORIGINAL APPROVED TITLE SHEET(S), INCLUDING ORIGINAL SIGNATURES, IS FILED IN THE VDOT CENTRAL OFFICE PLAN LIBRARY. ANY MISUSE OF ELECTRONIC FILES, INCLUDING SCANNED SIGNATURES, IS ILLEGAL AND ENFORCED TO THE FULL EXTENT OF THE LAW.
ALL CONSTRUCTION IS TO BE PERFORMED WITHIN THE EXISTING RIGHT OF THE WAY.



COPYRIGHT © 2021 ARLINGTON COUNTY VIRGINIA - ALL RIGHTS RESERVED



APPROVALS	DATE
<i>Amy Plawn</i> QUALITY CONTROL ENGINEER	02/23/23
<i>Edward Sanders</i> CONSTRUCTION MANAGEMENT SUPERVISOR	03/03/23
<i>[Signature]</i> WATER, SEWER, STREETS BUREAU CHIEF	3/2/23
<i>[Signature]</i> TRANSPORTATION DIRECTOR	03/03/2023
<i>[Signature]</i> PROJECT MANAGER	3/7/23

REVISIONS	DATE

TIER 1 PROJECT

LOCALLY ADMINSTRATED PROJECTS

NAME OF LOCALITY

NAME OF RESPONSIBLE LOCAL OFFICIAL (TYPE)

RECOMMENDED FOR APPROVAL FOR RIGHT OF WAY ACQUISITION

DATE DISTRICT PLANNING AND INVESTMENT MANAGER

NAME OF RESPONSIBLE LOCAL GOVERNMENT OFFICIAL (TYPE)

RECOMMENDED FOR APPROVAL FOR CONSTRUCTION

DATE TITLE OF POSITION

14TH ST. N. & N. VEITCH ST.
P31D
14TH ST N. @ N. VEITCH ST.
VDOT COVER

NOTE:
ALL CONSTRUCTION IS TO BE PERFORMED WITHIN THE EXISTING RIGHT OF WAY

DESIGNED: K. PATEL
DRAWN: K.PATEL
CHECKED: Z. DRAGACEVAC
PLOTTED: MARCH 8 2023

SCALE:

SWM #XX-XXXX

C000.2

FILENAME: COVER_MAP.DWG PATH: Q:\DAN\P31D\S-5 - 14TH ST N & N VEITCH ST\DESIGN\CAD\ACTIVE PLOTTED BY: RPATEL

WP-2

CONSTRUCTION JOINT DETAIL

REMOVE EXISTING ASPHALT LAYERS TO EXISTING SUBBASE AND REPLACE WITH PROPOSED ASPHALT WIDENING LAYERS
 PROPOSED MINIMUM 1 1/2" THICK ASPHALT SURFACE COURSE (SEE NOTE 5)
 * MINIMUM 12 INCHES OR GREATER AS NECESSARY TO ABUT THE FULL THICKNESS OF EXISTING ASPHALT LAYERS AS DETERMINED BY CORES (SEE NOTE 3)

NOTES:

- ASPHALT PAVEMENT WIDENING SHALL HAVE A PAVEMENT DESIGN IN ACCORDANCE WITH CURRENT VDOT PROCEDURES AND BE APPROVED BY THE ENGINEER. SUBSURFACE DRAINAGE OF THE EXISTING AND PROPOSED PAVEMENT SHALL BE ADDRESSED IN THE PAVEMENT DESIGN.
- A MINIMUM OF THREE CORES SHALL BE TAKEN ALONG THE CENTER OF THE ADJACENT TRAVEL LANE TO DETERMINE THE TYPE AND THICKNESS OF EXISTING PAVEMENT LAYERS. THESE CORES SHALL BE SPACED NO MORE THAN 500 FEET APART.
- THE ADJACENT TRAVEL LANE SHALL BE MILLED A MINIMUM DEPTH OF 1 1/2" INCHES AND REPLACED WITH AN ASPHALT SURFACE COURSE TO MATCH THE PROPOSED PAVEMENT WIDENING SURFACE COURSE, UNLESS WAIVED BY THE ENGINEER.
- THE ENGINEER MAY REQUIRE THE MILLING DEPTH OF THE EXISTING PAVEMENT TO BE ADJUSTED TO ACHIEVE AN ACCEPTABLE PAVEMENT CROSS-SLOPE AND EFFECTIVE SURFACE DRAINAGE.
- EXISTING PAVEMENT MARKINGS AND MARKERS WITHIN THE PROJECT LIMITS SHALL BE RESTORED SUBJECT TO THE APPROVAL OF THE ENGINEER.
- FINAL TRANSVERSE PAVEMENT TE-IN SHALL CONFORM TO THE REQUIREMENTS OF SECTION 315.05(a) OF THE SPECIFICATIONS EXCEPT THAT ALL JOINTS AT TE-IN LOCATIONS SHALL BE TESTED USING A 3 FOOT STRAIGHTEDGE IN ACCORDANCE WITH THE REQUIREMENTS OF SECTION 315.07(a) OF THE SPECIFICATIONS.

VDOT ROAD AND BRIDGE STANDARDS
 SHEET 1 OF 1 REVISION DATE 303.02

ASPHALT PAVEMENT WIDENING FOR WIDENING SUBJECT TO TRAFFIC
 VIRGINIA DEPARTMENT OF TRANSPORTATION

SPECIFICATION REFERENCE
 315

2016 ROAD & BRIDGE STANDARDS

CG-12 DETECTABLE WARNING SURFACE
 TYPE A (PERPENDICULAR) APPLICATION

NOTES:

- FOR GENERAL NOTES ON THE DETECTABLE WARNING SURFACE, SEE SHEET 1 OF 5.
- THIS DESIGN TO BE USED FOR CONSTRUCTION THAT INCORPORATES WIDER SIDEWALK LANDING 14' WIDE REQUIRED AT TOP OF CURB RAMP. MINIMUM CURB RAMP LENGTH 8 FEET FOR NEW CONSTRUCTION.
- GUTTER PAN SHALL BE A MAXIMUM SLOPE OF 20:1 AT THE RAMP OPENING.
- DIAGONAL PLACEMENT IS NOT PERMITTED.

VDOT ROAD AND BRIDGE STANDARDS
 SHEET 2 OF 5 REVISION DATE 04/19 204.02

2016 ROAD & BRIDGE STANDARDS

CG-12 DETECTABLE WARNING SURFACE
 TYPE B (PARALLEL) APPLICATION

ROADWAY GRADE IN PERCENT	MINIMUM RAMP LENGTH IN FEET
0	4
1	5
2	6
3	8
4	9
5	10
6	14

VDOT ROAD AND BRIDGE STANDARDS
 SHEET 3 OF 5 REVISION DATE 04/19 204.03

(C-2) STANDARD CURB & GUTTER

(C-2R) STANDARD REVERSE PITCH CURB & GUTTER

(C-3) STANDARD HEADER CURB

(C-31) STANDARD CURB & GUTTER FOR TRANSIT STATION

(C-4) STANDARD CURB & GUTTER FOR TRANSIT STATION

(C-5) ALTERNATE CURB FOR MEDIANS

NOTES:

- SECTION C-3 IS TO BE USED ONLY WITH RIGID TYPE PAVEMENT UNLESS OTHERWISE DIRECTED IN WRITING OR WHEN SHOWN ON APPROVED PLANS.
- EXPANSION JOINTS IN HEADER CURB AND STANDARD CURB AND GUTTER SHALL BE 40' APART OR AT EXPANSION JOINTS IN CONCRETE PAVEMENT.
- EXPANSION JOINTS MAY BE OMITTED IF 1/8" JOINTS ARE PLACED EVERY 10' OF LESS.
- EXPANSION JOINTS IN THE SIDEWALK SHALL BE 40' APART. IF ADJACENT TO CONCRETE CURB, EXPANSION JOINTS SHALL MATCH JOINT OF CURB. AN EXPANSION JOINT SHALL BE PLACED BETWEEN CURB AND SIDEWALK.
- SEE DRAWING R-2.2 FOR DETAIL OF SIDEWALK STRESS COLUMN TO BE PLACED UNDER SIDEWALK WHEN PLACED ADJACENT TO BACK OF CURB.
- SEE ARLINGTON COUNTY SPECIFICATION SECTIONS 02611 AND 03100 FOR MATERIAL SPECS.
- PROVIDE 6" MINIMUM AGGREGATE BASE HAVING CBR-30 UNDER CURB AND GUTTER.
- PROVIDE 3" MINIMUM AGGREGATE BASE HAVING CBR-30 UNDER SIDEWALK
- WHENEVER CURB ABUTTS RIGID PAVEMENT, PROVIDE LONGITUDINAL JOINT PER VDOT PR-2.
- SECTION C-5 TO BE USED WHEN BICYCLE LANE RUNS ALONG A MEDIAN.

CONCRETE CURB & GUTTER AND SIDEWALK

ARLINGTON COUNTY, VIRGINIA
 DEPARTMENT OF ENVIRONMENTAL SERVICES


ISSUED 9/14/2020
DRAWING NO. R-2.0

TREE SENSITIVE CONCRETE SIDEWALK
 311300.IINS

NOTES:

- ALL WORK SHALL BE SUPERVISED BY AN ISA CERTIFIED ARBORIST.
- NO ROOTS GREATER THAN 1" SHALL BE CUT WITHOUT REVIEW BY ARLINGTON COUNTY URBAN FORESTER.
- EXCAVATION SHALL BE NOT MORE THAN MINIMUM NEEDED TO ACHIEVE REQUIRED FINAL GRADE.
- ALL EXCAVATION SHALL BE BY SSAT AND/OR BY HAND TO MINIMIZE ROOT DAMAGE AS DIRECTED BY CERTIFIED ARBORIST.
- WORK SHALL NOT DAMAGE TREE TRUNK, LIMBS OR ROOTS TO REMAIN.

N.T.S.
ARLINGTON COUNTY, VIRGINIA
 DEPARTMENT OF ENVIRONMENTAL SERVICES



APPROVALS	DATE
<i>Amy Plawin</i>	02/23/23
QUALITY CONTROL ENGINEER	
<i>Edward Sanders</i>	03/03/23
CONSTRUCTION MANAGEMENT SUPERVISOR	
<i>Alan</i>	3/2/23
WATER, SEWER, STREETS BUREAU CHIEF	
<i>Henry</i>	03/03/2023
TRANSPORTATION DIRECTOR	
<i>Mark</i>	3/7/23
PROJECT MANAGER	

REVISIONS	DATE


14TH ST N. & N. VEITCH ST.
 P31D
 14TH ST N. @ N. VEITCH ST.

DETAILS

DESIGNED: K. PATEL
 DRAWN: K. PATEL
 CHECKED: Z. DRAGACEVAC

PLOTTED: MARCH 8 2023


SCALE: AS SHOWN



DEPARTMENT OF ENVIRONMENTAL SERVICES
 FACILITIES & ENGINEERING DIVISION
 ENGINEERING BUREAU
 2100 CLARENDON BOULEVARD, SUITE 813
 ARLINGTON, VA 22201
 PHONE: 703.228.3629
 FAX: 703.228.3606

COPYRIGHT © 2021 ARLINGTON COUNTY VIRGINIA - ALL RIGHTS RESERVED

SEAL



APPROVALS	DATE
<i>Amy Pflaum</i> QUALITY CONTROL ENGINEER	02/23/23
<i>Edward Sanders</i> CONSTRUCTION MANAGEMENT SUPERVISOR	03/03/23
<i>[Signature]</i> WATER/SEWER, STREETS BUREAU CHIEF	3/2/23
<i>[Signature]</i> TRANSPORTATION DIRECTOR	03/03/2023
<i>[Signature]</i> PROJECT MANAGER	3/7/23

REVISIONS	DATE

14TH ST. N. & N. VEITCH ST.
 P31D
 14TH ST N. @ N. VEITCH ST.
 TYPICAL SECTIONS

DESIGNED: K. PATEL
 DRAWN: K.PATEL
 CHECKED: Z. DRAGACEVAC
 PLOTTED: MARCH 8 2023

SCALE:

AS SHOWN

C004.1

LINETYPE LEGEND

FEATURE	EXISTING	PROPOSED
BUILDING	— — —	— — —
CENTERLINE / BASELINE	— — —	— — —
COMMUNICATIONS CABLE	— COM —	— COM —
CONTOURS - MAJOR, MINOR	— 250 — 250 — 250 —	— 250 —
CRITICAL ROOT ZONE	— CRZ — CRZ —	— CRZ — CRZ —
EASEMENT	— — —	— — —
ELECTRIC (UNDERGROUND)	— UGE — UGE —	— — —
FENCE (MATERIAL NOTED)	— X — X — X — X — X —	— X — X — X — X — X —
FIBER OPTIC	— — —	— — —
GAS LINE	— GAS — GAS —	— GAS — GAS —
X" GAS LINE (SIZE INCLUDED IF AVAILABLE)	— # " g — # " g — # " g —	— X" G — X" G —
GUARDRAIL	— — —	— — —
HARDSCAPE FEATURE (MATERIAL NOTED)	— — —	— — —
LIMITS OF DISTURBANCE	— LOD —	— LOD —
LIMITS OF WORK	— LOW — LOW —	— LOW — LOW —
OVERHEAD WIRES	— —	— —
PAVEMENT MINI SKIP LINE	— — —	— — —
PAVEMENT SKIP LINE	— — —	— — —
PROPERTY LINE	— — —	— — —
RIGHT-OF-WAY LINE	— — —	— — —
ROOT PRUNING	— RP — RP —	— RP — RP —
SANITARY SEWER	— — —	— SAN — SAN —
SANITARY SEWER UNDER 20" (SIZE INCLUDED IF AVAILABLE)	— # " s — # " s —	— — —
SANITARY SEWER OVER 20"	— — —	— — —
SILT FENCE	— SF — SF —	— SF — SF —
STORM (SIZE NOTED)	— STM — STM —	— — —
STREAM	— — —	— — —
STREET LIGHT CONDUIT	— SL — SL —	— SL — SL —
TELEPHONE (UNDERGROUND)	— UGT — UGT —	— UGT — UGT —
TREE LINE	— — —	— — —
TREE PROTECTION FENCE	— TP — TP —	— TP — TP —
WALL	— — —	— — —
WATERLINE UNDER 20" (SIZE INCLUDED IF AVAILABLE)	— # " w — # " w —	— — —
WATERLINE OVER 20"	— — —	— — —

SYMBOL LEGEND

EXISTING FEATURE	PROPOSED FEATURE
EX CABLE PEDESTAL	EX ELECTRIC BOX
EX FIRE HYDRANT	PROP FIRE HYDRANT
EX GAS VALVE	PROP GAS VALVE
EX GROUND LIGHT	EX GUY WIRES
EX IRON PIPE OR PIN	EX LIGHT POLE
EX MAILBOX	EX MONUMENT
EX PARKING METER	EX PAY STATION
EX SANITARY MANHOLE	EX STORM BASIN
EX STORM MANHOLE	EX STORM MANHOLE
EX TELEPHONE PEDESTAL	EX TRAFFIC CONTROL BOX
EX TRAFFIC SIGN	EX TRASH CAN
EX TRAVERSE	EX TREES, WOODED AREA
EX UTILITY MANHOLE TYPE INDICATED ELEC, TELE, ETC	EX UTILITY POLE
EX WATER MANHOLE	EX WATER METER
EX WATER VALVE	EX YARD INLET
EX BENCHMARK	EX BENCHMARK
NORTH ARROW	NORTH ARROW
	CONSTRUCTION NOTES (LEADER TO AREA AFFECTED)
	DETAIL NUMBER (SEE NOTE)
	CURVE NUMBER (SEE CURVE TABLE)
	LINE NUMBER (SEE LINE TABLE)
	TEST HOLE

SYMBOL LEGEND

EXISTING FEATURE	PROPOSED FEATURE
EX STRIPING	PROP STRIPING
EX BUS STOP	PROP BUS STOP

LABEL LEGEND

EXISTING	PROPOSED
EXISTING SANITARY STRUCTURE NUMBER	PROPOSED SANITARY SEWER STRUCTURE NUMBER
EXISTING STORM SEWER STRUCTURE NUMBER	PROPOSED STORM SEWER STRUCTURE NUMBER

HATCH LEGEND

PROP MILL & OVERLAY SEE TYPICAL SECTION FOR DETAILS
PROP FULL DEPTH ASPHALT SEE TYPICAL SECTION FOR DETAILS
PROP CONCRETE
REPLACE & MATCH EXISTING DRIVEWAY OR LEADWALK. SEE CONSTRUCTION NOTES
DEMOLITION AREA

ARLINGTON VIRGINIA
 DEPARTMENT OF ENVIRONMENTAL SERVICES
 FACILITIES & ENGINEERING DIVISION
 ENGINEERING BUREAU
 2100 CLARENDON BOULEVARD, SUITE 813
 ARLINGTON, VA 22201
 PHONE: 703.228.3629
 FAX: 703.228.3606

COPYRIGHT © 2021 ARLINGTON COUNTY VIRGINIA - ALL RIGHTS RESERVED

SEAL

ZORAN DRAGACEVAC
 No. 031869
 PROFESSIONAL ENGINEER


APPROVALS	DATE
<i>Amy Plawin</i>	02/23/23
QUALITY CONTROL ENGINEER	
<i>Edward Sanders</i>	03/03/23
CONSTRUCTION MANAGEMENT SUPERVISOR	
<i>Alan</i>	3/2/23
WATER/SEWER, STREETS BUREAU CHIEF	
<i>Henry</i>	03/03/2023
TRANSPORTATION DIRECTOR	
<i>K. Patel</i>	3/7/23
PROJECT MANAGER	

REVISIONS	DATE

14TH ST N. & N. VEITCH ST.
 P31D
 14TH ST N. @ N. VEITCH ST.
LEGEND

DESIGNED: K. PATEL
 DRAWN: K. PATEL
 CHECKED: Z. DRAGACEVAC
 PLOTTED: MARCH 8 2023

SCALE:
 N/A



COURTHOUSE PLAZA

LOT 3
D.B. 2319, PG. 483

RPC 18004PLB
COURTHOUSE PLAZA
ASSOCIATES
AND
COUNTY BOARD OF
ARLINGTON COUNTY, VA

P.I. 4+63.09 14th Street N.
 $\Delta = 25^\circ 42' 43''$ Lt.
P.I. 6+15.61 N. Veitch Street
 $\Delta = 90^\circ 08' 00''$ Lt.

COURTYARDS

BLOCK 6 ~ PARCEL B
D.B. 120, PG. 242
D.B. 2832, PG. 1459

RPC 18003602
COURTHOUSE HILL, LLC

C/L Curve Data
P.I. = 5+25.82
R = 178.50'
A = 37.75'
T = 18.95'
 $\Delta = 12^\circ 07' 01''$

SURVEY CONTROL

7	7010592.3715	11885701.6826	237.472	TRV-NAIL FND
20	7010539.4402	11885486.5265	236.905	TRV-NAIL FND
71	7010272.4787	11885753.9649	234.342	TRV-NAIL SET
72	7010077.9617	11885788.1146	230.673	TRV-NAIL SET
73	7010061.8330	11885619.1940	207.796	TRV-NAIL SET
74	7010245.3154	11885552.1984	224.688	TRV-NAIL SET
81	7010095.6911	11885976.5019	231.156	TRV-NAIL SET

STORM SEWER TABLE

#6908	TOP = 234.71
15" RCP INV. IN = 224.03 (20006)	
15" RCP INV. IN = 228.48 (20018)	
15" RCP INV. OUT = 223.58 (7011)	
#6919	TOP = ??
NEED LOCATION ??	
15" RCP INV OUT = ????? (6930)	
#6930	TOP = 225.07
15" RCP INV IN = 215.06 (NORTHWEST)	
15" RCP INV OUT = 215.01 (7039)	
#7011	TOP = 232.26
15" RCP INV IN = 223.21 (6908)	
15" RCP INV IN = 228.43 (7012)	
15" RCP INV OUT = 223.02 (7056)	
#7012	TOP = 232.36
15" RCP INV IN = 228.65 (7029)	
15" RCP INV OUT = 228.61 (7011)	
#7029	TOP = 231.38
15" RCP INV IN = 229.32 (7012)	
#7034	TOP = 215.62
12" RCP INV IN = 208.42 (NORTHWEST)	
15" RCP INV OUT = 207.63 (7112)	
#7039	TOP = 214.62
15" RCP INV IN = 209.82 (6930)	
15" RCP INV OUT = 208.78 (7045)	
#7043	TOP = 231.37
10" RCP INV IN = 229.57 (29418)	
15" RCP INV OUT = 226.62 (7086)	
#7045	TOP = 213.08
15" RCP INV IN = 208.16 (7039)	
36" RCP INV OUT = 207.84 (23521)	
#7056	TOP = 230.78
15" RCP INV IN = 222.58 (7011)	
15" RCP INV IN = 215.01 (NORTHEAST)	
15" RCP INV OUT = 214.58 (7101)	
#7067	TOP = 211.30
15" RCP INV IN = 206.08 (7196)	
15" RCP INV OUT = 205.99 (25652)	

STORM SEWER TABLE

#7086	TOP = 230.09
15" RCP INV IN = NOT FOUND (7119)	
15" RCP INV IN = 224.84 (7043)	
15" RCP INV OUT = 224.20 (7101)	
#7101	TOP = 219.42
15" RCP INV IN = 212.92 (7086)	
15" RCP INV IN = 212.80 (7056)	
15" RCP INV OUT = 212.70 (25651)	
#7112	TOP = 207.27
15" RCP INV IN = 199.28 (7034)	
15" RCP INV OUT = 197.01 (7163)	
#7114	TOP = 208.51
15" RCP INV IN = 200.93 (25652)	
18" RCP INV OUT = 197.71 (7163 ?)	
#7119	TOP = 230.33
15" RCP INV OUT = 227.14 (7086)	
#7163	TOP = 206.03
15" RCP INV IN = 193.02 (7112)	
15" RCP INV IN = 198.58 (23677)	
18" RCP INV IN = 193.93 (7114 ?)	
36" RCP INV IN = 188.43 (23675)	
36" RCP INV OUT = 186.75 (7206)	
#7174	TOP = 206.66
36" RCP INV IN = 197.66 (7196)	
36" RCP INV OUT = 194.74 (23675)	
#7184	TOP = 213.68
15" RCP INV IN = 205.94 (NORTH)	
15" RCP INV OUT = 205.87 (7196)	
#7196	TOP = 213.50
15" RCP INV IN = 205.04 (7184)	
36" RCP INV IN = 207.88 (23521)	
36" RCP INV OUT = 203.70 (7174)	
#7206	TOP = 202.56
15" RCP INV IN = 184.90 (25655)	
36" RCP INV IN = 185.80 (7163)	
36" RCP INV OUT = 183.83 (7323)	
#7323	TOP = 200.98
15" RCP INV IN = 186.32 (7322)	
15" RCP INV IN = ????? (25657 ?)	
36" RCP INV IN = 182.17 (7206)	
48" RCP INV OUT = 182.61 (7327)	

STORM SEWER TABLE

#7322	TOP = 201.84
15" RCP INV IN = 189.00 (WEST)	
15" RCP INV IN = 191.00 (25677)	
15" RCP INV OUT = 186.66 (7323)	
#7327	TOP = 201.62
48" RCP INV. IN = 178.07 (7323)	
#20006	TOP = 232.00
15" RCP INV. OUT = 225.78 (6908)	
#20018	TOP = 233.98
15" RCP INV. IN = 230.11 (20013)	
15" RCP INV. OUT = 230.06 (6908)	
#20013	TOP = 233.77
15" RCP INV. OUT = 230.53 (20018)	
#23675	TOP = 206.14
15" RCP INV IN = 197.12 (23678)	
36" RCP INV IN = 193.73 (7174)	
36" RCP INV OUT = 193.68 (7163)	
#23667	TOP = 206.31
15" RCP INV OUT = 199.41 (7163)	
#23678	TOP = 206.27
12" RCP INV IN = 198.52 (NORTH)	
15" RCP INV IN = 200.93 (23679)	
15" RCP INV OUT = 197.70 (23675)	
#23679	TOP = 205.41 (GRATE)
15" RCP INV OUT = 202.03 (23678)	
#25651	TOP = 213.89
NO ACCESS	
#25652	TOP = 211.36
15" RCP INV IN = 199.44 (7067)	
15" RCP INV IN = 204.07 (25651)	
15" RCP INV OUT = 198.92 (7114)	
#25655	TOP = 203.56
15" RCP INV OUT = 191.98 (7206)	
#25657	TOP = ????? (NEEDS LOCATE)
15" RCP INV OUT = ????? (?????)	
#25677	TOP = 202.00
15" RCP INV OUT = 191.81 (7322)	
#29418	TOP = 232.49
10" RCP INV OUT = 229.70 (7043)	

SANITARY SEWER TABLE

#3090	TOP = 204.05
C/L INV. = NO ACCESS	
#12118	TOP = 224.01
C/L INV. = 215.78	
#13463	TOP = 216.35
C/L INV. = 202.73	
#13464	TOP = 206.35
C/L INV. = 193.52	
#13465	TOP = 204.81
C/L INV. = 191.82	
#13470	TOP = 222.02
C/L INV. = 213.18	
#14158	TOP = 215.18
C/L INV. = 206.69	
#14243	TOP = 201.55
C/L INV. = 183.02	
#14244	TOP = 201.31
C/L INV. = NO ACCESS	
#4245	TOP = 204.19
C/L INV. = 191.82	
#41545	TOP = 209.09
C/L INV. = 197.91	

ARLINGTON VIRGINIA

DEPARTMENT OF ENVIRONMENTAL SERVICES
FACILITIES & ENGINEERING DIVISION
ENGINEERING BUREAU
2100 CLARENDON BOULEVARD, SUITE 813
ARLINGTON, VA 22201
PHONE: 703.228.3629
FAX: 703.228.3606

COPYRIGHT © 2021 ARLINGTON COUNTY VIRGINIA - ALL RIGHTS RESERVED



APPROVALS	DATE
<i>Amy Plawin</i>	02/23/23
QUALITY CONTROL ENGINEER	
<i>Edward Sanders</i>	03/03/23
CONSTRUCTION MANAGEMENT SUPERVISOR	
<i>[Signature]</i>	3/2/23
WATER, SEWER, STREETS BUREAU CHIEF	
<i>[Signature]</i>	03/03/2023
TRANSPORTATION DIRECTOR	
<i>[Signature]</i>	3/7/23
PROJECT MANAGER	


REVISIONS	DATE

14TH ST. N. & N. VEITCH ST.
P31D

14TH ST N. @ N. VEITCH ST.


EXISTING CONDITIONS PLAN

DESIGNED: K. PATEL
DRAWN: K.PATEL
CHECKED: Z. DRAGACEVAC
PLOTTED: MARCH 8 2023



GENERAL SURVEY NOTES:

- THIS TOPOGRAPHIC SURVEY WAS COMPLETED UNDER THE DIRECT AND RESPONSIBLE CHARGE OF THE COUNTY SURVEY SECTION FROM AN ACTUAL GROUND SURVEY; THE IMAGE AND/OR ORIGINAL DATA WAS OBTAINED FROM 01/2016 TO 07/2016; AND THIS PLAT, MAP OR DIGITAL GEOSPATIAL DATA INCLUDING METADATA MEETS MINIMUM ACCURACY STANDARDS UNLESS OTHERWISE NOTED.
- HORIZONTAL DATUM: VIRGINIA COORDINATE SYSTEM 1983.
- VERTICAL DATUM: NORTH AMERICA VERTICAL DATUM 1988.
- CONTOUR INTERVAL: 1'
- BOUNDARY INFORMATION SHOWN HEREON WAS COMPILED FROM EXISTING LAND RECORDS AND DOES NOT REPRESENT A FIELD RUN BOUNDARY SURVEY.



Demolition note:
 Where existing pavement is to be removed within the Critical Root Zone of a tree, leave pavement in place as long as possible during construction. Remove pavement with the rollback technique, keep equipment on paving, and limit overdig. Do not cut roots bigger than 1" without approval. Once pavement has been removed, vehicular traffic is strictly prohibited until paving is replaced. Replaced paving should be a bridged, tree-friendly detail or flexible pavers set on stonedust (not CR6) with no compaction beyond 85%, hand compact. Coordinate with the Urban Forester when process or construction details can't follow this specification.



ARLINGTON VIRGINIA
 DEPARTMENT OF ENVIRONMENTAL SERVICES
 FACILITIES & ENGINEERING DIVISION
 ENGINEERING BUREAU
 2100 CLARENDON BOULEVARD, SUITE 813
 ARLINGTON, VA 22201
 PHONE: 703.228.3629
 FAX: 703.228.3606

COPYRIGHT © 2021 ARLINGTON COUNTY VIRGINIA - ALL RIGHTS RESERVED






APPROVALS	DATE
<i>Amy Plawn</i> QUALITY CONTROL ENGINEER	02/23/23
<i>Edward Sanders</i> CONSTRUCTION MANAGEMENT SUPERVISOR	03/03/23
<i>Alan</i> WATER/SEWER, STREETS BUREAU CHIEF	3/2/23
<i>Henry</i> TRANSPORTATION DIRECTOR	03/03/2023
<i>K. Patel</i> PROJECT MANAGER	3/7/23

REVISIONS	DATE

14TH ST. N. & N. VEITCH ST.
 P31D
 14TH ST N. @ N. VEITCH ST.
 DEMOLITION PLAN

DESIGNED: K. PATEL
 DRAWN: K. PATEL
 CHECKED: Z. DRAGACEVAC
 PLOTTED: MARCH 8 2023







THIS SHEET IS FOR EROSION AND SEDIMENTATION CONTROL USE ONLY

EROSION & SEDIMENTATION CONTROL NOTES

- Contractor to contact the Arlington Forester to schedule a pre-construction inspection of tree protection measures before any work near the critical root zones of trees. To schedule the pre-construction meeting call 703-228-1863.
- Contractor to protect trees per the plan according to the Arlington County DPR Design Standard Detail 0311300.14NS
- Contractor to root prune trees per the plan according to the Arlington County DPR Design Standard Detail 0311300.11NS, where called out on the plan.
- Contractor to call the urban forester at 703-228-1863, 72 hours before planting, to schedule inspection of the trees to be planted. Warranty for 1 year after planting shall be the contractor's responsibility. The urban forester and DPR is responsible for inspection.
- Contractor to prepare tree planting strips for the replacement trees according to Arlington County DPR Design Standard Detail 329300.4a and 329300.4b.
- Contractor to prepare street tree planting pits according to the Arlington County DPR Design Standard Detail 329300.3a, 329300.3b, and 329300.11c
- Contractor to plant the trees according to Arlington County DPR Design Standard Detail 329300.1 (on flat land) and 329300.2 (on slopes)

EROSION AND SEDIMENT CONTROL LEGEND

3.05	TEMPORARY SILT FENCE	SF	— X — X —
3.07	STORM DRAIN INLET PROTECTION	IP	
3.38	TREE PROTECTION	TP	— TP —
3.33	SODDING	SO	
	CRITICAL ROOT ZONE	CRZ	— CRZ —




APPROVALS	DATE
<i>Amy Plawin</i> QUALITY CONTROL ENGINEER	02/23/23
<i>Edward Sanders</i> CONSTRUCTION MANAGEMENT SUPERVISOR	03/03/23
<i>[Signature]</i> WATER/SEWER, STREETS BUREAU CHIEF	3/2/23
<i>[Signature]</i> TRANSPORTATION DIRECTOR	03/03/2023
<i>[Signature]</i> PROJECT MANAGER	3/7/23

REVISIONS	DATE

14TH ST. N. & N. VEITCH ST.
P31D
14TH ST N. @ N. VEITCH ST.

EROSION AND SEDIMENT CONTROL PLAN

DESIGNED: K. PATEL
DRAWN: K. PATEL
CHECKED: Z. DRAGACEVAC
PLOTTED: MARCH 8 2023



EROSION AND SEDIMENT CONTROL NARRATIVE

PROJECT DESCRIPTION:

RECONSTRUCT CURBS AND SIDEWALKS TO INSTALL ADA COMPLIANT CURB RAMPS AND SIDEWALK AREAS. WORK CAN INCLUDE CONSTRUCTION OF CURB EXTENSIONS (MUBS), RELOCATION OF EXISTING FEATURES SUCH AS FIRE HYDRANTS, SIGN POLES AND DRAINAGE INLETS. THIS PROJECT IS UNDER ROCKY RUN WATERSHED AREA. THE TOTAL DISTURBED ARE IS 7,047 S.F.(0.1618 ACRES) AND THE TOTAL PROJECT AREA IS 21,165 SF (0.4859 ACRES).

EXISTING SITE CONDITIONS:

THE TOPOGRAPHY OF THE PROJECT HAVE SLOPE RANGING FROM 1% TO 17%. THERE ARE EXISTING DRAINAGE STRUCTURES SERVING THESE SITES IN THE FORM OF CURB INLETS. THE CURRENT LAND COVER IS MAINLY IMPERVIOUS.

ADJACENT PROPERTIES:

PRIVATE PROPERTIES ARE LOCATED ALONG THE ROADWAY.

OFF-SITE AREAS:

THE EXTENT OF OFFSITE CONSTRUCTION IS LIMITED.

CRITICAL AREAS:

THERE ARE NO STEEP SLOPES OR CRITICAL AREAS LOCATED WITHIN THE LIMITS OF DISTURBANCE.

EROSION AND SEDIMENT CONTROL MEASURES:

THE EROSION AND SEDIMENT CONTROL MEASURES FOR THIS PROJECT AREA INCLUDE SAFETY FENCE AND INLET PROTECTION. INLET PROTECTION IS REQUIRED OUTSIDE THE PROJECT LIMITS WHEN/WHERE WATER FROM DISTURBED AREA FLOWS. (REVISE AS NEEDED)

PERMANENT STABILIZATION:

ALL AREAS DISTURBED BY CONSTRUCTION SHALL BE STABILIZED WITH GRASS, MULCH OR SOD. SEE THE PROPOSED PLANS FOR ADDITIONAL INFORMATION.

STORMWATER RUNOFF CONSIDERATIONS:

NO ADDITIONAL IMPERVIOUS AREA WILL BE ADDED TO THIS PROJECT.

TOTAL LAND DISTURBANCE.....= 7047 SF (0.1618 ACRES)
PRE-IMPROVEMENT IMPERVIOUS AREA.....= 6946 SF (0.1595 ACRES)
POST-IMPROVEMENT IMPERVIOUS AREA.....= 6802 SF (0.1562 ACRES)
DECREASE IMPERVIOUS AREA.....= 144 SF (0.0033 ACRES)

SOILS INFORMATION:

THE FOLLOWING SOILS ARE FOUND ON SITE (SEE SOILS MAP ON SHEET C031.1 FOR LOCATION)

SOIL#:	SOIL NAME:	HYDROLOGIC GROUP:	ERODABILITY:
12	URBAN LAND-UORHTENTS	VARIABLES	N/A

FLOODPLAIN AND RESOURCE PROTECTION AREA (RPA):

THERE ARE NO FLOODPLAIN OR RESOURCE PROTECTION AREAS LOCATED WITHIN THIS PROJECT SITE

EROSION & SEDIMENT CONTROL PROJECT PHASING

1. PHASE I:

- a. PRE-CONSTRUCTION MEETING WITH THE PROJECT OFFICER, CONTRACTOR, AND COUNTY INSPECTOR.
- b. INSTALL THE TEMPORARY CONSTRUCTION ENTRANCE (IF NEEDED) IN THE LOCATION SHOWN ON THE E&S PHASE I PLAN. MUD AND DEBRIS SHALL BE WASHED FROM ALL TRUCKS EXISTING THE SITE.
- c. INSTALL PERIMETER TREE DEMARCATION FENCING IN THE FORM OF TREE PROTECTION FENCE (TP) AS SHOWN ON E&S PHASE I PLAN.
- d. PERFORM INITIAL PERIMETER CLEARING TO INSTALL REMAINDER OF PERIMETER CONTROLS SUCH AS DIVERSION DIKE (DD), SILT FENCE (SF), AND SUPER SILT FENCE (SSF) AS PER THE PHASE I PLAN.
- e. INSTALL INLET PROTECTION ON EXISTING STORM DRAIN INLETS BEFORE CLEANING AND CONSTRUCTION.
- f. CONTACT ARLINGTON COUNTY PROJECT OFFICER FOR A PERIMETER INSPECTION PRIOR TO CLEARING THE REMAINDER OF THE SITE IN ORDER TO OBTAIN PHASE II GRADING PERMIT.
- g. CLEAR THE SITE TO THE LIMITS AS SHOWN ON THE CONSTRUCTION PLANS.

2. PHASE II:

- a. NO UTILITY CONSTRUCTION WITH THIS PROJECT, ADJUST ALL UNDERGROUND UTILITIES AND BEGIN SITE GRADING.
- b. INLET PROTECTION (IP) SHALL BE PROVIDED AT STORM DRAIN INLETS AS THEY ARE CONSTRUCTED.
- c. ONCE THE SITE IS BROUGHT TO NEAR FINAL GRADE, AND THE UTILITY CONSTRUCTION IS COMPLETE, COMMENCE CONSTRUCTION OF CURB & GUTTER, STREET, SIDEWALKS, AND OTHER IMPROVEMENTS
- d. THE CONTROL MEASURES MAY NOT BE REMOVED UNTIL ALL OF THE DISTURBED AREAS HAVE BEEN STABILIZED AND ONLY AS APPROVED AND DIRECTED BY THE INSPECTOR.

RUNOFF SHALL BE TREATED WITH SILT FENCE AND INLET PROTECTION PRIOR TO ENTERING MAJOR STORM SEWER SYSTEMS.

EROSION AND SEDIMENT CONTROL MEASURES

UNLESS OTHERWISE INDICATED, ALL VEGETATIVE AND STRUCTURAL EROSION AND SEDIMENT CONTROL PRACTICES SHALL BE CONSTRUCTED AND MAINTAINED ACCORDING TO MINIMUM STANDARDS AND SPECIFICATIONS OF THE VIRGINIA EROSION AND SEDIMENT CONTROL HANDBOOK AND THE ARLINGTON COUNTY EROSION AND SEDIMENT CONTROL ORDINANCE. THE MINIMUM STANDARDS OF THE VIRGINIA EROSION AND SEDIMENT CONTROL HANDBOOK SHALL BE ADHERED TO UNLESS OTHERWISE WAIVED OR APPROVED BY A VARIANCE.

1. STRUCTURAL PRACTICES

- a. TEMPORARY CONSTRUCTION ENTRANCE - VESCH 3.02
 - a.a. A TEMPORARY CONSTRUCTION ENTRANCE WITH A WASH RACK SHALL BE INSTALLED AT THE EXISTING ACCESS POINT TO THE SITE. DURING MUDDY CONDITIONS, DRIVERS OF CONSTRUCTION VEHICLES WILL BE REQUIRED TO WASH THEIR WHEELS BEFORE RE-ENTERING THE LOCAL ROADWAYS.
 - a.b. THE ENTRANCE SHALL BE MAINTAINED IN A CONDITION WHICH WILL PREVENT TRACKING OR FLOW OF MUD ONTO PUBLIC RIGHTS-OF-WAY. THIS MAY REQUIRE PERIODIC WASHING OF THE MATS AND/OR REPLACEMENT OF WOOD CHIPS AS NECESSARY.
 - a.c. ALL MATERIALS SPILLED, DROPPED, WASHED, OR TRACKED FROM VEHICLES ONTO ROADWAYS OR INTO STORM DRAINS MUST BE REMOVED IMMEDIATELY.
 - a.d. THE USE OF WATER TRUCKS TO REMOVE MATERIALS DROPPED, WASHED, OR TRACKED INTO ROADWAYS WILL NOT BE PERMITTED UNDER ANY CIRCUMSTANCES.
- b. SILT FENCE - VESCH 3.05
 - b.a. SILT FENCE WILL BE INSTALLED WITH THE E&S PLAN TO FILTER RUNOFF FROM DISTURBED AREAS. RUNOFF SHALL NOT BE DIRECTED PARALLEL TO THE INSTALLATION OF SILT FENCE.
 - b.b. SILT FENCES SHALL BE INSPECTED IMMEDIATELY AFTER EACH RAINFALL AND AT LEAST DAILY DURING PROLONGED RAINFALL. ANY REQUIRED REPAIRS SHALL BE MADE IMMEDIATELY.
 - b.c. CLOSE ATTENTION SHALL BE PAID TO THE REPAIR OF DAMAGED SILT FENCE RESULTING FROM UNDERCUTTING.
 - b.d. SHOULD THE FABRIC ON A SILT FENCE DECOMPOSE OR BECOME INEFFECTIVE PRIOR TO THE END OF THE EXPECTED USABLE LIFE, THE FABRIC SHALL BE REPLACED IMMEDIATELY.
 - b.e. SEDIMENT DEPOSITS SHALL BE REMOVED AFTER EACH STORM EVENT. THEY MUST BE REMOVED WHEN DEPOSITS REACH APPROXIMATELY ONE-HALF THE HEIGHT OF THE BARRIER.
 - b.f. ANY SEDIMENT DEPOSITS REMAINING IN PLACE AFTER THE SILT FENCE IS NO LONGER REQUIRED SHALL BE DRESSED TO CONFORM WITH THE EXISTING GRADE, THEN PREPARED AND SEEDED.
- c. TEMPORARY DIVERSION DIKE - VESCH 3.09
 - c.a. A SYSTEM OF TEMPORARY DIKES, TO DIRECT FLOW INTO PROPOSED & EXISTING STORM SEWER STRUCTURES WILL BE INSTALLED AS INDICATED IN EROSION & SEDIMENT CONTROL PLAN.
 - c.b. THE STRUCTURES SHALL BE INSPECTED AFTER EACH RAIN EVENT AND REPAIRS SHALL BE MADE AS NECESSARY.
 - d. STORM DRAIN INLET PROTECTION - VESCH 3.07
 - d.a. ALL EXISTING & PROPOSED STORM SEWER INLETS IN AND AROUND THE PROJECT LIMITS SHALL BE PROTECTED DURING CONSTRUCTION. SEDIMENT-LADEN WATER SHALL BE FILTERED BEFORE ENTERING THE STORM SEWER INLETS.
 - d.b. THE STRUCTURE SHALL BE INSPECTED AFTER EACH RAIN EVENT AND REPAIRS SHALL BE MADE AS NECESSARY.
 - d.c. STRUCTURES SHALL BE REMOVED AND THE AREA STABILIZED WHEN THE REMAINING DRAINAGE AREA HAS BEEN PROPERLY STABILIZED.
- e. DEWATERING STRUCTURE - VESCH 3.26
 - e.a. SEDIMENT LADEN OR TURBID WATER SHALL BE FILTERED, SETTLED OR SIMILARLY TREATED PRIOR TO DISCHARGE.
 - e.b. THE FILTERING DEVICES MUST BE INSPECTED FREQUENTLY AND REPAIRED OR REPLACED ONCE THE SEDIMENT BUILD-UP PREVENTS THE STRUCTURE FROM FUNCTIONING AS DESIGNED.
 - e.c. THE ACCUMULATED SEDIMENT WHICH IS REMOVED FROM A DEWATERING DEVICE MUST BE SPREAD ON-SITE AND STABILIZED OR DISPOSED OF AT AN APPROVED DISPOSAL SITE AS PER THE APPROVED PLAN.

f. TREE PROTECTION - VESCH 3.38

- f.a. ALL TREES ARE TO BE PROTECTED UNLESS OTHERWISE DIRECTED BY THE COUNTY INSPECTOR AND URBAN FORESTER. THE COUNTY'S URBAN FORESTER (703-228-1863) SHALL INSPECT ALL TREE PROTECTION 72 HOURS PRIOR TO THE START OF CONSTRUCTION. IN SPITE OF PRECAUTIONS, SOME DAMAGE TO PROTECTED TREES MAY OCCUR. IN SUCH CASES, THE FOLLOWING MAINTENANCE GUIDELINES SHALL BE FOLLOWED:
 - f.a.a. SOIL AERATION: IF THE SOIL HAS BECOME COMPACTED OVER THE ROOT ZONE OF ANY TREE, THE GROUND SHALL BE AERATED BY PUNCHING HOLES WITH AN IRON BAR. THE BAR SHALL BE DRIVEN 1-FOOT DEEP AND THEN MOVED BACK AND FORTH UNTIL THE SOIL IS LOOSEENED. THIS PROCEDURE SHALL BE REPEATED EVERY 18 INCHES UNTIL ALL OF THE COMPACTED SOIL BENEATH THE CROWN OF THE TREE HAS BEEN LOOSEENED.
 - f.a.b. REPAIR OF DAMAGE:
 - f.a.a.A. ANY DAMAGE TO THE CROWN, TRUNK, OR ROOT SYSTEM OF ANY TREE RETAINED ON THE SITE SHALL BE REPAIRED IMMEDIATELY.
 - f.a.a.B. WHENEVER MAJOR ROOT OR BARK DAMAGE OCCURS, REMOVE SOME FOLIAGE TO REDUCE THE DEMAND FOR WATER AND NUTRIENTS.
 - f.a.a.C. DAMAGED ROOTS SHALL IMMEDIATELY BE CUT OFF CLEANLY INSIDE THE EXPOSED OR DAMAGED AREA. CUT SURFACES SHALL BE PAINTED WITH APPROVED TREE PAINT, AND MOIST PEAT MOSS, BURLAP, OR TOPSOIL SHALL BE SPREAD OVER THE EXPOSED AREA.
 - f.a.a.D. TO TREAT BARK DAMAGE, CAREFULLY CUT AWAY ALL LOOSEENED BARK BACK INTO THE UNDAMAGED AREA, TAPER THE CUT AT THE TOP AND BOTTOM, AND PROVIDE DRAINAGE AT THE BASE OF THE WOUND.
 - f.a.a.E. ALL TREE LIMBS DAMAGED DURING CONSTRUCTION OR REMOVED FOR ANY OTHER REASON SHALL BE CUT OFF ABOVE THE COLLAR AT THE PRECEDING BRANCH JUNCTION.
 - f.a.a.F. CARE FOR SERIOUS INJURIES SHALL BE PRESCRIBED BY A FORESTER OR A TREE SPECIALIST.
 - f.b. FERTILIZATION: BROADLEAF TREES THAT HAVE BEEN STRESSED OR DAMAGED SHALL RECEIVE A HEAVY APPLICATION OF FERTILIZER TO AID THEIR RECOVERY.
 - f.b.a. TREES SHALL BE FERTILIZED IN THE LATE FALL (AFTER OCTOBER 1) OR THE EARLY SPRING (FROM THE TIME FROST IS OUT OF THE GROUND UNTIL MAY 1). FALL APPLICATIONS ARE PREFERRED, AS THE NUTRIENTS WILL BE MADE AVAILABLE OVER A LONGER PERIOD OF TIME.
 - f.b.b. FERTILIZER SHALL BE APPLIED TO THE SOIL OVER THE FEEDER ROOTS. IN NO CASE SHALL IT BE APPLIED CLOSER THAN 3 FEET TO THE TRUNK. THE ROOT SYSTEM OF CONIFERS EXTENDS SOME DISTANCE BEYOND THE DRIP LINE. INCREASE THE AREA TO BE FERTILIZED BY ONE FOURTH THE AREA OF THE CROWN.
 - f.b.c. FERTILIZER SHALL BE APPLIED USING APPROVED FERTILIZATION METHODS AND EQUIPMENT.
 - f.b.d. FORMULATIONS AND APPLICATION RATES SHALL CONFORM TO THE GUIDELINES GIVEN IN TABLE 3.38-A OF VESCH.

2. VEGETATIVE PRACTICES

- a. TOPSOILING (STOCKPILE) - VESCH 3.30
 - a.a. TOPSOIL WILL BE STRIPPED FROM AREAS TO BE GRADED AND STOCKPILED FOR LATER USE. STOCKPILE LOCATIONS MAY HAVE TO BE LOCATED OFF-SITE AND ARE TO BE STABILIZED WITH TEMPORARY VEGETATION. PRIOR TO LAND-DISTURBING ACTIVITIES, THE CONTRACTOR SHALL SUBMIT A SUPPLEMENTARY E&S PLAN (IF THE STOCKPILE IS LOCATED OFF-SITE). THIS SUPPLEMENTAL PLAN WOULD HAVE TO BE APPROVED BY THE PLAN APPROVING AUTHORITY BEFORE ANY OFF-SITE ACTIVITY COMMENCES.
- b. TEMPORARY SEEDING - VESCH 3.31
 - b.a. ALL DENUDED AREAS, WHICH WILL BE LEFT DORMANT FOR EXTENDED PERIODS OF TIME SHALL BE SEEDED WITH FAST GERMINATING TEMPORARY VEGETATION IMMEDIATELY FOLLOWING GRADING. SELECTION OF THE SEED MIXTURE WILL DEPEND ON THE TIME OF YEAR IT IS APPLIED.
 - b.b. SEE SHEET III-288 OF THE VIRGINIA EROSION AND SEDIMENT CONTROL HANDBOOK (VESCH) FOR ALLOWABLE PLANTING MATERIAL, SEEDING RATES, AND DATES. THE PLANTING REQUIREMENTS OF THE "SOUTH" SHALL BE FOLLOWED. LIMING SHALL BE BASED ON TABLE 3.31-A OF VESCH. FERTILIZERS SHALL BE APPLIED AS 600 LB/ACRE. THE FERTILIZER SHALL BE INCORPORATED INTO THE TOP 2-4" OF SOIL. SEED SHALL BE EVENLY APPLIED AND SMALL GRAINS SHALL BE PLANTED NO MORE THAN 1.5" DEEP. SEEDING MADE IN FALL FOR WINTER COVER AND DURING HOT SUMMER MONTHS SHALL BE MULCHED.
- c. EROSION CONTROL BLANKET AND MULCHING - VESCH 3.36 AND 3.35
 - c.a. EROSION CONTROL BLANKETS WILL BE INSTALLED OVER FILL SLOPES WHICH HAVE BEEN BROUGHT TO FINAL GRADE AND HAVE BEEN SEEDED TO PROTECT THE SLOPES FROM RILL AND GULLY EROSION AND TO ALLOW SEED TO GERMINATE PROPERLY. MULCH (STRAW OR FIBER) WILL BE USED ON RELATIVELY FLAT AREAS AND WILL BE APPLIED AS A SECOND STEP IN SEEDING OPERATION.
- d. DUST CONTROL - VESCH 3.39
 - d.a. DUST SHALL BE CONTROLLED USING A VARIETY OF METHODS SUCH AS VEGETATIVE COVER, MULCH, TILLAGE, IRRIGATION, SPRAY-ON ADHESIVES, STONE BARRIERS, AND CALCIUM CHLORIDE. THE IMPLEMENTATION OF THE DUST CONTROL METHODS SHALL BE INSTALLED PER SECTION 3.39 OF VESCH.
 - e. PERMANENT SEEDING - VESCH 3.32
 - e.a. SINCE THE SUBJECT SITE IS LOCATED WITHIN THE COASTAL PLAIN AREA OF VIRGINIA, SHEET III-304 OF THE VIRGINIA EROSION AND SEDIMENT CONTROL HANDBOOK SHALL BE FOLLOWED FOR FINAL SEEDING MATERIAL, SEEDING RATES, AND DATES OF APPLICATION.
 - f. SODDING - VESCH 3.33
 - f.a. SODDED AREAS SHALL BE BROUGHT TO FINAL GRADE IN ACCORDANCE WITH THE APPROVED PLANS. SOIL TESTS SHALL BE MADE TO DETERMINE THE EXACT REQUIREMENTS FOR LIME AND FERTILIZER. PRIOR TO LAYING SOD, SOIL SURFACE SHALL BE CLEAR OF TRASH, DEBRIS AND LARGE OBJECTS. QUALITY OF SOD SHALL BE STATE CERTIFIED TO ENSURE GENETIC PURITY AND HIGH QUALITY. SOD SHALL NOT BE LAID ON FROZEN SOIL SURFACE, OR IN EXCESSIVELY WET OR DRY WEATHER. SOD SHALL BE DELIVERED AND INSTALLED WITHIN 36 HOURS, AND SHALL BE INSTALLED PER PAGE III-339 OF VESCH.

THE EROSION AND SEDIMENT CONTROL INSPECTOR SHALL HAVE THE AUTHORITY TO ADD OR DELETE EROSION AND SEDIMENT CONTROLS AS NEEDED IN THE FIELD. IN ADDITION, NO SEDIMENT TRAPS OR BASINS MAY BE REMOVED WITHOUT PRIOR APPROVAL OF THE INSPECTOR.

EROSION AND SEDIMENT CONTROL MANAGEMENT MEASURES

LANDSCAPE / TREE PRESERVATION NOTES

PRIOR TO ANY LAND DISTURBING ACTIVITY, THE CONTRACTOR SHALL CONTACT THE ARLINGTON COUNTY ARBORIST TO SCHEDULE AN INSPECTION.

LAND CONSERVATION NOTES:

- 1. NO DISTURBED AREA WILL REMAIN DENUDED FOR MORE THAN 7 CALENDAR DAYS UNLESS OTHERWISE AUTHORIZED BY THE DIRECTOR OR HIS AGENT.
- 2. ALL EROSION AND SEDIMENT CONTROL MEASURES ARE TO BE PLACED PRIOR TO OR AS THE FIRST STEP IN GRADING. FIRST AREAS TO BE CLEARED ARE TO BE THOSE REQUIRED FOR THE PERIMETER CONTROLS.
- 3. ALL STORM AND SANITARY SEWER LINES NOT IN STREETS ARE TO BE MULCHED AND SEEDED WITHIN 5 DAYS AFTER BACKFILL. NO MORE THAN 100 FEET ARE TO BE OPEN AT ANY ONE TIME.
- 4. ELECTRIC POWER, TELEPHONE AND GAS SUPPLY TRENCHES ARE TO BE COMPACTED, SEEDED AND MULCHED WITHIN 5 DAYS AFTER BACKFILLING.
- 5. ALL TEMPORARY EARTH BERMS, DIVERSIONS AND SEDIMENT CONTROL DAMS ARE TO BE MULCHED AND SEEDED FOR TEMPORARY VEGETATIVE COVER IMMEDIATELY AFTER GRADING. STRAW OR HAY MULCH IS REQUIRED. THE SAME APPLIES TO ALL SOIL STOCKPILES.
- 6. DURING CONSTRUCTION, ALL STORM SEWER INLETS WILL BE PROTECTED BY INLET PROTECTION.
- 7. ANY DISTURBED AREA NOT COVERED BY NOTE 1 ABOVE AND NOT PAVED, SODDED OR BUILT UPON BY NOV. 1, OR DISTURBED AFTER THAT DATE, SHALL BE MULCHED IMMEDIATELY WITH HAY OR STRAW MULCH AT THE RATE OF 2 TONS/ACRE AND OVER-SEEDED BY APRIL 15.
- 8. AT THE COMPLETION OF ANY PROJECT CONSTRUCTION AND PRIOR TO BOND RELEASE, ALL TEMPORARY SEDIMENT CONTROLS SHALL BE REMOVED AND ALL DENUDED AREAS SHALL BE STABILIZED.

EROSION & SEDIMENT CONTROL PROGRAM:

- 1. THE EROSION CONTROL PLAN IS INTENDED TO ESTABLISH ENTRANCES AND PERIMETER CONTROL MEASURES WHICH INCLUDES SILT FENCE (SF), INLET PROTECTION (IP), AND OTHER CONTROLS SPECIFIED ON THE PLANS.
- 2. WHERE CONSISTENT WITH JOB SAFETY REQUIREMENTS, ALL EXCAVATED MATERIAL SHALL BE PLACED ON THE UPHILL SIDE OF TRENCHES. NO MATERIAL SHALL BE PLACED IN STREAMBEDS. ANY STOCKPILED MATERIAL WHICH WILL REMAIN IN PLACE LONGER THAN 7 DAYS SHALL BE SEEDED AND MULCHED. WHEN SPOIL IS PLACED ON THE DOWNHILL SIDE OF TRENCH, IT SHALL BE BACKSLOPED TO DRAIN TOWARD THE TRENCH. WHEN NECESSARY TO DEWATER THE TRENCH, THE PUMP DISCHARGE HOSE SHALL OUTLET IN A STABILIZED AREA OR A SEDIMENT TRAPPING DEVICE.
- 3. ALL PRACTICES AND CONTROL DEVICES DESCRIBED HEREIN SHALL CONFORM TO THE CURRENT VIRGINIA EROSION AND SEDIMENT CONTROL HANDBOOK (VESCH). IN ADDITION, THE CONTRACTOR SHALL TAKE THE FOLLOWING STEPS TO MINIMIZE THE VOLUME OF SILT:
 - a. CONTRACTOR SHALL EVALUATE THE SITE TO DETERMINE EXTENSIVE CUT AND FILL AREAS, AND SHALL WORK THOSE AREAS TO MINIMIZE THE USE OF HEAVY EQUIPMENT. CONTRACTOR SHALL BRING DISTURBED AREAS TO GRADE (ROUGH OR FINISHED) AND STABILIZE THOSE AREAS WITH TEMPORARY OR PERMANENT VEGETATION. THESE DISTURBED AREAS SHALL BE STABILIZED PRIOR TO BEGINNING WORK IN ANOTHER AREA.
 - b. FILL AREAS SHALL BE COMPACTED COMPLETELY PRIOR TO THE END OF EACH WORK DAY. FILL SLOPE SURFACES SHALL BE KEPT ROUGH TO REDUCE SHEET EROSION OF THE SLOPES. CONTRACTOR SHALL RE-DIRECT CONCENTRATED RUNOFF, BY EARTH BERMS OR OTHER DEVICES, AROUND ACTIVELY DISTURBED AREAS TO STABILIZED OUTLETS.
 - c. CUT SLOPES SHALL BE PROTECTED FROM CONCENTRATED FLOW BY BERMS (ABOVE THE SLOPE) AND DIRECTED AROUND THE DISTURBED AREA TO STABILIZED OUTLETS.
- 4. MEASURES TO CONTROL EROSION AND SILTATION SHALL BE PROVIDED PURSUANT TO AND IN COMPLIANCE WITH CURRENT STATE AND LOCAL REGULATIONS. THE INFORMATION CONTAINED IN THE CONSTRUCTION PLANS AND/OR THE APPROVAL OF THE PLANS SHALL IN NO WAY RELIEVE THE CONTRACTOR OR HIS AGENT OF ANY LEGAL RESPONSIBILITY WHICH MAY BE REQUIRED BY THE CODE OF VIRGINIA AND CHAPTER 57 OF THE ARLINGTON COUNTY CODE.
- 5. ALL AREAS, ON OR OFF-SITE, THAT ARE DISTURBED BY THIS CONSTRUCTION AND WHICH ARE NOT PAVED OR BUILT UPON SHALL BE ADEQUATELY STABILIZED TO CONTROL EROSION AND SEDIMENTATION. ACCEPTABLE STABILIZATION SHALL CONSIST OF PERMANENT GRASS SEED MIXTURE OR SOD THAT IS INSTALLED IN ACCORDANCE WITH THE PROJECT SPECIFICATIONS. ALL SLOPES 3:1 AND GREATER SHALL BE RECEIVE SOIL STABILIZATION IN ACCORDANCE WITH THE SPECIFICATIONS.
- 6. WHERE STREAM CROSSINGS ARE REQUIRED FOR EQUIPMENT, TEMPORARY CULVERTS SHALL BE PROVIDED.
- 7. FOR FURTHER REQUIREMENTS AND DETAILS OF TREE PRESERVATION, PLANTING, EROSION AND SEDIMENT CONTROL, SEE COUNTY CONSTRUCTION STANDARDS AND SPECIFICATIONS AND/OR THE VIRGINIA EROSION AND SEDIMENT CONTROL HANDBOOK.

GENERAL EROSION AND SEDIMENT CONTROL NOTES

- 1. UNLESS OTHERWISE INDICATED, ALL VEGETATIVE AND STRUCTURAL EROSION AND SEDIMENT CONTROL PRACTICES WILL BE CONSTRUCTED AND MAINTAINED ACCORDING TO THE MINIMUM STANDARDS AND SPECIFICATIONS OF THE VIRGINIA EROSION AND SEDIMENT CONTROL HANDBOOK AND VIRGINIA REGULATIONS VR 625-02-00 EROSION AND SEDIMENT CONTROL REGULATIONS.
- 2. THE PLAN APPROVING AUTHORITY MUST BE NOTIFIED ONE WEEK PRIOR TO THE PRE-CONSTRUCTION CONFERENCE, ONE WEEK PRIOR TO THE COMMENCEMENT OF LAND DISTURBING ACTIVITY, AND ONE WEEK PRIOR TO THE FINAL INSPECTION.
- 3. ALL EROSION AND SEDIMENT CONTROL MEASURES ARE TO BE PLACED PRIOR TO OR AS THE FIRST STEP IN CLEARING.
- 4. A COPY OF THE APPROVED EROSION AND SEDIMENT CONTROL PLAN SHALL BE MAINTAINED ON THE SITE AT ALL TIMES.
- 5. PRIOR TO COMMENCING LAND DISTURBING ACTIVITIES IN THE AREAS OTHER THAN INDICATED ON THESE PLANS (INCLUDING, BUT NOT LIMITED TO, OFF-SITE BORROW OR WASTE AREAS), THE CONTRACTOR SHALL SUBMIT A SUPPLEMENTARY EROSION AND SEDIMENT CONTROL PLAN TO THE OWNER FOR REVIEW AND APPROVAL BY THE PLAN APPROVING AUTHORITY.
- 6. THE CONTRACTOR IS RESPONSIBLE FOR INSTALLATION OF ANY ADDITIONAL EROSION AND SEDIMENT CONTROL MEASURES NECESSARY TO PREVENT EROSION AND SEDIMENTATION AS DETERMINED BY THE PLAN APPROVING AUTHORITY.
- 7. ALL DISTURBED AREAS ARE TO DRAIN TO APPROVED SEDIMENT CONTROL MEASURES AT ALL TIMES DURING LAND DISTURBING ACTIVITIES AND DURING SITE DEVELOPMENT UNTIL FINAL STABILIZATION IS ACHIEVED.
- 8. DURING DEWATERING OPERATIONS, WATER WILL BE PUMPED INTO AN APPROVED FILTERING DEVICE.
- 9. THE CONTRACTOR SHALL INSPECT ALL EROSION AND SEDIMENT CONTROL MEASURES PERIODICALLY AND AFTER EACH RUNOFF-PRODUCING RAINFALL EVENT. ANY NECESSARY REPAIRS OR CLEANUP TO MAINTAIN THE EFFECTIVENESS OF THE EROSION CONTROL DEVICES SHALL BE MADE IMMEDIATELY.
- 10. ALL BIOFILTERS SHALL BE KEPT OFF-LINE UNTIL CONSTRUCTION IS COMPLETED AND ALL AREAS HAVE BEEN PROPERLY STABILIZED. THIS SHALL BE ACHIEVED BY USING INLET PROTECTION AT THE CURB CUTS AND STORMWATER CATCH BASINS LEADING DIRECTLY INTO THE BIOFILTERS.
- 11. ALL TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES SHALL BE REMOVED WITHIN 30 DAYS AFTER FINAL SITE STABILIZATION OR AFTER THE TEMPORARY MEASURES ARE NO LONGER NEEDED.

PRE-STORM EROSION & SEDIMENTATION CHECKLIST:

PER GENERAL EROSION AND SEDIMENT CONTROL NOTE 6, THE CONTRACTOR IS RESPONSIBLE FOR THE INSTALLATION AND MAINTENANCE OF ANY ADDITIONAL EROSION AND SEDIMENT CONTROL (ESC) MEASURES NECESSARY TO PREVENT EROSION AND SEDIMENTATION AS DETERMINED BY THE COUNTY. THESE SUPPLEMENTARY PRACTICES ARE IN ADDITION TO THOSE SHOWN IN AN EROSION AND SEDIMENT CONTROL PLAN. EROSION AND SEDIMENT CONTROL PRACTICES SHALL BE MODIFIED AS NEEDED TO ENSURE ONLY CLEAR WATER IS DISCHARGED FROM THE SITE.

THE FOLLOWING ACTIONS SHALL BE TAKEN PRIOR TO STORM EVENTS WITH PREDICTED HEAVY AND/OR LARGE VOLUME RAINFALL TO PREVENT SEDIMENT DISCHARGES FROM A CONSTRUCTION SITE. A TYPICAL SUMMER THUNDERSTORM IS AN EXAMPLE OF A STORM EVENT WITH PREDICTED HEAVY AND/OR LARGE VOLUME RAINFALL.

- 1. PERIMETER CONTROLS
 - a. SILT FENCE SHALL BE CHECKED FOR UNDERMINING, HOLES, OR DETERIORATION OF THE FABRIC. FENCING SHALL BE REPLACED IMMEDIATELY IF THE FABRIC IS DAMAGED OR WON. SILT FENCE MUST BE TRENCHED INTO THE GROUND PER STATE SPECIFICATIONS (VESCH STD & SPEC 3.09).
 - b. WOODEN STAKES OR STEEL POSTS SHALL BE PROPERLY SECURED UPRIGHT INTO THE GROUND. DAMAGED POSTS OR STAKES MUST BE REPLACED. SEDIMENT THAT HAS ACCUMULATED AGAINST THE SILT FENCE SHALL BE REMOVED. ACCUMULATED SEDIMENT MUST BE REMOVED WHEN THE LEVEL REACHES ONE-HALF THE HEIGHT OF THE FENCING.
 - d. HAY BALES OR A STONE BERM SHALL BE PLACED ACROSS THE CONSTRUCTION ENTRANCE TO PREVENT SEDIMENT FROM LEAVING THE CONSTRUCTION SITE.
- 2. EXPOSED SLOPES AND SOIL
 - a. EXPOSED SLOPES NOT AT THE FINAL STABILIZATION PHASE SHALL BE COVERED WITH TARP, PLASTIC SHEETING, OR EROSION CONTROL MATTING. COVERING MATERIAL SHALL BE PROPERLY SECURED/ANCHORED.
 - b. CONTROLS SHALL BE INSTALLED TO PREVENT CONCENTRATED FLOW DOWN AN EXPOSED SLOPE. BERMS OR DIVERSION DIKES SHALL BE INSTALLED AT THE TOP OF CUT/EXPOSED SLOPES TO DIRECT STORM FLOW AROUND THE DISTURBED AREA.
 - c. EXPOSED SLOPES AT THE FINAL STABILIZATION PHASE SHALL BE STABILIZED USING SLOPE STABILIZATION PRACTICES SUCH AS SOIL STABILIZATION BLANKETS OR MATTING AS SPECIFIED IN THE VIRGINIA EROSION AND SEDIMENT CONTROL HANDBOOK (VESCH STD & SPEC 3.36). BLANKETS OR MATS MUST BE PROPERLY SECURED AND ANCHORED TO THE SOLE USING STAPLES, PINS, OR STAKES.
 - d. SEEDED AREAS SHALL BE CHECKED AND RESEEDED AS NECESSARY TO COVER EXPOSED SOIL. RECENTLY SEEDED AREAS SHALL BE PROTECTED BY STRAW OR SOIL STABILIZATION BLANKETS TO PREVENT SEEDING FROM BEING WASHED AWAY.
- 3. STOCKPILES
 - a. STOCKPILED SOIL AND OTHER LOOSE MATERIALS THAT CAN BE WASHED AWAY SHALL BE COVERED WITH A TARP, PLASTIC SHEETING, OR OTHER STABILIZATION MATTING. THE COVER MUST BE PROPERLY SECURED/ANCHORED DOWN TO PREVENT IT FROM BEING BLOWN OFF AND EXPOSING MATERIALS TO RAIN. CONTROLS SUCH AS HAY BALES OR BOOMS SHALL BE PLACED ALONG THE PERIMETER OF THE STOCKPILE (DOWNHILL SIDE).
- 4. INLET PROTECTION
 - a. INLET PROTECTION CONTROLS SHALL BE INSPECTED TO ENSURE THEY ARE FUNCTIONING PROPERLY AND FLOODING WILL NOT OCCUR. CLOGGED OR DAMAGED CONTROLS MUST BE REPLACED IMMEDIATELY. ENSURE CONTROLS ALLOW FOR OVERFLOW/BYPASS OF STORMWATER RUNOFF DURING SIGNIFICANT STORM EVENTS.

IN ADDITION TO THESE PRE-STORM ACTIONS, ALL EROSION AND SEDIMENT CONTROL (ESC) MEASURES MUST BE CHECKED DAILY AND AFTER EACH SIGNIFICANT RAINFALL.

POLLUTION PREVENTION PLAN NOTES (STORMWATER MANUAL - SECTION 2.4)

- 1. ONLY THE FOLLOWING NON-STORMWATER DISCHARGES ARE AUTHORIZED BY ARLINGTON COUNTY'S M54 PERMIT, UNLESS THE STATE WATER CONTROL BOARD, THE VIRGINIA SOIL AND WATER CONSERVATION BOARD (BOARD), OR ARLINGTON COUNTY DETERMINES THE DISCHARGE TO BE A SIGNIFICANT SOURCE OF POLLUTANTS TO SURFACE WATERS:
 - a. WATER LINE FLUSHING; LANDSCAPE IRRIGATION; DIVERTED STREAM FLOWS; RISING GROUND WATERS; UNCONTAMINATED GROUND WATER INFILTRATION (AS DEFINED AT 40 CFR 35.2005(20)); UNCONTAMINATED PUMPED GROUND WATER; DISCHARGES FROM POTABLE WATER SOURCES; FOUNDATION DRAINS; AIR CONDITIONING CONDENSATION; IRRIGATION WATER; SPRINGS; WATER FROM CRAWL SPACE PUMPS; FOOTING DRAINS; LAWN WATERING; INDIVIDUAL RESIDENTIAL CAR WASHING; FLOWS FROM RIPARIAN HABITATS AND WETLANDS; DECHLORINATED SWIMMING POOL DISCHARGES; DISCHARGES OR FLOWS FROM FIREFIGHTING; AND, OTHER ACTIVITIES GENERATING DISCHARGES IDENTIFIED BY THE DEPARTMENT OF ENVIRONMENTAL QUALITY AS NOT REQUIRING VPDES AUTHORIZATION.
- 2. APPROPRIATE CONTROLS MUST BE IMPLEMENTED TO PREVENT ANY NON-STORMWATER DISCHARGES NOT INCLUDED ON THE ABOVE LIST (E.G., CONCRETE WASH WATER, PAINT WASH WATER, VEHICLE WASH WATER, DETERGENT WASH WATER, ETC.) FROM BEING DISCHARGED INTO ARLINGTON COUNTY'S M54 SYSTEM, WHICH INCLUDES THE CURB AND GUTTER SYSTEM, AS WELL AS CATCH BASINS AND OTHER STORM DRAIN INLETS, OR STREAM NETWORK.
- 3. PER CHAPTER 26 OF THE ARLINGTON COUNTY CODE, IT SHALL BE UNLAWFUL FOR ANY PERSON TO DISCHARGE DIRECTLY OR INDIRECTLY INTO THE STORM SEWER SYSTEM OR STATE WATERS, ANY SUBSTANCE LIKELY, IN THE OPINION OF THE COUNTY MANAGER, TO HAVE AN ADVERSE EFFECT ON THE STORM SEWER SYSTEM OR STATE WATERS.

UTILITY INSTALLATION:

UNDERGROUND UTILITY LINES SHALL BE INSTALLED IN ACCORDANCE WITH THE FOLLOWING STANDARDS IN ADDITION TO OTHER APPLICABLE CRITERIA:

- 1. NO MORE THAN 100 LINEAR FEET OF TRENCH MAY BE OPENED AT ONE TIME.
- 2. EXCAVATED MATERIAL SHALL BE PLACED ON THE UPHILL SIDE OF TRENCHES.
- 3. EFFLUENT FROM DEWATERING OPERATIONS SHALL BE FILTERED OR PASSED THROUGH AN APPROVED SEDIMENT TRAPPING DEVICE, OR BOTH, AND DISCHARGED IN A MANNER THAT DOES NOT ADVERSELY AFFECT FLOWING STREAMS OR OFF-SITE PROPERTY.
- 4. MATERIAL USED FOR BACKFILLING TRENCHES SHALL BE PROPERLY COMPACTED IN ORDER TO MINIMIZE EROSION AND PROMOTE STABILIZATION.
- 5. STABILIZATION SHALL BE ACCOMPLISHED IN ACCORDANCE WITH THESE REGULATIONS.
- 6. APPLICABLE SAFETY REGULATIONS SHALL BE COMPLIED WITH.
- 9. ANY DISTURBED AREA NOT COVERED BY NOTE #1 ABOVE AND PAVED, SODDED OR BUILT UPON BY NOVEMBER 1ST, OR DISTURBED AFTER THAT DATE, SHALL BE MULCHED WITH HAY OR STRAW AT THE RATE OF 2 TONS PER ACRE AND OVER-SEEDED NO LATER THAN MAY 15TH.
- 10. AT THE COMPLETION OF THE CONSTRUCTION PROJECT AND PRIOR TO BOND RELEASE, ALL TEMPORARY SEDIMENT CONTROLS SHALL BE REMOVED AND ALL DENUDED AREAS SHALL BE STABILIZED. ARLINGTON COUNTY INSPECTOR TO APPROVE REMOVAL OF ALL TEMPORARY SILTATION MEASURES.

MAINTENANCE PROGRAM:

THE FOLLOWING IS A PROGRAM OF MAINTENANCE FOR THE MECHANICAL CONTROLS SPECIFIED IN THIS NARRATIVE AND ON THE PLAN:

- 1. THE SITE SUPERINTENDENT OR HIS/HER REPRESENTATIVE SHALL MAKE A VISUAL INSPECTION OF ALL MECHANICAL CONTROLS AND NEWLY STABILIZED AREA (I.E. SEEDED AND MULCHED AND/OR SODDED AREAS) ON A DAILY BASIS; ESPECIALLY AFTER A HEAVY RAINFALL EVENT TO ENSURE THAT ALL CONTROLS ARE MAINTAINED AND PROPERLY FUNCTIONING. ANY DAMAGED CONTROLS SHALL BE REPAIRED PRIOR TO THE END OF THE WORK DAY INCLUDING RE-SEEDING AND MULCHING OR RE-SODDING IF NECESSARY.
- 2. ALL SEDIMENT TRAPPING DEVICES SHALL BE CLEARED OUT AT 50% TRAP CAPACITY AND THE SEDIMENT SHALL BE DISPOSED OF BY SPREADING ON THE SITE OR IF NOT SUITABLE FOR FILL, HAULING AWAY AND DEPOSITING AT AN ACCEPTABLE DUMP SITE.
- 3. THE CONTRACTOR SHALL TAKE SPECIAL CARE TO PREVENT MUD AND/OR OTHER DEBRIS FROM BEING ENTERED ONTO EXISTING SWM/BMP FACILITIES OR DOWNSTREAM WATER WAYS. SHOULD OFF-SITE AREAS BECOME POLLUTED BY CONSTRUCTION ACTIVITIES, THE CONTRACTOR SHALL BE RESPONSIBLE FOR CLEANING THE AFFECTED AREAS TO THE SATISFACTION OF THE INSPECTOR.
- 4. AT THE COMPLETION OF CONSTRUCTION AND PRIOR TO BOND RELEASE, ALL TEMPORARY SEDIMENT CONTROLS SHALL BE REMOVED AND ANY REMAINING DENUDED AREAS SHALL BE STABILIZED. CERTAIN DEVICES MAY BE REMOVED PRIOR TO CONSTRUCTION COMPLETION BUT ONLY WITH THE APPROVAL OF THE COUNTY INSPECTOR.
- 5. AFTER CONSTRUCTION OPERATIONS HAVE ENDED, ALL DISTURBED AREAS SHALL BE STABILIZED. UPON APPROVAL OF THE COUNTY INSPECTOR, MECHANICAL SEDIMENT CONTROLS SHALL BE REMOVED AND THE GROUND PERMANENTLY STABILIZED WITH VEGETATION WITHIN 30 DAYS.



DEPARTMENT OF ENVIRONMENTAL SERVICES
FACILITIES & ENGINEERING DIVISION
ENGINEERING BUREAU
2100 CLARENDON BOULEVARD, SUITE 813
ARLINGTON, VA 22201
PHONE: 703.228.3629
FAX: 703.228.3606

COPYRIGHT © 2021 ARLINGTON COUNTY VIRGINIA - ALL RIGHTS RESERVED

SEAL









APPROVALS	DATE
<i>Any Plawn</i>	02/23/23
<i>Edward Sanders</i>	03/03/23
<i>Alan</i>	3/2/23
<i>Hagan</i>	03/03/2023
<i>Mark</i>	3/7/23

REVISIONS	DATE

APPROVALS	DATE

14TH ST. N. & N. VEITCH ST. P31D



ARLINGTON VIRGINIA

DEPARTMENT OF ENVIRONMENTAL SERVICES

FACILITIES & ENGINEERING DIVISION

ENGINEERING BUREAU

2100 CLARENDON BOULEVARD, SUITE 813

ARLINGTON, VA 22201

PHONE: 703.228.3629

FAX: 703.228.3606

COPYRIGHT © 2021 ARLINGTON COUNTY VIRGINIA - ALL RIGHTS RESERVED

SEAL

COMMONWEALTH OF VIRGINIA

ZORAN DRAGACEVAC

No. 031869

PROFESSIONAL ENGINEER

APPROVALS	DATE
<i>Amy Plawin</i>	02/23/23
QUALITY CONTROL ENGINEER	
<i>Edward Sanders</i>	03/03/23
CONSTRUCTION MANAGEMENT SUPERVISOR	
<i>Alan</i>	3/2/23
WATER, SEWER, STREETS BUREAU CHIEF	
<i>Henry</i>	03/03/2023
TRANSPORTATION DIRECTOR	
<i>Stefan</i>	3/7/23
PROJECT MANAGER	

REVISIONS	DATE

14TH ST. N. & N. VEITCH ST.

P31D

14TH ST. N. @ N. VEITCH ST.

EROSION AND SEDIMENT CONTROL NOTES AND DETAILS

DESIGNED: K. PATEL

DRAWN: K. PATEL

CHECKED: Z. DRAGACEVAC

PLOTTED: MARCH 8 2023

SCALE:

AS SHOWN

TABLE 3.31-B
(Revised June 2003)
TEMPORARY SEEDING SPECIFICATIONS
QUICK REFERENCE FOR ALL REGIONS

SEED		
APPLICATION DATES	SPECIES	APPLICATION RATES
Sept. 1 - Feb. 15	50/50 Mix of Annual Ryegrass (lolium multi-florum) & Cereal (Winter) Rye (Secale cereale)	50 - 100 (lbs/acre)
Feb. 16 - Apr. 30	Annual Ryegrass (lolium multi-florum)	60 - 100 (lbs/acre)
May 1 - Aug. 31	German Millet	50 (lbs/acre)

FERTILIZER & LIME

- Apply 10-10-10 fertilizer at a rate of 450 lbs. / acre (or 10 lbs. / 1,000 sq. ft.)
- Apply Pulverized Agricultural Limestone at a rate of 2 tons/acre (or 90 lbs. / 1,000 sq. ft.)

NOTE:
1 - A soil test is necessary to determine the actual amount of lime required to adjust the soil pH of site.
2 - Incorporate the lime and fertilizer into the top 4 - 6 inches of the soil by disking or by other means.
3 - When applying Slowly Available Nitrogen, use rates available in Erosion & Sediment Control Technical Bulletin # 4, 2003 Nutrient Management for Development Sites at <http://www.dcr.state.va.us/sw/e&s.htm#pubs>

TABLE 3.32-D
(Revised June 2003)
PERMANENT SEEDING SPECIFICATIONS FOR PIEDMONT AREA


SEED ¹		
LAND USE	SPECIES	APPLICATION PER ACRE
Minimum Care Lawn (Commercial or Residential)	Tall Fescue ¹	95-100%
	Perennial Ryegrass	0-5%
	Kentucky Bluegrass ¹	0-5%
		TOTAL: 175-200 lbs.
High-Maintenance Lawn	Tall Fescue ¹	TOTAL: 200-250 lbs.
General Slope (3:1 or less)	Tall Fescue ¹	128 lbs.
	Red Top Grass or Creeping Red Fescue	2 lbs.
	Seasonal Nurse Crop ²	20 lbs.
Low-Maintenance Slope (Steeper than 3:1)	Tall Fescue ¹	108 lbs.
	Red Top Grass or Creeping Red Fescue	2 lbs.
	Seasonal Nurse Crop ²	20 lbs.
	Crownvetch ³	20 lbs.
		TOTAL: 150 lbs.

NOTE:
1 - When selecting varieties of turfgrass, use the Virginia Crop Improvement Association (VCIA) recommended turfgrass variety list. Quality seed will bear a label indicating that they are approved by VCIA. A current turfgrass variety list is available at the local County Extension office or through VCIA at 804-746-4884 or at <http://sudan.cses.vt.edu/html/Turf/turf/publications/publications2.html>
2 - Use seasonal nurse crop in accordance with seeding dates as stated below:
February 16th - April Annual Rye
May 1st - August 15th Foxtail Millet
August 16th - October Annual Rye
November - February 15th Winter Rye
3 - Substitute Sericea lespedeza for Crownvetch east of Farmville, VA (May through September use hulled seed, all other periods, use unhulled Sericea). If Flatpea is used, increase rate to 30 lbs./acre. If Weeping Lovegrass is used, include in any slope or low maintenance mixture during warmer seeding periods, increase to 30-40

FERTILIZER & LIME


- Apply 10-20-10 fertilizer at a rate of 500 lbs. / acre (or 12 lbs. / 1,000 sq. ft.)
- Apply Pulverized Agricultural Limestone at a rate of 2 tons/acre (or 90 lbs. / 1,000 sq. ft.)

NOTE:
- A soil test is necessary to determine the actual amount of lime required to adjust the soil pH of site.
- Incorporate the lime and fertilizer into the top 4 - 6 inches of the soil by disking or by other means.
- When applying Slowly Available Nitrogen, use rates available in Erosion & Sediment Control Technical Bulletin # 4, 2003 Nutrient Management for Development Sites at <http://www.dcr.state.va.us/sw/e&s.htm#pubs>



APPROVALS	DATE
<i>Amy Plawin</i> QUALITY CONTROL ENGINEER	02/23/23
<i>Edward Sanders</i> CONSTRUCTION MANAGEMENT SUPERVISOR	03/03/23
<i>[Signature]</i> WATER/SEWER, STREETS BUREAU CHIEF	3/2/23
<i>[Signature]</i> TRANSPORTATION DIRECTOR	03/03/2023
<i>[Signature]</i> PROJECT MANAGER	3/7/23

REVISIONS	DATE



SOURCE: VA. DSWC

PLATE: 3.33-1

14TH ST. N. & N. VEITCH ST.
P31D
14TH ST N. @ N. VEITCH ST.
EROSION AND SEDIMENT CONTROL
NOTES AND DETAILS

DESIGNED: K. PATEL
DRAWN: K.PATEL
CHECKED: Z. DRAGACEVAC
PLOTTED: MARCH 8 2023

SCALE:

AS SHOWN


RUNOFF REDUCTION NOTES:

THE RUNOFF REDUCTION SPREADSHEET INFORMATION ON THIS PLAN IS FOR DATA TRACKING PURPOSES TO DOCUMENT THE AREA OF LAND DISTURBANCE AND TO CHARACTERIZE PRE- AND POST-DEVELOPMENT LAND USE CONDITIONS. IN ACCORDANCE WITH ARLINGTON COUNTY'S CHESAPEAKE BAY TOTAL MAXIMUM DAILY LOAD (TMDL) ACTION PLAN, APPROVED BY THE VIRGINIA DEPARTMENT OF ENVIRONMENTAL QUALITY (DEQ) ON SEPTEMBER 1, 2015, LINEAR DEVELOPMENT PROJECTS CONDUCTED BY THE COUNTY ARE ADMINISTERED AND TRACKED AS FOLLOWS CONSISTENT WITH 9VAC25-870-69.4, 9VAC25-870-76, AND 9VAC25-870-92:


- POLLUTANT LOAD CHANGES WILL BE COMPUTED AS DESCRIBED IN SECTION 3.A OF THE ACTION PLAN.
- RETROFIT OPPORTUNITIES WILL BE EVALUATED FOR EACH PROJECT, USING THE SCREENING AND SELECTION CRITERIA APPLIED AND DESCRIBED IN THE ADOPTED STORMWATER MASTER PLAN.
- RETROFIT PROJECTS THAT MEET THE SCREENING CRITERIA AND ARE DETERMINED BY ARLINGTON TO BE FEASIBLE AND COST-EFFECTIVE WILL BE IMPLEMENTED WITH SPECIFIC LINEAR DEVELOPMENT PROJECTS. POLLUTANT LOAD REDUCTIONS FROM RETROFIT PROJECTS WILL BE COMPUTED AS DESCRIBED IN SECTION 5 OF THE ACTION PLAN.
- IN CASES WHERE RETROFIT PROJECTS ARE NOT FEASIBLE AND COST-EFFECTIVE FOR A PARTICULAR LINEAR PROJECT, ANY POLLUTANT OF CONCERN (POC) LOAD INCREASES THAT MIGHT OCCUR FOR THAT PROJECT WILL BE ADDRESSED BY LARGER OVERALL POC LOAD REDUCTIONS IN PLACE OR ADDED THROUGH TMDL ACTION PLAN IMPLEMENTATION.

IN THE ABOVE MANNER ARLINGTON, AS THE MS4 OPERATOR AND THE CONSTRUCTION SITE OPERATOR FOR ITS LINEAR DEVELOPMENT PROJECTS, IMPLEMENTS LINEAR PROJECTS AND RETROFIT PROJECTS IN A MANNER THAT ACHIEVES THE MOST TMDL POC REDUCTION FOR THE LEAST COST, WHILE FULLY ACCOUNTING FOR LOAD CHANGES THAT OCCUR WITH LINEAR DEVELOPMENT PROJECT ACTIVITY CONSISTENT WITH THE DEQ CHESAPEAKE BAY TMDL SPECIAL CONDITION GUIDANCE.

2011 BMP Standards and Specifications		2013 Draft BMP Standards and Specifications	
Project Name:	P31D 14TH STREET N.	Project Name:	P31D 14TH STREET N.
Date:	2 May 22	Date:	2 May 22
Site Information	Linear Development Project? Yes	Site Information	Linear Development Project? Yes
Post-Development Project (Treatment Volume and Loads)	Enter Total Disturbed Area (acres) → 0.1618	Check: (linear project?) Yes	BMP Design Specifications List: 2013 Draft Stds & Specs
	Maximum reduction required: 20%		Land cover area entered correctly? ✓
	The site's net increase in impervious cover (acres) is: 0.0000		Total disturbed area entered? ✓
	Post-Development TP Load Reduction for Site (lb/yr): 0.0637		
Pre-Development Land Cover (acres)	A Soils	B Soils	C Soils
Forest/Open Space (acres)	0.0000	0.0000	0.0000
Managed Turf (acres)	0.0003	0.0003	0.0003
Impervious Cover (acres)	0.1595	0.1595	0.1595
Total	0.1603	0.1603	0.1603
Post-Development Land Cover (acres)	A Soils	B Soils	C Soils
Forest/Open Space (acres)	0.0000	0.0000	0.0000
Managed Turf (acres)	0.0056	0.0056	0.0056
Impervious Cover (acres)	0.1562	0.1562	0.1562
Total	0.1618	0.1618	0.1618
Area Check	OK	OK	OK
Constants	Runoff Coefficients (Rv)		
Annual Rainfall (inches)	43	A Soils	B Soils
Target Rainfall Excess (inches)	1.00	0.02	0.03
Total Phosphorus TPL (lb/acre)	0.26	0.15	0.22
Total Nitrogen TPL (lb/acre)	1.86	0.95	0.95
Target TP Load (lb/acre/yr)	0.41		
TP Load Reduction Factor	0.90		
LAND COVER SUMMARY - PRE-REDEVELOPMENT	LAND COVER SUMMARY - POST DEVELOPMENT		
Pre-Development Land Cover Summary	Post-Development Land Cover Summary	Pre-Development Land Cover Summary	Post-Development Land Cover Summary
Forest/Open Space (acres)	0.0000	Forest/Open Space (acres)	0.0000
Managed Turf (acres)	0.0003	Managed Turf (acres)	0.0056
Impervious Cover (acres)	0.1595	Impervious Cover (acres)	0.1562
Total	0.1603	Total	0.1618
Final Post-Development TP Load (lb/yr)	0.3410	Final Post-Development TP Load (lb/yr)	0.3410
TP Load Reduction Required for Redeveloped Area (lb/yr)	0.0637	TP Load Reduction Required for New Impervious Area (lb/yr)	0
Post-Development Requirement for Site Area	TP Load Reduction Required (lb/yr)	0.0637	




ROOT PRUNING
311300.5 (2016) (02231.5) N.T.S. ARLINGTON DPR



- NOTES:
1. TREE PROTECTION FENCE (TPF) SHALL BE INSTALLED PRIOR TO ANY SITE WORK, CLEARING OR DEMOLITION. ARLINGTON COUNTY URBAN FORESTER SHALL BE NOTIFIED 72 HOURS PRIOR TO INSTALLATION.
 2. TPF SHALL BE MAINTAINED THROUGHOUT CONSTRUCTION.
 3. SIGN MATERIAL TO BE WEATHER RESISTANT.
 4. TREE PROTECTION BARRIERS MUST BE CONSTRUCTED WITH A SOLID WOOD FRAME CLAD WITH PLYWOOD OR APPROVED EQUIVALENT. SECURE BOARDS TO ENSURE PROTECTION IS NOT MOVED DURING PROJECT.
 5. HEIGHT OF BOARDING MAY BE LESS THAN 6 FEET TO ACCOMMODATE ANY BRANCHES THAT MAY BE LOWER. HEIGHT OF LESS THAN 6' SHALL BE APPROVED BY ARLINGTON COUNTY URBAN FORESTER.
 6. REMOVE TPF ONLY WITH APPROVAL FROM ARLINGTON COUNTY URBAN FORESTER AFTER ALL SITE WORK HAS BEEN COMPLETED.
 7. PROVIDE 12"(WIDTH) X4"(HEIGHT) CUT-OUTS ALONG PANELS FACING PAVED SURFACES SUCH AS SIDEWALKS, TWO CUT-OUTS PER FENCE PANEL.

TREE PROTECTION BARRIERS FOR RESTRICTED SPACE AND TREE PITS N.T.S. ARLINGTON DPR
311300.14NS (2019)



4' CHAIN LINK TREE PROTECTION FENCE (RESIDENTIAL) 1/2" = 1'-0" ARLINGTON DPR
311300.2 (2016) (02231.2)

GENERAL NOTES :

- Contractor to contact the Arlington Forester to schedule a pre-construction inspection of tree protection measures before any work near the critical root zones of trees. To schedule the pre-construction meeting call 703-228-1863.
- Contractor to protect trees per the plan according to the Arlington County DPR Design Standard Detail 311300.14NS
- Contractor to root prune trees per the plan according to the Arlington County DPR Design Standard Detail 02231.5, where called out on the plan.
- Contractor to call the urban forester at 703-228-1863, 72 hours before planting, to schedule inspection of the trees to be planted. Warranty for 1 year after planting shall be the contractor's responsibility. The urban forester and DPR is responsible for inspection.
- Contractor to prepare tree planting strips for the replacement trees according to Arlington County DPR Design Standard Detail 329300.4a and 329300.4b.
- Contractor to prepare street tree planting pits according to the Arlington County DPR Design Standard Detail 329300.3a, 329300.3b, and 329300.11c
- Contractor to plant the trees according to Arlington County DPR Design Standard Detail 329300.1 (on flat land) or 329300.2 (on slopes)

ARLINGTON VIRGINIA
DEPARTMENT OF ENVIRONMENTAL SERVICES
FACILITIES & ENGINEERING DIVISION
ENGINEERING BUREAU
2100 CLARENDON BOULEVARD, SUITE 813
ARLINGTON, VA 22201
PHONE: 703.228.3629
FAX: 703.228.3606

COPYRIGHT © 2021 ARLINGTON COUNTY VIRGINIA - ALL RIGHTS RESERVED

SEAL
COMMONWEALTH OF VIRGINIA
ZORAN DRAGACEVAC
No. 031869
PROFESSIONAL ENGINEER

APPROVALS	DATE
<i>Amy Plawin</i>	02/23/23
QUALITY CONTROL ENGINEER	
<i>Edward Sanders</i>	03/03/23
CONSTRUCTION MANAGEMENT SUPERVISOR	
<i>Alan</i>	3/2/23
WATER, SEWER, STREETS BUREAU CHIEF	
<i>Henry</i>	03/03/2023
TRANSPORTATION DIRECTOR	
<i>Paul</i>	3/7/23
PROJECT MANAGER	

REVISIONS	DATE

14TH ST. N. & N. VEITCH ST. P31D
14TH ST. N. @ N. VEITCH ST.

EROSION AND SEDIMENT CONTROL NOTES AND DETAILS

DESIGNED: K. PATEL
DRAWN: K. PATEL
CHECKED: ##
PLOTTED: MARCH 8 2023

SCALE:
AS SHOWN

STORMWATER POLLUTION PREVENTION PLAN

STORMWATER POLLUTION PREVENTION PLAN (SWPPP)
Arlington County Projects
(Linear Development / Stormwater Retrofit)

For Construction Activities At:

P31D/SITE S-5
14TH ST. N. & N. VEITCH ST.
Arlington, VA, 22205

Latitude = 38.8833 N (decimal degrees)

Longitude = - 77.0833 W (decimal degrees)

Construction Activity Operator:

Department of Environmental Services- Arlington County

2100 Clarendon Blvd, Suite 813
Arlington, Virginia, 22201
703-228-7537
ktaktak@arlingtonva.us
Kamal Taktak
703-228-7527

SWPPP Preparation Date:

05.02.2022

CERTIFICATION

I certify under penalty of law that I have read and understand this document and that this document and all attachments were prepared in accordance with a system designed to assure that qualified personnel properly gathered and evaluated the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations.

Operator Name: Zoran Dragacevac

Title: Design Team Supervisor, Department of Environmental Service

Signature:

Date: 05/06/2022

Arlington County SWPPP 12/2016

STORMWATER POLLUTION PREVENTION PLAN

1.0 SWPPP Documents Located Onsite & Available for Review

Table with 2 columns: SWPPP Document Type, Located Onsite & Available for Review? (Yes/No/NA)

Required documents must be kept at a centralized location on the project site (i.e. in a mail box or other container)

2.0 Authorized Non-Stormwater Discharges

Table with 2 columns: Type of Authorized Non-Stormwater Discharges, Likely Present at Your Project Site? (Yes/No)

3.0 Pollution Prevention Awareness

Employees will be given a "walk through" of the site identifying areas of possible pollution and will be shown Erosion and Sediment Controls and Pollution Prevention Practices (identified in Sections 4.0 and 5.0 of this SWPPP) that are applicable to their assigned job duties.

4.0 Erosion & Sediment Controls

Table with 5 columns: Select all that apply, Erosion & Sediment Control, Estimated Installation Date, Estimated Removal Date, Responsible Party

Arlington County SWPPP 12/2016

STORMWATER POLLUTION PREVENTION PLAN

Table with 2 columns: (Std. & Spec 3.08 and/or Arlington County Std. & Spec from approved ESC plan), (Std. & Spec 3.25 and/or Arlington County Std. & Spec from approved ESC plan)

Pre-Storm Erosion and Sediment Control Checklist

The following actions shall be taken prior to storm events with predicted heavy and/or large volume rainfall to prevent sediment discharges from a construction site.

- Perimeter controls (silt fence, hay bales, stone berms) used to prevent sediment from leaving the site shall be checked for undermining, holes, or deterioration and repaired/replaced if needed.
Sediment that has accumulated against perimeter controls shall be removed if the depth exceeds more than 1/2 of the silt fence height.
Exposed soil or slopes shall be covered with straw, tarps, plastic sheeting, or erosion control matting.

Arlington County SWPPP 12/2016

STORMWATER POLLUTION PREVENTION PLAN

5.0 Potential Sources of Pollution & Pollution Prevention Practices


Table with 10 columns: Pollutant-Generating Activity, Likely Present at your Project Site?, Sediment, Nutrients, Heavy Metals, pH (acids and bases), Pesticides & Herbicides, Oil & Grease, Bacteria & Viruses, Trash/Debris, Solids, Other Toxic Chemicals, Pollution Prevention Practice, Responsible Party

Arlington County SWPPP 11/2016

STORMWATER POLLUTION PREVENTION PLAN


Pollution Prevention Practices:

- Clearing, grading, excavating, and un-stabilized areas - Maintain as much existing vegetation as practicable. Utilize erosion and sediment controls to prevent sediment from leaving the construction site.
Paving and saw cutting operations - Cover storm drain inlets during paving and saw cutting operations. Use pollution prevention materials such as drip pans and absorbent/oli dry for all paving machines to limit leaks and spills of paving materials and fluids.
Concrete operations, washout, and cement waste - Direct concrete wash water into a leak-proof container or leak-proof settling basin that is designed so that no overflows can occur due to inadequate sizing or precipitation.



Arlington County SWPPP 12/2016

STORMWATER POLLUTION PREVENTION PLAN




- Washing / cleaning - Prevent the discharge of wash water to the storm drain system or surface waters.
Dewatering operations - Construction site dewatering may not be discharged without treatment. Sediment laden or turbid water shall be filtered, settled or similarly treated prior to discharge.

Arlington County SWPPP 12/2016



DEPARTMENT OF ENVIRONMENTAL SERVICES
FACILITIES & ENGINEERING DIVISION
ENGINEERING BUREAU
2100 CLARENDON BOULEVARD, SUITE 813
ARLINGTON, VA 22201
PHONE: 703.228.3629
FAX: 703.228.3606

COPYRIGHT © 2021 ARLINGTON COUNTY VIRGINIA - ALL RIGHTS RESERVED



APPROVALS DATE

Amy Plawin 02/23/23
Edward Sanders 03/03/23
3/2/23
03/03/2023
3/7/23

REVISIONS DATE

Table with 2 columns: REVISIONS, DATE

14TH ST. N. & N. VEITCH ST. P31D

14TH ST. N. @ N. VEITCH ST.

STORMWATER POLLUTION PREVENTION PLAN

DESIGNED: K. PATEL
DRAWN: K.PATEL
CHECKED: Z. DRAGACEVAC

PLOTTED: MARCH 8 2023

SCALE: N/A

N/A

C035.1

STORMWATER POLLUTION PREVENTION PLAN

- Stormwater Management Controls: Pump from Settling Pit, Manufactured System, Other. Material / chemical use and storage. Equipment and vehicle maintenance. Waste management / disposal.

Arlington County SWPPP 12/2016

STORMWATER POLLUTION PREVENTION PLAN

- 7.0 Spill Prevention & Response: Most spills can be cleaned up using a spill kit. 1st Priority: Protect all people. 2nd Priority: Protect equipment and property. 3rd Priority: Protect the environment.

Emergency Contacts: Local Contacts: Arlington County Fire & Police, DES Water, Sewer, Streets 24-Hour Emergency, Washington Gas Emergency. Nights, Holidays & Weekends: VA Dept. of Emergency Management 24 Hour Reporting Service.

Spill kit on site: Yes No. Location(s) of spill kit:

Arlington County SWPPP 12/2016

STORMWATER POLLUTION PREVENTION PLAN

- (9) Sanitary waste - Prevent the discharge of sanitary waste by providing convenient and well-maintained portable sanitary facilities. (10) Nutrient management - Apply nutrients in accordance with manufacturer's recommendations.

Additional information and details can be found in the Arlington County Planning & Field Guide for Pollution Prevention (P2).

Table with 4 columns: Select all that apply, Stormwater Management Control, Estimated Installation Date, Responsible Party. Rows include Exempted, Linear development project, Post-development Stormwater Management Controls, and Rooftop Disconnection.

In accordance with Arlington County's Chesapeake Bay Total Maximum Daily Load (TMDL) Action Plan, approved by the Virginia Department of Environmental Quality (DEQ) on September 1, 2015...

In the above manner Arlington, as the MS4 operator and the construction site operator for its linear development projects, implements linear projects and retrofit projects in a manner that achieves the most TMDL POC reduction for the least cost...

Arlington County SWPPP 12/2016

STORMWATER POLLUTION PREVENTION PLAN

8.0 Self Inspection Report & Corrective Action Log (make additional copies as necessary). Company/Organization, Name of Inspector, Telephone Number, Qualifications.

Inspection Schedule: Discharges to impaired waters, surface waters within a TMDL watershed, or exceptional waters: Once every 4 business days. Inspection Date:

Table with 4 columns: Erosion & Sediment Controls/ Pollution Prevention Practices, In Compliance?, Corrective Action Needed & Notes, Date Corrective Action Taken. Rows include sediment controls, perimeter controls, storm drains, slopes, dewatering, dust, and mature trees.

Arlington County SWPPP 12/2016

STORMWATER POLLUTION PREVENTION PLAN

Table with 3 columns: Control, Description, (See Cover Page of this SWPPP). Rows include Sheet flow to Vegetated Filter, Grass Channel, Rainwater Harvesting, Permeable Pavement, Infiltration, Bio-retention, and Others.

Arlington County SWPPP 12/2016

STORMWATER POLLUTION PREVENTION PLAN

Table with 3 columns: Question, Yes/No/NA, Answer. Rows include washout facilities, trash and waste materials, trash receptacles, non-stormwater discharges, vehicle and equipment fueling, materials stored properly, portable lavatories, and spill kit accessibility.

Are there any unauthorized discharges at the time of this inspection? Has any unauthorized discharge occurred since the last inspection?

Non - Compliance Issues: Describe any incidents of non-compliance not described above (use another page if necessary).

Certification: I certify under penalty of law that I have read and understand this document and that this document and all attachments were prepared in accordance with a system designed to assure that qualified personnel properly gathered and evaluated the information submitted.

Operator or Assigned Qualified Personnel Name: Signature: Date:

Arlington County SWPPP 12/2016




APPROVALS DATE: Amy Plawin 02/23/23, Edward Sanders 03/03/23, Construction Management Supervisor 3/2/23, Water/Sewer, Streets Bureau Chief 03/03/2023, Transportation Director 3/7/23, Project Manager.

REVISIONS DATE table with 2 columns.

14TH ST. N. & N. VEITCH ST. P31D 14TH ST N. @ N. VEITCH ST. STORMWATER POLLUTION PREVENTION PLAN

DESIGNED: K. PATEL, DRAWN: K.PATEL, CHECKED: Z. DRAGACEVAC, PLOTTED: MARCH 8 2023

SCALE: N/A



ROW ASSESSMENT

- NO ROW ACQUISITION OR PERMANENT EASEMENTS ARE ANTICIPATED WITH THIS PROJECT.

UTILITY IMPACT ASSESSMENT

WET UTILITIES:

- NO STORM SYSTEM IMPROVEMENT IS ANTICIPATED WITH THIS PROJECT.
- WATER METERS AND VALVES - VERTICAL ADJUSTMENTS ARE ANTICIPATED WITH THIS PROJECT.
- SANITARY MANHOLE - NO POTENTIAL CONFLICT.

DRY UTILITIES:

- NO IMPACTS TO EXISTING UTILITY POLES.
- NO IMPACTS TO EXISTING STREET LIGHT POLES.
- NO NEW STREET LIGHTS PROPOSED.
- NO IMPACTS TO EXISTING UNDERGROUND FACILITIES.

PERMIT ASSESSMENT

- COUNTY LDA PERMIT IS REQUIRED AS THE LAND DISTURBANCE IS MORE THAN 2500SF.

PARKING IMPACTS

- NO IMPACT ON EXISTING ON-STREET PARKING SPACE, EXCEPT N/E CORNER.

TREE IMPACTS

- NO TREE REMOVALS ARE ANTICIPATED WITH THIS PROJECT. FURTHER TREE IMPACTS TO BE EVALUATED BY COUNTY URBAN FORESTER.

OTHER IMPACTS

- ADDITIONAL FULL DEPTH PAVEMENT TO BE EVALUATED IN FINAL DESIGN STAGE.
- NO RETAINING WALLS ARE EXPECTED.

CONSTRUCTION NOTES

- 1 PROP CURB AND GUTTER (C-2) ARL STD (R-2.0)
- 1A PROP HEADER CURB (C-3) ARL STD (R-2.0)
- 2 PROP SIDEWALK ARL STD (R-2.0)
- 2.1 REMOVE AND RESET CONCRETE PAVR (R-2.1), PROVIDE SMOOTH TRANSITION TO MEET EXISTING WALKWAY GRADE.
- 2.2 REMOVE EXISTING CONCRETE TRAY AND PAVR FROM CROSSWALK AND REPLACE WITH FULL DEPTH ASPHALT.
- 2A PROP RAMP (CG-12A) VDOT ROAD & BRIDGE STANDARDS (204.02) SEE CURB RAMP DETAIL SHEET # C002.1
- 2B PROP RAMP (CG-12B) VDOT ROAD & BRIDGE STANDARDS (204.03) SEE CURB RAMP DETAIL SHEET #C002.1
- 6 PROPOSED ASPHALT FULL DEPTH REPLACEMENT AS PER ARLINGTON COUNTY STANDARD (R-1.4)
- 7 PROPOSED DETECTABLE WARNING SURFACE DARK GRAY COLOR PER ARLINGTON COUNTY STANDARD H-3.2, CURB RAMPS
- 8 ASPHALT - MILL AND OVERLAY (1/2" TO 3")
- 9 MATCH EXISTING T.O.C. OR SIDEWALK GRADE.
- 10 ADJUST EXISTING UTILITY BOX OR MH TO PROPOSED GRADE.
- 10A ADJUST SANITARY MANHOLE TO NEW GRADE PER SPEC 02500-3.4
- 10B ADJUST STORM MANHOLE TO NEW GRADE PER SPEC 02500-3.4
- 11 EXISTING STREET LIGHT POLE TO REMAIN
- 11A EXISTING FIRE HYDRANT TO REMAIN IN PLACE
- 11B EXISTING CABLE BOX TO REMAIN
- 11C EXISTING PARKING METER TO REMAIN
- 12 PROPOSED SOD PER ARLINGTON STD. & SPEC. SECTION 329200 SEEDING AND SODDING.
- 12A PROTECT TREE DURING CONSTRUCTION OF PROPOSED WORK AS SHOWN. CALL URBAN FORESTER (702-228-7980) PRIOR TO BEGINNING WORK ADJACENT TO TREES. PROCEED WITH WORK AS DIRECTED BY THE PROJECT OFFICER IF ANY CONFLICT ARISES WITH PROPOSED WORK.
- 13 REMOVE AND RESET MULCH, TO NEW GRADE BEHIND THE CURB

TREE PRESERVATION NOTES:

- CONTRACTOR TO CONTACT THE ARLINGTON FORESTER TO SCHEDULE A PRE-CONSTRUCTION INSPECTION OF THE TREE PROTECTION MEASURES BEFORE ANY WORK NEAR THE CRITICAL ROOT ZONES OF THE TREE. TO SCHEDULE THE PRE-CONSTRUCTION MEETING CALL 703-228-7980
- CONTRACTOR TO PROTECT TREES PER THE PLAN ACCORDING TO THE ARLINGTON COUNTY DPR DESIGN STANDARD DETAIL 311300.1
- CONTRACTOR TO ROOT PRUNE PER THE PLAN ACCORDING TO THE ARLINGTON COUNTY DPR DESIGN STANDARD DETAIL 311300.1, WHERE CALL OUT ON THE PLAN
- NO MECHANICAL DIGGING IN CRZ ZONE OF TREE, CONTRACTOR TO DO HAND DIGGING TO PROTECT ROOT ZONE.

ARLINGTON VIRGINIA
 DEPARTMENT OF ENVIRONMENTAL SERVICES
 FACILITIES & ENGINEERING DIVISION
 ENGINEERING BUREAU
 2100 CLARENDON BOULEVARD, SUITE 813
 ARLINGTON, VA 22201
 PHONE: 703.228.3629
 FAX: 703.228.3606

COPYRIGHT © 2021 ARLINGTON COUNTY VIRGINIA - ALL RIGHTS RESERVED

SEAL


ZORAN DRAGACEVAC
 No. 031869
 PROFESSIONAL ENGINEER


APPROVALS	DATE
<i>Amy Plawin</i>	02/23/23
QUALITY CONTROL ENGINEER	
<i>Edward Sanders</i>	03/03/23
CONSTRUCTION MANAGEMENT SUPERVISOR	
<i>Alan</i>	3/2/23
WATER, SEWER, STREETS BUREAU CHIEF	
<i>Henry</i>	03/03/2023
TRANSPORTATION DIRECTOR	
<i>Patel</i>	3/7/23
PROJECT MANAGER	

REVISIONS	DATE

14TH ST. N. & N. VEITCH ST.
 P31D
 14TH ST. N. @ N. VEITCH ST.
 PLAN AND PROFILE

DESIGNED: K. PATEL
 DRAWN: K.PATEL
 CHECKED: Z. DRAGACEVAC
 PLOTTED: MARCH 8 2023





CR-1

STANDARD ABBREVIATION:

- EX: EXISTING GRADE
- FG: FINISH GRADE
- TC: TOP OF CURB
- EP: EDGE OF PAVEMENT

ARLINGTON VIRGINIA
 DEPARTMENT OF ENVIRONMENTAL SERVICES
 FACILITIES & ENGINEERING DIVISION
 ENGINEERING BUREAU
 2100 CLARENDON BOULEVARD, SUITE 813
 ARLINGTON, VA 22201
 PHONE: 703.228.3629
 FAX: 703.228.3606

COPYRIGHT © 2021 ARLINGTON COUNTY VIRGINIA - ALL RIGHTS RESERVED





APPROVALS	DATE
<i>Amy Plawn</i> QUALITY CONTROL ENGINEER	02/23/23
<i>Edward Sanders</i> CONSTRUCTION MANAGEMENT SUPERVISOR	03/03/23
<i>[Signature]</i> WATER/SEWER, STREETS BUREAU CHIEF	3/2/23
<i>[Signature]</i> TRANSPORTATION DIRECTOR	03/03/2023
<i>[Signature]</i> PROJECT MANAGER	3/7/23

REVISIONS	DATE

14TH ST. N. & N. VEITCH ST.
 P31D
 14TH ST N. @ N. VEITCH ST.
 RAMP DETAILS

DESIGNED: K. PATEL
 DRAWN: K. PATEL
 CHECKED: Z. DRAGACEVAC
 PLOTTED: MARCH 8 2023





CR-2

STANDARD ABBREVIATION:

EX: EXISTING GRADE
 FG: FINISH GRADE
 TC: TOP OF CURB
 EP: EDGE OF PAVEMENT





APPROVALS	DATE
<i>Amy Plawn</i> QUALITY CONTROL ENGINEER	02/23/23
<i>Edward Sanders</i> CONSTRUCTION MANAGEMENT SUPERVISOR	03/03/23
<i>[Signature]</i> WATER/SEWER, STREETS BUREAU CHIEF	3/2/23
<i>[Signature]</i> TRANSPORTATION DIRECTOR	03/03/2023
<i>[Signature]</i> PROJECT MANAGER	3/7/23

REVISIONS	DATE

14TH ST. N. & N. VEITCH ST.
 P31D
 14TH ST N. @ N. VEITCH ST.
 RAMP DETAILS


DESIGNED: K. PATEL
 DRAWN: K. PATEL
 CHECKED: ##
 PLOTTED: MARCH 8 2023





STANDARD ABBREVIATION:

- EX: EXISTING GRADE
- FG: FINISH GRADE
- TC: TOP OF CURB
- EP: EDGE OF PAVEMENT





APPROVALS	DATE
<i>Amy Pflaum</i> QUALITY CONTROL ENGINEER	02/23/23
<i>Edward Sanders</i> CONSTRUCTION MANAGEMENT SUPERVISOR	03/03/23
<i>[Signature]</i> WATER/SEWER, STREETS BUREAU CHIEF	3/2/23
<i>[Signature]</i> TRANSPORTATION DIRECTOR	03/03/2023
<i>[Signature]</i> PROJECT MANAGER	3/7/23

REVISIONS	DATE

14TH ST. N. & N. VEITCH ST.
 P31D
 14TH ST N. @ N. VEITCH ST.
 RAMP DETAILS

DESIGNED: K. PATEL
 DRAWN: K. PATEL
 CHECKED: Z. DRAGACEVAC
 PLOTTED: MARCH 8 2023






STANDARD ABBREVIATION:

- EX: EXISTING GRADE
- FG: FINISH GRADE
- TC: TOP OF CURB
- EOP: EDGE OF PAVEMENT

CR-4




APPROVALS	DATE
<i>Amy Plawin</i> QUALITY CONTROL ENGINEER	02/23/23
<i>Edward Sanders</i> CONSTRUCTION MANAGEMENT SUPERVISOR	03/03/23
<i>[Signature]</i> WATER/SEWER, STREETS BUREAU CHIEF	3/2/23
<i>[Signature]</i> TRANSPORTATION DIRECTOR	03/03/2023
<i>[Signature]</i> PROJECT MANAGER	3/7/23

REVISIONS	DATE


14TH ST. N. & N. VEITCH ST.
 P31D
 14TH ST N. @ N. VEITCH ST.
 RAMP DETAILS

DESIGNED: K. PATEL
 DRAWN: K. PATEL
 CHECKED: Z. DRAGACEVAC
 PLOTTED: MARCH 8 2023




BL EOP CR-1


PROFILE BL-EOP CR-1




PROFILE BL-EOP CR-2



PROFILE BL-EOP CR-4




PROFILE BL-EOP CR-3



DEPARTMENT OF ENVIRONMENTAL SERVICES
 FACILITIES & ENGINEERING DIVISION
 ENGINEERING BUREAU
 2100 CLARENDON BOULEVARD, SUITE 813
 ARLINGTON, VA 22201
 PHONE: 703.228.3629
 FAX: 703.228.3606

COPYRIGHT © 2021 ARLINGTON COUNTY VIRGINIA - ALL RIGHTS RESERVED




APPROVALS	DATE
<i>Amy Plawin</i> QUALITY CONTROL ENGINEER	02/23/23
<i>Edward Sanders</i> CONSTRUCTION MANAGEMENT SUPERVISOR	03/03/23
<i>[Signature]</i> WATER, SEWER, STREETS BUREAU CHIEF	3/2/23
<i>[Signature]</i> TRANSPORTATION DIRECTOR	03/03/2023
<i>[Signature]</i> PROJECT MANAGER	3/7/23

REVISIONS	DATE

14TH ST. N. & N. VEITCH ST.
 P31D
 14TH ST N. @ N. VEITCH ST.
 CURB RETURN PROFILES

DESIGNED: K. PATEL
 DRAWN: K. PATEL
 CHECKED: Z. DRAGACEVAC
 PLOTTED: MARCH 9 2023




BL-EOP CR-1



DEPARTMENT OF ENVIRONMENTAL SERVICES
FACILITIES & ENGINEERING DIVISION
ENGINEERING BUREAU
2100 CLARENDON BOULEVARD, SUITE 813
ARLINGTON, VA 22201
PHONE: 703.228.3629
FAX: 703.228.3606

COPYRIGHT © 2021 ARLINGTON COUNTY VIRGINIA - ALL RIGHTS RESERVED






SEAL



APPROVALS	DATE
<i>Amy Plawn</i> QUALITY CONTROL ENGINEER	02/23/23
<i>Edward Sanders</i> CONSTRUCTION MANAGEMENT SUPERVISOR	03/03/23
<i>[Signature]</i> WATER/SEWER, STREETS BUREAU CHIEF	3/2/23
<i>[Signature]</i> TRANSPORTATION DIRECTOR	03/03/2023
<i>[Signature]</i> PROJECT MANAGER	3/7/23


REVISIONS DATE

REVISIONS	DATE



14TH ST. N. & N. VEITCH ST.
P31D
14TH ST N. @ N. VEITCH ST.
CROSS-SECTIONS

DESIGNED: K. PATEL
DRAWN: K. PATEL
CHECKED: Z. DRAGACEVAC
PLOTTED: MARCH 9 2023



C044.1


BL-EOP CR-2



DEPARTMENT OF ENVIRONMENTAL SERVICES
FACILITIES & ENGINEERING DIVISION
ENGINEERING BUREAU
2100 CLARENDON BOULEVARD, SUITE 813
ARLINGTON, VA 22201
PHONE: 703.228.3629
FAX: 703.228.3606

COPYRIGHT © 2021 ARLINGTON COUNTY VIRGINIA - ALL RIGHTS RESERVED







SEAL



APPROVALS	DATE
<i>Amy Plawn</i> QUALITY CONTROL ENGINEER	02/23/23
<i>Edward Sanders</i> CONSTRUCTION MANAGEMENT SUPERVISOR	03/03/23
<i>[Signature]</i> WATER, SEWER, STREETS BUREAU CHIEF	3/2/23
<i>[Signature]</i> TRANSPORTATION DIRECTOR	03/03/2023
<i>[Signature]</i> PROJECT MANAGER	3/7/23

REVISIONS DATE


REVISIONS	DATE



14TH ST. N. & N. VEITCH ST.
P31D
14TH ST N. @ N. VEITCH ST.

CROSS-SECTIONS


DESIGNED: K. PATEL
DRAWN: K. PATEL
CHECKED: Z. DRAGACEVAC
PLOTTED: MARCH 9 2023



C044.2







BL-EOP CR-3

SEAL



APPROVALS	DATE
<i>Amy Plawn</i> QUALITY CONTROL ENGINEER	02/23/23
<i>Edward Sanders</i> CONSTRUCTION MANAGEMENT SUPERVISOR	03/03/23
<i>[Signature]</i> WATER, SEWER, STREETS BUREAU CHIEF	3/2/23
<i>[Signature]</i> TRANSPORTATION DIRECTOR	03/03/2023
<i>[Signature]</i> PROJECT MANAGER	3/7/23

REVISIONS DATE




14TH ST. N. & N. VEITCH ST.

14TH ST N. @ N. VEITCH ST.

CROSS-SECTIONS

DESIGNED: K. PATEL
 DRAWN: K. PATEL
 CHECKED: Z. DRAGACEVAC
 PLOTTED: MARCH 9 2023



C044.3

REVISED ON 11/19/2021


BL-EOP CR-4



DEPARTMENT OF ENVIRONMENTAL SERVICES
 FACILITIES & ENGINEERING DIVISION
 ENGINEERING BUREAU
 2100 CLARENDON BOULEVARD, SUITE 813
 ARLINGTON, VA 22201
 PHONE: 703.228.3629
 FAX: 703.228.3606

COPYRIGHT © 2021 ARLINGTON COUNTY VIRGINIA - ALL RIGHTS RESERVED

SEAL



APPROVALS DATE

Amy Plawn 02/23/23
 QUALITY CONTROL ENGINEER

Edward Sanders 03/03/23
 CONSTRUCTION MANAGEMENT SUPERVISOR

[Signature] 3/2/23
 WATER, SEWER, STREETS BUREAU CHIEF

[Signature] 03/03/2023
 TRANSPORTATION DIRECTOR

[Signature] 3/7/23
 PROJECT MANAGER

REVISIONS DATE


NO.	DESCRIPTION	DATE

14TH ST. N. & N. VEITCH ST.

14TH ST N. @ N. VEITCH ST.









CROSS-SECTIONS


DESIGNED: K. PATEL
 DRAWN: K. PATEL
 CHECKED: Z. DRAGACEVAC
 PLOTTED: MARCH 9 2023



C044.4

FILENAME: P31D_S-5-234-CROSS_SECTIONS.DWG PATH: Q:\DATA\PROJECTS\14TH ST N & N VEITCH ST\DESIGN\CAD\ACTIVE PLOTTED BY: KPATEL





SURVEY CONTROL

7	7010592.3715	11885701.6826	237.472	TRV-NAIL FND
20	7010539.4402	11885486.5265	236.905	TRV-NAIL FND
71	7010272.4787	11885753.9649	234.342	TRV-NAIL SET
72	7010077.9617	11885788.1146	230.673	TRV-NAIL SET
73	7010061.8330	11885619.1940	207.796	TRV-NAIL SET
74	7010245.3154	11885552.1984	224.688	TRV-NAIL SET
81	7010095.6911	11885976.5019	231.156	TRV-NAIL SET

BL EOP CR-1							
	Length	Radius	Line/Chord Direction	Station (Start)	Station (End)	Northing, Easting (Start)	Northing, Easting (End)
C1	25.12	16.50	S52° 05' 12.18"E	0+03.23	0+28.35	7010138.1465, 11885595.2148	7010124.1578, 11885613.1755
L1	16.67		S6° 09' 33.80"E	-0+25.00	-0+08.34	7010166.1541, 11885591.7240	7010149.5821, 11885593.5124
L2	8.34		S8° 28' 02.49"E	-0+08.34	0+00.00	7010149.5821, 11885593.5124	7010141.3367, 11885594.7399
L3	3.23		S8° 28' 02.49"E	0+00.00	0+03.23	7010141.3367, 11885594.7399	7010138.1465, 11885595.2148
L4	4.14		N84° 17' 38.13"E	0+28.35	0+32.49	7010124.1578, 11885613.1755	7010124.5695, 11885617.2962
L5	25.00		N84° 17' 38.13"E	0+32.49	0+57.49	7010124.5695, 11885617.2962	7010127.0551, 11885642.1723


BL EOP CR-2							
	Length	Radius	Line/Chord Direction	Station (Start)	Station (End)	Northing, Easting (Start)	Northing, Easting (End)
C3	8.30	13.50	N78° 56' 35.85"W	0+11.99	0+20.29	7010076.5261, 11885646.2184	7010078.0938, 11885638.1955
C4	10.15	16.50	N78° 56' 35.85"W	0+20.29	0+30.45	7010078.0938, 11885638.1955	7010080.0099, 11885628.3897
C5	25.80	16.50	S38° 38' 26.15"W	0+40.31	0+66.10	7010078.8823, 11885618.5945	7010060.7224, 11885604.0766
C6	10.15	16.50	S23° 46' 29.58"E	0+81.03	0+91.18	7010045.8866, 11885605.6756	7010036.7430, 11885609.7036
C7	8.30	13.50	S23° 46' 33.16"E	0+91.18	0+99.48	7010036.7430, 11885609.7036	7010029.2622, 11885612.9993
L9	25.00		S83° 25' 58.64"W	-0+25.00	0+00.00	7010080.7564, 11885682.9657	7010077.8973, 11885658.1297
L10	11.99		S83° 25' 58.64"W	0+00.00	0+11.99	7010077.8973, 11885658.1297	7010076.5261, 11885646.2184
L11	9.86		S83° 25' 58.64"W	0+30.45	0+40.31	7010080.0099, 11885628.3897	7010078.8823, 11885618.5945
L12	14.92		S6° 09' 06.34"E	0+66.10	0+81.03	7010060.7224, 11885604.0766	7010045.8866, 11885605.6756
L13	7.88		S6° 09' 06.34"E	0+99.48	1+07.36	7010029.2622, 11885612.9993	7010021.4298, 11885613.8435
L14	25.00		S6° 09' 06.34"E	1+07.36	1+32.36	7010021.4298, 11885613.8435	7009996.5737, 11885616.5225

BL EOP CR-3							
	Length	Radius	Line/Chord Direction	Station (Start)	Station (End)	Northing, Easting (Start)	Northing, Easting (End)
C8	8.30	13.50	N11° 16' 36.85"E	0+06.97	0+15.28	7010009.1492, 11885571.3104	7010017.1660, 11885572.9089
C9	10.15	16.50	N11° 16' 36.85"E	0+15.28	0+25.43	7010017.1660, 11885572.9089	7010026.9644, 11885574.8627
C10	54.04	26.50	N64° 45' 46.23"W	0+25.43	0+79.46	7010026.9644, 11885574.8627	7010046.2145, 11885534.0229
C11	10.15	16.50	S39° 11' 50.70"W	0+79.46	0+89.61	7010046.2145, 11885534.0229	7010038.4715, 11885527.7085
C12	8.30	13.50	S39° 11' 50.70"W	0+89.61	0+97.92	7010038.4715, 11885527.7085	7010032.1364, 11885522.5422
L15	25.01		N6° 20' 48.66"W	-0+25.00	0+00.01	7009977.3745, 11885574.8446	7010002.2328, 11885572.0797
L16	6.96		N6° 20' 48.66"W	0+00.01	0+06.97	7010002.2328, 11885572.0797	7010009.1492, 11885571.3104
L17	2.68		S56° 49' 16.21"W	0+97.92	1+00.60	7010032.1364, 11885522.5422	7010030.6672, 11885520.2952
L18	25.00		S54° 23' 56.63"W	1+00.60	1+25.60	7010030.6672, 11885520.2952	7010016.1138, 11885499.9680

BL EOP CR-4							
	Length	Radius	Line/Chord Direction	Station (Start)	Station (End)	Northing, Easting (Start)	Northing, Easting (End)
C13	25.01	272.53	N53° 13' 53.92"E	-0+25.01	0+00.00	7010080.0234, 11885509.9398	7010094.9879, 11885529.9663
C14	8.91	13.50	N77° 13' 35.11"E	0+07.88	0+16.78	7010099.3004, 11885536.5571	7010101.2339, 11885545.0856
C15	9.46	16.50	N79° 41' 58.09"E	0+16.78	0+26.24	7010101.2339, 11885545.0856	7010102.9024, 11885554.2662
C16	32.48	26.50	N28° 09' 46.51"E	0+26.24	0+58.72	7010102.9024, 11885554.2662	7010129.7774, 11885568.6541
C17	8.76	16.50	N22° 08' 58.00"W	0+58.72	0+67.48	7010129.7774, 11885568.6541	7010137.7916, 11885565.3918
C18	12.47	23.50	N22° 08' 58.00"W	0+67.48	0+79.95	7010137.7916, 11885565.3918	7010149.2056, 11885560.7456
L19	4.87		N55° 51' 37.93"E	0+00.00	0+04.87	7010094.9879, 11885529.9663	7010097.7221, 11885533.9988
L20	3.01		N58° 19' 42.28"E	0+04.87	0+07.88	7010097.7221, 11885533.9988	7010099.3004, 11885536.5571
L21	7.09		N6° 56' 55.21"W	0+79.95	0+87.04	7010149.2056, 11885560.7456	7010156.2452, 11885559.8876
L22	25.00		N6° 56' 55.21"W	0+87.04	1+12.04	7010156.2452, 11885559.8876	7010181.0616, 11885556.8631

14TH STREET							
	Length	Radius	Line/Chord Direction	Station (Start)	Station (End)	Northing, Easting (Start)	Northing, Easting (End)
C19	37.75	178.50	S51° 53' 44.59"W	5+06.87	5+44.62	7010077.2282, 11885545.3997	7010053.9766, 11885515.7504
C20	119.39	181.51	S64° 40' 47.83"W	5+44.62	6+64.01	7010053.9766, 11885515.7504	7010003.8327, 11885409.7661
L25	189.42		S83° 39' 58.28"W	2+73.67	4+63.09	7010121.3565, 1188570.7753	7010100.4595, 11885582.5115
L26	43.78		S57° 57' 15.18"W	5+06.87	5+06.87	7010100.4595, 11885582.5115	7010077.2282, 11885545.3997
L27	135.99		S83° 31' 19.00"W	6+64.01	8+00.00	7010003.8327, 11885409.7661	7009988.4900, 11885274.6447

VEITCH STREET							
	Length	Radius	Line/Chord Direction	Station (Start)	Station (End)	Northing, Easting (Start)	Northing, Easting (End)
L28	152.78		S6° 28' 01.72"E	4+62.83	6+15.61	7010252.2626, 11885565.3039	7010100.4595, 11885582.5115
L29	229.50		S6° 28' 01.72"E	6+15.61	8+45.10	7010100.4595, 11885582.5115	7009872.4245, 11885608.3604



APPROVALS	DATE
<i>Amy Plawin</i> QUALITY CONTROL ENGINEER	02/23/23
<i>Edward Sanders</i> CONSTRUCTION MANAGEMENT SUPERVISOR	03/03/23
<i>[Signature]</i> WATER, SEWER, STREETS BUREAU CHIEF	3/2/23
<i>[Signature]</i> TRANSPORTATION DIRECTOR	03/03/2023
<i>[Signature]</i> PROJECT MANAGER	3/7/23

REVISIONS

REVISIONS	DATE


14TH ST. N. & N. VEITCH ST.
P31D
14TH ST N. @ N. VEITCH ST.


GEOMETRIC CONTROL PLAN

DESIGNED: K. PATEL
DRAWN: K. PATEL
CHECKED: Z. DRAGACEVAC

PLOTTED: MARCH 9 2023

SCALE:






CONSTRUCTION SIGNAGE NOTES

- ② EXISTING SIGN TO BE REMOVED AND RESET
- ③ EXISTING SIGN TO BE REMOVED AND RELOCATE WITH NEW POST.

All existing signage to remain unless otherwise noted.



HIGH VISIBILITY CROSSWALK
NOT TO SCALE

PAVEMENT MARKING NOTES:

- STREET WIDTH MEASUREMENTS ARE FROM FACE OF CURB TO FACE OF CURB. LANES ARE MEASURED FROM CENTER OF MARKING TO CENTER OF MARKING.
- CONTACT DES-TRANSPORTATION ENGINEERING & OPERATIONS CONSTRUCTION MANAGEMENT SPECIALIST OR HIS DESIGNEE AT 703-228-6598 OR 571-437-1077 TO APPROVE MARKING LAYOUT 48 HOURS PRIOR TO INSTALLATION OF MARKINGS.
- PAVEMENT MARKINGS TO BE IN ACCORDANCE WITH THE FOLLOWING AND ANY REVISIONS HERE TO:
 - A. THE MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES.
 - B. ARLINGTON COUNTY MARKING STANDARDS.
- ALL MARKINGS SHALL BE THERMOPLASTIC PER ARLINGTON COUNTY MARKING STANDARDS.
- STOP BARS SHALL BE A MINIMUM OF 4' IN ADVANCE OF A MARKED CROSSWALK. IF THERE IS NO MARKED CROSSWALK, STOP BAR SHALL BE NO MORE THAN 30' FROM THE NEAREST EDGE OF THE INTERSECTED TRAVELED WAY.
- CROSSWALKS SHALL BE 10' WIDE UNLESS OTHERWISE NOTED.
- LEFT TURN ARROWS SHALL BE LOCATED 25' BACK FROM STOP BAR. FOR ADDITIONAL ARROWS FOLLOW COUNTY MARKING STANDARDS.
- ON-STREET PARKING LANE IS 7' WIDE (UNLESS OTHERWISE NOTED) AND MARKED WITH 4" WIDE WHITE LINES. BEGINNING AND END OF PARKING SHALL BE MARKED WITH AN END LINE PERPENDICULAR TO CURB EXCEPT AT NUBS OR WHERE OTHERWISE INDICATED.
- SHARED LANE MARKINGS SHALL BE PLACED IN CENTER OF LANE, 250' APART UNLESS OTHERWISE SPECIFIED.
- BIKE LANE SYMBOLS TO BE PLACED 330' APART UNLESS OTHERWISE SPECIFIED.
- EDGE LINES ARE ONLY REQUIRED WHERE SHOWN ON THE PLANS.
- FOR DETAILS SEE ARLINGTON COUNTY PAVEMENT MARKING SPECIFICATION, DETAILS MK-1 TO MK-12

SIGN NOTES:

- FOR ALL SIGN POSTS PLACED IN CONCRETE USE 7 GAUGE HEAVY DUTY ANCHOR (30"x2.50") WITH HARDWARE FOR 2" POST. USE 3/8" CORNER BOLT WITH FLANGED NUT AND 3/8" DRIVER RIVET WITH WASHER.
- CONTACT T&O CONSTRUCTION MANAGER OR HIS DESIGNEE AT 703-228-6598 OR 571-437-1077 48 HRS PRIOR TO POURING CONCRETE. ALTERNATIVE CONTACT AT 703-228-3788 OR 571-414-7497.

STANDARD PAVEMENT MARKING LEGEND


(A)	TYPE B CLASS 1	WHITE 4" WIDTH	PARKING LANES, EDGE LINES, LANE LINES
(B)	TYPE B CLASS 1	WHITE 4" WIDTH, 10' LONG, 30' SPACING	DASHED LANE LINES
(C)	TYPE B CLASS 1	WHITE 4" WIDTH, 2' LONG 10' SPACING	LANE TRANSITIONS, TURN LANE SKIPS
(D)	TYPE B CLASS 1	WHITE 18" WIDTH	STOP BARS
(E)	TYPE B CLASS 1	WHITE 24" WIDTH	CONTINENTAL CROSS WALKS
(F)	TYPE B CLASS 1	WHITE 6" WIDTH	TURN LANES, TRANSVERSE CROSS WALKS, BIKE LANES
(G)	TYPE B CLASS 1	YELLOW 4" WIDTH, 10' LONG, 30' SPACING	DIVIDED TRAFFIC, TWO WAY TURN LANES
(H)	TYPE B CLASS 1	YELLOW 4" WIDTH	EDGE LINES
(I)	TYPE B CLASS 1	YELLOW 4" WIDTH, DOUBLE LINE, 4" SPACING	CENTERLINES
(J)	TYPE B CLASS 1	WHITE 6" WIDTH, 10' SPACING @45 DEGREE	HATCH LINES, SAFETY ZONES
(K)	TYPE B CLASS 1	WHITE SINGLE ARROW	TURN LANES
(L)	TYPE B CLASS 1	WHITE COMBINATION ARROW	TURN LANES
(M)	TYPE B CLASS 1	WHITE 8" LETTERS	PAVEMENT LETTERS (STOP, YIELD, BUS, ONLY, etc.)
(N)	TYPE B CLASS 1	WHITE 6" WIDTH, 2' LONG, 10' SPACING	LANE TRANSITIONS, TURN LANE SKIPS
(O)	TYPE B CLASS 1	WHITE 12" WIDTH, 20' SPACING @45 DEGREE	GORE MARKINGS
(P)	TYPE B CLASS 1	YELLOW 8" WIDTH @45 DEGREE	GORE MARKINGS
(Q)	TYPE B CLASS 1	WHITE 6" WIDTH, 2' LONG, 4' SPACING	LANE TRANSITIONS
(R)	TYPE B CLASS 1	WHITE 4" WIDTH, DOUBLE LINE, 4" SPACING	CURB EXTENSIONS
(S)	TYPE B CLASS 1	WHITE 24" WIDTH	VDOT - STOP BARS
(T)	TYPE B CLASS 1	YELLOW 6" WIDTH, 2' LONG, 4' SPACING	LANE TRANSITIONS



DEPARTMENT OF ENVIRONMENTAL SERVICES
 FACILITIES & ENGINEERING DIVISION
 ENGINEERING BUREAU
 2100 CLARENDON BOULEVARD, SUITE 813
 ARLINGTON, VA 22201
 PHONE: 703.228.3629
 FAX: 703.228.3606

COPYRIGHT © 2021 ARLINGTON COUNTY VIRGINIA - ALL RIGHTS RESERVED

SEAL



APPROVALS DATE

Amy Plawn 02/23/23
 QUALITY CONTROL ENGINEER
Edward Sanders 03/03/23
 CONSTRUCTION MANAGEMENT SUPERVISOR
[Signature] 3/2/23
 WATER, SEWER, STREETS BUREAU CHIEF
[Signature] 03/03/2023
 TRANSPORTATION DIRECTOR
[Signature] 3/7/23
 PROJECT MANAGER

REVISIONS DATE


NO.	DESCRIPTION	DATE


14TH ST. N. & N. VEITCH ST.
P31D

14TH ST N. @ N. VEITCH ST.
SIGNAGE_AND_STRIPING

DESIGNED: K. PATEL
 DRAWN: K.PATEL
 CHECKED: Z. DRAGACEVAC
 PLOTTED: MARCH 9 2023

SCALE:





CONSTRUCTION NOTES

- FOR ALL ARTERIAL STREETS, PORTABLE VARIABLE MESSAGE SIGNS WITH CLOSURE INFORMATION MUST BE INSTALLED AHEAD OF THE PROJECT SITE AT EACH VEHICULAR APPROACH 3 WEEKS PRIOR TO STREET CLOSURE IN LOCATIONS DIRECTED BY THE PROJECT OFFICER.
- CONTRACTOR SHALL REMOVE EXISTING PAVEMENT MARKINGS IN CONFLICT WITH TEMPORARY PAVEMENT MARKINGS.
- CONTACT TRANSPORTATION ENGINEERING OPERATIONS AT 703-228-6598 OR 571-437-1077 AND THE PROJECT OFFICER TO APPROVE MARKING LAYOUT 48 HOURS PRIOR TO INSTALLATION OF MARKINGS.
- ONE LANE CLOSURE IN EACH DIRECTION OF TRAFFIC WILL BE PERMITTED FOR FINAL PAVEMENT OVERLAY.
- DURING CONSTRUCTION, THE CONTRACTOR SHALL MAINTAIN THE FLOW OF TRAFFIC ON ANY INTERSECTION WITHIN THE WORK AREA.
- THE CONTRACTOR SHALL NOTIFY ARLINGTON COUNTY PUBLIC SCHOOLS TWO WEEKS PRIOR TO STARTING CONSTRUCTION.
- THE CONTRACTOR SHALL SUBMIT ANY REQUESTS FOR TEMPORARY "NO PARKING" RESTRICTIONS TO THE PROJECT OFFICER AT LEAST 3 WORKING DAYS PRIOR TO THE DESIRED ONSET OF RESTRICTIONS. PRIOR TO A REQUEST FOR THE REMOVAL OF ACCESS TO ANY ADA PARKING SPACE THE CONTRACTOR MUST HAVE MADE PROVISION FOR ALTERNATIVE ADA PARKING AS INDICATED ON THE APPROVED PLAN OR AS DIRECTED BY THE PROJECT OFFICER.
- WHEN THE APPROVED PLAN CALLS FOR THE REMOVAL OF ANY PARKING METER THE CONTRACTOR MUST MAKE A REQUEST TO THE PROJECT OFFICER AT LEAST ONE WEEK IN ADVANCE OF THE DESIRED REMOVAL. THE PROJECT OFFICER WILL THEN COORDINATE THE PARKING METER REMOVAL WITH TRAFFIC ENGINEERING AND OPERATIONS.

MOT NOTES:

- PARKING SHALL BE RESTRICTED BY THE COUNTY AS PART OF THE RIGHT OF WAY PERMIT. CONTACT DES-PERMITTING SECTION, 703-228-4798, AT LEAST 72 HOURS PRIOR TO COMMENCEMENT OF WORK.
- ALL TEMPORARY BUS TRAVEL LANES MUST BE MINIMUM 11' WIDE.
- THE CONTRACTOR SHALL MAINTAIN ADA ACCESSIBLE PARKING SPACES AT ALL TIMES DURING CONSTRUCTION. THE CONTRACTOR SHALL CONTACT DES - PERMITTING, 703-228-4798, TO COORDINATE RELOCATION OF EXISTING ADA ACCESSIBLE PARKING SPACES OR TO INSTALL TEMPORARY SIGNAGE OUT OF AND ADJACENT TO THE WORK ZONE AS CONSTRUCTION PROGRESSES. MULTIPLE RELOCATIONS MAY BE NECESSARY DURING EACH PHASE.

PEDESTRIAN NOTE:

- PEDESTRIANS SHALL BE APPROPRIATELY DIRECTED WITH ADVANCED WARNING SIGNS PLACED AT INTERSECTIONS, TO CROSS TO THE OPPOSITE SIDE OF THE ROADWAY IN ORDER TO PREVENT CONFLICT WITH MIDDLEBLOCK WORK SITES.



DEPARTMENT OF ENVIRONMENTAL SERVICES
 FACILITIES & ENGINEERING DIVISION
 ENGINEERING BUREAU
 2100 CLARENDON BOULEVARD, SUITE 813
 ARLINGTON, VA 22201
 PHONE: 703.228.3629
 FAX: 703.228.3606

COPYRIGHT © 2021 ARLINGTON COUNTY VIRGINIA - ALL RIGHTS RESERVED



APPROVALS	DATE
<i>Amy Plawin</i> QUALITY CONTROL ENGINEER	02/23/23
<i>Edward Sanders</i> CONSTRUCTION MANAGEMENT SUPERVISOR	03/03/23
<i>[Signature]</i> WATER, SEWER, STREETS BUREAU CHIEF	3/2/23
<i>[Signature]</i> TRANSPORTATION DIRECTOR	03/03/2023
<i>[Signature]</i> PROJECT MANAGER	3/7/23

REVISIONS	DATE

14TH ST. N. & N. VEITCH ST.
 P31D
 14TH ST N. @ N. VEITCH ST.

MAINTENANCE OF TRAFFIC PLAN

ZONE TABLE			
ZONE#	TTC#	COMMENTS	DURATION
ZONE A	TTC-23.2 TTC-36.2 TTC-16.2	LANE CLOSURE ON A TWO-LANE ROADWAY USING FLAGGERS CROSSWALK CLOSURE AND PEDESTRIAN DETOUR OPERATIONS OUTSIDE LANE CLOSURE OPERATION ON A FOUR LANE ROADWAY	1 WEEK - 1 MONTH
ZONE B	TTC-28.2 TTC-36.2 TTC-16.2	LANE CLOSURE OPERATION IN AN INTERSECTION CROSSWALK CLOSURE AND PEDESTRIAN DETOUR OPERATIONS OUTSIDE LANE CLOSURE OPERATION ON A FOUR LANE ROADWAY	1 WEEK - 1 MONTH
ZONE C	TTC-23.2 TTC-36.2 TTC-26.2	LANE CLOSURE ON A TWO-LANE ROADWAY USING FLAGGERS CROSSWALK CLOSURE AND PEDESTRIAN DETOUR OPERATIONS LANE CLOSURE OPERATION - NEAR SIDE OF AN INTERSECTION	1 WEEK - 1 MONTH
ZONE D	TTC-23.2 TTC-36.2 TTC - 5.2	LANE CLOSURE ON A TWO-LANE ROADWAY USING FLAGGERS CROSSWALK CLOSURE AND PEDESTRIAN DETOUR OPERATIONS SHOULDER OPERATION WITH MINOR ENCROACHMENTS	1 WEEK - 1 MONTH


NOTE: THE DURATIONS SHOWN WERE DEVELOPED FOR PLANNING AND ESTIMATION PURPOSES ONLY. THE DURATIONS IN NO WAY ALTER THE CONTRACT TIME FOR COMPLETION, OR INFRINGES ON THE CONTRACTORS MEANS AND METHODS. THE CONTRACTOR'S SUBMITTED SCHEDULE SUPERSEDES THE ESTIMATED DURATIONS SHOWN.

- NOTES:**
- THE FOLLOWING ZONES CAN NOT BE BUILT AT THE SAME TIME:
 1: B, AND C
 2: A, AND B
 3: C, AND D
 4: A, AND D
 - ZONE A, B, C, AND D SHOULD BE FURNISHED WITH (R9-11) SIGN TO ADDRESS THE SIDEWALK CLOSING.
 - WARNING SIGN SPACING : 100'
 CHANNELIZATION DEVICES SPACING FOR TRANSITION AREAS = 20'
 - TEMPORARY SIGNS AND BARRICADES SHOULD NOT BE PLACED WHERE THEY WILL OBSTRUCT PEDESTRIAN PASSAGE, EXCEPT WHEN SIGN IS INTENDED TO CLOSE THE SIDEWALK SECTION.

MAINTENANCE OF TRANSPORTATION PLAN


LEGEND:

- ARROW PANEL
- ARROW PANEL ON TRAILER
- AREA UNDER CONSTRUCTION
- AREA CONSTRUCTED IN PREVIOUS PHASE
- SUB-PHASE OF AREA UNDER CONSTRUCTION
- TRAFFIC FLOW
- TRAFFIC DRUM
- 2" X 36" TUBULAR MARKERS
- ARROW PANEL ON TRAILER
- SIGN
- TYPE III BARRICADE
- FLAGGER




Commonwealth of Virginia VDOT
 Virginia Department of Transportation
 VERIFICATION OF COMPLETION OF VDOT ADVANCED WORK ZONE TRAFFIC CONTROL TRAINING AND FLAGGER CERTIFICATION
 This is to verify that Keri Patel has successfully completed training and an examination by the Department on the proper practices and methods for the installation, maintenance, removal of temporary traffic control devices and flagging operations.
 Expiration Date: 07/31/2026
 Verification Number: 070722120
 Keri Patel
 State Traffic Engineer

DESIGNED: K. PATEL
 DRAWN: K. PATEL
 CHECKED: Z. DRAGACEVAC
 PLOTTED: MARCH 9 2023




Lane Closure on a Two-Lane Roadway Using Flaggers (Figure TTC-23.2)




1: Revision 1 - 4/1/2015
2: Revision 2 - 9/1/2019

Crosswalk Closure and Pedestrian Detour Operation (Figure TTC-36.2)



1: Revision 1 - 4/1/2015
2: Revision 2 - 7/1/2018

Lane Closure Operation in an Intersection (Figure TTC-28.2)



2: Revision 2 - 9/1/2019

Typical Traffic Control Lane Closure on a Two-Lane Roadway Using Flaggers (Figure TTC-23.2)

NOTES

- Guidance: 1. Sign spacing distance should be 350'-500' where the posted speed limit is 45 mph or less...
Standard: 4. Portable Temporary Rumble Strips (PTRS) shall be used as noted in Section 6F.99.
Option: 8. A SLOW (W21-LV10) sign may be required in this area to give advance warning...
Standard: 14. When used, three portable temporary rumble (PTRS) strips shall be installed across the entire travel lane adjacent to the BE PREPARED TO STOP (W3-4) sign.

1: Revision 1 - 4/1/2015
2: Revision 2 - 9/1/2019

Typical Traffic Control Crosswalk Closure and Pedestrian Detour Operation (Figure TTC-36.2)

NOTES

- Standard: 1. When crosswalks or other pedestrian facilities are closed or relocated, temporary facilities shall be detectable and shall include accessibility features...
Guidance: 3. Audible information devices should be considered where midblock closings and changed crosswalk areas cause inadequate communication...
Standard: 11. The YIELD HERE TO PEDESTRIANS (R1-5) sign shall be placed at the Yield Line.

1: Revision 1 - 4/1/2015
2: Revision 2 - 9/1/2019

Typical Traffic Control Lane Closure Operation in an Intersection (Figure TTC-28.2)

NOTES

- Guidance: 1. The control of traffic through the intersection in order of preference should be: a. Obtain the services of law enforcement personnel.
Standard: 4. Channelizing device spacing shall be on 20' centers or less.
Guidance: 6. If room permits, a shadow vehicle with at least one rotating amber light or high intensity amber flashing or oscillating light should be parked 80'-120' in advance of the first work crew.

1: Revision 1 - 4/1/2015
2: Revision 2 - 9/1/2019



DEPARTMENT OF ENVIRONMENTAL SERVICES
FACILITIES & ENGINEERING DIVISION
ENGINEERING BUREAU
2100 CLARENDON BOULEVARD, SUITE 813
ARLINGTON, VA 22201
PHONE: 703.228.3629
FAX: 703.228.3606

COPYRIGHT © 2021 ARLINGTON COUNTY VIRGINIA - ALL RIGHTS RESERVED




Table with columns for APPROVALS and DATE, listing signatories like Amy Plawin, Edward Sanders, and Project Manager.

REVISIONS DATE

Table with columns for REVISIONS and DATE, showing revision history.

14TH ST. N. & N. VEITCH ST.
P31D
14TH ST N. @ N. VEITCH ST.

MAINTENANCE OF TRAFFIC NOTES & DETAILS

DESIGNED: K. PATEL
DRAWN: K. PATEL
CHECKED: Z. DRAGACEVAC


PLOTTED: MARCH 9 2023

SCALE:

AS SHOWN


C122.1

Shoulder Operation with Minor Encroachment (Figure TTC-5.2)




1: Revision 1 - 4/1/2015
2: Revision 2 - 9/1/2019

Outside Lane Closure Operation on a Four-Lane Roadway (Figure TTC-16.2)



2: Revision 2 - 9/1/2019

Lane Closure Operation - Near Side of an Intersection (Figure TTC-26.2)



1: Revision 1 - 4/1/2015
2: Revision 2 - 9/1/2019

Typical Traffic Control Shoulder Operation with Minor Encroachment (Figure TTC-5.2) NOTES

- Standard
1. For required sign assemblies for multi-lane roadways see Note 1, TTC-4.1
Guidance
2. Sign spacing should be 1300'-1500' for Limited Access highways.
Option:
4. The ROAD WORK AHEAD (W20-1) sign on an intersecting roadway may be omitted...
5. A shadow vehicle with either an arrow board operating in the caution mode...
6. Vehicle hazard warning signals shall not be used instead of the vehicle's high-intensity amber rotating, flashing, or oscillating lights.
7. Taper length (L) and channelizing device spacing shall be at the following:
Channelizing Device Spacing table
8. Channelizing device spacing shall be at the following:
Channelizing Device Spacing table
9. On roadways with paved shoulders having a width of 8 feet or more, channelizing devices shall be used to close the shoulder in advance of the merging taper to direct vehicular traffic to remain within the traveled way.
10. The buffer space length The buffer space length shall be as shown in Table 6H-3 on Page 6H-5 for the posted speed limit.
11. A truck-mounted attenuator (TMA) shall be used on Limited Access highways and multi-lane roadways with posted speed limit equal to or greater than 45 mph.
12. When a side road intersects the highway within the temporary traffic control zone, additional traffic control devices shall be placed as needed.

1: Revision 1 - 4/1/2015
2: Revision 2 - 9/1/2019

Typical Traffic Control Outside Lane Closure Operation on a Four-Lane Roadway (Figure TTC-16.2) NOTES

- Standard:
1. On divided highways having a median wider than 8', right and left sign assemblies shall be required.
Guidance:
2. Sign spacing should be 1300'-1500' for Limited Access highways.
3. When closing a lane, a PCMS should be used in advance of the first warning sign if all of the left side signs cannot be installed.
4. Care should be exercised when establishing the limits of the work zone to insure maximum possible sight distance in advance of the transition, based on the posted speed limit and at least equal to or greater than the values in Table 6H-3.
5. All vehicles, equipment, workers, and their activities should be restricted to one side of the pavement.
Standard:
6. Taper length (L) and channelizing device spacing shall be at the following:
Taper Length L table
7. Channelizing device spacing shall be at the following:
Channelizing Device Spacing table
8. An arrow board shall be used when a lane is closed. When more than one lane is closed, a separate arrow board shall be used for each closed lane (see Figure TTC-18).
9. The buffer space length shall be shown in Table 6H-3 on Page 6H-5 for the posted speed limit.
10. A shadow vehicle with either a Type B or C arrow board operating in the caution mode, or at least one high intensity amber rotating, flashing, or oscillating light shall be parked 80'-120' in advance of the first work crew.
11. Vehicle hazard warning signals shall not be used instead of the vehicle's high-intensity amber rotating, flashing, or oscillating lights but can be used to supplement the amber rotating, flashing, or oscillating lights.
12. When a side road intersects the highway within the TTC zone, additional TTC devices shall be placed as needed.
Option:
13. PTRS and their supporting signs may be used, see Sections 6F.99 and 6G.25. Long-term transverse rumble strips may be used in long-term situations, see Section 6F.99 and TTC-20.
14. The supplemental PTRS may be eliminated.

1: Revision 1 - 4/1/2015
2: Revision 2 - 9/1/2019

Typical Traffic Control Lane Closure Operation - Near Side of an Intersection (Figure TTC-26.2) NOTES

- Guidance:
1. Sign spacing distance should be 350'-500' where the posted speed limit is 45 mph or less, 500'-800' where the posted speed limit is greater than 45 mph.
Standard:
2. On divided highways having a median wider than 8', right and left sign assemblies shall be required.
3. Taper length (L) shall be at the following:
Taper Length L table
4. Channelizing device spacing shall be at the following:
Channelizing Device Spacing table
Guidance:
5. If room permits, a shadow vehicle with at least one rotating, oscillating, or amber strobe light should be parked 80'-120' in advance of the first work crew.
Standard:
6. If the posted speed limit is 45 mph or greater, the shadow vehicle shall have a truck-mounted attenuator.
7. For emergency situations (any non-planned operation) of 30 minutes or less duration, two rotating amber lights or two high intensity amber flashing or oscillating lights mounted on the vehicle and visible for 360° shall be required in addition to the channelizing devices shown around the vehicle. Also, vehicle hazard warning signals shall be used.
Guidance:
8. If the work space extends across a crosswalk, the crosswalk should be closed using the information and devices shown in Figure TTC-36.
Standard:
9. If the left turn lane is closed a NO LEFT TURN (Symbol) (R3-2) shall be used.
Option:
10. PTRS may be used as shown in Figure TTC-17 and in accordance with Section 6F-99.
11. The supplemental PTRS may be eliminated.

1: Revision 1 - 4/1/2015
2: Revision 2 - 9/1/2019




Table with columns: APPROVALS, DATE. Includes signatures and dates for Amy Plawin, Edward Sanders, and others.

REVISIONS DATE

Table with columns: REVISIONS, DATE. Includes revision details.

14TH ST. N. & N. VEITCH ST. P31D

14TH ST. N. @ N. VEITCH ST.

MAINTENANCE OF TRAFFIC NOTES & DETAILS

DESIGNED: K. PATEL
DRAWN: K.PATEL
CHECKED: Z. DRAGACEVAC

PLOTTED: MARCH 9 2023

SCALE:

AS SHOWN