ENGINEER DEPARTMENT OF **ENVIRONMENTAL SERVICES**


FACILITIES & ENGINEERING DIVISION ENGINEERING BUREAU 2100 CLARENDON BOULEVARD, SUITE 813 ARLINGTON, VA 22201 PHONE: 703.228.3629 FAX: 703.228.3606 WWW.ARLINGTONVA.US


OWNER DES/DTD/PLAN

CONTRACTOR TO BE DETERMINED

DIVISION OF TRANSPORTATION & DEVELOPMENT/ TRANSPORTATION PLANNING BUREAU 2100 CLARENDON BOULEVARD, SUITE 900, ARLINGTON, VA 22201 PHONE: 703.228.6570 FAX: 703.228.3606 WWW.ARLINGTONVA.US

LOCATION MAP





ARLINGTON VIRGINIA

DEPARTMENT OF

ENVIRONMENTAL SERVICES



APPROVALS

Edward Sanders

REVISIONS

GENERAL NOTES:

CLARENDON BLVD. & N CLEVELAND ST

INTERSECTION OF CLARENDON BLVD. & N

GENERAL CONSTRUCTION NOTES

PROJECT NUMBER: P31D

- ALL CONSTRUCTION WORK FOR THIS PROJECT SHALL CONFORM TO THE ARLINGTON COUNTY DEPARTMENT OF ENVIRONMENTAL SERVICES, CONSTRUCTION STANDARDS AND SPECIFICATIONS, AND WHERE APPLICABLE THE VIRGINIA DEPARTMENT OF TRANSPORTATION (VDOT) ROAD AND BRIDGE SPECIFICATIONS, AND ROAD AND BRIDGE STANDARDS. THE LATEST EDITIONS OF EACH RELEVANT MANUAL SHALL BE USED.
- ALL CONSTRUCTION AND WORK ACTIVITIES SHALL COMPLY WITH THE VIRGINIA WORK AREA PROTECTION MANUAL AND ALL OTHER RELEVANT WORK SAFETY REQUIREMENTS, LATEST EDITIONS.
- . THE CONTRACTOR SHALL IMMEDIATELY NOTIFY THE PROJECT OFFICER OF ANY DISCREPANCIES BETWEEN ACTUAL FIELD CONDITIONS AND THE APPROVED PLANS.

CONSTRUCTION DRAWINGS FOR:

CLEVELAND ST

- THE CONTRACTOR SHALL CONTACT "MISS UTILITY" AT 811 FOR MARKING THE LOCATIONS OF EXISTING UNDERGROUND UTILITIES (i.e. WATER, SEWER, GAS, TELEPHONE, ELECTRIC, AND CABLE TV) AT LEAST 72 HOURS PRIOR TO ANY EXCAVATION OR CONSTRUCTION. THE CONTRACTOR IS REQUIRED TO IDENTIFY AND PROTECT ALL OTHER UTILITY LINES FOUND IN THE WORK SITE AREA BELONGING TO OTHER OWNERS THAT ARE NOT MEMBERS OF "MISS UTILITY". PRIVATE WATER, SEWER AND GAS LATERALS WILL NOT BE MARKED BY MISS UTILITY OR THE COUNTY. THE CONTRACTOR SHALL LOCATE AND PROTECT THESE SERVICES DURING CONSTRUCTION.
- THE CONTRACTOR SHALL BE RESPONSIBLE FOR LAYING OUT THE WORK AND SHALL RETAIN A PROFESSIONAL LAND SURVEYOR LICENSED IN THE COMMONWEALTH OF VIRGINIA TO PROVIDE ALL NECESSARY CONSTRUCTION LAYOUTS AND ESTABLISH ALL CONTROL LINES, GRADES, AND ELEVATION DURING CONSTRUCTION. THE CONTRACTOR SHALL SUBMIT A COPY OF ALL CUT SHEETS FOR REVIEW, PER THE SPECIFICATIONS. THE COST OF ALL NECESSARY SURVEYING SERVICES SHALL BE CONSIDERED INCIDENTAL TO THE WORK AND, UNLESS OTHERWISE SPECIFIED, THE COST SHALL BE INCORPORATED INTO THE COSTS FOR RELEVANT ITEMS.
- THE LOCATION OF ALL EXISTING UTILITIES SHOWN ON THESE PLANS ARE FROM BEST AVAILABLE RECORDS AND SHALL BE CONSIDERED TO BE APPROXIMATE. WHEN CONSTRUCTION ACTIVITY REACHES IN PROXIMITY TO EXISTING UTILITIES, THE TRENCH(ES) SHALL BE OPENED A SUFFICIENT DISTANCE AHEAD OF THE WORK OR TEST PITS SHALL BE MADE TO VERIFY THE EXACT LOCATION AND INVERTS OF THE UTILITY TO ALLOW FOR POSSIBLE CHANGES IN THE LINE OR GRADE AS DIRECTED BY OFFICER. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ANY DAMAGE TO THE EXISTING UTILITIES AND THE RELATED STRUCTURES. ALL EXISTING UTILITY SYSTEMS SHALL BE PROTECTED TO PREVENT DAMAGE DURING THE CONTRACTOR'S OPERATIONS. ANY SYSTEM DAMAGED SHALL BE PROMPTLY REPAIRED AT NO COST TO THE OWNER.
- EXISTING MANHOLE FRAMES, COVERS, VALVE BOXES, AND OTHER APPURTENANCES SHALL BE ADJUSTED TO THE FINAL GRADE OR REPLACED, AS NECESSARY. UNLESS OTHERWISE SPECIFIED, THE COST FOR THIS SHALL BE CONSIDERED INCIDENTAL TO THE WORK, AND SHALL BE INCORPORATED INTO THE
- COSTS FOR RELEVANT ITEMS. THE CONTRACTOR SHALL PROVIDE ADA COMPLIANT ACCESS THROUGH OR AROUND THE SITE AT ALL TIMES AND SHALL ENSURE THE SAFETY OF ALL THOSE PASSING THROUGH OR ADJACENT TO THE SITE.
- ALL SIDEWALK AND CURB AND GUTTER DEMOLITION SHALL BEGIN AND END AT THE CONSTRUCTION JOINT NEAREST TO THE DEPICTED DEMOLITION EXTENTS WITH A NEAT SAWCUT LINE TO FULL DEPTH OF PAVEMENT SECTION.

STORMWATER AND ENVIRONMENTAL PROTECTION

10. THE CONTRACTOR SHALL CONFINE ALL ACTIVITIES AT THE SITE ASSOCIATED WITH CONSTRUCTION ACTIVITIES, TO INCLUDE STORAGE OF EQUIPMENT AND OR MATERIALS, ACCESS TO THE WORK, FORMWORK, ETC. TO WITHIN THE DESIGNATED LIMITS OF DISTURBANCE (LOD).

TREE PROTECTION

11. TREES SHALL BE PROTECTED PER THE REQUIREMENTS OF ARLINGTON PARKS & RECREATION

TRAFFIC CONTROL

- 12. CONTRACTOR SHALL NOTIFY THE PROJECT OFFICER AT LEAST 3 WORKING DAYS PRIOR TO DISTURBING ANY EXISTING, OR INSTALLING ANY NEW, TRAFFIC SIGNS, SIGNALS, OR OTHER TRAFFIC CONTROL
- 13. THE CONTRACTOR SHALL PREMARK THE LAYOUT OF ANY PERMANENT TRAFFIC CONTROL STRIPING. INDICATING THE PROPOSED LOCATION AND TYPE OF MARKING TO BE INSTALLED. THE PREMARKING MAY CONSIST OF TYPE D TAPE, CHALK, OR LUMBER CRAYONS, THE CONTRACTOR SHALL ALLOW 3 WORKING DAYS FOR THE INSPECTION AND APPROVAL OF THE PREMARKINGS PRIOR TO PLACING THE
- 14. THE CONTRACTOR SHALL SUBMIT ANY REQUESTS FOR TEMPORARY "NO PARKING" RESTRICTIONS TO THE PROJECT OFFICER AT LEAST 5 BUSINESS DAYS PRIOR TO THE DESIRED ONSET OF RESTRICTIONS. PRIOR TO A REQUEST FOR THE REMOVAL OF ACCESS TO ANY ADA PARKING SPACE THE CONTRACTOR MUST HAVE MADE PROVISION FOR ALTERNATIVE ADA PARKING AS INDICATED ON THE APPROVED PLAN OR AS DIRECTED BY THE PROJECT OFFICER.
- 15. WHEN THE APPROVED PLAN CALLS FOR THE REMOVAL OF ANY PARKING METER THE CONTRACTOR MUST MAKE A REQUEST TO THE PROJECT OFFICER AT LEAST ONE WEEK IN ADVANCE OF THE DESIRED REMOVAL. THE PROJECT OFFICER WILL THEN COORDINATE THE PARKING METER REMOVAL WITH TRAFFIC ENGINEERING AND OPERATIONS.
- 16. THE CONTRACTOR SHALL PRESERVE ALL BUS STOPS, INCLUDING MAINTAINING ADEQUATE ACCESSIBILITY THROUGH AND ADJACENT TO THE CONSTRUCTION FOR BUSES AND THEIR PASSENGERS THE CONTRACTOR SHALL NOT CLOSE, RELOCATE, OR OTHERWISE MODIFY A BUS STOP WITHOUT PRIOR REQUEST OF THE PROJECT OFFICER. ANY RELOCATION OR CLOSURE OF A BUS STOP SHALL REQUIRE AT LEAST FOUR WEEKS ADVANCE NOTICE FOR COORDINATION WITH THE COUNTY'S BUS STOP COORDINATOR - 703-228-3049.
- 17. WHEN CONDITIONS WARRANT DUE TO TRAFFIC VOLUMES, PATTERNS, OR SPECIAL EVENTS, THE COUNTY MAY SUSPEND OR OTHERWISE DIRECT THE CONTRACTOR'S ACTIVITIES TO PROTECT THE PUBLIC AND OR THE COUNTY'S TRANSPORTATION NETWORK.

WATER DISTRIBUTION, STORM AND SANITARY SEWER SYSTEMS

- 18. UNLESS OTHERWISE DIRECTED, CONTRACTORS ARE EXPRESSLY PROHIBITED FROM OPERATING ANY WATER VALVES OR APPURTENANCES. CONTRACTORS SHALL SUBMIT ALL REQUESTS FOR VALVE OPERATIONS TO THE PROJECT OFFICER AT LEAST 1 WEEK IN ADVANCE OF THE REQUIRED OPERATION
- 19. IN THE EVENT OF A WATER OR SEWER EMERGENCY, THE CONTRACTOR SHALL IMMEDIATELY NOTIFY THE COUNTY'S WATER CONTROL CENTER AT 703-228-6555 AND THE PROJECT OFFICER.
- 20. THE CONTRACTOR SHALL COORDINATE ALL UTILITY SHUTOFFS, DISCONNECTS, AND/OR ABANDONMEN' WITH UTILITY OWNER AND PROJECT OFFICER AT LEAST 1 WEEK IN ADVANCE OF THE REQUIRED

FIRE DEPARTMENT NOTES:

- 21. ALL EXISTING FIRE HYDRANTS AND FIRE DEPARTMENT CONNECTIONS SHALL BE MAINTAINED UNOBSTRUCTED AND ACCESSIBLE AT ALL TIMES IN ACCORDANCE WITH SECTIONS 507.5.4 AND 507.5.5 OF THE ARLINGTON COUNTY FIRE PREVENTION CODE.
- 22. ACCESS TO BUILDINGS FOR FIREFIGHTING SHALL BE MAINTAINED AT ALL TIMES. EXISTING FIRE APPARATUS ACCESS ROADS (FIRE LANES) SHALL BE KEPT CLEAR OF OBSTRUCTIONS IN ACCORDANCE WITH SECTION 503.4 OF THE ARLINGTON COUNTY FIRE PREVENTION CODE. ACCESS TO CONSTRUCTION SITES SHALL BE PROVIDED AND MAINTAINED IN ACCORDANCE WITH THE ARLINGTON COUNTY FIRE PREVENTION CODE.
- 23. IN THE EVENT THAT EXISTING FIRE DEPARTMENT CONNECTIONS OR FIRE APPARATUS ACCESS ROADS (FIRE LANES) MUST BE OBSTRUCTED TO FACILITATE CONSTRUCTION ACTIVITIES, CONTACT THE ARLINGTON COUNTY FIRE DEPARTMENT FIRE PREVENTION OFFICE AT 703-228-4644 TO COORDINATE REVIEW AND APPROVAL OF TEMPORARY FIRE DEPARTMENT CONNECTIONS AND/OR FIRE APPARATUS ACCESS ROADS PRIOR TO CREATING THE OBSTRUCTION.

Table of Contents

SHEET NUMBER C000.1 COVER C000.2 VDOT COVER **DETAILS** C002.1 C004.1 TYPICAL SECTIONS C006.1 LEGEND C011.1 EXISTING_CONDITIONS DEMOLITION_PLAN C031.1 EROSION_AND_SEDIMENT CONTROL PLAN EROSION_AND_SEDIMENT_CONTROL NOTES AND DETAILS EROSION_AND_SEDIMENT_CONTROL NOTES AND DETAILS C032.2 C032.3 EROSION_AND_SEDIMENT_CONTROL NOTES AND DETAILS EROSION_AND_SEDIMENT_CONTROL NOTES AND DETAILS C032.4 STORMWATER POLLUTION PREVENTION PLAN STORMWATER POLLUTION PREVENTION PLAN C041.1 PLAN AND PROFILE C042.2 RAMP DETAILS C042.3 RAMP DETAILS RAMP DETAILS C042.4 C043.1 **CURB RETURN PROFILES** C044.2 CROSS-SECTIONS C044.3 **CROSS-SECTIONS** C044.4 CROSS-SECTIONS C045.1 GEOMETRIC CONTROL PLAN C101.1 SIGNAGE_AND_STRIPING C121.1 MAINTENANCE OF TRAFFIC PLAN

MAINTENANCE OF TRAFFIC NOTES & DETAILS

MAINTENANCE OF TRAFFIC NOTES & DETAILS

C122.1

C122.2

VDOT PROJECT # EN18-000-880

UPC # 113868

LOCALITY PROJECT # P31D

SWM # 22-0205

14,800 VPD - CLARENDON BLVD (FROM N. HIGHLAND ST TO N. COURTHOUSE RD.) - 2016 - TE & O N/A - N. CLEVELAND ST. (FROM WILSON BLVD TO 12TH ST N.)

STREET CLASSIFICATION

CLARENDON BLVD. - MAJOR ARTERIAL N. CLEVELAND ST. - MINOR ARTERIAL

MAINTAINING AGENCY: ARLINGTON COUNTY

POSTED SPEED

CLARENDON BLVD. - 25 MPH N. CLEVELAND ST. - 25 MPH

2011 AASHTO CITY BUS

(V)

DESIGNED: K.PATEL DRAWN: K. PATEL CHECKED: Z. DRAGACEVAC

PLOTTED: MARCH 6 2023

SCALE:

AS NOTED

C000.

C122.2

C200.1

C200.2

ARLINGTON

VIRGINIA

ARLINGTON COUNTY BOARD APPROVAL DATE: N/A

ARLINGTON COUNTY PROGRAM OWNER: Transportation Planning Bureau

Sheet List Table SHEET TITLE NUMBER C000.2 VDOT COVER C002.1 C006.1 C011.1 EXISTING_CONDITIONS DEMOLITION_PLAN C021.1 C031.1 EROSION_AND_SEDIMENT CONTROL PLAN EROSION AND SEDIMENT CONTROL NOTES AND DETAILS C032.1 C032.2 EROSION_AND_SEDIMENT_CONTROL NOTES AND DETAILS EROSION_AND_SEDIMENT_CONTROL NOTES AND DETAILS C032.3 C032.4 EROSION_AND_SEDIMENT_CONTROL NOTES AND DETAILS C035.1 STORMWATER POLLUTION PREVENTION PLAN C035.2 STORMWATER POLLUTION PREVENTION PLAN C041.1 PLAN AND PROFILE C042.2 RAMP DETAILS RAMP DETAILS RAMP DETAILS **CURB RETURN PROFILES** CROSS-SECTIONS C044.3 CROSS-SECTIONS C044.4 CROSS-SECTIONS GEOMETRIC CONTROL PLAN C045.1 SIGNAGE_AND_STRIPING C101.1 MAINTENANCE OF TRAFFIC PLAN C121.1 MAINTENANCE OF TRAFFIC NOTES & DETAILS C122.1

MAINTENANCE OF TRAFFIC NOTES & DETAILS

TURNING MOVEMENT EXHIBIT-RT

TURNING MOVEMENT EXHIBIT-LT

CONSTRUCTION DRAWINGS FOR: CLARENDON BLVD. & N CLEVELAND ST INTERSECTION OF CLARENDON BLVD. & N **CLEVELAND ST**

> PROJECT NUMBER: P31D **UPC NUMBER: 113868**

LOCATION MAP



THE COMPLETE ELECTRONIC PDF VERSION OF THE PLAN ASSEMBLY AS AWARDED, INCLUDING ALL SUBSEQUENT REVISIONS, WILL BE THE OFFICIAL CONSTRUCTION PLANS. FOR INFORMATION RELATIVE TO ELECTRONIC FILES AND LAYERED PLANS, SEE GENERAL NOTES.

DESIGN FEATURES RELATING TO CONSTRUCTION OR TO REGULATION AND CONTROL OF TRAFFIC MAY BE SUBJECT TO CHANGE AS DEEMED NECESSARY BY THE DEPARTMENT.

THIS PROJECT IS TO BE CONSTRUCTED IN ACCORDANCE WITH THE DEPARTMENT'S 2020 ROAD AND BRIDGE SPECIFICATIONS, 2016 ROAD AND BRIDGE STANDARDS, 2009 MUTCD, 2011 VIRGINIA SUPPLEMENT TO THE MUTCD, 2011 VIRGINIA WORK AREA PROTECTION MANUAL REV 2 (2019), ARLINGTON COUNTY STANDARDS AND SPECIFICATIONS, AND AS AMENDED BY CONTRACT PROVISIONS AND THE COMPLETE ELECTRONIC PDF VERSION OF THE PLAN ASSEMBLY.

THE ORIGINAL APPROVED TITLE SHEET(S), INCLUDING ORIGINAL SIGNATURES, IS FILED IN THE VDOT CENTRAL OFFICE PLAN LIBRARY. ANY MISUSE OF ELECTRONIC FILES, INCLUDING SCANNED SIGNATURES, IS ILLEGAL AND ENFORCED TO THE FULL EXTENT OF ALL CONSTRUCTION IS TO BE PERFORMED WITHIN THE EXISTING RIGHT OF THE WAY.

POPULATION: ARLINGTON COUNTY 207,627 (2010 CENSUS)


STATE PROJECT NO.	SECTION	FEDERAL AID PROJECT NO.	TYPE CODE	UPC NO.	LENGTH INCLUDING BRIDGE(S)			LENGTH EXCLUDING BRIDGE(S)		TYPE	DESCRIPTION
PROJECT NO.		PROJECT NO.	CODE	NO.	FEET	MILES	FEET	MILES	NO.	O. PROJECT	
EN18-000-880	P101	FHWA-5B01(074)	PENG	113868	450	0.085	450	0.085		PRELIMINARY ENGINEERING	INTERSECTION IMPROVEMENTS
NOTE: PROJECT	T LENGTH B	ased on roadway cei	NTERLIN	E							

FHWA 534 DATA: 43128

STATE	FEDERAL AID		STATE	SHEET
SIAIL	PROJECT	ROUTE	PROJECT	NO.
VA	FHWA-5B01 (074)	N/A	EN18-000-880	1

FUNCTIONAL CLASSIFICATION AND TRAFFIC DATA						
FUNCTIONAL CLASSIFICATION AND TRAFFIC DATA						
ROADWAY	MAJOR ARTERIAL	MINOR ARTERIALS				
NOADWAT	CLARENDON BLVD.	N CLEVELAND STREET				
POSTED V (MPH)	25 MPH	25MPH				
ADT (2016)	14,800	N/A				

MAINTAINING AGENCY: ARLINGTON COUNTY



ARLINGTON

VIRGINIA

DEPARTMENT OF

ENVIRONMENTAL SERVICES

FACILITIES & ENGINEERING DIVISION

ENGINEERING BUREAU 2100 CLARENDON BOULEVARD, SUITE 813 ARLINGTON, VA 22201 PHONE: 703.228.3629 FAX: 703.228.3606 COPYRIGHT © 2021 ARLINGTON COUNT VIRGINIA - ALL RIGHTS RESERVED

APPROVALS

dward Sanders 2/15/202 CONSTRUCTION MANAGEMENT SUPERVISO WATER, SEWER, STREETS BUREAU CHIEF

DATE

REVISIONS

TIER 1 PROJECT

LOCALLY ADMINISTRATED PROJECTS RB CORRIDOR IMPROVEMENTS (P31D) NAME OF RESPONSIBLE LOCAL OFFICIAL (TYPE) RECOMMENDED FOR APPROVAL FOR RIGHT OF WAY ACQUISITION _____ DATE DISTRICT PLANNING AND INVESTMENT MANAGER NAME OF RESPONSIBLE LOCAL GOVERNMENT OFFICIAL (TYPE) RECOMMENDED FOR APPROVAL FOR CONSTRUCTION _____ TITLE OF POSITION

Z ARENDON

Ŋ

 \triangle z

ALL CONSTRUCTION IS TO BE PERFORMED WITHIN THE

CHECKED: Z. DRAGACEVAC PLOTTED: MARCH 6 2023

DESIGNED: K.PATEL


DRAWN: K. PATEL


SCALE:


AS NOTED


SWM #XX-XXXX


EXISTING RIGHT OF WAY














AS SHOWN

DESIGNED: K.PATEL

DRAWN: K. PATEL


PLOTTED: MARCH 6 2023

SCALE:

CHECKED: Z. DRAGACEVAC

C002.1

TYPICAL SECTION CONC. SIDEWALK 4'~6.25' PROPOSED 4" CLASS A3 ─ CONCRETE SIDEWALK PROPOSED 3" AGGREGATE BASE ___ MATERIAL TYPE I, SIZE 21A STANDARD CURB & GUTTER (C-2, R-2.0)




ARLINGTON VIRGINIA

DEPARTMENT OF **ENVIRONMENTAL SERVICES** FACILITIES & ENGINEERING DIVISION ENGINEERING BUREAU

2100 CLARENDON BOULEVARD, SUITE 813 ARLINGTON, VA 22201 PHONE: 703.228.3629 FAX: 703.228.3606

COPYRIGHT © 2021 ARLINGTON COUNTY VIRGINIA - ALL RIGHTS RESERVED



APPROVALS

Amy Pflaum QUALITY CONPROL ENGINEER Cdward Sanders 2/15/2023

CONSTRUCTION MANAGEMENT SUPERVISOR WATER, SEWER, STREETS BUREAU CHIEF

Hun

REVISIONS

N CLEVELAND S. RENDON BLVD. & N VD ST CLARENDON BLVD, & N P31D INTERSECTION OF CLARE CLEVELAND

TYPICAL SECTIONS

DESIGNED: K.PATEL DRAWN: K. PATEL CHECKED: Z. DRAGACEVAC

PLOTTED: MARCH 6 2023

SCALE:

AS SHOWN

C004.1

LINETYPE LEGEND

PROPOSED

EXISTING

FEATURE

SYMBOL LEGEND

EXISTING FEATURE

PROPOSED FEATURE

SYMBOL	LEGENI

	PROPOSED FEATURE	
(A)	PROP STRIPING	A
=	PROP BUS STOP	F
LABEL	LEGEND	
	PROPOSED	
(XXXX)	PROPOSED SANITARY SEWER STRUCTURE NUMBER	XXXX
$\overline{x}\overline{x}\overline{x}$	PROPOSED STORM SEWER STRUCTURE NUMBER	$\langle XXXX \rangle$
	LABEL	PROP STRIPING PROP BUS STOP LABEL LEGEND PROPOSED PROPOSED SANITARY SEWER STRUCTURE NUMBER PROPOSED STORM SEWER

HATCH LEGEND

PROP MILL & OVERLAY SEE TYPICAL SECTION FOR DETAILS		
PROP FULL DEPTH ASPHALT SEE TYPICAL SECTION FOR DETAILS		
PROP CONCRETE		
REPLACE & MATCH EXISTING DRIVEWAY OR LEADWALK. SEE CONSTRUCTION NOT	ES	
DEMOLITION AREA		



DEPARTMENT OF

VIRGINIA - ALL RIGHTS RESERVED

ENVIRONMENTAL SERVICES

FACILITIES & ENGINEERING DIVISION
ENGINEERING BUREAU
2100 CLARENDON BOULEVARD, SUITE 813
ARLINGTON, VA 22201
PHONE: 703.228.3629
FAX: 703.228.3606

COPYRIGHT © 2021 ARLINGTON COUNTY

ZORAN DRAGACEVAC

No. 031869

No. 031869

APPROVALS

Amy Pflaum
QUALITY CONTROL ENGINEER

Construction Management Supervisor

2/2/23

WATER, SEWER, STREETS BUREAU CHIEF

TRANSPORTATION DIRECTOR

2/27/2023

DATE

REVISIONS

BLVD, & N CLEVELAND ST P31D ION OF CLARENDON BLVD. & N CLEVELAND ST

CLARENDON BLVD, & P31D INTERSECTION OF CLAR CLEVELAN


DESIGNED: K.PATEL
DRAWN: K. PATEL
CHECKED: Z. DRAGACEVAC

PLOTTED: MARCH 6 2023

SCALE:

N/A

C006.1



PROJECT CONTROL DATA

Point No.	Northing(Y)	Easting(X)	Elev(Z)	Description
600	7009855.8773	11884103.4349	230.67	PIPE & CAP
601	7010003.4716	11884394.2996	235.17	P.K. NAIL
602	7010219.9158	11884301.6827	237.92	P.K. NAIL
603	7010067.7500	11884019.5121	236.26	P.K. NAIL
604	7009975.6954	11883707.2003	242.36	P.K. NAIL

GENERAL SURVEY NOTES:

- 1. THIS TOPOGRAPHIC SURVEY WAS COMPLETED UNDER THE DIRECT AND RESPONSIBLE CHARGE OF THE COUNTY SURVEY SECTION FROM AN ACTUAL GROUND SURVEY; THE IMAGE AND/OR ORIGINAL DATA WAS OBTAINED FROM 05/2016 TO 06/2016; AND THIS PLAT, MAP OR DIGITAL GEOSPATIAL DATA INCLUDING METADATA MEETS MINIMUM ACCURACY STANDARDS UNLESS OTHERWISE NOTED.
- 2. HORIZONTAL DATUM: VIRGINIA COORDINATE SYSTEM 1983.
- 3. VERTICAL DATUM: NORTH AMERICA VERTICAL DATUM 1988.
- 4. CONTOUR INTERVAL: 1'
- 5. BOUNDARY INFORMATION SHOWN HEREON WAS COMPILED FROM EXISTING LAND RECORDS AND DOES NOT REPRESENT A FIELD RUN BOUNDARY SURVEY.

ARLINGTON VIRGINIA

DEPARTMENT OF **ENVIRONMENTAL SERVICES FACILITIES & ENGINEERING DIVISION** ENGINEERING BUREAU 2100 CLARENDON BOULEVARD, SUITE 813 ARLINGTON, VA 22201 PHONE: 703.228.3629 FAX: 703.228.3606

COPYRIGHT © 2021 ARLINGTON COUNTY VIRGINIA - ALL RIGHTS RESERVED



APPROVALS

Amy Pflaum QUALITY CONTROL ENGINEER Edward Sanders 2/15/2023 CONSTRUCTION MANAGEMENT SUPERVISO

WATER, SEWER, STREETS BUREAU CHIEF


REVISIONS

Ŋ □ Z


DESIGNED: K.PATEL

DRAWN: K. PATEL CHECKED: Z. DRAGACEVAC PLOTTED: MARCH 6 2023

SCALE:



C011.1



Demolition note:

Where existing pavement is to be removed within the Critical Root Zone of a tree, leave pavement in place as long as possible during construction. Remove pavement with the rollback technique, keep equipment on paving, and limit overdig. Do not cut roots beigger than 1" without approval. Once pavement has been removed, vehicular traffic is strictly prohibited until paving is replaced. Replaced paving should be a bridged, tree-friendly detail or flexible pavers set on stonedust (not CR6) with no compaction beyond 85%, hand compact. Coordinate with the Urban Forester when process or construction details can't follow this specification.

ARLINGTON VIRGINIA

DEPARTMENT OF
ENVIRONMENTAL SERVICES
FACILITIES & ENGINEERING DIVISION
ENGINEERING BUREAU
2100 CLARENDON BOULEVARD, SUITE 813
ARLINGTON, VA 22201
PHONE: 703.228.3629

COPYRIGHT © 2021 ARLINGTON COUNTY VIRGINIA - ALL RIGHTS RESERVED

FAX: 703.228.3606

ZORAN DRAGACEVAC No. 031869

APPROVALS

Amy Pflaum 02/08/23
QUALITY CONTROL ENGINEER

Cdward Sanders 2/15/2023

DATE

WATER, SEWER, STREETS BUREAU CHIEF

CONSTRUCŢION MANAGEMENT SUPERVISOR

NSPORTATION DIRECTOR

2/27/2023
DIECT MANAGER

REVISIONS

ST

DON BLVD, & N CLEVELAND (P31D) SECTION OF CLARENDON BLVD. & N CLEVELAND ST

DESIGNED: K.PATEL
DRAWN: K. PATEL


CHECKED: Z. DRAGACEVAC


PLOTTED: MARCH 6 2023


SCALE:

GRAPHIC SCALE

C021.1







THIS SHEET IS FOR EROSION AND SEDIMENTATION CONTROL USE ONLY

EROSION & SEDIMENTATION CONTROL NOTES

i. Contractor to contact the Arlington Forester to schedule a pre-construction inspection of tree protection measures before any work near the critical root zones of trees. To schedule the pre-construction meeting call 703-228-7980.

ii. Contractor to protect trees per the plan according to the Arlington County DPR Design Standard Detail 02231.1

iii. Contractor to root prune trees per the plan according to the Arlington County DPR Design Standard Detail 02231.5, where called out on the plan.

iv. Contractor to call the urban forester at 703-228-1863, 72 hours before planting, to schedule inspection of the trees to be planted. Warranty for 1 year after planting shall be the contractor's responsibility. The urban forester and DPR is responsible for inspection.

v. Contractor to prepare tree planting strips for the replacement trees according to Arlington County DPR Design Standard Detail 329300.4a and 329300.4b.

vi. Contractor to prepare street tree planting pits according to the Arlington County DPR Design Standard Detail 329300.3a, 329300.3b, and 329300.11c

vii. Contractor to plant the trees according to Arlington County DPR Design Standard Detail 329300.1 (on flat land) or 329300.2 (on slopes)

EROSION AND SEDIMENT CONTROL LEGEND

3.05 TEMPORARY SILT FENCE SF — X—— X—

3.07 STORM DRAIN INLET PROTECTION IP

3.38 TREE PROTECTION TP — TP —

3.33 SODDING SO

CRITICAL ROOT ZONE

— CRZ —

ARLINGTON VIRGINIA

DEPARTMENT OF

ENVIRONMENTAL SERVICES

FACILITIES & ENGINEERING DIVISION
ENGINEERING BUREAU

2100 CLARENDON BOULEVARD, SUITE 813
ARLINGTON, VA 22201
PHONE: 703.228.3629
FAX: 703.228.3606

COPYRIGHT © 2021 ARLINGTON COUNTY VIRGINIA - ALL RIGHTS RESERVED



APPROVALS

Amy Pflaum 02/08/23
QUALITY CONTROL ENGINEER

Calvard Sanders 2/15/2023
CONSTRUCTION MANAGEMENT SUPERVISOR

DATE

WATER, SEWER, STREETS BUREAU CHIEF

TRANSPORTATION DIRECTOR

2/2/23

02/21/202

REVISIONS

PLAN

ARENDON BLVD, & N CLEVELAND ST
P31D
INTERSECTION OF CLARENDON BLVD. & N
CLEVELAND ST

CONTROL

SEDIMENT


AND

EROSION

DESIGNED: K.PATEL
DRAWN: K. PATEL
CHECKED: Z. DRAGACEVAC

PLOTTED: MARCH 6 2023

SCALE:



EROSION AND SEDIMENT CONTROL NARRATIVE

PROJECT DESCRIPTION:

RECONSTRUCT CURBS AND SIDEWALKS TO INSTALL ADA COMPLIANT CURB RAMPS AND SIDEWALK AREAS. WORK CAN INCLUDE CONSTRUCTION OF CURB EXTENSIONS (NUBS), RELOCATION OF EXISTING FEATURES SUCH AS FIRE HYDRANTS, SIGN POLES AND DRAINAGE INLETS. THIS PROJECT IS UNDER ROCKY RUN WATERSHED AREA. THE TOTAL DISTURBED ARE IS 3,189 S.F. (0.0732 ACRES) AND THE TOTAL PROJECT AREA IS 18,722 SF (0.4298 ACRES).

EXISTING SITE CONDITIONS:

THE TOPOGRAPHY OF THE PROJECT HAVE SLOPE RANGING FROM 1% TO 10%. THERE ARE EXISTING DRAINAGE STRUCTURES SERVING THESE SITES IN THE FORM OF CURB INLETS. THE CURRENT LAND COVER IS MAINLY IMPERVIOUS.

ADJACENT PROPERTIES:

PRIVATE PROPERTIES ARE LOCATED ALONG THE ROADWAY

OFF-SITE AREAS:

THE EXTENT OF OFFSITE CONSTRUCTION IS LIMITED

CRITICAL AREAS:

THERE ARE NO STEEP SLOPES OR CRITICAL AREAS LOCATED WITHIN THE LIMITS OF DISTURBANCE.

EROSION AND SEDIMENT CONTROL MEASURES:

THE EROSION AND SEDIMENT CONTROL MEASURES FOR THIS PROJECT AREA INCLUDE SAFETY FENCE AND INLET PROTECTION. INLET PROTECTION IS REQUIRED OUTSIDE THE PROJECT LIMITS WHEN/WHERE WATER FROM DISTURBED AREA FLOWS. (REVISE AS NEEDED)

PERMANENT STABILIZATION:

ALL AREAS DISTURBED BY CONSTRUCTION SHALL BE STABILIZED WITH GRASS, MULCH OR SOD. SEE THE PROPOSED PLANS FOR ADDITIONAL

STORMWATER RUNOFF CONSIDERATIONS:

NO ADDITIONAL IMPERVIOUS AREA WILL BE ADDED TO THIS PROJECT TOTAL LAND DISTURBANCE..... 3189 SF (0.0732 ACRES) PRE-IMPROVEMENT IMPERVIOUS AREA...... 2950 SF (0.0677 ACRES) POST-IMPROVEMENT IMPERVIOUS AREA..... = 2939 SF (0.0675 ACRES) DECREASE IMPERVIOUS AREA..... 11 SF (0.0003 ACRES)

SOILS INFORMATION:

THE FOLLOWING SOILS ARE FOUND ON SITE (SEE SOILS MAP ON SHEET CO31.1 FOR LOCATION)

SOIL#: SOIL NAME: HYDROLOGIC GROUP: ERODABILITY: URBAN LAND-UDORTHENTS VARIES

FLOODPLAIN AND RESOURCE PROTECTION AREA (RPA):

THERE ARE NO FLOODPLAIN OR RESOURCE PROTECTION AREAS LOCATED WITHIN THIS PROJECT SITE

EROSION & SEDIMENT CONTROL PROJECT PHASING

1. PHASE I:

- a. PRE-CONSTRUCTION MEETING WITH THE PROJECT OFFICER, CONTRACTOR, AND COUNTY INSPECTOR.
- b. INSTALL THE TEMPORARY CONSTRUCTION ENTRANCE (IF NEEDED) IN THE LOCATION SHOWN ON THE E&S PHASE I PLAN. MUD AND DEBRIS SHALL BE WASHED FROM ALL TRUCKS EXISTING THE SITE.
- c. INSTALL PERIMETER TREE DEMARCATION FENCING IN THE FORM OF TREE PROTECTION FENCE (TP) AS SHOWN ON E&S PHASE I PLAN.
- d. PERFORM INITIAL PERIMETER CLEARING TO INSTALL REMAINDER OF PERIMETER CONTROLS SUCH AS DIVERSION DIKE (DD), SILT FENCE (SF), AND SUPER SILT FENCE (SSF) AS PER THE PHASE I PLAN.
- e. INSTALL INLET PROTECTION ON EXISTING STORM DRAIN INLETS BEFORE CLEANING AND CONSTRUCTION.
- f. CONTACT ARLINGTON COUNTY PROJECT OFFICER FOR A PERIMETER INSPECTION PRIOR TO CLEARING THE REMAINDER OF THE SITE IN ORDER TO OBTAIN PHASE II GRADING PERMIT.
- g. CLEAR THE SITE TO THE LIMITS AS SHOWN ON THE CONSTRUCTION PLANS.

2. PHASE II:

- a. NO UTILITY CONSTRUCTION WITH THIS PROJECT, ADJUST ALL UNDERGROUND UTILITIES AND BEGIN SITE GRADING.
- b. INLET PROTECTION (IP) SHALL BE PROVIDED AT STORM DRAIN INLETS AS THEY ARE CONSTRUCTED.
- c. ONCE THE SITE IS BROUGHT TO NEAR FINAL GRADE, AND THE UTILITY CONSTRUCTION IS COMPLETE, COMMENCE CONSTRUCTION OF CURB & GUTTER, STREET, SIDEWALKS, AND OTHER IMPROVEMENTS
- d. THE CONTROL MEASURES MAY NOT BE REMOVED UNTIL ALL OF THE DISTURBED AREAS HAVE BEEN STABILIZED AND ONLY AS APPROVED AND DIRECTED BY THE INSPECTOR.

RUNOFF SHALL BE TREATED WITH SILT FENCE AND INLET PROTECTION PRIOR TO ENTERING MAJOR STORM SEWER SYSTEMS.

EROSION AND SEDIMENT CONTROL MEASURES

UNLESS OTHERWISE INDICATED, ALL VEGETATIVE AND STRUCTURAL EROSION AND SEDIMENT CONTROL PRACTICES SHALL BE CONSTRUCTED AND MAINTAINED ACCORDING TO MINIMUM STANDARDS AND SPECIFICATIONS OF THE VIRGINIA EROSION AND SEDIMENT CONTROL HANDBOOK AND THE ARLINGTON COUNTY EROSION AND SEDIMENT CONTROL ORDINANCE. THE MINIMUM STANDARDS OF THE VIRGINIA EROSION AND SEDIMENT CONTROL HANDBOOK SHALL BE ADHERED TO UNLESS OTHERWISE WAIVED OR APPROVED BY A VARIANCE.

1. STRUCTURAL PRACTICES

- a. TEMPORARY CONSTRUCTION ENTRANCE VESCH 3.02
- a.a. A TEMPORARY CONSTRUCTION ENTRANCE WITH A WASH RACK SHALL BE INSTALLED AT THE EXISTING ACCESS POINT TO THE SITE. DURING MUDDY CONDITIONS, DRIVERS OF CONSTRUCTION VEHICLES WILL BE REQUIRED TO WASH THEIR WHEELS BEFORE RE-ENTERING THE LOCAL ROADWAYS.
- a.b. THE ENTRANCE SHALL BE MAINTAINED IN A CONDITION WHICH WILL PREVENT TRACKING OR FLOW OF MUD ONTO PUBLIC RIGHTS-OF-WAY. THIS MAY REQUIRE PERIODIC WASHING OF THE MATS AND/OR REPLACEMENT OF WOOD CHIPS AS NECESSARY.
- a.c. ALL MATERIALS SPILLED, DROPPED, WASHED, OR TRACKED FROM VEHICLES ONTO ROADWAYS OR INTO STORM DRAINS MUST BE REMOVED
- a.d. THE USE OF WATER TRUCKS TO REMOVE MATERIALS DROPPED, WASHED, OR TRACKED INTO ROADWAYS WILL NOT BE PERMITTED UNDER
- ANY CIRCUMSTANCES. b. SILT FENCE - VESCH 3.05
- b.a. SILT FENCE WILL BE INSTALLED WITH THE E&S PLAN TO FILTER RUNOFF FROM DISTURBED AREAS. RUNOFF SHALL NOT BE DIRECTED PARALLEL TO THE INSTALLATION OF SILT FENCE.
- b.b. SILT FENCES SHALL BE INSPECTED IMMEDIATELY AFTER EACH RAINFALL AND AT LEAST DAILY DURING PROLONGED RAINFALL. ANY REQUIRED REPAIRS SHALL BE MADE IMMEDIATELY.
- b.c. CLOSE ATTENTION SHALL BE PAID TO THE REPAIR OF DAMAGED SILT FENCE RESULTING FROM UNDERCUTTING.
- b.d. SHOULD THE FABRIC ON A SILT FENCE DECOMPOSE OR BECOME INEFFECTIVE PRIOR TO THE END OF THE EXPECTED USABLE LIFE, THE FABRIC SHALL BE REPLACED IMMEDIATELY.
- b.e. SEDIMENT DEPOSITS SHALL BE REMOVED AFTER EACH STORM EVENT. THEY MUST BE REMOVED WHEN DEPOSITS REACH APPROXIMATELY ONE-HALF THE HEIGHT OF THE BARRIER.
- b.f. ANY SEDIMENT DEPOSITS REMAINING IN PLACE AFTER THE SILT FENCE IS NO LONGER REQUIRED SHALL BE DRESSED TO CONFORM WITH THE EXISTING GRADE, THEN PREPARED AND SEEDED.
- c. TEMPORARY DIVERSION DIKE VESCH 3.09
- c.a. A SYSTEM OF TEMPORARY DIKES, TO DIRECT FLOW INTO PROPOSED & EXISTING STORM SEWER STRUCTURES WILL BE INSTALLED AS INDICATED IN EROSION & SEDIMENT CONTROL PLAN.
- c.b. THE STRUCTURES SHALL BE INSPECTED AFTER EACH RAIN EVENT AND REPAIRS SHALL BE MADE AS NECESSARY.
- d. STORM DRAIN INLET PROTECTION VESCH 3.07
- d.a. ALL EXISTING & PROPOSED STORM SEWER INLETS IN AND AROUND THE PROJECT LIMITS SHALL BE PROTECTED DURING CONSTRUCTION. SEDIMENT-LADEN WATER SHALL BE FILTERED BEFORE ENTERING THE STORM SEWER INLETS.
- d.b. THE STRUCTURE SHALL BE INSPECTED AFTER EACH RAIN EVENT AND REPAIRS SHALL BE MADE AS NECESSARY.
- d.c. Structures shall be removed and the area stabilized when the remaining drainage area has been properly stabilized. e. DEWATERING STRUCTURE - VESCH 3.26
- e.a. SEDIMENT LADEN OR TURBID WATER SHALL BE FILTERED, SETTLED OR SIMILARLY TREATED PRIOR TO DISCHARGE.
- e.b. THE FILTERING DEVICES MUST BE INSPECTED FREQUENTLY AND REPAIRED OR REPLACED ONCE THE SEDIMENT BUILD-UP PREVENTS THE STRUCTURE FROM FUNCTIONING AS DESIGNED.
- e.c. THE ACCUMULATED SEDIMENT WHICH IS REMOVED FROM A DEWATERING DEVICE MUST BE SPREAD ON-SITE AND STABILIZED OR DISPOSED OF AT AN APPROVED DISPOSAL SITE AS PER THE APPROVED PLAN.

- f. TREE PROTECTION VESCH 3.38
- f.a. ALL TREES ARE TO BE PROTECTED UNLESS OTHERWISE DIRECTED BY THE COUNTY INSPECTOR AND URBAN FORESTER. THE COUNTY'S URBAN FORESTER (703-228-1863) SHALL INSPECT ALL TREE PROTECTION 72 HOURS PRIOR TO THE START OF CONSTRUCTION. IN SPITE OF PRECAUTIONS, SOME DAMAGE TO PROTECTED TREES MAY OCCUR. IN SUCH CASES, THE FOLLOWING MAINTENANCE GUIDELINES SHALL BE
- f.a.a. SOIL AERATION: IF THE SOIL HAS BECOME COMPACTED OVER THE ROOT ZONE OF ANY TREE, THE GROUND SHALL BE AERATED WITH INSTRUCTIONS FROM URBAN FORESTER. f.a.b. REPAIR OF DAMAGE:
- ANY DAMAGE TO THE CROWN, TRUNK, OR ROOT SYSTEM OF ANY TREE RETAINED ON THE SITE SHALL BE REPAIRED IMMEDIATELY IF POSSIBLE.
- DAMAGED ROOTS SHALL IMMEDIATELY BE CUT OFF CLEANLY IF BROKEN, OR IF EXPOSED, BRIDGE WITH BASE MATERIAL RATHER THAN CUTTING. DO NOT COMPACT BASE BEYOND 85% WITH CRZ.

2. VEGETATIVE PRACTICES

- a. TOPSOILING (STOCKPILE) VESCH 3.30
- a.a. TOPSOIL WILL BE STRIPPED FROM AREAS TO BE GRADED AND STOCKPILED FOR LATER USE. STOCKPILE LOCATIONS MAY HAVE TO BE LOCATED OFF-SITE AND ARE TO BE STABILIZED WITH TEMPORARY VEGETATION. PRIOR TO LAND-DISTURBING ACTIVITIES, THE CONTRACTOR SHALL SUBMIT A SUPPLEMENTARY E&S PLAN (IF THE STOCKPILE IS LOCATED OFF-SITE). THIS SUPPLEMENTAL PLAN WOULD HAVE TO BE APPROVED BY THE PLAN APPROVING AUTHORITY BEFORE ANY OFF-SITE ACTIVITY COMMENCES.
- b. TEMPORARY SEEDING VESCH 3.31
- b.a. ALL DENUDED AREAS, WHICH WILL BE LEFT DORMANT FOR EXTENDED PERIODS OF TIME SHALL BE SEEDED WITH FAST GERMINATING TEMPORARY VEGETATION IMMEDIATELY FOLLOWING GRADING. SELECTION OF THE SEED MIXTURE WILL DEPEND ON THE TIME OF YEAR IT
- b.b. SEE SHEET III-288 OF THE VIRGINIA EROSION AND SEDIMENT CONTROL HANDBOOK (VESCH) FOR ALLOWABLE PLANTING MATERIAL, SEEDING RATES, AND DATES. THE PLANTING REQUIREMENTS OF THE "SOUTH" SHALL BE FOLLOWED. LIMING SHALL BE BASED ON TABLE 3.31-A OF VESCH. FERTILIZERS SHALL BE APPLIED AS 600 LB/ACRE. THE FERTILIZER SHALL BE INCORPORATED INTO THE TOP 2-4" OF SOIL. SEED SHALL BE EVENLY APPLIED AND SMALL GRAINS SHALL BE PLANTED NO MORE THAN 1.5" DEEP. SEEDING MADE IN FALL FOR WINTER COVER AND DURING HOT SUMMER MONTHS SHALL BE MULCHED.
- c. EROSION CONTROL BLANKET AND MULCHING VESCH 3.36 AND 3.35
- c.a. EROSION CONTROL BLANKETS WILL BE INSTALLED OVER FILL SLOPES WHICH HAVE BEEN BROUGHT TO FINAL GRADE AND HAVE BEEN SEEDED TO PROTECT THE SLOPES FROM RILL AND GULLY EROSION AND TO ALLOW SEED TO GERMINATE PROPERLY. MULCH (STRAW OR FIBER) WILL BE USED ON RELATIVELY FLAT AREAS AND WILL BE APPLIED AS A SECOND STEP IN SEEDING OPERATION.
- d. DUST CONTROL VESCH 3.39
- d.a. DUST SHALL BE CONTROLLED USING A VARIETY OF METHODS SUCH AS VEGETATIVE COVER, MULCH, TILLAGE, IRRIGATION, SPRAY-ON ADHESIVES, STONE BARRIERS, AND CALCIUM CHLORIDE. THE IMPLEMENTATION OF THE DUST CONTROL METHODS SHALL BE INSTALLED PER
- SECTION 3.39 OF VESCH e. PERMANENT SEEDING - VESCH 3.32
- e.a. SINCE THE SUBJECT SITE IS LOCATED WITHIN THE COASTAL PLAIN AREA OF VIRGINIA, SHEET III-304 OF THE VIRGINIA EROSION AND SEDIMENT CONTROL HANDBOOK SHALL BE FOLLOWED FOR FINAL SEEDING MATERIAL, SEEDING RATES, AND DATES OF APPLICATION. f. SODDING - VESCH 3.33
- f.a. SODDED AREAS SHALL BE BROUGHT TO FINAL GRADE IN ACCORDANCE WITH THE APPROVED PLANS. SOIL TESTS SHALL BE MADE TO DETERMINE THE EXACT REQUIREMENTS FOR LIME AND FERTILIZER. PRIOR TO LAYING SOD, SOIL SURFACE SHALL BE CLEAR OF TRASH, DEBRIS AND LARGE OBJECTS. QUALITY OF SOD SHALL BE STATE CERTIFIED TO ENSURE GENETIC PURITY AND HIGH QUALITY. SOD SHALL NOT BE LAID ON FROZEN SOIL SURFACE, OR IN EXCESSIVELY WET OR DRY WEATHER. SOD SHALL BE DELIVERED AND INSTALLED WITHIN 36 HOURS, AND SHALL BE INSTALLED PER PAGE III-339 OF VESCH.
- THE EROSION AND SEDIMENT CONTROL INSPECTOR SHALL HAVE THE AUTHORITY TO ADD OR DELETE EROSION AND SEDIMENT CONTROLS AS NEEDED IN THE FIELD. IN ADDITION, NO SEDIMENT TRAPS OR BASINS MAY BE REMOVED WITHOUT PRIOR APPROVAL OF THE INSPECTOR.

EROSION AND SEDIMENT CONTROL MANAGEMENT MEASURES

LANDSCAPE / TREE PRESERVATION NOTES

PRIOR TO ANY LAND DISTURBING ACTIVITY, THE CONTRACTOR SHALL CONTACT THE ARLINGTON COUNTY ARBORIST TO SCHEDULE AN INSPECTION.

LAND CONSERVATION NOTES:

- 1. NO DISTURBED AREA WILL REMAIN DENUDED FOR MORE THAN 7 CALENDAR DAYS UNLESS OTHERWISE AUTHORIZED BY THE DIRECTOR OR HIS AGENT. 2. ALL EROSION AND SEDIMENT CONTROL MEASURES ARE TO BE PLACED PRIOR TO OR AS THE FIRST STEP IN GRADING. FIRST AREAS TO BE CLEARED ARE TO BE THOSE REQUIRED FOR THE PERIMETER CONTROLS.
- 3. ALL STORM AND SANITARY SEWER LINES NOT IN STREETS ARE TO BE MULCHED AND SEEDED WITHIN 5 DAYS AFTER BACKFILL. NO MORE THAN 100 FEET ARE TO BE OPEN AT ANY ONE TIME. 4. ELECTRIC POWER, TELEPHONE AND GAS SUPPLY TRENCHES ARE TO BE COMPACTED, SEEDED AND MULCHED WITHIN 5 DAYS AFTER BACKFILLING.

5. ALL TEMPORARY EARTH BERMS, DIVERSIONS AND SEDIMENT CONTROL DAMS ARE TO BE MULCHED AND SEEDED FOR TEMPORARY VEGETATIVE COVER

- IMMEDIATELY AFTER GRADING. STRAW OR HAY MULCH IS REQUIRED. THE SAME APPLIES TO ALL SOIL STOCKPILES. 6. DURING CONSTRUCTION, ALL STORM SEWER INLETS WILL BE PROTECTED BY INLET PROTECTION.
- 7. ANY DISTURBED AREA NOT COVERED BY NOTE 1 ABOVE AND NOT PAVED, SODDED OR BUILT UPON BY NOV. 1, OR DISTURBED AFTER THAT DATE, SHALL BE MULCHED IMMEDIATELY WITH HAY OR STRAW MULCH AT THE RATE OF 2 TONS/ACRE AND OVER-SEEDED BY APRIL 15.
- 8. AT THE COMPLETION OF ANY PROJECT CONSTRUCTION AND PRIOR TO BOND RELEASE, ALL TEMPORARY SEDIMENT CONTROLS SHALL BE REMOVED AND ALL DENUDED AREAS SHALL BE STABILIZED.

EROSION & SEDIMENT CONTROL PROGRAM:

- 1. THE EROSION CONTROL PLAN IS INTENDED TO ESTABLISH ENTRANCES AND PERIMETER CONTROL MEASURES WHICH INCLUDES SILT FENCE (SF), INLET PROTECTION (IP), AND OTHER CONTROLS SPECIFIED ON THE PLANS.
- 2. WHERE CONSISTENT WITH JOB SAFETY REQUIREMENTS, ALL EXCAVATED MATERIAL SHALL BE PLACED ON THE UPHILL SIDE OF TRENCHES. NO MATERIAL SHALL BE PLACED IN STREAMBEDS. ANY STOCKPILED MATERIAL WHICH WILL REMAIN IN PLACE LONGER THAN 7 DAYS SHALL BE SEEDED AND MULCHED, WHEN SPOIL IS PLACED ON THE DOWNHILL SIDE OF TRENCH, IT SHALL BE BACKSLOPED TO DRAIN TOWARD THE TRENCH, WHEN NECESSARY TO DEWATER THE TRENCH, THE PUMP DISCHARGE HOSE SHALL OUTLET IN A STABILIZED AREA OR A SEDIMENT TRAPPING DEVICE.
- 3. ALL PRACTICES AND CONTROL DEVICES DESCRIBED HEREIN SHALL CONFORM TO THE CURRENT VIRGINIA EROSION AND SEDIMENT CONTROL HANDBOOK (VESCH). IN ADDITION, THE CONTRACTOR SHALL TAKE THE FOLLOWING STEPS TO MINIMIZE THE VOLUME OF SILT:
- a. CONTRACTOR SHALL EVALUATE THE SITE TO DETERMINE EXTENSIVE CUT AND FILL AREAS, AND SHALL WORK THOSE AREAS TO MINIMIZE THE USE OF HEAVY EQUIPMENT. CONTRACTOR SHALL BRING DISTURBED AREAS TO GRADE (ROUGH OR FINISHED) AND STABILIZE THOSE AREAS WITH TEMPORARY OR PERMANENT VEGETATION. THESE DISTURBED AREAS SHALL BE STABILIZED PRIOR TO BEGINNING WORK IN ANOTHER AREA.
- b. FILL AREAS SHALL BE COMPACTED COMPLETELY PRIOR TO THE END OF EACH WORK DAY. FILL SLOPE SURFACES SHALL BE KEPT ROUGH TO REDUCE SHEET EROSION OF THE SLOPES. CONTRACTOR SHALL RE-DIRECT CONCENTRATED RUNOFF, BY EARTH BERMS OR OTHER DEVICES, AROUND ACTIVELY DISTURBED AREAS TO STABILIZED OUTLETS.
- c. CUT SLOPES SHALL BE PROTECTED FROM CONCENTRATED FLOW BY BERMS (ABOVE THE SLOPE) AND DIRECTED AROUND THE DISTURBED AREA TO STABILIZED OUTLETS.
- 4. MEASURES TO CONTROL EROSION AND SILTATION SHALL BE PROVIDED PURSUANT TO AND IN COMPLIANCE WITH CURRENT STATE AND LOCAL REGULATIONS. THE INFORMATION CONTAINED IN THE CONSTRUCTION PLANS AND/OR THE APPROVAL OF THE PLANS SHALL IN NO WAY RELIEVE THE CONTRACTOR OR HIS AGENT OF ANY LEGAL RESPONSIBILITY WHICH MAY BE REQUIRED BY THE CODE OF VIRGINIA AND CHAPTER 57 OF THE ARLINGTON COUNTY CODE.
- 5. ALL AREAS, ON OR OFF-SITE, THAT ARE DISTURBED BY THIS CONSTRUCTION AND WHICH ARE NOT PAVED OR BUILT UPON SHALL BE ADEQUATELY STABILIZED TO CONTROL EROSION AND SEDIMENTATION. ACCEPTABLE STABILIZATION SHALL CONSIST OF PERMANENT GRASS SEED MIXTURE OR SOD THAT IS INSTALLED IN ACCORDANCE WITH THE PROJECT SPECIFICATIONS. ALL SLOPES 3:1 AND GREATER SHALL BE RECEIVE SOIL STABILIZATION IN ACCORDANCE WITH THE SPECIFICATIONS.
- 6. WHERE STREAM CROSSINGS ARE REQUIRED FOR EQUIPMENT, TEMPORARY CULVERTS SHALL BE PROVIDED.
- 7. FOR FURTHER REQUIREMENTS AND DETAILS OF TREE PRESERVATION, PLANTING, EROSION AND SEDIMENT CONTROL, SEE COUNTY CONSTRUCTION STANDARDS AND SPECIFICATIONS AND/OR THE VIRGINIA EROSION AND SEDIMENT CONTROL HANDBOOK.

GENERAL EROSION AND SEDIMENT CONTROL NOTES

- 1. UNLESS OTHERWISE INDICATED, ALL VEGETATIVE AND STRUCTURAL EROSION AND SEDIMENT CONTROL PRACTICES WILL BE CONSTRUCTED AND MAINTAINED ACCORDING TO THE MINIMUM STANDARDS AND SPECIFICATIONS OF THE VIRGINIA EROSION AND SEDIMENT CONTROL HANDBOOK AND VIRGINIA REGULATIONS VR 625-02-00 EROSION AND SEDIMENT CONTROL REGULATIONS.
- 2. THE PLAN APPROVING AUTHORITY MUST BE NOTIFIED ONE WEEK PRIOR TO THE PRE-CONSTRUCTION CONFERENCE, ONE WEEK PRIOR TO THE COMMENCEMENT OF LAND DISTURBING ACTIVITY, AND ONE WEEK PRIOR TO THE FINAL INSPECTION.
- 3. ALL EROSION AND SEDIMENT CONTROL MEASURES ARE TO BE PLACED PRIOR TO OR AS THE FIRST STEP IN CLEARING.
- 4. A COPY OF THE APPROVED EROSION AND SEDIMENT CONTROL PLAN SHALL BE MAINTAINED ON THE SITE AT ALL TIMES.
- 5. PRIOR TO COMMENCING LAND DISTURBING ACTIVITIES IN THE AREAS OTHER THAN INDICATED ON THESE PLANS (INCLUDING, BUT NOT LIMITED TO, OFF-SITE BORROW OR WASTE AREAS), THE CONTRACTOR SHALL SUBMIT A SUPPLEMENTARY EROSION AND SEDIMENT CONTROL PLAN TO THE OWNER FOR REVIEW AND APPROVAL BY THE PLAN APPROVING AUTHORITY.
- 6. THE CONTRACTOR IS RESPONSIBLE FOR INSTALLATION OF ANY ADDITIONAL EROSION AND SEDIMENT CONTROL MEASURES NECESSARY TO PREVENT EROSION AND SEDIMENTATION AS DETERMINED BY THE PLAN APPROVING AUTHORITY.

- 7. ALL DISTURBED AREAS ARE TO DRAIN TO APPROVED SEDIMENT CONTROL MEASURES AT ALL TIMES DURING LAND DISTURBING ACTIVITIES AND DURING SITE DEVELOPMENT UNTIL FINAL STABILIZATION IS ACHIEVED.
- 8. DURING DEWATERING OPERATIONS, WATER WILL BE PUMPED INTO AN APPROVED FILTERING DEVICE.
- 9. THE CONTRACTOR SHALL INSPECT ALL EROSION AND SEDIMENT CONTROL MEASURES PERIODICALLY AND AFTER EACH RUNOFF-PRODUCING RAINFALL EVENT. ANY NECESSARY REPAIRS OR CLEANUP TO MAINTAIN THE EFFECTIVENESS OF THE EROSION CONTROL DEVICES SHALL BE MADE IMMEDIATELY
- 10. ALL BIOFILTERS SHALL BE KEPT OFF-LINE UNTIL CONSTRUCTION IS COMPLETED AND ALL AREAS HAVE BEEN PROPERLY STABILIZED. THIS SHALL BE ACHIEVED BY USING INLET PROTECTION AT THE CURB CUTS AND STORMWATER CATCH BASINS LEADING DIRECTLY INTO THE BIOFILTERS.
- 11. ALL TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES SHALL BE REMOVED WITHIN 30 DAYS AFTER FINAL SITE STABILIZATION OR AFTER THE TEMPORARY MEASURES ARE NO LONGER NEEDED.

PRE-STORM EROSION & SEDIMENTATION CHECKLIST:

PER GENERAL EROSION AND SEDIMENT CONTROL NOTE 6, THE CONTRACTOR IS RESPONSIBLE FOR THE INSTALLATION AND MAINTENANCE OF ANY ADDITIONAL EROSION AND SEDIMENT CONTROL (ESC) MEASURES NECESSARY TO PREVENT EROSION AND SEDIMENTATION AS DETERMINED BY THE COUNTY. THESE SUPPLEMENTARY PRACTICES ARE IN ADDITION TO THOSE SHOWN IN AN EROSION AND SEDIMENT CONTROL PLAN. EROSION AND SEDIMENT CONTROL PRACTICES SHALL BE MODIFIED AS NEEDED TO ENSURE ONLY CLEAR WATER IS DISCHARGED FROM THE SITE.

THE FOLLOWING ACTIONS SHALL BE TAKEN PRIOR TO STORM EVENTS WITH PREDICTED HEAVY AND/OR LARGE VOLUME RAINFALL TO PREVENT SEDIMENT DISCHARGES FROM A CONSTRUCTION SITE. A TYPICAL SUMMER THUNDERSTORM IS AN EXAMPLE OF A STORM EVENT WITH PREDICTED HEAVY AND/OR LARGE VOLUME RAINFALL

1. PERIMETER CONTROLS

- a. SILT FENCE SHALL BE CHECKED FOR UNDERMINING, HOLES, OR DETERIORATION OF THE FABRIC. FENCING SHALL BE REPLACED IMMEDIATELY IF THE FABRIC IS DAMAGED OR WON. SILT FENCE MUST BE TRENCHED INTO THE GROUND PER STATE SPECIFICATIONS (VESCH STD & SPEC 3.09). b. WOODEN STAKES OR STEEL POSTS SHALL BE PROPERLY SECURED UPRIGHT INTO THE GROUND. DAMAGED POSTS OR STAKES MUST BE REPLACED.
- c. SEDIMENT THAT HAS ACCUMULATED AGAINST THE SILT FENCE SHALL BE REMOVED. ACCUMULATED SEDIMENT MUST BE REMOVED WHEN THE LEVEL REACHES ONE-HALF THE HEIGHT OF THE FENCING.
- d. HAY BALES OR A STONE BERM SHALL BE PLACED ACROSS THE CONSTRUCTION ENTRANCE TO PREVENT SEDIMENT FROM LEAVING THE CONSTRUCTION SITE.

2. EXPOSED SLOPES AND SOIL

- a. EXPOSED SLOPES NOT AT THE FINAL STABILIZATION PHASE SHALL BE COVERED WITH TARPS, PLASTIC SHEETING, OR EROSION CONTROL MATTING. COVERING MATERIAL SHALL BE PROPERLY SECURED/ANCHORED.
- b. CONTROLS SHALL BE INSTALLED TO PREVENT CONCENTRATED FLOW DOWN AN EXPOSED SLOPE. BERMS OR DIVERSION DIKES SHALL BE INSTALLED AT THE TOP OF CUT/EXPOSED SLOPES TO DIRECT STORM FLOW AROUND THE DISTURBED AREA.
- c. EXPOSED SLOPES AT THE FINAL STABILIZATION PHASE SHALL BE STABILIZED USING SLOPE STABILIZATION PRACTICES SUCH AS SOIL STABILIZATION BLANKETS OR MATTING AS SPECIFIED IN THE VIRGINIA EROSION AND SEDIMENT CONTROL HANDBOOK (VESCH STD & SPEC 3.36) BLANKETS OR MATS MUST BE PROPERLY SECURED AND ANCHORED TO THE SLOPE USING STAPLES, PINS, OR STAKES.
- d. SEEDED AREAS SHALL BE CHECKED AND RESEEDED AS NECESSARY TO COVER EXPOSED SOIL. RECENTLY SEEDED AREAS SHALL BE PROTECTED BY STRAW OR SOIL STABILIZATION BLANKETS TO PREVENT SEEDING FROM BEING WASHED AWAY.

3. STOCKPILES

a. STOCKPILED SOIL AND OTHER LOOSE MATERIALS THAT CAN BE WASHED AWAY SHALL BE COVERED WITH A TARP, PLASTIC SHEETING, OR OTHER STABILIZATION MATTING. THE COVER MUST BE PROPERLY SECURED/ANCHORED DOWN TO PREVENT IT FROM BEING BLOWN OFF AND EXPOSING MATERIALS TO RAIN. CONTROLS SUCH AS HAY BALES OR BOOMS SHALL BE PLACED ALONG THE PERIMETER OF THE STOCKPILE (DOWNHILL SIDE).

4. INLET PROTECTION a. INLET PROTECTION CONTROLS SHALL BE INSPECTED TO ENSURE THEY ARE FUNCTIONING PROPERLY AND FLOODING WILL NOT OCCUR. CLOGGED OR DAMAGED CONTROLS MUST BE REPLACED IMMEDIATELY. ENSURE CONTROLS ALLOW FOR OVERFLOW/BYPASS OF STORMWATER

RUNOFF DURING SIGNIFICANT STORM EVENTS. IN ADDITION TO THESE PRE-STORM ACTIONS, ALL EROSION AND SEDIMENT CONTROL (ESC) MEASURES MUST BE CHECKED DAILY AND AFTER EACH SIGNIFICANT RAINFALL.

POLLUTION PREVENTION PLAN NOTES (STORMWATER MANUAL - SECTION 2.4)

- 1. ONLY THE FOLLOWING NON-STORMWATER DISCHARGES ARE AUTHORIZED BY ARLINGTON COUNTY'S MS4 PERMIT, UNLESS THE STATE WATER CONTROL BOARD, THE VIRGINIA SOIL AND WATER CONSERVATION BOARD (BOARD), OR ARLINGTON COUNTY DETERMINES THE DISCHARGE TO BE A SIGNIFICANT SOURCE OF POLLUTANTS TO SURFACE WATERS:
- a. WATER LINE FLUSHING; LANDSCAPE IRRIGATION; DIVERTED STREAM FLOWS; RISING GROUND WATERS; UNCONTAMINATED GROUND WATER INFILTRATION (AS DEFINED AT 40 CFR 35.2005(20)); UNCONTAMINATED PUMPED GROUND WATER; DISCHARGES FROM POTABLE WATER SOURCES; FOUNDATION DRAINS; AIR CONDITIONING CONDENSATION; IRRIGATION WATER; SPRINGS; WATER FROM CRAWL SPACE PUMPS; FOOTING DRAINS; LAWN WATERING; INDIVIDUAL RESIDENTIAL CAR WASHING; FLOWS FROM RIPARIAN HABITATS AND WETLANDS; DECHLORINATED SWIMMING POOL DISCHARGES; DISCHARGES OR FLOWS FROM FIREFIGHTING; AND, OTHER ACTIVITIES GENERATING DISCHARGES IDENTIFIED BY THE DEPARTMENT OF ENVIRONMENTAL QUALITY AS NOT REQUIRING VPDES AUTHORIZATION
- 2. APPROPRIATE CONTROLS MUST BE IMPLEMENTED TO PREVENT ANY NON-STORMWATER DISCHARGES NOT INCLUDED ON THE ABOVE LIST (E.G. CONCRETE WASH WATER, PAINT WASH WATER, VEHICLE WASH WATER, DETERGENT WASH WATER, ETC.) FROM BEING DISCHARGED INTO ARLINGTON COUNTY'S MS4 SYSTEM, WHICH INCLUDES THE CURB AND GUTTER SYSTEM, AS WELL AS CATCH BASINS AND OTHER STORM DRAIN INLETS, OR STREAM
- 3. PER CHAPTER 26 OF THE ARLINGTON COUNTY CODE, IT SHALL BE UNLAWFUL FOR ANY PERSON TO DISCHARGE DIRECTLY OR INDIRECTLY INTO THE STORM SEWER SYSTEM OR STATE WATERS, ANY SUBSTANCE LIKELY, IN THE OPINION OF THE COUNTY MANAGER, TO HAVE AN ADVERSE EFFECT ON THE STORM SEWER SYSTEM OR STATE WATERS.

UTILITY INSTALLATION:

- UNDERGROUND UTILITY LINES SHALL BE INSTALLED IN ACCORDANCE WITH THE FOLLOWING STANDARDS IN ADDITION TO OTHER APPLICABLE CRITERIA:
- 1. NO MORE THAN 100 LINEAR FEET OF TRENCH MAY BE OPENED AT ONE TIME.
- 2. EXCAVATED MATERIAL SHALL BE PLACED ON THE UPHILL SIDE OF TRENCHES. 3. EFFLUENT FROM DEWATERING OPERATIONS SHALL BE FILTERED OR PASSED THROUGH AN APPROVED SEDIMENT TRAPPING DEVICE, OR BOTH, AND
- DISCHARGED IN A MANNER THAT DOES NOT ADVERSELY AFFECT FLOWING STREAMS OR OFF-SITE PROPERTY. 4. MATERIAL USED FOR BACKFILLING TRENCHES SHALL BE PROPERLY COMPACTED IN ORDER TO MINIMIZE EROSION AND PROMOTE STABILIZATION.
- 5. STABILIZATION SHALL BE ACCOMPLISHED IN ACCORDANCE WITH THESE REGULATIONS.
- 6. APPLICABLE SAFETY REGULATIONS SHALL BE COMPLIED WITH. 9. ANY DISTURBED AREA NOT COVERED BY NOTE #1 ABOVE AND PAVED, SODDED OR BUILT UPON BY NOVEMBER 1ST, OR DISTURBED AFTER THAT DATE, SHALL BE MULCHED WITH HAY OR STRAW AT THE RATE OF 2 TONS PER ACRE AND OVER-SEEDED NO LATER THAN MAY 15TH.
- 10. AT THE COMPLETION OF THE CONSTRUCTION PROJECT AND PRIOR TO BOND RELEASE, ALL TEMPORARY SEDIMENT CONTROLS SHALL BE REMOVED

AND ALL DENUDED AREAS SHALL BE STABILIZED. ARLINGTON COUNTY INSPECTOR TO APPROVE REMOVAL OF ALL TEMPORARY SILTATION MEASURES.

- **MAINTENANCE PROGRAM:** THE FOLLOWING IS A PROGRAM OF MAINTENANCE FOR THE MECHANICAL CONTROLS SPECIFIED IN THIS NARRATIVE AND ON THE PLAN:
- 1. THE SITE SUPERINTENDENT OR HIS/HER REPRESENTATIVE SHALL MAKE A VISUAL INSPECTION OF ALL MECHANICAL CONTROLS AND NEWLY STABILIZED AREA (I.E. SEEDED AND MULCHED AND/OR SODDED AREAS) ON A DAILY BASIS; ESPECIALLY AFTER A HEAVY RAINFALL EVENT TO ENSURE THAT ALL CONTROLS ARE MAINTAINED AND PROPERLY FUNCTIONING. ANY DAMAGED CONTROLS SHALL BE REPAIRED PRIOR TO THE END OF THE
- WORK DAY INCLUDING RE-SEEDING AND MULCHING OR RE-SODDING IF NECESSARY. 2. ALL SEDIMENT TRAPPING DEVICES SHALL BE CLEARED OUT AT 50% TRAP CAPACITY AND THE SEDIMENT SHALL BE DISPOSED OF BY SPREADING ON THE SITE OR IF NOT SUITABLE FOR FILL, HAULING AWAY AND DEPOSITING AT AN ACCEPTABLE DUMP SITE.
- 3. THE CONTRACTOR SHALL TAKE SPECIAL CARE TO PREVENT MUD AND/OR OTHER DEBRIS FROM BEING ENTERED ONTO EXISTING SWM/BMP FACILITIES OR DOWNSTREAM WATER WAYS. SHOULD OFF-SITE AREAS BECOME POLLUTED BY CONSTRUCTION ACTIVITIES, THE CONTRACTOR SHALL BE RESPONSIBLE FOR CLEANING THE AFFECTED AREAS TO THE SATISFACTION OF THE INSPECTOR.

REMAINING DENUDED AREAS SHALL BE STABILIZED. CERTAIN DEVICES MAY BE REMOVED PRIOR TO CONSTRUCTION COMPLETION BUT ONLY WITH


THE APPROVAL OF THE COUNTY INSPECTOR. 5. AFTER CONSTRUCTION OPERATIONS HAVE ENDED, ALL DISTURBED AREAS SHALL BE STABILIZED. UPON APPROVAL OF THE COUNTY INSPECTOR, MECHANICAL SEDIMENT CONTROLS SHALL BE REMOVED AND THE GROUND PERMANENTLY STABILIZED WITH VEGETATION WITHIN 30 DAYS.

4. AT THE COMPLETION OF CONSTRUCTION AND PRIOR TO BOND RELEASE, ALL TEMPORARY SEDIMENT CONTROLS SHALL BE REMOVED AND ANY

ARLINGTON VIRGINIA

DEPARTMENT OF ENVIRONMENTAL SERVICES **FACILITIES & ENGINEERING DIVISION** ENGINEERING BUREAU 2100 CLARENDON BOULEVARD, SUITE 813 ARLINGTON, VA 22201 PHONE: 703.228.3629

FAX: 703.228.3606 COPYRIGHT © 2021 ARLINGTON COUNTY



APPROVALS

02/08/23 QUALITY CONTROL ENGINEER dward Sanders 2/15/202 CONSTRUCTION MANAGEMENT SUPERVISO WATER, SEWER, STREETS BUREAU CHIEF Hum TRANSPORTATION DIRECTOR

DATE

REVISIONS

S

Z

B

Σ \square

 O

DESIGNED: K.PATEL DRAWN: K. PATEL


CHECKED: Z. DRAGACEVAC


PLOTTED: MARCH 6 2023


SCALE:

C032.

CLARENDON BLVD. & N CLEVELAND ST P31D












DATE







CONTROL S SI AND SEDIMENT (AND DETAILS EROSION_AND_NOTES ARENDON

DESIGNED: K.PATEL DRAWN: K. PATEL CHECKED: Z. DRAGACEVAC PLOTTED: MARCH 6 2023 SCALE:

AS SHOWN

C032.2

TABLE 3.31-B (Revised June 2003) TEMPORARY SEEDING SPECIFICATIONS QUICK REFERENCE FOR ALL REGIONS

SEED						
APPLICATION DATES	SPECIES	APPLICATION RATES				
	50/50 Mix of Annual Ryegrass (Iolium multi- florum) & Cereal (Winter) Rye (Secale cereale)	50 -100 (lbs/acre)				
Feb. 16 - Apr. 30	Annual Ryegrass (lolium multi-florum)	60 - 100 (lbs/acre)				
May 1 - Aug. 31	German Millet	50 (lbs/acre)				

FERTILIZER & LIME

 Apply 10-10-10 fertilizer at a rate of 450 lbs. / acre (or 10 lbs. / 1,000 sq. ft.) Apply Pulverized Agricultural Limestone at a rate of 2 tons/acre (or 90 lbs. / 1,000 sq. ft.)

1 - A soil test is necessary to determine the actual amount of lime required to adjust the soil pH of site. 2 - Incorporate the lime and fertilizer into the top 4 – 6 inches of the soil by disking or by other means.

3 - When applying Slowly Available Nitrogen, use rates available in <u>Erosion & Sediment Control Technical Bulletin</u> # 4, 2003 Nutrient Management for Development Sites at http://www.dcr.state.va.us/sw/e&s.htm#pubs

TABLE 3.32-D (Revised June 2003) PERMANENT SEEDING SPECIFICATIONS FOR PIEDMONT AREA

	SEED ¹	
LAND USE	SPECIES	APPLICATION PER ACRE
	Tall Fescue ¹	95-100%
Minimum Care Lawn	Perennial Ryegrass	0-5%
(Commercial or Residential)	Kentucky Bluegrass ¹	0-5%
		TOTAL: 175-200 lbs.
High-Maintenance Lawn	Tall Fescue ¹	TOTAL: 200-250 lbs.
	Tall Fescue ¹	128 lbs.
General Slope (3:1 or less)	Red Top Grass or Creeping Red Fescue	2 lbs.
Gerieral Slope (5.1 or less)	Seasonal Nurse Crop ²	<u>20 lbs.</u>
	·	TOTAL: 150 lbs.
	Tall Fescue ¹	108 lbs.
Low-Maintenance Slope	Red Top Grass or Creeping Red Fescue	2 lbs.
(Steeper than 3:1)	Seasonal Nurse Crop ²	20 lbs.
(Clooper triair 5.1)	Crownvetch ³	<u>20 lbs.</u>
		TOTAL: 150 lbs.

- When selecting varieties of turfgrass, use the Virginia Crop Improvement Association (VCIA) recommended turfgrass variety list. Quality seed will bear a label indicating that they are approved by VCIA. A current turfgrass variety list is available at the local County Extension office or through VCIA at 804-746-4884 or at

http://sudan.cses.vt.edu/html/Turf/turf/publications/publications2.html 2 - Use seasonal nurse crop in accordance with seeding dates as stated below:


> February 16th - April Annual Rye Foxtail Millet May 1st - August 15th August 16th - October Annual Rye November - February 15th ... Winter Rye

3 - Substitute Sericea lespedeza for Crownvetch east of Farmville, VA (May through September use hulled seed, all other periods, use unhulled Sericea). If Flatpea is used, increase rate to 30 lbs./acre. If Weeping Lovegrass is used, include in any slope or low maintenance mixture during warmer seeding periods, increase to 30 -40


FERTILIZER & LIME

- Apply 10-20-10 fertilizer at a rate of 500 lbs. / acre (or 12 lbs. / 1,000 sq. ft.) Apply Pulverized Agricultural Limestone at a rate of 2 tons/acre (or 90 lbs. / 1,000 sq. ft.)
- A soil test is necessary to determine the actual amount of lime required to adjust the soil pH of site.

- Incorporate the lime and fertilizer into the top 4 – 6 inches of the soil by disking or by other means. - When applying Slowly Available Nitrogen, use rates available in <u>Erosion & Sediment Control Technical Bulletin</u> # 4, 2003 Nutrient Management for Development Sites at http://www.dcr.state.va.us/sw/e&s.htm#pubs




MASON'S TROWEL IS A HANDY TOOL FOR TUCKING DOWN THE ENDS AND TRIMMING PIECES.



APPEARANCE OF GOOD SOD

OF 4" AS NEEDED.

WATER WELL AS SOON AS THE SOD IS LAID.



SHOOTS OR GRASS BLADES. GRASS SHOULD BE GREEN AND HEALTHY, MOWED AT A 2"-3" CUTTING HEIGHT.

THATCH - GRASS CLIPPINGS AND DEAD LEAVES, UP TO 1/2" THICK.

<u>ROOT ZONE - SOIL AND ROOTS.</u> SHOULD BE 1/2"-3/4" THICK, WITH DENSE ROOT MAT FOR STRENGTH.

SOURCE: VA. DSWC

ARLINGTON

VIRGINIA

DEPARTMENT OF

ENVIRONMENTAL SERVICES FACILITIES & ENGINEERING DIVISION ENGINEERING BUREAU 2100 CLARENDON BOULEVARD, SUITE 813 ARLINGTON, VA 22201 PHONE: 703.228.3629 FAX: 703.228.3606 COPYRIGHT © 2021 ARLINGTON COUNTY VIRGINIA - ALL RIGHTS RESERVED

ZORAN DRAGACEVAC

Edward Sanders 2/15/2023

CONSTRUCTION MANAGEMENT SUPERVISOR

WATER, SEWER, STREETS BUREAU CHIEF

DATE

APPROVALS

Amy Pflaum QUALITY CONTROL ENGINEER

REVISIONS

Ŋ

EVELAND
IN BLVD. & N

SEDIMENT_CAND DETAILS

EROSION_AND_ NOTES_

SODDING

LAY SOD IN A STAGGERED PATTERN. BUTT THE STRIPS TIGHTLY AGAINST EACH OTHER. DO NOT LEAVE SPACES AND DO NOT OVERLAP. A SHARPENED

TO ACHIEVE FIRM

CONTACT WITH THE SOIL.

<u>BUTTING</u> - ANGLED ENDS CAUSED BY THE AUTO-MATIC SOD CUTTER MUST BE MATCHED CORRECTLY.

ESTABLISHED - IN 2-3 WEEKS. SET THE MOWER HIGH (2"-3").

PLATE: 3.33-1

DESIGNED: K.PATEL

DRAWN: K. PATEL CHECKED: Z. DRAGACEVAC

SCALE:

ARENDON

PLOTTED: MARCH 6 2023

AS SHOWN

C032.3

2011 BMP Standards and Specifications			IP Standards and Sp	ecifications	omphanter spice							
Project Name:	pa	1D CLARENDON	BLVD. @ N. CLEVE	I AND ST	-	CLEAR	ALL	data input cells				\blacksquare
Date:			19-Jul-22			CLEAR	ALL	constant values				
Site Information		Linear Dev	elopment Project?	Yes				calculation cells				+
Site information								final results				+
Post-Development Project	(Treatme	nt Volume	and Loads)									
	•			d Area (acres) →	0.0732			Check:	TRUE			+-1
				reduction required:	20%		BMP Design Spe			aft Stds & Specs		± 1
		The site's net in		ous cover (acres) is:	0.0000	L	and cover areas ent		√			\perp
		Post-Developm	ent TP Load Reduc	tion for Site (lb/yr):	0.0295		Total disturbed	d area entered?	√			-
Pre-ReDevelopment Land Cover (acre	s)											
Forest/Open Space (acres) undisturbed	A Soils	B Soils	C Soils	D Soils	Totals							\blacksquare
forest/open space Managed Turf (acres) — disturbed, graded for					0.0000							+-
vards or other turf to be mowed/managed		0,0055			0.0055							+-
Impervious Cover (acres)		0.0677			0.0677							+
Pact Davidonment Land Cover (acres)												\blacksquare
Post-Development Land Cover (acres)	A Soils	B Soils	C Soils	D Soils	Totals							
Forest/Open Space (acres) undisturbed, protected forest/open space or reforested land					0.0000							
Managed Turf (acres) — disturbed, graded for vards or other turf to be mowed/managed		0.0057			0.0057							
Impervious Cover (acres)		0.0675			0.0675							
Area Check	OK.	OK.	OK.	OK.	0.0732							$\perp \parallel$
Comptonts			Dunctic to	to (Du)								\Box
Constants Annual Rainfall (inches)	43		Runoff Coefficien	A Soils	B Soils	C Soils	D Soils					$\pm \pm$
Target Rainfall Event (inches) Total Phosphorus (TP) EMC (mg/L)	1.00 0.26		Forest/Open Space Managed Turf	0.02 0.15	0.03 0.20	0.04 0.22	0.05 0.25					
Total Nitrogen (TN) EMC (mg/L) Target TP Load (lb/acre/yr)	1.86 0.41		Impervious Cover	0.95	0.95	0.95	0.95					+
Pj (unitless correction factor)	0.90											\blacksquare
LAND COVER SUMMARY P	RE-REDEVE	LOPMENT			L	AND COVER	SUMMARY P	OST DEVELO	PMEN	IT		
Land Cover Summ				Land Cover Summa			Land Cover Sur			Land Cover Summ	-	1
Pre-ReDevelopment	Listed	Adjusted ¹		Post ReDev. & New Forest/Open Space	100000		Post-ReDeve Forest/Open Space			Post-Development Nev	w Impervious	\vdash
Forest/Open Space Cover (acres) Weighted Rv(forest)	0.0000	0.0000		Cover (acres) Weighted Rv(forest)	0.0000		Cover (acres) Weighted Rv(forest)	0.0000				Н
% Forest	0%	0%		% Forest Managed Turf Cover	0%		% Forest	0%				
Managed Turf Cover (acres)	0.0055	0.0055		(acres)	0.0057		Managed Turf Cover (acres)	0.0057				ш
Weighted Rv(turf)	0.2000	0.2000		Weighted Rv (turf)	0.2000		Weighted Rv (turf)	0.2000				ш
% Managed Turf	8%	8%		% Managed Turf	8%		% Managed Turf	8%				Н
Impervious Cover (acres)	0.0677	0.0677		Impervious Cover (acres)	0.0675		ReDev. Impervious Cover (acres)	0.0675		New Impervious Cover (acres)	0.0000	
Rv(impervious)	0.9500 92%	0.9500		Rv(impervious)	0.9500		Rv(impervious)	0.9500		Rv(impervious)	-4	П
% Impervious Total Site Area (acres)	0.0732	92% 0.0732		% Impervious Final Site Area (acres)	92% 0.0732		% Impervious Total ReDev. Site Area	92%				Н
Site Rv	0.8936	0.8936		Final Post Dev Site Rv	0.8916		(acres) ReDev Site Rv	0.8916				
Treatment Volume and	Nutrient Lo	ad				Treat	ment Volume an	d Nutrient Loa	d			
Treatment volume and	A NUMBER LO	au		First Bart Barrian		Heat		d Nutrient Loa		Back Barrelannant		
Pre-ReDevelopment Treatment Volume (acre-ft)	0.0055	0.0055		Final Post-Development Treatment Volume (acre-ft)	0.0054		Post-ReDevelopment Treatment Volume (acre-ft)	0.0054		Post-Development Treatment Volume (acre-ft)	~	
Pre-ReDevelopment Treatment Volume (cubic feet)	237.4565	237.4565		Final Post-Development Treatment Volume (cubic feet)	236.9120		Post-ReDevelopment Treatment Volume (cubic feet)	236.9120		Post-Development Treatment Volume (cubic feet)	+	
Pre-ReDevelopment TP Load (lb/yr)	0.1492	0.1492		Final Post- Development TP Load (lb/yr)	0.1489		Post-ReDevelopment Load (TP) (Ib/yr)*	0.1489		Post-Development TP Load (lb/yr)	-	П
Pre-ReDevelopment TP Load per acre (lb/acre/yr)	2.0400	2.0400		Final Post-Development TP Load per acre (lb/acre/yr)	2.0300		Post-ReDevelopment TP Load per acre (lb/acre/yr)	2.0300				
Baseline TP Load (lb/yr) (0.41 lbs/acre/yr applied to pre-redevelopment area land proposed for new impervious co		0.0300					Max. Reduction Required (Below Pre- ReDevelopment Load)	20%				
Adjusted Land Cover Summary: Pre ReDevelopment land cover minus pervious lan managed turf) acreage proposed for new impervio Adjusted total acreage is consistent with Post-ReD	ous cover.						TP Load Reduction Required for Redeveloped Area (lb/yr)	0.0295		TP Load Reduction Required for New Impervious Area (lb/yr)	0	
of new impervious cover).		,_ ,as ucreage	-									
Column I shows load reduction requriement for ne development load limit, 0.41 lbs/acre/year).	w impervious cove	r (based on new										
			Post-De	velopment Requ	irement for S	ite Area						
			TP Load	Reduction Required	(lb/yr)	0.0295						
				roject TP Load Reduction		0.0295						
						1.00						


RUNOFF REDUCTION NOTES:


THE RUNOFF REDUCTION SPREADSHEET INFORMATION ON THIS PLAN IS FOR DATA TRACKING PURPOSES TO DOCUMENT THE AREA OF LAND DISTURBANCE AND TO CHARACTERIZE PRE- AND POST-DEVELOPMENT LAND USE CONDITIONS.

IN ACCORDANCE WITH ARLINGTON COUNTY'S CHESAPEAKE BAY TOTAL MAXIMUM DAILY LOAD (TMDL) ACTION PLAN, APPROVED BY THE VIRGINIA DEPARTMENT OF ENVIRONMENTAL QUALITY (DEQ) ON SEPTEMBER 1, 2015, LINEAR DEVELOPMENT PROJECTS CONDUCTED BY THE COUNTY ARE ADMINISTERED AND TRACKED AS FOLLOWS CONSISTENT WITH 9VAC25-870-69.A.4, 9VAC25-870-76, AND 9VAC25-870-92:

- POLLUTANT LOAD CHANGES WILL BE COMPUTED AS DESCRIBED IN SECTION 3.A OF THE ACTION PLAN.
- RETROFIT OPPORTUNITIES WILL BE EVALUATED FOR EACH PROJECT, USING THE SCREENING AND SELECTION CRITERIA APPLIED AND DESCRIBED IN THE ADOPTED STORMWATER MASTER PLAN.
- RETROFIT PROJECTS THAT MEET THE SCREENING CRITERIA AND ARE DETERMINED BY ARLINGTON TO BE FEASIBLE AND COST-EFFECTIVE WILL BE IMPLEMENTED WITH SPECIFIC LINEAR DEVELOPMENT PROJECTS. POLLUTANT LOAD REDUCTIONS FROM RETROFIT PROJECTS WILL BE COMPUTED AS DESCRIBED IN SECTION 5 OF THE ACTION PLAN.
- IN CASES WHERE RETROFIT PROJECTS ARE NOT FEASIBLE AND COST-EFFECTIVE FOR A PARTICULAR LINEAR PROJECT, ANY POLLUTANT OF CONCERN (POC) LOAD INCREASES THAT MIGHT OCCUR FOR THAT PROJECT WILL BE ADDRESSED BY LARGER OVERALL POC LOAD REDUCTIONS IN PLACE OR ADDED THROUGH TMDL ACTION PLAN IMPLEMENTATION.

IN THE ABOVE MANNER ARLINGTON, AS THE MS4 OPERATOR AND THE CONSTRUCTION SITE OPERATOR FOR ITS LINEAR DEVELOPMENT PROJECTS, IMPLEMENTS LINEAR PROJECTS AND RETROFIT PROJECTS IN A MANNER THAT ACHIEVES THE MOST TMDL POC REDUCTION FOR THE LEAST COST, WHILE FULLY ACCOUNTING FOR LOAD CHANGES THAT OCCUR WITH LINEAR DEVELOPMENT PROJECT ACTIVITY CONSISTENT WITH THE DEQ CHESAPEAKE BAY TMDL SPECIAL CONDITION






TREE PROTECTION BARRIERS FOR RESTRICTED SPACE AND TREE PITS N.T.S

311300.14NS (2019)




GENERAL NOTES:

- . Contractor to contact the Arlington Forester to schedule a pre-construction inspection of tree protection measures before any work near the critical root zones of trees. To schedule the pre-construction meeting call 703-228-1863.
- ii. Contractor to protect trees per the plan according to the Arlington County DPR Design Standard Detail 311300.14NS
- iii. Contractor to root prune trees per the plan according to the Arlington County DPR Design Standard Detail 02231.5, where called out on the plan.
- iv. Contractor to call the urban forester at 703-228-1863, 72 hours before planting, to schedule inspection of the trees to be planted. Warranty for 1 year after planting shall be the contractor's responsibility. The urban forester and DPR is responsible for inspection.
- v. Contractor to prepare tree planting strips for the replacement trees according to Arlington County DPR Design Standard Detail 329300.4a and 329300.4b.
- vi. Contractor to prepare street tree planting pits according to the Arlington County DPR Design Standard Detail 329300.3a, 329300.3b, and 329300.11c
- vii. Contractor to plant the trees according to Arlington County DPR Design Standard Detail 329300.1 (on flat land) or 329300.2 (on slopes)



4' CHAIN LINK TREE PROTECTION FENCE (RESIDENTIAL)

311300.2 (2016) (02231.2)



AS SHOWN

S

Z

ARENDON

DESIGNED: K.PATEL

DRAWN: K. PATEL

PLOTTED: MARCH 6 2023

SCALE:

1/2" = 1'-0"

ARLINGTON

CHECKED: Z. DRAGACEVAC

SEDIMENT_CAND DETAILS

EROSION

STORMWATER POLLUTION PREVENTION PLAN (SWPPP) **Arlington County Template**

Project Name	CLARENDON BLVD. AND N CLEVELAND ST.			
LDA Permit#	LDA	CGP#:		
Project Address	CLARENDON BLVD	N BLVD. AND N CLEVELAND ST.		
Watershed	SITE IS UNDER ROO	CKY WATERSHED AREA		
Latitude	38.8833 N (decir	mal degrees)		

Operator Name	Arlington County Government		
Company Name	Department of Environmental Services		
Address	2100 CLARENDON BLVD, SUITE 813, ARLINGTON, VA 22201 (C/o Solomon Shikur)		
Phone Number	703-228-6509 (24 Hr Emergency)		
Email Address	Zdragacevac@arlingtonva.us		
24-hour Emergency Contact Phone #	703-228-6509		

CERTIFICATION STATEMENT

"I certify under penalty of law that I have read and understand this document and that this document and all attachments were prepared in accordance with a system designed to assure that qualified personnel properly gathered and evaluated the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment

Operator Name	Zoran Dragacevac	
Signature		
Title	Design team supervisor	
Date	08/05/2022	

ARLINGTON

4.0 Erosion & Sediment Control (ESC)

Details and specs shown on the approved ESC plan are part of this SWPPP.

All controls shall be checked daily and after runoff producing rainfall events. Maintenance will be performed as specified in the ESC plan and state specifications, or as directed by an inspector.

Select all that apply	Erosion & Sediment Control	Estimated Installation Date	Estimated Removal Date
	Safety Fence		
\boxtimes	Silt Fence (detail on approved ESC plan)		
\boxtimes	Super Silt Fence (detail on approved ESC plan)		
	Construction Entrance (detail on approved ESC plan)		
\boxtimes	Tree Protection (Arlington County Std. & Spec)		
	Dewatering (Device shown on approved ESC plan or device selected in Section 5.0 (5) (PPP5))		
\boxtimes	Temporary Seeding	As required	NA
	Permanent Seeding		NA
\boxtimes	Sodding		NA
	Outlet Protection (detail on approved ESC plan)		
	Turbidity Curtain (detail on approved ESC plan)		
	Stream Crossing / Cofferdams (detail on approved ESC plan)		
	Pump Around System (detail on approved ESC plan)		
\boxtimes	Other Practice(s) - Storm Drain Inlet Protection (Std & Spec 3.08)		

V-06/2021

Watershed / Impaired Waters / Total Maximum Daily Load (TMDL) Information

This project site is in the Chesapeake Bay and Potomac River watersheds; TMDLs have been established for sediment, nutrients (nitrogen, phosphorus), and PCBs. A TMDL has also been established for bacteria in the Four Mile Run Watershed. Measures will be taken to minimize the discharge of these pollutants of concern to the storm drain system and surface waters.

☑ Site inspections will be conducted every four (4) business days

☐ Permanent or temporary soil stabilization shall be applied to denuded areas within seven days after final grade is reached on any portion of the site.

☑ Nutrients shall be applied in accordance with manufacturer's recommendations or an approved nutrient management plan and shall not be applied during rainfall events, during windy conditions, or when rain is in the immediate 48-hour forecast.

For projects located in the Potomac River Watershed, measures will be taken to prevent /minimize the discharge of PCBs from the project site. Proper sediment controls and stabilization measures will be implemented. Debris and waste materials generated during demolition activities shall be properly disposed in accordance with local, state, and federal regulations.

☐ Arlington County's TMDL Action Plan for Bacteria covers the entire County. Measures will be taken to prevent /minimize the discharge of bacteria from the project site. Pollution prevention controls focused on managing dumpsters, portable lavatories, and other wastes will be implemented (additional information is provided in Section 6.0 Potential Sources of Pollution & Pollution Prevention Practices).

1.0 SWPPP Documents Located Onsite & Available for Review

SWPPP Documents	Located Onsite 8	& Available for Revi	<u>ev</u>
LDA Permit			
 Erosion & Sediment Control Plan (or agreement in lieu of) 			
Pollution Prevention Plan	⊠ Yes		
Stormwater Management Plan	☐ Yes	⊠ N/A	
Construction General Permit	☐ Yes	⊠ N/A	
Notice of Coverage Letter	☐ Yes	⊠ N/A	
Registration Statement	☐ Yes	⊠ N/A	

Required documents are kept in a centralized location on the project site (i.e. mail box or another container marked SWPPP). Permits are displayed on site.

2.0 Authorized Non-Stormwater Discharges

Types of Authorized Non-Stormwater Discharges	Likely Prese	ent at Project Sit
 Uncontaminated / filtered excavation dewatering 		\square NA
 Uncontaminated / filtered wash water 	☐ Yes	extstyle ext
Potable water sources that do not create an in-stream impact	☐ Yes	\boxtimes NA
Pumped uncontaminated ground water	☐ Yes	extstyle ext
Landscape irrigation	☐ Yes	extstyle ext
• Other	☐ Yes	\square NA

V-06/2021

V-06/2021

Pre-Storm Site Preparation Checklist

Per Erosion and Sediment Control General Note 6, the Contractor is responsible for the installation and maintenance of any additional erosion and sediment control (ESC) measures necessary to prevent erosion and sedimentation as determined by the County. Controls and measures shall be modified as needed to ensure only clean water is discharged from the site.

The following actions shall be taken <u>prior to storm events with predicted heavy and/or large</u> <u>volume</u> <u>rainfall</u> to prevent sediment discharges from a construction site. A typical summer thunderstorm is an example of a storm event with predicted heavy and/or large volume rainfall.

Perimeter controls

- o Silt fence shall be checked for undermining, holes, or deterioration of the fabric. Fencing shall be replaced immediately if the fabric is damaged or worn. Silt fence must be trenched into the ground per state specifications (Std & Spec 3.09).
- o Wooden stakes or steel posts shall be properly secured upright into the ground. Damaged posts or stakes must be replaced.
- Sediment that has accumulated against the silt fence should be removed. Accumulated sediment must be removed when the level reaches one-half the height of the fencing.
- o Hay bales or a stone berm should be placed across the construction entrance to minimize sediment from leaving the construction site.

Exposed slopes, soil, and stockpiles

- o Exposed slopes not at the final stabilization phase shall be covered with 2" layer of straw, plastic sheeting, or erosion control matting. Cover material shall be properly secured/anchored.
- o Controls shall be installed to prevent concentrated flow down an exposed slope. Berms or diversion dikes shall be installed at the top of cut / exposed slopes to direct storm flow around the disturbed area.
- Exposed slopes at the final stabilization phase shall be stabilized using slope stabilization practices such as soil stabilization blankets or matting as specified in the Virginia Erosion and Sediment Control Handbook (VESCH) Std & Spec 3.36. Blankets or mats must be properly secured and anchored to the slope using staples, pins, or stakes.
- o Recently seeded areas shall be protected by straw, matting, or soil stabilization blankets to prevent seeding from being washed away.
- o Stockpiled soil and other loose materials that can be washed away shall be covered with a tarp, plastic sheeting, or other stabilization matting. The cover must be properly secured / anchored down to prevent it from being blown off and exposing materials to rain. Controls such as hay bales or booms should be placed along the perimeter of the stock pile (downhill side).

3.0 Pollution Prevention Awareness / Subcontractor Information

☐ Employees and subcontractors <u>will</u> be given a "walk through" of the site identifying areas of possible pollution and will be shown Erosion and Sediment Controls and Pollution Prevention Practices identified in the SWPPP that are applicable to their assigned job responsibilities.

Refresher meetings and "walk throughs" for new staff will be conducted on an as needed basis.

ate of walk-through(s):	
)ate of walk-through(s):	

Subcontractor(s) Information	
Name of Subcontractor:	
Type of work conducted on this project / area of responsibility:	
Name of main contact person:	
Phone:	
Email:	

Name of Subcontractor:	
Type of work conducted on this project / area of responsibility:	
Name of main contact person:	
Phone:	
Email:	

Name of Subcontractor:	
Type of work conducted on this	
project / area of responsibility:	
Name of main contact person:	
Phone:	
Email:	

V-06/2021

5.0 Pollution Prevention Practices (PPP)

Pollution prevention practices (PPP) including daily good housekeeping efforts will be employed at the project site to prevent pollution discharges. Equipment, tools and materials needed for cleanup (brooms, shovels, vacuums, trash bags) will be readily available on site.

The following selected ("checked") activities will be conducted during this project and the corresponding pollution prevention controls and practices will be implemented. Specific controls and additional information are included as applicable.

(1) 🖂 Clearing, Grading, Excavating - Sediment Control / Stabilization (PPP1)

- Erosion and sediment controls selected and/or described in Section 4.0 will be installed and maintained to protect resources and prevent sediment from leaving the site/LOD and entering the storm drain system or surface waters.
- Sediment tracking onto paved areas outside the LOD / construction entrances will be
- Plastic sheeting, tarps, 2" deep straw cover, mulch and/or erosion matting will be used for
- temporary stabilization of exposed soil / slopes. • The Pre-Storm Site Preparation Checklist will be followed and implemented.

(2) Saw Cutting and Paving Operations (PPP2)

- Slurry or other debris shall not enter a storm drain or surface water.
- Spill containment techniques such as the use of sand bags or booms around the immediate work area shall be used to contain and capture any non-stormwater
- Slurry from saw cutting operations must be contained, collected (vacuumed), and disposed of properly.

Description of to	emporary o	controls that	t will be use	d:		
•						

(3) Solution Concrete Operations - Washout and Waste Management (PPP3)

Concrete wash out will be conducting in a leak-proof container or leak-proof settling basin that is designed so that no overflows can occur due to inadequate sizing or precipitation. Hardened concrete wastes shall be removed and disposed of in a manner consistent with the handling of other construction wastes.

- Concrete wash water shall not be discharged to a storm drain or surface water.
- Washout facilities will be sized appropriately for the needs of the project.
- Washout facilities will not be located near storm drains.
- Mixers and truck chutes will be washed out in designated contained washout areas No tracking from washout areas will occur.
- Plastic sheeting, boards, or tarps will be placed under concrete truck chutes during pouring Concrete washout areas will not be used for dewatering

The selected concrete wash out facility will be used:	
☐ Washout Structure - Wood Planks	
Machaut Structura Straw Rales	

☐ Washout Structure - Wood Planks	
☐ Washout Structure - Straw Bales	
☐ Prefabricated Containment System – Type:	
☐ Other:	

V-06/2021

C035.1

CLARENDON BLVD. & N CLEVELAND ST P31D

ARLINGTON

VIRGINIA

DEPARTMENT OF

ENVIRONMENTAL SERVICES

FACILITIES & ENGINEERING DIVISION

ENGINEERING BUREAU 2100 CLARENDON BOULEVARD, SUITE 813

> ARLINGTON, VA 22201 PHONE: 703.228.3629

FAX: 703.228.3606

COPYRIGHT © 2021 ARLINGTON COUNTY VIRGINIA - ALL RIGHTS RESERVED

ZORAN DRAGACEVAC

Edward Sanders 2/15/2023

CONSTRUCTION MANAGEMENT SUPERVISOR

WATER, SEWER, STREETS BUREAU CHIEF

0

POLLUTION PLAN

ORMW,

DATE

APPROVALS

Ŋ

EVEL

Z

B

RENDON

DESIGNED: K.PATEL

DRAWN: K. PATEL

PLOTTED: MARCH 6 2023

SCALE:

CHECKED: Z. DRAGACEVAC

Amy Pflaum QUALITY CONTROL ENGINEER

231D\S-8 - CLARENDON BLVD & N CLEVELAND ST\DESIGN\CAD\ACTIVE PLOTTED BY: KPATEL
∵. Д
) BY
Ë
PLO
_
ACT.
AD/
) NE
ESIC
J.T.
ND S
ELA
CLEV
Z
⊗ ⊘
BL
<u>N</u>
REN
CLA
8-9
1D\5
\\P3:
ATA
0:\E
Ë
. PA
DWG
PP.
SWF
)TES_SWPPP.DWG PATH: Q:\DA
N_
S
:20-E_AND_S_NO
.0-E
22

(4) Washing Activities (PPP4)

Wash water discharges to the storm drain system or surface waters are prohibited.

- The following pollution prevention practices and controls will be implemented where applicable: Wash water or liquid wastes shall not enter a storm drain or surface waters.
- A suitable containment system for cleaning equipment such as a drum, prefabricated system,
- lined container, or portable wash pad will be provided. • The wash / containment area will be sized appropriately for the needs of the project.
- The wash / containment area(s) will be situated away from storm drains.

• Containers will be monitored for leaks or damage. Containers will be replaced as needed.

Washout containment / controls for this project will include:

(5) Dewatering Operations (PPP5)

Construction site dewatering will not be discharged without the use of controls. Sediment laden or turbid water associated with dewatering shall be filtered, settled or similarly treated prior to discharge. The dewatering detail on approved ESC plan will be used. Dewatering operations will be monitored to ensure the controls being used are effective (clear water being discharged) and no clogging or overflow is occurring. Controls will be cleaned out or replaced when the control is no longer effective at removing sediment. Pumping will be conducted so that the rate of discharge does not overwhelm the dewatering system and allows for adequate settling and/or filtration.

Dewatering controls that will be used:

- ☐ Filter bag on stone bed with haybales
- ☐ Portable sediment tank
- ☐ Manufactured / customized system

(6) Materials / Chemical Use and Storage (PPP6)

Areas will be designated for material delivery and storage. These areas will be near construction entrances and not situated near storm drains. Lay downs areas will be shown on plans. Storage and containment areas will be adequately enclosed or covered. Additional pollution prevention practices and controls include:

- Stockpiled soil and other loose materials that can be washed away shall be covered with a tarp, plastic sheeting, or other stabilization matting when not being actively accessed. Covers must be properly secured / anchored down to prevent the covering from being blown off and exposing materials to rain. Controls such as hay bales or booms should be placed along the perimeter of stock pile (downhill side).
- Stockpiled materials located on the edge of roadways will not obstruct flow along the curb line (gutter). Adequate space between the curb and stockpile will be left to allow stormwater to flow along the curb line. Pipes or boards laid over curbs may be used to create the flow
- Secondary containment will be used for storage of fuels, oil, grease, paint, solvents, sealers, cleaners, and other chemicals. Materials will be kept secured and covered when not in use.

Designated areas for refueling vehicles or equipment or perform maintenance will be located away from storm drains and surface waters. Additional pollution prevention practices and controls

V-06/2021

V-06/2021

Spill Prevention, Response, and Reporting

Spills and leaks will be cleaned up upon discovery using dry cleaning methods (placement of absorbent materials, sweeping, shoveling, bagging, proper disposal). Spills will not be hosed down unless the wash water is contained, collected and disposed of properly.

Spill kits will be kept on site. The spill kit shall be labeled, stocked, and readily accessible. **Employees** will be informed of the location of the spill kit(s) and how to respond to and report spills.

Spill kits should contain absorbent materials, pads, socks, plastic bags, and personal protective

Location(s) of spill kit(s) on site:

Spill Response and Reporting:

- Check for hazards (flammable material, noxious fumes, cause of spill) if flammable liquid, turn off engines and nearby electrical equipment. <u>If serious hazards are present leave the area and</u>
- Ensure the spill area is safe to enter and does not pose an immediate threat to health and safety
- Stop the spill source.
- Notify personnel in area of spill and potential dangers.
- Ask for assistance to block off area and help with cleanup efforts.

equipment (gloves, eye protection). Shovels/brooms should be accessible.

- Take measures to prevent a spill from spreading and/or entering storm drains (socks, booms,
- Clean up spill using dry methods and dispose of materials in accordance with Safety Data Sheet specification and local, state, and federal regulations.
- Never flush or "hose down" a spill down into a storm drain. If spilled material has entered a storm drain or surface water; call the Fire Department (911)

Emergency Contacts:

- Arlington County Fire & Police
- 911 / 703-558-2222 DES Water, Sewer, Streets 24-Hour Emergency 703-228-6555 Washington Gas Emergency Line 703-750-1400
- VA Dept. of Emergency Management (24 hour) 804-674-2400
- Water or sewer breaks, or overflows will be reported to Arlington County Department of Environmental Services, Water, Sewer, Streets 24-Hour Emergency # 703-228-6555
- Leaking underground storage tanks will be reported to the Virginia Department of Environmental Quality Northern Regional Office, 703-583-3800 and the Arlington County Fire Prevention Office, 703-228-4644

- Vehicles and equipment will be inspected daily for leaks. Any leaks or spills will be addressed
- Containment measures will be used when conducting fueling (e.g. place fuel mats, spill pads,
- boards, or plastic sheeting on ground) to contain drips, leaks, spills.
- Fuel tank (s) will have containment.
- Fuel tanks and containers will be inspected daily for signs of damage.
- Employees will be instructed not to "top off" or overfill vehicles or equipment to prevent spills. Secondary containment and secure storage will be provided for fuel, oil, solvent and/or
- Drip pans, sheeting, and/or absorbent pads will be placed under heavy equipment when not
- in use (i.e. overnight) to capture any potential leaks.

(8) Waste Management (PPP8)

Trash, waste, and construction debris will be managed and disposed of properly. Designated areas for trash and debris collection will be situated as far away from storm drains as possible. Additional pollution prevention practices and controls include:

- A sufficient number of waste containers will be kept on a site to handle the quantity of waste
- Waste collection / pick up will be conducted as necessary to prevent overfilling.
- Containers will have lids or covers that can be used to cover open containers at the end of the work day and prior to rain events. Roll off containers will be kept covered when not being accessed. Lids and doors on dumpsters and/or / trash can will be kept closed.
- Waste containers will be checked frequently for damage / leaks. Any cleaning will be conducting using DRY methods. Waste containers will not be power washed or hosed out
- unless the wash water is collected and disposed of into the sanitary sewer system. Damaged containers / receptacles (leaking, cracked, corroded, or otherwise deteriorating) will be replaced.

(9) Portable Lavatories (PPP9)

Portable lavatory units will be properly situated and maintained to prevent pollution releases. Additional pollution prevention practices and controls include:

- Portable lavatories will be situated away from storm drains and surface waters.
- Portable lavatories will be kept level and have secondary containment (i.e. trays) if situated on paved surfaces.
- Units will be inspected for leaks or damage will be conducted frequently.
- Routine maintenance / cleaning will occur, and units will be replaced if damaged or leaking.

(10) Unitarient Management / Fertilizer Application (PPP10)

Fertilizer will be applied in accordance with manufacturer's recommendations. Fertilizer will not be applied during rainfall events or windy conditions, or when rain is forecasted. Fertilizer will be properly secured and stored under cover when not being used. Residual fertilizer on paved surfaces will be swept up.

V-06/2021

8.0 Self Inspection Report Form

Inspection Schedule: Once every 4 business days (Chesapeake Bay Watershed TMDI requirement)

Project Name:		LDA Permit #	!:
		CGP#:	
Name of Inspector:			
Company/Organization:			
Telephone Number:			
Email Address:			
Inspection Date / Time:		Weather Conditions	:
Phase of construction:			
☐ Initial Clearing & Grading	☐ Building / Construction	☐ Final Grading	☐ Final Stabilization

Permit and SWPPP documentation are on site and available for review: ☐ Yes ☐ No

	on & Sediment Control (ESC)/ tion Prevention Practice (PPP)	In Compliance?	Noncompliance Issue(s) and Corrective Action(s) Needed
PPP	Construction entrances or other	☐ Yes	
1	designated controls are in place to prevent sediment from being tracked off	□ No	
	site / onto paved areas?	□ NA	
PPP	Perimeter controls (silt fence) are	☐ Yes	
1	adequately installed, in good condition, and properly maintained?	□ No	
	and properly manneance.	□ NA	
PPP	Containment controls / methods are	☐ Yes	
1	being used to prevent pollutants from entering storm drains?	□ No	
		□ NA	
PPP	All slopes and disturbed areas, including stockpiles, not actively being worked are properly covered or stabilized?	☐ Yes	
1, 6		□ No	
		□ NA	
PPP	Construction dust is properly controlled?	☐ Yes	
1		□ No	
		□ NA	
PPP	Tree protection and signs are in place	☐ Yes	
1	and the enclosed protected area is free of debris, materials, equipment?	□ No	
		□ NA	
PPP	Non-stormwater discharges (i.e. wash	☐ Yes	
2, 4	water, saw cut slurry) are properly managed and waste is properly disposed	□ No	
	of?	□ NA	
PPP	Washout facilities (concrete, paint) are accessible, labeled, and maintained (not	☐ Yes	
3, 4	leaking or damaged)?	□ No	
		□ NA	

V-06/2021

6.0 Stormwater Management Controls

The stormwater management plan in the approved plan set is part of this SWPPP. The sequence of construction for stormwater management facilities (SWMF) will be followed. Measures will be taken to prevent issues such as soil compaction and/or sediment intrusion / clogging that would compromise the functionality of the approved specified SWMF.

Select all that apply	Stormwater Management Control	Installation Date
	Permeable Pavement / Pavers (1 or 2)	
	Bio-retention (1 or 2)	
	Dry Well	
	Infiltration Trench (1 or 2)	
	Manufactured Device	
	Green Roof (1 or 2)	
	Other approved post construction control:	
\boxtimes	Linear development project per Arlington County Chesapeake Bay Total Maximum Daily Load (TMDL) Action Plan ¹	
	Exempt – linear stormwater management retrofit, stream restoration, underground utility work, routine maintenance projects	

¹ In accordance with Arlington County's Chesapeake Bay Total Maximum Daily Load (TMDL) Action Plan, approved by the Virginia Department of Environmental Quality (DEQ), linear development projects conducted by the County are administered and tracked as follows consistent with 9VAC25-870-69.A.4, 9VAC25-870-76, and 9VAC25-870-92:

- Pollutant load changes will be computed as described in Section 3.A of the Action Plan.
- Retrofit opportunities will be evaluated for each project, using the screening and selection criteria applied and described in the adopted Stormwater Master Plan.
- Retrofit projects that meet the screening criteria and are determined by Arlington to be feasible and cost-effective will be implemented with specific linear development projects. Pollutant load reductions from retrofit projects will be computed as described in Section 5 of the Action Plan.
- In cases where retrofit projects are not feasible and cost-effective for a particular linear project, any POC load increases that might occur for that project will be addressed by larger overall POC load reductions in place or added through TMDL action plan implementation.

In the above manner Arlington, as the MS4 operator and the construction site operator for its linear development projects, implements linear projects and retrofit projects in a manner that achieves the most TMDL POC reduction for the least cost, while fully accounting for load changes that occur with linear development project activity consistent with the DEQ Chesapeake Bay TMDL Special Condition Guidance.

V-06/2021

	on & Sediment Control (ESC)/ tion Prevention Practice (PPP)	In Compliance?	Noncompliance Issue(s) and Corrective Action(s) Needed
PPP 5	Filtering controls for dewatering operations are in place and working properly (only clear water is being discharged off site)?	☐ Yes ☐ No ☐ NA	
PPP 6	Materials that are potential stormwater contaminants are properly stored (covered / secondary containment in place)?	☐ Yes ☐ No ☐ NA	
PPP 7	Vehicle and equipment fueling, maintenance, and/or staging areas are free of spills and leaks? Fuel storage has proper containment?	☐ Yes ☐ No ☐ NA	
PPP 8	Trash and waste materials are properly managed and disposed of?	☐ Yes ☐ No ☐ NA	
PPP 8	Dumpsters and roll off containers are properly covered / contained and not leaking?	☐ Yes ☐ No ☐ NA	
PPP 9	Portable lavatories are level, in good condition, not leaking, and situated away from storm drains?	☐ Yes ☐ No ☐ NA	
PPP 10	Fertilizer is applied in accordance with manufacturer's specifications or an approved nutrient management plan and are not applied during rainfall events or just prior to forecasted storm event.	☐ Yes ☐ No ☐ NA	
Sec. 7.0	Spill kits are stocked and accessible?	☐ Yes ☐ No ☐ NA	

Are there any unauthorized discharges at the time of this inspection? \square Yes \square No If yes, describe the type and location of discharge:

Has any unauthorized discharge occurred since the last inspection? \Box Yes \Box No If yes, describe the type and location of discharge:

Notes / comments:

Certification

I certify that I am qualified to conduct this inspection and the information provided in this report, is, to the best of my knowledge and belief, true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of enforcement actions for knowing violations.

Operator or Assigned Qualified Personnel Name: _____

INSPECTION REPORTS WILL BE KEPT ONSITE IN THE SWPPP BOX OR OTHER APPROVED LOCATION

V-06/2021

9.0 Major Grading & Stabilization Activities Log

Date Activity Initiated	Description of the Grading or Stabilization Activity	Date Grading Activity Ceased	Date Stabilization Measures Initiated	Description of the Stabilization Measure
	Final Stabilization*			

Specifications for final stabilization outlined on the approved plan will be followed. Measures will be aken to ensure soils are not compacted and will support the growth of vegetation (seeding and/o

10.0 SWPPP Modifications Log

Modifications will be made if it is determined that the existing control measures or practices are ineffective in minimizing the discharge or pollutants from the project site.

Modification Date	Description of Modification

V-06/2021

C035.2

ARLINGTON

VIRGINIA

DEPARTMENT OF

ENVIRONMENTAL SERVICES

FACILITIES & ENGINEERING DIVISION

ENGINEERING BUREAU

2100 CLARENDON BOULEVARD, SUITE 813

ARLINGTON, VA 22201

PHONE: 703.228.3629

FAX: 703.228.3606

COPYRIGHT © 2021 ARLINGTON COUNTY

VIRGINIA - ALL RIGHTS RESERVED

ORAN DRAGACEVAC

DATE

APPROVALS

Ċί

DON

REN

DESIGNED: K.PATEL

DRAWN: K. PATEL

PLOTTED: MARCH 6 2023

SCALE:

CHECKED: Z. DRAGACEVAC

RMW

0

Amy Pflaum


QUALITY CONTROL ENGINEER

Edward Sanders 2/15/2023

CONSTRUCTION MANAGEMENT SUPERVISOR

WATER, SEWER, STREETS BUREAU CHIEF

CLARENDON BLVD. & N CLEVELAND ST P31D



ROW ASSESSMENT

 NO ROW ACQUISITION OR PERMANENT EASEMENTS ARE ANTICIPATED WITH THIS PROJECT.

UTILITY IMPACT ASSESSMENT

WET UTILITIES:

- NO STORM SYSTEM IMPROVEMENT IS ANTICIPATED WITH THIS PROJECT.
- WATER METERS AND VALVES VERTICAL ADJUSTMENTS ARE ANTICIPATED WITH THIS PROJECT.
- SANITARY MANHOLE NO POTENTIAL CONFLICT.

DRY UTILITIES:

- NO IMPACTS TO EXISTING UTILITY POLES.
- NO IMPACTS TO EXISTING STREET LIGHT POLES.NO NEW STREET LIGHTS PROPOSED.
- NO IMPACTS TO EXISTING UNDERGROUND FACILITIES.

PERMIT ASSESSMENT

COUNTY LDA PERMIT IS REQUIRED.

PARKING IMPACTS

• NO IMPACT ON EXISTING ON-STREET PARKING SPACE, EXCEPT S/E CORNER.

TREE IMPACTS

• NO TREE REMOVALS ARE ANTICIPATED WITH THIS PROJECT. FURTHER TREE IMPACTS TO BE EVALUATED BY COUNTY URBAN FORESTER.

OTHER IMPACTS

- NO FULL DEPTH PAVEMENT TO BE EXPECTED.
- NO RETAINING WALLS ARE EXPECTED.

CONSTRUCTION NOTES

PROP CURB AND GUTTER (C-2) ARL STD (R-2.0)

PROP HEADER CURB (C-3) ARL STD (R-2.0)

PROP SIDEWALK ARL STD (R-2.0)

 $\frac{1}{1}$ PROVIDE SMOOTH TRANSITION TO MEET EXISTING WALKWAY GRADE.

PROP RAMP (CG-12A) VDOT ROAD & BRIDGE

STANDARDS (204.02) SEE CURB RAMP DETAIL SHEET #

C002.1

PROP RAMP (CG-12B) VDOT ROAD & BRIDGE

2B STANDARDS (204.03) SEE CURB RAMP DETAIL SHEET #C002.1

PROPOSED ASPHALT FULL DEPTH REPLACEMENT AS PER ARLINGTON COUNTY STANDARD (R-1.4)

PROPOSED DETECTABLE WARNING SURFACE DARK
GRAY COLOR PER ARLINGTON COUNTY STANDARD

GRAY COLOR PER ARLINGTON COUNTY STANDARD H-3.2, CURB RAMPS

ASPHALT - MILL AND OVERLAY ($\frac{1}{2}$ "TO 3") PER ARLINGTON COUNTY STANDARD (R-1.4)

 $\sqrt{9}$ MATCH EXISTING T.O.C. OR SIDEWALK GRADE.

10 ADJUST EXISTING UTILITY BOX TO PROPOSED GRADE.

REMOVE EXISTING PARKING METER.

EXISTING PARKING METER TO BE REMAIN.

PROVIDE MULCH PER ARLINGTON STD. & SPEC.

12 SECTION 329100 PLANT PREPARATION.

NO MECHANICAL DIGGING IN CRZ AREA OF TREE, CONTRACTOR TO DO HAND DIGGING AND HAND COMPACTION TO PROTECT ROOT ZONE AREA, AND SHOULD BE MULCHED.

TREE PRESERVATION NOTES:

- 1 CONTRACTOR TO CONTACT THE ARLINGTON FORESTER TO SCHEDULE A PRE-CONSTRUCTION INSPECTION OF THE TREE PROTECTION MEASURES BEFORE ANY WORK NEAR THE CRITICAL ROOT ZONES OF THE TREE. TO SCHEDULE THE PRE-CONSTRUCTION MEETING CALL 703-228-7980
- 2 CONTRACTOR TO PROTECT TREES PER THE PLAN ACCORDING TO THE ARLINGTON COUNTY DPR DESIGN STANDARD DETAIL 02231.1
- CONTRACTOR TO ROOT PRUNE TREE PER THE PLAN ACCORDING TO THE ARLINGTON COUNTY DPR DESIGN STANDARD DETAIL 02231.5,
- WHERE CALL OUT ON THE PLAN NO MECHANICAL DIGGING IN CRZ OF TREE, CONTRACTOR TO DO HAND DIGGING TO PROTECT ROOT ZONE.

ARLINGTON VIRGINIA

DEPARTMENT OF ENVIRONMENTAL SERVICES FACILITIES & ENGINEERING DIVISION ENGINEERING BUREAU

2100 CLARENDON BOULEVARD, SUITE 813 ARLINGTON, VA 22201 PHONE: 703.228.3629 FAX: 703.228.3606

COPYRIGHT © 2021 ARLINGTON COUNTY

VIRGINIA - ALL RIGHTS RESERVED

ZORAN DRAGACEVAC No. 031869

APPROVALS

Amy Pflaum 02/08/23
QUALITY CONTROL ENGINEER

Calvard Sanders 2/15/2023
CONSTRUCTION MANAGEMENT SUPERVISOR

2/2/23
WATER, SEWER, STREETS BUREAU CHIEF

DATE

SPORTATION DIRECTOR

2/27/202
ECT MANAGER

REVISIONS

LVD, & N CLEVELAND ST P31D N OF CLARENDON BLVD. & N CLEVELAND ST

PLAN AND

DESIGNED: K.PATEL
DRAWN: K. PATEL
CHECKED: Z. DRAGACEVAC

PLOTTED: MARCH 6 2023


SCALE:

VERT. SCALE

25

25

HORIZ. SCALE
C041.1



ARLINGTON VIRGINIA

DEPARTMENT OF **ENVIRONMENTAL SERVICES**

ZORAN DRAGACEVAC


Edward Sanders 2/15/2023


DATE

WATER, SEWER, STREETS BUREAU CHIEF

HORIZ. SCALE C042.2


EP: EDGE OF PAVEMENT








ARLINGTON VIRGINIA DEPARTMENT OF **ENVIRONMENTAL SERVICES** FACILITIES & ENGINEERING DIVISION ENGINEERING BUREAU 2100 CLARENDON BOULEVARD, SUITE 813 ARLINGTON, VA 22201 PHONE: 703.228.3629 FAX: 703.228.3606 COPYRIGHT © 2021 ARLINGTON COUNTY VIRGINIA - ALL RIGHTS RESERVED ZORAN DRAGACEVAC APPROVALS DATE Amy Pflaum QUALITY CONTROL ENGINEER Edward Sanders 2/15/2023 CONSTRUCŢION MANAGEMENT SUPERVISOR WATER, SEWER, STREETS BUREAU CHIEF **REVISIONS** CLEVELAND SUDON BLVD. & N CLARENDON BLY INTERSECTION C DESIGNED: K.PATEL CHECKED: Z. DRAGACEVAC PLOTTED: MARCH 7 2023 HORIZ. SCALE


C042.4












ARLINGTON VIRGINIA DEPARTMENT OF **ENVIRONMENTAL SERVICES** FACILITIES & ENGINEERING DIVISION ENGINEERING BUREAU 2100 CLARENDON BOULEVARD, SUITE 813 ARLINGTON, VA 22201 PHONE: 703.228.3629 FAX: 703.228.3606 COPYRIGHT © 2021 ARLINGTON COUNTY VIRGINIA - ALL RIGHTS RESERVED ZORAN DRAGACEVAC DATE Amy Pflaum QUALITY CONTROL ENGINEER Edward Sanders 2/15/2023 CONSTRUCŢION MANAGEMENT SUPERVISOR WATER, SEWER, STREETS BUREAU CHIEF **REVISIONS** DESIGNED: K.PATEL DRAWN: K. PATEL CHECKED: Z. DRAGACEVAC PLOTTED: MARCH 7 2023 VERT. SCALE HORIZ. SCALE C044.2



I	

PROJECT CONTROL DATA

Point No. Northing(Y) Easting(X)

 Northing(Y)
 Easting(X)
 Elev(Z)
 Description

 7009855.8773
 11884103.4349
 230.67
 PIPE & CAP

 7010003.4716
 11884394.2996
 235.17
 P.K. NAIL

 7010219.9158
 11884301.6827
 237.92
 P.K. NAIL

 7010067.7500
 11884019.5121
 236.26
 P.K. NAIL

 7009975.6954
 11883707.2003
 242.36
 P.K. NAIL

	BL-EOP-CR-4											
	Length	Radius	Line/Chord Direction	Station (Start)	Station (End)	Northing, Easting (Start)	Northing, Easting (End)					
C5	8.30	13.50	N79° 26' 24.87"E	0+05.00	0+13.30	7009949.7904, 11884315.6186	7009951.2872 , 11884323.6478					
C6	10.15	16.50	N79° 25' 16.50"E	0+13.30	0+23.45	7009951.2872, 11884323.6478	7009953.1218 , 11884333.4710					
C7	31.22	26.50	N28° 02' 38.34"E	0+23.45	0+54.67	7009953.1218, 11884333.4710	7009979.1099 , 11884347.3147					
C8	10.44	16.50	N23° 49' 35.92"W	0+54.67	0+65.11	7009979.1099, 11884347.3147	7009988.4987 , 11884343.1686					
С9	8.78	13.50	N23° 18' 28.04"W	0+65.11	0+73.89	7009988.4987, 11884343.1686	7009996.4238 , 11884339.7542					
L9	20.00		N61° 49' 56.10"E	-0+20.00	0+00.00	7009937.9890, 11884293.5793	7009947.4300, 11884311.2104					
L10	5.00		N61° 49' 56.10"E	0+00.00	0+05.00	7009947.4300, 11884311.2104	7009949.7904, 11884315.6186					
L11	3.66		N4° 40' 06.93"W	0+73.89	0+77.55	7009996.4238, 11884339.7542	7010000.0731, 11884339.4562					
L12	16.96		N4° 40' 06.93"W	0+77.55	0+94.51	7010000.0731, 11884339.4562	7010016.9765, 11884338.0758					
L13	8.04		N6° 44' 33.53"W	0+94.51	1+02.56	7010016.9765, 11884338.0758	7010024.9647, 11884337.1314					

CLARENDON									
	Length	Radius	Line/Chord Direction	Station (Start)	Station (End)	Northing, Easting (Start)	Northing, Easting (End)		
L14	700.00		N61° 44' 35.11"E	13+00.00	20+00.00	7009750.7758, 11883989.9093	7010082.1740, 11884606.4928		

	CLEVELAND										
	Length	Radius	Line/Chord Direction	Station (Start)	Station (End)	Northing, Easting (Start)	Northing, Easting (End)				
L15	603.23		S6° 27' 45.89"E	0+00.00	6+03.23	7010260.9709, 11884326.1971	7009661.5743, 11884394.0950				


	BL EOP CR-2										
	Length	Radius	Line/Chord Direction	Station (Start)	Station (End)	Northing, Easting (Start)	Northing, Easting (End)				
C1	25.79	21.50	N26° 52' 18.15"E	0+22.92	0+48.72	7009919.4608, 11884381.5555	7009941.1133 , 11884392.5269				
L1	7.54		N61° 14' 21.42"E	0+48.72	0+56.26	7009941.1133, 11884392.5269	7009944.7415, 11884399.1374				
L2	25.00		N61° 14' 21.42"E	0+56.26	0+81.26	7009944.7415, 11884399.1374	7009956.7703, 11884421.0533				
L3	12.82		N7° 29' 45.12"W	-0+12.82	-0+00.00	7009884.0234, 11884386.2183	7009896.7289, 11884384.5465				
L4	22.93		N7° 29' 45.12"W	-0+00.00	0+22.92	7009896.7289, 11884384.5465	7009919.4608, 11884381.5555				

	BL EOP CR-3										
	Length	Radius	Line/Chord Direction	Station (Start)	Station (End)	Northing, Easting (Start)	Northing, Easting (End)				
C2	8.30	13.50	N44° 18' 43.71"E	0+00.66	0+08.96	7009895.9324, 11884307.8134	7009901.7817 , 11884313.524				
C3	10.15	16.50	N44° 18' 43.71"E	0+08.96	0+19.12	7009901.7817, 11884313.5240	7009908.9309 , 11884320.503				
C4	41.82	21.50	S62° 20' 04.06"E	0+19.12	0+60.94	7009908.9309, 11884320.5035	7009892.4318 , 11884351.975				
L5	24.34		N61° 56' 09.22"E	-0+24.34	-0+00.00	7009884.1709, 11884285.7529	7009895.6201, 11884307.2276				
L6	0.66		N61° 56' 09.22"E	-0+00.00	0+00.66	7009895.6201, 11884307.2276	7009895.9324, 11884307.8134				
L7	22.44		S6° 36' 17.35"E	0+60.94	0+83.38	7009892.4318, 11884351.9757	7009870.1410, 11884354.5568				
L8	25.00		S6° 36' 17.35"E	0+83.38	1+08.38	7009870.1410, 11884354.5568	7009845.3069, 11884357.4323				

					BL-EOP-	-CR-4		
	Length Radius Line/Chord Direction		Station (Start)	Station (End)	Northing, Easting (Start)	Northing, Easting (End)		
C5	8.30	13.50	N79° 26' 24.87"E	0+05.00	0+13.30	7009949.7904, 11884315.6186	7009951.2872 , 11884323.6478	
C6	10.15	16.50	N79° 25' 16.50"E	0+13.30	0+23.45	7009951.2872, 11884323.6478	7009953.1218 , 11884333.4710	
C7	31.22	26.50	N28° 02' 38.34"E	0+23.45	0+54.67	7009953.1218, 11884333.4710	7009979.1099 , 11884347.3147	
C8	10.44	16.50	N23° 49' 35.92"W	0+54.67	0+65.11	7009979.1099, 11884347.3147	7009988.4987 , 11884343.1686	
С9	8.78	13.50	N23° 18' 28.04"W	0+65.11	0+73.89	7009988.4987, 11884343.1686	7009996.4238 , 11884339.7542	
L9	20.00		N61° 49' 56.10"E	-0+20.00	0+00.00	7009937.9890, 11884293.5793	7009947.4300, 11884311.2104	
L10	5.00		N61° 49' 56.10"E	0+00.00	0+05.00	7009947.4300, 11884311.2104	7009949.7904, 11884315.6186	
L11	3.66		N4° 40' 06.93"W	0+73.89	0+77.55	7009996.4238, 11884339.7542	7010000.0731, 11884339.4562	
L12	16.96		N4° 40' 06.93"W	0+77.55	0+94.51	7010000.0731, 11884339.4562	7010016.9765, 11884338.0758	
L13	8.04		N6° 44' 33.53"W	0+94.51	1+02.56	7010016.9765, 11884338.0758	7010024.9647, 11884337.1314	

					- -	
0' 06.93"W	0+77.55	0+94.51	7010000.0731, 11884339.4562	7010016.9765, 11884338.0758		<u> </u>
4' 33.53"W	0+94.51	1+02.56	7010016.9765, 11884338.0758	7010024.9647, 11884337.1314	A c	
					CLARENDON BLVD, & N CLEVELANI	LARENDON BLV
		CLAREN	NDON		V. T.	
c/Chord ection	Station (Start)	Station (End)	Northing, Easting (Start)	Northing, Easting (End)	N BL	֧֧֧֧֧֧֧֓֞֝֝֝֝֝֝֓֓֓֝֝֝֓֓֓֓֝֟֝֓֓֓֝֟֝֓֓֓֝֟֝֓֓֓֝֡֝֞֝֓֡֝֝֡֓֝֡֝֡֝֡֡֝֝֡֓֡֝֡֝֡֝֡֝֡֡֡֝֡֡
4' 35.11"E	13+00.00	20+00.00	7009750.7758, 11883989.9093	7010082.1740, 11884606.4928	00	J L
					CLAREN	INTERSECTION OF
		CLEVEL	AND			_
VChord	Station	Station	Northing Fasting	Northing Fasting	DESIGNED: K.I	.PA

DESIGNED: DRAWN: CHECKED:	
PLOTTED: M.	ARCH 7 2023
SCALE	:
0	25



ARLINGTON

VIRGINIA

DEPARTMENT OF **ENVIRONMENTAL SERVICES** FACILITIES & ENGINEERING DIVISION ENGINEERING BUREAU 2100 CLARENDON BOULEVARD, SUITE 813 ARLINGTON, VA 22201 PHONE: 703.228.3629 FAX: 703.228.3606 COPYRIGHT © 2021 ARLINGTON COUNTY VIRGINIA - ALL RIGHTS RESERVED

ZORAN DRAGACEVAC

DATE

APPROVALS

Amy Pflaum QUALITY CONTROL ENGINEER

REVISIONS


Edward Sanders 2/15/2023 CONSTRUCȚION MANAGEMENT SUPERVISOR

WATER, SEWER, STREETS BUREAU CHIEF

C045.1

GEOMETRIC

N. CLEVELAND STREET	
END CONSTRUCTION BL EOP CR-4 STA: 0+77.55 = STA: 2+60.73 O/S 16.19' RT. N. CLEVELAND ST.	19+00
START CONSTRUCTION BLEOP CR.4	END CONSTRUCTION BL EOP CR-2 STA: 0+56.26 = STA: 7+52.29 STA: 0/5 22.89' RT. CLERANDON BLVD.
END CONSTRUCTION BL EOP CR.3 END CONSTRUCTION	P.O.T. 17+21.72 CLARENDON BOULEVARD P.I. 3+12.53 N. CLEVELAND STREET $\Delta = 111^{\circ} 47' 39'' RT.$ START CONSTRUCTION BL EOP $CR-2 STA: 0+00 = STA: 3+68.49 O/S$ $16.98' LT. N. CLEVELAND ST.$
END CONSTRU STA: 0+83.38 5.81' RT. N. 0	



SHARKTEETH DETAIL

Direction of Travel

YIELD MARKINGS DETAIL

FIRE HYDRANT

PARKING METER

SIGN

STRIPING

BIKE SYMBOL DETAIL

(b) Maximum Dimensions

Triangle height is equal to 1.5 times

the base dimension

base [


PROPOSED SIGNING LEGEND

R	HERE			HERE TO
R7-1AL	R1-5R	W11-2	W16-7P	R1-5L
12" x 18"	30"X30"	30" x 30"	24" x 12"	30"X30"

CONSTRUCTION SIGNAGE NOTES

- 2 EXISTING SIGN TO BE REMOVED AND RELOCATE
- WITH NEW POST. 3 PROPOSED NEW SIGN
- ERADICATE AS NECESSARY ANY EXISTING PAVEMENT MARKING

All existing signage to remain unless otherwise noted.



HIGH VISIBILITY CROSSWALK NOT TO SCALE

PAVEMENT MARKING NOTES:

- 1. STREET WIDTH MEASUREMENTS ARE FROM FACE OF CURB TO FACE OF CURB. LANES ARE MEASURED FROM CENTER OF MARKING TO CENTER OF MARKING.
- 2. CONTACT DES-TRANSPORTATION ENGINEERING & OPERATIONS CONSTRUCTION MANAGEMENT SPECIALIST OR HIS DESIGNEE AT 703-228-6598 OR 571-437-1077 TO APPROVE MARKING LAYOUT 48 HOURS PRIOR TO INSTALLATION OF MARKINGS.
- 3. PAVEMENT MARKINGS TO BE IN ACCORDANCE WITH THE FOLLOWING AND ANY **REVISIONS HERE TO:**
- THE MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES. ARLINGTON COUNTY MARKING STANDARDS.
- 4. ALL MARKINGS SHALL BE THERMOPLASTIC PER ARLINGTON COUNTY MARKING
- 5. STOP BARS SHALL BE A MINIMUM OF 4' IN ADVANCE OF A MARKED CROSSWALK. IF THERE IS NO MARKED CROSSWALK, STOP BAR SHALL BE NO MORE THAN 30' FROM THE NEAREST EDGE OF THE INTERSECTED TRAVELED WAY.
- 6. CROSSWALKS SHALL BE 10' WIDE UNLESS OTHERWISE NOTED.
- 7. LEFT TURN ARROWS SHALL BE LOCATED 25' BACK FROM STOP BAR. FOR ADDITIONAL ARROWS FOLLOW COUNTY MARKING STANDARDS.
- 8. ON-STREET PARKING LANE IS 7' WIDE (UNLESS OTHERWISE NOTED) AND MARKED WITH 4" WIDE WHITE LINES. BEGINNING AND END OF PARKING SHALL BE MARKED WITH AN END LINE PERPENDICULAR TO CURB EXCEPT AT NUBS OR WHERE OTHERWISE INDICATED.
- 9. SHARED LANE MARKINGS SHALL BE PLACED IN CENTER OF LANE, 250' APART UNLESS OTHERWISE SPECIFIED.
- 10. BIKE LANE SYMBOLS TO BE PLACED 330' APART UNLESS OTHERWISE SPECIFIED.
- 11. EDGE LINES ARE ONLY REQUIRED WHERE SHOWN ON THE PLANS.
- 12. FOR DETAILS SEE ARLINGTON COUNTY PAVEMENT MARKING SPECIFICATION, DETAILS MK-1 TO MK-12

SIGN NOTES:

YELLOW 4" WIDTH, DOUBLE LINE, 4" SPACING CENTERLINES

WHITE 12" WIDTH, 20' SPACING @45 DEGREE GORE MARKINGS

WHITE 4" WIDTH, DOUBLE LINE, 4' SPACING CURB EXTENSIONS

WHITE SINGLE ARROW

WHITE 8' LETTERS

WHITE 24" WIDTH

Z TYPE B CLASS 1 WHITE YIELD MARKINGS

WHITE COMBINATION ARROW

YELLOW 8" WIDTH @45 DEGREE

WHITE 6" WIDTH, 2' LONG, 10' SPACING

WHITE 6" WIDTH, 2' LONG, 4' SPACING

YELLOW 6" WIDTH, 2' LONG, 4' SPACING

TYPE B CLASS 1

WHITE 6" WIDTH, 10' SPACING @45 DEGREE HATCH LINES, SAFETY ZONES

TURN LANES

TURN LANES

GORE MARKINGS

LANE TRANSITIONS

VDOT - STOP BARS

LANE TRANSITIONS

PAVEMENT MARKINGS

PAVEMENT LETTERS (STOP, YIELD, BUS, ONLY, etc.)

LANE TRANSITIONS, TURN LANE SKIPS

- 1. FOR ALL SIGN POSTS PLACED IN CONCRETE USE 7 GAUGE HEAVY DUTY ANCHOR (30"X2.50") WITH HARDWARE FOR 2" POST. USE $\frac{5}{16}$ " CORNER BOLT WITH FLANGED NUT AND $\frac{3}{8}$ " DRIVER RIVET WITH WASHER.
- 2. CONTACT TE&O CONSTRUCTION MANAGER OR HIS DESIGNEE AT 703-228-6598 OR 571-437-1077 48 HRS PRIOR TO POURING CONCRETE. ALTERNATIVE CONTACT AT 703-228-3788 OR 571-414-7497.

ARLINGTON VIRGINIA

DEPARTMENT OF **ENVIRONMENTAL SERVICES FACILITIES & ENGINEERING DIVISION** ENGINEERING BUREAU 2100 CLARENDON BOULEVARD, SUITE 813

PHONE: 703.228.3629 FAX: 703.228.3606 COPYRIGHT © 2021 ARLINGTON COUNTY

ARLINGTON, VA 22201

VIRGINIA - ALL RIGHTS RESERVED

ZORAN DRAGACEVAC

APPROVALS

Amy Pflaum QUALITY CONTROL ENGINEER Edward Sanders 2/15/2023

DATE

CONSTRUCTION MANAGEMENT SUPERVISO WATER, SEWER, STREETS BUREAU CHIEF

REVISIONS


S \triangle z Z

ARENDON

SIGNAGE

DESIGNED: K.PATEL DRAWN: K. PATEL CHECKED: Z. DRAGACEVAC

PLOTTED: MARCH 7 2023 SCALE:



C101.

		ZONE TABLE	
ZONE#	TTC#	COMMENTS	DURATION
ZONE A	TTC-23.2 TTC-36.2 TTC-16.2	LANE CLOSURE ON A TWO-LANE ROADWAY USING FLAGGERS CROSSWALK CLOSURE AND PEDESTRIAN DETOUR OPERATIONS OUTSIDE LANE CLOSURE OPERATION ON A FOUR LANE ROADWAY	1 WEEK - 1 MONTH
ZONE B	TTC-28.2 TTC-36.2 TTC-16.2	LANE CLOSURE OPERATION IN AN INTERSECTION CROSSWALK CLOSURE AND PEDESTRIAN DETOUR OPERATIONS OUTSIDE LANE CLOSURE OPERATION ON A FOUR LANE ROADWAY	1 WEEK - 1 MONTH
ZONE D	TTC-23.2 TTC-36.2 TTC - 5.2	LANE CLOSURE ON A TWO-LANE ROADWAY USING FLAGGERS CROSSWALK CLOSURE AND PEDESTRIAN DETOUR OPERATIONS SHOULDER OPERATION WITH MINOR ENCROACHMENTS	1 WEEK - 1 MONTH

NOTE: THE DURATIONS SHOWN WERE DEVELOPED FOR PLANNING AND ESTIMATION PURPOSES ONLY. THE DURATIONS IN NO WAY ALTER THE CONTRACT TIME FOR COMPLETION, OR INFRINGES ON THE CONTRACTORS MEANS AND METHODS. THE CONTRACTOR'S SUBMITTED SCHEDULE SUPERSEDES THE ESTIMATED DURATIONS SHOWN.

NOTES:

1. THE FOLLOWING ZONES CAN NOT BE BUILT AT THE SAME TIME:

1: A AND B

2: A AND D

2. ZONE A, B, AND D SHOULD BE FURNISHED WITH (R9-11) SIGN TO ADDRESS THE SIDEWALK CLOSING.

3. WARNING SIGN SPACING: 100'

CHANNELIZATION DEVICES SPACING FOR TRANSITION AREAS = 20'

4. TEMPORARY SIGNS AND BARRICADES SHOULD NOT BE PLACED WHERE THEY WILL OBSTRUCT PEDESTRIAN PASSAGE, EXCEPT WHEN SIGN IS INTENDED TO CLOSE THE SIDEWALK SECTION.

WORKING HOURS:

1. IN ARLINGTON RIGHT-OF-WAY: 9:00 AM TO 4:00 PM (MON.-FRI.) 2. ALL LANES SHALL BE FULLY OPEN TO TRAFFIC OUTSIDE THE ABOVE HOURS UNLESS SPECIFIED

OTHERWISE IN THE MAINTENANCE OF TRAFFIC PLANS.

CONSTRUCTION NOTES


- FOR ALL ARTERIAL STREETS, PORTABLE VARIABLE MESSAGE SIGNS WITH CLOSURE INFORMATION MUST BE INSTALLED AHEAD OF THE PROJECT SITE AT EACH VEHICULAR APPROACH 3 WEEKS PRIOR TO STREET CLOSURE IN LOCATIONS DIRECTED BY THE PROJECT OFFICER.
- CONTRACTOR SHALL REMOVE EXISTING PAVEMENT MARKINGS IN CONFLICT WITH TEMPORARY PAVEMENT MARKINGS.
- CONTACT TRANSPORTATION ENGINEERING OPERATIONS AT 703-228-6598 OR 571-437-1077 AND THE PROJECT OFFICER TO APPROVE MARKING LAYOUT 48 HOURS PRIOR TO INSTALLATION OF MARKINGS.
- ONE LANE CLOSURE IN EACH DIRECTION OF TRAFFIC WILL BE PERMITTED FOR FINAL PAVEMENT OVERLAY.
- 5. DURING CONSTRUCTION, THE CONTRACTOR SHALL MAINTAIN THE FLOW OF TRAFFIC ON ANY INTERSECTION WITHIN THE WORK AREA.
- THE CONTRACTOR SHALL NOTIFY ARLINGTON COUNTY PUBLIC SCHOOLS TWO WEEKS PRIOR TO STARTING CONSTRUCTION.
- 7. THE CONTRACTOR SHALL SUBMIT ANY REQUESTS FOR TEMPORARY "NO PARKING" RESTRICTIONS TO THE PROJECT OFFICER AT LEAST 3 WORKING DAYS PRIOR TO THE DESIRED ONSET OF RESTRICTIONS. PRIOR TO A REQUEST FOR THE REMOVAL OF ACCESS TO ANY ADA PARKING SPACE THE CONTRACTOR MUST HAVE MADE PROVISION FOR ALTERNATIVE ADA PARKING AS INDICATED ON THE APPROVED PLAN OR AS DIRECTED BY THE PROJECT OFFICER
- 8. WHEN THE APPROVED PLAN CALLS FOR THE REMOVAL OF ANY PARKING METER THE CONTRACTOR MUST MAKE A REQUEST TO THE PROJECT OFFICER AT LEAST ONE WEEK IN ADVANCE OF THE DESIRED REMOVAL. THE PROJECT OFFICER WILL THEN COORDINATE THE PARKING METER REMOVAL WITH TRAFFIC ENGINEERING AND OPERATIONS.

MOT NOTES:


- PARKING SHALL BE RESTRICTED BY THE COUNTY AS PART OF THE RIGHT OF WAY PERMIT. CONTACT DES-PERMITTING SECTION, 703-228-4798, AT LEAST 72 HOURS PRIOR TO COMMENCEMENT OF WORK.
- 2. ALL TEMPORARY BUS TRAVEL LANES MUST BE MINIMUM 11' WIDE.
- THE CONTRACTOR SHALL MAINTAIN ADA ACCESSIBLE PARKING SPACES AT ALL TIMES DURING CONSTRUCTION. THE CONTRACTOR SHALL CONTACT DES - PERMITING, 703-228-4798, TO COORDINATE RELOCATION OF EXISTING ADA ACCESSIBLE PARKING SPACES OR TO INSTALL TEMPORARY SIGNAGE OUT OF AND ADJACENT TO THE WORK ZONE AS CONSTRUCTION PROGRESSES. MULTIPLE RELOCATIONS MAY BE NECESSARY DURING EACH

PEDESTRIAN NOTE:

PEDESTRIANS SHALL BE APPROPRIATELY DIRECTED WITH ADVANCED WARNING SIGNS PLACED AT INTERSECTIONS, TO CROSS TO THE OPPOSITE SIDE OF THE ROADWAY IN ORDER TO PREVENT CONFLICT WITH MIDBLOCK WORK SITES.



MAINTENANCE OF TRANSPORTATION PLAN



Commonwealth of Virginia VDDT Virginia Department of Transportation VERIFICATION OF COMPLETION OF VOOT ADVANCED WORK ZONE TRAFFIC CONTROL TRAINING AND FLAGGER CERTIFICATION This is to verify that Kirti Patel has successfully completed training and an examination by the Department on the proper practices and methods for the installation, maintenance, removal of temporary traffic control devices and flagging operations. **Expiration Date:**

Z J Klanj Verification Number: 070722120 State Traffic Engineer

ARLINGTON VIRGINIA DEPARTMENT OF

ENVIRONMENTAL SERVICES FACILITIES & ENGINEERING DIVISION ENGINEERING BUREAU 2100 CLARENDON BOULEVARD, SUITE 813 ARLINGTON, VA 22201 PHONE: 703.228.3629 FAX: 703.228.3606

COPYRIGHT © 2021 ARLINGTON COUNTY

VIRGINIA - ALL RIGHTS RESERVED ZORAN DRAGACEVAC

APPROVALS

Amy Pflaum QUALITY CONTROL ENGINEER Edward Sanders 2/15/2023 CONSTRUCTION MANAGEMENT SUPERVISOR

DATE

WATER, SEWER, STREETS BUREAU CHIEF

REVISIONS


(V)

DESIGNED: K.PATEL DRAWN: K. PATEL CHECKED: Z. DRAGACEVAC


PLOTTED: MARCH 7 2023 SCALE:


GRAPHIC SCALE

C121.



Page 6H-55





Typical Traffic Control Lane Closure on a Two-Lane Roadway Using Flaggers (Figure TTC-23.2) **NOTES**

1. Sign spacing distance should be 350'-500' where the posted speed limit is 45 mph or less, and 500'-800' where the posted speed limit is greater than 45 mph.

2. Care should be exercised when establishing the limits of the work zone to insure maximum possible sight distance in advance of the flagger station and transition, based on the posted speed limit and at least equal to or greater than the values in Table 6H-3. Generally speaking, motorists should have a clear line of sight from the graphic flagger symbol sign to the flagger.

3. To maintain efficient traffic flow in a flagging operation on a two-lane roadway, the maximum time motorists should be stopped at a flagger station is 8 minutes for high volume roadways (average daily traffic of 500 or more vehicles per day) to a maximum of 12 minutes for low volume roadways (less than

4. Portable Temporary Rumle Strips (PTRS) shall be used as noted in Section 6F.99.

5. Flagging stations shall be located far enough in advance of the work space to permit approaching traffic to reduce speed and/or stop before passing the work space and allow sufficient distance for departing traffic in the left lane to return to the right lane before reaching opposing traffic (see Table 6H-3 on Page 6H-5).

6. All flaggers shall be state certified and have their certification card in their possession when performing flagging duties (see Section 6E.01, Qualifications for Flaggers).

7. Cone spacing shall be based on the posted speed and the values in Table 6H-4 on Page 6H-6.

8. A shadow vehicle with at least one high intensity amber rotating, flashing, or oscillating light shall be parked 80'-120' in advance of the first work crew.

8. A SLOW (W21-V10) sign² may be required in this area to give advance warning of the operation ahead by slowing approaching traffic prior to reaching the flagger station or queued traffic.

9. If the queue of traffic reaches the BE PREPARED TO STOP (W3-4) sign then the signs, and if used the

PTRS¹ should be readjusted at greater distances. 10. When a highway-rail crossing exists within or upstream of the transition area and it is anticipated that queues resulting from the lane closure might extend through the highway-rail grade crossing, the temporary traffic control zone should be extended so that the transition area precedes the highway-rail

11. At night, flagger stations shall be illuminated, except in emergencies (see Section 6E.08).

12. Cones may be eliminated when using a pilot vehicle operation or when the total roadway width is 20 feet

13. For low-volume situations with short work zones on straight roadways where the flagger is visible to road users approaching from both directions, a single flagger, positioned to be visible to road users approaching from both directions, may be used (see Chapter 6E).

Standard:

14. When used², three portable temporary rumble (PTRS) strips shall be installed across the entire travel lane adjacent to the BE PREPARED TO STOP (W3-4) sign. The portable temporary rumble strips shall be monitored and adjusted as necessary during the work shift to ensure proper placement on the roadway. When the PTRS are installed, the RUMBLE STRIPS AHEAD (W20-V26) sign shall also be utilized.

1: Revision 1 – 4/1/2015 2: Revision 2 – 9/1/2019 Page 6H-80

September 2019

September 2019

Crosswalk Closure and Pedestrian Detour Operation (Figure TTC-36.2)

Typical Traffic Control

NOTES

Standard:

1. When crosswalks or other pedestrian facilities are closed or relocated, temporary facilities shall be detectable and shall include accessibility features consistent with the features present in the existing

2. Curb parking shall be prohibited for at least 50 feet in advance of the midblock crosswalk.

Guidance:

3. Audible information devices should be considered where midblock closings and changed crosswalk areas

cause inadequate communication to be provided to pedestrians who have visual disabilities. 4. Pedestrian traffic signal displays controlling closed crosswalks should be covered or deactivated.

5. Temporary markings should be considered for operations exceeding three days in duration. Option:

6. Only the TTC devices related to pedestrians are shown. Other devices, such as lane closure signing or ROAD NARROWS (W5-1) signs, may be used to control vehicular traffic.

7. For nighttime closures, Type A Flashing warning lights may be used on barricades supporting signs and closing sidewalks.

Standard:

8. In order to maintain the systematic use of the fluorescent yellow-green background for school warning signs in a jurisdiction, the fluorescent yellow-green background for school warning signs shall be used in TTC zones.2

9. All sidewalk closures shall be closed with Type 3 Barricades. The SIDEWALK CLOSED (R9-9) sign and the SIDEWALK CROSS HERE (R9-11) sign shall be installed above the Type 3 Barricade. The KEEP RIGHT sign can cover the top rail of the Type 3 Barricade.2

10. Refer to Sections 3B-16 through 3B-18 of the 2009 MUTCD and the Virginia Supplement to the MUTCD¹ for crosswalk¹ lines, yield lines and other related TTC devices that may be used to control vehicular traffic at midblock crosswalks.

Standard:2

1: Revision 1 - 4/1/2015

2: Revision 2 – 9/1/2019

11. The YIELD HERE TO PEDESTRIANS (R1-5) sign shall be placed at the Yield Line.

12. Fluorescent yellow-green PEDESTRIAN TRAFFIC (W11-2) symbol sign, AHEAD (W16-9p) plaque and ARROW (W16-7p) plaque shall be used to identify the work zone crosswalk.

Page 6H-64

Typical Traffic Control Lane Closure Operation in an Intersection (Figure TTC-28.2)

NOTES

Guidance:

1. The control of traffic through the intersection in order of preference should be:

a. Obtain the services of law enforcement personnel.

b. Detour the effective routes to other roads and streets as approved and directed by the District Traffic

September 2019

c. Place a state certified flagger on each leg of the intersection controlling a single lane of traffic. Appropriate signing as shown should be used for law enforcement and flagging operations. For detour

signs see Figure TTC-34. 2. Sign spacing distance should be 350'-500' where the posted speed limit is 45 mph or less, 500'-800' where the posted speed limit is greater than 45 mph.

3. To maintain efficient traffic flow in a flagging operation on a two-lane roadway the maximum time motorist should be stopped at a flagger station is 8 minutes for high volume roadways (average daily traffic of 500 or more vehicles per day) to a maximum of 12 minutes for low volume roadways (less than

500 vehicles per day). For additional information see Section 6E.07.2 Standard:

4. Channelizing device spacing shall be on 20' centers or less.

5. PTRS shall be used as noted in Section 6F.99.

Guidance:

6. If room permits, a shadow vehicle with at least one rotating amber light or high intensity amber flashing or oscilllating¹ light should be parked 80'-120' in advance of the first work crew. Standard:

7. For emergency situations (any non-planned operation) of 30 minutes or less duration, two rotating amber lights or high intensity amber flashing or oscillating¹ lights mounted on the vehicle and visible for 360° shall be required in addition to the channelizing devices shown around the vehicle. Also, vehicle hazard warning signals shall be used.

Guidance:

8. If the work space extends across a crosswalk, the crosswalk should be closed using the information and devices shown in Figure TTC-36.

Support:

9. Turns can be prohibited as required by vehicular traffic conditions. Unless the streets are wide, it might be physically impossible to make certain turns, especially for large vehicles.

1: Revision 1 – 4/1/2015 2: Revision 2 – 9/1/2019

ARLINGTON VIRGINIA DEPARTMENT OF ENVIRONMENTAL SERVICES **FACILITIES & ENGINEERING DIVISION ENGINEERING BUREAU** 2100 CLARENDON BOULEVARD, SUITE 813 ARLINGTON, VA 22201 PHONE: 703.228.3629 FAX: 703.228.3606 COPYRIGHT © 2021 ARLINGTON COUNT VIRGINIA - ALL RIGHTS RESERVED ZORAN DRAGACEVAC **APPROVALS** Amy Pflaum QUALITY CONTROL ENGINEER dward Sanders 2/15/202 CONSTRUCTION MANAGEMENT SUPERVISO WATER, SEWER, STREETS BUREAU CHIEF **REVISIONS** Ŋ EVEL Z -VD, & P31D OF CLAR B ARENDON DESIGNED: K.PATEL DRAWN: K. PATEL

DATE

 ∞

MAINTENAN

AS SHOWN

C122.1

CHECKED: Z. DRAGACEVAC

PLOTTED: MARCH 7 2023

SCALE:

Page 6H-17

September 2019

Outside Lane Closure Operation on a Four-Lane Roadway (Figure TTC-16.2) PTRS SPACING (CENTER TO CENTER)
POSTED/STATUTORY SPEED LIMIT 15 FEET 41 - 55 MPH 20 FEET > 55 MPH SHADOW VEHICLE REQUIRED (TMA REQUIREMENT SEE NOTE 10) ILLUMINATED FLASHING (AMBER CAUTION MODE TYPE B OR C SUPPLEMENTAL PTRS OPTIONAL SEE NOTE 14 SEE NOTE 2 ILLUMINATED FLASHING ARRÓW BÓARD SEE NOTES 4 & 8 SEE NOTE 2 R4-V7L KEEP PTRS OPTIONAL SEE SEE NOTE 13 NOTE 2 W20-V28L REQUIRED WITH PTRS REQUIRED PCMS - SEE NOTE 3 2: Revision 2 – 9/1/2019

Page 6H-41

September 2019

Page 6H-16

1: Revision 1 – 4/1/2015 2: Revision 2 – 9/1/2019

September 2019

Typical Traffic Control

Shoulder Operation with Minor Encroachment (Figure TTC-5.2)

NOTES

1. For required sign assemblies for multi-lane roadways see Note 1, TTC-4.1

- 2. Sign spacing should be 1300'-1500' for Limited Access highways. For all other roadways, the sign spacing should be 500'-800' where the posted speed limit is greater than 45 mph, and 350'-500' where
- the posted speed limit is 45 mph or less. 3. When work takes up part of a lane on a high volume roadway; vehicular traffic volumes, vehicle mix, speed and capacity should be analyzed to determine whether the affected lane should be closed. Unless the lane encroachment analysis permits a remaining lane width of 10 feet, the lane should be closed. If the closure operation is on a Limited Access highway, the minimum lane width is 11 feet.

Option:

- 4. The ROAD WORK AHEAD (W20-1) sign on an intersecting roadway may be omitted where drivers emerging from that roadway will encounter another advance warning sign prior to this activity area.
- 5. A shadow vehicle with either an arrow board operating in the caution mode, or at least one highintensity amber rotating, flashing, or oscillating light shall be parked 80' - 120' in advance of the
- 6. Vehicle hazard warning signals shall not be used instead of the vehicle's high-intensity amber rotating, flashing, or oscillating lights. Vehicle hazard warning signals can be used to supplement high-intensity amber rotating, flashing, or oscillating lights. 7. Taper length (L) and channelizing device spacing shall be at the following:

					Taper	Len	gth L					
Speed	L	ane Wic	dth (Fee	t)			Speed	Li	ane Wid	lth (Feet	t)	
Limit (mph)	9	10	11	12	Remarks		Limit (mph)	9	10	11	12	Remarks
25	95	105	115	125	L=S ² W/60		50	450	500	550	600	L=SW
30	135	150	165	180	L=S2W/60		55	495	550	605	660	L= SW
35	185	205	225	245	L=S ² W/60		60	540	600	660	720	L=SW
40	240	270	295	320	L=S ² W/60		65	585	650	715	780	L=SW
45	405	450	495	540	L=SW		70	630	700	770	840	L=SW
Limited	Access	highwa	ys shal	l use a 1	1000' mergin	g tap	er regard	lless of	the pos	ted spe	ed, a 75	0' shifting
	taper fo	r posted	speeds	s < 65 m	ph and a 10	00' s	hifting tap	per for p	osted s	peeds 2	≥ 65 mp	h.²
				5	Shoulder Tape	er = 1	∕₃ L Minim	um				

8. Channelizing device spacing shall be at the following:

Channelizing Device Spacing											
Location		l Limit ph)	Location	Speed (mp		Location Spacing	Speed Limit (mph)				
Spacing	0 -35	36 +	Spacing	0 -35	36 +		0 -35	36 +			
Transition	20'	40'	Travelway	40'	80'	*Construction Access	80'	120'			

- 9. On roadways with paved shoulders having a width of 8 feet or more, channelizing devices shall be used to close the shoulder in advance of the merging taper to direct vehicular traffic to remain within the traveled way.²
- 10. The buffer space length The buffer space length shall be as shown in Table 6H-3 on Page 6H-5 for the posted speed limit.
- 11. A truck-mounted attenuator (TMA) shall be used on Limited Access highways and multi-lane
- roadways with posted speed limit equal to or greater than 45 mph. 12. When a side road intersects the highway within the temporary traffic control zone, additional traffic
- control devices shall be placed as needed.

1: Revision 1 – 4/1/2015 2: Revision 2 – 9/1/2019 Page 6H-40

September 2019

Typical Traffic Control

Outside Lane Closure Operation on a Four-Lane Roadway (Figure TTC-16.2)

NOTES

1. On divided highways having a median wider than 8', right and left sign assemblies shall be

- 2. Sign spacing should be 1300'-1500' for Limited Access highways. For all other roadways, the sign spacing should be 500'-800' where the posted speed limit is greater than 45 mph, and 350'-500' where the posted speed limit is 45 mph or less.
- 3. When closing a lane, a PCMS should be used in advance of the first warning sign if all of the left side
- signs cannot be installed.² 4. Care should be exercised when establishing the limits of the work zone to insure maximum possible sight distance in advance of the transition, based on the posted speed limit and at least equal to or greater than the values in Table 6H-3. For Limited Access highways a minimum of 1000' is desired.
- 5. All vehicles, equipment, workers, and their activities should be restricted to one side of the pavement. Standard:

6. Taper length (L) and channelizing device spacing shall be at the following:

					Taper	Len	gth L					
Speed	L	ane Wid	th (Fee	t)			Speed	La	Lane Width (Feet)			
Limit (mph)	9	10	11	12	Remarks		Limit (mph)	9	10	11	12	Remarks
25	95	105	115	125	L=S2W/60		50	450	500	550	600	L=SW
30	135	150	165	180	L=S2W/60		55	495	550	605	660	L= SW
35	185	205	225	245	L=S ² W/60		60	540	600	660	720	L=SW
40	240	270	295	320	L=S ² W/60		65	585	650	715	780	L=SW
45	405	450	495	540	L=SW		70	630	700	770	840	L=SW
	Limited	Access	highwa	ys shall	use a 1000'	merg	ging tape	r regard	ess of t	he pos	ted spe	ed.
	Shiftin	g Taper	s see Ta	able 6H-	·2. ²			Shoulde	r Taper	= 1/3 L N	/linimun	n

7. Channelizing device spacing shall be at the following:

	0	•							
				Channelizin	ng Device Spa	acing			
Location		Speed Limit (mph)		Location Spacing	Speed L (mph)	.imit	Location Spacing	Speed Limit (mph)	
Spacing		0 -35	36 +	Spacing	0 -35	36 +		0 -35	36 +
Transition	sition 20' 40' Travelway		40'	80'	* Construction Access	80'	120'		

*Construction access spacing may be increased to this distance, but shall not exceed one access per ¼ mile.

- 8. An arrow board shall be used when a lane is closed. When more than one lane is closed, a separate arrow board shall be used for each closed lane (see Figure TTC-18).
- 9. The buffer space length shall be shown in Table 6H-3 on Page 6H-5 for the posted speed limit. 10. A shadow vehicle with either a Type B or C arrow board operating in the caution mode, or at least one high intensity amber rotating, flashing, or oscillating light shall be parked 80'-120' in advance of the first work crew. When the posted speed limit is 45 mph or greater, a truck-
- mounted attenuator shall be used. 11. Vehicle hazard warning signals shall not be used instead of the vehicle's high-intensity amber rotating, flashing, or oscillating lights but can be used to supplement the amber rotating, flashing,
- 12. When a side road intersects the highway within the TTC zone, additional TTC devices shall be


placed as needed.

13. PTRS and their supporting signs may be used, see Sections 6F.99 and 6G.25. Long-term transverse rumble strips may be used in long-term situations, see Section 6F.99 and TTC-20.2 14. The supplemental PTRS may be eliminated.²

1: Revision 1 – 4/1/2015 2: Revision 2 – 9/1/2019 **ARLINGTON VIRGINIA** DEPARTMENT OF

ENVIRONMENTAL SERVICES FACILITIES & ENGINEERING DIVISION ENGINEERING BUREAU 2100 CLARENDON BOULEVARD, SUITE 813 ARLINGTON, VA 22201 PHONE: 703.228.3629 FAX: 703.228.3606

COPYRIGHT © 2021 ARLINGTON COUNTY VIRGINIA - ALL RIGHTS RESERVED



APPROVALS

Amy Pflaum QUALITY CONTROL ENGINEER Edward Sanders 2/15/2023 CONSTRUCTION MANAGEMENT SUPERVISOR

DATE

WATER, SEWER, STREETS BUREAU CHIEF

REVISIONS

 ∞ Ŋ **EVELANI** Z BLVD. & P31D ON OF CLAR ARENDON MAINTENAN

DESIGNED: K.PATEL DRAWN: K. PATEL CHECKED: Z. DRAGACEVAC

PLOTTED: MARCH 7 2023

SCALE:

AS SHOWN

C122.2