

OJAI UNIFIED SCHOOL DISTRICT

BID ADDENDUM NO. 1 ISSUED 5/24/2019

TO THE CONTRACT DOCUMENTS, SPECIFICATIONS AND PLANS FOR OJAI UNIFIED SCHOOL DISTRICT

REROOFING PROJECT AT SAN ANTONIO ELEMENTARY PROJECT NO. 2019-1308

THE BIDDER SHALL ATTACH THE ADDENDUM TO THE DOCUMENTS SUBMITTED WITH THE BID TO OJAI UNIFIED SCHOOL DISTRICT TO CERTIFY THAT THE BID ADDENDUM INFORMATION WAS RECEIVED.

BID DUE DATE: May 29

The following additions, modifications, corrections, deletions and clarifications are hereby made to the Contract Documents of the subject Project and constitute **Addendum Number 1**. This Addendum is hereby incorporated into the contract documents by reference.

I. GENERAL INFORMATION

A. Contract Documents

No Change.


II. REVISED SPECIFICATIONS AND DRAWINGS

A. Specifications

No Change

SAN ANTONIO REROOFING PROJECT
PROJECT NO. 2019-1308

ADDENDUM NO. 1



B. Drawings

No Change.

END OF **BID ADDENDUM NO. 1** ISSUED 5/24/2019

III. RESPONSES TO REQUESTS FOR INFORMATION

No.	QUESTION	RESPONSE	RESPONSE BY
1	Are the existing gutters and gutter support brackets to remain?	Yes, the gutters and brackets are to remain. Contractor to reinforce fastening of existing gutter brackets to existing wood substrates only.	RNT
2	At the walk, we found extensive damage, likely from woodpeckers on the ornamental vergeboards and finials. Will repairing or replacing these wood ornaments be in the project scope?	Contractor to replace vergeboards and finials with new hardwood. District will provide finials for contractor to install.	RNT
3	If the District is wanting a traditional look, will we be reinstalling the edge flashing?	Contractor to install edge flashing per plans.	RNT
4	Is the existing standing seam metal roofing to remain?	Unless it is discovered to be compromised, yes, it is to remain and be protected in place.	RNT