

21-29 ASPHALT PAVING SPECIFICATIONS

Jones County School System seeks to enter into a contract for FY21 for a company to provide asphalt paving. The focus of this eRFP will be on Jones County High School football field project since it has an immediate need. Proposed pricing for this project shall be in effect for the term of the contract, which will expire on 6/30/2021 for additional projects that the system chooses to add.

Minimum requirements:

- Contractor and all sub-contractors must be pre-qualified through the Georgia Department of Transportation

Scope for the JCHS Heavy Duty Paving :

Jones County School System will be utilizing a county cooperative agreement to provide pre-site work however it is the responsibility of the contractor to ensure the minimum conditions exist prior to work:

- ✓ Earth is compacted to 95% Standard Proctor and proof rolled.
- ✓ 8 inches of graded aggregate compacted to 95% Standard Proctor

Once the contractor has ensured minimum conditions exist, Contractor will:

- 2 ½ inches of Type 19 mm Super pave asphalt binder
- 1 ½ inches of Type 9.5 Super pave Type 2 asphalt surface course

For this project, it is the responsibility of the contractor to ensure and forecast any and all cost associated to complete this project. See Map-JCHS ASPHALT PAVING, for specifications regarding area to be paved. The red marked area will be paved, the site should be prepped however it is the responsibility of the contractor to verify the condition of the area prior to beginning the project. No personal tours of the space will be conducted, contract can visit the site on their own to obtain any measurements or information needed to complete the project.

Start date for this project has not been determined yet.

Contractor will:

- Remove existing asphalt and unusable dirt/gravel to include hauling off site.
- Upon arrival at the site, contractor will check-in with the designated contact person on-site and evaluate the specific materials and labor required to perform the service.
- Contractor shall provide work only after authorized by JCSS Maintenance Director on any future projects, a written quote with scope of work will be required prior to any work and completed according to the approved cost estimate.
- Complete work during normal business hours which are Monday through Friday, excluding JCSS holidays, 7:00 am to 4:00 pm. Work outside of this schedule should be preauthorized by the Maintenance Director.