

Bid Form Proposal
City of LaGrange
LaGrange Bicycle Playground

LaGrange THREAD - Kid's Bicycle Playground Bid Form Proposal					
DATE	Update 8/17/2023				
SECTION A: TRAIL AND ROADWAY					
Item Number	Quantity	Units	Item Description	Unit Price	Cost
GENERAL					
140-1000	1	LS	MOBILIZATION		
150-1000	1	LS	TRAFFIC CONTROL		
210-0100	1	LS	GRADING COMPLETE (INCLUDING DEMOLITION & TREE REMOVAL)		
TRAIL AND ROADWAY CONSTRUCTION					
441-5001	65	LF	CONC HEADER CURB, 6IN TP2, (Labor, Form, Finish Only)		
402-3910	5	TN	RECY. ASPH. CONC. 12.5MM SUPERPAVE GP2 ONLY, INCL BITUM, MTL, & H LIME, PER PAVEMENT OVER GUTTER DETAIL. DEPTH VARIES		
432-0200	47	SY	MILL EXIST. ASPH. SURFACE PER PAVEMENT OVER GUTTER DETAIL. MILL DEPTH VARIES		
441-0105	1400	SY	CONCRETE TRAIL, 5IN, 3000 PSI, MED BROOM FINISH, INCL ADA RAMP, BENCH & BIKE PADS (Labor, Form, Finish Only)		
441-6012	72	LF	CONC. CURB & GUTTER, 6IN X 24IN TP2 (Labor, Form, Finish Only)		
444-1000	1400	LF	SAWED JOINTS IN CONCRETE TRAIL & SIDEWALK PAVEMENTS @ 10' O.C.		
444-1001	160	LF	SAWED JOINTS IN CONCRETE TRAIL (SCORED CONC. PAVEMENT)		
500-3101	6	CY	CLASS A CONC STAIRS INCL. REINF & CONC (10FT WIDE)		
500-3102	25	SY	CLASS A CONCRETE, SPEED HUMP, PER PLANS, (Labor, Form, Finish Only)		
900-0039	200	SF	BRICK PAVERS: PINE HALL, MIXED COLOR PER PLANS (CITY APPROVAL), 4IN X 8IN		
999-5200	48	SF	BRICK PAVERS: PAVESTONE, RED ADA 4IN X 8IN		
TREE PROTECTION					
222-1002	380	SY	#57 STONE (CLEAN), 6 IN, (ROOT BRIDGING AREAS)		
603-7000	380	SY	PLASTIC FILTER FABRIC (ROOT BRIDGING AREAS)		
643-8200	600	LF	BARRIER TREE FENCE (ORANGE), 4 FT		
SIGNAGE					
636-1036	28	SF	HIGHWAY SIGNS TP1 MATL., REFL. SHEETING TP1		
636-1042		LS	THREAD TRAIL SQUARE MATL 0.125 ALUM, DIRECT PRINT & THREAD TRAIL SQUARE POST		not in contract- city responsibility
636-2070	56	LF	GALV STEEL POSTS TP7		
STRIPING & MARKINGS					
652-0091	18	SF	MMA PAVEMENT MARKING, WHITE, YIELD SYMBOL		
652-5301	215	LF	THERMO SOLID TRAF STRIPE, 8 IN, WHITE (GDOT CROSSWALK)		
652-6501	920	LF	MMA SKIP TRAF STRIPE, 4 IN, YELLOW (TRAIL CL)		
652-6502	144	LF	MMA SOLID TRAF STRIPE, 12 IN, WHITE (TRAIL STOP BAR)		
652-6503	12	EA	MMA PVMNT MARKING 'STOP' WHITE, PER TRAIL DETAIL		
653-0110	6	EA	MMA ARROW MARKING, TP 1		
653-0120	1	EA	MMA ARROW MARKING, TP 3		
653-0150	1	EA	MMA ARROW MARKING, TP 5		
653-1804	272	LF	MMA SOLID TRAF STRIPE, 8 IN, WHITE (CROSSWALK)		
653-1501	20	LF	MMA SOLID TRAF STRIPE, 4 IN, WHITE		
653-1502	136	LF	MMA SOLID TRAF STRIPE, 4 IN, YELLOW		
653-1503	38	LF	MMA SKIP TRAF STRIPE, 4 IN, WHITE		
653-1504	80	LF	MMA SOLID STRIPE, 4 IN TO 8 IN, CITY APPROVED COLOR, PER PLANS (SPEED TABLE & RAILROAD CROSSING DETAILS)		
SITE FURNISHINGS					
643-8400	560	LF	2 PANEL WOOD FENCE (INC. POSTS, RAILS, & ATTACHMENTS)		
900-0527	3	EA	REMOVABLE STEEL BOLLARDS, INCL ALL ATTACHMENTS		
900-0528		EA	BENCH		not in contract- city responsibility
900-0529		EA	TRASH RECEPTACLE		not in contract- city responsibility
900-0533		EA	BIKE RACK		not in contract- city responsibility
				Section A Subtotal	\$0.00
SECTION B: STRUCTURAL ITEMS					
Item Number	Quantity	Units	Item Description	Unit Price	Cost
500-3101	5	CY	CONCRETE STRUCTURAL SLAB, (10 FT) INCL. REINFORCING (Designed by Structural Engineer)		
515-1000	40	LF	METAL POST CABLE RAIL, AT STRUCTURAL SLAB (Designed by Structural Engineer)		
516-0001	25	LF	TUBULAR METAL POST & HANDRAIL, POWDER COATED BLACK, PER STAIR DETAIL		
				Section B Subtotal	\$0.00
SECTION C: EROSION CONTROL/STORM DRAINAGE					
Item Number	Quantity	Units	Item Description	Unit Price	Cost
EROSION CONTROL					
163-0300	1	EA	CONSTRUCTION EXIT		
163-0301	12	MO	EROSION CONTROL INSPECTIONS, WEEKLY AND MONTHLY		
163-0402	1	LS	TEMPORARY CONC. WASHDOWN		
163-0528	740	LF	CONSTRUCT AND REMOVE TEMPORARY SEDIMENT BARRIER, TYPE NS		
163-0550	2	EA	CONSTRUCT AND REMOVE INLET SEDIMENT TRAP, TYPE F		
165-0030	740	LF	MAINTENANCE OF EROSION CONTROL FENCE		
165-0101	1	EA	MAINTENANCE OF CONSTRUCTION EXIT		
165-0105	2	EA	MAINTENANCE OF INLET SEDIMENT TRAP		
167-1000	12	MO	WATER QUALITY MONITORING AND SAMPLING		
700-6910	1	AC	PERMANENT GRASSING		
700-8000	1	AC	FERTILIZER MIX GRADE		

DRAINAGE				
668-2100	1	EA	GRATE INLET (6500 GRATE)	
550-1180	92	LF	STORM DRAIN PIPE, 18 IN, HDPE, H 1-10	
603-1300	35	SY	GDOT TYPE 3 EQUIVALENT RIVER ROCK (12 IN. THICK)	
603-2997	35	SY	FILTER BLANKET	
Section C Subtotal				\$0.00

SECTION D: LANDSCAPE AND PARK AMENITIES					
Item Number	Quantity	Units	Item Description	Unit Price	Cost
700-9900		LS	LANDSCAPE (TREES, PLANTS, + 1 YR MAINT)		not in contract- city responsibility
900-0001	1	LS	ALUM. BIKE CHANNEL, INCL ALL MOUNTING & HARDWARE, & DIRECT PRINT GRAPHIC (CITY APPROVED), PER PLANS		
900-0002	1	LS	CUSTOM METAL FABRICATED RAILROAD TRACK STRUCTURE, INCL. ALL METAL & WOOD MEMBERS, FASTENERS & ATTACHMENTS, BALLAST & EDGE RESTRAINT, BASIS OF DESIGN PER PLANS (Designed by Architect)		
900-0003	1	LS	CUSTOM METAL FABRICATED TUNNEL STRUCTURE, BASIS OF DESIGN PER PLANS (Designed by Structural Engineer)		
Section D Subtotal				\$0.00	

SECTION E: CONTINGENCY					
Item Number	Quantity	Units	Item Description	Unit Price	Cost
999-1000	1	ALLOW	CONSTRUCTION CONTINGENCY 10%	\$0.00	\$0.00
Section E Subtotal				\$0.00	

SECTION A SUB TOTAL: ROADWAY AND TRAIL				\$0.00
SECTION B SUBTOTAL: STRUCTURAL ITEMS				\$0.00
SECTION C SUB TOTAL:EROSION CONTROL/STORM DRAINAGE				\$0.00
SECTION D SUB TOTAL: LANDSCAPE AND PARK AMENITIES				\$0.00
SECTION E: CONTINGENCY				\$0.00
TOTAL:				\$0.00

LS	LUMP SUM
SY	SQUARE YARD
CY	CUBIC YARD
LF	LINEAR FOOT
EA	EACH
ALLOW	ALLOWANCE
SF	SQUARE FOOT
GLF	GALLON PER LINEAR FOOT
GAL	GALLON
TN	TON
AC	ACRE
LB	POUND