

Scope of Work

Nordhoff High School

Athletic Court Resurfacing Project # 2020-1728

Gym Front:

1. Pulverize & remove all asphalt in Area A.
2. Cut and remove intruding surface roots to a depth of 12 inches as needed.
3. Fine grade and recompact the existing subgrade to a minimum depth of 6 inches.
4. Install new concrete ribbon gutter from gym entry, heading west, and tying into exiting ribbon gutter. (Area B)
5. Install new 10'x10' concrete landing into women's restroom. (Area C)
6. Apply tack oil to the vertical surfaces of the existing pavement.
7. Install 3 inches (after compaction) of hot mix asphalt pavement.
8. Re-stripe the asphalt surface per the existing layout using 1 coat of traffic paint.
9. Re-install basketball poles in existing locations to regulations height.