

**Village of Palmetto Bay  
Thalatta Park Pier  
Proposal Form  
RFP# 1920-12-002**

Item No.	Item	Quantity	Unit	Unit Cost	Cost
1	General Conditions including mobilization, bonds, insurance, etc.	1	LS		\$ -
2	Demolition (including old boat ramp), clearing and grubbing, earthwork, fill.	1	LS		\$ -
3	Environmental controls, dust control, mangrove and tree protection, permit compliance, turbidity barrier.	1	LS		\$ -
4	12" Square Precast Concrete Piles	43	EA		\$ -
5	Pile Cap Complete	25	CY		\$ -
6	Precast Concrete Deck (Overlook area, 6" and 8" thick)	690	SF		\$ -
7	Precast Concrete Deck (6' Wide, 6" thick)	740	SF		\$ -
8	42" High Precast Concrete Balustrades	400	LF		\$ -
9	6' Wide Approach Slab	1	EA		\$ -
10	6' Wide Paved Area including concrete edge base, compaction, sand, etc.	360	SF		\$ -
11	Rip-rap	74	CY		\$ -
12	Filter fabric	1760	SF		\$ -
13	Sod	1	LS		\$ -
14	Solar Lights	30	EA		\$ -
15	Navigation Lights Incl. All Ancillary Materials to Service Connection	4	EA		\$ -
16	No Fishing Sign (F&I)	2	EA		\$ -
17	Owner Allowance (Do not Bid)	1	LS	\$ 40,000.00	\$ 40,000.00
				<b>TOTAL:</b>	