



PROJECT MANUAL

The City of Orange Beach FIRE DEPARTMENT ADMINISTRATION BUILDING and POST OFFICE ROOF REPLACEMENTS

25778 JOHN M. SNOOK DR., ORANGE BEACH, AL 36561

February 21, 2022

City of Orange Beach
Public Works Department
23908 Canal Rd, Orange Beach, AL 36561
(251) 923-5858

And

Watermark Design Group, LLC



watermark
DESIGN



thompson
ENGINEERING

CITY OF ORANGE BEACH
FIRE ADMINISTRATION BUILDING and POST OFFICE ROOF REPLACEMENTS
ISSUED 02-21-2022

TABLE OF CONTENTS

TABLE OF CONTENTS 4
SEALS PAGE1

PROCUREMENT AND CONTRACT REQUIREMENTS:

00100 INVITATION TO BID 1
00300 INSTRUCTION TO BIDDERS 6
00400 BID FORM 2
00401 LIST OF SUB-CONTRACTORS..... 1
00410 BID SPECIFICATIONS / SUMMARY 2
00430 REQUIREMENTS FOR CONTRACTS AND PURCHASES 1
00440 AFFIDAVIT OF CONTRACTOR OR DIRECT VENDOR..... 2
00600 BID BOND 2
00610 NOTICE OF AWARD (SAMPLE)..... 1
00620 PERFORMANCE BOND (SAMPLE) 1
00630 LABOR AND MATERIALS BOND (SAMPLE)..... 1
00640 CONTRACT (SAMPLE) 2
00650 NOTICE TO PROCEED (SAMPLE) 1
00660 WAIVER AND RELEASE OF LIEN (SAMPLE) 1

GENERAL REQUIREMENTS AND TECHNICAL SPECIFICATIONS

DIVISION 01 - GENERAL REQUIREMENTS

012100 ALLOWANCES..... 4
012200 UNIT PRICES 1
012600 CONTRACT MODIFICATION PROCEDURES..... 2
012900 PAYMENT PROCEDURES 4
013100 PROJECT MANAGEMENT AND COORDINATION 7
013200 CONSTRUCTION PROGRESS DOCUMENTATION 7
013300 SUBMITTAL PROCEDURES..... 9
014000 QUALITY REQUIREMENTS 6
014200 REFERENCES..... 2
015000 TEMPORARY FACILITIES AND CONTROLS 6
016000 PRODUCT REQUIREMENTS 6
017300 EXECUTION..... 7
017700 CLOSEOUT PROCEDURES 5
017823 OPERATION AND MAINTENANCE DATA 5
017839 PROJECT RECORD DOCUMENTS 4
017900 DEMONSTRATION AND TRAINING..... 4

DIVISION 06 - WOOD, PLASTICS, AND COMPOSITES

061000 ROUGH CARPENTRY..... 3

DIVISION 07 - THERMAL AND MOISTURE PROTECTION


075420 THERMOPLASTIC POLYOLEFIN (TPO) ROOFING..... 7

CITY OF ORANGE BEACH
FIRE ADMINISTRATION BUILDING and POST OFFICE ROOF REPLACEMENTS
ISSUED 02-21-2022

076100	STANDING SEAM METAL ROOF PANELS	7
076200	SHEET METAL FLASHING AND TRIM	7
079200	JOINT SEALANTS.....	7

CITY OF ORANGE BEACH
FIRE ADMINISTRATION BUILDING and POST OFFICE ROOF REPLACEMENTS
ISSUED 02-21-2022

PROFESSIONAL SEALS

<p>ARCHITECT</p>  <p>02-21-2022</p>	<p>LANDSCAPE – N/A</p>	<p>CIVIL – N/A</p>
<p>STRUCTURAL – N/A</p>	<p>MECHANICAL – N/A</p>	<p>ELECTRICAL – N/A</p>

CITY OF ORANGE BEACH
FIRE ADMINISTRATION BUILDING and POST OFFICE ROOF REPLACEMENTS
ISSUED 02-21-2022

PUBLIC NOTICE

INVITATION TO BID

Sealed bids will be received, opened, and read aloud in public session for **FIRE DEPARTMENT ADMINISTRATION BUILDING and POST OFFICE ROOF REPLACEMENTS** for the **CITY OF ORANGE BEACH, ALABAMA**, at **10:00 AM CDT on Thursday, April 28, 2022**, at the City Hall Municipal Complex located at 4099 Orange Beach Blvd., Highway 161, Orange Beach, Alabama. Work will include all materials and labor for the demo and installation of new roofs as defined within the documents for the Orange Beach Fire Department Administration Building and Post Office. Qualified contractors are invited to bid.

A mandatory Pre-Bid Meeting will be held at **10:00 AM CDT on Thursday, April 21, 2022** at the City Hall Municipal Complex located at 4099 Orange Beach Blvd., Highway 161, Orange Beach, Alabama.

Bids in excess of Fifty Thousand Dollars (\$50,000) must be accompanied by a certified check or bid bond payable to the City of Orange Beach in an amount not less than 5% of the bid amount, but in no event more than \$10,000. Performance and Labor and Material Payment Bonds will be required from the Contractor. The Contractor will be required to obtain a business license from the City to operate within the Corporate Limits.

Bid specifications may be obtained from Orange Beach City Hall, 4099 Orange Beach Blvd., Orange Beach, Alabama, Monday through Friday from 8:00 a.m. until 5:00 p.m., or downloaded from the City's website at www.orangebeachal.gov.

Sealed bids may be mailed or delivered directly to the City of Orange Beach prior to the public opening. All sealed bids must be clearly and legibly marked "SEALED BID," the bidder's name, the name of the bid, and the opening date and time. Contact Renee Eberly at (251) 981-6806 or reberly@orangebeachal.gov with any questions.

Sealed bids must be mailed to the following address:

City of Orange Beach
Attention: City Clerk
P.O. Box 458
Orange Beach, Alabama 36561

Or hand delivered to:

City of Orange Beach
Attention: City Clerk
4099 Orange Beach Blvd.
Orange Beach, Alabama 36561

Be advised that overnight delivery by express or courier to Orange Beach is not guaranteed. Faxed bids will not be accepted.

The lowest responsive, responsible bid will be accepted with key consideration based upon best value and benefit to the public. The City of Orange Beach reserves the right to reject any and all bids, to waive any irregularity in the bids received, and to accept or reject any items of the bid for the benefit of the public. No conditional bids will be accepted. No bid may be withdrawn for a period of thirty (30) days after the scheduled closing date and time for the receipt of bids.

CITY OF ORANGE BEACH
FIRE ADMINISTRATION BUILDING and POST OFFICE ROOF REPLACEMENTS
ISSUED 02-21-2022

INVITATION TO BID

INVITATION TO BID DATE: March 31, 2022

BID TITLE: FIRE DEPARTMENT ADMINISTRATION BUILDING and POST OFFICE ROOF REPLACEMENTS

PRE-BID MEETING: April 21, 2022 at 10:00 A.M. (Central)

PLACE OF PRE-BID & BID OPENING: City of Orange Beach, City Hall, 4099 Orange Beach Blvd.

BIDS MUST BE RECEIVED BEFORE: April 28, 2022 at 10:00 A.M. (Central)

BIDS WILL BE PUBLICLY OPENED: April 28, 2021 at 10:00 A.M. (Central)

Sealed bids will be received by the City of Orange Beach at the Office of the City Clerk located at Orange Beach City Hall until the above time and date at which time they will be opened as soon thereafter as practicable.

NOTE: For this bid to be considered responsive, all information in this section should be supplied, as appropriate, or the entire bid may be disqualified. Bid response must be in ink or typed with original signature. No errors will be corrected after bids are opened. No prices shall include State or Federal Exercise Taxes; tax exemption certificates furnished upon request. The City of Orange Beach reserves the right to accept or reject all bids or any portion thereof. The City reserves the right to require a bid bond, in which case specific information shall be provided the bid documents.

ALL BIDS MUST BE RETURNED AS FOLLOWS:

All bidders must use the bid form provided in the bid documents and show on the envelope "SEALED BID," the bid title, the bidder's name, and the opening date and time. Each bid must be in a separate envelope.

U.S. Postal Service
City of Orange Beach
Attention: City Clerk
P.O. Box 458
Orange Beach, Alabama 36561

Courier (UPS, FedEx, etc.)
City of Orange Beach
Attention: City Clerk
4099 Orange Beach Blvd.
Orange Beach, Alabama 36561

1. For the purchase or lease of personal property only, a resident person, firm or corporation, whose bid is no more than five percent (5%) greater than the lowest bid, may be the successful bidder and the contract may be awarded to such resident responsible bidder. A resident bidder is defined by the City Council of Orange Beach as any business located within Baldwin County.
2. Contact John (Sandy) McArthur, Watermark Design at 251-378-6175/smcarthur@watermarkarch.com for questions concerning the technical specifications.
3. Contact Renee Eberly, City Clerk/Procurement Officer at 251-981-6806/reberly@orangebeachal.gov for questions concerning technical specifications or general bid procedures.

END OF INVITATION TO BID

CITY OF ORANGE BEACH
FIRE ADMINISTRATION BUILDING and POST OFFICE ROOF REPLACEMENTS
ISSUED 02-21-2022

**INSTRUCTIONS TO BIDDERS & GENERAL CONDITIONS
(PUBLIC WORKS PROJECTS)**

1.0 INTRODUCTION

All bidders will be bound to the general conditions and requirements set forth in these general instructions and such instructions shall form an integral part of each purchase contract awarded by the Orange Beach City Council. Applicability of general conditions as stated below shall be determined by the City of Orange Beach. All bids must be submitted on and in accordance with the instructions provided by the City of Orange Beach.

2.0 BID DOCUMENTS

A complete set of Bid Documents is included herein. The date, time, and place of a bid opening will be given in the Invitation to bidders. Copies of the complete set of Bid Documents may be inspected and/or obtained at the following location:

Orange Beach City Hall
4099 Orange Beach Boulevard
Orange Beach, AL 36561

Or downloaded from the City's website:
www.orangebeachal.gov, see "Bids"

3.0 EXAMINATION OF DOCUMENTS AND PROJECT SITE

- 3.1 Carefully examine the Bid Documents, Specifications, and the Work Site.
- 3.2 Bids shall include all costs required to execute the work under the existing conditions.
- 3.3 Extra payments will not be made for conditions which can be determined by examining the documents and the site.

4.0 INTERPRETATIONS AND ADDENDA

- 4.1 Should a bidder find discrepancies, ambiguities, or omissions in the Specifications, or should he/she be in doubt as to their meaning, he/she shall immediately notify the Procurement Officer (Renee Eberly at 251-981-6806 or reberly@orangebeachal.gov).
- 4.2 The Procurement Officer will issue Addenda to clarify discrepancies, ambiguities, or omissions in the Specifications.
- 4.3 Addenda will be posted on the City's website at: www.orangebeachal.gov
- 4.4 Addenda shall become part of the bid and all bidders must acknowledge receipt of Addenda on their Bid Form or their bid will be rejected. Bidders shall be bound by all Addenda.
- 4.5 The City is not responsible for any oral instructions.

5.0 PREPARATION OF BID

- 5.1 The bid must be submitted on the Bid Form furnished. All information required by the Bid Documents must be given to constitute a complete bid.
- 5.2 The Bidder must print, in figures, without interlineations, alterations, or erasures, a Unit Price. The Bidder shall then print the total sum on the line designated as "Bid Total." The City will check the total sum printed by the Bidder, and, in case of error or discrepancy, the unit price shall prevail and the total shall be corrected.

CITY OF ORANGE BEACH
FIRE ADMINISTRATION BUILDING and POST OFFICE ROOF REPLACEMENTS
ISSUED 02-21-2022

- 5.3 Prices and all information must be legible. Illegible or vague bids may be rejected.
- 5.4 All signatures must be written. Facsimile, printed, or typewritten signatures are not acceptable.
- 5.5 Under penalty of perjury, the Bidder certifies by signature on the Bid Form that:
 - The bid has been arrived at by the Bidder independently and has been submitted without collusion with any other vendor of materials, supplies, equipment, or services for the type described in the Invitation to Bid; and
 - The contents of the bid have not been communicated by the Bidder; nor to his/her best knowledge and belief by any of his/her employees or agents to any person not an employee or agent of the Bidder or its surety on any bond furnished herewith prior to the official opening of the bid.

6.0 DELIVERY AND SUBMISSION OF BID

- 6.1 Each bid shall be placed, together with the Bid Bond, if applicable, in a sealed envelope. Bid envelopes must be clearly marked "SEALED BID," the Bidder's name, the title of the bid, and the opening date and time.
- 6.2 All bids received after the time stated in the Invitation to Bid will not be considered and will be returned unopened to the Bidder. The Bidder assumes risk of delay in the mail. Whether sent by mail or by means of personal delivery, the bidder assumes responsibility for having bids deposited on time at the place specified.
- 6.3 The submission of a bid will be construed to mean that the Bidder is fully informed as to the extent and character of the supplies, materials, or equipment required, and as a representation that the bidder can furnish the supplies, materials, or equipment satisfactorily in complete compliance with the specifications.

7.0 MODIFICATIONS AND WITHDRAWALS OF BIDS

- 7.1 No alteration, erasure, or addition is to be made in the typewritten or printed matter. Deviations from the specifications must be set forth in the space provided in bid or by attached sheets for this purpose.
- 7.2 Bids may not be modified after submittal.
- 7.3 Bidder may withdraw his/her bid, either personally or by written request, at any time prior to the scheduled bid opening time.
- 7.4 No bidder may withdraw his/her bid for a period of thirty (30) days after the bid opening.

8.0 RIGHT TO REJECT BID

Bids may be rejected if they contain any omissions, alterations of form, additions not called for, conditional bids, alternate bids unless requested by the City, incomplete bids, erasures, or irregularities of any kind. Bids in which the Unit or Lump Sum prices are obviously unbalanced may be rejected. The City reserves the right to reject any and all bids for any reason and to waive any informality or irregularity in the bids received.

9.0 BASIS OF AWARD

- 9.1 The City will award a single contract, dependent on the availability of funds.
- 9.2 The contract will be awarded to the lowest responsive qualified contractor, subject to the City's right to reject any or all bids and to waive informality and irregularity in bids and bidding.

CITY OF ORANGE BEACH
FIRE ADMINISTRATION BUILDING and POST OFFICE ROOF REPLACEMENTS
ISSUED 02-21-2022

- 9.3 The City shall have the right to accept alternates in any order or combination, unless otherwise specifically provided in the bid documents, and to determine the low bidder on the basis of the sum of the base bid and alternates accepted.

10.0 ENGINEER RECOMMENDATIONS

All bids for technical products or services in conjunction with ongoing or new construction system projects shall be approved for specification compliance by the City's Project Engineer and a designated representative of the City of Orange Beach. No bid shall be awarded without first hearing the recommendation of the City's Project Engineer.

11.0 SAMPLE OF MATERIALS

Sample of items, when required, must be furnished free of expense to the City and, if not destroyed, will upon request be returned at the bidder's expense.

12.0 PRE-QUALIFICATION OF CONTRACTORS

Each Bidder shall be prepared, if requested by the City, to present evidence of its experience, qualifications, and financial ability to carry out the terms of the Contract. The City reserves the right to disqualify any bidder who, in the sole judgement of the City, fails to adequately demonstrate qualifications and experience sufficient to enable that bidder to successfully complete the scope of work under this Contract.

13.0 EXECUTION OF CONTRACT

13.1 Within ten (10) days of Notice of Award, the Contractor shall deliver to the City proof of insurance as required by Contract Documents. All proof of insurance shall be approved by the City before the Contractor may proceed with Work.

13.2 The Contractor shall commence work within ten (10) days following receipt of the Notice to Proceed or on a date stipulated in the authorization to proceed.

14.0 LAWS AND REGULATIONS

The Contractor's attention is directed to the fact that all applicable State laws, Municipal Ordinances, and the Rules and Regulations of all authorities having jurisdiction over construction of the project shall apply to the Contract throughout, and they will be deemed to be included in the Contract the same as though herein written out in full.

15.0 ALABAMA LICENSE CONTRACTOR

All Contractors submitting bids in excess of Fifty Thousand Dollars (\$50,000.00) must be licensed contractors in the State of Alabama and must state their License Number on their Bid Form. Contracts less than Fifty Thousand Dollars (\$50,000.00) will not require a General Contractor's License; however, all other requirements shall remain the same.

16.0 BUSINESS LICENSE

The successful bidder will be required to obtain a City of Orange Beach Business License in order to operate within the Corporate Limits.

17.0 BUILDING PERMITS

The successful bidder shall be required to comply with all building permit procedures and requirements. Building permit fees for this project shall be waived

CITY OF ORANGE BEACH
FIRE ADMINISTRATION BUILDING and POST OFFICE ROOF REPLACEMENTS
ISSUED 02-21-2022

18.0 BID BOND

All bids in excess of Fifty Thousand Dollars (\$50,000.00) shall require a bid bond equal to 5% of the contract amount or \$10,000, whichever is lesser. Bid bonds will be returned by the City after the contract has been awarded.

19.0 PERFORMANCE BOND

If the winning bid is in excess of Fifty Thousand Dollars (\$50,000.00), the Contractor shall obtain a performance bond equal to 100% of the contract amount and shall provide such bond within ten (10) days of Notice of Award.

20.0 LABOR & MATERIALS BOND

If the winning bid is in excess of Fifty Thousand Dollars (\$50,000.00), the Contractor shall obtain a Labor & Materials Payment Bond equal to but not less than 50% of the contract amount and shall provide such bond within ten (10) days of Notice of Award. The bond shall include payment of reasonable attorney's fees incurred by successful claimants in civil actions.

21.0 INSURANCE REQUIREMENTS

Contractor agrees, at its sole expense, to maintain on a primary and non-contributory basis during the life of this Contract, or the performance of Work hereunder, insurance coverages, limits, and endorsements as set out below. Contractor agrees to obtain Commercial General Liability, Business Auto Liability, Worker's Compensation, and Commercial Umbrella/Excess Liability before starting the work. Contractor also agrees to undertake the obligation to insure that all subcontractors abide by these same insurance requirements.

The Contractor agrees the insurance requirements herein as well as City's review or acknowledgment is not intended to and shall not in any manner limit or qualify the liabilities and obligations assumed by the Contractor under this Contract.

Commercial General Liability

Contractor agrees to maintain Commercial General Liability at a limit of liability not less than \$1,000,000 Each Occurrence, \$2,000,000 Annual Aggregate. Contractor agrees its coverage will not contain any restrictive endorsement(s) excluding or limiting Product/Completed Operations, Independent Contractors, Broad Form Property Damage, X-C-U Coverage, Contractual Liability, or Cross Liability.

Business Automobile Liability

Contractor agrees to maintain Business Automobile Liability at a limit of liability not less than \$1,000,000 Each Occurrence. Coverage shall include liability for Owned, Non-Owned, and Hired Automobiles.

Worker's Compensation & Employer's Liability

Regardless of any "minimum requirements" of the State of Alabama, Contractor shall obtain Worker's Compensation insurance covering **all** workers involved in the Work. (Note: Elective exemptions or coverage through an employee leasing arrangement will violate this requirement.) Subcontractor shall also obtain Employer's Liability insurance with minimum limits of \$500,000 Each Accident, \$500,000 Disease Policy Limit, and \$500,000 Each Employee.

Commercial Umbrella/Excess Liability

Contractor agrees to maintain either a Commercial Umbrella or Excess Liability at a limit of liability not less than \$1,000,000 Each Occurrence, \$1,000,000 Aggregate. The Contractor agrees to endorse the City as an "Additional Insured" on the Commercial Umbrella/Excess Liability, unless the Commercial Umbrella/Excess Liability provides coverage on a pure/true follow-form basis, or the City is automatically defined as an Additional Protected Person.

CITY OF ORANGE BEACH
FIRE ADMINISTRATION BUILDING and POST OFFICE ROOF REPLACEMENTS
ISSUED 02-21-2022

Additional Insured Endorsements

The Contractor agrees to endorse the City as an Additional Insured on the Commercial General Liability with the following Additional Insured endorsement, or similar endorsement providing equal or broader Additional Insured coverage than:

- CG2010 10 01 – Additional Insured; Owners, Lessees, or Contractors, OR
- CG2010 07 04 – Additional Insured; Owners, Lessees, or Contractors; Scheduled Person or Organization endorsement

The name of the organization endorsed as Additional Insured for all endorsements shall read “City of Orange Beach.”

Waiver of Subrogation

Contractor agrees by entering into this written Contract to a Waiver of Subrogation in favor of the City. If a policy prohibits waiving subrogation rights without an endorsement, the Contractor agrees to endorse it with a Waiver of Transfer of Rights of Recovery against Others, or an equivalent endorsement. This Waiver of Subrogation requirement shall not apply to any policy which voids coverage if subrogation is waived.

Right to Revise or Reject

The City reserves the right to revise any insurance requirement based on insurance market conditions affecting the availability or affordability of coverage; or changes in the scope of work/specifications affecting the applicability of coverage. Additionally, the City reserves the right, but not the obligation, to review and reject and insurance policies failing to meet the criteria stated herein, or any insurer(s) providing coverage, due to its poor financial condition or failure to operate legally in the State of Alabama. In such events, City shall provide Contractor written notice of such revisions or rejections.

No Representation of Coverage Adequacy

The coverages, limits, or endorsements required herein protect the primary interests of the City, and the Contractor agrees in no way should these coverages, limits, or endorsements required be relied upon when assessing the extent or determining appropriate types and limits of coverage to protect the Contractor against any loss exposures, whether as a result of the Project or otherwise.

Certificate of Insurance

Contractor agrees to provide City a Certificate of Insurance evidencing the above coverages. If the Contractor receives a non-renewal or cancellation or other material change notice from an insurance carrier affording coverage required herein, Contractor agrees to notify the City immediately with specifics as to which coverage is no longer in compliance. The City shall have the right, but not the obligation, of prohibiting Contractor from entering the Work site until a new Certificate of Insurance is provided to the City evidencing the replacement coverage. The Contractor agrees the City reserves the right to withhold payment to Contractor until evidence of reinstated or replacement coverage is provided to the City. If the Contractor fails to maintain the insurance as set forth herein, the Contractor agrees the City shall have the right, but not the obligation, to purchase replacement insurance, which the Contractor agrees to reimburse any premiums or expenses incurred by the City.

The Contractor agrees the Certificate(s) of Insurance shall:

1. Clearly indicate the City has been endorsed on the Commercial Umbrella/Excess Liability and Commercial General Liability policy as an Additional Insured. Clearly indicate the CITY HALL ROOF REPLACEMENT and project number.
2. Clearly indicated Certificate Holder(s) as follows:

Original to: City of Orange Beach
 Attn: City Clerk

CITY OF ORANGE BEACH
FIRE ADMINISTRATION BUILDING and POST OFFICE ROOF REPLACEMENTS
ISSUED 02-21-2022

P.O. Box 458
Orange Beach, AL 36561
Fax (251) 981-1442

22.0 COMPLETION DATE

- 22.1 Unless otherwise specified by the City, the Contractor shall commence the work within ten (10) days from the date of receipt of the Notice to Proceed, and shall complete the work within one hundred eighty (180) calendar days from the date of receipt of the Notice to Proceed.
- 22.2 The completion date shall not be extended except for unavoidable delays caused by, but not limited to, fires, floods, storms, strikes, accidents, or other circumstances beyond the Contractor's control. The Contractor may request additional completion time within one week from the occurrence of the delay. The City shall be the sole judge of such "unavoidable delays," and the extent thereof. In the event that such a determination is made, the date of completion shall be extended by a length of time equal to that lost by such circumstances. The City shall not be liable to the Contractor for any damages or additional compensation as a consequence of any delay, hindrance, interference, or other similar event beyond the City's control. Failure by the Contractor to notify the City within one week from the occurrence of delay will constitute a forfeiture of any potential time extension.

23.0 LIQUIDATED DAMAGES

- 23.1 Deduction at the rate of Three Hundred Dollars (\$300.00) per day shall be made from the total Contract price for each and every calendar day beyond the one hundred eighty (180) days from the date of Notice to Proceed that the work remains not satisfactorily completed.
- 23.2 The above mentioned sum shall be deducted as Liquidated Damages. Such liquidated damages are intended to represent estimated actual damages and are not intended as a penalty, and Contractor shall pay them to the City without limiting the City's right to terminate this agreement for default as provided elsewhere herein.

24.0 DEFAULT OF CONTRACTOR

In cases of default of the contractor, the City may procure the Work from other sources and hold the contractor responsible for any excess cost occasioned thereby.

25.0 PAYMENT

The Bidder may submit an Application for Payment for provided labor and materials in accordance with the accepted Unit Prices. Payment shall be made to the Bidder within thirty (30) days of receipt and approval of Application for Payment.

CITY OF ORANGE BEACH
FIRE ADMINISTRATION BUILDING and POST OFFICE ROOF REPLACEMENTS
ISSUED 02-21-2022

BID FORM

The following Bid Form shall be used. Bids submitted on alternate forms may be rejected. Fill in all blank spaces with an appropriate entry. Bid Form must be signed by an officer of the company and notarized.

TO: CITY OF ORANGE BEACH
4099 Orange Beach Blvd, Orange Beach, AL 36561

RE: FIRE DEPARTMENT ADMINISTRATION BUILDING and POST OFFICE ROOF
REPLACEMENTS
25778 John M. Snook Dr., Orange Beach, AL 36561

Summary of Work:

The Orange Beach Fire Department Administration Building and Post Office roof replacement scopes of work include, but are not limited to, the following. (Note: Contractor is responsible for field verification of all measurements and quantities required to complete bids and installations.)

Fire Department Administration Building scope includes:

1. Removal of approximately 2,750 square feet of concrete tile and associated components down to the existing plywood deck.
2. Removal of approximately 2,600 square feet of existing low-sloped exposed fastener metal roof down to plywood deck
3. Removal of existing cupola vent, existing metal flashings, and existing gutters and downspouts.
4. Installation of a new underlayment for both low-slope and pitched slope roofs.
5. Installation of approximately 2750 square feet standing seam metal roofing system, including metal flashings, trim, and a vented ridge.
6. Installation of approximately 2,600 square feet TPO low-slope roof system
7. Installation of new gutters and downspouts.

Post Office Building Scope includes:

1. Removal of approximately 7,980 square feet of concrete tile and associated components down to the existing plywood deck.
2. Removal of existing metal flashings and existing gutters and downspouts.
3. Installation of a new underlayment for pitched slope roof.
4. Installation of approximately 7,980 square feet standing seam metal roofing system, including metal flashings, trim, and a vented ridge.
5. Installation of new gutters and downspouts.

CITY OF ORANGE BEACH
FIRE ADMINISTRATION BUILDING and POST OFFICE ROOF REPLACEMENTS
ISSUED 02-21-2022

Acknowledgement:

The undersigned bidder acknowledges having inspected the site(s) and the conditions affecting and governing the accomplishment of the project, and proposes to furnish all materials and perform all labor, as specified, to complete the project.

Company Name

Company Representative

Street Address

Title

City, State, Zip

Phone

Federal Employer ID No. *(if no FEIN, enter SSN)*

Email

Alabama General Contractors License No.

**CITY OF ORANGE BEACH
 FIRE ADMINISTRATION BUILDING and POST OFFICE ROOF REPLACEMENTS
 ISSUED 02-21-2022**

Bid:

BASE BID: _____ \$ _____
(Amount in Words) (Amount in Figures)

CONTINGENCY ALLOWANCE (See 012100 Allowances) \$ 20,000.00

TOTAL BID (Base Bid + Allowance) \$ _____

Unit Prices: (See Section 01220 - UNIT PRICES, 2.1 Schedule)

Item	Description	Units	Unit Price
1	Replacement of Damaged Plywood Roof Deck (See 061600 Sheathing)	4' x 8' Sheet	\$ _____
2	Replacement of Deteriorated Wood Blocking (See 061600 Sheathing)	Board Feet	\$ _____

Addenda:

The bidder acknowledges receipt of the following addenda covering revisions to the bid documents, and states that the costs, if any, of such revisions have been included in the base bid and other prices quoted herein:

Addendum No. _____ **Dated:** _____

Addendum No. _____ **Dated:** _____

Note: If no addenda have been received, write in "none."

Roofing System Manufacturer, Product Name:

A material/color sample and written specifications for proposed roofing assembly must be attached to the bid.

System	Manufacturer	Product Name/Number
Standing Seam	_____	_____
TPO Roofing	_____	_____

Warranties: (See Individual Sections for Warranty Requirements)

Sample Warranties shall be attached to the bid and shall specify any and all exclusions, including products and services. If such warranties are provided at additional cost, the incremental cost must be so specified and included in the base bid. The procedure necessary to notify such warranty must be specified. Any additional charges relating to the utilization of the warranty provided must be specified.

CITY OF ORANGE BEACH
FIRE ADMINISTRATION BUILDING and POST OFFICE ROOF REPLACEMENTS
ISSUED 02-21-2022

Signature:

I/we agree to furnish at the prices shown and guarantee that each offered will meet or exceed all specifications, terms and conditions, and requirements listed. This is the total price and includes all delivery or freight charges to the City of Orange Beach. Any attachment hereto is made and becomes a part of this inquiry and must be signed by the bidder. I herein affirm that I have not been in any agreement or collusion among bidders in restraint of competition to bid at a fixed price or to refrain from bidding otherwise. By signing this contract, the company represents and agrees that it is not currently engaged in, nor will it engage in, any boycott of a person or entity based in or doing business with a jurisdiction with which the State of Alabama can enjoy open trade.

_____	_____
Company Name	Authorized Signature (INK)
_____	_____
Mail Address	Typed Authorized Name
_____	_____
City, State, Zip	Title
_____	_____
Phone Including Area Code	Fax Number

SWORN TO AND SUBSCRIBED BEFORE ME THIS DAY OF _____, 20_____.

Notary Public

Commission Expires

CITY OF ORANGE BEACH
FIRE ADMINISTRATION BUILDING and POST OFFICE ROOF REPLACEMENTS
ISSUED 02-21-2022

LIST OF SUBCONTRACTORS

NOTE: Must be submitted to Owner/Architect within 24 hours after Bid time. All categories shall be completed indicating by Company name: General Contractor, Sub-contractors; Suppliers).

Each bidder (General Contractor) is asked to submit with his proposal a list of the principal subcontractors/suppliers he proposes to use, listing the name in the category of work

In addition to the Architect/Owners' approval, after receipt of proposal, no changes in subcontractors will be made without written approval from the City of Semmes.

1. Roofing Installer: _____
2. Roofing Supplier/Manufacturer: _____
3. Sheet Metal Flashing and Trim: _____
4. Specialties: _____
5. Other subcontractors/suppliers as applicable: _____

CITY OF ORANGE BEACH
FIRE ADMINISTRATION BUILDING and POST OFFICE ROOF REPLACEMENTS
ISSUED 02-21-2022

BID SPECIFICATIONS

A. Project Location

The Orange Beach Fire Administration Building is located at 25855 John M. Snook Dr., Orange Beach, AL 36561. The Orange Beach Post Office Building is located at 25778 John M. Snook Dr., Orange Beach, AL 36561.

B. City Staff Contact

The City's staff contact for this project shall be Mr. Tim Tucker: (251) 747-1599

C. Site Inspection

Bidders are strongly encouraged to schedule a walkthrough of the project location with the City's staff contact. There will be a pre-bid conference for this project with a site walkthrough following.

D. Work Schedule

After contract award, the Contractor shall coordinate the work schedule with the City Hall Operations. Any modifications to the work schedule shall be first approved by City Hall Operations.

E. Coordination

The Contractor shall coordinate all work with the City Hall Operations and designated City Staff. The intent is for the work to the City Hall to be completed without closing the facility. It is the responsibility of the Contractor to coordinate the work as to eliminate or minimize any delay, obstruction, disruption, or interference to City functions and any businesses surrounding the City Hall.

F. Project Description

The Orange Beach Fire Administration Building and Post Office Roof Replacements project consists of Demolition for the existing concrete tile and low-sloped roofs and replacement of a standing seam metal roofing system and TPO system per design documents.

G. Scope of Work

1. Contractor is responsible to provide a complete demo and re-roof installation at the Orange Beach complexes, including all labor, materials, tools, supervision, and equipment necessary to complete the Work.
2. Contractor acknowledges that the documents included with this Contract Agreement are complete and represent the design intent. As such, the bid total pricing included with this Contract Agreement is firm and reflects the work required for complete installation and associated work in accordance with the intent of the Contract Documents and is not subject to change.
3. The specific items included as part of this scope of work are listed for emphasis only and are not intended to limit the scope of work in any way.
4. The Work of this contract is hereby further clarified and defined. In accordance with the nature of this contract, this clarification does not relieve the Contractor from providing all elements of a complete system that conforms to the requirements of the Contract Documents. It is the Contractor's responsibility, based on their expertise and knowledge of the work, to include all items, materials, and procedures necessary to complete the execution of the work that, although not shown, can be reasonably inferred to be a part of the work.
5. Contractor is responsible to supply and install all work in accordance with all applicable codes and manufacturer and industry standards.
6. Contractor's price includes:

CITY OF ORANGE BEACH
FIRE ADMINISTRATION BUILDING and POST OFFICE ROOF REPLACEMENTS
ISSUED 02-21-2022

- a) All taxes associated with this scope of work; **OR TAX EXEMPT PROJECT FORM**
 - b) All salaried and field personnel required to complete the work;
 - c) All permits required for this work; and
 - d) Contractor acknowledges that multiple mobilizations for the entire duration of the project may be required and has accounted for all costs within the lump sum price.
- 7. Contractor is responsible for all material handling required to perform this scope of work.
 - 8. Contractor shall coordinate delivery of material with the Project Schedule and the City. Contractor shall properly store all materials and equipment per the manufacturer's recommendations in the event that materials or equipment are delivered prematurely.
 - 9. Contractor is responsible for all field measurements required to complete all installations.
 - 10. Contractor is responsible for all layout required to complete all installations.

H. Storage of Materials

All equipment and materials may be stored only at the location(s) approved by the City. It is expressly noted that no payments will be made for materials stored off-site.

I. Disposal of Materials

Any waste and excess materials shall be disposed of by the Contractor in a safe manner conforming to all Federal and State Occupational and Environmental Laws and Regulations including, but not limited to, the Occupational Safety and Health Act (OSHA), the Clean Air Act (CAA), the Clean Water Act (CWA), the Safe Drinking Water Act (SDWA), the Toxic Substances Control Act (TSCA), and the Alabama Department of Environmental Management (ADEM) Regulations.

CITY OF ORANGE BEACH
FIRE ADMINISTRATION BUILDING and POST OFFICE ROOF REPLACEMENTS
ISSUED 02-21-2022

REQUIREMENTS FOR CONTRACTS AND PURCHASES

Effective January 1, 2012 under the “Beason-Hammon Alabama Taxpayer and Citizen Protection Act,” Act No. 2011-535, Alabama Code (1975) Section 31-13-1, Et Seq., before entering into a contract with the City to:

1. Perform a service;
2. Perform work;
3. Provide a product;
4. Accept a grant; and/or
5. Accept an initiative

The State of Alabama requires the business entity to sign a notarized affidavit agreeing:

1. Not to knowingly employ, hire for employment, or continue to employ, any unauthorized aliens in the State of Alabama;
2. To enroll in the E-Verify Program, to verify the immigration status of every employee required to be re-verified through that system and to provide documentation of its enrollment; and
3. To require its subcontractors to comply with the above requirements.

Before any contract can be let, purchase can be made, or payment can be issued by the City of Orange Beach after January 1, 2012, the Affidavit on the reverse side of this document must be completed, notarized, and returned to our offices.

Note: Proof of enrollment in the E-Verify Program must accompany the Affidavit, unless you do not have or hire any employees.

Questions about this process may be directed to Renee Eberly, City Clerk/Procurement Officer, at (251) 981-6806 or via e-mail at reberly@orangebeachal.gov.

COMPLETED AFFIDAVIT MUST BE RETURNED IN SEALED BID.

CITY OF ORANGE BEACH
FIRE ADMINISTRATION BUILDING and POST OFFICE ROOF REPLACEMENTS
ISSUED 02-21-2022

AFFIDAVIT OF CONTRACTOR OR DIRECT VENDOR

State of _____

County of _____

Before me, a notary public, personally appeared _____ (print name) who, being duly sworn, says as follows:

As a condition for the award of any contract, grant, or incentive by the City of Orange Beach, Alabama, I hereby attest that in my capacity as _____ (state position) for _____ (state business entity/employer/contractor name) that said business entity/employer/contractor shall not knowingly employ, hire for employment, or continue to employ an unauthorized alien within the State of Alabama.

I further attest that said business entity/employer/contractor is enrolled in the E-Verify program.

(Attach documentation establishing that business entity/employer/contractor is enrolled in the E-Verify Program.)

Signature of Affiant

Sworn to and subscribed before me this _____ day of _____, 20_____.

I certify that the affiant is known (or made known) to me to be the identical party he or she claims to be.

Signature and Seal of Notary Public

My Commission Expires: _____

CITY OF ORANGE BEACH
FIRE ADMINISTRATION BUILDING and POST OFFICE ROOF REPLACEMENTS
ISSUED 02-21-2022

BID BOND

KNOW ALL MEN BY THESE PRESENTS:

THAT _____
(Name of Contractor/Principal)

_____, as Principal,
(Address)

and _____
(Name of Surety)

of _____, as Surety,
(Address)

are held and firmly bound unto **the City of Orange Beach**, as obligee, in the full and just sum of:

_____ lawful money of the United States, for the payment of which sum, well and truly to be made, we bind ourselves, our heirs, executors, administrators, successors and assigns, jointly and severally, firmly by these presents.

WHEREAS, the said Principal is herewith submitting its bid for:

FIRE ADMINISTRATION BUILDING and POST OFFICE ROOF REPLACEMENTS

The condition of this obligation is such that, if the aforesaid Principal shall be awarded the Contract, the said Principal will, within the time required, enter into a formal Contract, and give a good and sufficient bond to secure the performance of the terms and conditions of the Contract, then this obligation to be void; otherwise, the Principal and the Surety will pay unto the full amount of said bond. If no other bids are received, the full amount of the proposal guarantee shall be so retained or recovered as liquidated damages for such default.

SIGNED, SEALED AND DELIVERED _____
(Date)

Witness

Principal (Seal)

Title

Witness

Surety (Seal)

Title

Bids will not be considered unless Bid Bond is signed by Principal and Surety,
or in lieu thereof, a certified check must accompany the bid.

CITY OF ORANGE BEACH
FIRE ADMINISTRATION BUILDING and POST OFFICE ROOF REPLACEMENTS
ISSUED 02-21-2022

NOTICE OF AWARD (SAMPLE)

DATED:

TO:

PROJECT: **FIRE ADMINISTRATION BUILDING and POST OFFICE ROOF REPLACEMENTS**

You have been awarded a contract for **FIRE ADMINISTRATION BUILDING and POST OFFICE ROOF REPLACEMENTS**.

Within ten (10) days of the date of this Notice of Award, you must deliver to the City the enclosed contract documents, fully executed, signed and witnessed, and a Certificate of Insurance as follows:

- 4 originals Contract
- 1 original Performance Bond
- 1 original Labor and Material Bond
- 1 original Certificate of Insurance certifying compliance with all insurance requirements as specified in the General Conditions
- 1 copy Alabama General Contractors License
- 1 copy Orange Beach Business License

Please contact Bill Fetner in the Finance Department at (251) 981-6783 for more information regarding the Business License.

Within ten (10) days after receipt of the above documents, the City will return to you one (1) fully signed original of the Contract.

You will be notified of the time and place for a preconstruction conference; your proposed work schedule must be delivered to the City at that time.

Failure to deliver the aforementioned contract documents and insurance certificate within the time specified will entitle the City to consider your bid abandoned, to annul this Notice of Award, and to declare your Bid Bond forfeited.

CITY OF ORANGE BEACH

By: _____
Renee Eberly, City Clerk/Procurement Officer

CITY OF ORANGE BEACH
FIRE ADMINISTRATION BUILDING and POST OFFICE ROOF REPLACEMENTS
ISSUED 02-21-2022

PERFORMANCE BOND (SAMPLE)

KNOW ALL MEN:

That we _____, hereinafter called the Principal,
(Insert here the name and address or legal title of the Contractor)

_____, hereinafter called the Surety,
(Insert here the name and address or legal title of the Surety)

are held and firmly bound unto the Owner in the sum of _____
(\$_____) for the payment whereof the Principal and the Surety bind themselves, their heirs, executors,
administrators, successors and assigns, jointly and severally, firmly, by these presents.

WHEREAS, the Principal has, by means of a written agreement dated _____ entered
into a Contract with the Owner for _____ which agreement is by reference made a
part hereof.

NOW THEREFORE, the conditions of the obligation are such that if the Principal shall faithfully perform the Contract
on his part, and satisfy all claims and demands, incurred for the same, and shall fully indemnify and save harmless
the Owner from all costs and damage which he may suffer by reason of failure to do so, and shall reimburse and
repay the Owner all outlay and expense which the Owner may incur in making good for any such default thence this
obligation shall be null and void; otherwise, it shall remain in full force and effect.

PROVIDED, HOWEVER, that no suit, action or proceedings, by reason of any default whatever be brought on his bond
after twelve months from the day on which the final payment under the Contract falls due.

PROVIDED, further, that said Surety, for value received hereby stipulate and agree that no change, extension of time,
or addition to the terms of the Contract or to the work to be performed thereunder of the specifications thereof shall
in any way effect their obligations on this bond, and they do hereby waive notice of any such change, extension of
time, alteration or addition to the terms of the Contract, or to the work, or to the specifications.

CITY OF ORANGE BEACH
FIRE ADMINISTRATION BUILDING and POST OFFICE ROOF REPLACEMENTS
ISSUED 02-21-2022

SIGNED, SEALED, AND DELIVERED this _____ day of _____.

Attest:

(Corporate Principal Sign Here)

By: _____

Attest:

(Surety Sign Here)

By: _____

COUNTERSIGNED:

By: _____

CITY OF ORANGE BEACH
FIRE ADMINISTRATION BUILDING and POST OFFICE ROOF REPLACEMENTS
ISSUED 02-21-2022

LABOR AND MATERIALS BOND (SAMPLE)

KNOW ALL MEN BY THESE PRESENTS, THAT WE _____,
as Principal, and _____, as Surety, are held
and firmly bound unto said Owner, hereinafter called the Obligee, in the penal sum of
_____ Dollars (\$_____)
lawful money of the United States, for the payment of which sum and truly to be made, we bind ourselves, our heirs,
personal representatives, successors and assigns, jointly and severally, firmly by these presents.

WHEREAS, the Principal has entered into a certain Contract with said Obligee dated _____,
hereinafter called the Contract, for _____ and the specifications for said work
shall be deemed a part hereof as fully as if set out herein.

NOW THEREFORE, the conditions of the obligation are such that if the Principal and all subcontractors to whom any
portion of the work in said Contract is sublet and all assignees of said Principal and of such subcontractors shall
promptly make payments to all persons supplying him or them with labor, materials, or supplies for or in the
prosecution of the work provided for in such Contract, or any amendment or extension of or addition to said
Contract, and for the payment of reasonable attorney's fees incurred by the successful claimant or plaintiffs in suits
or claims against the Contractor arising out of or in connection with the said Contract, then the above obligation shall
be void; otherwise to remain in full force and effect.

PROVIDED, HOWEVER, that this bond is subject to the following conditions and limitations.

- (a) Any person, firm or corporation that has furnished labor, materials, or supplies for or in the prosecution of the work provided for in said Contract shall have a direct right to action against the Principal and Surety on this bond, which right of action shall be asserted in a proceeding, instituted in the County in which the work provided for in said Contract is to be performed or in any County in which said Principal or Surety does business. Such right of action shall be asserted in a proceeding instituted in the name of the claimant or claimants for his or their use and benefit against the Principal and Surety or either of them, but not later than one (1) year after the final settlement of said Contract falls due, in which action such claim or claims shall be adjusted and judgement rendered thereon.
- (b) The Principal and Surety hereby designate and appoint _____, or his successor or representative as the agent of each of them to receive and accept services of process or other pleading issued, or filed in any proceeding instituted on this bond and hereby consent that such service shall be the same as personal service on the Principal and/or Surety.
- (c) The Surety shall not be liable hereunder for any damages or compensation recoverable under Workmen's Compensation or Employer's Liability Statute.
- (d) In no event shall the Surety be liable for a greater sum than the penalty of this bond, or subject to any suit, action or proceeding thereon that is instituted later than one (1) year after the final settlement of said Contract.

CITY OF ORANGE BEACH
FIRE ADMINISTRATION BUILDING and POST OFFICE ROOF REPLACEMENTS
ISSUED 02-21-2022

- (e) This bond is given pursuant to the terms of an Act of the Legislature of the State of Alabama approved February 8, 1935, entitled, "An Act to further provide for Bonds and Contractors on State and other public works and suits thereon."
- (f) The full name and residence of each individual party to the bond must be inserted in the first paragraph.
- (g) If the Principal is a partnership, the full name of all partners must be inserted in the first paragraph which must recite that they are the partners composing the partnership (to be named) and all partners must execute the bond as individuals.
- (h) The State of Incorporation of each corporate party to bond must be inserted in the first paragraph and the bond must be executed under the Corporate Seal of each party attested by its secretary or other appropriate officer.
- (i) The date of the bond must not be prior to the date of the Contract.

SIGNED, SEALED, AND DELIVERED this _____ day of _____.

Attest:

(Corporate Principal Sign Here)

By: _____

Attest:

(Surety Sign Here)

By: _____

CITY OF ORANGE BEACH
FIRE ADMINISTRATION BUILDING and POST OFFICE ROOF REPLACEMENTS
ISSUED 02-21-2022

CONTRACT (SAMPLE)

THIS AGREEMENT, made and entered into the ____ day of _____, 2022, by and between _____, hereinafter called the Contractor, and the **City of Orange Beach, Alabama**, and/or its assigns, hereinafter called the Owner.

WITNESSETH:

That the Contractor, for the consideration hereinafter set out, hereby agrees with the Owner as follows:

1. That the Contractor shall perform all of the work in a satisfactory manner in accordance with the plans, specifications, bid requirements and conditions, which are attached hereto and made a part hereof as if fully contained herein, for **Fire Administration Building and Post Office Roof Replacements**.
2. That the Contractor shall commence the work to be performed under this agreement within the Contract Time as defined in the *General Conditions*.

All work shall be accomplished with quality in a manner which will maintain safety to life and property, and reduce to a minimum any interference with abutting property or public travel. All work shall be inspected and approved by the City Public Works Director or his designee as Owner's representatives before payment shall be made.

3. The Owner hereby agrees to pay to the Contractor for satisfactory performance of the agreement, subject to additions and deductions as provided in the contractual documents, in lawful money of the United States as follows:

_____.

4. Estimates of work completed shall be made by the Contractor each month and submitted to the Owner. Within thirty (30) calendar days after submittal by the Contractor, the owner shall make partial payments to the Contractor on the basis of the estimate of work, duly certified and approved by the City Construction Manager, and performed during the preceding calendar month by the Contractor, less two and a half percent (2.5%) of the amount of such estimate which is to be retained by the owner until all work (100%) has been satisfactorily completed in accordance with this agreement.
5. Upon substantial completion and inspection of all work covered by this agreement, payment of the Contract sum shall be made within thirty (30) calendar days, less retainage.

Said retainage shall be retained until: 1) Submission by the Contractor of evidence satisfactory to the Owner that all payrolls, material bills, and other costs incurred by the Contractor in connection with the construction of the work have been paid in full including a Waiver and Release of Lien on the form included in the Contract Documents; 2) Legal notice of advertisement of completion has been advertised four (4) consecutive weeks in some newspaper of general circulation in Baldwin County, Alabama, as approved by the Owner; 3) Final inspection by the City Public Works Director or his designee and final acceptance of the work by the Owner.

CITY OF ORANGE BEACH
FIRE ADMINISTRATION BUILDING and POST OFFICE ROOF REPLACEMENTS
ISSUED 02-21-2022

6. It is mutually agreed between the Owner and the Contractor that timely performance is of the essence to this Contract, and the Contractor agrees to keep a working force on the job of the size that is adequate to perform all work in accordance with the Contractor's approved work schedule.
7. The Contractor hereby agrees to warrant that all material and workmanship is of the quality, quantity, and character specified and shown, and that any faulty materials or workmanship made known to him within one (1) year after date of final certificate of payment shall be made good by him without additional expense to the Owner.

Failure to complete the work within the allotted Contract time will cause loss to the Owner in administrative, engineering, inspection, interest, and supervision charges. Therefore, any overrun in the Contract time, which in the opinion of the City Contract Manager is caused by undue delay, shall be charged to the Contractor at \$300.00 per day and deducted from the final payment as liquidate damages.

8. The Owner reserves the right to terminate the contract upon written notice to the Contractor at least five (5) days prior to said termination. In the event that the Contract is terminated, the Contractor will be compensated in accordance with the bid items of the Contract and its attachment for all approved work in place.

IN WITNESS WHEREOF, the parties hereto have executed this agreement on the day and date first above written in two (2) counterparts, each of which shall, without proof or accounting for the other counterpart, be deemed an original contract.

(Corporate Seal)

_____ **(Contractor)**

By: _____

Its _____

Attest: _____

Its _____

(Seal)

City of Orange Beach, Alabama (Owner)

By: _____

Tony Kennon, Mayor

Attest: _____

Renee Eberly, City Clerk

**CITY OF ORANGE BEACH
FIRE ADMINISTRATION BUILDING and POST OFFICE ROOF REPLACEMENTS
ISSUED 02-21-2022**

NOTICE TO PROCEED (SAMPLE)

DATED:

TO:

PROJECT: **FIRE ADMINISTRATION BUILDING and POST OFFICE ROOF REPLACEMENTS**

You are hereby notified to commence work in accordance with the Agreement dated _____, 2022, on or before _____, 2022. You are to complete the work within one hundred eighty (180) consecutive calendar days, or by _____, 2022.

City of Orange Beach, Alabama (Owner)

By: _____

ACCEPTANCE OF NOTICE

Receipt of the above NOTICE TO PROCEED is hereby acknowledged this _____ day of _____, 2022.

By: _____

CITY OF ORANGE BEACH
FIRE ADMINISTRATION BUILDING and POST OFFICE ROOF REPLACEMENTS
ISSUED 02-21-2022

WAIVER AND RELEASE OF LIEN (SAMPLE)

FROM:

TO: City of Orange Beach, Alabama (Owner)

PROJECT: **FIRE ADMINISTRATION BUILDING and POST OFFICE ROOF REPLACEMENTS**

KNOW ALL MEN BY THESE PRESENTS:

1. The undersigned, having been employed by the **City of Orange Beach** to furnish labor and/or materials for the referenced project, does hereby waive and release any and all lien and claim or right to lien and claim against the **City of Orange Beach** on the referenced project on account of labor, services, equipment, materials, etc. furnished for the referenced project.
2. The undersigned further certifies that to the best of his knowledge and belief, there are no unsatisfied or outstanding claims of any character arising out of the furnishing of labor, equipment, services, and/or materials for the referenced project.
3. The undersigned further agree that, after execution of this document, it will indemnify, defend at its expense, and save the **City of Orange Beach** harmless from any and all claims or liens arising out of the undersigned's furnishing of labor, equipment, services, and/or materials for the referenced project.
4. The undersigned has executed this document in order to induce the **City of Orange Beach** to make final payment to and in no way acts as a release of any claim the undersigned may have against parties other than the **City of Orange Beach** arising out of the furnishing of labor and/or materials for the referenced project.

IN WITNESS WHEREOF, the undersigned has signed and sealed this instrument this ____ day of _____, 2022.

STATE OF ALABAMA
COUNTY OF BALDWIN

Personally appeared before me the undersigned Notary Public in and for said County and State, _____, who is known to me and who, after being duly sworn, deposes and says that the facts stated in the above affidavit are true.

NOTARY PUBLIC

SECTION 012100 - ALLOWANCES

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. This Section includes administrative and procedural requirements governing allowances.
 - 1. Certain items are specified in the Contract Documents by allowances. Allowances have been established in lieu of additional requirements and to defer selection of actual materials and equipment to a later date when additional information is available for evaluation. If necessary, additional requirements will be issued by Change Order.
- B. Types of allowances include the following:
 - 1. Lump-sum allowances.
- C. Related Sections include the following:
 - 1. Division 01 Section "Contract Modification Procedures" for procedures for submitting and handling Change Orders for allowances.
 - 2. Divisions 02 through 49 Sections for items of Work covered by allowances.

1.3 SELECTION AND PURCHASE

- A. At the earliest practical date after award of the Contract, advise Architect of the date when final selection and purchase of each product or system described by an allowance must be completed to avoid delaying the Work.
- B. At Architect's request, obtain proposals for each allowance for use in making final selections. Include recommendations that are relevant to performing the Work.
- C. Purchase products and systems selected by Architect from the designated supplier.

1.4 SUBMITTALS

- A. Coordinate and process submittals for allowance items in same manner as for other portions of the Work.

1.5 COORDINATION

- A. Coordinate allowance items with other portions of the Work. Furnish templates as required to coordinate installation.

1.6 LUMP-SUM ALLOWANCES

- A. Allowance shall include cost to Contractor of specific products and materials ordered by Owner under allowance and shall include taxes, freight, and delivery to Project site.

CITY OF ORANGE BEACH
FIRE ADMINISTRATION BUILDING and POST OFFICE ROOF REPLACEMENTS
ISSUED 02-21-2022

- B. Unless otherwise indicated, Contractor's costs for receiving and handling at Project site, labor, installation, overhead and profit, and similar costs related to products and materials ordered by Owner under allowance shall be included as part of the Contract Sum and not part of the allowance.

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine products covered by an allowance promptly on delivery for damage or defects. Return damaged or defective products to manufacturer for replacement.

3.2 PREPARATION

- A. Coordinate materials and their installation for each allowance with related materials and installations to ensure that each allowance item is completely integrated and interfaced with related work.

3.3 SCHEDULE OF ALLOWANCES

- A. Allowance No.1: Contingency Allowance - \$20,000.00 for unforeseen conditions to be used at the Owners discretion.

END OF SECTION 012100

CITY OF ORANGE BEACH
FIRE ADMINISTRATION BUILDING and POST OFFICE ROOF REPLACEMENTS
ISSUED 02-21-2022

SECTION 01220 - UNIT PRICES

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section includes:
 - 1. Administrative and procedural requirements for unit prices.
 - 2. Schedule of Unit Prices
- B. Related Requirements:
 - 1. Section 01250 "Contract Modification Procedures" for procedures for submitting and handling Change Orders.

1.3 DEFINITIONS

- A. Unit price is an amount incorporated in the Agreement which applicable for the duration of the Work as a price per unit of measurement for materials, equipment, services, or a portion of the Work, added to or deducted from the Contract Sum by appropriate modification if the scope of Work or estimated quantities of Work required by the Contract Documents are increased or decreased.

1.4 PROCEDURES

- A. Unit prices include all necessary material, plus cost for delivery, installation, insurance, applicable taxes, overhead, and profit.
- B. Measurement and Payment: See individual Specification Sections for work that requires establishment of unit prices. Methods of measurement and payment for unit prices are specified in those Sections.
- C. Owner reserves the right to reject Contractor's measurement of work-in-place that involves use of established unit prices and to have this work measured, at Owner's expense, by an independent surveyor acceptable to Contractor.
- D. List of Unit Prices: A schedule of unit prices is included in Part 3. Specification Sections referenced in the schedule contain requirements for materials described under each unit price.

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION

2.1 SCHEDULE OF UNIT PRICES

- A. Unit Price No. 1: REPLACEMENT OF DAMAGED PLYWOOD ROOF DECK.
 - 1. Description: Remove damaged decking down to the structural supports; install new plywood deck by mechanically attaching to existing supports.
 - 2. Unit of Measurement: 4 x 8 sheet.
- B. Unit Price No. 2: REPLACEMENT OF DETERIORATED WOOD BLOCKING AT ROOF EDGE.
 - 1. Description: Remove, dispose, and install new to match existing.
 - 2. Unit of Measurement: board foot.

END OF SECTION

CITY OF ORANGE BEACH
FIRE ADMINISTRATION BUILDING and POST OFFICE ROOF REPLACEMENTS
ISSUED 02-21-2022

SECTION 012600 - CONTRACT MODIFICATION PROCEDURES

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. This Section specifies administrative and procedural requirements for handling and processing Contract modifications.
- B. Related Sections include the following:
 - 1. Division 01 Section "Product Requirements" for administrative procedures for handling requests for substitutions made after Contract award.

1.3 MINOR CHANGES IN THE WORK

- A. Architect will issue supplemental instructions authorizing Minor Changes in the Work, not involving adjustment to the Contract Sum or the Contract Time, on AIA Document G710, "Architect's Supplemental Instructions."

1.4 PROPOSAL REQUESTS

- A. Owner-Initiated Proposal Requests: Architect will issue a detailed description of proposed changes in the Work that may require adjustment to the Contract Sum or the Contract Time. If necessary, the description will include supplemental or revised Drawings and Specifications.
 - 1. Proposal Requests issued by Architect are for information only. Do not consider them instructions either to stop work in progress or to execute the proposed change.
 - 2. Within 10 days after receipt of Proposal Request, submit a quotation estimating cost adjustments to the Contract Sum and the Contract Time necessary to execute the change.
 - a. Include a list of quantities of products required or eliminated and unit costs, with total amount of purchases and credits to be made. If requested, furnish survey data to substantiate quantities.
 - b. Indicate applicable taxes, delivery charges, equipment rental, and amounts of trade discounts.
 - c. Include costs of labor and supervision directly attributable to the change.
 - d. Include an updated Contractor's Construction Schedule that indicates the effect of the change, including, but not limited to, changes in activity duration, start and finish times, and activity relationship. Use available total float before requesting an extension of the Contract Time.

CITY OF ORANGE BEACH
FIRE ADMINISTRATION BUILDING and POST OFFICE ROOF REPLACEMENTS
ISSUED 02-21-2022

- B. Contractor-Initiated Proposals: If latent or unforeseen conditions require modifications to the Contract, Contractor may propose changes by submitting a request for a change to Architect.
1. Include a statement outlining reasons for the change and the effect of the change on the Work. Provide a complete description of the proposed change. Indicate the effect of the proposed change on the Contract Sum and the Contract Time.
 2. Include a list of quantities of products required or eliminated and unit costs, with total amount of purchases and credits to be made. If requested, furnish survey data to substantiate quantities.
 3. Indicate applicable taxes, delivery charges, equipment rental, and amounts of trade discounts.
 4. Include costs of labor and supervision directly attributable to the change.
 5. Include an updated Contractor's Construction Schedule that indicates the effect of the change, including, but not limited to, changes in activity duration, start and finish times, and activity relationship. Use available total float before requesting an extension of the Contract Time.
 6. Comply with requirements in Division 01 Section "Product Requirements" if the proposed change requires substitution of one product or system for product or system specified.
- C. Proposal Request Form: Use AIA Document G709 for Proposal Requests.

1.5 CHANGE ORDER PROCEDURES

- A. On Owner's approval of a Proposal Request, Architect will issue a Change Order for signatures of Owner and Contractor on AIA Document G701.

1.6 CONSTRUCTION CHANGE DIRECTIVE

- A. Construction Change Directive: Architect may issue a Construction Change Directive on AIA Document G714. Construction Change Directive instructs Contractor to proceed with a change in the Work, for subsequent inclusion in a Change Order.
1. Construction Change Directive contains a complete description of change in the Work. It also designates method to be followed to determine change in the Contract Sum or the Contract Time.
- B. Documentation: Maintain detailed records on a time and material basis of work required by the Construction Change Directive.
1. After completion of change, submit an itemized account and supporting data necessary to substantiate cost and time adjustments to the Contract.

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION (Not Used)

END OF SECTION 012600

CITY OF ORANGE BEACH
FIRE ADMINISTRATION BUILDING and POST OFFICE ROOF REPLACEMENTS
ISSUED 02-21-2022

SECTION 012900 - PAYMENT PROCEDURES

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. This Section specifies administrative and procedural requirements necessary to prepare and process Applications for Payment.
- B. Related Sections include the following:
 - 1. Division 01 Section "Contract Modification Procedures" for administrative procedures for handling changes to the Contract.
 - 2. Division 01 Section "Construction Progress Documentation" for administrative requirements governing preparation and submittal of Contractor's Construction Schedule and Submittals Schedule.

1.3 DEFINITIONS

- A. Schedule of Values: A statement furnished by Contractor allocating portions of the Contract Sum to various portions of the Work and used as the basis for reviewing Contractor's Applications for Payment.

1.4 SCHEDULE OF VALUES

- A. Coordination: Coordinate preparation of the Schedule of Values with preparation of Contractor's Construction Schedule.
 - 1. Correlate line items in the Schedule of Values with other required administrative forms and schedules, including the following:
 - a. Application for Payment forms with Continuation Sheets.
 - b. Submittals Schedule.
 - c. Contractor's Construction Schedule.
 - 2. Submit the Schedule of Values to Architect at earliest possible date but no later than seven days before the date scheduled for submittal of initial Applications for Payment.
- B. Format and Content: Use the Project Manual table of contents as a guide to establish line items for the Schedule of Values. Provide at least one line item for each Specification Section.
 - 1. Identification: Include the following Project identification on the Schedule of Values:
 - a. Project name and location.

CITY OF ORANGE BEACH
FIRE ADMINISTRATION BUILDING and POST OFFICE ROOF REPLACEMENTS
ISSUED 02-21-2022

- b. Name of Architect.
 - c. Architect's project number.
 - d. Contractor's name and address.
 - e. Date of submittal.
2. Submit draft of AIA Document G703 Continuation Sheets.
 3. Arrange the Schedule of Values in tabular form with separate columns to indicate the following for each item listed:
 - a. Related Specification Section or Division.
 - b. Description of the Work.
 - c. Name of subcontractor.
 - d. Name of manufacturer or fabricator.
 - e. Name of supplier.
 - f. Change Orders (numbers) that affect value.
 - g. Dollar value.
 - 1) Percentage of the Contract Sum to nearest one-hundredth percent, adjusted to total 100 percent.
 4. Provide a breakdown of the Contract Sum in enough detail to facilitate continued evaluation of Applications for Payment and progress reports. Coordinate with the Project Manual table of contents. Provide several line items for principal subcontract amounts, where appropriate.
 5. Round amounts to nearest whole dollar; total shall equal the Contract Sum.
 6. Provide a separate line item in the Schedule of Values for each part of the Work where Applications for Payment may include materials or equipment purchased or fabricated and stored, but not yet installed.
 - a. Differentiate between items stored on-site and items stored off-site. If specified, include evidence of insurance or bonded warehousing.
 7. Provide separate line items in the Schedule of Values for initial cost of materials, for each subsequent stage of completion, and for total installed value of that part of the Work.
 8. Each item in the Schedule of Values and Applications for Payment shall be complete. Include total cost and proportionate share of general overhead and profit for each item.
 - a. Temporary facilities and other major cost items that are not direct cost of actual work-in-place may be shown either as separate line items in the Schedule of Values or distributed as general overhead expense, at Contractor's option.
 9. Schedule Updating: Update and resubmit the Schedule of Values before the next Applications for Payment when Change Orders or Construction Change Directives result in a change in the Contract Sum.

1.5 APPLICATIONS FOR PAYMENT

- A. Each Application for Payment shall be consistent with previous applications and payments as certified by Architect and paid for by Owner.

CITY OF ORANGE BEACH
FIRE ADMINISTRATION BUILDING and POST OFFICE ROOF REPLACEMENTS
ISSUED 02-21-2022

1. Initial Application for Payment, Application for Payment at time of Substantial Completion, and final Application for Payment involve additional requirements.
- B. Payment Application Times: The date for each progress payment is indicated in the Agreement between Owner and Contractor. The period of construction Work covered by each Application for Payment is the period indicated in the Agreement.
- C. Payment Application Forms: Use AIA Document G702 and AIA Document G703 Continuation Sheets as form for Applications for Payment.
- D. Application Preparation: Complete every entry on form. Notarize and execute by a person authorized to sign legal documents on behalf of Contractor. Architect will return incomplete applications without action.
 1. Entries shall match data on the Schedule of Values and Contractor's Construction Schedule. Use updated schedules if revisions were made.
 2. Include amounts of Change Orders and Construction Change Directives issued before last day of construction period covered by application.
- E. Transmittal: Submit 3 signed and notarized original copies of each Application for Payment to Architect by a method ensuring receipt within 24 hours. One copy shall include waivers of lien and similar attachments if required.
 1. Transmit each copy with a transmittal form listing attachments and recording appropriate information about application.
- F. Waivers of Mechanic's Lien: With each Application for Payment, submit waivers of mechanic's lien from every entity who is lawfully entitled to file a mechanic's lien arising out of the Contract and related to the Work covered by the payment.
 1. Submit partial waivers on each item for amount requested in previous application, after deduction for retainage, on each item.
 2. When an application shows completion of an item, submit final or full waivers.
 3. Owner reserves the right to designate which entities involved in the Work must submit waivers.
 4. Waiver Forms: Submit waivers of lien on forms, executed in a manner acceptable to Owner.
- G. Initial Application for Payment: Administrative actions and submittals that must precede or coincide with submittal of first Application for Payment include the following:
 1. List of subcontractors.
 2. Schedule of Values.
 3. Contractor's Construction Schedule (preliminary if not final).
 4. Products list.
 5. Schedule of unit prices.
 6. List of Contractor's staff assignments.
 7. List of Contractor's principal consultants.
 8. Copies of building permits.
 9. Copies of authorizations and licenses from authorities having jurisdiction for performance of the Work.
 10. Initial progress report.
 11. Report of preconstruction conference.
 12. Certificates of insurance and insurance policies.

CITY OF ORANGE BEACH
FIRE ADMINISTRATION BUILDING and POST OFFICE ROOF REPLACEMENTS
ISSUED 02-21-2022

13. Performance and payment bonds.
 14. Data needed to acquire Owner's insurance.
- H. Application for Payment at Substantial Completion: After issuing the Certificate of Substantial Completion, submit an Application for Payment showing 100 percent completion for portion of the Work claimed as substantially complete.
1. Include documentation supporting claim that the Work is substantially complete and a statement showing an accounting of changes to the Contract Sum.
 2. This application shall reflect Certificates of Partial Substantial Completion issued previously for Owner occupancy of designated portions of the Work.
- I. Final Payment Application: Submit final Application for Payment with releases and supporting documentation not previously submitted and accepted, including, but not limited, to the following:
1. Evidence of completion of Project closeout requirements.
 2. Insurance certificates for products and completed operations where required and proof that taxes, fees, and similar obligations were paid.
 3. Updated final statement, accounting for final changes to the Contract Sum.
 4. AIA Document G706, "Contractor's Affidavit of Payment of Debts and Claims."
 5. AIA Document G706A, "Contractor's Affidavit of Release of Liens."
 6. AIA Document G707, "Consent of Surety to Final Payment."
 7. Evidence that claims have been settled.
 8. Final meter readings for utilities, a measured record of stored fuel, and similar data as of date of Substantial Completion or when Owner took possession of and assumed responsibility for corresponding elements of the Work.
 9. Final, liquidated damages settlement statement.

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION (Not Used)

END OF SECTION 012900

CITY OF ORANGE BEACH
FIRE ADMINISTRATION BUILDING and POST OFFICE ROOF REPLACEMENTS
ISSUED 02-21-2022

SECTION 013100 - PROJECT MANAGEMENT AND COORDINATION

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. This Section includes administrative provisions for coordinating construction operations on Project including, but not limited to, the following:
 - 1. Coordination Drawings.
 - 2. Administrative and supervisory personnel.
 - 3. Project meetings.
 - 4. Requests for Interpretation (RFIs).
- B. Each contractor shall participate in coordination requirements. Certain areas of responsibility will be assigned to a specific contractor.
- C. Related Sections include the following:
 - 1. Division 01 Section "Construction Progress Documentation" for preparing and submitting Contractor's Construction Schedule.
 - 2. Division 01 Section "Execution" for procedures for coordinating general installation and field-engineering services, including establishment of benchmarks and control points.
 - 3. Division 01 Section "Closeout Procedures" for coordinating closeout of the Contract.

1.3 DEFINITIONS

- A. RFI: Request from Contractor seeking interpretation or clarification of the Contract Documents.

1.4 COORDINATION

- A. Coordination: Coordinate construction operations included in different Sections of the Specifications to ensure efficient and orderly installation of each part of the Work. Coordinate construction operations, included in different Sections, that depend on each other for proper installation, connection, and operation.
 - 1. Schedule construction operations in sequence required to obtain the best results where installation of one part of the Work depends on installation of other components, before or after its own installation.
 - 2. Coordinate installation of different components with other contractors to ensure maximum accessibility for required maintenance, service, and repair.
 - 3. Make adequate provisions to accommodate items scheduled for later installation.
 - 4. Where availability of space is limited, coordinate installation of different components to ensure maximum performance and accessibility for required

CITY OF ORANGE BEACH
FIRE ADMINISTRATION BUILDING and POST OFFICE ROOF REPLACEMENTS
ISSUED 02-21-2022

maintenance, service, and repair of all components, including mechanical and electrical.

- B. Prepare memoranda for distribution to each party involved, outlining special procedures required for coordination. Include such items as required notices, reports, and list of attendees at meetings.
 - 1. Prepare similar memoranda for Owner and separate contractors if coordination of their Work is required.
- C. Administrative Procedures: Coordinate scheduling and timing of required administrative procedures with other construction activities and activities of other contractors to avoid conflicts and to ensure orderly progress of the Work. Such administrative activities include, but are not limited to, the following:
 - 1. Preparation of Contractor's Construction Schedule.
 - 2. Preparation of the Schedule of Values.
 - 3. Installation and removal of temporary facilities and controls.
 - 4. Delivery and processing of submittals.
 - 5. Progress meetings.
 - 6. Preinstallation conferences.
 - 7. Project closeout activities.
 - 8. Startup and adjustment of systems.
 - 9. Project closeout activities.
- D. Conservation: Coordinate construction activities to ensure that operations are carried out with consideration given to conservation of energy, water, and materials.
 - 1. Salvage materials and equipment involved in performance of, but not actually incorporated into, the Work. Refer to other Sections for disposition of salvaged materials that are designated as Owner's property.

1.5 SUBMITTALS

- A. Coordination Drawings: Prepare Coordination Drawings if limited space availability necessitates maximum utilization of space for efficient installation of different components or if coordination is required for installation of products and materials fabricated by separate entities.
 - 1. Content: Project-specific information, drawn accurately to scale. Do not base Coordination Drawings on reproductions of the Contract Documents or standard printed data. Include the following information, as applicable:
 - a. Indicate functional and spatial relationships of components of architectural, structural, civil, mechanical, and electrical systems.
 - b. Indicate required installation sequences.
 - c. Indicate dimensions shown on the Contract Drawings and make specific note of dimensions that appear to be in conflict with submitted equipment and minimum clearance requirements. Provide alternate sketches to Architect for resolution of such conflicts. Minor dimension changes and difficult installations will not be considered changes to the Contract.
 - 2. Sheet Size: At least 8-1/2 by 11 inches but no larger than 30 by 40 inches.

CITY OF ORANGE BEACH
FIRE ADMINISTRATION BUILDING and POST OFFICE ROOF REPLACEMENTS
ISSUED 02-21-2022

3. Number of Copies: Submit two opaque copies of each submittal. Architect will return one copy.
 - a. Submit five copies where Coordination Drawings are required for operation and maintenance manuals. Architect will retain two copies; remainder will be returned.
 4. Refer to individual Sections for Coordination Drawing requirements for Work in those Sections.
- B. Key Personnel Names: Within 15 days of starting construction operations, submit a list of key personnel assignments, including superintendent and other personnel in attendance at Project site. Identify individuals and their duties and responsibilities; list addresses and telephone numbers, including home and office telephone numbers. Provide names, addresses, and telephone numbers of individuals assigned as standbys in the absence of individuals assigned to Project.
1. Post copies of list in Project meeting room, in temporary field office, and by each temporary telephone. Keep list current at all times.
- 1.6 ADMINISTRATIVE AND SUPERVISORY PERSONNEL**
- A. General: In addition to Project superintendent, provide other administrative and supervisory personnel as required for proper performance of the Work.
- 1.7 PROJECT MEETINGS**
- A. General: Schedule and conduct meetings and conferences at Project site, unless otherwise indicated.
 1. Attendees: Inform participants and others involved, and individuals whose presence is required, of date and time of each meeting. Notify Owner and Architect of scheduled meeting dates and times.
 2. Agenda: Prepare the meeting agenda. Distribute the agenda to all invited attendees.
 3. Minutes: Record significant discussions and agreements achieved. Distribute the meeting minutes to everyone concerned, including Owner and Architect, within three days of the meeting.
 - B. Preconstruction Conference: Schedule a preconstruction conference before starting construction, at a time convenient to Owner and Architect, but no later than 15 days after execution of the Agreement. Hold the conference at Project site or another convenient location. Conduct the meeting to review responsibilities and personnel assignments.
 1. Attendees: Authorized representatives of Owner, Architect, and their consultants; Contractor and its superintendent; major subcontractors; suppliers; and other concerned parties shall attend the conference. All participants at the conference shall be familiar with Project and authorized to conclude matters relating to the Work.
 2. Agenda: Discuss items of significance that could affect progress, including the following:

CITY OF ORANGE BEACH
FIRE ADMINISTRATION BUILDING and POST OFFICE ROOF REPLACEMENTS
ISSUED 02-21-2022

- a. Tentative construction schedule.
 - b. Critical work sequencing and long-lead items.
 - c. Designation of key personnel and their duties.
 - d. Procedures for processing field decisions and Change Orders.
 - e. Procedures for RFIs.
 - f. Procedures for testing and inspecting.
 - g. Procedures for processing Applications for Payment.
 - h. Distribution of the Contract Documents.
 - i. Submittal procedures.
 - j. Preparation of Record Documents.
 - k. Responsibility for temporary facilities and controls.
 - l. Office, work, and storage areas.
 - m. Equipment deliveries and priorities.
 - n. First aid.
 - o. Security.
 - p. Progress cleaning.
3. Minutes: Architect will record and distribute meeting minutes.
- C. Preinstallation Conferences: Conduct a preinstallation conference at Project site before each construction activity that requires coordination with other construction.
1. Attendees: Installer and representatives of manufacturers and fabricators involved in or affected by the installation and its coordination or integration with other materials and installations that have preceded or will follow, shall attend the meeting. Advise Architect of scheduled meeting dates.
 2. Agenda: Review progress of other construction activities and preparations for the particular activity under consideration, including requirements for the following:
 - a. The Contract Documents.
 - b. Options.
 - c. Related RFIs.
 - d. Related Change Orders.
 - e. Purchases.
 - f. Deliveries.
 - g. Submittals.
 - h. Review of mockups.
 - i. Possible conflicts.
 - j. Compatibility problems.
 - k. Time schedules.
 - l. Weather limitations.
 - m. Manufacturer's written recommendations.
 - n. Warranty requirements.
 - o. Compatibility of materials.
 - p. Acceptability of substrates.
 - q. Temporary facilities and controls.
 - r. Space and access limitations.
 - s. Regulations of authorities having jurisdiction.
 - t. Testing and inspecting requirements.
 - u. Installation procedures.

CITY OF ORANGE BEACH
FIRE ADMINISTRATION BUILDING and POST OFFICE ROOF REPLACEMENTS
ISSUED 02-21-2022

- v. Coordination with other work.
 - w. Required performance results.
 - x. Protection of adjacent work.
 - y. Protection of construction and personnel.
- 3. Record significant conference discussions, agreements, and disagreements, including required corrective measures and actions.
 - 4. Reporting: Distribute minutes of the meeting to each party present and to parties who should have been present.
 - 5. Do not proceed with installation if the conference cannot be successfully concluded. Initiate whatever actions are necessary to resolve impediments to performance of the Work and reconvene the conference at earliest feasible date.
- D. Progress Meetings: Conduct progress meetings at biweekly intervals. Coordinate dates of meetings with preparation of payment requests.
- 1. Attendees: In addition to representatives of Owner and Architect, each contractor, subcontractor, supplier, and other entity concerned with current progress or involved in planning, coordination, or performance of future activities shall be represented at these meetings. All participants at the conference shall be familiar with Project and authorized to conclude matters relating to the Work.
 - 2. Agenda: Review and correct or approve minutes of previous progress meeting. Review other items of significance that could affect progress. Include topics for discussion as appropriate to status of Project.
 - a. Contractor's Construction Schedule: Review progress since the last meeting. Determine whether each activity is on time, ahead of schedule, or behind schedule, in relation to Contractor's Construction Schedule. Determine how construction behind schedule will be expedited; secure commitments from parties involved to do so. Discuss whether schedule revisions are required to ensure that current and subsequent activities will be completed within the Contract Time.
 - 1) Review schedule for next period.
 - b. Review present and future needs of each entity present, including the following:
 - 1) Interface requirements.
 - 2) Sequence of operations.
 - 3) Status of submittals.
 - 4) Deliveries.
 - 5) Off-site fabrication.
 - 6) Access.
 - 7) Site utilization.
 - 8) Temporary facilities and controls.
 - 9) Hazards and risks.
 - 10) Progress cleaning.
 - 11) Quality and work standards.
 - 12) Status of correction of deficient items.
 - 13) Field observations.
 - 14) RFIs.

CITY OF ORANGE BEACH
FIRE ADMINISTRATION BUILDING and POST OFFICE ROOF REPLACEMENTS
ISSUED 02-21-2022

- 15) Status of proposal requests.
 - 16) Pending changes.
 - 17) Status of Change Orders.
 - 18) Pending claims and disputes.
 - 19) Documentation of information for payment requests.
3. Minutes: Architect will record and distribute to Contractor the meeting minutes.
 4. Reporting: Distribute minutes of the meeting to each party present and to parties who should have been present.
 - a. Schedule Updating: Revise Contractor's Construction Schedule after each progress meeting where revisions to the schedule have been made or recognized. Issue revised schedule concurrently with the report of each meeting.

1.8 REQUESTS FOR INTERPRETATION (RFIs)

- A. Procedure: Immediately on discovery of the need for interpretation of the Contract Documents, and if not possible to request interpretation at Project meeting, prepare and submit an RFI in the form specified.
 1. RFIs shall originate with Contractor. RFIs submitted by entities other than Contractor will be returned with no response.
 2. Coordinate and submit RFIs in a prompt manner so as to avoid delays in Contractor's work or work of subcontractors.
- B. Content of the RFI: Include a detailed, legible description of item needing interpretation and the following:
 1. Project name.
 2. Date.
 3. Name of Contractor.
 4. Name of Architect.
 5. RFI number, numbered sequentially.
 6. Specification Section number and title and related paragraphs, as appropriate.
 7. Drawing number and detail references, as appropriate.
 8. Field dimensions and conditions, as appropriate.
 9. Contractor's suggested solution(s). If Contractor's solution(s) impact the Contract Time or the Contract Sum, Contractor shall state impact in the RFI.
 10. Contractor's signature.
 11. Attachments: Include drawings, descriptions, measurements, photos, Product Data, Shop Drawings, and other information necessary to fully describe items needing interpretation.
 - a. Supplementary drawings prepared by Contractor shall include dimensions, thicknesses, structural grid references, and details of affected materials, assemblies, and attachments.
- C. Hard-Copy RFIs: CSI Form 13.2A.
 1. Identify each page of attachments with the RFI number and sequential page number.

CITY OF ORANGE BEACH
FIRE ADMINISTRATION BUILDING and POST OFFICE ROOF REPLACEMENTS
ISSUED 02-21-2022

- D. Architect's Action: Architect will review each RFI, determine action required, and return it. Allow seven working days for Architect's response for each RFI. RFIs received after 1:00 p.m. will be considered as received the following working day.
1. The following RFIs will be returned without action:
 - a. Requests for approval of submittals.
 - b. Requests for approval of substitutions.
 - c. Requests for coordination information already indicated in the Contract Documents.
 - d. Requests for adjustments in the Contract Time or the Contract Sum.
 - e. Requests for interpretation of Architect's actions on submittals.
 - f. Incomplete RFIs or RFIs with numerous errors.
 2. Architect's action may include a request for additional information, in which case Architect's time for response will start again.
 3. Architect's action on RFIs that may result in a change to the Contract Time or the Contract Sum may be eligible for Contractor to submit Change Proposal according to Division 01 Section "Contract Modification Procedures."
 - a. If Contractor believes the RFI response warrants change in the Contract Time or the Contract Sum, notify Architect in writing within 10 days of receipt of the RFI response.
- E. On receipt of Architect's action, update the RFI log and immediately distribute the RFI response to affected parties. Review response and notify Architect within seven days if Contractor disagrees with response.
- F. RFI Log: Prepare, maintain, and submit a tabular log of RFIs organized by the RFI number. Submit log weekly. Include the following:
1. Project name.
 2. Name and address of Contractor.
 3. Name and address of Architect.
 4. RFI number including RFIs that were dropped and not submitted.
 5. RFI description.
 6. Date the RFI was submitted.
 7. Date Architect's response was received.
 8. Identification of related Minor Change in the Work, Construction Change Directive, and Proposal Request, as appropriate.
 9. Identification of related Field Order, Work Change Directive, and Proposal Request, as appropriate.

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION (Not Used)

END OF SECTION 013100

CITY OF ORANGE BEACH
FIRE ADMINISTRATION BUILDING and POST OFFICE ROOF REPLACEMENTS
ISSUED 02-21-2022

SECTION 013200 - CONSTRUCTION PROGRESS DOCUMENTATION

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. This Section includes administrative and procedural requirements for documenting the progress of construction during performance of the Work, including the following:
 - 1. Preliminary Construction Schedule.
 - 2. Contractor's Construction Schedule.
 - 3. Daily construction reports.
 - 4. Material location reports.
 - 5. Field condition reports.
- B. Related Sections include the following:
 - 1. Division 01 Section "Payment Procedures" for submitting the Schedule of Values.
 - 2. Division 01 Section "Project Management and Coordination" for submitting and distributing meeting and conference minutes.
 - 3. Division 01 Section "Submittal Procedures" for submitting schedules and reports.
 - 4. Division 01 Section "Quality Requirements" for submitting a schedule of tests and inspections.

1.3 DEFINITIONS

- A. Activity: A discrete part of a project that can be identified for planning, scheduling, monitoring, and controlling the construction project. Activities included in a construction schedule consume time and resources.
 - 1. Critical activities are activities on the critical path. They must start and finish on the planned early start and finish times.
 - 2. Predecessor Activity: An activity that precedes another activity in the network.
 - 3. Successor Activity: An activity that follows another activity in the network.
- B. Cost Loading: The allocation of the Schedule of Values for the completion of an activity as scheduled. The sum of costs for all activities must equal the total Contract Sum, unless otherwise approved by Architect.
- C. CPM: Critical path method, which is a method of planning and scheduling a construction project where activities are arranged based on activity relationships. Network calculations determine when activities can be performed and the critical path of Project.
- D. Critical Path: The longest connected chain of interdependent activities through the network schedule that establishes the minimum overall Project duration and contains no float.

CITY OF ORANGE BEACH
FIRE ADMINISTRATION BUILDING and POST OFFICE ROOF REPLACEMENTS
ISSUED 02-21-2022

- E. Event: The starting or ending point of an activity.
- F. Float: The measure of leeway in starting and completing an activity.
 - 1. Float time is not for the exclusive use or benefit of either Owner or Contractor, but is a jointly owned, expiring Project resource available to both parties as needed to meet schedule milestones and Contract completion date.
 - 2. Free float is the amount of time an activity can be delayed without adversely affecting the early start of the successor activity.
 - 3. Total float is the measure of leeway in starting or completing an activity without adversely affecting the planned Project completion date.
- G. Fragnet: A partial or fragmentary network that breaks down activities into smaller activities for greater detail.
- H. Major Area: A story of construction, a separate building, or a similar significant construction element.
- I. Milestone: A key or critical point in time for reference or measurement.
- J. Network Diagram: A graphic diagram of a network schedule, showing activities and activity relationships.
- K. Resource Loading: The allocation of manpower and equipment necessary for the completion of an activity as scheduled.

1.4 SUBMITTALS

- A. Preliminary Construction Schedule: Submit two opaque copies.
 - 1. Approval of cost-loaded preliminary construction schedule will not constitute approval of Schedule of Values for cost-loaded activities.
- B. Preliminary Network Diagram: Submit two opaque copies, large enough to show entire network for entire construction period. Show logic ties for activities.
- C. Contractor's Construction Schedule: Submit two opaque copies of initial schedule, large enough to show entire schedule for entire construction period.
 - 1. Submit an electronic copy of schedule, using software indicated, on CD-R, and labeled to comply with requirements for submittals. Include type of schedule (Initial or Updated) and date on label.
- D. CPM Reports: Concurrent with CPM schedule, submit three copies of each of the following computer-generated reports. Format for each activity in reports shall contain activity number, activity description, cost and resource loading, original duration, remaining duration, early start date, early finish date, late start date, late finish date, and total float in calendar days.
 - 1. Activity Report: List of all activities sorted by activity number and then early start date, or actual start date if known.
 - 2. Logic Report: List of preceding and succeeding activities for all activities, sorted in ascending order by activity number and then early start date, or actual start date if known.
 - 3. Total Float Report: List of all activities sorted in ascending order of total float.

CITY OF ORANGE BEACH
FIRE ADMINISTRATION BUILDING and POST OFFICE ROOF REPLACEMENTS
ISSUED 02-21-2022

- 4. Earnings Report: Compilation of Contractor's total earnings from the Notice to Proceed until most recent Application for Payment.
- E. Daily Construction Reports: Submit two copies at weekly intervals.
- F. Material Location Reports: Submit two copies at weekly intervals.
- G. Field Condition Reports: Submit two copies at time of discovery of differing conditions.

1.5 COORDINATION

- A. Coordinate preparation and processing of schedules and reports with performance of construction activities and with scheduling and reporting of separate contractors.
- B. Coordinate Contractor's Construction Schedule with the Schedule of Values, list of subcontracts, Submittals Schedule, progress reports, payment requests, and other required schedules and reports.
 - 1. Secure time commitments for performing critical elements of the Work from parties involved.
 - 2. Coordinate each construction activity in the network with other activities and schedule them in proper sequence.

PART 2 - PRODUCTS

2.1 CONTRACTOR'S CONSTRUCTION SCHEDULE, GENERAL

- A. Procedures: Comply with procedures contained in AGC's "Construction Planning & Scheduling."
- B. Time Frame: Extend schedule from date established for the Notice to Proceed to date of Substantial Completion.
 - 1. Contract completion date shall not be changed by submission of a schedule that shows an early completion date, unless specifically authorized by Change Order.
- C. Activities: Treat each story or separate area as a separate numbered activity for each principal element of the Work. Comply with the following:
 - 1. Activity Duration: Define activities so no activity is longer than 20 days, unless specifically allowed by Architect.
 - 2. Procurement Activities: Include procurement process activities for the following long lead items and major items, requiring a cycle of more than 60 days, as separate activities in schedule. Procurement cycle activities include, but are not limited to, submittals, approvals, purchasing, fabrication, and delivery.
 - 3. Submittal Review Time: Include review and resubmittal times indicated in Division 01 Section "Submittal Procedures" in schedule. Coordinate submittal review times in Contractor's Construction Schedule with Submittals Schedule.
 - 4. Startup and Testing Time: Include activity line items for startup and testing.
 - 5. Substantial Completion: Indicate completion in advance of date established for Substantial Completion, and allow time for Architect's administrative procedures necessary for certification of Substantial Completion.
- D. Milestones: Include milestones indicated in the Contract Documents in schedule, including, but not limited to, the Notice to Proceed, Substantial Completion, and Final Completion.

CITY OF ORANGE BEACH
FIRE ADMINISTRATION BUILDING and POST OFFICE ROOF REPLACEMENTS
ISSUED 02-21-2022

- E. Cost Correlation: At the head of schedule, provide a cost correlation line, indicating planned and actual costs. On the line, show dollar volume of the Work performed as of dates used for preparation of payment requests.
1. Refer to Division 01 Section "Payment Procedures" for cost reporting and payment procedures.

2.2 PRELIMINARY CONSTRUCTION SCHEDULE

- A. Bar-Chart Schedule: Submit preliminary horizontal bar-chart-type construction schedule within seven days of date established for the Notice to Proceed.
- B. Preparation: Indicate each significant construction activity separately. Identify first workday of each week with a continuous vertical line. Outline significant construction activities for first 60 days of construction. Include skeleton diagram for the remainder of the Work and a cash requirement prediction based on indicated activities.

2.3 CONTRACTOR'S CONSTRUCTION SCHEDULE (CPM SCHEDULE)

- A. General: Prepare network diagrams using AON (activity-on-node) format.
- B. CPM Schedule: Prepare Contractor's Construction Schedule using a computerized, cost- and resource-loaded, time-scaled CPM network analysis diagram for the Work.
1. Develop network diagram in sufficient time to submit CPM schedule so it can be accepted for use no later than [30] days after date established for the Notice to Proceed.
 - a. Failure to include any work item required for performance of this Contract shall not excuse Contractor from completing all work within applicable completion dates, regardless of Architect's approval of the schedule.
 2. Conduct educational workshops to train and inform key Project personnel, including subcontractors' personnel, in proper methods of providing data and using CPM schedule information.
 3. Establish procedures for monitoring and updating CPM schedule and for reporting progress. Coordinate procedures with progress meeting and payment request dates.
 4. Use "one workday" as the unit of time. Include list of nonworking days and holidays incorporated into the schedule.
- C. CPM Schedule Preparation: Prepare a list of all activities required to complete the Work. Using the preliminary network diagram, prepare a skeleton network to identify probable critical paths.
1. Activities: Indicate the estimated time duration, sequence requirements, and relationship of each activity in relation to other activities. Include estimated time frames for the following activities:
 - a. Preparation and processing of submittals.
 - b. Mobilization and demobilization.
 - c. Purchase of materials.
 - d. Delivery.

CITY OF ORANGE BEACH
FIRE ADMINISTRATION BUILDING and POST OFFICE ROOF REPLACEMENTS
ISSUED 02-21-2022

- e. Fabrication.
 - f. Utility interruptions.
 - g. Installation.
 - h. Testing.
2. Critical Path Activities: Identify critical path activities, including those for interim completion dates. Scheduled start and completion dates shall be consistent with Contract milestone dates.
 3. Processing: Process data to produce output data on a computer-drawn, time-scaled network. Revise data, reorganize activity sequences, and reproduce as often as necessary to produce the CPM schedule within the limitations of the Contract Time.
 4. Format: Mark the critical path. Locate the critical path near center of network; locate paths with most float near the edges.
 - a. Subnetworks on separate sheets are permissible for activities clearly off the critical path.
- D. Initial Issue of Schedule: Prepare initial network diagram from a list of straight "early start-total float" sort. Identify critical activities. Prepare tabulated reports showing the following:
1. Contractor or subcontractor and the Work or activity.
 2. Description of activity.
 3. Principal events of activity.
 4. Immediate preceding and succeeding activities.
 5. Early and late start dates.
 6. Early and late finish dates.
 7. Activity duration in workdays.
 8. Total float or slack time.
 9. Average size of workforce.
 10. Dollar value of activity (coordinated with the Schedule of Values).
- E. Schedule Updating: Concurrent with making revisions to schedule, prepare tabulated reports showing the following:
1. Identification of activities that have changed.
 2. Changes in early and late start dates.
 3. Changes in early and late finish dates.
 4. Changes in activity durations in workdays.
 5. Changes in the critical path.
 6. Changes in total float or slack time.
 7. Changes in the Contract Time.
- F. Value Summaries: Prepare two cumulative value lists, sorted by finish dates.
1. In first list, tabulate activity number, early finish date, dollar value, and cumulative dollar value.
 2. In second list, tabulate activity number, late finish date, dollar value, and cumulative dollar value.
 3. In subsequent issues of both lists, substitute actual finish dates for activities completed as of list date.

CITY OF ORANGE BEACH
FIRE ADMINISTRATION BUILDING and POST OFFICE ROOF REPLACEMENTS
ISSUED 02-21-2022

4. Prepare list for ease of comparison with payment requests; coordinate timing with progress meetings.
 - a. In both value summary lists, tabulate "actual percent complete" and "cumulative value completed" with total at bottom.
 - b. Submit value summary printouts one week before each regularly scheduled progress meeting.

2.4 REPORTS

- A. Daily Construction Reports: Prepare a daily construction report recording the following information concerning events at Project site:
 1. List of subcontractors at Project site.
 2. Approximate count of personnel at Project site.
 3. Equipment at Project site.
 4. Material deliveries.
 5. High and low temperatures and general weather conditions.
 6. Accidents.
 7. Meetings and significant decisions.
 8. Unusual events (refer to special reports).
 9. Stoppages, delays, shortages, and losses.
 10. Emergency procedures.
 11. Orders and requests of authorities having jurisdiction.
 12. Change Orders received and implemented.
 13. Construction Change Directives received and implemented.
 14. Services connected and disconnected.
 15. Equipment or system tests and startups.
 16. Partial Completions and occupancies.
 17. Substantial Completions authorized.
- B. Material Location Reports: At weekly intervals, prepare and submit a comprehensive list of materials delivered to and stored at Project site. List shall be cumulative, showing materials previously reported plus items recently delivered. Include with list a statement of progress on and delivery dates for materials or items of equipment fabricated or stored away from Project site.
- C. Field Condition Reports: Immediately on discovery of a difference between field conditions and the Contract Documents, prepare and submit a detailed report. Submit with a request for interpretation on CSI Form 13.2A. Include a detailed description of the differing conditions, together with recommendations for changing the Contract Documents.

PART 3 - EXECUTION

3.1 CONTRACTOR'S CONSTRUCTION SCHEDULE

- A. Contractor's Construction Schedule Updating: At monthly intervals, update schedule to reflect actual construction progress and activities. Issue schedule one week before each regularly scheduled progress meeting.

CITY OF ORANGE BEACH
FIRE ADMINISTRATION BUILDING and POST OFFICE ROOF REPLACEMENTS
ISSUED 02-21-2022

1. Revise schedule immediately after each meeting or other activity where revisions have been recognized or made. Issue updated schedule concurrently with the report of each such meeting.
 2. Include a report with updated schedule that indicates every change, including, but not limited to, changes in logic, durations, actual starts and finishes, and activity durations.
 3. As the Work progresses, indicate Actual Completion percentage for each activity.
- B. Distribution: Distribute copies of approved schedule to Architect Owner, separate contractors, testing and inspecting agencies, and other parties identified by Contractor with a need-to-know schedule responsibility.
1. Post copies in Project meeting rooms and temporary field offices.
 2. When revisions are made, distribute updated schedules to the same parties and post in the same locations. Delete parties from distribution when they have completed their assigned portion of the Work and are no longer involved in performance of construction activities.

END OF SECTION 013200

CITY OF ORANGE BEACH
FIRE ADMINISTRATION BUILDING and POST OFFICE ROOF REPLACEMENTS
ISSUED 02-21-2022

SECTION 013300 - SUBMITTAL PROCEDURES

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. This Section includes administrative and procedural requirements for submitting Shop Drawings, Product Data, Samples, and other submittals.
- B. Related Sections include the following:
 - 1. Division 01 Section "Payment Procedures" for submitting Applications for Payment and the Schedule of Values.
 - 2. Division 01 Section "Project Management and Coordination" for submitting and distributing meeting and conference minutes and for submitting Coordination Drawings.
 - 3. Division 01 Section "Construction Progress Documentation" for submitting schedules and reports, including Contractor's Construction Schedule and the Submittals Schedule.
 - 4. Division 01 Section "Quality Requirements" for submitting test and inspection reports and for mockup requirements.
 - 5. Division 01 Section "Closeout Procedures" for submitting warranties.
 - 6. Division 01 Section "Project Record Documents" for submitting Record Drawings, Record Specifications, and Record Product Data.
 - 7. Division 01 Section "Operation and Maintenance Data" for submitting operation and maintenance manuals.
 - 8. Divisions 02 through 49 Sections for specific requirements for submittals in those Sections.

1.3 DEFINITIONS

- A. Action Submittals: Written and graphic information that requires Architect's responsive action.
- B. Informational Submittals: Written information that does not require Architect's responsive action. Submittals may be rejected for not complying with requirements.

1.4 SUBMITTAL PROCEDURES

- A. Coordination: Coordinate preparation and processing of submittals with performance of construction activities.
 - 1. Coordinate each submittal with fabrication, purchasing, testing, delivery, other submittals, and related activities that require sequential activity.

CITY OF ORANGE BEACH
FIRE ADMINISTRATION BUILDING and POST OFFICE ROOF REPLACEMENTS
ISSUED 02-21-2022

2. Coordinate transmittal of different types of submittals for related parts of the Work so processing will not be delayed because of need to review submittals concurrently for coordination.
 - a. Architect reserves the right to withhold action on a submittal requiring coordination with other submittals until related submittals are received.
- B. Processing Time: Allow enough time for submittal review, including time for resubmittals, as follows. Time for review shall commence on Architect's receipt of submittal. No extension of the Contract Time will be authorized because of failure to transmit submittals enough in advance of the Work to permit processing, including resubmittals.
 1. Initial Review: Allow 15 days for initial review of each submittal. Allow additional time if coordination with subsequent submittals is required. Architect will advise Contractor when a submittal being processed must be delayed for coordination.
 2. Intermediate Review: If intermediate submittal is necessary, process it in same manner as initial submittal.
 3. Resubmittal Review: Allow 15 days for review of each resubmittal.
- C. Identification: Place a permanent label or title block on each submittal for identification.
 1. Indicate name of firm or entity that prepared each submittal on label or title block.
 2. Provide a space approximately 6 by 8 inches on label or beside title block to record Contractor's review and approval markings and action taken by Architect.
 3. Include the following information on label for processing and recording action taken:
 - a. Project name.
 - b. Date.
 - c. Name and address of Architect.
 - d. Name and address of Contractor.
 - e. Name and address of subcontractor.
 - f. Name and address of supplier.
 - g. Name of manufacturer.
 - h. Submittal number or other unique identifier, including revision identifier.
 - 1) Submittal number shall use Specification Section number followed by a decimal point and then a sequential number (e.g., 061000.01). Resubmittals shall include an alphabetic suffix after another decimal point (e.g., 061000.01.A).
 - i. Number and title of appropriate Specification Section.
 - j. Drawing number and detail references, as appropriate.
 - k. Location(s) where product is to be installed, as appropriate.
 - l. Other necessary identification.
- D. Deviations: Highlight, encircle, or otherwise specifically identify deviations from the Contract Documents on submittals.
- E. Additional Copies: Unless additional copies are required for final submittal, and unless Architect observes noncompliance with provisions in the Contract Documents, initial submittal may serve as final submittal.

CITY OF ORANGE BEACH
FIRE ADMINISTRATION BUILDING and POST OFFICE ROOF REPLACEMENTS
ISSUED 02-21-2022

1. Submit one copy of submittal to concurrent reviewer in addition to specified number of copies to Architect.
 2. Additional copies submitted for maintenance manuals will not be marked with action taken and will be returned.
- F. Transmittal: Package each submittal individually and appropriately for transmittal and handling. Transmit each submittal using a transmittal form. Architect will discard submittals received from sources other than Contractor.
1. Transmittal Form: Use AIA Document G810.
 2. On an attached separate sheet, prepared on Contractor's letterhead, record relevant information, requests for data, revisions other than those requested by Architect on previous submittals, and deviations from requirements in the Contract Documents, including minor variations and limitations. Include same label information as related submittal.
- G. Resubmittals: Make resubmittals in same form and number of copies as initial submittal.
1. Note date and content of previous submittal.
 2. Note date and content of revision in label or title block and clearly indicate extent of revision.
 3. Resubmit submittals until they are marked "NO EXCEPTIONS TAKEN" or "MAKE CORRECTION NOTED."
- H. Distribution: Furnish copies of final submittals to manufacturers, subcontractors, suppliers, fabricators, installers, authorities having jurisdiction, and others as necessary for performance of construction activities. Show distribution on transmittal forms.
- I. Use for Construction: Use only final submittals with mark indicating "NO EXCEPTIONS TAKEN" or "MAKE CORRECTION NOTED" taken by Architect.

PART 2 - PRODUCTS

2.1 ACTION SUBMITTALS

- A. General: Prepare and submit Action Submittals required by individual Specification Sections.
1. Submit electronic submittals directly to extranet specifically established for Project.
- B. Product Data: Collect information into a single submittal for each element of construction and type of product or equipment.
1. If information must be specially prepared for submittal because standard printed data are not suitable for use, submit as Shop Drawings, not as Product Data.
 2. Mark each copy of each submittal to show which products and options are applicable.
 3. Include the following information, as applicable:
 - a. Manufacturer's written recommendations.
 - b. Manufacturer's product specifications.
 - c. Manufacturer's installation instructions.

CITY OF ORANGE BEACH
FIRE ADMINISTRATION BUILDING and POST OFFICE ROOF REPLACEMENTS
ISSUED 02-21-2022

- d. Standard color charts.
 - e. Manufacturer's catalog cuts.
 - f. Wiring diagrams showing factory-installed wiring.
 - g. Printed performance curves.
 - h. Operational range diagrams.
 - i. Mill reports.
 - j. Standard product operation and maintenance manuals.
 - k. Compliance with specified referenced standards.
 - l. Testing by recognized testing agency.
 - m. Application of testing agency labels and seals.
 - n. Notation of coordination requirements.
4. Submit Product Data before or concurrent with Samples.
5. Number of Copies: Submit three copies of Product Data, unless otherwise indicated. Architect will return two copies. Mark up and retain one returned copy as a Project Record Document.
- C. Shop Drawings: Prepare Project-specific information, drawn accurately to scale. Do not base Shop Drawings on reproductions of the Contract Documents or standard printed data, unless submittal of Architect's CAD Drawings are otherwise permitted.
1. Preparation: Fully illustrate requirements in the Contract Documents. Include the following information, as applicable:
- a. Dimensions.
 - b. Identification of products.
 - c. Fabrication and installation drawings.
 - d. Roughing-in and setting diagrams.
 - e. Wiring diagrams showing field-installed wiring, including power, signal, and control wiring.
 - f. Shopwork manufacturing instructions.
 - g. Templates and patterns.
 - h. Schedules.
 - i. Design calculations.
 - j. Compliance with specified standards.
 - k. Notation of coordination requirements.
 - l. Notation of dimensions established by field measurement.
 - m. Relationship to adjoining construction clearly indicated.
 - n. Seal and signature of professional engineer if specified.
 - o. Wiring Diagrams: Differentiate between manufacturer-installed and field-installed wiring.
2. Sheet Size: Except for templates, patterns, and similar full-size drawings, submit Shop Drawings on sheets at least 8-1/2 by 11 inches but no larger than 30 by 40 inches.
3. Number of Copies: Submit three opaque copies of each submittal, unless copies are required for operation and maintenance manuals. Submit five copies where copies are required for operation and maintenance manuals. Architect will retain two copies; remainder will be returned.

CITY OF ORANGE BEACH
FIRE ADMINISTRATION BUILDING and POST OFFICE ROOF REPLACEMENTS
ISSUED 02-21-2022

- D. Samples: Submit Samples for review of kind, color, pattern, and texture for a check of these characteristics with other elements and for a comparison of these characteristics between submittal and actual component as delivered and installed.
1. Transmit Samples that contain multiple, related components such as accessories together in one submittal package.
 2. Identification: Attach label on unexposed side of Samples that includes the following:
 - a. Generic description of Sample.
 - b. Product name and name of manufacturer.
 - c. Sample source.
 - d. Number and title of appropriate Specification Section.
 3. Disposition: Maintain sets of approved Samples at Project site, available for quality-control comparisons throughout the course of construction activity. Sample sets may be used to determine final acceptance of construction associated with each set.
 - a. Samples not incorporated into the Work, or otherwise designated as Owner's property, are the property of Contractor.
 4. Samples for Initial Selection: Submit manufacturer's color charts consisting of units or sections of units showing the full range of colors, textures, and patterns available.
 - a. Number of Samples: Submit one full set(s) of available choices where color, pattern, texture, or similar characteristics are required to be selected from manufacturer's product line. Architect will return submittal with options selected.
- E. Product Schedule or List: As required in individual Specification Sections, prepare a written summary indicating types of products required for the Work and their intended location. Include the following information in tabular form:
1. Type of product. Include unique identifier for each product.
 2. Number and name of room or space.
 3. Location within room or space.
 4. Number of Copies: Submit three copies of product schedule or list, unless otherwise indicated. Architect will return two copies.
- F. Submittals Schedule: Comply with requirements specified in Division 01 Section "Construction Progress Documentation."
- G. Application for Payment: Comply with requirements specified in Division 01 Section "Payment Procedures."
- H. Schedule of Values: Comply with requirements specified in Division 01 Section "Payment Procedures."
- I. Subcontract List: Prepare a written summary identifying individuals or firms proposed for each portion of the Work, including those who are to furnish products or equipment fabricated to a special design. Include the following information in tabular form:

CITY OF ORANGE BEACH
FIRE ADMINISTRATION BUILDING and POST OFFICE ROOF REPLACEMENTS
ISSUED 02-21-2022

1. Name, address, and telephone number of entity performing subcontract or supplying products.
2. Number and title of related Specification Section(s) covered by subcontract.
3. Drawing number and detail references, as appropriate, covered by subcontract.
4. Number of Copies: Submit three copies of subcontractor list, unless otherwise indicated. Architect will return two copies.
 - a. Mark up and retain one returned copy as a Project Record Document.

2.2 INFORMATIONAL SUBMITTALS

- A. General: Prepare and submit Informational Submittals required by other Specification Sections.
 1. Number of Copies: Submit two copies of each submittal, unless otherwise indicated. Architect will not return copies.
 2. Certificates and Certifications: Provide a notarized statement that includes signature of entity responsible for preparing certification. Certificates and certifications shall be signed by an officer or other individual authorized to sign documents on behalf of that entity.
 3. Test and Inspection Reports: Comply with requirements specified in Division 01 Section "Quality Requirements."
- B. Coordination Drawings: Comply with requirements specified in Division 01 Section "Project Management and Coordination."
- C. Contractor's Construction Schedule: Comply with requirements specified in Division 01 Section "Construction Progress Documentation."
- D. Qualification Data: Prepare written information that demonstrates capabilities and experience of firm or person. Include lists of completed projects with project names and addresses, names and addresses of architects and owners, and other information specified.
- E. Welding Certificates: Prepare written certification that welding procedures and personnel comply with requirements in the Contract Documents. Submit record of Welding Procedure Specification (WPS) and Procedure Qualification Record (PQR) on AWS forms. Include names of firms and personnel certified.
- F. Installer Certificates: Prepare written statements on manufacturer's letterhead certifying that Installer complies with requirements in the Contract Documents and, where required, is authorized by manufacturer for this specific Project.
- G. Manufacturer Certificates: Prepare written statements on manufacturer's letterhead certifying that manufacturer complies with requirements in the Contract Documents. Include evidence of manufacturing experience where required.
- H. Product Certificates: Prepare written statements on manufacturer's letterhead certifying that product complies with requirements in the Contract Documents.
- I. Material Certificates: Prepare written statements on manufacturer's letterhead certifying that material complies with requirements in the Contract Documents.
- J. Material Test Reports: Prepare reports written by a qualified testing agency, on testing agency's standard form, indicating and interpreting test results of material for compliance with requirements in the Contract Documents.

CITY OF ORANGE BEACH
FIRE ADMINISTRATION BUILDING and POST OFFICE ROOF REPLACEMENTS
ISSUED 02-21-2022

- K. Product Test Reports: Prepare written reports indicating current product produced by manufacturer complies with requirements in the Contract Documents. Base reports on evaluation of tests performed by manufacturer and witnessed by a qualified testing agency, or on comprehensive tests performed by a qualified testing agency.
- L. Research/Evaluation Reports: Prepare written evidence, from a model code organization acceptable to authorities having jurisdiction, that product complies with building code in effect for Project. Include the following information:
 - 1. Name of evaluation organization.
 - 2. Date of evaluation.
 - 3. Time period when report is in effect.
 - 4. Product and manufacturers' names.
 - 5. Description of product.
 - 6. Test procedures and results.
 - 7. Limitations of use.
- M. Schedule of Tests and Inspections: Comply with requirements specified in Division 01 Section "Quality Requirements."
- N. Preconstruction Test Reports: Prepare reports written by a qualified testing agency, on testing agency's standard form, indicating and interpreting results of tests performed before installation of product, for compliance with performance requirements in the Contract Documents.
- O. Compatibility Test Reports: Prepare reports written by a qualified testing agency, on testing agency's standard form, indicating and interpreting results of compatibility tests performed before installation of product. Include written recommendations for primers and substrate preparation needed for adhesion.
- P. Field Test Reports: Prepare reports written by a qualified testing agency, on testing agency's standard form, indicating and interpreting results of field tests performed either during installation of product or after product is installed in its final location, for compliance with requirements in the Contract Documents.
- Q. Maintenance Data: Prepare written and graphic instructions and procedures for operation and normal maintenance of products and equipment. Comply with requirements specified in Division 01 Section "Operation and Maintenance Data."
- R. Design Data: Prepare written and graphic information, including, but not limited to, performance and design criteria, list of applicable codes and regulations, and calculations. Include list of assumptions and other performance and design criteria and a summary of loads. Include load diagrams if applicable. Provide name and version of software, if any, used for calculations. Include page numbers.
- S. Manufacturer's Instructions: Prepare written or published information that documents manufacturer's recommendations, guidelines, and procedures for installing or operating a product or equipment. Include name of product and name, address, and telephone number of manufacturer. Include the following, as applicable:
 - 1. Preparation of substrates.
 - 2. Required substrate tolerances.
 - 3. Sequence of installation or erection.
 - 4. Required installation tolerances.
 - 5. Required adjustments.

CITY OF ORANGE BEACH
FIRE ADMINISTRATION BUILDING and POST OFFICE ROOF REPLACEMENTS
ISSUED 02-21-2022

6. Recommendations for cleaning and protection.
- T. Manufacturer's Field Reports: Prepare written information documenting factory-authorized service representative's tests and inspections. Include the following, as applicable:
1. Name, address, and telephone number of factory-authorized service representative making report.
 2. Statement on condition of substrates and their acceptability for installation of product.
 3. Statement that products at Project site comply with requirements.
 4. Summary of installation procedures being followed, whether they comply with requirements and, if not, what corrective action was taken.
 5. Results of operational and other tests and a statement of whether observed performance complies with requirements.
 6. Statement whether conditions, products, and installation will affect warranty.
 7. Other required items indicated in individual Specification Sections.
- U. Insurance Certificates and Bonds: Prepare written information indicating current status of insurance or bonding coverage. Include name of entity covered by insurance or bond, limits of coverage, amounts of deductibles, if any, and term of the coverage.
- V. Material Safety Data Sheets (MSDSs): Submit information directly to Owner; do not submit to Architect.
1. Architect will not review submittals that include MSDSs and will return the entire submittal for resubmittal.

PART 3 - EXECUTION

3.1 CONTRACTOR'S REVIEW

- A. Review each submittal and check for coordination with other Work of the Contract and for compliance with the Contract Documents. Note corrections and field dimensions. Mark with approval stamp before submitting to Architect.
- B. Approval Stamp: Stamp each submittal with a uniform, approval stamp. Include Project name and location, submittal number, Specification Section title and number, name of reviewer, date of Contractor's approval, and statement certifying that submittal has been reviewed, checked, and approved for compliance with the Contract Documents.

3.2 ARCHITECT'S/ ACTION

- A. General: Architect will not review submittals that do not bear Contractor's approval stamp and will return them without action.
- B. Action Submittals: Architect will review each submittal, make marks to indicate corrections or modifications required, and return it. Architect will stamp each submittal with an action stamp and will mark stamp appropriately to indicate action taken, as follows:
 1. NO EXCEPTION TAKEN:

CITY OF ORANGE BEACH
FIRE ADMINISTRATION BUILDING and POST OFFICE ROOF REPLACEMENTS
ISSUED 02-21-2022

- a. The submittal in general conforms to the design concept of the project and information given in the contract documents.
 - b. No re-submittal required.
2. MAKE CORRECTIONS NOTED:
- a. The submittal in general conforms to the design concept of the project and information given in the contract documents, however minor non-compliances have been found and noted.
 - b. No re-submittal required, provided noted non-compliances are incorporated into the submittal.
3. REVISE AND RESUBMIT:
- a. The submittal has non-compliant information which has been noted.
 - b. The Contractor is required to correct non-compliant information and review the submittal in its entirety.
 - c. Re-submittal is required.
4. REJECTED:
- a. The submittal is incorrect in either form or content.
 - b. The submittal is a substitution.
 - c. Submit the proper information.
- C. Informational Submittals: Architect will review each submittal and will not return it, or will return it if it does not comply with requirements. Architect will forward each submittal to appropriate party.
- D. Partial submittals are not acceptable, will be considered nonresponsive, and will be returned without review.
- E. Submittals not required by the Contract Documents may not be reviewed and may be discarded.

END OF SECTION 013300

SECTION 014000 - QUALITY REQUIREMENTS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. This Section includes administrative and procedural requirements for quality assurance and quality control.
- B. Testing and inspecting services are required to verify compliance with requirements specified or indicated. These services do not relieve Contractor of responsibility for compliance with the Contract Document requirements.
 - 1. Specific quality-assurance and -control requirements for individual construction activities are specified in the Sections that specify those activities. Requirements in those Sections may also cover production of standard products.
 - 2. Specified tests, inspections, and related actions do not limit Contractor's other quality-assurance and -control procedures that facilitate compliance with the Contract Document requirements.
 - 3. Requirements for Contractor to provide quality-assurance and -control services required by Architect, Owner, or authorities having jurisdiction are not limited by provisions of this Section.
- C. Related Sections include the following:
 - 1. Division 01 Section "Allowances" for testing and inspecting allowances.
 - 2. Division 01 Section "Construction Progress Documentation" for developing a schedule of required tests and inspections.
 - 3. Division 01 Section "Cutting and Patching" for repair and restoration of construction disturbed by testing and inspecting activities.
 - 4. Divisions 02 through 49 Sections for specific test and inspection requirements.

1.3 DEFINITIONS

- A. Quality-Assurance Services: Activities, actions, and procedures performed before and during execution of the Work to guard against defects and deficiencies and substantiate that proposed construction will comply with requirements.
- B. Quality-Control Services: Tests, inspections, procedures, and related actions during and after execution of the Work to evaluate that actual products incorporated into the Work and completed construction comply with requirements. Services do not include contract enforcement activities performed by Architect.
- C. Mockups: Full-size, physical assemblies that are constructed on-site. Mockups are used to verify selections made under sample submittals, to demonstrate aesthetic effects and, where indicated, qualities of materials and execution, and to review construction, coordination, testing, or operation; they are not Samples. Approved mockups establish the standard by which the Work will be judged.

CITY OF ORANGE BEACH
FIRE ADMINISTRATION BUILDING and POST OFFICE ROOF REPLACEMENTS
ISSUED 02-21-2022

- D. Laboratory Mockups: Full-size, physical assemblies that are constructed at testing facility to verify performance characteristics.
- E. Preconstruction Testing: Tests and inspections that are performed specifically for the Project before products and materials are incorporated into the Work to verify performance or compliance with specified criteria.
- F. Product Testing: Tests and inspections that are performed by an NRTL, an NVLAP, or a testing agency qualified to conduct product testing and acceptable to authorities having jurisdiction, to establish product performance and compliance with industry standards.
- G. Source Quality-Control Testing: Tests and inspections that are performed at the source, i.e., plant, mill, factory, or shop.
- H. Field Quality-Control Testing: Tests and inspections that are performed on-site for installation of the Work and for completed Work.
- I. Testing Agency: An entity engaged to perform specific tests, inspections, or both. Testing laboratory shall mean the same as testing agency.
- J. Installer/Applicator/Erector: Contractor or another entity engaged by Contractor as an employee, Subcontractor, or Sub-subcontractor, to perform a particular construction operation, including installation, erection, application, and similar operations.
 - 1. Using a term such as "carpentry" does not imply that certain construction activities must be performed by accredited or unionized individuals of a corresponding generic name, such as "carpenter." It also does not imply that requirements specified apply exclusively to tradespeople of the corresponding generic name.
- K. Experienced: When used with an entity, "experienced" means having successfully completed a minimum of five previous projects similar in size and scope to this Project; being familiar with special requirements indicated; and having complied with requirements of authorities having jurisdiction.

1.4 CONFLICTING REQUIREMENTS

- A. General: If compliance with two or more standards is specified and the standards establish different or conflicting requirements for minimum quantities or quality levels, comply with the most stringent requirement. Refer uncertainties and requirements that are different, but apparently equal, to Architect for a decision before proceeding.
- B. Minimum Quantity or Quality Levels: The quantity or quality level shown or specified shall be the minimum provided or performed. The actual installation may comply exactly with the minimum quantity or quality specified, or it may exceed the minimum within reasonable limits. To comply with these requirements, indicated numeric values are minimum or maximum, as appropriate, for the context of requirements. Refer uncertainties to Architect for a decision before proceeding.

1.5 SUBMITTALS

- A. Qualification Data: For testing agencies specified in "Quality Assurance" Article to demonstrate their capabilities and experience. Include proof of qualifications in the form of a recent report on the inspection of the testing agency by a recognized authority.

CITY OF ORANGE BEACH
FIRE ADMINISTRATION BUILDING and POST OFFICE ROOF REPLACEMENTS
ISSUED 02-21-2022

- B. Reports: Prepare and submit certified written reports that include the following:
1. Date of issue.
 2. Project title and number.
 3. Name, address, and telephone number of testing agency.
 4. Dates and locations of samples and tests or inspections.
 5. Names of individuals making tests and inspections.
 6. Description of the Work and test and inspection method.
 7. Identification of product and Specification Section.
 8. Complete test or inspection data.
 9. Test and inspection results and an interpretation of test results.
 10. Record of temperature and weather conditions at time of sample taking and testing and inspecting.
 11. Comments or professional opinion on whether tested or inspected Work complies with the Contract Document requirements.
 12. Name and signature of laboratory inspector.
 13. Recommendations on retesting and re-inspecting.
- C. Permits, Licenses, and Certificates: For Owner's records, submit copies of permits, licenses, certifications, inspection reports, releases, jurisdictional settlements, notices, receipts for fee payments, judgments, correspondence, records, and similar documents, established for compliance with standards and regulations bearing on performance of the Work.

1.6 QUALITY ASSURANCE

- A. General: Qualifications paragraphs in this Article establish the minimum qualification levels required; individual Specification Sections specify additional requirements.
- B. Installer Qualifications: A firm or individual experienced in installing, erecting, or assembling work similar in material, design, and extent to that indicated for this Project, whose work has resulted in construction with a record of successful in-service performance.
- C. Manufacturer Qualifications: A firm experienced in manufacturing products or systems similar to those indicated for this Project and with a record of successful in-service performance, as well as sufficient production capacity to produce required units.
- D. Fabricator Qualifications: A firm experienced in producing products similar to those indicated for this Project and with a record of successful in-service performance, as well as sufficient production capacity to produce required units.
- E. Professional Engineer Qualifications: A professional engineer who is legally qualified to practice in jurisdiction where Project is located and who is experienced in providing engineering services of the kind indicated. Engineering services are defined as those performed for installations of the system, assembly, or product that are similar to those indicated for this Project in material, design, and extent.
- F. Testing Agency Qualifications: An NRTL, an NVLAP, or an independent agency with the experience and capability to conduct testing and inspecting indicated, as documented according to ASTM E 548; and with additional qualifications specified in individual Sections; and where required by authorities having jurisdiction, that is acceptable to authorities.
1. NRTL: A nationally recognized testing laboratory according to 29 CFR 1910.7.

CITY OF ORANGE BEACH
FIRE ADMINISTRATION BUILDING and POST OFFICE ROOF REPLACEMENTS
ISSUED 02-21-2022

2. NVLAP: A testing agency accredited according to NIST's National Voluntary Laboratory Accreditation Program.

G. Factory-Authorized Service Representative Qualifications: An authorized representative of manufacturer who is trained and approved by manufacturer to inspect installation of manufacturer's products that are similar in material, design, and extent to those indicated for this Project.

1.7 QUALITY CONTROL

A. Owner Responsibilities: Where quality-control services are indicated as Owner's responsibility, Owner will engage a qualified testing agency to perform these services.

1. Owner will furnish Contractor with names, addresses, and telephone numbers of testing agencies engaged and a description of types of testing and inspecting they are engaged to perform.
2. Costs for retesting and re-inspecting construction that replaces or is necessitated by work that failed to comply with the Contract Documents will be charged to Contractor, and the Contract Sum will be adjusted by Change Order.

B. Tests and inspections not explicitly assigned to Owner are the Contractor's responsibility. Unless otherwise indicated, provide quality-control services specified and those required by authorities having jurisdiction. Perform quality-control services required of Contractor by authorities having jurisdiction, whether specified or not.

1. Where services are indicated as Contractor's responsibility, engage a qualified testing agency to perform these quality-control services.
 - a. Contractor shall not employ same entity engaged by Owner, unless agreed to in writing by Owner.
2. Notify testing agencies at least 24 hours in advance of time when Work that requires testing or inspecting will be performed.
3. Where quality-control services are indicated as Contractor's responsibility, submit a certified written report, in duplicate, of each quality-control service.
4. Testing and inspecting requested by Contractor and not required by the Contract Documents are the Contractor's responsibility.
5. Submit additional copies of each written report directly to authorities having jurisdiction, when they so direct.

C. Manufacturer's Field Services: Where indicated, engage a factory-authorized service representative to inspect field-assembled components and equipment installation, including service connections. Report results in writing as specified in Division 01 Section "Submittal Procedures."

D. Retesting/Re-inspecting: Regardless of whether original tests or inspections were Contractor's responsibility, provide quality-control services, including retesting and re-inspecting, for construction that replaced Work that failed to comply with the Contract Documents.

E. Testing Agency Responsibilities: Cooperate with Architect and Contractor in performance of duties. Provide qualified personnel to perform required tests and inspections.

CITY OF ORANGE BEACH
FIRE ADMINISTRATION BUILDING and POST OFFICE ROOF REPLACEMENTS
ISSUED 02-21-2022

1. Notify Architect and Contractor promptly of irregularities or deficiencies observed in the Work during performance of its services.
 2. Determine the location from which test samples will be taken and in which in-situ tests are conducted.
 3. Conduct and interpret tests and inspections and state in each report whether tested and inspected work complies with or deviates from requirements.
 4. Submit a certified written report, in duplicate, of each test, inspection, and similar quality-control service through Contractor.
 5. Do not release, revoke, alter, or increase the Contract Document requirements or approve or accept any portion of the Work.
 6. Do not perform any duties of Contractor.
- F. Associated Services: Cooperate with agencies performing required tests, inspections, and similar quality-control services, and provide reasonable auxiliary services as requested. Notify agency sufficiently in advance of operations to permit assignment of personnel. Provide the following:
1. Access to the Work.
 2. Incidental labor and facilities necessary to facilitate tests and inspections.
 3. Adequate quantities of representative samples of materials that require testing and inspecting. Assist agency in obtaining samples.
 4. Facilities for storage and field curing of test samples.
 5. Delivery of samples to testing agencies.
 6. Preliminary design mix proposed for use for material mixes that require control by testing agency.
 7. Security and protection for samples and for testing and inspecting equipment at Project site.
- G. Coordination: Coordinate sequence of activities to accommodate required quality-assurance and -control services with a minimum of delay and to avoid necessity of removing and replacing construction to accommodate testing and inspecting.
1. Schedule times for tests, inspections, obtaining samples, and similar activities.

1.8 SPECIAL TESTS AND INSPECTIONS

- A. Special Tests and Inspections: Conducted by a qualified testing agency as required by authorities having jurisdiction, as indicated in individual Specification Sections, and as follows:
1. Verifying that manufacturer maintains detailed fabrication and quality-control procedures and reviewing the completeness and adequacy of those procedures to perform the Work.
 2. Notifying Architect and Contractor promptly of irregularities and deficiencies observed in the Work during performance of its services.
 3. Submitting a certified written report of each test, inspection, and similar quality-control service to Architect with copy to Contractor and to authorities having jurisdiction.
 4. Submitting a final report of special tests and inspections at Substantial Completion, which includes a list of unresolved deficiencies.
 5. Interpreting tests and inspections and stating in each report whether tested and inspected work complies with or deviates from the Contract Documents.

CITY OF ORANGE BEACH
FIRE ADMINISTRATION BUILDING and POST OFFICE ROOF REPLACEMENTS
ISSUED 02-21-2022

6. Retesting and re-inspecting corrected work.

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION

3.1 TEST AND INSPECTION LOG

- A. Prepare a record of tests and inspections. Include the following:
1. Date test or inspection was conducted.
 2. Description of the Work tested or inspected.
 3. Date test or inspection results were transmitted to Architect.
 4. Identification of testing agency or special inspector conducting test or inspection.
- B. Maintain log at Project site. Post changes and modifications as they occur. Provide access to test and inspection log for Architect's reference during normal working hours.

3.2 REPAIR AND PROTECTION

- A. General: On completion of testing, inspecting, sample taking, and similar services, repair damaged construction and restore substrates and finishes.
1. Provide materials and comply with installation requirements specified in other Specification Sections. Restore patched areas and extend restoration into adjoining areas with durable seams that are as invisible as possible.
 2. Comply with the Contract Document requirements for Division 01 Section "Cutting and Patching."
- B. Protect construction exposed by or for quality-control service activities.
- C. Repair and protection are Contractor's responsibility, regardless of the assignment of responsibility for quality-control services.

END OF SECTION 014000

CITY OF ORANGE BEACH
FIRE ADMINISTRATION BUILDING and POST OFFICE ROOF REPLACEMENTS
ISSUED 02-21-2022

SECTION 014200 - REFERENCES

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.

1.2 DEFINITIONS

- A. General: Basic Contract definitions are included in the Conditions of the Contract.
- B. "Approved": When used to convey Architect's action on Contractor's submittals, applications, and requests, "approved" is limited to Architect's duties and responsibilities as stated in the Conditions of the Contract.
- C. "Directed": A command or instruction by Architect. Other terms including "requested," "authorized," "selected," "required," and "permitted" have the same meaning as "directed."
- D. "Indicated": Requirements expressed by graphic representations or in written form on Drawings, in Specifications, and in other Contract Documents. Other terms including "shown," "noted," "scheduled," and "specified" have the same meaning as "indicated."
- E. "Regulations": Laws, ordinances, statutes, and lawful orders issued by authorities having jurisdiction, and rules, conventions, and agreements within the construction industry that control performance of the Work.
- F. "Furnish": Supply and deliver to Project site, ready for unloading, unpacking, assembly, installation, and similar operations.
- G. "Install": Operations at Project site including unloading, temporarily storing, unpacking, assembling, erecting, placing, anchoring, applying, working to dimension, finishing, curing, protecting, cleaning, and similar operations.
- H. "Provide": Furnish and install, complete and ready for the intended use.
- I. "Project Site": Space available for performing construction activities. The extent of Project site is shown on Drawings and may or may not be identical with the description of the land on which Project is to be built.

1.3 INDUSTRY STANDARDS

- A. Applicability of Standards: Unless the Contract Documents include more stringent requirements, applicable construction industry standards have the same force and effect as if bound or copied directly into the Contract Documents to the extent referenced. Such standards are made a part of the Contract Documents by reference.
- B. Publication Dates: Comply with standards in effect as of date of the Contract Documents unless otherwise indicated.

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION (Not Used)

**CITY OF ORANGE BEACH
FIRE ADMINISTRATION BUILDING and POST OFFICE ROOF REPLACEMENTS
ISSUED 02-21-2022**

END OF SECTION 014200

CITY OF ORANGE BEACH
FIRE ADMINISTRATION BUILDING and POST OFFICE ROOF REPLACEMENTS
ISSUED 02-21-2022

SECTION 015000 - TEMPORARY FACILITIES AND CONTROLS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. This Section includes requirements for temporary utilities, support facilities, and security and protection facilities.
- B. Related Sections include the following:
 - 1. Division 01 Section "Summary" for limitations on utility interruptions and other work restrictions.
 - 2. Division 01 Section "Submittal Procedures" for procedures for submitting copies of implementation and termination schedule and utility reports.
 - 3. Division 01 Section "Execution" for progress cleaning requirements.
 - 4. Divisions 02 through 49 Sections for temporary heat, ventilation, and humidity requirements for products in those Sections.

1.3 USE CHARGES

- A. General: Cost or use charges for temporary facilities shall be included in the Contract Sum. Allow other entities to use temporary services and facilities without cost, including, but not limited to, Architect, testing agencies, and authorities having jurisdiction.
- B. Sewer Service: Pay sewer service use charges for sewer usage by all entities for construction operations.
- C. Water Service: Pay water service use charges for water used by all entities for construction operations.
- D. Electric Power Service: Pay electric power service use charges for electricity used by all entities for construction operations.
- E. Sewer, Water, and Electric Power Service: Use charges are specified in Division 01 Section "Multiple Contract Summary."

1.4 SUBMITTALS

- A. Site Plan: Show temporary facilities, utility hookups, staging areas, and parking areas for construction personnel.

1.5 QUALITY ASSURANCE

- A. Electric Service: Comply with NECA, NEMA, and UL standards and regulations for temporary electric service. Install service to comply with NFPA 70.
- B. Tests and Inspections: Arrange for authorities having jurisdiction to test and inspect each temporary utility before use. Obtain required certifications and permits.

CITY OF ORANGE BEACH
FIRE ADMINISTRATION BUILDING and POST OFFICE ROOF REPLACEMENTS
ISSUED 02-21-2022

1.6 PROJECT CONDITIONS

- A. Temporary Use of Permanent Facilities: Installer of each permanent service shall assume responsibility for operation, maintenance, and protection of each permanent service during its use as a construction facility before Owner's acceptance, regardless of previously assigned responsibilities.

PART 2 - PRODUCTS

- A. Pavement: Comply with Drawings

2.2 TEMPORARY FACILITIES (Contractors option for field office)

- A. Field Offices, General: Prefabricated or mobile units with serviceable finishes, temperature controls, and foundations adequate for normal loading.
- B. Common-Use Field Office: Of sufficient size to accommodate needs of construction personnel. Keep office clean and orderly. Furnish and equip offices as follows:
 - 1. Furniture required for Project-site documents including file cabinets, plan tables, plan racks, and bookcases.
 - 2. Conference room of sufficient size to accommodate meetings of 10 individuals. Provide electrical power service and 120-V ac duplex receptacles, with not less than 1 receptacle on each wall. Furnish room with conference table, chairs, and 4-foot-square tack board.
 - 3. Drinking water and private toilet.
 - 4. Heating and cooling equipment necessary to maintain a uniform indoor temperature of 68 to 72 deg F.
 - 5. Lighting fixtures capable of maintaining average illumination of 20 fc at desk height.
- C. Storage and Fabrication Sheds: Provide sheds sized, furnished, and equipped to accommodate materials and equipment for construction operations.
 - 1. Store combustible materials apart from building.

2.2 EQUIPMENT

- A. HVAC Equipment: Unless Owner authorizes use of permanent HVAC system, provide vented, self-contained, liquid-propane-gas or fuel-oil heaters with individual space thermostatic control.
 - 1. Use of gasoline-burning space heaters, open-flame heaters, or salamander-type heating units is prohibited.
 - 2. Heating Units: Listed and labeled for type of fuel being consumed, by a testing agency acceptable to authorities having jurisdiction, and marked for intended use.
 - 3. Permanent HVAC System: If Owner authorizes use of permanent HVAC system for temporary use during construction, provide filter with MERV of 8 at each return air grille in system and remove at end of construction.

PART 3 - EXECUTION

3.1 INSTALLATION, GENERAL

CITY OF ORANGE BEACH
FIRE ADMINISTRATION BUILDING and POST OFFICE ROOF REPLACEMENTS
ISSUED 02-21-2022

A. Locate facilities where they will serve Project adequately and result in minimum interference with performance of the Work. Relocate and modify facilities as required by progress of the Work.

1. Locate facilities to limit site disturbance as specified in Division 01 Section "Summary."

B. Provide each facility ready for use when needed to avoid delay. Do not remove until facilities are no longer needed or are replaced by authorized use of completed permanent facilities.

3.2 TEMPORARY UTILITY INSTALLATION

A. General: Install temporary service or connect to existing service.

1. Arrange with utility company, Owner, and existing users for time when service can be interrupted, if necessary, to make connections for temporary services.

B. Sewers and Drainage: Provide temporary utilities to remove effluent lawfully.

1. Connect temporary sewers to municipal system as directed by authorities having jurisdiction.

C. Water Service: Install water service and distribution piping in sizes and pressures adequate for construction.

D. Sanitary Facilities: Provide temporary toilets, wash facilities, and drinking water for use of construction personnel. Comply with authorities having jurisdiction for type, number, location, operation, and maintenance of fixtures and facilities.

1. Toilets: Use of Owner's existing toilet facilities will be permitted, as long as facilities are cleaned and maintained in a condition acceptable to Owner. At Substantial Completion, restore these facilities to condition existing before initial use.

E. Heating: Provide temporary heating required by construction activities for curing or drying of completed installations or for protecting installed construction from adverse effects of low temperatures or high humidity. Select equipment that will not have a harmful effect on completed installations or elements being installed.

F. Ventilation and Humidity Control: Provide temporary ventilation required by construction activities for curing or drying of completed installations or for protecting installed construction from adverse effects of high humidity. Select equipment that will not have a harmful effect on completed installations or elements being installed. Coordinate ventilation requirements to produce ambient condition required and minimize energy consumption.

G. Electric Power Service: Provide electric power service and distribution system of sufficient size, capacity, and power characteristics required for construction operations.

1. Install electric power service in accordance with Division 26 "Electrical", unless otherwise indicated.

2. Connect temporary service to Owner's existing power source, as directed by Owner.

CITY OF ORANGE BEACH
FIRE ADMINISTRATION BUILDING and POST OFFICE ROOF REPLACEMENTS
ISSUED 02-21-2022

- H. Lighting: Provide temporary lighting with local switching that provides adequate illumination for construction operations, observations, inspections, and traffic conditions.
 - 1. Install and operate temporary lighting that fulfills security and protection requirements without operating entire system.
- I. Telephone Service: Provide temporary telephone service in common-use facilities for use by all construction personnel. Install one telephone line(s) for each field office.
 - 1. At each telephone, post a list of important telephone numbers.
 - a. Police and fire departments.
 - b. Ambulance service.
 - c. Contractor's home office.
 - d. Architect's office.
 - e. Engineers' offices.
 - f. Owner's office.
 - g. Principal subcontractors' field and home offices.
 - 2. Provide superintendent with cellular telephone or portable two-way radio for use when away from field office.

3.3 SUPPORT FACILITIES INSTALLATION

- A. General: Comply with the following:
 - 1. Provide incombustible construction for offices, shops, and sheds located within construction area or within 30 feet of building lines. Comply with NFPA 241.
 - 2. Maintain support facilities until near Substantial Completion. Remove before Substantial Completion. Personnel remaining after Substantial Completion will be permitted to use permanent facilities, under conditions acceptable to Owner.
- B. Temporary Roads and Paved Areas: Construct and maintain temporary roads and paved areas adequate for construction operations. Locate temporary roads and paved areas in same location as permanent roads and paved areas. Extend temporary roads and paved areas, within construction limits indicated, as necessary for construction operations.
 - 1. Coordinate elevations of temporary roads and paved areas with permanent roads and paved areas.
 - 2. Prepare subgrade and install subbase and base for temporary roads and paved areas in accordance with the Drawings.
 - 3. Recondition base after temporary use, including removing contaminated material, regrading, proofrolling, compacting, and testing.
 - 4. Delay installation of final course of permanent hot-mix asphalt pavement until immediately before Substantial Completion. Repair hot-mix asphalt base-course pavement before installation of final course in accordance with the Drawings
- C. Parking: Provide temporary parking areas for construction personnel.
- D. Dewatering Facilities and Drains: Comply with requirements of authorities having jurisdiction. Maintain Project site, excavations, and construction free of water.

CITY OF ORANGE BEACH
FIRE ADMINISTRATION BUILDING and POST OFFICE ROOF REPLACEMENTS
ISSUED 02-21-2022

1. Dispose of rainwater in a lawful manner that will not result in flooding Project or adjoining properties nor endanger permanent Work or temporary facilities.
- E. Project Identification and Temporary Signs: Provide Project identification and other signs. Install signs where indicated to inform public and individuals seeking entrance to Project. Unauthorized signs are not permitted.
1. Provide temporary, directional signs for construction personnel and visitors.
 2. Maintain and touchup signs so they are legible at all times.
- F. Waste Disposal Facilities: Provide waste-collection containers in sizes adequate to handle waste from construction operations. Comply with requirements of authorities having jurisdiction. Comply with Division 01 Section "Execution" for progress cleaning requirements.

3.4 SECURITY AND PROTECTION FACILITIES INSTALLATION

- A. Environmental Protection: Provide protection, operate temporary facilities, and conduct construction in ways and by methods that comply with environmental regulations and that minimize possible air, waterway, and subsoil contamination or pollution or other undesirable effects.
- B. Temporary Erosion and Sedimentation Control: Comply with requirements on the Drawings
- C. Stormwater Control: Comply with authorities having jurisdiction. Provide barriers in and around excavations and subgrade construction to prevent flooding by runoff of stormwater from heavy rains.
- D. Tree and Plant Protection: Install temporary fencing located as indicated or outside the drip line of trees to protect vegetation from damage from construction operations. Protect tree root systems from damage, flooding, and erosion.
- E. Pest Control: Engage pest-control service to recommend practices to minimize attraction and harboring of rodents, roaches, and other pests and to perform extermination and control procedures at regular intervals so Project will be free of pests and their residues at Substantial Completion. Obtain extended warranty for Owner. Perform control operations lawfully, using environmentally safe materials.
- F. Security Enclosure and Lockup: Install substantial temporary enclosure around partially completed areas of construction. Provide lockable entrances to prevent unauthorized entrance, vandalism, theft, and similar violations of security.

3.5 OPERATION, TERMINATION, AND REMOVAL

- A. Supervision: Enforce strict discipline in use of temporary facilities. To minimize waste and abuse, limit availability of temporary facilities to essential and intended uses.
- B. Maintenance: Maintain facilities in good operating condition until removal.
1. Maintain operation of temporary enclosures, heating, cooling, humidity control, ventilation, and similar facilities on a 24-hour basis where required to achieve indicated results and to avoid possibility of damage.
- C. Temporary Facility Changeover: Do not change over from using temporary security and protection facilities to permanent facilities until Substantial Completion.

CITY OF ORANGE BEACH
FIRE ADMINISTRATION BUILDING and POST OFFICE ROOF REPLACEMENTS
ISSUED 02-21-2022

- D. Termination and Removal: Remove each temporary facility when need for its service has ended, when it has been replaced by authorized use of a permanent facility, or no later than Substantial Completion. Complete or, if necessary, restore permanent construction that may have been delayed because of interference with temporary facility. Repair damaged Work, clean exposed surfaces, and replace construction that cannot be satisfactorily repaired.
1. Materials and facilities that constitute temporary facilities are property of Contractor. Owner reserves right to take possession of Project identification signs.
 2. Remove temporary paving not intended for or acceptable for integration into permanent paving. Where area is intended for landscape development, remove soil and aggregate fill that do not comply with requirements for fill or subsoil. Remove materials contaminated with road oil, asphalt and other petrochemical compounds, and other substances that might impair growth of plant materials or lawns. Repair or replace street paving, curbs, and sidewalks at temporary entrances, as required by authorities having jurisdiction.
 3. At Substantial Completion, clean and renovate permanent facilities used during construction period. Comply with final cleaning requirements specified in Division 01 Section "Closeout Procedures."

END OF SECTION 015000

SECTION 016000 - PRODUCT REQUIREMENTS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. This Section includes administrative and procedural requirements for selection of products for use in Project; product delivery, storage, and handling; manufacturers' standard warranties on products; special warranties; product substitutions; and comparable products.
- B. Related Sections include the following:
 - 1. Division 01 Section "References" for applicable industry standards for products specified.
 - 2. Division 01 Section "Closeout Procedures" for submitting warranties for Contract closeout.
 - 3. Divisions 02 through 49 Sections for specific requirements for warranties on products and installations specified to be warranted.

1.3 DEFINITIONS

- A. Products: Items purchased for incorporating into the Work, whether purchased for Project or taken from previously purchased stock. The term "product" includes the terms "material," "equipment," "system," and terms of similar intent.
 - 1. Named Products: Items identified by manufacturer's product name, including make or model number or other designation shown or listed in manufacturer's published product literature, that is current as of date of the Contract Documents.
 - 2. New Products: Items that have not previously been incorporated into another project or facility, except that products consisting of recycled-content materials are allowed, unless explicitly stated otherwise. Products salvaged or recycled from other projects are not considered new products.
 - 3. Comparable Product: Product that is demonstrated and approved through submittal process, or where indicated as a product substitution, to have the indicated qualities related to type, function, dimension, in-service performance, physical properties, appearance, and other characteristics that equal or exceed those of specified product.
- B. Substitutions: Changes in products, materials, equipment, and methods of construction from those required by the Contract Documents and proposed by Contractor.
- C. Basis-of-Design Product Specification: Where a specific manufacturer's product is named and accompanied by the words "basis of design," including make or model number or other designation, to establish the significant qualities related to type, function, dimension, in-service performance, physical properties, appearance, and

CITY OF ORANGE BEACH
FIRE ADMINISTRATION BUILDING and POST OFFICE ROOF REPLACEMENTS
ISSUED 02-21-2022

other characteristics for purposes of evaluating comparable products of other named manufacturers.

1.4 SUBMITTALS

- A. Substitution Requests: Submit three copies of each request for consideration. Identify product or fabrication or installation method to be replaced. Include Specification Section number and title and Drawing numbers and titles.
1. Substitution Request Form: Use CSI Form 13.1A.
 2. Documentation: Show compliance with requirements for substitutions and the following, as applicable:
 - a. Statement indicating why specified material or product cannot be provided.
 - b. Coordination information, including a list of changes or modifications needed to other parts of the Work and to construction performed by Owner and separate contractors, that will be necessary to accommodate proposed substitution.
 - c. Detailed comparison of significant qualities of proposed substitution with those of the Work specified. Significant qualities may include attributes such as performance, weight, size, durability, visual effect, and specific features and requirements indicated.
 - d. Product Data, including drawings and descriptions of products and fabrication and installation procedures.
 - e. Samples, where applicable or requested.
 - f. List of similar installations for completed projects with project names and addresses and names and addresses of architects and owners.
 - g. Material test reports from a qualified testing agency indicating and interpreting test results for compliance with requirements indicated.
 - h. Research/evaluation reports evidencing compliance with building code in effect for Project, from a model code organization acceptable to authorities having jurisdiction.
 - i. Detailed comparison of Contractor's Construction Schedule using proposed substitution with products specified for the Work, including effect on the overall Contract Time. If specified product or method of construction cannot be provided within the Contract Time, include letter from manufacturer, on manufacturer's letterhead, stating lack of availability or delays in delivery.
 - j. Cost information, including a proposal of change, if any, in the Contract Sum.
 - k. Contractor's certification that proposed substitution complies with requirements in the Contract Documents and is appropriate for applications indicated.
 - l. Contractor's waiver of rights to additional payment or time that may subsequently become necessary because of failure of proposed substitution to produce indicated results.
 3. Architect's Action: If necessary, Architect will request additional information or documentation for evaluation within 7 days of receipt of a request for substitution. Architect will notify Contractor of acceptance or rejection of proposed substitution

CITY OF ORANGE BEACH
FIRE ADMINISTRATION BUILDING and POST OFFICE ROOF REPLACEMENTS
ISSUED 02-21-2022

within 15 days of receipt of request, or 7 days of receipt of additional information or documentation, whichever is later.

- a. Form of Acceptance: Change Order.
 - b. Use product specified if Architect cannot make a decision on use of a proposed substitution within time allocated.
- B. Comparable Product Requests: Submit three copies of each request for consideration. Identify product or fabrication or installation method to be replaced. Include Specification Section number and title and Drawing numbers and titles.
- 1. Architect's Action: If necessary, Architect will request additional information or documentation for evaluation within one week of receipt of a comparable product request. Architect will notify Contractor of approval or rejection of proposed comparable product request within 15 days of receipt of request, or 7 days of receipt of additional information or documentation, whichever is later.
 - a. Form of Approval: As specified in Division 01 Section "Submittal Procedures."
 - b. Use product specified if Architect cannot make a decision on use of a comparable product request within time allocated.
- C. Basis-of-Design Product Specification Submittal: Comply with requirements in Division 01 Section "Submittal Procedures." Show compliance with requirements.

1.5 QUALITY ASSURANCE

- A. Compatibility of Options: If Contractor is given option of selecting between two or more products for use on Project, product selected shall be compatible with products previously selected, even if previously selected products were also options.

1.6 PRODUCT DELIVERY, STORAGE, AND HANDLING

- A. Deliver, store, and handle products using means and methods that will prevent damage, deterioration, and loss, including theft. Comply with manufacturer's written instructions.
- B. Delivery and Handling:
 - 1. Schedule delivery to minimize long-term storage at Project site and to prevent overcrowding of construction spaces.
 - 2. Coordinate delivery with installation time to ensure minimum holding time for items that are flammable, hazardous, easily damaged, or sensitive to deterioration, theft, and other losses.
 - 3. Deliver products to Project site in an undamaged condition in manufacturer's original sealed container or other packaging system, complete with labels and instructions for handling, storing, unpacking, protecting, and installing.
 - 4. Inspect products on delivery to ensure compliance with the Contract Documents and to ensure that products are undamaged and properly protected.
- C. Storage:
 - 1. Store products to allow for inspection and measurement of quantity or counting of units.

CITY OF ORANGE BEACH
FIRE ADMINISTRATION BUILDING and POST OFFICE ROOF REPLACEMENTS
ISSUED 02-21-2022

2. Store materials in a manner that will not endanger Project structure.
3. Store products that are subject to damage by the elements, under cover in a weathertight enclosure above ground, with ventilation adequate to prevent condensation.
4. Store cementitious products and materials on elevated platforms.
5. Store foam plastic from exposure to sunlight, except to extent necessary for period of installation and concealment.
6. Comply with product manufacturer's written instructions for temperature, humidity, ventilation, and weather-protection requirements for storage.
7. Protect stored products from damage and liquids from freezing.
8. Provide a secure location and enclosure at Project site for storage of materials and equipment by Owner's construction forces. Coordinate location with Owner.

1.7 PRODUCT WARRANTIES

- A. Warranties specified in other Sections shall be in addition to, and run concurrent with, other warranties required by the Contract Documents. Manufacturer's disclaimers and limitations on product warranties do not relieve Contractor of obligations under requirements of the Contract Documents.
 1. **Manufacturer's Warranty:** Preprinted written warranty published by individual manufacturer for a particular product and specifically endorsed by manufacturer to Owner.
 2. **Special Warranty:** Written warranty required by or incorporated into the Contract Documents, either to extend time limit provided by manufacturer's warranty or to provide more rights for Owner.
- B. **Special Warranties:** Prepare a written document that contains appropriate terms and identification, ready for execution. Submit a draft for approval before final execution.
 1. **Manufacturer's Standard Form:** Modified to include Project-specific information and properly executed.
 2. Refer to Divisions 02 through 49 Sections for specific content requirements and particular requirements for submitting special warranties.
- C. **Submittal Time:** Comply with requirements in Division 01 Section "Closeout Procedures."

PART 2 - PRODUCTS

2.1 PRODUCT SELECTION PROCEDURES

- A. **General Product Requirements:** Provide products that comply with the Contract Documents, that are undamaged and, unless otherwise indicated, that are new at time of installation.
 1. Provide products complete with accessories, trim, finish, fasteners, and other items needed for a complete installation and indicated use and effect.
 2. **Standard Products:** If available, and unless custom products or nonstandard options are specified, provide standard products of types that have been produced and used successfully in similar situations on other projects.
 3. Owner reserves the right to limit selection to products with warranties not in conflict with requirements of the Contract Documents.

CITY OF ORANGE BEACH
FIRE ADMINISTRATION BUILDING and POST OFFICE ROOF REPLACEMENTS
ISSUED 02-21-2022

4. Where products are accompanied by the term "as selected," Architect will make selection.
 5. Where products are accompanied by the term "match sample," sample to be matched is Architect's.
 6. Descriptive, performance, and reference standard requirements in the Specifications establish "salient characteristics" of products.
- B. Product Selection Procedures:
1. Available Products: Where Specifications include a list of names of both products and manufacturers, provide one of the products listed, or an unnamed product, that complies with requirements. Comply with provisions in Part 2 "Comparable Products" Article for consideration of an unnamed product.
 2. Available Manufacturers: Where Specifications include a list of manufacturers, provide a product by one of the manufacturers listed, or an unnamed manufacturer, that complies with requirements. Comply with provisions in Part 2 "Comparable Products" Article for consideration of an unnamed product.
 3. Basis-of-Design Product: Where Specifications name a product and include a list of manufacturers, provide the specified product or a comparable product by one of the other named manufacturers. Drawings and Specifications indicate sizes, profiles, dimensions, and other characteristics that are based on the product named. Comply with provisions in Part 2 "Comparable Products" Article for consideration of an unnamed product by the other named manufacturers.

2.2 PRODUCT SUBSTITUTIONS

- A. Timing: Architect will consider Contractor's requests for substitution if received within 10 days prior to bid date. In the absence of prior approval, the Architect will require all components to be as specified, with no exceptions.
- B. Conditions: Architect will consider Contractor's request for substitution when the following conditions are satisfied. If the following conditions are not satisfied, Architect will return requests without action, except to record noncompliance with these requirements:
1. Requested substitution offers Owner a substantial advantage in cost, time, energy conservation, or other considerations, after deducting additional responsibilities Owner must assume. Owner's additional responsibilities may include compensation to Architect for redesign and evaluation services, increased cost of other construction by Owner, and similar considerations.
 2. Requested substitution does not require extensive revisions to the Contract Documents.
 3. Requested substitution is consistent with the Contract Documents and will produce indicated results.
 4. Substitution request is fully documented and properly submitted.
 5. Requested substitution will not adversely affect Contractor's Construction Schedule.
 6. Requested substitution has received necessary approvals of authorities having jurisdiction.
 7. Requested substitution is compatible with other portions of the Work.
 8. Requested substitution has been coordinated with other portions of the Work.
 9. Requested substitution provides specified warranty.

CITY OF ORANGE BEACH
FIRE ADMINISTRATION BUILDING and POST OFFICE ROOF REPLACEMENTS
ISSUED 02-21-2022

2.3 COMPARABLE PRODUCTS

- A. Timing: Architect will consider Contractor's requests for comparable product if received within 10 days prior to bid date. In the absence of prior approval, the Architect will require all components to be as specified, with no exceptions.
- B. Conditions: Architect will consider Contractor's request for comparable product when the following conditions are satisfied. If the following conditions are not satisfied, Architect will return requests without action, except to record noncompliance with these requirements:
 - 1. Evidence that the proposed product does not require extensive revisions to the Contract Documents, that it is consistent with the Contract Documents and will produce the indicated results, and that it is compatible with other portions of the Work.
 - 2. Detailed comparison of significant qualities of proposed product with those named in the Specifications. Significant qualities include attributes such as performance, weight, size, durability, visual effect, and specific features and requirements indicated.
 - 3. Evidence that proposed product provides specified warranty.
 - 4. List of similar installations for completed projects with project names and addresses and names and addresses of architects and owners, if requested.
 - 5. Samples, if requested.

PART 3 - EXECUTION (Not Used)

END OF SECTION 016000

CITY OF ORANGE BEACH
FIRE ADMINISTRATION BUILDING and POST OFFICE ROOF REPLACEMENTS
ISSUED 02-21-2022

SECTION 017300 - EXECUTION

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. This Section includes general procedural requirements governing execution of the Work including, but not limited to, the following:

- 1. Construction layout.
- 2. Field engineering and surveying.
- 3. General installation of products.
- 4. Progress cleaning.
- 5. Starting and adjusting.
- 6. Protection of installed construction.
- 7. Correction of the Work.

- B. Related Sections include the following:

- 1. Division 01 Section "Project Management and Coordination" for procedures for coordinating field engineering with other construction activities.
- 2. Division 01 Section "Submittal Procedures" for submitting surveys.
- 3. Division 01 Section "Cutting and Patching" for procedural requirements for cutting and patching necessary for the installation or performance of other components of the Work.
- 4. Division 01 Section "Closeout Procedures" for submitting final property survey with Project Record Documents, recording of Owner-accepted deviations from indicated lines and levels, and final cleaning.

1.3 SUBMITTALS

- A. Qualification Data: For professional engineer.
- B. Certificates: Submit certificate signed by professional engineer certifying that location and elevation of improvements comply with requirements.
- C. Certified Surveys: Submit two copies signed by professional engineer.
- D. Final Property Survey: Submit 10 copies showing the Work performed and record survey data.

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION

3.1 EXAMINATION

CITY OF ORANGE BEACH
FIRE ADMINISTRATION BUILDING and POST OFFICE ROOF REPLACEMENTS
ISSUED 02-21-2022

- A. Existing Conditions: The existence and location of site improvements, utilities, and other construction indicated as existing are not guaranteed. Before beginning work, investigate and verify the existence and location of mechanical and electrical systems and other construction affecting the Work.
 - 1. Before construction, verify the location and points of connection of utility services.
- B. Existing Utilities: The existence and location of underground and other utilities and construction indicated as existing are not guaranteed. Before beginning site work, investigate and verify the existence and location of underground utilities and other construction affecting the Work.
 - 1. Before construction, verify the location and invert elevation at points of connection of sanitary sewer, storm sewer, and water-service piping; and underground electrical services.
 - 2. Furnish location data for work related to Project that must be performed by public utilities serving Project site.
- C. Acceptance of Conditions: Examine substrates, areas, and conditions, with Installer or Applicator present where indicated, for compliance with requirements for installation tolerances and other conditions affecting performance. Record observations.
 - 1. Written Report: Where a written report listing conditions detrimental to performance of the Work is required by other Sections, include the following:
 - a. Description of the Work.
 - b. List of detrimental conditions, including substrates.
 - c. List of unacceptable installation tolerances.
 - d. Recommended corrections.
 - 2. Verify compatibility with and suitability of substrates, including compatibility with existing finishes or primers.
 - 3. Examine roughing-in for mechanical and electrical systems to verify actual locations of connections before equipment and fixture installation.
 - 4. Examine walls, floors, and roofs for suitable conditions where products and systems are to be installed.
 - 5. Proceed with installation only after unsatisfactory conditions have been corrected. Proceeding with the Work indicates acceptance of surfaces and conditions.

3.2 PREPARATION

- A. Existing Utility Information: Furnish information to local utility that is necessary to adjust, move, or relocate existing utility structures, utility poles, lines, services, or other utility appurtenances located in or affected by construction. Coordinate with authorities having jurisdiction.
- B. Field Measurements: Take field measurements as required to fit the Work properly. Recheck measurements before installing each product. Where portions of the Work are indicated to fit to other construction, verify dimensions of other construction by field measurements before fabrication. Coordinate fabrication schedule with construction progress to avoid delaying the Work.

CITY OF ORANGE BEACH
FIRE ADMINISTRATION BUILDING and POST OFFICE ROOF REPLACEMENTS
ISSUED 02-21-2022

- C. Space Requirements: Verify space requirements and dimensions of items shown diagrammatically on Drawings.
- D. Review of Contract Documents and Field Conditions: Immediately on discovery of the need for clarification of the Contract Documents, submit a request for information to Architect. Include a detailed description of problem encountered, together with recommendations for changing the Contract Documents. Submit requests on CSI Form 13.2A, "Request for Interpretation."

3.3 CONSTRUCTION LAYOUT

- A. Verification: Before proceeding to lay out the Work, verify layout information shown on Drawings, in relation to the property survey and existing benchmarks. If discrepancies are discovered, notify Architect promptly.
- B. General: Engage a professional engineer to lay out the Work using accepted surveying practices.
 - 1. Establish benchmarks and control points to set lines and levels at each story of construction and elsewhere as needed to locate each element of Project.
 - 2. Establish dimensions within tolerances indicated. Do not scale Drawings to obtain required dimensions.
 - 3. Inform installers of lines and levels to which they must comply.
 - 4. Check the location, level and plumb, of every major element as the Work progresses.
 - 5. Notify Architect when deviations from required lines and levels exceed allowable tolerances.
 - 6. Close site surveys with an error of closure equal to or less than the standard established by authorities having jurisdiction.
- C. Site Improvements: Locate and lay out site improvements, including pavements, grading, fill and topsoil placement, utility slopes, and invert elevations.
- D. Building Lines and Levels: Locate and lay out control lines and levels for structures, building foundations, column grids, and floor levels, including those required for mechanical and electrical work. Transfer survey markings and elevations for use with control lines and levels. Level foundations and piers from two or more locations.
- E. Record Log: Maintain a log of layout control work. Record deviations from required lines and levels. Include beginning and ending dates and times of surveys, weather conditions, name and duty of each survey party member, and types of instruments and tapes used. Make the log available for reference by Architect.

3.4 FIELD ENGINEERING

- A. Reference Points: Locate existing permanent benchmarks, control points, and similar reference points before beginning the Work. Preserve and protect permanent benchmarks and control points during construction operations.
 - 1. Do not change or relocate existing benchmarks or control points without prior written approval of Architect. Report lost or destroyed permanent benchmarks or control points promptly. Report the need to relocate permanent benchmarks or control points to Architect before proceeding.
 - 2. Replace lost or destroyed permanent benchmarks and control points promptly. Base replacements on the original survey control points.

CITY OF ORANGE BEACH
FIRE ADMINISTRATION BUILDING and POST OFFICE ROOF REPLACEMENTS
ISSUED 02-21-2022

- B. Benchmarks: Establish and maintain a minimum of two permanent benchmarks on Project site, referenced to data established by survey control points. Comply with authorities having jurisdiction for type and size of benchmark.
 - 1. Record benchmark locations, with horizontal and vertical data, on Project Record Documents.
 - 2. Where the actual location or elevation of layout points cannot be marked, provide temporary reference points sufficient to locate the Work.
 - 3. Remove temporary reference points when no longer needed. Restore marked construction to its original condition.
- C. Certified Survey: On completion of foundation walls, major site improvements, and other work requiring field-engineering services, prepare a certified survey showing dimensions, locations, angles, and elevations of construction and site work.
- D. Final Property Survey: Prepare a final property survey showing significant features (real property) for Project. Include on the survey a certification, signed by professional engineer, that principal metes, bounds, lines, and levels of Project are accurately positioned as shown on the survey.
 - 1. Show boundary lines, monuments, streets, site improvements and utilities, existing improvements and significant vegetation, adjoining properties, acreage, grade contours, and the distance and bearing from a site corner to a legal point.
 - 2. Recording: At Substantial Completion, have the final property survey recorded by or with authorities having jurisdiction as the official "property survey."

3.5 INSTALLATION

- A. General: Locate the Work and components of the Work accurately, in correct alignment and elevation, as indicated.
 - 1. Make vertical work plumb and make horizontal work level.
 - 2. Where space is limited, install components to maximize space available for maintenance and ease of removal for replacement.
 - 3. Conceal pipes, ducts, and wiring in finished areas, unless otherwise indicated.
 - 4. Maintain minimum headroom clearance of 8 feet in spaces without a suspended ceiling.
- B. Comply with manufacturer's written instructions and recommendations for installing products in applications indicated.
- C. Install products at the time and under conditions that will ensure the best possible results. Maintain conditions required for product performance until Substantial Completion.
- D. Conduct construction operations so no part of the Work is subjected to damaging operations or loading in excess of that expected during normal conditions of occupancy.
- E. Tools and Equipment: Do not use tools or equipment that produce harmful noise levels.
- F. Templates: Obtain and distribute to the parties involved templates for work specified to be factory prepared and field installed. Check Shop Drawings of other work to confirm

CITY OF ORANGE BEACH
FIRE ADMINISTRATION BUILDING and POST OFFICE ROOF REPLACEMENTS
ISSUED 02-21-2022

that adequate provisions are made for locating and installing products to comply with indicated requirements.

- G. Anchors and Fasteners: Provide anchors and fasteners as required to anchor each component securely in place, accurately located and aligned with other portions of the Work.
 - 1. Mounting Heights: Where mounting heights are not indicated, mount components at heights directed by Architect.
 - 2. Allow for building movement, including thermal expansion and contraction.
 - 3. Coordinate installation of anchorages. Furnish setting drawings, templates, and directions for installing anchorages, including sleeves, concrete inserts, anchor bolts, and items with integral anchors, that are to be embedded in concrete or masonry. Deliver such items to Project site in time for installation.
- H. Joints: Make joints of uniform width. Where joint locations in exposed work are not indicated, arrange joints for the best visual effect. Fit exposed connections together to form hairline joints.
- I. Hazardous Materials: Use products, cleaners, and installation materials that are not considered hazardous.

3.6 PROGRESS CLEANING

- A. General: Clean Project site and work areas daily, including common areas. Coordinate progress cleaning for joint-use areas where more than one installer has worked. Enforce requirements strictly. Dispose of materials lawfully.
 - 1. Comply with requirements in NFPA 241 for removal of combustible waste materials and debris.
 - 2. Do not hold materials more than 7 days during normal weather or 3 days if the temperature is expected to rise above 80°F.
 - 3. Containerize hazardous and unsanitary waste materials separately from other waste. Mark containers appropriately and dispose of legally, according to regulations.
- B. Site: Maintain Project site free of waste materials and debris.
- C. Work Areas: Clean areas where work is in progress to the level of cleanliness necessary for proper execution of the Work.
 - 1. Remove liquid spills promptly.
 - 2. Where dust would impair proper execution of the Work, broom-clean or vacuum the entire work area, as appropriate.
- D. Installed Work: Keep installed work clean. Clean installed surfaces according to written instructions of manufacturer or fabricator of product installed, using only cleaning materials specifically recommended. If specific cleaning materials are not recommended, use cleaning materials that are not hazardous to health or property and that will not damage exposed surfaces.
- E. Concealed Spaces: Remove debris from concealed spaces before enclosing the space.

CITY OF ORANGE BEACH
FIRE ADMINISTRATION BUILDING and POST OFFICE ROOF REPLACEMENTS
ISSUED 02-21-2022

- F. Exposed Surfaces in Finished Areas: Clean exposed surfaces and protect as necessary to ensure freedom from damage and deterioration at time of Substantial Completion.
- G. Waste Disposal: Burying or burning waste materials on-site will not be permitted. Washing waste materials down sewers or into waterways will not be permitted.
- H. During handling and installation, clean and protect construction in progress and adjoining materials already in place. Apply protective covering where required to ensure protection from damage or deterioration at Substantial Completion.
- I. Clean and provide maintenance on completed construction as frequently as necessary through the remainder of the construction period. Adjust and lubricate operable components to ensure operability without damaging effects.
- J. Limiting Exposures: Supervise construction operations to assure that no part of the construction, completed or in progress, is subject to harmful, dangerous, damaging, or otherwise deleterious exposure during the construction period.

3.7 STARTING AND ADJUSTING

- A. Start equipment and operating components to confirm proper operation. Remove malfunctioning units, replace with new units, and retest.
- B. Adjust operating components for proper operation without binding. Adjust equipment for proper operation.
- C. Test each piece of equipment to verify proper operation. Test and adjust controls and safeties. Replace damaged and malfunctioning controls and equipment.
- D. Manufacturer's Field Service: If a factory-authorized service representative is required to inspect field-assembled components and equipment installation, comply with qualification requirements in Division 01 Section "Quality Requirements."

3.8 PROTECTION OF INSTALLED CONSTRUCTION

- A. Provide final protection and maintain conditions that ensure installed Work is without damage or deterioration at time of Substantial Completion.
- B. Comply with manufacturer's written instructions for temperature and relative humidity.

3.9 CORRECTION OF THE WORK

- A. Repair or remove and replace defective construction. Restore damaged substrates and finishes. Comply with requirements in Division 01 Section "Cutting and Patching."
 - 1. Repairing includes replacing defective parts, refinishing damaged surfaces, touching up with matching materials, and properly adjusting operating equipment.
- B. Restore permanent facilities used during construction to their specified condition.
- C. Remove and replace damaged surfaces that are exposed to view if surfaces cannot be repaired without visible evidence of repair.
- D. Repair components that do not operate properly. Remove and replace operating components that cannot be repaired.
- E. Remove and replace chipped, scratched, and broken glass or reflective surfaces.

**CITY OF ORANGE BEACH
FIRE ADMINISTRATION BUILDING and POST OFFICE ROOF REPLACEMENTS
ISSUED 02-21-2022**

END OF SECTION 017300

SECTION 017329 - CUTTING AND PATCHING

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. This Section includes procedural requirements for cutting and patching.
- B. Related Sections include the following:
 - 1. Divisions 02 through 49 Sections for specific requirements and limitations applicable to cutting and patching individual parts of the Work.

1.3 DEFINITIONS

- A. Cutting: Removal of in-place construction necessary to permit installation or performance of other Work.
- B. Patching: Fitting and repair work required to restore surfaces to original conditions after installation of other Work.

1.4 QUALITY ASSURANCE

- A. Structural Elements: Do not cut and patch structural elements in a manner that could change their load-carrying capacity or load-deflection ratio.
- B. Operational Elements: Do not cut and patch operating elements and related components in a manner that results in reducing their capacity to perform as intended or that results in increased maintenance or decreased operational life or safety. Operating elements include the following:
 - 1. Primary operational systems and equipment.
 - 2. Air or smoke barriers.
 - 3. Fire-suppression systems.
 - 4. Mechanical systems piping and ducts.
 - 5. Control systems.
 - 6. Communication systems.
 - 7. Electrical wiring systems.
 - 8. Operating systems of special construction in Division 13 Sections.
- C. Miscellaneous Elements: Do not cut and patch miscellaneous elements or related components in a manner that could change their load-carrying capacity, that results in reducing their capacity to perform as intended, or that results in increased maintenance or decreased operational life or safety. Miscellaneous elements include the following:
 - 1. Water, moisture, or vapor barriers.
 - 2. Membranes and flashings.
 - 3. Equipment supports.

CITY OF ORANGE BEACH
FIRE ADMINISTRATION BUILDING and POST OFFICE ROOF REPLACEMENTS
ISSUED 02-21-2022

4. Piping, ductwork, vessels, and equipment.
 5. Noise- and vibration-control elements and systems.
- D. Visual Requirements: Do not cut and patch construction in a manner that results in visual evidence of cutting and patching. Do not cut and patch construction exposed on the exterior or in occupied spaces in a manner that would, in Architect's opinion, reduce the building's aesthetic qualities. Remove and replace construction that has been cut and patched in a visually unsatisfactory manner.

PART 2 - PRODUCTS

2.1 MATERIALS

- A. General: Comply with requirements specified in other Sections.
- B. In-Place Materials: Use materials identical to in-place materials. For exposed surfaces, use materials that visually match in-place adjacent surfaces to the fullest extent possible.
 1. If identical materials are unavailable or cannot be used, use materials that, when installed, will match the visual and functional performance of in-place materials.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine surfaces to be cut and patched and conditions under which cutting and patching are to be performed.
 1. Compatibility: Before patching, verify compatibility with and suitability of substrates, including compatibility with in-place finishes or primers.
 2. Proceed with installation only after unsafe or unsatisfactory conditions have been corrected.

3.2 PREPARATION

- A. Temporary Support: Provide temporary support of Work to be cut.
- B. Protection: Protect in-place construction during cutting and patching to prevent damage. Provide protection from adverse weather conditions for portions of Project that might be exposed during cutting and patching operations.
- C. Adjoining Areas: Avoid interference with use of adjoining areas or interruption of free passage to adjoining areas.

3.3 PERFORMANCE

- A. General: Employ skilled workers to perform cutting and patching. Proceed with cutting and patching at the earliest feasible time, and complete without delay.
 1. Cut in-place construction to provide for installation of other components or performance of other construction, and subsequently patch as required to restore surfaces to their original condition.
- B. Cutting: Cut in-place construction by sawing, drilling, breaking, chipping, grinding, and similar operations, including excavation, using methods least likely to damage

CITY OF ORANGE BEACH
FIRE ADMINISTRATION BUILDING and POST OFFICE ROOF REPLACEMENTS
ISSUED 02-21-2022

elements retained or adjoining construction. If possible, review proposed procedures with original Installer; comply with original Installer's written recommendations.

1. In general, use hand or small power tools designed for sawing and grinding, not hammering and chopping. Cut holes and slots as small as possible, neatly to size required, and with minimum disturbance of adjacent surfaces. Temporarily cover openings when not in use.
 2. Proceed with patching after construction operations requiring cutting are complete.
- C. Patching: Patch construction by filling, repairing, refinishing, closing up, and similar operations following performance of other Work. Patch with durable seams that are as invisible as possible. Provide materials and comply with installation requirements specified in other Sections.
1. Inspection: Where feasible, test and inspect patched areas after completion to demonstrate integrity of installation.
 2. Exposed Finishes: Restore exposed finishes of patched areas and extend finish restoration into retained adjoining construction in a manner that will eliminate evidence of patching and refinishing.
 - a. Clean piping, conduit, and similar features before applying paint or other finishing materials.
 - b. Restore damaged pipe covering to its original condition.
- D. Cleaning: Clean areas and spaces where cutting and patching are performed. Completely remove paint, mortar, oils, putty, and similar materials.

END OF SECTION 017329

CITY OF ORANGE BEACH
FIRE ADMINISTRATION BUILDING and POST OFFICE ROOF REPLACEMENTS
ISSUED 02-21-2022

SECTION 017700 - CLOSEOUT PROCEDURES

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. This Section includes administrative and procedural requirements for contract closeout, including, but not limited to, the following:

1. Inspection procedures.
2. Warranties.
3. Final cleaning.

- B. Related Sections include the following:

1. Division 01 Section "Payment Procedures" for requirements for Applications for Payment for Substantial and Final Completion.
2. Division 01 Section "Execution" for progress cleaning of Project site.
3. Division 01 Section "Project Record Documents" for submitting Record Drawings, Record Specifications, and Record Product Data.
4. Division 01 Section "Operation and Maintenance Data" for operation and maintenance manual requirements.
5. Division 01 Section "Demonstration and Training" for requirements for instructing Owner's personnel.
6. Divisions 02 through 49 Sections for specific closeout and special cleaning requirements for the Work in those Sections.

1.3 SUBSTANTIAL COMPLETION

- A. Preliminary Procedures: Before requesting inspection for determining date of Substantial Completion, complete the following. List items below that are incomplete in request.

1. Prepare a list of items to be completed and corrected (punch list), the value of items on the list, and reasons why the Work is not complete.
2. Advise Owner of pending insurance changeover requirements.
3. Submit specific warranties, workmanship bonds, maintenance service agreements, final certifications, and similar documents.
4. Obtain and submit releases permitting Owner unrestricted use of the Work and access to services and utilities. Include occupancy permits, operating certificates, and similar releases.
5. Prepare and submit Project Record Documents, operation and maintenance manuals, damage or settlement surveys, property surveys, and similar final record information.

CITY OF ORANGE BEACH
FIRE ADMINISTRATION BUILDING and POST OFFICE ROOF REPLACEMENTS
ISSUED 02-21-2022

6. Deliver tools, spare parts, extra materials, and similar items to location designated by Owner. Label with manufacturer's name and model number where applicable.
 7. Make final changeover of permanent locks and deliver keys to Owner. Advise Owner's personnel of changeover in security provisions.
 8. Complete startup testing of systems.
 9. Submit test/adjust/balance records.
 10. Terminate and remove temporary facilities from Project site, along with mockups, construction tools, and similar elements.
 11. Advise Owner of changeover in heat and other utilities.
 12. Submit changeover information related to Owner's occupancy, use, operation, and maintenance.
 13. Complete final cleaning requirements, including touchup painting.
 14. Touch up and otherwise repair and restore marred exposed finishes to eliminate visual defects.
- B. Inspection: Submit a written request for inspection for Substantial Completion. On receipt of request, Architect will either proceed with inspection or notify Contractor of unfulfilled requirements. Architect will prepare the Certificate of Substantial Completion after inspection or will notify Contractor of items, either on Contractor's list or additional items identified by Architect, that must be completed or corrected before certificate will be issued.
1. Re-inspection: Request re-inspection when the Work identified in previous inspections as incomplete is completed or corrected.
 2. Results of completed inspection will form the basis of requirements for Final Completion.

1.4 FINAL COMPLETION

- A. Preliminary Procedures: Before requesting final inspection for determining date of Final Completion, complete the following:
1. Submit a final Application for Payment according to Division 01 Section "Payment Procedures."
 2. Submit certified copy of Architect's Substantial Completion inspection list of items to be completed or corrected (punch list), endorsed and dated by Architect. The certified copy of the list shall state that each item has been completed or otherwise resolved for acceptance.
 3. Submit evidence of final, continuing insurance coverage complying with insurance requirements.
 4. Submit pest-control final inspection report and warranty.
 5. Instruct Owner's personnel in operation, adjustment, and maintenance of products, equipment, and systems.
- B. Inspection: Submit a written request for final inspection for acceptance. On receipt of request, Architect will either proceed with inspection or notify Contractor of unfulfilled requirements. Architect will prepare a final Certificate for Payment after inspection or will notify Contractor of construction that must be completed or corrected before certificate will be issued.

CITY OF ORANGE BEACH
FIRE ADMINISTRATION BUILDING and POST OFFICE ROOF REPLACEMENTS
ISSUED 02-21-2022

1. Re-inspection: Request re-inspection when the Work identified in previous inspections as incomplete is completed or corrected.

1.5 LIST OF INCOMPLETE ITEMS (PUNCH LIST)

- A. Preparation: Submit three copies of list. Include name and identification of each space and area affected by construction operations for incomplete items and items needing correction including, if necessary, areas disturbed by Contractor that are outside the limits of construction. Use CSI Form 14.1A.
 1. Organize list of spaces in sequential order, starting with exterior areas first.
 2. Organize items applying to each space by major element, including categories for ceiling, individual walls, floors, equipment, and building systems.
 3. Include the following information at the top of each page:
 - a. Project name.
 - b. Date.
 - c. Name of Architect.
 - d. Name of Contractor.
 - e. Page number.

1.6 WARRANTIES

- A. Submittal Time: Submit written warranties on request of Architect for designated portions of the Work where commencement of warranties other than date of Substantial Completion is indicated.
- B. Partial Occupancy: Submit properly executed warranties within 15 days of completion of designated portions of the Work that are completed and occupied or used by Owner during construction period by separate agreement with Contractor.
- C. Organize warranty documents into an orderly sequence based on the table of contents of the Project Manual.
 1. Bind warranties and bonds in heavy-duty, 3-ring, vinyl-covered, loose-leaf binders, thickness as necessary to accommodate contents, and sized to receive 8-1/2-by-11-inch paper.
 2. Provide heavy paper dividers with plastic-covered tabs for each separate warranty. Mark tab to identify the product or installation. Provide a typed description of the product or installation, including the name of the product and the name, address, and telephone number of Installer.
 3. Identify each binder on the front and spine with the typed or printed title "WARRANTIES," Project name, and name of Contractor.
- D. Provide additional copies of each warranty to include in operation and maintenance manuals.

PART 2 - PRODUCTS

2.1 MATERIALS

- A. Cleaning Agents: Use cleaning materials and agents recommended by manufacturer or fabricator of the surface to be cleaned. Do not use cleaning agents that are potentially hazardous to health or property or that might damage finished surfaces.

CITY OF ORANGE BEACH
FIRE ADMINISTRATION BUILDING and POST OFFICE ROOF REPLACEMENTS
ISSUED 02-21-2022

PART 3 - EXECUTION

3.1 FINAL CLEANING

- A. General: Provide final cleaning. Conduct cleaning and waste-removal operations to comply with local laws and ordinances and Federal and local environmental and antipollution regulations.
- B. Cleaning: Employ experienced workers or professional cleaners for final cleaning. Clean each surface or unit to condition expected in an average commercial building cleaning and maintenance program. Comply with manufacturer's written instructions.
 - 1. Complete the following cleaning operations before requesting inspection for certification of Substantial Completion for entire Project or for a portion of Project:
 - a. Clean Project site, yard, and grounds, in areas disturbed by construction activities, including landscape development areas, of rubbish, waste material, litter, and other foreign substances.
 - b. Sweep paved areas broom clean. Remove petrochemical spills, stains, and other foreign deposits.
 - c. Rake grounds that are neither planted nor paved to a smooth, even-textured surface.
 - d. Remove tools, construction equipment, machinery, and surplus material from Project site.
 - e. Clean exposed exterior and interior hard-surfaced finishes to a dirt-free condition, free of stains, films, and similar foreign substances. Avoid disturbing natural weathering of exterior surfaces. Restore reflective surfaces to their original condition.
 - f. Remove debris and surface dust from limited access spaces, including roofs, plenums, shafts, trenches, equipment vaults, manholes, attics, and similar spaces.
 - g. Sweep concrete floors broom clean in unoccupied spaces.
 - h. Vacuum carpet and similar soft surfaces, removing debris and excess nap; shampoo if visible soil or stains remain.
 - i. Clean transparent materials, including mirrors and glass in doors and windows. Remove glazing compounds and other noticeable, vision-obscuring materials. Replace chipped or broken glass and other damaged transparent materials. Polish mirrors and glass, taking care not to scratch surfaces.
 - j. Remove labels that are not permanent.
 - k. Touch up and otherwise repair and restore marred, exposed finishes and surfaces. Replace finishes and surfaces that cannot be satisfactorily repaired or restored or that already show evidence of repair or restoration.
 - 1) Do not paint over "UL" and similar labels, including mechanical and electrical nameplates.
 - l. Wipe surfaces of mechanical and electrical equipment and similar equipment. Remove excess lubrication, paint and mortar droppings, and other foreign substances.
 - m. Replace parts subject to unusual operating conditions.

CITY OF ORANGE BEACH
FIRE ADMINISTRATION BUILDING and POST OFFICE ROOF REPLACEMENTS
ISSUED 02-21-2022

- n. Clean plumbing fixtures to a sanitary condition, free of stains, including stains resulting from water exposure.
 - o. Replace disposable air filters and clean permanent air filters. Clean exposed surfaces of diffusers, registers, and grills.
 - p. Clean ducts, blowers, and coils if units were operated without filters during construction.
 - q. Clean light fixtures, lamps, globes, and reflectors to function with full efficiency. Replace burned-out bulbs, and those noticeably dimmed by hours of use, and defective and noisy starters in fluorescent and mercury vapor fixtures to comply with requirements for new fixtures.
 - r. Leave Project clean and ready for occupancy.
- C. Pest Control: Engage an experienced, licensed exterminator to make a final inspection and rid Project of rodents, insects, and other pests. Prepare a report.
- D. Comply with safety standards for cleaning. Do not burn waste materials. Do not bury debris or excess materials on Owner's property. Do not discharge volatile, harmful, or dangerous materials into drainage systems. Remove waste materials from Project site and dispose of lawfully.

END OF SECTION 017700

CITY OF ORANGE BEACH
FIRE ADMINISTRATION BUILDING and POST OFFICE ROOF REPLACEMENTS
ISSUED 02-21-2022

SECTION 017823 - OPERATION AND MAINTENANCE DATA

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. This Section includes administrative and procedural requirements for preparing operation and maintenance manuals, including the following:
 - 1. Operation manuals for systems, subsystems, and equipment.
 - 2. Maintenance manuals for the care and maintenance of systems and equipment.
- B. Related Sections include the following:
 - 1. Division 01 Section "Submittal Procedures" for submitting copies of submittals for operation and maintenance manuals.
 - 2. Division 01 Section "Closeout Procedures" for submitting operation and maintenance manuals.
 - 3. Division 01 Section "Project Record Documents" for preparing Record Drawings for operation and maintenance manuals.
 - 4. Divisions 02 through 49 Sections for specific operation and maintenance manual requirements for the Work in those Sections.

1.3 DEFINITIONS

- A. System: An organized collection of parts, equipment, or subsystems united by regular interaction.
- B. Subsystem: A portion of a system with characteristics similar to a system.

1.4 SUBMITTALS

- A. Final Submittal: Submit one copy of each manual in final form at least 15 days before final inspection. Architect will return copy with comments within 15 days after final inspection.
 - 1. Correct or modify each manual to comply with Architect's comments. Submit 3 copies of each corrected manual within 15 days of receipt of Architect's comments.

1.5 COORDINATION

- A. Where operation and maintenance documentation includes information on installations by more than one factory-authorized service representative, assemble and coordinate information furnished by representatives and prepare manuals.

PART 2 - PRODUCTS

CITY OF ORANGE BEACH
FIRE ADMINISTRATION BUILDING and POST OFFICE ROOF REPLACEMENTS
ISSUED 02-21-2022

2.1 MANUALS, GENERAL

- A. Organization: Unless otherwise indicated, organize each manual into a separate section for each system and subsystem, and a separate section for each piece of equipment not part of a system. Each manual shall contain the following materials, in the order listed:
1. Title page.
 2. Table of contents.
 3. Manual contents.
- B. Title Page: Enclose title page in transparent plastic sleeve. Include the following information:
1. Subject matter included in manual.
 2. Name and address of Project.
 3. Name and address of Owner.
 4. Date of submittal.
 5. Name, address, and telephone number of Contractor.
 6. Name and address of Architect.
 7. Cross-reference to related systems in other operation and maintenance manuals.
- C. Table of Contents: List each product included in manual, identified by product name, indexed to the content of the volume, and cross-referenced to Specification Section number in Project Manual.
1. If operation or maintenance documentation requires more than one volume to accommodate data, include comprehensive table of contents for all volumes in each volume of the set.
- D. Manual Contents: Organize into sets of manageable size. Arrange contents alphabetically by system, subsystem, and equipment. If possible, assemble instructions for subsystems, equipment, and components of one system into a single binder.
1. Binders: Heavy-duty, 3-ring, vinyl-covered, loose-leaf binders, in thickness necessary to accommodate contents, sized to hold 8-1/2-by-11-inch paper; with clear plastic sleeve on spine to hold label describing contents and with pockets inside covers to hold folded oversize sheets.
 - a. If two or more binders are necessary to accommodate data of a system, organize data in each binder into groupings by subsystem and related components. Cross-reference other binders if necessary to provide essential information for proper operation or maintenance of equipment or system.
 - b. Identify each binder on front and spine, with printed title "OPERATION AND MAINTENANCE MANUAL," Project title or name, and subject matter of contents. Indicate volume number for multiple-volume sets.
 2. Dividers: Heavy-paper dividers with plastic-covered tabs for each section. Mark each tab to indicate contents. Include typed list of products and major components of equipment included in the section on each divider, cross-referenced to Specification Section number and title of Project Manual.

CITY OF ORANGE BEACH
FIRE ADMINISTRATION BUILDING and POST OFFICE ROOF REPLACEMENTS
ISSUED 02-21-2022

3. Protective Plastic Sleeves: Transparent plastic sleeves designed to enclose diagnostic software diskettes for computerized electronic equipment.
4. Supplementary Text: Prepared on 8-1/2-by-11-inch white bond paper.
5. Drawings: Attach reinforced, punched binder tabs on drawings and bind with text.
 - a. If oversize drawings are necessary, fold drawings to same size as text pages and use as foldouts.
 - b. If drawings are too large to be used as foldouts, fold and place drawings in labeled envelopes and bind envelopes in rear of manual. At appropriate locations in manual, insert typewritten pages indicating drawing titles, descriptions of contents, and drawing locations.

2.2 OPERATION MANUALS

- A. Content: In addition to requirements in this Section, include operation data required in individual Specification Sections and the following information:
 1. System, subsystem, and equipment descriptions.
 2. Performance and design criteria if Contractor is delegated design responsibility.
 3. Operating standards.
 4. Operating procedures.
 5. Operating logs.
 6. Wiring diagrams.
 7. Control diagrams.
 8. Piped system diagrams.
 9. Precautions against improper use.
 10. License requirements including inspection and renewal dates.
- B. Descriptions: Include the following:
 1. Product name and model number.
 2. Manufacturer's name.
 3. Equipment identification with serial number of each component.
 4. Equipment function.
 5. Operating characteristics.
 6. Limiting conditions.
 7. Performance curves.
 8. Engineering data and tests.
 9. Complete nomenclature and number of replacement parts.
- C. Operating Procedures: Include the following, as applicable:
 1. Startup procedures.
 2. Equipment or system break-in procedures.
 3. Routine and normal operating instructions.
 4. Regulation and control procedures.
 5. Instructions on stopping.
 6. Normal shutdown instructions.
 7. Seasonal and weekend operating instructions.
 8. Required sequences for electric or electronic systems.
 9. Special operating instructions and procedures.

CITY OF ORANGE BEACH
FIRE ADMINISTRATION BUILDING and POST OFFICE ROOF REPLACEMENTS
ISSUED 02-21-2022

- D. Systems and Equipment Controls: Describe the sequence of operation, and diagram controls as installed.
- E. Piped Systems: Diagram piping as installed, and identify color-coding where required for identification.

2.3 SYSTEMS AND EQUIPMENT MAINTENANCE MANUAL

- A. Content: For each system, subsystem, and piece of equipment not part of a system, include source information, manufacturers' maintenance documentation, maintenance procedures, maintenance and service schedules, spare parts list and source information, maintenance service contracts, and warranty and bond information, as described below.
- B. Source Information: List each system, subsystem, and piece of equipment included in manual, identified by product name and arranged to match manual's table of contents. For each product, list name, address, and telephone number of Installer or supplier and maintenance service agent, and cross-reference Specification Section number and title in Project Manual.
- C. Manufacturers' Maintenance Documentation: Manufacturers' maintenance documentation including the following information for each component part or piece of equipment:
 - 1. Standard printed maintenance instructions and bulletins.
 - 2. Drawings, diagrams, and instructions required for maintenance, including disassembly and component removal, replacement, and assembly.
 - 3. Identification and nomenclature of parts and components.
 - 4. List of items recommended to be stocked as spare parts.
- D. Maintenance Procedures: Include the following information and items that detail essential maintenance procedures:
 - 1. Test and inspection instructions.
 - 2. Troubleshooting guide.
 - 3. Precautions against improper maintenance.
 - 4. Disassembly; component removal, repair, and replacement; and reassembly instructions.
 - 5. Aligning, adjusting, and checking instructions.
 - 6. Demonstration and training videotape, if available.
- E. Maintenance and Service Schedules: Include service and lubrication requirements, list of required lubricants for equipment, and separate schedules for preventive and routine maintenance and service with standard time allotment.
 - 1. Scheduled Maintenance and Service: Tabulate actions for daily, weekly, monthly, quarterly, semiannual, and annual frequencies.
 - 2. Maintenance and Service Record: Include manufacturers' forms for recording maintenance.
- F. Spare Parts List and Source Information: Include lists of replacement and repair parts, with parts identified and cross-referenced to manufacturers' maintenance documentation and local sources of maintenance materials and related services.

CITY OF ORANGE BEACH
FIRE ADMINISTRATION BUILDING and POST OFFICE ROOF REPLACEMENTS
ISSUED 02-21-2022

- G. Maintenance Service Contracts: Include copies of maintenance agreements with name and telephone number of service agent.
- H. Warranties and Bonds: Include copies of warranties and bonds and lists of circumstances and conditions that would affect validity of warranties or bonds.
 - 1. Include procedures to follow and required notifications for warranty claims.

PART 3 - EXECUTION

3.1 MANUAL PREPARATION

- A. Operation and Maintenance Manuals: Assemble a complete set of operation and maintenance data indicating operation and maintenance of each system, subsystem, and piece of equipment not part of a system.
 - 1. Engage a factory-authorized service representative to assemble and prepare information for each system, subsystem, and piece of equipment not part of a system.
 - 2. Prepare a separate manual for each system and subsystem, in the form of an instructional manual for use by Owner's operating personnel.
- B. Manufacturers' Data: Where manuals contain manufacturers' standard printed data, include only sheets pertinent to product or component installed. Mark each sheet to identify each product or component incorporated into the Work. If data include more than one item in a tabular format, identify each item using appropriate references from the Contract Documents. Identify data applicable to the Work and delete references to information not applicable.
 - 1. Prepare supplementary text if manufacturers' standard printed data are not available and where the information is necessary for proper operation and maintenance of equipment or systems.
- C. Drawings: Prepare drawings supplementing manufacturers' printed data to illustrate the relationship of component parts of equipment and systems and to illustrate control sequence and flow diagrams. Coordinate these drawings with information contained in Record Drawings to ensure correct illustration of completed installation.
 - 1. Do not use original Project Record Documents as part of operation and maintenance manuals.
 - 2. Comply with requirements of newly prepared Record Drawings in Division 01 Section "Project Record Documents."
- D. Comply with Division 01 Section "Closeout Procedures" for schedule for submitting operation and maintenance documentation.

END OF SECTION 017823

CITY OF ORANGE BEACH
FIRE ADMINISTRATION BUILDING and POST OFFICE ROOF REPLACEMENTS
ISSUED 02-21-2022

SECTION 017839 - PROJECT RECORD DOCUMENTS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. This Section includes administrative and procedural requirements for Project Record Documents, including the following:
 - 1. Record Drawings.
 - 2. Record Specifications.
- B. Related Sections include the following:
 - 1. Division 01 Section "Closeout Procedures" for general closeout procedures.
 - 2. Division 01 Section "Operation and Maintenance Data" for operation and maintenance manual requirements.
 - 3. Divisions 02 through 49 Sections for specific requirements for Project Record Documents of the Work in those Sections.

1.3 SUBMITTALS

- A. Record Drawings: Comply with the following:
 - 1. Number of Copies: Submit one set(s) of marked-up Record Prints.
- B. Record Specifications: Submit one copy of Project's Specifications, including addenda and contract modifications.

PART 2 - PRODUCTS

2.1 RECORD DRAWINGS

- A. Record Prints: Maintain one set of blue- or black-line white prints of the Contract Drawings and Shop Drawings.
 - 1. Preparation: Mark Record Prints to show the actual installation where installation varies from that shown originally. Require individual or entity who obtained record data, whether individual or entity is Installer, subcontractor, or similar entity, to prepare the marked-up Record Prints.
 - a. Give particular attention to information on concealed elements that would be difficult to identify or measure and record later.
 - b. Accurately record information in an understandable drawing technique.
 - c. Record data as soon as possible after obtaining it. Record and check the markup before enclosing concealed installations.

CITY OF ORANGE BEACH
FIRE ADMINISTRATION BUILDING and POST OFFICE ROOF REPLACEMENTS
ISSUED 02-21-2022

2. Content: Types of items requiring marking include, but are not limited to, the following:
 - a. Dimensional changes to Drawings.
 - b. Revisions to details shown on Drawings.
 - c. Depths of foundations below first floor.
 - d. Locations and depths of underground utilities.
 - e. Revisions to routing of piping and conduits.
 - f. Revisions to electrical circuitry.
 - g. Actual equipment locations.
 - h. Duct size and routing.
 - i. Locations of concealed internal utilities.
 - j. Changes made by Change Order or Construction Change Directive.
 - k. Changes made following Architect's written orders.
 - l. Details not on the original Contract Drawings.
 - m. Field records for variable and concealed conditions.
 - n. Record information on the Work that is shown only schematically.
 3. Mark the Contract Drawings or Shop Drawings, whichever is most capable of showing actual physical conditions, completely and accurately. If Shop Drawings are marked, show cross-reference on the Contract Drawings.
 4. Mark record sets with erasable, red-colored pencil. Use other colors to distinguish between changes for different categories of the Work at same location.
 5. Mark important additional information that was either shown schematically or omitted from original Drawings.
 6. Note Construction Change Directive numbers, alternate numbers, Change Order numbers, and similar identification, where applicable.
- B. Record Transparencies: Immediately before inspection for Certificate of Substantial Completion, review marked-up Record Prints with Architect. When authorized, prepare a full set of corrected transparencies of the Contract Drawings and Shop Drawings.
1. Incorporate changes and additional information previously marked on Record Prints. Erase, redraw, and add details and notations where applicable.
 2. Refer instances of uncertainty to Architect for resolution.
 3. Print the Contract Drawings and Shop Drawings for use as Record Transparencies. Architect will make the Contract Drawings available to Contractor's print shop.
- C. Newly Prepared Record Drawings: Prepare new Drawings instead of preparing Record Drawings where Architect determines that neither the original Contract Drawings nor Shop Drawings are suitable to show actual installation.
1. New Drawings may be required when a Change Order is issued as a result of accepting an alternate, substitution, or other modification.
 2. Consult Architect for proper scale and scope of detailing and notations required to record the actual physical installation and its relation to other construction. Integrate newly prepared Record Drawings into Record Drawing sets; comply with procedures for formatting, organizing, copying, binding, and submitting.

CITY OF ORANGE BEACH
FIRE ADMINISTRATION BUILDING and POST OFFICE ROOF REPLACEMENTS
ISSUED 02-21-2022

- D. Format: Identify and date each Record Drawing; include the designation "PROJECT RECORD DRAWING" in a prominent location.
1. Record Prints: Organize Record Prints and newly prepared Record Drawings into manageable sets. Bind each set with durable paper cover sheets. Include identification on cover sheets.
 2. Record Transparencies: Organize into unbound sets matching Record Prints. Place transparencies in durable tube-type drawing containers with end caps. Mark end cap of each container with identification. If container does not include a complete set, identify Drawings included.
 3. Identification: As follows:
 - a. Project name.
 - b. Date.
 - c. Designation "PROJECT RECORD DRAWINGS."
 - d. Name of Architect.
 - e. Name of Contractor.

2.2 RECORD SPECIFICATIONS

- A. Preparation: Mark Specifications to indicate the actual product installation where installation varies from that indicated in Specifications, addenda, and contract modifications.
1. Give particular attention to information on concealed products and installations that cannot be readily identified and recorded later.
 2. Mark copy with the proprietary name and model number of products, materials, and equipment furnished, including substitutions and product options selected.
 3. Record the name of manufacturer, supplier, Installer, and other information necessary to provide a record of selections made.
 4. For each principal product, indicate whether Record Product Data has been submitted in operation and maintenance manuals instead of submitted as Record Product Data.
 5. Note related Change Orders and Record Drawings where applicable.

2.3 MISCELLANEOUS RECORD SUBMITTALS

- A. Assemble miscellaneous records required by other Specification Sections for miscellaneous record keeping and submittal in connection with actual performance of the Work. Bind or file miscellaneous records and identify each, ready for continued use and reference.

PART 3 - EXECUTION

3.1 RECORDING AND MAINTENANCE

- A. Recording: Maintain one copy of each submittal during the construction period for Project Record Document purposes. Post changes and modifications to Project Record Documents as they occur; do not wait until the end of Project.
- B. Maintenance of Record Documents and Samples: Store Record Documents and Samples in the field office apart from the Contract Documents used for construction. Do not use Project Record Documents for construction purposes. Maintain Record

CITY OF ORANGE BEACH
FIRE ADMINISTRATION BUILDING and POST OFFICE ROOF REPLACEMENTS
ISSUED 02-21-2022

Documents in good order and in a clean, dry, legible condition, protected from deterioration and loss. Provide access to Project Record Documents for Architect's reference during normal working hours.

END OF SECTION 017839

CITY OF ORANGE BEACH
FIRE ADMINISTRATION BUILDING and POST OFFICE ROOF REPLACEMENTS
ISSUED 02-21-2022

SECTION 017900 - DEMONSTRATION AND TRAINING

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. This Section includes administrative and procedural requirements for instructing Owner's personnel, including the following:
 - 1. Demonstration of operation of systems, subsystems, and equipment.
 - 2. Training in operation and maintenance of systems, subsystems, and equipment.
- B. Related Sections include the following:
 - 1. Divisions 02 through 49 Sections for specific requirements for demonstration and training for products in those Sections.

1.3 SUBMITTALS

- A. Instruction Program: Submit two copies of outline of instructional program for demonstration and training, including a schedule of proposed dates, times, length of instruction time, and instructors' names for each training module. Include learning objective and outline for each training module.
 - 1. At completion of training, submit one complete training manual(s) for Owner's use.
- B. Qualification Data: For instructor.

1.4 QUALITY ASSURANCE

- A. Facilitator Qualifications: A firm or individual experienced in training or educating maintenance personnel in a training program similar in content and extent to that indicated for this Project, and whose work has resulted in training or education with a record of successful learning performance.
- B. Instructor Qualifications: A factory-authorized service representative, complying with requirements in Division 01 Section "Quality Requirements," experienced in operation and maintenance procedures and training.

1.5 COORDINATION

- A. Coordinate instruction schedule with Owner's operations. Adjust schedule as required to minimize disrupting Owner's operations.
- B. Coordinate instructors, including providing notification of dates, times, length of instruction time, and course content.

CITY OF ORANGE BEACH
FIRE ADMINISTRATION BUILDING and POST OFFICE ROOF REPLACEMENTS
ISSUED 02-21-2022

- C. Coordinate content of training modules with content of approved emergency, operation, and maintenance manuals. Do not submit instruction program until operation and maintenance data has been reviewed and approved by Architect.

PART 2 - PRODUCTS

2.1 INSTRUCTION PROGRAM

- A. Program Structure: Develop an instruction program that includes individual training modules for each system and equipment not part of a system, as required by individual Specification Sections, and as follows:
1. Fire-protection systems, including fire alarm and fire-extinguishing systems.
 2. HVAC instrumentation and controls.
 3. Packaged engine generators, including transfer switches.
- B. Training Modules: Develop a learning objective and teaching outline for each module. Include a description of specific skills and knowledge that participant is expected to master. For each module, include instruction for the following:
1. Documentation: Review the following items in detail:
 - a. Emergency manuals.
 - b. Operations manuals.
 - c. Maintenance manuals.
 - d. Project Record Documents.
 - e. Identification systems.
 - f. Warranties and bonds.
 - g. Maintenance service agreements and similar continuing commitments.
 2. Emergencies: Include the following, as applicable:
 - a. Instructions on meaning of warnings, trouble indications, and error messages.
 - b. Instructions on stopping.
 - c. Shutdown instructions for each type of emergency.
 - d. Operating instructions for conditions outside of normal operating limits.
 - e. Sequences for electric or electronic systems.
 - f. Special operating instructions and procedures.
 3. Operations: Include the following, as applicable:
 - a. Startup procedures.
 - b. Equipment or system break-in procedures.
 - c. Routine and normal operating instructions.
 - d. Regulation and control procedures.
 - e. Control sequences.
 - f. Safety procedures.
 - g. Instructions on stopping.
 - h. Normal shutdown instructions.
 - i. Operating procedures for emergencies.
 - j. Operating procedures for system, subsystem, or equipment failure.

CITY OF ORANGE BEACH
FIRE ADMINISTRATION BUILDING and POST OFFICE ROOF REPLACEMENTS
ISSUED 02-21-2022

- k. Seasonal and weekend operating instructions.
 - l. Required sequences for electric or electronic systems.
 - m. Special operating instructions and procedures.
4. Adjustments: Include the following:
- a. Alignments.
 - b. Checking adjustments.
 - c. Noise and vibration adjustments.
 - d. Economy and efficiency adjustments.
5. Troubleshooting: Include the following:
- a. Diagnostic instructions.
 - b. Test and inspection procedures.
6. Maintenance: Include the following:
- a. Inspection procedures.
 - b. Types of cleaning agents to be used and methods of cleaning.
 - c. List of cleaning agents and methods of cleaning detrimental to product.
 - d. Procedures for routine cleaning
 - e. Procedures for preventive maintenance.
 - f. Procedures for routine maintenance.
 - g. Instruction on use of special tools.
7. Repairs: Include the following:
- a. Diagnosis instructions.
 - b. Repair instructions.
 - c. Disassembly; component removal, repair, and replacement; and reassembly instructions.
 - d. Instructions for identifying parts and components.
 - e. Review of spare parts needed for operation and maintenance.

PART 3 - EXECUTION

3.1 PREPARATION

- A. Assemble educational materials necessary for instruction, including documentation and training module. Assemble training modules into a combined training manual.
- B. Set up instructional equipment at instruction location.

3.2 INSTRUCTION

- A. Engage qualified instructors to instruct Owner's personnel to adjust, operate, and maintain systems, subsystems, and equipment not part of a system.
 - 1. Architect will furnish an instructor to describe basis of system design, operational requirements, criteria, and regulatory requirements.
 - 2. Owner will furnish an instructor to describe Owner's operational philosophy.
 - 3. Owner will furnish Contractor with names and positions of participants.

CITY OF ORANGE BEACH
FIRE ADMINISTRATION BUILDING and POST OFFICE ROOF REPLACEMENTS
ISSUED 02-21-2022

- B. Scheduling: Provide instruction at mutually agreed on times. For equipment that requires seasonal operation, provide similar instruction at start of each season.
 - 1. Schedule training with Owner with at least seven days' advance notice.
- C. Cleanup: Collect used and leftover educational materials and give to Owner. Remove instructional equipment. Restore systems and equipment to condition existing before initial training use.

END OF SECTION 017900

CITY OF ORANGE BEACH
FIRE ADMINISTRATION BUILDING and POST OFFICE ROOF REPLACEMENTS
ISSUED 02-21-2022

SECTION 06100 - ROUGH CARPENTRY

PART 1 - GENERAL

- 1.1 RELATED DOCUMENTS
- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.
- 1.2 SUMMARY
- A. Section Includes:
1. Wood blocking and Nailers.
 2. Roof Sheathing.
- 1.3 DEFINITIONS
- A. Dimension Lumber: Lumber of 2 inches nominal or greater but less than 5 inches nominal in least dimension.
- B. Lumber grading agencies, and the abbreviations used to reference them, include the following:
1. SPIB: The Southern Pine Inspection Bureau.
- 1.4 REFERENCE PUBLICATIONS, CODES AND STANDARDS
- A. The editions in effect as of the issue date of these documents or as modified by amendment thereof of the following publications, codes, and standards shall be deemed part of this specification as applicable:
1. U.S. Department of Commerce, Simplified Practice Recommendation R16-53 American Lumber Standards for Softwood Lumber
 2. IBC 2009 Building Code
 3. Occupational Safety and Health Administration (OSHA)
 4. American Society of Testing and Materials (ASTM)
 5. All Applicable Federal, State, Local and Owner Regulations
- 1.5 QUALITY ASSURANCE
- A. Testing Agency Qualifications: For testing agency providing classification marking for fire-retardant treated material, an inspection agency acceptable to authorities having jurisdiction that periodically performs inspections to verify that the material bearing the classification marking is representative of the material tested.
- 1.6 DELIVERY, STORAGE, AND HANDLING
- A. All materials shall be delivered to the site in their original, undamaged containers.
- B. Stack lumber flat with spacers beneath and between each bundle to provide air circulation. Protect lumber from weather by covering with waterproof sheeting, securely anchored. Provide for air circulation around stacks and under coverings.
- C. The Contractor shall verify all items delivered comply with this specification.
- D. The Contractor shall inspect each item for damage and replace any deficiencies, errors, or damaged items in a timely fashion so as not to delay construction.

PART 2 - PRODUCTS

- 2.1 WOOD PRODUCTS, GENERAL
- A. Lumber: Provide lumber that complies with the applicable rules of any rules-writing agency certified by the ALSC Board of Review.
1. Factory mark each piece of lumber with grade stamp of grading agency.

CITY OF ORANGE BEACH
FIRE ADMINISTRATION BUILDING and POST OFFICE ROOF REPLACEMENTS
ISSUED 02-21-2022

2. Where nominal sizes are indicated, provide actual sizes required by DOC PS 20 for moisture content specified. Where actual sizes are indicated, they are minimum dressed sizes for dry lumber.

3. Provide dressed lumber, S4S, unless otherwise indicated.

B. Maximum Moisture Content of Lumber: 15 percent for 2-inch nominal thickness or less, 19 percent for more than 2-inch nominal thickness unless otherwise indicated.

2.2 WOOD-PRESERVATIVE-TREATED LUMBER

A. Preservative Treatment by Pressure Process: AWPA U1; Category UC3b.

1. Preservative Chemicals: Inorganic Boron (SBX), or any treatment that is acceptable to authorities having jurisdiction and containing no arsenic or chromium.

B. Kiln-dry lumber after treatment to a maximum moisture content of 19 percent. Do not use material that is warped or that does not comply with requirements for untreated material.

C. Mark lumber with treatment quality mark of an inspection agency approved by the ALSC Board of Review.

D. Application: Treat all rough carpentry unless otherwise indicated.

1. Wood nailers, curbs, equipment support bases, blocking, stripping, and similar members in connection with roofing, flashing, and waterproofing.

2. Wood blocking in contact with masonry or concrete.

2.3 PLYWOOD ROOF SHEATHING

A. Sheathing for infill of openings from removal of cupola and replacement of damaged plywood sheathing at roof.

1. Exterior Exposure 1

2. Grade: CD (CDX).

3. Nominal Thickness: 5/8".

2.4 FASTENERS

A. General: Provide fasteners of size and type indicated that comply with requirements specified in this article for material and manufacture.

1. Where rough carpentry is exposed to weather, in ground contact, pressure-preservative treated, or in area of high relative humidity, provide fasteners with hot-dip zinc coating complying with ASTM A 153/A 153M.

B. Nails: ASTM F 1667, 8d, 2 1/2", Deformed-shank (i.e., ring- or screw-shank)

C. Power-Driven Fasteners: NES NER-272.

D. Wood Screws: #14 x 2 1/2" heavy duty roofing screws with a pan head. Screws should be capable of penetrating a minimum of 1 1/2" into top chord of wood truss.

PART 3 - EXECUTION

3.1 WOOD BLOCKING INSTALLATION

A. Provide blocking and framing as indicated and as required to support facing materials and trim.

B. Sort and select lumber so that natural characteristics will not interfere with installation or with fastening other materials to lumber. Do not use materials with defects that interfere with function of member or pieces that are too small to use with minimum number of joints or optimum joint arrangement.

C. Comply with AWPA M4 for applying field treatment to cut surfaces of preservative-treated lumber.

D. Securely attach rough carpentry work to substrate by anchoring and fastening as indicated, complying with the following:

CITY OF ORANGE BEACH
FIRE ADMINISTRATION BUILDING and POST OFFICE ROOF REPLACEMENTS
ISSUED 02-21-2022

1. NES NER-272 for power-driven fasteners.
 2. Table 2304.9.1, "Fastening Schedule," in ICC's International Building Code.
 - E. Use steel common nails unless otherwise indicated. Select fasteners of size that will not fully penetrate members where opposite side will be exposed to view or will receive finish materials. Make tight connections between members. Install fasteners without splitting wood. Drive nails snug but do not countersink nail heads unless otherwise indicated.
 - F. If preservative chemicals other than Inorganic Boron (SBX) is used for treating wood blocking, provide ASTM D 226/D 226M, Type II (No. 30), asphalt-saturated organic felt; nonperforated, between preservative treated wood blocking and sheet metal flashing and trim..
- 3.2 NEW / EXISTING PLYWOOD / OSB INSTALLATION
- A. General: Comply with applicable recommendations in APA Form No. E30, "Engineered Wood Construction Guide," for types of structural-use panels and applications indicated.
 - B. Fastening Methods: Fasten panels as indicated below:
 1. Roof Sheathing:(Additional Anchors)
 - a. Screws:
 - 1) 20 fasteners per sheet, minimum of (4) fasteners per framing member.
- 3.3 INSPECTIONS, TESTING AND QUALITY ASSURANCE
- A. Visual observation of items of the work will be performed by the Owner's Representative and Architect. Any item deemed unacceptable or unsatisfactory shall be repaired or replaced at the Contractor's expense.
- 3.4 PROTECTION
- A. Protect wood that has been treated with inorganic boron (SBX) from weather. If, despite protection, inorganic boron-treated wood becomes wet, apply EPA-registered borate treatment. Apply borate solution by spraying to comply with EPA-registered label.
 - B. Protect rough carpentry from weather. If, despite protection, rough carpentry becomes sufficiently wet that moisture content exceeds that specified, apply EPA-registered borate treatment. Apply borate solution by spraying to comply with EPA-registered label.

END OF SECTION

CITY OF ORANGE BEACH
FIRE ADMINISTRATION BUILDING and POST OFFICE ROOF REPLACEMENTS
ISSUED 02-21-2022

SECTION 07542-THERMOPLASTIC POLYOLEFIN (TPO) ROOFING

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section Includes:

- 1. Adhered thermoplastic polyolefin (TPO) roofing system.
- 2. Roof insulation.

B. Related Requirements:

- 1. Section 06100 "Rough Carpentry" for wood nailers, curbs, and blocking; and for wood-based, structural-use roof deck panels.
- 2. Section 07620 "Sheet Metal Flashing and Trim" for metal roof flashings and counter flashings.
- 3. Section 07920 "Joint Sealants" for joint sealants, joint fillers, and joint preparation.

1.3 DEFINITIONS

- A. Roofing Terminology: Definitions in ASTM D 1079 and glossary in NRCA's "The NRCA Roofing and Waterproofing Manual" apply to work of this Section.

1.4 PRE-INSTALLATION ROOFING CONFERENCE

- A. Owner, Architect, General Contractor, roofing installer, roofing system manufacturer's representative, and installers whose work interfaces with or affects roofing, including fabricators/installers of sheet metal flashing, installers of roof accessories and roof-mounted equipment.

- 1. Conduct conference at Project site.
- 2. Review methods and procedures related to roofing installation, including manufacturer's written instructions.
- 3. Review and finalize construction schedule, and verify availability of materials, Installer's personnel, equipment, and facilities needed to make progress and avoid delays.
- 4. Examine deck substrate conditions and finishes for compliance with requirements, including flatness and fastening.
- 5. Review structural loading limitations of roof deck during and after roofing.
- 6. Review base flashings, special roofing details, roof drainage, roof penetrations, equipment curbs, and condition of other construction that affects roofing system.
- 7. Review governing regulations and requirements for insurance and certificates if applicable.
- 8. Review temporary protection requirements for roofing system during and after installation.
- 9. Review roof observation and repair procedures after roofing installation.

1.5 ACTION SUBMITTALS

- A. Product Data: For each type of product.
- B. Shop Drawings: For roofing system. Include plans, elevations, sections, details, and attachments to other work, including:
 - 1. Base flashings, edge flashings, expansion joint flashings, equipment curb flashings, penetration flashings, and membrane terminations.
 - 2. Tapered Insulation for all sloped areas (entire roof system), including crickets.
- C. Samples for Verification: For the following products:

CITY OF ORANGE BEACH
FIRE ADMINISTRATION BUILDING and POST OFFICE ROOF REPLACEMENTS
ISSUED 02-21-2022

1. Sheet roofing, of color required.
2. Walkway pads or rolls, of color required.

1.6 INFORMATIONAL SUBMITTALS

- A. Qualification Data: For Installer and manufacturer.
 1. Evidence that Manufacturer, Contractor, and Contractor Personnel meet the requirements of the Quality Assurance article below.
- B. Manufacturer Certificates: Signed by roofing manufacturer certifying that roofing system complies with requirements specified in "Performance Requirements" Article.
 1. Submit evidence of compliance with performance requirements.
- C. Field quality-control reports.
- D. Sample Warranties: For manufacturer's special warranties.

1.7 CLOSEOUT SUBMITTALS

- A. Maintenance Data: For roofing system to include in maintenance manuals.

1.8 QUALITY ASSURANCE

- A. Installer Qualifications: A qualified firm that is approved, authorized, or licensed by roofing system manufacturer to install manufacturer's product and that is eligible to receive a manufacturer's special extended warranty.
 - a. Carlisle "Authorized Applicator"
 - b. Firestone "Red Shield Contractor"
 - c. GAF "Master Contractor"
 - d. Johns Manville "Peak Advantage Contractor"
2. Company must have a minimum operating history of five years (from the present time) in the commercial roofing industry and have installed the specified roofing system or a similar on a minimum of 2 roofs per year in the last 5 years.
3. Site supervisory personnel must have a minimum of 5 years of experience installing roofing systems similar to the system specified.

1.9 DELIVERY, STORAGE, AND HANDLING

- A. Deliver roofing materials to Project site in original containers with seals unbroken and labeled with manufacturer's name, product brand name and type, date of manufacture, approval or listing agency markings, and directions for storing and mixing with other components.
- B. Store liquid materials in their original undamaged containers in a clean, dry, protected location and within the temperature range required by roofing system manufacturer. Protect stored liquid material from direct sunlight.
 1. Discard and legally dispose of liquid material that cannot be applied within its stated shelf life.
- C. Protect roof insulation materials from physical damage and from deterioration by sunlight, moisture, soiling, and other sources. Store in a dry location. Comply with insulation manufacturer's written instructions for handling, storing, and protecting during installation.
- D. Handle and store roofing materials, and place equipment in a manner to avoid permanent deflection of deck.

1.10 FIELD CONDITIONS

- A. Weather Limitations: Proceed with installation only when existing and forecasted weather conditions permit roofing system to be installed according to manufacturer's written instructions and warranty requirements.

CITY OF ORANGE BEACH
FIRE ADMINISTRATION BUILDING and POST OFFICE ROOF REPLACEMENTS
ISSUED 02-21-2022

1.11 WARRANTY

- A. General Warranty: The Manufacturer Warranty shall be for the specified and installed roofing system. The special warranty specified in this Article shall not deprive the Owner of other rights the Owner may have under other provisions of the Contract Documents and shall be in addition to, and run concurrent with, other warranties made by the Contractor under requirements of the Contract Documents.
- B. Special Warranty: The General Contractor will provide to the owner a written 5-year General Contractors Guarantee signed by the General Contractor.
- C. Manufacturer's Warranty: Issued for no less than 20 years after date of Substantial Completion. The general contractor is to complete and mail the manufacturer's NDL warranty form and provide a copy for the owner. Warranty shall provide 100% non-prorated coverage of all newly installed components of the roof assembly for materials and labor (workmanship errors).
- D. Standard Manufacturer's roofing guarantees which contain language regarding the governing of the guarantee by any state other than the State of Alabama, must be amended to exclude such language, and substituting the requirement that the Laws of the State of Alabama shall govern all such guarantees.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

- A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - 1. Carlisle
 - 2. Firestone
 - 3. GAF
 - 4. Johns Manville
- B. Source Limitations: Obtain components including roof insulation for roofing system from same manufacturer as membrane roofing or manufacturer approved by membrane roofing manufacturer.

2.2 PERFORMANCE REQUIREMENTS

- A. General Performance: Installed roofing and base flashings shall withstand specified uplift pressures, thermally induced movement, and exposure to weather without failure due to defective manufacture, fabrication, installation, or other defects in construction. Roofing and base flashings shall remain watertight.
 - 1. Accelerated Weathering: Roofing system shall withstand 2000 hours of exposure when tested according to ASTM G 151 and ASTM G 155.
 - 2. Impact Resistance: Roofing system shall resist impact damage when tested according to ASTM D 3746 or ASTM D 4272.
- B. Material Compatibility: Roofing materials shall be compatible with one another and adjacent materials under conditions of service and application required, as demonstrated by roofing manufacturer based on testing and field experience.
- C. Roofing System Design: Provide membrane roofing system that is identical to systems that have been successfully tested by a qualified testing and inspecting agency to resist uplift pressure calculated according to ASCE 7-10/SEI 7.
 - 1. Roof Uplift Pressures are as follows:
 - a. Zone 1 Wind Pressure: -56 PSF
 - b. Zone 2 Wind Pressure: -94 PSF (6' Width)
 - c. Zone 3 Wind Pressure: -142 PSF
 - 2. Edge Metal Design Pressures

CITY OF ORANGE BEACH
FIRE ADMINISTRATION BUILDING and POST OFFICE ROOF REPLACEMENTS
ISSUED 02-21-2022

- a. Horizontal Pressure: -70 PSF
- b. Vertical Pressure: -155 PSF

2.3 TPO ROOFING

- A. Fabric-Reinforced TPO Sheet: ASTM D 6878, internally fabric or scrim reinforced, uniform, flexible TPO sheet. Exposed Face Color to be White.
 - 1. Thickness ASTM D751: 60 mils, nominal
 - 2. Thickness Over Scrim:min. 0.027in
 - 3. Breaking Strength, ASTM D751: min. of 300 lbf.
 - 4. Breaking Strength after heat aging, ASTM D753, ASTM D751:90%
 - 5. Tearing Strength, ASTM D751: min. of 85 lbs.
 - 6. Tearing Strength after heat aging, ASTM D753, ASTM D751:60%
 - 7. Accelerated Weathering (without cracking or crazing), ASTM G155:min. of 24,000 hrs.

2.4 AUXILIARY ROOFING MATERIALS

- A. General: Auxiliary materials recommended by roofing system manufacturer for intended use and compatible with roofing.
- B. Sheet Flashing: Manufacturer's standard TPO sheet flashing, minimum 80 mils thick, same color as TPO sheet.
- C. Bonding Adhesive: Manufacturer's standard solvent-based bonding adhesive for membrane, and solvent-based bonding adhesive for base flashings.
- D. Metal Termination Bars: Manufacturer's standard, predrilled stainless-steel or aluminum bars, approximately 1 by 1/8-inch-thick; with anchors.
- E. Miscellaneous Accessories: Provide pourable sealers, preformed cone and vent sheet flashings, preformed inside and outside corner sheet flashings, T-joint covers, lap sealants, termination reglets, and other accessories.

2.5 COVER BOARD

- A. Products: Subject to compliance with the manufacturer's rated and tested assembly requirements, with a minimum thickness of 1/4", provide the following 4'x4' coverboard at areas designated on the drawings:
 - 1. U.S. Gypsum Corporation - Securock
 - 2. Georgia-Pacific Corporation - Dens Deck Prime.

2.6 RIGID INSULATION

- A. Products: Subject to compliance with the manufacturer's rated and tested assembly requirements, provide closed-cell Polyisocyanurate insulation with glass-reinforced facer meeting the requirements of ASTM C 1289, Type II, Class 1, Grade 2 (20 psi) at areas designated on the drawings. Tapered insulation system to be installed at special areas as noted on the drawings:
- B. Provide preformed saddles, crickets, tapered edge strips, and other insulation shapes where indicated for sloping to drain. Fabricate to slopes indicated.
- C. Provide roof insulation accessories recommended by insulation manufacturer for intended use and compatibility with roofing.
- D. Insulation Adhesive: Subject to compliance with the manufacturer's rated and tested assembly requirements, provide manufacturer's recommended adhesive formulated to attach roof insulation to substrate or to another insulation layer.

CITY OF ORANGE BEACH
FIRE ADMINISTRATION BUILDING and POST OFFICE ROOF REPLACEMENTS
ISSUED 02-21-2022

2.7 WALKWAYS

- A. Flexible Walkways: Manufacturers factory-formed, nonporous, heavy-duty, slip-resisting, surface-textured walkway pads, approximately 3/16-inch-thick and acceptable to roofing system manufacturer.

2.8 SHEET METAL FLASHING AND TRIM

- A. Refer to Section 07620 "Sheet Metal Flashing and Trim" for metal roof flashings, copings and trim.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine substrates, areas, and conditions, with Manufacturer and Installer present, for compliance with requirements and other conditions affecting performance of the Work:
 - 1. Verify that roof openings and penetrations are in place, curbs are set and braced, and roof-drain bodies are securely clamped in place.
 - 2. Verify that wood blocking, curbs, and nailers are securely anchored to roof deck at penetrations and terminations and that nailers match thicknesses of insulation.
 - 3. Verify that substrate is visibly dry and free of moisture. Test for capillary moisture by plastic sheet method according to ASTM D 4263.
- B. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 PREPARATION

- A. Clean substrate of dust, debris, moisture, and other substances detrimental to roofing installation according to roofing system manufacturer's written instructions. Remove sharp projections.
- B. Prevent materials from entering and clogging roof drains and conductors and from spilling or migrating onto surfaces of other construction. Remove roof-drain plugs when no work is taking place or when rain is forecast.

3.3 INSULATION INSTALLATION

- A. Installation shall be in accordance with roofing system manufacturer's written instructions and as dictated by the tested assembly. Fasten at corners and center of board to eliminate ridging and curling of the boards.
- B. Coordinate installing roofing system components so insulation is not exposed to precipitation or left exposed at the end of the workday.
- C. Install insulation with long joints of insulation in a continuous straight line with end joints staggered between rows. Tightly butt boards together and fill any gaps greater than 1/8". Provide mitered cuts at slope transitions.
 - 1. Cut and fit insulation within 1/4 inch of nailers, projections, and penetrations.

3.4 COVER BOARD INSTALLATION

- A. Install coverboard according to roofing system manufacturer's written instructions and as dictated by the tested assembly. Stagger side and end joints when installed over rigid insulation. Tightly butt boards together and ensure a tight fit, with gaps no greater than 1/8". Provide mitered cuts at slope transitions.

3.5 ADHERED ROOFING INSTALLATION

- A. Install roofing system according to roofing system manufacturer's written instructions.
- B. Complete terminations and base flashings and provide temporary seals to prevent water from entering completed sections of roofing system at the end of the workday or when rain is forecast. Remove and discard temporary seals before beginning work on adjoining roofing.
- C. Adhere roofing over area to receive roofing according to roofing system manufacturer's written instructions. Unroll roofing and allow to relax before installing.

CITY OF ORANGE BEACH
FIRE ADMINISTRATION BUILDING and POST OFFICE ROOF REPLACEMENTS
ISSUED 02-21-2022

- D. Start installation of roofing in presence of roofing system manufacturer's technical personnel.
- E. Accurately align roofing, and maintain uniform side and end laps of minimum dimensions required by manufacturer. Stagger end laps.
- F. Bonding Adhesive: Apply to substrate and underside of roofing at rate required by manufacturer, and allow to partially dry before installing roofing. Do not apply to splice area of roofing.
- G. In addition to adhering, mechanically fasten roofing securely at terminations, penetrations, and perimeter of roofing.
- H. Apply roofing with side laps shingled with slope of roof deck where possible.
- I. Seams: Clean seam areas, overlap roofing, and hot-air weld side and end laps of roofing and sheet flashings according to manufacturer's written instructions, to ensure a watertight seam installation.
 - 1. Test lap edges with probe to verify seam weld continuity. Apply lap sealant to seal cut edges of sheet.
 - 2. Test field strength of seams.
 - a. Take a minimum of three samples daily, in the morning, at noon and at day's end.
 - b. Cut the samples across the seam 6" on each side of the seam and 2" wide. Peel these samples by hand to failure to test seam strength. Good seams will delaminate the TPO film from the reinforcing scrim. Save all samples and identify with sample number.
 - c. Maintain a log with sample number, date, time, tester and result. Provide a plan indicating all test locations by test number. Maintain log and Plan at the site for review by Architect, Owner and manufacturer
 - 3. Repair tears, voids, and lapped seams in roofing that do not comply with requirements.
- J. Spread sealant bed over deck-drain flange at roof drains, and securely seal roofing in place with clamping ring.

3.6 BASE FLASHING INSTALLATION

- A. Install sheet flashings and preformed flashing accessories, and adhere to substrates according to roofing system manufacturer's written instructions.
- B. Apply bonding adhesive to substrate and underside of sheet flashing at required rate, and allow to partially dry. Do not apply to seam area of flashing.
- C. Flash penetrations and field-formed inside and outside corners with cured or uncured sheet flashing.
- D. Clean seam areas, overlap, and firmly roll sheet flashings into the adhesive. Hot-air weld side and end laps to ensure a watertight seam installation.
- E. Terminate and seal top of sheet flashings and mechanically anchor to substrate through termination bars.

3.7 WALKWAY INSTALLATION

- A. Flexible Walkways: Install walkway products in locations indicated. Heat weld to substrate or adhere walkway products to substrate with compatible adhesive according to roofing system manufacturer's written instructions.

3.8 FIELD QUALITY CONTROL

- A. Testing Agency: Engage a qualified testing agency to inspect substrate conditions, surface preparation, membrane application, flashings, protection, and drainage components, and to furnish reports to Architect.
- B. Final Roof Inspection: Arrange for roofing system manufacturer's technical personnel to inspect roofing installation on completion.
- C. Correct deficiencies in or remove roofing system that does not comply with requirements, repair substrates, and repair or reinstall roofing system to a condition free of damage and deterioration at time of Substantial Completion and according to warranty requirements.

CITY OF ORANGE BEACH
FIRE ADMINISTRATION BUILDING and POST OFFICE ROOF REPLACEMENTS
ISSUED 02-21-2022

D. Additional testing and inspecting, at Contractor's expense, will be performed to determine if replaced or additional work complies with specified requirements.

3.9 PROTECTING AND CLEANING

- A. Protect roofing system from damage and wear during remainder of construction period. When remaining construction does not affect or endanger roofing, inspect roofing for deterioration and damage, describing its nature and extent in a written report, with copies to Architect and Owner.
- B. Clean overspray and spillage from adjacent construction using cleaning agents and procedures recommended by manufacturer of affected construction.

END OF SECTION 075423

CITY OF ORANGE BEACH
FIRE ADMINISTRATION BUILDING and POST OFFICE ROOF REPLACEMENTS
ISSUED 02-21-2022

SECTION 076100-STANDING SEAM ROOF PANELS

PART 1 - GENERAL.

1.1 DESCRIPTION

- A. Work described in this section includes pre-formed metal roofing system complete with clips, perimeter and penetration flashing, closures, trim and required fascia panels, soffit panels and insulation.
- B. Related work specified elsewhere:
 - 1. Sheathing.
 - 2. Sheet metal flashing and trim.

1.2 SUBMITTALS

- A. Shop drawings: Show roof panel system with flashings and accessories in plan and elevation; sections and details. Include metal thickness and finishes, panel lengths, joining details, anchorage details for required wind loads indicated on drawings, flashings and special fabrication provisions for termination and penetrations. Indicate relationships with adjacent and interfacing work. Indicate Building Code compliance. Provide P.E. stamping. Shop drawings to be prepared by metal roof panel manufacturer.
- B. Design Test Reports.
 - 1. Submit copies of design test reports for each of the performance testing standards listed in specification section 1.6.
 - 2. Test reports shall be performed by independent, accredited test in laboratories, and shall bear the seal of a registered professional engineer.
- C. Warranty: Provide unexecuted specimen warranty documents for each warranty as required in specification section 1.7.
- D. Samples.
 - 1. Submit sample of panel section, at least 6" x 6" showing seam profile and also a sample of color selected.
 - 2. Submit sample of panel clip, gable clip, and preformed foam closures.

1.3 DELIVERY, STORAGE, AND HANDLING

- A. Inspect materials upon delivery.
- B. Handle materials to prevent damage.
- C. Store materials off ground providing for drainage; under cover providing for air circulation; and protected from any debris.

1.4 REFERENCE STANDARDS.

- A. American Iron and Steel Institute (AISI):
 - 1. SG02-1: 2001 Edition of the North American Specification for the Design of Cold-Formed Steel Structural Members.

CITY OF ORANGE BEACH
FIRE ADMINISTRATION BUILDING and POST OFFICE ROOF REPLACEMENTS
ISSUED 02-21-2022

- B. American Society for Testing and Materials (ASTM):
 - 1. A653-03: Specification for Steel Sheet, Zinc-coated (Galvanized) or Zinc-Iron Alloy-Coated (Galvannealed) by the Hot-Dip Process.
 - 2. A792-03: Specification for Steel Sheet, 55% Aluminum-Zinc Alloy-Coated by the Hot-Dip Process.
 - 3. B209-02a: Specification for Aluminum and Aluminum-Alloy Sheet and Plate.
 - 4. D1056-00: Specification for Flexible Cellular Materials - Sponge or Expanded Rubber.
 - 5. D3575-00e1: Standard Test Methods for Flexible Cellular Materials made from Olefin Polymers.
 - 6. E1592-01: Standard Test Method for Structural Performance of Sheet Metal Roof and Siding Systems by Uniform Static Air Pressure Difference.
 - 7. E1646-95(2003): Standard Test Method for Water Penetration of Exterior Metal Roof Panel Systems by Uniform Static Air Pressure Difference.
 - 8. E1680-95(2003): Standard Test Method for Rate of Air Leakage Through Exterior Metal Roof Panel Systems.
- C. Sheet Metal and Air Conditioning Contractors National Association (SMACNA):
 - 1. Architectural Sheet Metal Manual, 6th edition.
- D. Underwriters Laboratory (UL):
 - 1. UL 580, 4th Ed.: Standard for Tests for Uplift Resistance of Roof Assemblies.

1.5 QUALITY CRITERIA/INSTALLER QUALIFICATIONS.

- A. Engage an experienced metal roofing contractor (erector) to install standing seam system who has a minimum of five (5) years' experience specializing in the installation of structural standing-seam metal roof systems.
- B. Contractor must be certified by manufacturer specified as supplier of standing seam system and obtain written certification from manufacturer that installer is approved for installation of specified system.
- C. Successful contractor must obtain all components of roof system from a single manufacturer. Any secondary products that are required which cannot be supplied by the specified manufacturer must be recommended and approved in writing by primary manufacturer prior to bidding.
- D. Fabricator/Installer shall submit work experience and evidence of adequate financial responsibility. Architect reserves the right to inspect fabrication facilities in determining qualifications.
- E. Applicable erection tolerances: Maximum variation from true planes or lines: 1/4" in 20'-0"; 3/8" in 40'-0" or more.

CITY OF ORANGE BEACH
FIRE ADMINISTRATION BUILDING and POST OFFICE ROOF REPLACEMENTS
ISSUED 02-21-2022

1.6 DESIGN AND PERFORMANCE CRITERIA.

- A. Thermal Expansion and Contraction.
 - 1. Completed metal roofing and flashing system shall be capable of withstanding expansion and contraction of components caused by changes in temperature without buckling, or reducing performance ability.
 - 2. The design temperature differential shall be not less than +/- 220 degrees F.
 - 3. Interface between panel and clip shall provide for unlimited thermal movement in each direction along the longitudinal direction.
- B. Uniform Wind Uplift Load Capacity.
 - 1. Installed roof system shall withstand negative wind uplift pressures complying with the following criteria.
 - a. Design Code: ASCE 7, Method 2 for Components and Cladding.
 - b. Roof Area Negative Uplift Pressure: See drawings
 - 2. Capacity shall be determined using defined method in accordance with ASTM E 1592, testing of sheet metal roof panels.
- C. Uniform Positive Load Capacity.
 - 1. Uniform positive load capacity shall be determined in accordance with AISI SG02-1.
 - 2. The installed roof system shall be capable of resisting the following positive uniform roof loads: Roof Live Load of 20 psf.; Roof Snow Load N/A.
 - 3. Installed roof system shall carry positive uniform design loads with a maximum system deflection of L/180 as measured at the rib (web) of the panel.
- D. Wind Uplift Classification: The panel system shall be listed as a Class 90 windstorm rated system, as determined by UL 580.
- E. Fire Resistance Classification: The panel system shall be listed as a Class A fire rated system, as determined by UL 790.
- F. Air infiltration: The panel system shall be tested in accordance with ASTM E1680, and meet or exceed the following performance requirements:

<u>Pressure</u>	<u>Area Leakage Rate</u>
1.57 PSF	0.0028 cfm/sq.
6.24 PSF	0.0041 cfm/sq. ft.
20.0 PSF	0.0059 cfm/sq. ft.

- G. Static air pressure water infiltration: The panel system shall be tested in accordance with ASTM E1646, and meet or exceed the following performance requirements:

<u>Pressure</u>	<u>Result</u>
5 Gal/Hr. per S.F. and Static Air	No Leakage

CITY OF ORANGE BEACH
FIRE ADMINISTRATION BUILDING and POST OFFICE ROOF REPLACEMENTS
ISSUED 02-21-2022

Pressure of 20.0 psf. for 15 minutes

1.7 **WARRANTIES.**

- A. Endorse and forward to owner the following warranties:
 - 1. 20 year limited watertight warranty, jointly signed by the installer and the manufacturer.
 - 2. Manufacturer's standard 20-year finish warranty covering checking, crazing, peeling, chalking, fading, and adhesion.
 - 3. Installer's 3-year warranty covering roof panel system installation and water tightness.
- B. Warranties shall commence on date of substantial completion.

PART 2 - PRODUCTS

2.1 **STANDING SEAM ROOFING SYSTEM MANUFACTURERS.**

- A. A.Basis of Design Manufacturer: MBCI Metal Roof and Wall Systems, Division of NCI Group, Inc.; Houston TX. Tel: (877)713-6224.
- B. Alternate manufacturers are subject to full compliance with specification requirements, and shall be submitted for approval prior to bid. Approved alternate manufacturers are:
 - 1. Drexel Metal – DMC200S-2” Standing Seam Metal Roof Panels (12” Coverage)
 - 2. Fabral Power Seam 12” x 2” 24 GA Standing Seam Metal Roof System
 - 3. No substitutions will be permitted after the bid date of this project.

2.2 **STANDING SEAM ROOFING PANELS**

- A. Mechanically-seamed, Concealed Fastener, Metal Roof Panels: Basis of Design Manufacturer: MBCI Metal Roof and Wall Systems, Division of NCI Group, Inc.; Houston TX. Tel: (877)713-6224
 - 1. Basis of Design: MBCI, SuperLok
- B. Materials.
 - 1. Panel materials: Aluminum-Zinc Alloy-Coated Steel Sheet: ASTM A 792/A 792M, structural quality, Grade 50, Coating Class AZ55 (Grade 340, Coating Class AZM165) unpainted Galvalume Plus coating.
 - a. Nominal Coated Thickness: 24 gage
 - b. Panel Surface: Smooth with striations in pan.
 - 2. Flashing and flat stock material: Fabricate in profiles indicated on drawings of same material, thickness, and finish as roof panel system, unless indicated otherwise.
- C. Characteristics.
 - 1. The same panel profile from a single manufacturer shall be used for ALL standing seam roof areas.

CITY OF ORANGE BEACH
FIRE ADMINISTRATION BUILDING and POST OFFICE ROOF REPLACEMENTS
ISSUED 02-21-2022

2. Configuration: Structural metal roof panel consisting of formed metal sheet with vertical ribs at panel edges, installed by lapping and mechanically interlocking edges of adjacent panels, and attaching panels to supports using concealed clips and fasteners in a weather tight installation.
 - a. Panel Width: 12 inches.
 - b. Panel Seam Height: 2 inch
 - c. Joint Type: Mechanically seamed.
3. Panels must be furnished in continuous lengths from ridge to the eave with no overlaps unless approved by manufacturer to length of run.
4. Site Formed Panels: Bidder will not be allowed to supply panels formed at the job-site on portable roll formers; metal panels must be factory pre-manufactured and engineered for this project.

CITY OF ORANGE BEACH
FIRE ADMINISTRATION BUILDING and POST OFFICE ROOF REPLACEMENTS
ISSUED 02-21-2022

D. METAL ROOF PANEL ACCESSORIES

1. General: Provide complete metal roof panel assembly incorporating trim, copings, fasciae, gutters and downspouts, and miscellaneous flashings, in [manufacturer's standard profiles] [profiles as indicated]. Provide required fasteners, closure strips, thermal spacers, splice plates, support plates, and sealants as indicated in manufacturer's written instructions.
 - a. Flashing and Trim: Match material, thickness, and finish of metal panel face sheet.
 - b. Panel Clips: Provide panel clip of type specified, at spacing indicated on approved shop drawings.
 - c. Two-piece Floating: ASTM C 645, with ASTM A 653/A 653M, G90 (Z180) hot-dip galvanized zinc coating, configured for concealment in panel joints, and identical to clips utilized in tests demonstrating compliance with performance requirements.
 - d. Panel Fasteners: Self-tapping screws and other acceptable fasteners recommended by roof panel manufacturer. Where exposed fasteners cannot be avoided, supply long life fasteners with EPDM or neoprene gaskets, with heads matching color of metal panels by means of factory-applied coating.
 - e. Joint Sealers: Manufacturer's standard or recommended liquid and preformed sealers and tapes, and as follows:
 - f. Factory-Applied Seam Sealant: Manufacturer's standard hot-melt type.
 - g. Tape Sealers: Manufacturer's standard non-curing butyl tape, AAMA 809.2.
 - h. Pipe Flashing: Basis of design: Dektite, DF104G - Gray EPDM Round Flexible Pipe Flashing with Aluminum Collar. Install per manufacturer recommendations

E. Panel Clips.

1. Fasten as specified by manufacturer to meet wind loads.

2.3 FABRICATION.

- A. General: Provide factory fabricated and finished metal panels and accessories meeting performance requirements, indicated profiles, and structural requirements.

CITY OF ORANGE BEACH
FIRE ADMINISTRATION BUILDING and POST OFFICE ROOF REPLACEMENTS
ISSUED 02-21-2022

- B. Fabricate metal panel joints configured to accept factory-applied sealant providing weathertight seal and preventing metal-to-metal contact and minimizing noise resulting from thermal movement.
- C. Form panels in continuous lengths for full length of detailed runs, except where otherwise indicated on approved shop drawings.
- D. Sheet Metal Flashing and Trim: Fabricate flashing and trim to comply with manufacturer's written instructions, approved shop drawings, and project drawings. Form from materials matching metal panel substrate and finish.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine metal panel system substrate and supports with Installer present. Inspect for erection tolerances and other conditions that would adversely affect installation of metal panel installation.
 - 1. Inspect metal panel support substrate to determine if support components are installed as indicated on approved shop drawings. Confirm presence of acceptable supports at recommended spacing to match installation requirements of metal panels.
 - 2. Panel Support Tolerances: Confirm that panel supports are within tolerances acceptable to metal panel system manufacturer but not greater than the following:
 - a. 1/4 inch (6 mm) in 20 foot (6.1 m) in any direction.
 - b. 3/8 inch (9 mm) over any single roof plane.
- B. Correct out-of-tolerance work and other deficient conditions prior to proceeding with insulated metal roof panel system installation.

3.2 PREPARATION

- A. Miscellaneous Supports: Install sub-framing, girts, furring, and other miscellaneous panel support members according to ASTM C 754 and manufacturer's written instructions.
- B. Flashings: Install flashings to cover exposed underlayment per Section 07 62 00 "Sheet Metal Flashing and Trim."

3.3 METAL PANEL INSTALLATION

- A. Mechanically-Seamed, Standing Seam Metal Roof Panels: Install weather tight metal panel system in accordance with manufacturer's written instructions, approved shop drawings, and project drawings. Install metal roof panels in orientation, sizes, and locations indicated, free of waves, warps, buckles, fastening stresses, and distortions. Anchor panels and other components securely in place. Provide for thermal and structural movement.
- B. Attach panels to supports using clips, screws, fasteners, and sealants recommended by manufacturer and indicated on approved shop drawings.
 - 1. Fasten metal panels to supports with concealed clips at each location indicated on approved shop drawings, with spacing and fasteners recommended by manufacturer.
 - 2. Seamed Joint: Crimp standing seams with manufacturer-approved, motorized seamer tool so clip, metal roof panel, and factory-applied sealant are completely engaged.

CITY OF ORANGE BEACH
FIRE ADMINISTRATION BUILDING and POST OFFICE ROOF REPLACEMENTS
ISSUED 02-21-2022

3. Provide weatherproof jacks for pipe and conduit penetrating metal panels of types recommended by manufacturer.
4. Dissimilar Materials: Where elements of metal panel system will come into contact with dissimilar materials, treat faces and edges in contact with dissimilar materials as recommended by manufacturer.

3.4 ACCESSORY INSTALLATION

- A. General: Install metal panel trim, flashing, and accessories using recommended fasteners and joint sealers, with positive anchorage to building, and with weather tight mounting. Provide for thermal expansion. Coordinate installation with flashings and other components.
 1. Install components required for a complete metal panel assembly, including trim, copings, flashings, sealants, closure strips, and similar items.
 2. Comply with details of assemblies utilized to establish compliance with performance requirements and manufacturer's written installation instructions.
 3. Provide concealed fasteners except where noted on approved shop drawings.
 4. Set units true to line and level as indicated. Install work with laps, joints, and seams that will be permanently weather resistant.
- B. Joint Sealers: Install joint sealers where indicated and where required for weather tight performance of metal panel assemblies, in accordance with manufacturer's written instructions.
 1. Prepare joints and apply sealants per requirements of Division 07 Section "Joint Sealants."

3.5 FIELD QUALITY CONTROL

- A. Testing Agency: Owner will engage an independent testing and inspecting agency acceptable to Architect to perform field tests and inspections and to prepare test reports.

3.6 CLEANING AND PROTECTION

- A. Remove temporary protective films immediately in accordance with metal roof panel manufacturer's instructions. Clean finished surfaces as recommended by metal roof panel manufacturer.
- B. Replace damaged panels and accessories that cannot be repaired to the satisfaction of the Architect.

END OF SECTION 076100

CITY OF ORANGE BEACH
FIRE ADMINISTRATION BUILDING and POST OFFICE ROOF REPLACEMENTS
ISSUED 02-21-2022

SECTION 076200 – SHEET METAL FLASHING AND TRIM

PART 1 – GENERAL

1.1 SUMMARY

- A. Section Includes:
 - 1. Sheet metal flashing and trim, includes fascia.
 - 2. Fasteners and attachment devices.
 - 3. Coatings and slip sheets to isolate sheet metal from dissimilar materials.
 - 4. Rain diverters.

- B. Wood blocking, nailers, edge strips, and battens are not specified in this section.
 - 1. Related Sections:
 - 2. Reglet to Masonry: Elsewhere in Division 4.
 - 3. Wood blocking and nailers: Division 6.
 - 4. Roof Panels: Elsewhere in Division 7.
 - 5. Rain Diverters: Elsewhere in Division 7.
 - 6. Weather-stripping of doors and windows: Division 8.

1.2 REFERENCES

- A. AA DAF-45 -- Designation System for Aluminum Finishes; latest edition.
- B. AAMA 605.2 -- Specification for High Performance Organic Coating.
- C. Architectural Sheet Metal Manual; Sheet Metal and Air Conditioning Contractors National Association, Inc. (SMACNA); latest edition.
- D. ASTM A 526/ A 526M -- Standard Specification for Steel Sheet, Zinc-Coated (Galvanized) by the Hot-Dip Process, Commercial Quality; latest edition.
- E. ASTM B 32 -- Standard Specification for Solder Metal; latest edition.
- F. ASTM B 209 -- Standard Specification for Aluminum and Aluminum-Alloy Sheet and Plate; latest edition.
- G. FS TT -C-494A -- Coating Compound, Bituminous, Solvent Type, Acid Resistant; latest edition.
- H. FS IT -P-645A -- Primer, Paint, Zinc Chromate, Alkyd Type; latest edition.

1.3 PERFORMANCE

- A. General: Install sheet metal flashing and trim to withstand wind loads, structural movement, thermally induced movement and exposure to weather conditions.

CITY OF ORANGE BEACH
FIRE ADMINISTRATION BUILDING and POST OFFICE ROOF REPLACEMENTS
ISSUED 02-21-2022

1.4 SUBMITTALS

- A. Product Data: Submit manufacturer's technical product data, installation instructions and recommendations for use of each type of product required. Provide additional data as required to demonstrate compliance with project requirements.
- B. Submit 20-year paint warranty for Kynar finishes warranting against excess finish fade, chalking and peeling.
- C. Submit color selections available for Kynar 500 finishes. A minimum of 16 colors must be available for selection.

1.5 QUALITY ASSURANCE

- A. Installer: A firm having 3 years' successful experience, minimum, with installation of metal work of type and scope equivalent to work of this section.
- B. Quality Standard:
 - 1. Fabricate and install sheet metal work in accordance with Sheet Metal and Air Conditioning Contractors National Association (SMACNA) "Architectural Sheet Metal Manual," 1993, 5th edition, except where shown or specified otherwise.

PART 2 – PRODUCTS

2.1 MATERIALS

- A. Galvanized Steel Sheet: ASTM A 526, commercial quality, G90 hot-dip galvanized.
 - 1. Finish: Kynar 500, 2-coat finish.
 - 2. Minimum thickness: 24 gage (0.0239 inch), unless indicated otherwise.
- B. Aluminum: Alloy and temper recommended by aluminum producer and finisher for type of use and finish indicated and with not less than the strength and durability of alloy and temper designated below:
 - 1. Factory Painted Aluminum Sheet: ASTM B 209 (ASTM B 209M), 3003-H14, with a minimum thickness of 0.040 inch (1.0 mm) unless otherwise indicated.
- C. Sheet Lead: Hard tempered, containing 4 to 6 percent antimony, 3.0 pounds per square foot minimum weight for exposed sheet. Soft lead sheet, 4.0 pounds per square foot minimum weight for concealed uses.

CITY OF ORANGE BEACH
FIRE ADMINISTRATION BUILDING and POST OFFICE ROOF REPLACEMENTS
ISSUED 02-21-2022

2.2 ACCESSORIES

- A. Fasteners: Corrosion resistant metal of same material or as recommended by manufacturer of metal being fastened. Exposed fastener heads, where permitted, to match color and finish of sheet material.
- B. Solder: ASTM B 32, 50/50 tin-lead, rosin flux unless recommended otherwise by sheet metal manufacturer.
- C. Sealant: As specified in Division 7.
 - 1. Use non-curing type for concealed joints.
 - 2. Use non-sag elastomeric type for exposed joints.
- D. Joint Adhesive: Two-component non-corrosive epoxy adhesive, recommended by metal manufacturer for sealing of non-moving joints.
- E. Zinc-Chromate Alkyd Paint: FS TT-P-645.
- F. Bituminous Coating: Heavy bodied, sulfur-free, asphalt-based paint; FS TT -C-494.
- G. Fasteners: Same metal as sheet metal flashing or other noncorrosive metal as recommended by sheet metal manufacturer. Match finish of exposed heads with material being fastened.
- H. Asphalt Mastic: SSPCL Paint 12, solvent-type asphalt mastic, nominally free of sulfur and containing no asbestos fibers, compounded for 15-mil (0.4 mm) dry film thickness per coat.
- I. Mastic Sealant: Polyisobutylene; non-hardening, non-skinning, nondrying, non-migrating sealant.
- J. Elastomeric Sealant: Generic type recommended by sheet metal manufacturer and fabricator of components being sealed and complying with requirements for joint sealants as specified in Division 7 Section "Joint Sealants".
- K. Epoxy Seam Sealer: 2-part, noncorrosive, aluminum seam-cementing compound, recommended by aluminum manufacturer for exterior and interior nonmoving joints; including riveted joints.
- L. Adhesives: Type recommended by flashing sheet metal manufacturer for waterproof and weather resistant seaming and adhesive application of flashing sheet metal.
- M. Paper Slip Sheet: 5 lb./square (0.2444 kg/sq.m.) red rosin, sized building paper conforming to FS oo-B-790, Type I, Style Ib.

CITY OF ORANGE BEACH
FIRE ADMINISTRATION BUILDING and POST OFFICE ROOF REPLACEMENTS
ISSUED 02-21-2022

- N. Polyethylene Underlayment: ASTM D 4397, minimum 6-mil (0.15 mm) thick black polyethylene film, resistant to decay when tested according to ASTM E 154.
- O. Metal Accessories: Provide sheet metal clips, straps, anchoring devices, and similar accessory units as required for installation of work to comply with recommendations of SMACNA "Architectural Sheet Metal Manual" that apply to design dimensions, metal and other characteristics of item indicated.
- P. Roofing Cement: ASTM D 4586, Type I, asbestos free, asphalt based.

2.3 FABRICATION – GENERAL

- A. Form A ½ - inch hem on underside of exposed edges.
- B. Fabricate cleats and attachment devices from same material as sheet metal component being anchored or from compatible, non-corrosive metal recommended by sheet metal manufacturer.
 - 1. Gauge: As recommended by SMACNA or metal manufacturer for application, but in no case less than gage of metal being secured.
- C. Sheet Metal Fabrication Standard: Fabricate sheet metal flashing and trim to comply with recommendations of SMACNA's "Architectural Sheet Metal Manual" that apply to the design, dimensions, metal and other characteristics of the item indicated.
- D. Comply with details shown to fabricate sheet metal flashing and trim that fit substrates and result in waterproof and weather-resistant performance once installed. Verify shapes and dimensions of surfaces to be covered before fabricating sheet metal.
- E. Form exposed sheet metal Work that is without excessive oil canning, buckling and tool marks and that is true to line and levels indicated, with exposed edges folded back to form hems.
- F. Seams: Fabricate nonmoving seams in aluminum with flat-lock seams. Form seams and seal with epoxy seam sealer. Rivet joints for additional strength.
- G. Expansion Provisions: Space movement joints at maximum of 10 feet (3 m) with no joints allowed within 24 inches (610 mm) of corner or intersection. Where lapped or bayonet -type expansion provisions in Work cannot be used or would not be sufficiently weatherproof and waterproof, form expansion joints of intermeshing hooked flanges, not less than 1 inch (25 mm) deep, filled with mastic sealant (concealed within joints).
- H. Sealed Joints: Form non-expansion, but movable joints in metal to accommodate elastomeric sealant to comply with SMACNA standards.

CITY OF ORANGE BEACH
FIRE ADMINISTRATION BUILDING and POST OFFICE ROOF REPLACEMENTS
ISSUED 02-21-2022

- I. Separate metal from non-compatible metal or corrosive substrates by coating concealed surfaces at locations of contact with asphalt mastic or other permanent separation as recommended by manufacturer.
- J. Conceal fasteners and expansion provisions where possible. Exposed fasteners are not allowed on faces of sheet metal exposed to public view.
- K. Fabricate counter flashing wind restraint clips and attachment devices from same material as sheet metal component being anchored or from compatible, noncorrosive metal recommended by sheet metal manufacturer.
 - 1. Type: Continuous.
 - 2. Thickness: 0.062 inch.
 - 3. Anchorage: 8", maximum.

2.4 SHEET METAL FABRICATIONS

- A. General: Fabricate sheet metal items in thickness or weight needed to comply with performance requirements but not less than that listed below for each application and metal.
- B. Exposed Trim and Fascia: Fabrication from the following material:
 - 1. Aluminum 0.040 inch thick.
- C. Step flashing: Fabricate from the following material:
 - 1. Aluminum 0.040 inch thick.
- D. Counter flashing: Fabricate from the following material:
 - 1. Aluminum 0.040 inch thick.
- E. Roof Penetration Flashing: Fabricate from the following material:
 - 1. Stainless Steel: 0.0187 inch (0.5 mm) thick.
- F. Vent Stack Flashing: Fabricate from 2-1/2 lb. soft sheet lead.

PART 3 – EXECUTION

3.1 EXAMINATION

- A. Examine substrates and conditions under which products of this section are to be installed and verify that work may properly commence. Do not proceed with the work until unsatisfactory conditions have been fully resolved.

CITY OF ORANGE BEACH
FIRE ADMINISTRATION BUILDING and POST OFFICE ROOF REPLACEMENTS
ISSUED 02-21-2022

1. Verify that nailers, blocking and other attachment provisions for sheet metal work are properly located and securely fastened to resist effects of wind and thermal stresses.

3.2 PREPARATION

- A. Verify shapes and dimensions of surfaces to be covered before fabricating sheet metal.
- B. Isolate dissimilar metals by means of a heavy bituminous coating, approved paint coating, adhered polyethylene sheet or other means approved by Architect.

3.3 INSTALLATION

- A. General: Except as otherwise indicated, comply with manufacturer's installation instructions and recommendations, and with SMACNA "Architectural Sheet Metal Manual." Anchor units of work securely in place by methods indicated, providing for thermal expansion in metal units. Set units true to line and level indicated. Install work with laps, joints and seams permanently weatherproof and watertight. Install soffits for wind design speeds to meet the building code.
- B. Sealed Joints: Form minimum 1-inch hooked joints and embed flange into sealant or adhesive. Form metal to completely conceal sealant or adhesive.
 1. Use joint adhesive for non-moving joints specified not to be soldered.
 2. Moving joints: When ambient temperature is moderate (40-70 degrees F) at time of installation, set joined members for 50 percent movement either way. Adjust setting position of joined members proportionally for temperatures above 70 degrees F. Do not install sealant at temperatures below 40 degrees F. Refer to section on sealants elsewhere in Division 7 for handling and installation requirements for joint sealers.
- C. Soldered Joints:
 1. Do not solder aluminum sheets.
 2. Clean surfaces to be soldered, removing oils and foreign matter.
 3. Pre-tin edges of sheets to be soldered to a width of 1 ½ inches, except where pre-tinned surface would show in the finished work.
 4. Do not use torches for soldering.
 5. Heat surfaces to receive solder and flow solder into joint. Fill joint completely.
 6. Rivet joints where additional strength is required.
 7. Completely remove flux and spatter from exposed surfaces.

3.4 CLEANING AND PROTECTION

- A. Repair or replace work that is damaged or defaced as directed by Architect.

CITY OF ORANGE BEACH
FIRE ADMINISTRATION BUILDING and POST OFFICE ROOF REPLACEMENTS
ISSUED 02-21-2022

- B. Clean exposed metal surfaces, removing substances that would interfere with uniform oxidation and weathering.
- C. Remove masking on prefinished trim pieces immediately after installation.
- D. Provide final protection in a manner acceptable to installer and which ensures that sheet metal work will be without damage or deterioration at time of substantial completion.

END OF SECTION 07620

CITY OF ORANGE BEACH
FIRE ADMINISTRATION BUILDING and POST OFFICE ROOF REPLACEMENTS
ISSUED 02-21-2022

SECTION 079200 - JOINT SEALANTS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section Includes:
 - 1. Silicone joint sealants.
 - 2. Latex joint sealants.
- B. Related Sections:
 - 1. Division 04 Section "Unit Masonry" for masonry control and expansion joint fillers and gaskets.
 - 2. Division 08 Section "Glazing" for glazing sealants.
 - 3. Division 09 Section "Gypsum Board" for sealing perimeter joints.
 - 4. Division 09 Section "Tiling" for sealing tile joints.
 - 5. Refer to Drawings for "Concrete Paving Joint Sealants" for sealing joints in pavements, walkways, and curbing.

1.3 SUBMITTALS

- A. Product Data: For each joint-sealant product indicated.
- B. Samples for Initial Selection: Manufacturer's color charts consisting of strips of cured sealants showing the full range of colors available for each product exposed to view.
- C. Joint-Sealant Schedule: Include the following information:
 - 1. Joint-sealant application, joint location, and designation.
 - 2. Joint-sealant manufacturer and product name.
 - 3. Joint-sealant formulation.
 - 4. Joint-sealant color.
- D. Qualification Data: For qualified Installer.
- E. Product Certificates: For each kind of joint sealant and accessory, from manufacturer.
- F. Product Test Reports: Based on evaluation of comprehensive tests performed by a qualified testing agency, indicating that sealants comply with requirements.
- G. Warranties: Sample of special warranties.

1.4 QUALITY ASSURANCE

- A. Installer Qualifications: Manufacturer's authorized representative who is trained and approved for installation of units required for this Project.
- B. Source Limitations: Obtain each kind of joint sealant from single source from single manufacturer.

1.5 PROJECT CONDITIONS

- A. Do not proceed with installation of joint sealants under the following conditions:
 - 1. When ambient and substrate temperature conditions are outside limits permitted by joint-sealant manufacturer or are below 40 deg F.
 - 2. When joint substrates are wet.

CITY OF ORANGE BEACH
FIRE ADMINISTRATION BUILDING and POST OFFICE ROOF REPLACEMENTS
ISSUED 02-21-2022

3. Where joint widths are less than those allowed by joint-sealant manufacturer for applications indicated.
4. Where contaminants capable of interfering with adhesion have not yet been removed from joint substrates.

1.6 WARRANTY

- A. Special warranties specified in this article exclude deterioration or failure of joint sealants from the following:
1. Movement of the structure caused by structural settlement or errors attributable to design or construction resulting in stresses on the sealant exceeding sealant manufacturer's written specifications for sealant elongation and compression.
 2. Disintegration of joint substrates from natural causes exceeding design specifications.
 3. Mechanical damage caused by individuals, tools, or other outside agents.
 4. Changes in sealant appearance caused by accumulation of dirt or other atmospheric contaminants.

PART 2 - PRODUCTS

2.1 MATERIALS, GENERAL

- A. Compatibility: Provide joint sealants, backings, and other related materials that are compatible with one another and with joint substrates under conditions of service and application, as demonstrated by joint-sealant manufacturer, based on testing and field experience.
- B. Liquid-Applied Joint Sealants: Comply with ASTM C 920 and other requirements indicated for each liquid-applied joint sealant specified, including those referencing ASTM C 920 classifications for type, grade, class, and uses related to exposure and joint substrates.
1. Suitability for Immersion in Liquids. Where sealants are indicated for Use I for joints that will be continuously immersed in liquids, provide products that have undergone testing according to ASTM C 1247. Liquid used for testing sealants is de-ionized water, unless otherwise indicated.
- C. Stain-Test-Response Characteristics: Where sealants are specified to be non-staining to porous substrates, provide products that have undergone testing according to ASTM C 1248 and have not stained porous joint substrates indicated for Project.
- D. Suitability for Contact with Food: Where sealants are indicated for joints that will come in repeated contact with food, provide products that comply with 21 CFR 177.2600.
- E. Colors of Exposed Joint Sealants: As selected by Architect from manufacturer's full range.

2.2 SILICONE JOINT SEALANTS

- A. Single-Component, Nonsag, Neutral-Curing Silicone Joint Sealant: ASTM C 920, Type S, Grade NS, Class 100/50, for Use NT.
1. Products: Subject to compliance with requirements, available products that may be incorporated into the Work include, but are not limited to, the following:
 - a. Dow Corning Corporation; 790.
 - b. GE Advanced Materials - Silicones; SilPruf LM SCS2700.
 - c. Tremco Incorporated; Spectrem 1.
- B. Mildew-Resistant, Single-Component, Nonsag, Neutral-Curing Silicone Joint Sealant: ASTM C 920, Type S, Grade NS, Class 25, for Use NT.
1. Products: Subject to compliance with requirements, available products that may be incorporated into the Work include, but are not limited to, the following:
 - a. Pecora Corporation; 898.

2.3 LATEX JOINT SEALANTS

CITY OF ORANGE BEACH
FIRE ADMINISTRATION BUILDING and POST OFFICE ROOF REPLACEMENTS
ISSUED 02-21-2022

- A. Latex Joint Sealant: Acrylic latex or siliconized acrylic latex, ASTM C 834, Type OP, Grade NF.
 - 1. Products: Subject to compliance with requirements, available products that may be incorporated into the Work include, but are not limited to, the following:
 - a. BASF Building Systems; Sonolac.
 - b. Bostik, Inc.; Chem-Calk 600.
 - c. Pecora Corporation; AC-20+.
 - d. Tremco Incorporated; Tremflex 834.

2.4 JOINT SEALANT BACKING

- A. General: Provide sealant backings of material that are non-staining; are compatible with joint substrates, sealants, primers, and other joint fillers; and are approved for applications indicated by sealant manufacturer based on field experience and laboratory testing.
- B. Cylindrical Sealant Backings: ASTM C 1330, Type C (closed-cell material with a surface skin), and of size and density to control sealant depth and otherwise contribute to producing optimum sealant performance.
- C. Bond-Breaker Tape: Polyethylene tape or other plastic tape recommended by sealant manufacturer for preventing sealant from adhering to rigid, inflexible joint-filler materials or joint surfaces at back of joint. Provide self-adhesive tape where applicable.

2.5 MISCELLANEOUS MATERIALS

- A. Primer: Material recommended by joint-sealant manufacturer where required for adhesion of sealant to joint substrates indicated, as determined from preconstruction joint-sealant-substrate tests and field tests.
- B. Cleaners for Nonporous Surfaces: Chemical cleaners acceptable to manufacturers of sealants and sealant backing materials, free of oily residues or other substances capable of staining or harming joint substrates and adjacent nonporous surfaces in any way, and formulated to promote optimum adhesion of sealants to joint substrates.
- C. Masking Tape: Non-staining, nonabsorbent material compatible with joint sealants and surfaces adjacent to joints.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine joints indicated to receive joint sealants, with Installer present, for compliance with requirements for joint configuration, installation tolerances, and other conditions affecting joint-sealant performance.
- B. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 PREPARATION

- A. Surface Cleaning of Joints: Clean out joints immediately before installing joint sealants to comply with joint-sealant manufacturer's written instructions and the following requirements:
 - 1. Remove all foreign material from joint substrates that could interfere with adhesion of joint sealant, including dust, paints (except for permanent, protective coatings tested and approved for sealant adhesion and compatibility by sealant manufacturer), old joint sealants, oil, grease, waterproofing, water repellents, water, surface dirt, and frost.
 - 2. Clean porous joint substrate surfaces by brushing, grinding, mechanical abrading, or a combination of these methods to produce a clean, sound substrate capable of developing optimum bond with joint sealants. Remove loose particles remaining after cleaning operations above by vacuuming or blowing out joints with oil-free compressed air. Porous joint substrates include the following:
 - a. Masonry.

CITY OF ORANGE BEACH
FIRE ADMINISTRATION BUILDING and POST OFFICE ROOF REPLACEMENTS
ISSUED 02-21-2022

- b. Unglazed surfaces of ceramic tile.
 - c. Portland cement plasterwork (stucco).
 3. Remove laitance and form-release agents from concrete.
 4. Clean nonporous joint substrate surfaces with chemical cleaners or other means that do not stain, harm substrates, or leave residues capable of interfering with adhesion of joint sealants. Nonporous joint substrates include the following:
 - a. Metal.
 - b. Glass.
 - c. Porcelain enamel.
 - d. Glazed surfaces of ceramic tile.
- B. Joint Priming: Prime joint substrates where recommended by joint-sealant manufacturer or as indicated by preconstruction joint-sealant-substrate tests or prior experience. Apply primer to comply with joint-sealant manufacturer's written instructions. Confine primers to areas of joint-sealant bond; do not allow spillage or migration onto adjoining surfaces.
- C. Masking Tape: Use masking tape where required to prevent contact of sealant or primer with adjoining surfaces that otherwise would be permanently stained or damaged by such contact or by cleaning methods required to remove sealant smears. Remove tape immediately after tooling without disturbing joint seal.

3.3 INSTALLATION OF JOINT SEALANTS

- A. General: Comply with joint-sealant manufacturer's written installation instructions for products and applications indicated, unless more stringent requirements apply.
- B. Sealant Installation Standard: Comply with recommendations in ASTM C 1193 for use of joint sealants as applicable to materials, applications, and conditions indicated.
- C. Install sealant backings of kind indicated to support sealants during application and at position required to produce cross-sectional shapes and depths of installed sealants relative to joint widths that allow optimum sealant movement capability.
 1. Do not leave gaps between ends of sealant backings.
 2. Do not stretch, twist, puncture, or tear sealant backings.
 3. Remove absorbent sealant backings that have become wet before sealant application and replace them with dry materials.
- D. Install bond-breaker tape behind sealants where sealant backings are not used between sealants and backs of joints.
- E. Install sealants using proven techniques that comply with the following and at the same time backings are installed:
 1. Place sealants so they directly contact and fully wet joint substrates.
 2. Completely fill recesses in each joint configuration.
 3. Produce uniform, cross-sectional shapes and depths relative to joint widths that allow optimum sealant movement capability.
- F. Tooling of Nonsag Sealants: Immediately after sealant application and before skinning or curing begins, tool sealants according to requirements specified in subparagraphs below to form smooth, uniform beads of configuration indicated; to eliminate air pockets; and to ensure contact and adhesion of sealant with sides of joint.
 1. Remove excess sealant from surfaces adjacent to joints.
 2. Use tooling agents that are approved in writing by sealant manufacturer and that do not discolor sealants or adjacent surfaces.
 3. Provide concave joint profile per Figure 8A in ASTM C 1193, unless otherwise indicated.
 4. Provide flush joint profile where indicated per Figure 8B in ASTM C 1193.
 5. Provide recessed joint configuration of recess depth and at locations indicated per Figure 8C in ASTM C 1193.
 - a. Use masking tape to protect surfaces adjacent to recessed tooled joints.

CITY OF ORANGE BEACH
FIRE ADMINISTRATION BUILDING and POST OFFICE ROOF REPLACEMENTS
ISSUED 02-21-2022

3.4 FIELD QUALITY CONTROL

- A. Evaluation of Field-Adhesion Test Results: Sealants not evidencing adhesive failure from testing or noncompliance with other indicated requirements will be considered satisfactory. Remove sealants that fail to adhere to joint substrates during testing or to comply with other requirements. Retest failed applications until test results prove sealants comply with indicated requirements.

3.5 CLEANING

- A. Clean off excess sealant or sealant smears adjacent to joints as the Work progresses by methods and with cleaning materials approved in writing by manufacturers of joint sealants and of products in which joints occur.

3.6 PROTECTION

- A. Protect joint sealants during and after curing period from contact with contaminating substances and from damage resulting from construction operations or other causes so sealants are without deterioration or damage at time of Substantial Completion. If, despite such protection, damage or deterioration occurs, cut out and remove damaged or deteriorated joint sealants immediately so installations with repaired areas are indistinguishable from original work.

3.7 JOINT-SEALANT SCHEDULE

- A. Joint-Sealant Application: Exterior joints in vertical surfaces and horizontal non-traffic surfaces.
1. Joint Locations:
 - a. Control and expansion joints in unit masonry.
 - b. Joints in Portland cement plasterwork (stucco) finish systems.
 - c. Joints between different materials listed above.
 - d. Perimeter joints between materials listed above and frames of doors, windows and louvers.
 2. Silicone Joint Sealant: Single component, non-sag, neutral curing, Class 100/50.
 3. Joint-Sealant Color: As selected by Architect from manufacturer's full range of colors.
- B. Joint-Sealant Application: Interior joints in vertical surfaces and horizontal non-traffic surfaces.
1. Joint Locations:
 - a. Perimeter joints of exterior openings where indicated.
 - b. Vertical joints on exposed surfaces of interior unit masonry.
 - c. Perimeter joints between interior wall surfaces and frames of interior doors and windows.
 2. Joint Sealant: Latex.
 3. Joint-Sealant Color: As selected by Architect from manufacturer's full range of colors.
- C. Joint-Sealant Application: Mildew-resistant interior joints in vertical surfaces and horizontal non-traffic surfaces.
1. Joint Sealant Location:
 - a. Joints between plumbing fixtures and adjoining walls, floors, and counters.
 - b. Tile control and expansion joints where indicated.
 - c. Other joints as indicated.
 2. Joint Sealant: Mildew resistant, single component, non-sag, neutral curing, Silicone.
 3. Joint-Sealant Color: As selected by Architect from manufacturer's full range of colors.

END OF SECTION 079200