



CITY OF CRESTVIEW
Department of Public Services
715 Ferdon Boulevard North
Crestview, Florida 32536

Telephone No. (850) 682-6132
Fax No. (850) 682-7359
E-Mail: publicservices@cvflorg.gccoxmail.com

Director
Brona D. Steele
E-Mail: steele@cityofcrestview.org

Addendum Number 1

Project: Lift Station #9 Renovation
Project #: 19-0912
Addendum Date: 09-09-19

This project has the following addendums:

- 1) The time to substantial completion has been extended to 105 days and the time to final completion has been extended to 120 days.
- 2) The specified 100kw generator has been upsized to a 150kw generator.
- 3) The flow that will need to be bypassed is approximately 1000 GPM.
- 4) The existing discharge forcemain is 10" ductile iron. The existing bypass pump has a 6" quick connect. The aboveground piping is stainless steel schedule 40-316.
- 5) Most valves, pumps and piping are located within the pumphouse, however there are some valves location within the existing wetwell.
- 6) Site visits are encouraged. (see bid advertisement)

-end of addendum-