

Scope of Work

Topa Topa Elementary School
Playground Improvement Project # 2020-1508

Playground:

1. Pulverize & remove all asphalt in Area A.
2. Cut and remove intruding surface roots to a depth of 12 inches as needed.
3. Fine grade and recompact the existing subgrade to a minimum depth of 6 inches.
4. Regrade south edge of field installing a reverse slope from playground area to create natural drainage from the field to the west. (Area B)
5. Install redwood header board in areas without proper curbing.
6. Apply tack oil to the vertical surfaces of the existing pavement.
7. Install 3 inches (after compaction) of hot mix asphalt pavement.
8. Re-stripe the asphalt surface per the existing layout using 1 coat of traffic paint.
9. Install district provided basketball poles in existing locations to regulation height.