

Description	Lukken Industrial Drive	Unit Price	Total
Begin	US 27		
End	Troup St		
Distance	1.8 (9500 LF)		
Traffic Control	1 ea		
Tack	2300 Gal		
Asphalt Width	37 ft		
Asphalt Thickness	2 IN		
Leveling	90 Tons		
Edge Mill 2 inches	19000 LF		
A base 25 mm (6 inch deep patching)	850 Tons		
Asphalt 12.5 mm Superpave GP2	4393 Tons		
Stripe (stripe traffic, 5 inch, Yellow, single Centerline, 2 coats High Build Paint)	1.8 ea		
Stripe (solid traffic, 5 inch, White, Side Line, 2 coats High Build Paint)	1.8 ea		
12" Crosswalks, white, 2 coats High Build Paint)	4 ea		
Directional arrows, 2 coats High Build Paint)	30 ea		
12" Stop lines, white, 2 coats High Build Paint)	6 ea		