

## Scope of Work

Matilija Middle School

Playground Restoration Project # 2020-1613

### **Playground:**

1. Pulverize/remove all asphalt and concrete in Area A.
2. Cut and remove intruding surface roots to a depth of 12 inches as needed.
3. Regrade new area to the north to allow proper drainage to the south. (Area B).
4. Regrade new area to the south to allow proper drainage from the new asphalt to the existing ribbon gutter. (Area C).
5. Fine grade, recompact existing, and install new subgrade where necessary to a minimum depth of 6 inches.
6. Install redwood header board in areas without proper curbing.
7. Lift any utility vaults to match new asphalt and install new vault covers.
8. Apply tack oil to the vertical surfaces of the existing pavement.
9. Install 3 inches (after compaction) of hot mix asphalt pavement.
10. Re-stripe the asphalt surface per new district provided layout using 2 coats of traffic paint.
11. Re-install (4) district basketball poles per new district provided payout to regulation height.