TRACK AND FIELD ATHLETIC FACILITY IMPROVEMENTS PROGRAM February 22, 2021





SITE VICINITY MAP - AYNOR HIGH SCHOOL SCALE: NOT TO SCALE

ISSUED FOR CONSTRUCTION Sheet Index

SITE PLANS

Sheet Number	Sheet Title
G-000	TITLE SHEET
C-010	AYNOR HS EXISTING CONDITIONS PLAN
C-011	AYNOR HS DEMOLITION PLAN
C-110	AYNOR HS LAYOUT PLAN
C-111	AYNOR HS SURFACING AND DIMENSION PLAN
C-210	AYNOR HS GRADING PLAN
C-310	AYNOR HS DRAINAGE AND UTILITY PLAN
C-510	SEDIMENT AND EROSION CONTROL PLAN PHASE I
C-511	SEDIMENT AND EROSION CONTROL PLAN PHASE II
C-512	SEDIMENT AND EROSION CONTROL DETAILS
E-001	AYNOR HS ELECTRICAL SITE PLAN

V:\PROJECTS\ANY\K5\36108\CADD_ACAD\G-000_PH2.DWG :d: 2/23/2021 1:09:33 PM Plotted: 2/26/2021 2:22:53 PM Current User: Lindsay, Cady LastSavedBy: 617C


HORRY COUNTY SCHOOLS OFFICE OF FACILITIES 1160 E. HIGHWAY 501 CONWAY. SC 29526


SITE VICINITY MAP - GREEN SEA FLOYDS HIGH SCHOOL

C-020	GREEN SEA FLOYDS HS EXISTING CONDITIONS PLAN	C-230	NORTH MYRTLE HS GRADING PLAN
C-021	GREEN SEA FLOYDS HS DEMOLITION PLAN	C-330	NORTH MYRTLE HS DRAINAGE AND UTILITY PLAN
C-120	GREEN SEA FLOYDS HS LAYOUT PLAN	C-530	SEDIMENT AND EROSION CONTROL PLAN PHASE I
C-121	GREEN SEA FLOYDS HS SURFACING AND DIMENSION PLAN	C-531	SEDIMENT AND EROSION CONTROL PLAN PHASE I
C-220	GREEN SEA FLOYDS HS GRADING PLAN	C-532	SEDIMENT AND EROSION CONTROL PLAN PHASE II
C-320	GREEN SEA FLOYDS HS DRAINAGE AND UTILITY PLAN	C-533	SEDIMENT AND EROSION CONTROL PLAN PHASE II
C-520	SEDIMENT AND EROSION CONTROL PLAN PHASE I	C-534	SEDIMENT AND EROSION CONTROL DETAILS
C-521	SEDIMENT AND EROSION CONTROL PLAN PHASE II	E-001	NORTH MYRTLE HS ELECTRICAL SITE PLAN
C-522	SEDIMENT AND EROSION CONTROL DETAILS	C-600	TRACK AND FIELD DETAILS
E-001	GREEN SEA FLOYDS HS ELECTRICAL SITE PLAN	C-601	TRACK AND FIELD DETAILS
C-030	NORTH MYRTLE HS EXISTING CONDITIONS PLAN	C-602	TRACK AND FIELD DETAILS
C-031	NORTH MYRTLE HS DEMOLITION PLAN	C-603	TRACK AND FIELD DETAILS
C-130	NORTH MYRTLE HS LAYOUT PLAN	C-604	TRACK AND FIELD DETAILS
C-131	NORTH MYRTLE HS SURFACING AND DIMENSION PLAN		

SITE VICINITY MAP - NORTH MYRTLE HIGH SCHOOL SCALE: NOT TO SCALE










SURVEY NOTES


2. ELEVATIONS ARE REFERENCED TO THE NAVD 88 VERTICAL DATUM.














:\PROJECTS\ANY\K5\36108\CADD_ACAD\C-111_PH2 - AHS.DWG 2/26/2021 9:59:55 AM Plotted: 2/26/2021 2:26:04 PM Current User: Lindsay, Cady LastS








ater meter	LE	<u>geni</u>	<u>)</u>	
	TC = TD =	= TOP = TOP = TOP = TOP	OF OF	CONCF DRAIN





1. INCLUDES RURAL AREAS ADJACENT TO WELL-DEVELOPED LAWNS.


- 2. NOT REQUIRED ON SHOULDERS, MEDIANS, ETC.., AND SLOPES UNDER 5 FEET IN HEIGHT.
- 3. GIANT BERMUDA SEED, INCLUDING NK-37, SHALL NOT BE USED.
- 4. RESEEDING CRIMSON CLOVER SHALL BE INOCULATED IN ACCORDANCE WITH SUBSECTION 810.05. DO NOT PLANT CLOVER IN MEDIANS OR IN RURAL AREAS ADJACENT TO WELL-DEVELOPED LAWNS. 5. PENSACOLA BAHIA SHALL BE ALLOWED ONLY AS SHOWN IN SEEDING SCHEDULES 3 AND 4 AT THE
- RATE OF 50 POUNDS PER ACRE ONLY WHEN SEEDING PIT AREAS THAT ARE GOVERNED BY THE SOUTH CAROLINA MINING ACT. OTHERWISE, DO NOT INCLUDE BAHIA SEED IN THE MIX.
- 6. THE CONTRACTOR SHALL OBTAIN A SATISFACTORY STAND OF PERENNIAL VEGETATION WHOSE ROOT SYSTEM SHALL BE DEVELOPED SUFFICIENTLY TO SURVIVE DRY PERIODS AND WINTER WEATHER, AND BE CAPABLE OF RE-ESTABLISHMENT IN THE SPRING. THE PERENNIAL VEGETATIVE COVER SHALL HAVE A MINIMUM COVERAGE DENSITY OF 70% FOR THE SEEDED AREAS. CONTRACTOR SHALL DETERMINE ALL RATES OF APPLICATION NECESSARY TO PRODUCE THE REQUIRED STAND OF GRASS, AND SHALL FOLLOW THE APPLICATION PROCEDURES AS SPECIFIED HEREIN.
- 7. GIANT BERMUDA SEED, INCLUDING NK-37, SHALL NOT BE USED.

	SEEDING SCHE TEMPORARY VE	I r	Ds3
SCHEDULE NO.	COMMON NAME OF SEED	RATE PER ACRE (LBS.)	PLANTING DATES
1	COMMON BERMUDA (HULLED)	210	MARCH 16 TO
	TALL FESCUE	140	AUG. 31
2	COMMON BERMUDA (UNHULLED)	175	SEPT. 1 TO
	ANNUAL RYEGRASS	175	MARCH 15

NOTES:

THE CONTRACTOR SHALL OBTAIN A SATISFACTORY STAND OF PERENNIAL VEGETATION WHOSE ROOT SYSTEM SHALL BE DEVELOPED SUFFICIENTLY TO SURVIVE DRY PERIODS AND WINTER WEATHER, AND BE CAPABLE OF RE-ESTABLISHMENT IN THE SPRING. THE PERENNIAL VEGETATIVE COVER SHALL HAVE A MINIMUM COVERAGE DENSITY OF 70% FOR THE SEEDED AREAS. CONTRACTOR SHALL DETERMINE ALL RATES OF APPLICATION NECESSARY TO PRODUCE THE REQUIRED STAND OF GRASS, AND SHALL FOLLOW THE APPLICATION PROCEDURES AS SPECIFIED HEREIN.

	SEEDING SCHE PERMANENT VE	-	-	
SCHEDULE NO.	COMMON NAME OF SEED	RURAL RATE	URBAN RATE ¹	PLANTING DATES
	COMMON BERMUDA (HULLED) ³	30	30	MARCH 1
3 ⁵	WEEPING LOVEGRASS ²	10	10	ТО
	SERICEA LESPEDEZA (SCARIFIED) ²	50	50	AUG. 14
	COMMON BERMUDA (UNHULLED) ³	40	40	
	WEEPING LOVEGRASS ²	10	10	
4 ⁵	SERICEA LESPEDEZA (UNHULLED, UNSCARIFIED) ²	80	80	AUG. 5 TO FEB. 28
	RESEEDING CRIMSON CLOVER ⁴	20	0	
	RYE GRAIN	20	0	



NOTES:

1 INCLUDES RURAL AREAS ADJACENT TO WELL-DEVELOPED LAWNS. 2 NOT REQUIRED ON SHOULDERS, MEDIANS, ECT., AND SLOPES UNDER

5 FEET IN HEIGHT 3 GIANT BERMUDA SEED, INCLUDING NK-37, SHALL NOT BE USED.

- 4 RESEEDING CRIMSON CLOVER SHALL BE INOCULATED IN ACCORDANCE WITH SUBSECTION 810.05. DO NOT PLANT CLOVER IN MEDIANS OR IN RURAL AREAS ADJACENT TO WELL-DEVELOPED LAWNS.
- 5 PENSACOLA BAHIA SHALL BE ALLOWED ONLY AS SHOWN IN SEEDING SCHEDULES 3 AND 4 AT THE RATE OF 50 POUNDS PER ACRE ONLY WHEN SEEDING PIT AREAS THAT ARE GOVERNED BY THE SOUTH CAROLINA MINING ACT. OTHERWISE, DO NOT INCLUDE BAHIA SEED IN THE MIX. THE CONTRACTOR SHALL OBTAIN A SATISFACTORY STAND OF PERENNIAL VEGETATION WHOSE ROOT SYSTEM SHALL BE DEVELOPED SUFFICIENTLY TO SURVIVE DRY PERIODS AND WINTER WEATHER. AND BE CAPABLE OF

NECESSARY TO PRODUCE THE REQUIRED STAND OF GRASS, AND SHALL FOLLOW THE APPLICATION PROCEDURES AS SPECIFIED HEREIN.

RE-ESTABLISHMENT IN THE SPRING. THE PERENNIAL VEGETATIVE COVER SHALL HAVE A MINIMUM COVERAGE DENSITY OF 70% FOR THE SEEDED AREAS. CONTRACTOR SHALL DETERMINE ALL RATES OF APPLICATION

THE CONTRACTOR MAY INCLUDE QUANTITIES OF RYE GRAIN AND MILLET IN SCHEDULE 1 AND 3 IN ORDER TO ESTABLISH QUICK

GROUND CO	VER FOR EROSION CONTRO	OL PURPOSES.	Quiun
	SEEDING SCHED TEMPORARY VEG		
SCHEDULE NO.	COMMON NAME OF SEED	RATE PER ACRE (LBS.)	PLANTING DATES
1	ANNUAL SUDAN GRASS (SWEET OR TIFF)	40	APRIL 1- AUGUST 15
2	BROWN TOP MILLET	50	APRIL 1- AUGUST 15

RYE GRAIN 55 AUGUST 16 MARCH 31 OAT GRAIN IS TO BE ADDED TO ALL SCHEDULES, IF SEEDING DATE IS BETWEEN MARCH 1 AND APRIL 16, AT THE RATE OF 10 POUNDS PER ACRE.

THE CONTRACTOR SHALL OBTAIN A SATISFACTORY STAND OF VEGETATION THAT IS CAPABLE OF EROSION CONTROL. CONTRACTOR SHALL DETERMINE ALL RATES OF APPLICATION NECESSARY TO PRODUCE THE REQUIRED RESULTS. THE TEMPORARY VEGETATION SHALL PROVIDE MINIMUM DENSITY COVERAGE OF 70% OF THE SEEDED AREA.




- 1. CONTRACTOR TO LOCATE ALL EXISTING UTILITIES WITHIN AND IMMEDIATELY ADJACENT TO PROJECT AREA.
- 2. INSTALL CONSTRUCTION ENTRANCE.
- ALL TREE PROTECTION.

3. INSTALL PERIMETER EROSION CONTROL DEVICES, INCLUDING

4. DEMO EXISTING TRACK AND APPURTENANCES.

EROSION CONTROL LEGEND

SYMBOL	PRACTICE	DESCRIPTION
	INLET PROTECTION	A TEMPORARY SEDIMENT BARRIER LAID AROUND A STORM DRAIN INLET TO PREVENT SEDIMENT FROM ENTERING THE DRAINAGE SYSTEM.
	OUTLET PROTECTION	RIP RAP CHANNEL / BANK PLACED BELOW DRAINAGE OUTLETS TO REDUCE THE VELOCITY OF FLOW, EROSION, AND STABILIZE GRADES DOWNSTREAM OF OUTLET STRUCTURES.
CD 8	TEMPORARY CHECK DAM	RIP RAP BANK PLACED BELOW DRAINAGE OUTLETS TO REDUCE THE VELOCITY OF FLOW, EROSION AND STABILIZE GRADES DOWN STREAM OF DRAINAGE OUTLETS.
SF	SILT FENCE	A TEMPORARY STRUCTURE USED TO SLOW THE VELOCITY OF RUN-OFF, CAUSE SEDIMENT DEPOSITION AT THE STRUCTURE, AND FILTER SEDIMENT FROM RUN-OFF.
SF ₂ =	DOUBLE ROW SILT FENCE	A TEMPORARY STRUCTURE USED TO SLOW THE VELOCITY OF RUN-OFF, CAUSE SEDIMENT DEPOSITION AT THE STRUCTURE, AND FILTER SEDIMENT FROM RUN-OFF.
CL	CONSTRUCTION LIMITS	A DEFINED AREA THAT ALL LAND DISTURBANCE WILL OCCUR DURING CONSTRUCTION.
ECB XXXXX	PERMANENT EROSION CONTROL MATTING (HIGH PERFORMANCE TRM PYRAMAT BY SI GEOSOLUTIONS OR EQUAL)	A PERMANENT REINFORCEMENT MAT TO PREVENT SOIL EROSION AND MAINTAIN PERMANENT GROUND COVER.
Ds3	DISTURBED AREA STABILIZATION (WITH TEMPORARY VEGETATION)	ESTABLISHING PERMANENT VEGETATIVE COVER SUCH AS TREES, SHRUBS, VINES, GRASSES, SOD, OR LEGUMES ON DISTURBED AREAS.
ST Z	SEDIMENT TUBE	SEDIMENT TUBE PLACED IN EXISTING OR PROPOSED DITCH SECTIONS TO REDUCE THE VELOCITY OF FLOW, EROSION AND STABILIZE GRADES DOWN STREAM OR DRAINAGE OUTLETS.
CE	CONSTRUCTION ENTRANCE	A STONE STABILIZED PAD LOCATED AT ANY POINT THAT TRAFFIC WILL BE LEAVING A CONSTRUCTION SITE TO A PUBLIC RIGHT-OF-WAY, STREET, ALLEY, SIDEWALK, OR PARKING PLOT WHICH WILL REDUCE OR ELIMINATE THE TRANSPORT OF MUD FROM THE CONSTRUCTION SITE.




- DO NOT PLANT CLOVER IN MEDIANS OR IN RURAL AREAS ADJACENT TO WELL-DEVELOPED LAWNS. PENSACOLA BAHIA SHALL BE ALLOWED ONLY AS SHOWN IN SEEDING SCHEDULES 3 AND 4 AT THE
- SOUTH CAROLINA MINING ACT. OTHERWISE, DO NOT INCLUDE BAHIA SEED IN THE MIX.
- ROOT SYSTEM SHALL BE DEVELOPED SUFFICIENTLY TO SURVIVE DRY PERIODS AND WINTER WEATHER, AND BE CAPABLE OF RE-ESTABLISHMENT IN THE SPRING. THE PERENNIAL VEGETATIVE COVER SHALL HAVE A MINIMUM COVERAGE DENSITY OF 70% FOR THE SEEDED AREAS. CONTRACTOR SHALL DETERMINE ALL RATES OF APPLICATION NECESSARY TO PRODUCE THE REQUIRED STAND OF GRASS, AND SHALL FOLLOW THE APPLICATION PROCEDURES AS SPECIFIED HEREIN.

	SEEDING SCHE TEMPORARY VE		Ds3
SCHEDULE NO	COMMON NAME OF SEED	RATE PER ACRE	PLANTING DATES

NO.	OF SEED	(LBS.)	DATES
1	COMMON BERMUDA 210 (HULLED)		MARCH 16 TO
	TALL FESCUE	140	AUG. 31
2	COMMON BERMUDA (UNHULLED)	175	SEPT. 1 TO
	ANNUAL RYEGRASS	175	MARCH 15


	SEEDING SCHE PERMANENT VE	-	-	
SCHEDULE NO.	COMMON NAME OF SEED	RURAL RATE	URBAN RATE ¹	PLANTING DATES
	COMMON BERMUDA (HULLED) ³	30	30	MARCH 1
3 ⁵	WEEPING LOVEGRASS ²	10	10	ТО
	SERICEA LESPEDEZA (SCARIFIED) ²	50	50	AUG. 14
	COMMON BERMUDA (UNHULLED) ³	40	40	
	WEEPING LOVEGRASS ²	10	10	
4 ⁵	SERICEA LESPEDEZA (UNHULLED, UNSCARIFIED) ²	80	80	AUG. 5 TO FEB. 28
	RESEEDING CRIMSON CLOVER ⁴	20	0	
	RYE GRAIN	20	0	




GROUND CO	VER FOR EROSION CONTRO	JL PURPUSES.	
SEEDING SCHEDULE FOR TEMPORARY VEGETATION			
SCHEDULE NO.	COMMON NAME OF SEED	RATE PER ACRE (LBS.)	PLANTING DATES
1	ANNUAL SUDAN GRASS (SWEET OR TIFF)	40	APRIL 1- AUGUST 15
2	BROWN TOP MILLET	50	APRIL 1- AUGUST 15
3	RYE GRAIN	55	AUGUST 16- MARCH 31

EROSION CONTROL LEGEND

ICTION SEQUENCE:	SYMBOL	PRACTICE	DESCRIPTION
END ZONE TRACK EXTENSION AREA.	OTMBOL	TRACTICE	
DER DRAINAGE SYSTEM.		INLET PROTECTION	A TEMPORARY SEDIMENT BARRIER LAID AROUND A STORM DRAIN INLET TO PREVENT SEDIMENT FROM ENTERING THE DRAINAGE SYSTEM.
E TRACK AND INFIELD AREAS.			
AND INSTALL SYNTHETIC SURFACING.		OUTLET PROTECTION	RIP RAP CHANNEL / BANK PLACED BELOW DRAINAGE OUTLETS TO REDUCE THE VELOCITY OF FLOW, EROSION, AND STABILIZE GRADES DOWNSTREAM
K LINES AND FINISH REMAINING SITE IMPROVEMENTS.			OF OUTLET STRUCTURES.
SEED PERIMETER TIE IN POINTS.		TEMPORARY	RIP RAP BANK PLACED BELOW DRAINAGE OUTLETS TO REDUCE THE
ILIZATION OF ALL DENUDED AREAS.		CHECK DAM	VELOCITY OF FLOW, EROSION AND STABILIZE GRADES DOWN STREAM OF DRAINAGE OUTLETS.
IG SCHEDULE, WATER AND MAINTAIN TO INSURE OUND COVERAGE.			A TEMPORARY STRUCTURE USED TO SLOW THE VELOCITY OF RUN-OFF,
OVAL BY HORRY COUNTY, REMOVE ALL TEMPORARY	(SF) -	SILT FENCE	CAUSE SEDIMENT DEPOSITION AT THE STRUCTURE, AND FILTER SEDIMENT FROM RUN-OFF.
ONTROL DEVICES.	SF2 -	DOUBLE ROW SILT FENCE	A TEMPORARY STRUCTURE USED TO SLOW THE VELOCITY OF RUN-OFF, CAUSE SEDIMENT DEPOSITION AT THE STRUCTURE, AND FILTER SEDIMEN FROM RUN-OFF.
	CL — — —	CONSTRUCTION LIMITS	A DEFINED AREA THAT ALL LAND DISTURBANCE WILL OCCUR DURING CONSTRUCTION.
	ECB XXXX	PERMANENT EROSION CONTROL MATTING (HIGH PERFORMANCE TRM PYRAMAT BY SI GEOSOLUTIONS OR EQUAL)	A PERMANENT REINFORCEMENT MAT TO PREVENT SOIL EROSION AND MAINTAIN PERMANENT GROUND COVER.
	Ds3	DISTURBED AREA STABILIZATION (WITH TEMPORARY VEGETATION)	ESTABLISHING PERMANENT VEGETATIVE COVER SUCH AS TREES, SHRUB VINES, GRASSES, SOD, OR LEGUMES ON DISTURBED AREAS.
	ST 2	SEDIMENT TUBE	SEDIMENT TUBE PLACED IN EXISTING OR PROPOSED DITCH SECTIONS TO REDUCE THE VELOCITY OF FLOW, EROSION AND STABILIZE GRADES DOWN STREAM OR DRAINAGE OUTLETS.
	CE	CONSTRUCTION ENTRANCE	A STONE STABILIZED PAD LOCATED AT ANY POINT THAT TRAFFIC WILL BE LEAVING A CONSTRUCTION SITE TO A PUBLIC RIGHT-OF-WAY, STREET, ALLEY, SIDEWALK, OR PARKING PLOT WHICH WILL REDUCE OR ELIMINAT





ABBREVIATIONS AMPERE ALTERNATING CURRENT OVERLOAD POLE(S) PANEL PAIR AMPERE FRAME PNL 12ABOVE FINISHED FLOOR/GRADE PR PRIMARY POWER PHASE PRI PWR AMPERE INTERRUPTING CAPACITY AUXILIARY AMERICAN WIRE GAUGE PRESSURE TREATED RECEP RGS RLY RM RECEPTACLE (4)-RIGID GALVANIZED STEEL RELAY ROOM SECONDARY SHIELDED SWITCH SEC CIRCUIT BREAKER SH SW TEMPORARY/TEMPERATURE TERMINAL BOARD TYPICAL TEMP ΤB TYP COMMUNICATIONS CONNECTION, CONNECT UNLESS OTHERWISE NOTED UON VOLT, VOLTS VOLT-AMPERES DELTA CONNECTION DIAMETER WATT, WIRE WITH WEATHERPROOF XFMR/1 TRANSFORMER WYE CONNECTION DEVICES AND APPURTENANCES Φ[₩] DUPLEX RECEPTACLE EXISTING TO REMAIN TWO – 20 AMP DUPLEX RECEPTACLES UNDER SINGLE COVER JO JUNCTION BOX <u>RACEWAYS</u> ---- --- CONDUIT CONCEALED OR EXPOSED AS SPECIFIED ------- CONDUIT TURNING UP GENERAL CONTRACTOR CONDUIT TURNING DOWN GROUND FAULT CIRCUIT INTERRUPTER GROUND FAULT PROTECTION $\frac{PP-1}{1/3/5}$ HOMERUN BACK TO PANEL (PANEL AND CIRCUITS INDICATED) CIRCUIT CONTINUED OR CONNECTED TO EQUIPMENT AS INDICATED HIGH PRESSURE SODIUM ------ UNDERGROUND CONDUIT HIGH VOLTAGE IDENTIFY, IDENTIFICATION POWER DISTRIBUTION EQUIPMENT INCANDESCENT SURFACE MOUNTED BRANCH CIRCUIT PANELBOARD 240/120V, 10, 3W, UON JUNCTION BOX ΗН HAND HOLE THOUSAND CIRCULAR MILS CR CONTROL RELAY PANEL KILO VOLT AMPERE <u>GENERAL</u> NUMBER IN CIRCLE, WITH OR WITHOUT ARROW OR LEADER, REFER TO # LIGHT EMITTING DIODE MATCHING NUMBERED CODED NOTE X XXX DETAIL CALLOUT MAIN CIRCUIT BREAKER <u>GENERAL NOTES</u> METAL CLAD CABLE MANUFACTURER 1. REFER TO CIVIL DRAWINGS FOR SYMBOLS ASSOCIATED WITH WORK, EQUIPMENT, ETC.

BY OTHER(S). 2. ALL WORK SHOWN ON THE ELECTRICAL DRAWINGS SHALL BE BY THE ELECTRICAL CONTRACT UNLESS OTHERWISE INDICATED.

3. CONDUIT RUNS SHOWN ARE DIAGRAMMATIC UON. EXACT LOCATION OF ALL CONDUIT RUNS SHALL BE DETERMINED IN THE FIELD. COORDINATE INSTALLATIONS AND AVOID CONFLICT WITH PIPING, DUCTWORK, ACCESS DOORS AND WORK BY OTHER TRADES.

4. GENERAL NOTES APPLY TO ALL ELECTRICAL CONTRACT DRAWINGS.

AC

AF

AFF/G AIC AT

AUX AWG

BTM BKR BLDG

ČAB CB CIR

CKT

COMM CONN CTRL CU

△ DIA DISC DIST DIV DN DWG

ELEC

ENCL EQUIP ETR EXT

FC FIXT

FLR

FT FUT

G, GND

GALV

GC

GFI GFP

HGT HPS HTR

ΗV

ΗW

INCAND

J–BOX

KCM/Kcmil

JCT

KVA

ΚW

LGT

MAX

MCB MC

MFR

MH MECH MIN

MLO

MTD

NEC

NF

NL No/#

MT

LT(S) LED

ID

AMPERE TRIP

BOTTOM BREAKER BUILDING

CONDUIT

CABINET

CIRCUIT

CIRCUIT

CONTROL COPPER

DISCONNECT DISTRIBUTION

EACH EXHAUST FAN ELEVATION

ELECTRIC(AL)

ENCLOSURE EQUIPMENT

EXTERIOR

FUSE(D)

FIXTURE

GROUND

HEIGHT

HEATER

HOT WATER

JUNCTION

KILOWATT

LIGHTING

LIGHT(S)

LOUVER

MAXIMUM

METAL HALIDE

MAIN LUGS ONLY

NATIONAL ELECTRICAL CODE

MECHANICAL

MINIMUM

MOUNT

NORTH

NON-FUSED

NIGHT LIGHT

NUMBER

MOUNTED

FLOOR

FOOTCANDLES

FOOT (FEET) FUTURĖ


GALVANIZE(D)

DIVISION


DOWN DRAWING

CENTER LINE COMPANY

	ROVIDE CIRCUIT BREAKER, TYPE TO MA' TING.	ICH				###						
LOAI	XISTING POWER PANEL IS GE POWER MA D CENTER.		####	####	#### TOTA		#### VA	####	####			
NOT	ES:											
7	FINISH LINE RECEPTACLES (NOTE 2)											
5	MIDFIELD RECEPTACLES (NOTE 2)	20/1										
3	EXISTING LOAD TO REMAIN	20/1								30/2		
1	EXISTING LOAD TO REMAIN	20/1								70 /2	EXISTING MA	N CIRCUIT
СКТ	LOAD DESCRIPTION	CB AMPS/ POLE	CONN LOAD KVA		CONN LOAD KVA	[I		CONN LOAD KVA	CONN LOAD KVA	CB AMPS/ POLE	LOAL	DESCRIPTI
	SOURCE:	?	-		PA						CIRCUIT RATING:	
	LOCATION: MOUNTING: EXTERIOR WALL IN	<u>?</u> NEMA 3R NCLOSURE	<u>.</u>	EXI	PAN STIN(VER		MAINS:	PHASE, WIRE:	<u>120/</u>



<u>/240V, 1ф, 3W</u> <u>XXXA</u> <u> 10KAIC</u> BREAKER TO REMAIN SPACE SPACE




1 TYPICAL DIRECT BURIED CONDUIT(S) DETAIL - NOT TO SCALE

AYNOR HS ELECTRICAL SITE PLAN SCALE: 1" = 20'

CODED NOTES


- (1) 1" SCHEDULE 40 CONDUIT WITH (2)#6 AND (1)#6G FOR MIDFIELD RECEPTACLE FROM EXISTING PANEL
- (2) 1" SCHEDULE 40 PVC CONDUIT WITH (2)#4 AND (1)#4G FOR FINISH LINE RECEPTACLE FROM EXISTING PANEL.
- (3) provide communication junction box (see details 1 and 2 on C-602).
- (4) EXISTING POWER PANEL
- 5) 1 1/2" SCHEDULE 40 PVC CONDUIT WITH PULL STRING BETWEEN JUNCTION BOXES FOR INSTALLATION OF COMMUNICATION WIRING.
- \bigcirc PROVIDE JUNCTION BOX WITH GFI RECEPTACLE (SEE DETAILS 1 & 2 ON C-602).





-(5)

-(3)


Scale in fee










v:\PROJECTS\ANY\K5\36108\CADD_ACAD\C-120_PH2 - GSFHS.DWG : 2/11/2021 11:07:27 AM Plotted: 2/26/2021 2:32:29 PM Current User: Lindsay, Cady LastSav












SEEDING SCHEDULE FOR TEMPORARY VEGETATION								
SCHEDULE NO.	COMMON NAME OF SEED	RATE PER ACRE (LBS.)	PLANTING DATES					
1	ANNUAL SUDAN GRASS (SWEET OR TIFF)	40	APRIL 1- AUGUST 15					
2	BROWN TOP MILLET	50	APRIL 1- AUGUST 15					
3	RYE GRAIN	55	AUGUST 16- MARCH 31					




EROSION CONTROL LEGEND									
SYMBOL PRACTICE		DESCRIPTION							
	INLET PROTECTION	A TEMPORARY SEDIMENT BARRIER LAID AROUND A STORM DRAIN INLET TO PREVENT SEDIMENT FROM ENTERING THE DRAINAGE SYSTEM.							
₽ ₩	OUTLET PROTECTION	RIP RAP CHANNEL / BANK PLACED BELOW DRAINAGE OUTLETS TO REDUCE THE VELOCITY OF FLOW, EROSION, AND STABILIZE GRADES DOWNSTREAM OF OUTLET STRUCTURES.							
	TEMPORARY CHECK DAM	RIP RAP BANK PLACED BELOW DRAINAGE OUTLETS TO REDUCE THE VELOCITY OF FLOW, EROSION AND STABILIZE GRADES DOWN STREAM OF DRAINAGE OUTLETS.							
F)	SILT FENCE	A TEMPORARY STRUCTURE USED TO SLOW THE VELOCITY OF RUN-OFF, CAUSE SEDIMENT DEPOSITION AT THE STRUCTURE, AND FILTER SEDIMENT FROM RUN-OFF.							
F2 -	DOUBLE ROW SILT FENCE	A TEMPORARY STRUCTURE USED TO SLOW THE VELOCITY OF RUN-OFF, CAUSE SEDIMENT DEPOSITION AT THE STRUCTURE, AND FILTER SEDIMENT FROM RUN-OFF.							
<u>)</u>	CONSTRUCTION LIMITS	A DEFINED AREA THAT ALL LAND DISTURBANCE WILL OCCUR DURING CONSTRUCTION.							
	PERMANENT EROSION CONTROL MATTING (HIGH PERFORMANCE TRM PYRAMAT BY SI GEOSOLUTIONS OR EQUAL)	A PERMANENT REINFORCEMENT MAT TO PREVENT SOIL EROSION AND MAINTAIN PERMANENT GROUND COVER.							
Ds3	DISTURBED AREA STABILIZATION (WITH TEMPORARY VEGETATION)	ESTABLISHING PERMANENT VEGETATIVE COVER SUCH AS TREES, SHRUBS, VINES, GRASSES, SOD, OR LEGUMES ON DISTURBED AREAS.							
	SEDIMENT TUBE	SEDIMENT TUBE PLACED IN EXISTING OR PROPOSED DITCH SECTIONS TO REDUCE THE VELOCITY OF FLOW, EROSION AND STABILIZE GRADES DOWN STREAM OR DRAINAGE OUTLETS.							
E Contraction	CONSTRUCTION ENTRANCE	A STONE STABILIZED PAD LOCATED AT ANY POINT THAT TRAFFIC WILL BE LEAVING A CONSTRUCTION SITE TO A PUBLIC RIGHT-OF-WAY, STREET, ALLEY, SIDEWALK, OR PARKING PLOT WHICH WILL REDUCE OR ELIMINATE THE TRANSPORT OF MUD FROM THE CONSTRUCTION SITE.							




GROUND COVERT ON EROSION CONTROL TON OSES.								
SEEDING SCHEDULE FOR TEMPORARY VEGETATION								
SCHEDULE NO.	COMMON NAME OF SEED	RATE PER ACRE (LBS.)	PLANTING DATES					
1	ANNUAL SUDAN GRASS (SWEET OR TIFF)	40	APRIL 1- AUGUST 15					
2	BROWN TOP MILLET	50	APRIL 1- AUGUST 15					
3	RYE GRAIN	55	AUGUST 16- MARCH 31					





\2020\20095E - HORRY COUNTY SCHOOLS PHASE 2 TRACK AND FIELD IMPROVEMENTS\E\G.
 \218.20:30.30 M Picture. 2.73.70031 8:30.19 AM Current liser: Rolley Events LeetSchedBur
 \21.20:30.30 M Picture. 2.20.3031 8:30.19 AM Current liser: Rolley Events LeetSchedBur
 \21.20:30.30 M Picture. 2.20.3031 8:30.19 AM Current liser: Rolley Events LeetSchedBur
 \21.20:30.30 M Picture. 2.20.3031 8:30.19 AM Current liser: Rolley Events LeetSchedBur
 \21.20:30
 \21.20
 \21.20
 \21.20
 \21.20
 \21.20
 \21.20
 \21.20
 \21.20
 \21.20
 \21.20
 \21.20
 \21.20
 \21.20
 \21.20
 \21.20
 \21.20
 \21.20
 \21.20
 \21.20
 \21.20
 \21.20
 \21.20
 \21.20
 \21.20
 \21.20
 \21.20
 \21.20
 \21.20
 \21.20
 \21.20
 \21.20
 \21.20
 \21.20
 \21.20
 \21.20
 \21.20
 \21.20
 \21.20
 \21.20
 \21.20
 \21.20
 \21.20
 \21.20
 \21.20
 \21.20
 \21.20
 \21.20
 \21.20
 \21.20
 \21.20
 \21.20
 \21.20
 \21.20
 \21.20
 \21.20
 \21.20
 \21.20
 \21.20
 \21.20
 \21.20
 \21.20
 \21.20
 \21.20
 \21.20
 \21.20
 \21.20
 \21.20
 \21.20
 \21.20
 \21.20
 \21.20
 \21.20
 \21.20
 \21.20
 \21.20
 \21.20
 \21.20
 \21.20
 \21.20
 \21.20
 \21.20
 \21.20
 \21.20
 \21.20
 \21.20
 \21.20
 \21.20
 \21.20
 \21.20
 \21.20
 \21.20
 \21.20
 \21.20
 \21.20
 \21.20
 \21.20
 \21.20
 \21.20
 \21.20
 \21.20
 \21.20
 \21.20
 \21.20
 \21.20
 \21.20
 \21.20
 \21.20
 \21.20
 \21.20
 \21.20
 \21.20
 \21.20
 \21.20
 \21.20
 \21.20
 \21.20
 \21.20
 \21.20
 \21.20
 \21.20
 \21.20
 \21.20
 \21.20
 \21.20
 \21.20
 \21.20
 \21.20
 \21.20
 \21.20
 \21.20
 \21.20
 \21.20
 \21.20
 \21.20
 \21.20
 \21.20
 \21.20
 \21.20
 \21.20
 \21.20
 \21.20
 \21.20
 \21.20
 \21




	STABILIZIED
	CONSTRUCTION ENTRANC
U	SCALE: N.T.S.

EROSION CONTROL NOTES:

- 1. TOTAL DEVELOPMENT AREA : 3.90 ± ACRES
- 2. DISTURBED AREA THIS PHASE: 1.16 ± ACRES
- 3. IF NECESSARY, SLOPES, WHICH EXCEED EIGHT (8) VERTICAL FEET SHOULD BE STABILIZED WITH SYNTHETIC OR VEGETATIVE MATS, IN ADDITION TO HYDROSEEDING. IT MAY BE NECESSARY TO INSTALL TEMPORARY SLOPE DRAINS DURING CONSTRUCTION. TEMPORARY BERMS MAY BE NEEDED UNTIL THE SLOPE IS BROUGHT TO GRADE.
- STABILIZATION MEASURES SHALL BE INITIATED AS SOON AS PRACTICABLE IN PORTIONS OF THE SITE WHERE CONSTRUCTION ACTIVITIES HAVE TEMPORARILY OR PERMANENTLY CEASED, BUT IN NO CASE MORE THAN FOURTEEN (14) DAYS AFTER WORK HAS CEASED, EXCEPT AS STATED BELOW:
 WHERE STABILIZATION BY THE 14TH DAY IS PRECLUDED BY SNOW COVER OR FROZEN GROUND CONDITIONS STABILIZATION MEASURES MUST BE INITIATED AS SOON AS PRACTICABLE.
- WHERE CONSTRUCTION ACTIVITY ON A PORTION OF THE SITE IS TEMPORARILY CEASED, AND EARTH-DISTURBING ACTIVITIES WILL BE RESUMED WITHIN 14 DAYS, TEMPORARY STABILIZATION MEASURES DO NOT HAVE TO BE INITIATED ON THAT PORTION OF THE SITE.
- ALL SEDIMENT AND EROSION CONTROL DEVICES SHALL BE INSPECTED EVERY CALENDAR WEEK. IF PERIODIC INSPECTION OR OTHER INFORMATION INDICATES THAT A BMP HAS BEEN INAPPROPRIATELY OR INCORRECTLY INSTALLED, THE PERMITTEE MUST ADDRESS THE NECESSARY REPLACEMENT OR MODIFICATION REQUIRED TO CORRECT THE BMP WITHIN 48 HOURS OF IDENTIFICATION.
- 5. PROVIDE SILT FENCE AND/OR OTHER CONTROL DEVICES, AS MAY BE REQUIRED, TO CONTROL SOIL EROSION DURING UTILITY CONSTRUCTION. ALL DISTURBED AREAS SHALL BE CLEANED, GRADED AND STABILIZED WITH GRASSING IMMEDIATELY AFTER THE UTILITY INSTALLATION. FILL, COVER AND TEMPORARY SEEDING AT THE END OF EACH DAY ARE RECOMMENDED. IF WATER IS ENCOUNTERED WHILE TRENCHING, THE WATER SHOULD BE FILTERED TO REMOVE ANY SEDIMENTS BEFORE BEING PUMPED BACK INTO ANY WATERS OF THE STATE.
- ALL EROSION CONTROL DEVICES SHALL BE PROPERLY MAINTAINED DURING ALL PHASES OF CONSTRUCTION UNTIL THE COMPLETION OF ALL CONSTRUCTION ACTIVITIES AND ALL DISTURBED AREAS HAVE BEEN STABILIZED. ADDITIONAL CONTROL DEVICES MAY BE REQUIRED DURING CONSTRUCTION IN ORDER TO CONTROL EROSION AND/OR OFF SITE SEDIMENTATION. ALL TEMPORARY CONTROL DEVICES SHALL BE REMOVED ONCE CONSTRUCTION IS COMPLETE AND THE SITE IS STABILIZED.
- THE CONTRACTOR MUST TAKE NECESSARY ACTION TO MINIMIZE THE TRACKING OF MUD ONTO PAVED ROADWAYS FROM CONSTRUCTION AREAS AND THE GENERATION OF DUST. THE CONTRACTOR SHALL DAILY REMOVE MUD/SOIL FROM PAVEMENT, AS MAY BE REQUIRED.
 RESIDENTIAL SUBDIVISIONS REQUIRE EROSION CONTROL FEATURES FOR INFRASTRUCTURE AS WELL AS FOR
- INDIVIDUAL LOT CONSTRUCTION. INDIVIDUAL PROPERTY OWNERS SHALL FOLLOW THESE PLANS DURING CONSTRUCTION OR OBTAIN APPROVAL OF AN INDIVIDUAL PLAN IN ACCORDANCE WITH S.C. REG. 72-300 ET SEQ. AND SCR 100000.
 TEMPORARY DIVERSION BERMS AND/OR DITCHES WILL BE PROVIDED AS NEEDED DURING CONSTRUCTION TO PROTECT.
- WORK AREAS FROM UPSLOPE RUNOFF AND/OR TO DIVERT SEDIMENT-LADEN WATER TO APPROPRIATE TRAPS OR STABLE OUTLETS. 11. ALL WATERS OF THE STATE (W₀S), INCLUDING WETLANDS, ARE TO BE FLAGGED OR OTHERWISE CLEARLY MARKED
- IN THE FIELD. A DOUBLE ROW OF SILT FENCE IS TO BE INSTALLED IN ALL AREAS WHERE A 50 FOOT BUFFER CANNOT BE MAINTAINED BETWEEN THE DISTURBED AREA AND ALL WoS. A 10 FOOT BUFFER SHOULD BE MAINTAINED BETWEEN THE LAST ROW OF SILT FENCE AND ALL WoS.
- LITTER, CONSTRUCTION DEBRIS, OILS, FUELS AND BUILDING PRODUCTS WITH SIGNIFICANT POTENTIAL FOR IMPACT (SUCH AS STOCKPILES OF FRESHLY TREATED LUMBER) AND CONSTRUCTION CHEMICALS THAT COULD BE EXPOSED TO STORM WATER MUST BE PREVENTED FROM BECOMING A POLLUTANT SOURCE IN STORM WATER DISCHARGES.
 A COPY OF THE SWPPP, INSPECTION RECORDS, AND RAINFALL DATA MUST BE RETAINED AT THE CONSTRUCTION
- SITE OR A NEARBY LOCATION EASILY ACCESSIBLE DURING NORMAL BUSINESS HOURS, FROM THE DATE OF COMMENCEMENT OF CONSTRUCTION ACTIVITIES TO THE DATE THAT FINAL STABILIZATION IS REACHED. 14. INITIATE STABILIZATION MEASURES ON ANY EXPOSED STEEP SLOPE (3H:1V OR GREATER) WHERE LAND DISTURBING
- ACTIVITIES HAVE PERMANENTLY OR TEMPORARILY CEASED, AND WILL NOT RESUME FOR A PERIOD OF 7 CALENDAR DAYS. 15. MINIMIZE SOIL COMPACTION AND, UNLESS INFEASIBLE, PRESERVE TOPSOIL.
- 16. MINIMIZE THE DISCHARGE OF POLLUTANTS FROM EQUIPMENT AND VEHICLE WASHING, WHEEL WASH WATER, AND OTHER WASH WATERS. WASH WATERS MUST BE TREATED IN A SEDIMENT BASIN OR ALTERNATIVE CONTROL THAT PROVIDES EQUIVALENT OR BETTER TREATMENT PRIOR TO DISCHARGE.
- MINIMIZE THE DISCHARGE OF POLLUTANTS FROM DEWATERING OF TRENCHES AND EXCAVATED AREAS. THESE DISCHARGES ARE TO BE ROUTED THROUGH APPROPRIATE BMPs (SEDIMENT BASIN, FILTER BAG, ETC.).
 THE FOLLOWING DISCHARGES FROM SITES ARE PROHIBITED:
- WASTEWATER FROM WASHOUT OF CONCRETE, UNLESS MANAGED BY AN APPROPRIATE CONTROL;
 WASTEWATER FROM WASHOUT AND CLEANOUT OF STUCCO, PAINT, FORM RELEASE OILS CURING COMPOUNDS AND OTHER CONSTRUCTION MATERIALS;
 FUELS, OILS, OR OTHER POLLUTANTS USED IN VEHICLE AND EQUIPMENT OPERATION AND MAINTENANCE; AND
 SOAPS OR SOLVENTS USED IN VEHICLE AND EQUIPMENT WASHING.
- 19. AFTER CONSTRUCTION ACTIVITIES BEGIN, INSPECTIONS MUST BE CONDUCTED AT A MINIMUM OF AT LEAST ONCE EVERY CALENDAR WEEK AND MUST BE CONDUCTED UNTIL FINAL STABILIZATION IS REACHED ON ALL AREAS OF THE CONSTRUCTION SITE.
- 20. IF EXISTING BMPs NEED TO BE MODIFIED OR IF ADDITIONAL BMPs ARE NECESSARY TO COMPLY WITH THE REQUIREMENTS OF THIS PERMIT AND / OR SC'S WATER QUALITY STANDARDS, IMPLEMENTATION MUST BE COMPLETED BEFORE THE NEXT STORM EVENT WHENEVER PRACTICABLE. IF IMPLEMENTATION BEFORE THE NEXT STORM EVENT IS IMPRACTICABLE, THE SITUATION MUST BE DOCUMENTED IN THE SWPPP AND ALTERNATIVE BMPs MUST BE IMPLEMENTED AS SOON AS REASONABLY POSSIBLE.
- 21. A PRE-CONSTRUCTION CONFERENCE MUST BE HELD FOR EACH CONSTRUCTION SITE WITH AN APPROVED ON-SITE SWPPP PRIOR TO THE IMPLEMENTATION OF CONSTRUCTION ACTIVITIES. FOR NON-LINEAR PROJECTS THAT DISTURB 10 ACRES OR MORE THIS CONFERENCE MUST BE HELD ON-SITE UNLESS THE DEPARTMENT HAS APPROVED OTHERWISE.
- 22. THE CONTRACTOR SHALL BE RESPONSIBLE FOR MAINTAINING ALL SILT BARRIERS AND SEDIMENT CONTROL INSTALLATIONS DURING CONSTRUCTION UNTIL THE COMPLETION OF THE SITE DEVELOPMENT.
- 23. EROSION CONTROL DEVICES MUST BE INSTALLED IMMEDIATELY AFTER LAND DISTURBANCE OCCURS. THE LOCATION OF SOME OF THE CONTROL DEVICES MAY BE ALTERED FROM THAT SHOWN ON THE APPROVED PLANS, IF DRAINAGE PATTERNS DURING CONSTRUCTION VARY FROM THE FINAL DRAINAGE PATTERNS. IT SHALL BE THE CONTRACTORS RESPONSIBILITY TO PROVIDE SOIL EROSION CONTROL FOR ALL DRAINAGE PATTERNS DURING ALL STAGES OF CONSTRUCTION. ALL INADEQUACIES IN SOIL EROSION CONTROL DURING ANY PHASE OF CONSTRUCTION MUST BE REPORTED IMMEDIATELY TO THE ENGINEER.
- THE CONTRACTOR SHALL MAINTAIN ALL EROSION CONTROL MEASURES UNTIL PERMANENT VEGETATION HAS BEEN ESTABLISHED. THE CONTRACTOR SHALL INSPECT EROSION CONTROL MEASURES AT THE END OF EACH WORKING DAY TO ENSURE PROPER FUNCTIONING OF ALL DEVICES.
 FAILURE TO INSTALL, OPERATE AND MAINTAIN ALL EROSION CONTROL MEASURES, AS SHOWN ON THE APPROVED
- PLANS OR AS DIRECTED BY THE ENGINEER AND/OR OCRM WILL RESULT IN ALL WORK ON THE CONSTRUCTION SITE BEING STOPPED UNTIL PROPER CORRECTIVE MEASURES HAVE BEEN MET, AS REQUIRED AND/OR DIRECTED.
 26. ALL LAND DISTURBING ACTIVITIES REQUIRES COMPLIANCE UNDER THE NPDES GENERAL PERMIT FOR STORM WATER DISCHARGES FROM THE CONSTRUCTION ACTIVITIES (PERMIT NO. SCR100000). ANY NONCOMPLIANCE WITH
- THESE REGULATIONS IS A VIOLATION OF THE FEDERAL CLEAN WATER ACT AND MAY REQUIRE ENFORCEMENT ACTION BY HORRY COUNTY OR SCOHEC. 7. CONTRACTOR SHALL PROVIDE A WATER TIGHT ENCLOSURE FOR STORAGE OF THE OCRM CERTIFIED PLANS AND
- INSPECTION REPORTS. ENCLOSURE SHALL BE LOCATED IN AN AREA ACCESSIBLE TO REGULATORY PERSONNEL
- 29. ALL CONCRETE TO BE WASHED OUT IN AN APPROVED AREA.


28. ALL STOCKPILE TO BE PROTECTED WITH SILT FENCE.


OURCE DEDOLECTION	
TREE PROTECTION	




A AC AF AFF/G AIC AT AUX AWG	ABBREVIATIONS AMPERE ALTERNATING CURRENT AMPERE FRAME ABOVE FINISHED FLOOR/GRADE AMPERE INTERRUPTING CAPACITY AMPERE TRIP AUXILIARY AMERICAN WIRE GAUGE	OL P PNL PR PRI PWR Ø PT	OVERLOAD POLE(S) PANEL PAIR PRIMARY POWER PHASE PRESSURE TREATED
BTM BKR BLDG	BOTTOM BREAKER BUILDING	RECEPT RGS RLY RM	RECEPTACLE RIGID GALVANIZED STEEL RELAY ROOM
C CAB CB CIR CKT	CONDUIT CABINET CIRCUIT BREAKER CIRCUIT CIRCUIT	SEC SH SW	SECONDARY SHIELDED SWITCH
© CO COMM CONN	CENTER LINE COMPANY COMMUNICATIONS CONNECTION, CONNECT	TEMP TB TYP	TEMPORARY/TEMPERATURE TERMINAL BOARD TYPICAL
CTRL CU DIA	CONTROL COPPER DELTA CONNECTION DIAMETER	UON V VA	UNLESS OTHERWISE NOTED VOLT, VOLTS VOLT-AMPERES
DISC DIST DIV DN	DISCONNECT DISTRIBUTION DIVISION DOWN	W W/ WP	WATT, WIRE WITH WEATHERPROOF
DWG EA EF EL	DRAWING EACH EXHAUST FAN ELEVATION	XFMR/T Ƴ	TRANSFORMER WYE CONNECTION
ELEC ENCL EQUIP ETR EXT	ELECTRIC(AL) ENCLOSURE EQUIPMENT EXISTING TO REMAIN EXTERIOR		DEVICES AND APPURTENANCES
F FC FIXT FLR FT FUT	FUSE(D) FOOTCANDLES FIXTURE FLOOR FOOT (FEET) FUTURE	♥ TWO - JJ () JUNCT	– 20 AMP DUPLEX RECEPTACLES UNDER SINGLE COVER TION BOX <u>RACEWAYS</u>
G, GND GALV GC GFI GFP	GROUND GALVANIZE(D) GENERAL CONTRACTOR GROUND FAULT CIRCUIT INTERRUPTER GROUND FAULT PROTECTION	<u>PP-1</u>	 CONDUIT CONCEALED OR EXPOSED AS SPECIFIED CONDUIT TURNING UP CONDUIT TURNING DOWN HOMERUN BACK TO PANEL (PANEL AND CIRCUITS INDICATED)
HGT HPS HTR HV HW	HEIGHT HIGH PRESSURE SODIUM HEATER HIGH VOLTAGE HOT WATER	17575	CIRCUIT CONTINUED OR CONNECTED TO EQUIPMENT AS INDICATED
ID INCAND J—BOX	IDENTIFY, IDENTIFICATION INCANDESCENT JUNCTION BOX	s	POWER DISTRIBUTION EQUIPMENT
JCT KCM/Kcmil KVA KW	JUNCTION THOUSAND CIRCULAR MILS KILO VOLT AMPERE		AND HOLE
KW LGT LT(S) LED L	KILOWATT LIGHTING LIGHT(S) LIGHT EMITTING DIODE LOUVER	#	<u>GENERAL</u> NUMBER IN CIRCLE, WITH OR WITHOUT ARROW OR LEADER, REFER TO MATCHING NUMBERED CODED NOTE
MAX MCB MC MFR MH MECH MIN MLO MT MTD	MAXIMUM MAIN CIRCUIT BREAKER METAL CLAD CABLE MANUFACTURER METAL HALIDE MECHANICAL MINIMUM MAIN LUGS ONLY MOUNT MOUNTED	BY OTHE 2. ALL WOF	O CIVIL DRAWINGS FOR SYMBOLS ASSOCIATED WITH WORK, EQUIPMENT, ET
N NEC NF NL No/#	NORTH NATIONAL ELECTRICAL CODE NON-FUSED NIGHT LIGHT NUMBER	RUNS SH CONFLIC	RUNS SHOWN ARE DIAGRAMMATIC UON. EXACT LOCATION OF ALL CONDU- HALL BE DETERMINED IN THE FIELD. COORDINATE INSTALLATIONS AND AVO T WITH PIPING, DUCTWORK, ACCESS DOORS AND WORK BY OTHER TRADES NOTES APPLY TO ALL ELECTRICAL CONTRACT DRAWINGS.


	LOCATION: MOUNTING: <u>EXTERIOR WALL IN</u> SOURCE:	? NEMA_3R CLOSURE ?		EXI	STIN	NEL G NE	POV	VER		MAINS:	PHASE, WIRE: <u>120/208V, 3φ, 4</u> <u>225A M</u> CIRCUIT RATING:
СКТ	LOAD DESCRIPTION	CB AMPS/ POLE	CONN LOAD KVA	CONN LOAD KVA	CONN LOAD KVA		CONN _OAD KVA	CONN LOAD KVA	CONN LOAD KVA	CB AMPS/ POLE	LOAD DESCRIPTION
1	EXISTING LOAD TO REMAIN	20/1								20/1	EXISTING LOAD TO REMA
3	FINISH LINE RECEPTACLES (NOTE 2)	20/1									SPA
	MIDFIELD RECEPTACLE (NOTE 2)	20/1									SPA
7											SPA
	EXISTING LOAD TO REMAIN	60/3									SPA
11											SPA
13 15 17	EXISTING LOAD TO REMAIN	30/3				-				100/3	EXISTING LOAD TO REMA
19											SPA
21											SPA
23		150/3									SPA
25	EXISTING CONCESSION STAND	13073									SPA
27											SPA
29											SPA
NOT 1 F	ES: XISTING POWER PANEL IS SQUARE D		####	лллл	лллл		нтт	ШШШ	####		
NQO	D3225Q2MB.		####	####	####		####	####	####		
	ROVIDE CIRCUIT BREAKER, TYPE TO MAT TING.	СН				AL k ####	VA				










1 TYPICAL DIRECT BURIED CONDUIT(S) DETAIL - NOT TO SCALE


















: V:\PROJECTS\ANY\K5\36108\CADD_ACAD\C-130_PH2 - NMHS.DWG ed: 2/26/2021 9:59:27 AM Plotted: 2/26/2021 2:38:13 PM Current User: Lindsay, Cady LastSo











- 1. INCLUDES RURAL AREAS ADJACENT TO WELL-DEVELOPED LAWNS.
- 2. NOT REQUIRED ON SHOULDERS, MEDIANS, ETC.., AND SLOPES UNDER 5 FEET IN HEIGHT.
- 3. GIANT BERMUDA SEED, INCLUDING NK-37, SHALL NOT BE USED. 4. RESEEDING CRIMSON CLOVER SHALL BE INOCULATED IN ACCORDANCE WITH SUBSECTION 810.05.
- DO NOT PLANT CLOVER IN MEDIANS OR IN RURAL AREAS ADJACENT TO WELL-DEVELOPED LAWNS.
- 5. PENSACOLA BAHIA SHALL BE ALLOWED ONLY AS SHOWN IN SEEDING SCHEDULES 3 AND 4 AT THE RATE OF 50 POUNDS PER ACRE ONLY WHEN SEEDING PIT AREAS THAT ARE GOVERNED BY THE SOUTH CAROLINA MINING ACT. OTHERWISE, DO NOT INCLUDE BAHIA SEED IN THE MIX.
- 6. THE CONTRACTOR SHALL OBTAIN A SATISFACTORY STAND OF PERENNIAL VEGETATION WHOSE ROOT SYSTEM SHALL BE DEVELOPED SUFFICIENTLY TO SURVIVE DRY PERIODS AND WINTER WEATHER, AND BE CAPABLE OF RE-ESTABLISHMENT IN THE SPRING. THE PERENNIAL VEGETATIVE COVER SHALL HAVE A MINIMUM COVERAGE DENSITY OF 70% FOR THE SEEDED AREAS. CONTRACTOR SHALL DETERMINE ALL RATES OF APPLICATION NECESSARY TO PRODUCE THE REQUIRED STAND OF GRASS, AND SHALL FOLLOW THE APPLICATION PROCEDURES AS SPECIFIED HEREIN.
- 7. GIANT BERMUDA SEED, INCLUDING NK-37, SHALL NOT BE USED.

SEEDING SCHEDULE FOR TEMPORARY VEGETATION Ds3									
SCHEDULE NO.	COMMON NAME OF SEED	RATE PER ACRE (LBS.)	PLANTING DATES						
1	COMMON BERMUDA (HULLED)	210	MARCH 16 TO						
	TALL FESCUE	140	AUG. 31						
2	COMMON BERMUDA (UNHULLED)	175	SEPT. 1 TO						
	ANNUAL RYEGRASS	175	MARCH 15						


NOTES:

THE CONTRACTOR SHALL OBTAIN A SATISFACTORY STAND OF PERENNIAL VEGETATION WHOSE ROOT SYSTEM SHALL BE DEVELOPED SUFFICIENTLY TO SURVIVE DRY PERIODS AND WINTER WEATHER, AND BE CAPABLE OF RE-ESTABLISHMENT IN THE SPRING. THE PERENNIAL VEGETATIVE COVER SHALL HAVE A MINIMUM COVERAGE DENSITY OF 70% FOR THE SEEDED AREAS. CONTRACTOR SHALL DETERMINE ALL RATES OF APPLICATION NECESSARY TO PRODUCE THE REQUIRED STAND OF GRASS, AND SHALL FOLLOW THE APPLICATION PROCEDURES AS SPECIFIED HEREIN.









NOTES: 1 INCLUDES RURAL AREAS ADJACENT TO WELL-DEVELOPED LAWNS.

- 2 NOT REQUIRED ON SHOULDERS, MEDIANS, ECT., AND SLOPES UNDER 5 FEET IN HEIGHT
- 3 GIANT BERMUDA SEED, INCLUDING NK-37, SHALL NOT BE USED. 4 RESEEDING CRIMSON CLOVER SHALL BE INOCULATED IN ACCORDANCE WITH SUBSECTION 810.05. DO NOT PLANT CLOVER IN MEDIANS OR IN RURAL AREAS ADJACENT TO WELL-DEVELOPED LAWNS.
- 5 PENSACOLA BAHIA SHALL BE ALLOWED ONLY AS SHOWN IN SEEDING SCHEDULES 3 AND 4 AT THE RATE OF 50 POUNDS PER ACRE ONLY WHEN SEEDING PIT AREAS THAT ARE GOVERNED BY THE SOUTH CAROLINA MINING ACT. OTHERWISE, DO NOT INCLUDE BAHIA SEED IN THE MIX.

THE CONTRACTOR SHALL OBTAIN A SATISFACTORY STAND OF PERENNIAL VEGETATION WHOSE ROOT SYSTEM SHALL BE DEVELOPED SUFFICIENTLY TO SURVIVE DRY PERIODS AND WINTER WEATHER, AND BE CAPABLE OF RE-ESTABLISHMENT IN THE SPRING. THE PERENNIAL VEGETATIVE COVER SHALL HAVE A MINIMUM COVERAGE DENSITY OF 70% FOR THE SEEDED AREAS. CONTRACTOR SHALL DETERMINE ALL RATES OF APPLICATION NECESSARY TO PRODUCE THE REQUIRED STAND OF GRASS, AND SHALL FOLLOW THE APPLICATION PROCEDURES AS SPECIFIED HEREIN.

THE CONTRACTOR MAY INCLUDE QUANTITIES OF RYE GRAIN AND MILLET IN SCHEDULE 1 AND 3 IN ORDER TO ESTABLISH QUICK


GROUND COVER FOR EROSION CONTROL PURPOSES.								
SEEDING SCHEDULE FOR TEMPORARY VEGETATION								
COMMON NAME RATE PER PLANTING OF SEED ACRE (LBS.) DATES								
UAL SUDAN GRASS SWEET OR TIFF)	40	APRIL 1- AUGUST 15						
2 BROWN TOP MILLET 50 APRIL 1- AUGUST 15								
RYE GRAIN	55	AUGUST 16- MARCH 31						
	MPORARY VEG COMMON NAME OF SEED UAL SUDAN GRASS SWEET OR TIFF) OWN TOP MILLET	MPORARY VEGETATIONCOMMON NAME OF SEEDRATE PER ACRE (LBS.)UAL SUDAN GRASS SWEET OR TIFF)40OWN TOP MILLET50						

OAT GRAIN IS TO BE ADDED TO ALL SCHEDULES, IF SEEDING DATE IS BETWEEN MARCH 1 AND APRIL 16, AT THE RATE OF 10 POUNDS PER ACRE.


THE CONTRACTOR SHALL OBTAIN A SATISFACTORY STAND OF VEGETATION THAT IS CAPABLE OF EROSION CONTROL. CONTRACTOR SHALL DETERMINE ALL RATES OF APPLICATION NECESSARY TO PRODUCE THE REQUIRED RESULTS. THE TEMPORARY VEGETATION SHALL PROVIDE MINIMUM DENSITY COVERAGE OF 70% OF THE SEEDED AREA.

CONSTRUCTION SEQUE 1. CONTRACTOR TO LOCATE ALL EXIS IMMEDIATELY ADJACENT TO PROJ

- 2. INSTALL CONSTRUCTION ENTRAN 3. INSTALL PERIMETER EROSION CO
- ALL TREE PROTECTION. 4. DEMO EXISTING TRACK AND APPU



IENCE:		EROSION CONTROL LEGEND				
XISTING UTILITIES WITHIN AND OJECT AREA.	SYMBOL	PRACTICE	DESCRIPTION			
NCE.						
CONTROL DEVICES, INCLUDING		INLET PROTECTION	A TEMPORARY SEDIMENT BARRIER LAID AROUND A STORM DRAIN INLET TO PREVENT SEDIMENT FROM ENTERING THE DRAINAGE SYSTEM.			
PURTENANCES.		OUTLET PROTECTION	RIP RAP CHANNEL / BANK PLACED BELOW DRAINAGE OUTLETS TO REDUCE THE VELOCITY OF FLOW, EROSION, AND STABILIZE GRADES DOWNSTREAM OF OUTLET STRUCTURES.			
		TEMPORARY CHECK DAM	RIP RAP BANK PLACED BELOW DRAINAGE OUTLETS TO REDUCE THE VELOCITY OF FLOW, EROSION AND STABILIZE GRADES DOWN STREAM OF DRAINAGE OUTLETS.			
	SF	SILT FENCE	A TEMPORARY STRUCTURE USED TO SLOW THE VELOCITY OF RUN-OFF, CAUSE SEDIMENT DEPOSITION AT THE STRUCTURE, AND FILTER SEDIMENT FROM RUN-OFF.			
	SF2 -	DOUBLE ROW SILT FENCE	A TEMPORARY STRUCTURE USED TO SLOW THE VELOCITY OF RUN-OFF, CAUSE SEDIMENT DEPOSITION AT THE STRUCTURE, AND FILTER SEDIMEN FROM RUN-OFF.			
	CL — — —	CONSTRUCTION LIMITS	A DEFINED AREA THAT ALL LAND DISTURBANCE WILL OCCUR DURING CONSTRUCTION.			
	ECB XXXXX	PERMANENT EROSION CONTROL MATTING (HIGH PERFORMANCE TRM PYRAMAT BY SI GEOSOLUTIONS OR EQUAL)	A PERMANENT REINFORCEMENT MAT TO PREVENT SOIL EROSION AND MAINTAIN PERMANENT GROUND COVER.			
	Ds3	DISTURBED AREA STABILIZATION (WITH TEMPORARY VEGETATION)	ESTABLISHING PERMANENT VEGETATIVE COVER SUCH AS TREES, SHRUBS VINES, GRASSES, SOD, OR LEGUMES ON DISTURBED AREAS.			
	ST 6///	SEDIMENT TUBE	SEDIMENT TUBE PLACED IN EXISTING OR PROPOSED DITCH SECTIONS TO REDUCE THE VELOCITY OF FLOW, EROSION AND STABILIZE GRADES DOWN STREAM OR DRAINAGE OUTLETS.			
	CE SS	CONSTRUCTION ENTRANCE	A STONE STABILIZED PAD LOCATED AT ANY POINT THAT TRAFFIC WILL BE LEAVING A CONSTRUCTION SITE TO A PUBLIC RIGHT-OF-WAY, STREET, ALLEY, SIDEWALK, OR PARKING PLOT WHICH WILL REDUCE OR ELIMINATE			




- INCLUDES RURAL AREAS ADJACENT TO WELL-DEVELOPED LAWNS.
 NOT REQUIRED ON SHOULDERS, MEDIANS, ETC.., AND SLOPES UNDER
- 5 FEET IN HEIGHT.3. GIANT BERMUDA SEED, INCLUDING NK-37, SHALL NOT BE USED.
- RESEEDING CRIMSON CLOVER SHALL BE INOCULATED IN ACCORDANCE WITH SUBSECTION 810.05.
- DO NOT PLANT CLOVER IN MEDIANS OR IN RURAL AREAS ADJACENT TO WELL-DEVELOPED LAWNS.
- 5. PENSACOLA BAHIA SHALL BE ALLOWED ONLY AS SHOWN IN SEEDING SCHEDULES 3 AND 4 AT THE RATE OF 50 POUNDS PER ACRE ONLY WHEN SEEDING PIT AREAS THAT ARE GOVERNED BY THE SOUTH CAROLINA MINING ACT. OTHERWISE, DO NOT INCLUDE BAHIA SEED IN THE MIX.
- 6. THE CONTRACTOR SHALL OBTAIN A SATISFACTORY STAND OF PERENNIAL VEGETATION WHOSE ROOT SYSTEM SHALL BE DEVELOPED SUFFICIENTLY TO SURVIVE DRY PERIODS AND WINTER WEATHER, AND BE CAPABLE OF RE-ESTABLISHMENT IN THE SPRING. THE PERENNIAL VEGETATIVE COVER SHALL HAVE A MINIMUM COVERAGE DENSITY OF 70% FOR THE SEEDED AREAS. CONTRACTOR SHALL DETERMINE ALL RATES OF APPLICATION NECESSARY TO PRODUCE THE REQUIRED STAND OF GRASS, AND SHALL FOLLOW THE APPLICATION PROCEDURES AS SPECIFIED HEREIN.
- 7. GIANT BERMUDA SEED, INCLUDING NK-37, SHALL NOT BE USED.


SEEDING SCHEDULE FOR TEMPORARY VEGETATION Ds3						
SCHEDULE NO.						
1	COMMON BERMUDA (HULLED)	210	MARCH 16 TO			
	TALL FESCUE	140	AUG. 31			
2	COMMON BERMUDA (UNHULLED)	175	SEPT. 1 TO			
	ANNUAL RYEGRASS	175	MARCH 15			

NOTES:

THE CONTRACTOR SHALL OBTAIN A SATISFACTORY STAND OF PERENNIAL VEGETATION WHOSE ROOT SYSTEM SHALL BE DEVELOPED SUFFICIENTLY TO SURVIVE DRY PERIODS AND WINTER WEATHER, AND BE CAPABLE OF RE-ESTABLISHMENT IN THE SPRING. THE PERENNIAL VEGETATIVE COVER SHALL HAVE A MINIMUM COVERAGE DENSITY OF 70% FOR THE SEEDED AREAS. CONTRACTOR SHALL DETERMINE ALL RATES OF APPLICATION NECESSARY TO PRODUCE THE REQUIRED STAND OF GRASS, AND SHALL FOLLOW THE APPLICATION PROCEDURES AS SPECIFIED HEREIN.

SEEDING SCHEDULE FOR PERMANENT VEGETATION					
SCHEDULE NO.	COMMON NAME OF SEED	RURAL RATE	URBAN RATE ¹	PLANTING DATES	
	COMMON BERMUDA (HULLED) ³	30	30	MARCH 1	
3 ⁵	WEEPING LOVEGRASS ²	10	10	то	
	SERICEA LESPEDEZA (SCARIFIED) ²	50	50	AUG. 14	
	COMMON BERMUDA (UNHULLED) ³	40	40	AUG. 5 TO FEB_28	
	WEEPING LOVEGRASS ²	10	10		
4 ⁵	SERICEA LESPEDEZA (UNHULLED, UNSCARIFIED) ²	80	80		
	RESEEDING CRIMSON CLOVER ⁴	20	0		
	RYE GRAIN	20	0		





NOTES: 1 INCLUDES RURAL AREAS ADJACENT TO WELL-DEVELOPED LAWNS.

- 2 NOT REQUIRED ON SHOULDERS, MEDIANS, ECT., AND SLOPES UNDER 5 FEET IN HEIGHT
- 3 GIANT BERMUDA SEED, INCLUDING NK-37, SHALL NOT BE USED.
 4 RESEEDING CRIMSON CLOVER SHALL BE INOCULATED IN ACCORDANCE WITH SUBSECTION 810.05. DO NOT PLANT CLOVER IN MEDIANS OR IN

RURAL AREAS ADJACENT TO WELL-DEVELOPED LAWNS.

5 PENSACOLA BAHIA SHALL BE ALLOWED ONLY AS SHOWN IN SEEDING SCHEDULES 3 AND 4 AT THE RATE OF 50 POUNDS PER ACRE ONLY WHEN SEEDING PIT AREAS THAT ARE GOVERNED BY THE SOUTH CAROLINA

MINING ACT. OTHERWISE, DO NOT INCLUDE BAHIA SEED IN THE MIX.

THE CONTRACTOR SHALL OBTAIN A SATISFACTORY STAND OF PERENNIAL VEGETATION WHOSE ROOT SYSTEM SHALL BE DEVELOPED SUFFICIENTLY TO SURVIVE DRY PERIODS AND WINTER WEATHER, AND BE CAPABLE OF RE-ESTABLISHMENT IN THE SPRING. THE PERENNIAL VEGETATIVE COVER SHALL HAVE A MINIMUM COVERAGE DENSITY OF 70% FOR THE SEEDED AREAS. CONTRACTOR SHALL DETERMINE ALL RATES OF APPLICATION NECESSARY TO PRODUCE THE REQUIRED STAND OF GRASS, AND SHALL FOLLOW THE APPLICATION PROCEDURES AS SPECIFIED HEREIN. THE CONTRACTOR MAY INCLUDE QUANTITIES OF RYE GRAIN AND MILLET IN SCHEDULE 1 AND 3 IN ORDER TO ESTABLISH QUICK


GROUND COVER FOR EROSION CONTROL PURPOSES.					
SEEDING SCHEDULE FOR TEMPORARY VEGETATION					
SCHEDULE NO.	COMMON NAME OF SEED ACRE (LBS.) DATES				
1	ANNUAL SUDAN GRASS (SWEET OR TIFF)	40	APRIL 1- AUGUST 15		
2 BROWN TOP MILLET 50 APRIL 1- AUGUST 15					
3	RYE GRAIN	55	AUGUST 16- MARCH 31		


OAT GRAIN IS TO BE ADDED TO ALL SCHEDULES, IF SEEDING DATE IS BETWEEN MARCH 1 AND APRIL 16, AT THE RATE OF 10 POUNDS PER ACRE.

THE CONTRACTOR SHALL OBTAIN A SATISFACTORY STAND OF VEGETATION THAT IS CAPABLE OF EROSION CONTROL. CONTRACTOR SHALL DETERMINE ALL RATES OF APPLICATION NECESSARY TO PRODUCE THE REQUIRED RESULTS. THE TEMPORARY VEGETATION SHALL PROVIDE MINIMUM DENSITY COVERAGE OF 70% OF THE SEEDED AREA. CONSTRUCTION SEQ

- 1. CONTRACTOR TO LOCATE ALL IMMEDIATELY ADJACENT TO P
- INSTALL CONSTRUCTION ENTRA
 INSTALL PERIMETER EROSION (
- ALL TREE PROTECTION.
- 4. DEMO EXISTING TRACK AND A

			EROSION CONTROL LEGEND			
QUENCE:		S	YMBOL	PRACTICE	DESCRIPTION	
ALL EXISTING UTILITIES WITHIN AND D PROJECT AREA. NTRANCE.				INLET PROTECTION	A TEMPORARY SEDIMENT BARRIER LAID AROUND A STORM DRAIN INLET TO PREVENT SEDIMENT FROM ENTERING THE DRAINAGE SYSTEM.	
ON CONTROL DEVICES, INCLUDING		OP	œ	OUTLET PROTECTION	RIP RAP CHANNEL / BANK PLACED BELOW DRAINAGE OUTLETS TO REDUCE THE VELOCITY OF FLOW, EROSION, AND STABILIZE GRADES DOWNSTREAM OF OUTLET STRUCTURES.	
D APPURTENANCES.		CD	8	TEMPORARY CHECK DAM	RIP RAP BANK PLACED BELOW DRAINAGE OUTLETS TO REDUCE THE VELOCITY OF FLOW, EROSION AND STABILIZE GRADES DOWN STREAM OF DRAINAGE OUTLETS.	
		SF	-0	SILT FENCE	A TEMPORARY STRUCTURE USED TO SLOW THE VELOCITY OF RUN-OFF, CAUSE SEDIMENT DEPOSITION AT THE STRUCTURE, AND FILTER SEDIMENT FROM RUN-OFF.	
		(SF ₂)	-8	DOUBLE ROW SILT FENCE	A TEMPORARY STRUCTURE USED TO SLOW THE VELOCITY OF RUN-OFF, CAUSE SEDIMENT DEPOSITION AT THE STRUCTURE, AND FILTER SEDIMENT FROM RUN-OFF.	
		CL-		CONSTRUCTION LIMITS	A DEFINED AREA THAT ALL LAND DISTURBANCE WILL OCCUR DURING CONSTRUCTION.	
		ECB		PERMANENT EROSION CONTROL MATTING (HIGH PERFORMANCE TRM PYRAMAT BY SI GEOSOLUTIONS OR EQUAL)	A PERMANENT REINFORCEMENT MAT TO PREVENT SOIL EROSION AND MAINTAIN PERMANENT GROUND COVER.	
		[Ds3	DISTURBED AREA STABILIZATION (WITH TEMPORARY VEGETATION)	ESTABLISHING PERMANENT VEGETATIVE COVER SUCH AS TREES, SHRUBS VINES, GRASSES, SOD, OR LEGUMES ON DISTURBED AREAS.	
		ST		SEDIMENT TUBE	SEDIMENT TUBE PLACED IN EXISTING OR PROPOSED DITCH SECTIONS TO REDUCE THE VELOCITY OF FLOW, EROSION AND STABILIZE GRADES DOWN STREAM OR DRAINAGE OUTLETS.	
		CE		CONSTRUCTION ENTRANCE	A STONE STABILIZED PAD LOCATED AT ANY POINT THAT TRAFFIC WILL BE LEAVING A CONSTRUCTION SITE TO A PUBLIC RIGHT-OF-WAY, STREET, ALLEY, SIDEWALK, OR PARKING PLOT WHICH WILL REDUCE OR ELIMINATE THE TRANSPORT OF MUD FROM THE CONSTRUCTION SITE.	
				ala da serie da serie En esta serie da serie		
			concessions building		In the second se	






- 1. INCLUDES RURAL AREAS ADJACENT TO WELL-DEVELOPED LAWNS. 2. NOT REQUIRED ON SHOULDERS, MEDIANS, ETC.., AND SLOPES UNDER
- 5 FEET IN HEIGHT. 3. GIANT BERMUDA SEED, INCLUDING NK-37, SHALL NOT BE USED.
- 4. RESEEDING CRIMSON CLOVER SHALL BE INOCULATED IN ACCORDANCE WITH SUBSECTION 810.05.
- DO NOT PLANT CLOVER IN MEDIANS OR IN RURAL AREAS ADJACENT TO WELL-DEVELOPED LAWNS. 5. PENSACOLA BAHIA SHALL BE ALLOWED ONLY AS SHOWN IN SEEDING SCHEDULES 3 AND 4 AT THE
- RATE OF 50 POUNDS PER ACRE ONLY WHEN SEEDING PIT AREAS THAT ARE GOVERNED BY THE SOUTH CAROLINA MINING ACT. OTHERWISE, DO NOT INCLUDE BAHIA SEED IN THE MIX.
- 6. THE CONTRACTOR SHALL OBTAIN A SATISFACTORY STAND OF PERENNIAL VEGETATION WHOSE ROOT SYSTEM SHALL BE DEVELOPED SUFFICIENTLY TO SURVIVE DRY PERIODS AND WINTER WEATHER, AND BE CAPABLE OF RE-ESTABLISHMENT IN THE SPRING. THE PERENNIAL VEGETATIVE COVER SHALL HAVE A MINIMUM COVERAGE DENSITY OF 70% FOR THE SEEDED AREAS. CONTRACTOR SHALL DETERMINE ALL RATES OF APPLICATION NECESSARY TO PRODUCE THE REQUIRED STAND OF GRASS, AND SHALL FOLLOW THE APPLICATION PROCEDURES AS SPECIFIED HEREIN.


7.	GIANT BERMUDA SEED, INCLUDING NK-37, SHALL NOT BE USED.

SEEDING SCHEDULE FOR TEMPORARY VEGETATION Ds3					
SCHEDULE NO.	COMMON NAME OF SEED (LBS.) DATE				
1	COMMON BERMUDA 210 (HULLED)		MARCH 16 TO		
	TALL FESCUE	140	AUG. 31		
2	COMMON BERMUDA (UNHULLED)	175	SEPT. 1 TO		
	ANNUAL RYEGRASS	175	MARCH 15		

NOTES:

THE CONTRACTOR SHALL OBTAIN A SATISFACTORY STAND OF PERENNIAL VEGETATION WHOSE ROOT SYSTEM SHALL BE DEVELOPED SUFFICIENTLY TO SURVIVE DRY PERIODS AND WINTER WEATHER, AND BE CAPABLE OF RE-ESTABLISHMENT IN THE SPRING. THE PERENNIAL VEGETATIVE COVER SHALL HAVE A MINIMUM COVERAGE DENSITY OF 70% FOR THE SEEDED AREAS. CONTRACTOR SHALL DETERMINE ALL RATES OF APPLICATION NECESSARY TO PRODUCE THE REQUIRED STAND OF GRASS, AND SHALL FOLLOW THE APPLICATION PROCEDURES AS SPECIFIED HEREIN.





NOTES: 1 INCLUDES RURAL AREAS ADJACENT TO WELL-DEVELOPED LAWNS.

- 2 NOT REQUIRED ON SHOULDERS, MEDIANS, ECT., AND SLOPES UNDER 5 FEET IN HEIGHT
- 3 GIANT BERMUDA SEED, INCLUDING NK-37, SHALL NOT BE USED. 4 RESEEDING CRIMSON CLOVER SHALL BE INOCULATED IN ACCORDANCE WITH SUBSECTION 810.05. DO NOT PLANT CLOVER IN MEDIANS OR IN
- RURAL AREAS ADJACENT TO WELL-DEVELOPED LAWNS. 5 PENSACOLA BAHIA SHALL BE ALLOWED ONLY AS SHOWN IN SEEDING SCHEDULES 3 AND 4 AT THE RATE OF 50 POUNDS PER ACRE ONLY WHEN SEEDING PIT AREAS THAT ARE GOVERNED BY THE SOUTH CAROLINA

MINING ACT. OTHERWISE, DO NOT INCLUDE BAHIA SEED IN THE MIX. THE CONTRACTOR SHALL OBTAIN A SATISFACTORY STAND OF PERENNIAL VEGETATION WHOSE ROOT SYSTEM SHALL BE DEVELOPED SUFFICIENTLY TO SURVIVE DRY PERIODS AND WINTER WEATHER, AND BE CAPABLE OF RE-ESTABLISHMENT IN THE SPRING. THE PERENNIAL VEGETATIVE COVER SHALL HAVE A MINIMUM COVERAGE DENSITY OF 70% FOR THE SEEDED AREAS. CONTRACTOR SHALL DETERMINE ALL RATES OF APPLICATION NECESSARY TO PRODUCE THE REQUIRED STAND OF GRASS, AND SHALL FOLLOW THE APPLICATION PROCEDURES AS SPECIFIED HEREIN.

THE CONTRACTOR MAY INCLUDE QUANTITIES OF RYE GRAIN AND MILLET IN SCHEDULE 1 AND 3 IN ORDER TO ESTABLISH QUICK

GROUND COVER FOR EROSION CONTROL PURPOSES.						
SEEDING SCHEDULE FOR TEMPORARY VEGETATION						
SCHEDULE NO.	COMMON NAME OF SEED RATE PER PLANTING ACRE (LBS.) DATES					
1	ANNUAL SUDAN GRASS (SWEET OR TIFF)	40	APRIL 1- AUGUST 15			
2 BROWN TOP MILLET 50 APRIL 1- AUGUST 15						
3	RYE GRAIN	55	AUGUST 16- MARCH 31			

OAT GRAIN IS TO BE ADDED TO ALL SCHEDULES, IF SEEDING DATE IS BETWEEN MARCH 1 AND APRIL 16, AT THE RATE OF 10 POUNDS PER ACRE.

THE CONTRACTOR SHALL OBTAIN A SATISFACTORY STAND OF VEGETATION THAT IS CAPABLE OF EROSION CONTROL. CONTRACTOR SHALL DETERMINE ALL RATES OF APPLICATION NECESSARY TO PRODUCE THE REQUIRED RESULTS. THE TEMPORARY VEGETATION SHALL PROVIDE MINIMUM DENSITY COVERAGE OF 70% OF THE SEEDED AREA.

CONSTRUCTION S

- 1. EXCAVATE END ZONE TF 2. INSTALL UNDER DRAINAG 3. FINE GRADE TRACK AND 4. PAVE TRACK AND INSTAL 5. PAINT TRACK LINES AND
- 6. GRADE AND SEED PERIM
- 7. FINAL STABILIZATION OF 8. PER SEEDING SCHEDULE
- PROPER GROUND COVER 9. UPON APPROVAL BY HOR EROSION CONTROL DEVI

irrig. cntl. valve and water valve M Q fire hyd. w/ water valve Δ· Ĺ. . Z ... j . (IP) EX. CATCH BASIN RIM=40.44' INV. IN=34.20' (24") INV OUT=34 07' (24") SUMP=31.4 ····· _____ chain link fence (typ.) \sim \longrightarrow ~~~~ irrig. cntl. valve

football

(CL)


(CL)


bleachers

 $\overline{}$

		EROSION CONTROL LEGEND				
SEQUENCE:	SYMBOL	PRACTICE	DESCRIPTION			
TRACK EXTENSION AREA.	STWDUL	FRACTICE	DESCRIPTION			
NAGE SYSTEM.		INLET PROTECTION	A TEMPORARY SEDIMENT BARRIER LAID AROUND A STORM DRAIN INLET			
ND INFIELD AREAS.			TO PREVENT SEDIMENT FROM ENTERING THE DRAINAGE SYSTEM.			
TALL SYNTHETIC SURFACING.			RIP RAP CHANNEL / BANK PLACED BELOW DRAINAGE OUTLETS TO REDUC			
ND FINISH REMAINING SITE IMPROVEMENTS.		OUTLET PROTECTION	THE VELOCITY OF FLOW, EROSION, AND STABILIZE GRADES DOWNSTREAD OF OUTLET STRUCTURES.			
RIMETER TIE IN POINTS.						
OF ALL DENUDED AREAS.		TEMPORARY CHECK DAM	RIP RAP BANK PLACED BELOW DRAINAGE OUTLETS TO REDUCE THE VELOCITY OF FLOW, EROSION AND STABILIZE GRADES DOWN STREAM			
JLE, WATER AND MAINTAIN TO INSURE VERAGE.			OF DRAINAGE OUTLETS.			
			A TEMPORARY STRUCTURE USED TO SLOW THE VELOCITY OF RUN-OFF,			
IORRY COUNTY, REMOVE ALL TEMPORARY EVICES.		SILT FENCE	CAUSE SEDIMENT DEPOSITION AT THE STRUCTURE, AND FILTER SEDIME FROM RUN-OFF.			
	(SF ₂)	DOUBLE ROW SILT FENCE	A TEMPORARY STRUCTURE USED TO SLOW THE VELOCITY OF RUN-OFF, CAUSE SEDIMENT DEPOSITION AT THE STRUCTURE, AND FILTER SEDIMEN FROM RUN-OFF.			
		CONSTRUCTION LIMITS	A DEFINED AREA THAT ALL LAND DISTURBANCE WILL OCCUR DURING CONSTRUCTION.			
		PERMANENT EROSION	A PERMANENT REINFORCEMENT MAT TO PREVENT SOIL EROSION			
	ЕСВ)	CONTROL MATTING (HIGH PERFORMANCE TRM PYRAMAT	AND MAINTAIN PERMANENT GROUND COVER.			
		BY SI GEOSOLUTIONS OR EQUAL)				
	Ds3	DISTURBED AREA STABILIZATION	ESTABLISHING PERMANENT VEGETATIVE COVER SUCH AS TREES, SHRUB VINES, GRASSES, SOD, OR LEGUMES ON DISTURBED AREAS.			
		(WITH TEMPORARY VEGETATION)	VINES, GIAGGES, SOD, OK LEGUINES UN DISTURBED AREAS.			
			SEDIMENT TUBE PLACED IN EXISTING OR PROPOSED DITCH SECTIONS			
	(ST) ////	SEDIMENT TUBE	TO REDUCE THE VELOCITY OF FLOW, EROSION AND STABILIZE GRADES DOWN STREAM OR DRAINAGE OUTLETS.			
	CE SSS	CONSTRUCTION ENTRANCE	A STONE STABILIZED PAD LOCATED AT ANY POINT THAT TRAFFIC WILL BE LEAVING A CONSTRUCTION SITE TO A PUBLIC RIGHT-OF-WAY, STREET,			
			ALLEY, SIDEWALK, OR PARKING PLOT WHICH WILL REDUCE OR ELIMINATE THE TRANSPORT OF MUD FROM THE CONSTRUCTION SITE.			

EX. CATCH BASIN RIM=39.43' INV. OUT=34.29' (24") SUMP=31.44'






- INCLUDES RURAL AREAS ADJACENT TO WELL-DEVELOPED LAWNS.
 NOT REQUIRED ON SHOULDERS, MEDIANS, ETC.., AND SLOPES UNDER
- 5 FEET IN HEIGHT.
- 3. GIANT BERMUDA SEED, INCLUDING NK-37, SHALL NOT BE USED.
- 4. RESEEDING CRIMSON CLOVER SHALL BE INOCULATED IN ACCORDANCE WITH SUBSECTION 810.05. DO NOT PLANT CLOVER IN MEDIANS OR IN RURAL AREAS ADJACENT TO WELL-DEVELOPED LAWNS.
- 5. PENSACOLA BAHIA SHALL BE ALLOWED ONLY AS SHOWN IN SEEDING SCHEDULES 3 AND 4 AT THE RATE OF 50 POUNDS PER ACRE ONLY WHEN SEEDING PIT AREAS THAT ARE GOVERNED BY THE SOUTH CAROLINA MINING ACT. OTHERWISE, DO NOT INCLUDE BAHIA SEED IN THE MIX.
- THE CONTRACTOR SHALL OBTAIN A SATISFACTORY STAND OF PERENNIAL VEGETATION WHOSE ROOT SYSTEM SHALL BE DEVELOPED SUFFICIENTLY TO SURVIVE DRY PERIODS AND WINTER WEATHER, AND BE CAPABLE OF RE-ESTABLISHMENT IN THE SPRING. THE PERENNIAL VEGETATIVE COVER SHALL HAVE A MINIMUM COVERAGE DENSITY OF 70% FOR THE SEEDED AREAS. CONTRACTOR SHALL DETERMINE ALL RATES OF APPLICATION NECESSARY TO PRODUCE THE REQUIRED STAND OF GRASS, AND SHALL FOLLOW THE APPLICATION PROCEDURES AS SPECIFIED HEREIN.
 GIANT BERMUDA SEED. INCLUDING NK-37. SHALL NOT BE LISED.

GIANT BERMUDA SEED, INCLUDING NK-37, SF	HALL NOT BE USED.

SEEDING SCHEDULE FOR TEMPORARY VEGETATION Ds3					
SCHEDULE NO.	COMMON NAME OF SEED	PLANTING DATES			
1	COMMON BERMUDA (HULLED)	210	MARCH 16 TO		
	TALL FESCUE	140	AUG. 31		
2	COMMON BERMUDA (UNHULLED)	175	SEPT. 1 TO		
	ANNUAL RYEGRASS	175	MARCH 15		

NOTES:

THE CONTRACTOR SHALL OBTAIN A SATISFACTORY STAND OF PERENNIAL VEGETATION WHOSE ROOT SYSTEM SHALL BE DEVELOPED SUFFICIENTLY TO SURVIVE DRY PERIODS AND WINTER WEATHER, AND BE CAPABLE OF RE-ESTABLISHMENT IN THE SPRING. THE PERENNIAL VEGETATIVE COVER SHALL HAVE A MINIMUM COVERAGE DENSITY OF 70% FOR THE SEEDED AREAS. CONTRACTOR SHALL DETERMINE ALL RATES OF APPLICATION NECESSARY TO PRODUCE THE REQUIRED STAND OF GRASS, AND SHALL FOLLOW THE APPLICATION PROCEDURES AS SPECIFIED HEREIN.



SEEDING SCHEDULE FOR PERMANENT VEGETATION						
HEDULE NO.	COMMON NAME OF SEED	RURAL RATE	URBAN RATE ¹	PLANTING DATES		
3 ⁵	COMMON BERMUDA (HULLED) ³	30	30	MARCH 1		
	WEEPING LOVEGRASS ²	10	10	TO		
	SERICEA LESPEDEZA (SCARIFIED) ²	50	50	AUG. 14		
	COMMON BERMUDA (UNHULLED) ³	40	40			
	WEEPING LOVEGRASS ²	10	10			
4 ⁵	SERICEA LESPEDEZA (UNHULLED, UNSCARIFIED) ²	80	80	AUG. 5 TO FEB. 28		
	RESEEDING CRIMSON CLOVER ⁴	20	0			
	RYE GRAIN	20	0			

2020\20095E - HORRY COUNTY SCHOOLS PHASE 2 TRACK AND FIELD IMPROVEMENTS\E\NORTH MYRTLE BEACH\20095E-NORTH MYRTLE TRACK ERO.

NOTES: 1 INCLUDES RURAL AREAS ADJACENT TO WELL-DEVELOPED LAWNS.

- 2 NOT REQUIRED ON SHOULDERS, MEDIANS, ECT., AND SLOPES UNDER 5 FEET IN HEIGHT
- 3 GIANT BERMUDA SEED, INCLUDING NK-37, SHALL NOT BE USED.
 4 RESEEDING CRIMSON CLOVER SHALL BE INOCULATED IN ACCORDANCE WITH SUBSECTION 810.05. DO NOT PLANT CLOVER IN MEDIANS OR IN

RURAL AREAS ADJACENT TO WELL-DEVELOPED LAWNS.

5 PENSACOLA BAHIA SHALL BE ALLOWED ONLY AS SHOWN IN SEEDING SCHEDULES 3 AND 4 AT THE RATE OF 50 POUNDS PER ACRE ONLY WHEN SEEDING PIT AREAS THAT ARE GOVERNED BY THE SOUTH CAROLINA

MINING ACT. OTHERWISE, DO NOT INCLUDE BAHIA SEED IN THE MIX. THE CONTRACTOR SHALL OBTAIN A SATISFACTORY STAND OF PERENNIAL VEGETATION WHOSE ROOT SYSTEM SHALL BE DEVELOPED SUFFICIENTLY TO SURVIVE DRY PERIODS AND WINTER WEATHER, AND BE CAPABLE OF RE-ESTABLISHMENT IN THE SPRING. THE PERENNIAL VEGETATIVE COVER SHALL HAVE A MINIMUM COVERAGE DENSITY OF 70% FOR THE SEEDED AREAS. CONTRACTOR SHALL DETERMINE ALL RATES OF APPLICATION NECESSARY TO PRODUCE THE REQUIRED STAND OF GRASS, AND SHALL FOLLOW THE APPLICATION PROCEDURES AS SPECIFIED HEREIN. THE CONTRACTOR MAY INCLUDE QUANTITIES OF RYE GRAIN AND MILLET IN SCHEDULE 1 AND 3 IN ORDER TO ESTABLISH QUICK


GROUND COVER FOR EROSION CONTROL PURPOSES.										
SEEDING SCHEDULE FOR TEMPORARY VEGETATION										
SCHEDULE NO.			PLANTING DATES							
1	1 ANNUAL SUDAN GRASS (SWEET OR TIFF)		APRIL 1- AUGUST 15							
2	BROWN TOP MILLET	50	APRIL 1- AUGUST 15							
3	3 RYE GRAIN		AUGUST 16- MARCH 31							


OAT GRAIN IS TO BE ADDED TO ALL SCHEDULES, IF SEEDING DATE IS BETWEEN MARCH 1 AND APRIL 16, AT THE RATE OF 10 POUNDS PER ACRE.


THE CONTRACTOR SHALL OBTAIN A SATISFACTORY STAND OF VEGETATION THAT IS CAPABLE OF EROSION CONTROL. CONTRACTOR SHALL DETERMINE ALL RATES OF APPLICATION NECESSARY TO PRODUCE THE REQUIRED RESULTS. THE TEMPORARY VEGETATION SHALL PROVIDE MINIMUM DENSITY COVERAGE OF 70% OF THE SEEDED AREA. CONSTRUCTIO

- EXCAVATE END ZOI
 INSTALL UNDER DR
- 3. FINE GRADE TRACK
- PAVE TRACK AND IN
 PAINT TRACK LINES
- GRADE AND SEED F
 FINAL STABILIZATIO
- 8. PER SEEDING SCHE PROPER GROUND (
- 9. UPON APPROVAL B EROSION CONTROL

	_	EROSION CONTROL LEGEND							
ON SEQUENCE:	SYMBOL	PRACTICE	DESCRIPTION						
DNE TRACK EXTENSION AREA. RAINAGE SYSTEM.		INLET PROTECTION	A TEMPORARY SEDIMENT BARRIER LAID AROUND A STORM DRAIN INLET TO PREVENT SEDIMENT FROM ENTERING THE DRAINAGE SYSTEM.						
K AND INFIELD AREAS. NSTALL SYNTHETIC SURFACING.	OP W	OUTLET PROTECTION	RIP RAP CHANNEL / BANK PLACED BELOW DRAINAGE OUTLETS TO REDUC THE VELOCITY OF FLOW, EROSION, AND STABILIZE GRADES DOWNSTREA OF OUTLET STRUCTURES.						
S AND FINISH REMAINING SITE IMPROVEMENTS. PERIMETER TIE IN POINTS. ON OF ALL DENUDED AREAS.		TEMPORARY CHECK DAM	RIP RAP BANK PLACED BELOW DRAINAGE OUTLETS TO REDUCE THE VELOCITY OF FLOW, EROSION AND STABILIZE GRADES DOWN STREAM OF DRAINAGE OUTLETS.						
IEDULE, WATER AND MAINTAIN TO INSURE COVERAGE.	SF	SILT FENCE	A TEMPORARY STRUCTURE USED TO SLOW THE VELOCITY OF RUN-OFF, CAUSE SEDIMENT DEPOSITION AT THE STRUCTURE, AND FILTER SEDIME FROM RUN-OFF.						
BY HORRY COUNTY, REMOVE ALL TEMPORARY DL DEVICES.	SF2 =	DOUBLE ROW SILT FENCE	A TEMPORARY STRUCTURE USED TO SLOW THE VELOCITY OF RUN-OFF, CAUSE SEDIMENT DEPOSITION AT THE STRUCTURE, AND FILTER SEDIME FROM RUN-OFF.						
	CL — — —	CONSTRUCTION LIMITS	A DEFINED AREA THAT ALL LAND DISTURBANCE WILL OCCUR DURING CONSTRUCTION.						
	ECB XXXXX	PERMANENT EROSION CONTROL MATTING (HIGH PERFORMANCE TRM PYRAMAT BY SI GEOSOLUTIONS OR EQUAL)	A PERMANENT REINFORCEMENT MAT TO PREVENT SOIL EROSION AND MAINTAIN PERMANENT GROUND COVER.						
	Ds3	DISTURBED AREA STABILIZATION (WITH TEMPORARY VEGETATION)	ESTABLISHING PERMANENT VEGETATIVE COVER SUCH AS TREES, SHRUE VINES, GRASSES, SOD, OR LEGUMES ON DISTURBED AREAS.						
	ST 1/1/	SEDIMENT TUBE	SEDIMENT TUBE PLACED IN EXISTING OR PROPOSED DITCH SECTIONS TO REDUCE THE VELOCITY OF FLOW, EROSION AND STABILIZE GRADES DOWN STREAM OR DRAINAGE OUTLETS.						
	CE	CONSTRUCTION ENTRANCE	A STONE STABILIZED PAD LOCATED AT ANY POINT THAT TRAFFIC WILL BE LEAVING A CONSTRUCTION SITE TO A PUBLIC RIGHT-OF-WAY, STREET, ALLEY, SIDEWALK, OR PARKING PLOT WHICH WILL REDUCE OR ELIMINATE THE TRANSPORT OF MUD FROM THE CONSTRUCTION SITE.						
	ight o		Image: Barbara and State						







- 3. IF NECESSARY, SLOPES, WHICH EXCEED EIGHT (8) VERTICAL FEET SHOULD BE STABILIZED WITH SYNTHETIC OR VEGETATIVE MATS, IN ADDITION TO HYDROSEEDING. IT MAY BE NECESSARY TO INSTALL TEMPORARY SLOPE DRAINS DURING CONSTRUCTION. TEMPORARY BERMS MAY BE NEEDED UNTIL THE SLOPE IS BROUGHT TO GRADE.
- 4. STABILIZATION MEASURES SHALL BE INITIATED AS SOON AS PRACTICABLE IN PORTIONS OF THE SITE WHERE CONSTRUCTION ACTIVITIES HAVE TEMPORARILY OR PERMANENTLY CEASED, BUT IN NO CASE MORE THAN - WHERE STABILIZATION BY THE 14TH DAY IS PRECLUDED BY SNOW COVER OR FROZEN GROUND CONDITIONS
- WHERE CONSTRUCTION ACTIVITY ON A PORTION OF THE SITE IS TEMPORARILY CEASED, AND EARTH-DISTURBING ACTIVITIES WILL BE RESUMED WITHIN 14 DAYS, TEMPORARY STABILIZATION MEASURES DO NOT HAVE TO BE
- 5. ALL SEDIMENT AND EROSION CONTROL DEVICES SHALL BE INSPECTED EVERY CALENDAR WEEK. IF PERIODIC INSPECTION OR OTHER INFORMATION INDICATES THAT A BMP HAS BEEN INAPPROPRIATELY OR INCORRECTLY INSTALLED, THE PERMITTEE MUST ADDRESS THE NECESSARY REPLACEMENT OR MODIFICATION REQUIRED TO
- 6. PROVIDE SILT FENCE AND/OR OTHER CONTROL DEVICES. AS MAY BE REQUIRED. TO CONTROL SOIL EROSION DURING UTILITY CONSTRUCTION. ALL DISTURBED AREAS SHALL BE CLEANED, GRADED AND STABILIZED WITH GRASSING IMMEDIATELY AFTER THE UTILITY INSTALLATION. FILL, COVER AND TEMPORARY SEEDING AT THE END OF EACH DAY ARE RECOMMENDED. IF WATER IS ENCOUNTERED WHILE TRENCHING, THE WATER SHOULD BE FILTERED TO REMOVE ANY
- COMPLETION OF ALL CONSTRUCTION ACTIVITIES AND ALL DISTURBED AREAS HAVE BEEN STABILIZED. ADDITIONAL CONTROL DEVICES MAY BE REQUIRED DURING CONSTRUCTION IN ORDER TO CONTROL EROSION AND/OR OFF SITE SEDIMENTATION. ALL TEMPORARY CONTROL DEVICES SHALL BE REMOVED ONCE CONSTRUCTION IS COMPLETE AND
- FROM CONSTRUCTION AREAS AND THE GENERATION OF DUST. THE CONTRACTOR SHALL DAILY REMOVE MUD/SOIL
- INDIVIDUAL LOT CONSTRUCTION. INDIVIDUAL PROPERTY OWNERS SHALL FOLLOW THESE PLANS DURING CONSTRUCTION OR OBTAIN APPROVAL OF AN INDIVIDUAL PLAN IN ACCORDANCE WITH S.C. REG. 72-300 ET SEQ. AND SCR 100000.
- 10. TEMPORARY DIVERSION BERMS AND/OR DITCHES WILL BE PROVIDED AS NEEDED DURING CONSTRUCTION TO PROTECT WORK AREAS FROM UPSLOPE RUNOFF AND/OR TO DIVERT SEDIMENT-LADEN WATER TO APPROPRIATE TRAPS OR STABLE
- 11. ALL WATERS OF THE STATE (WoS), INCLUDING WETLANDS, ARE TO BE FLAGGED OR OTHERWISE CLEARLY MARKED IN THE FIELD. A DOUBLE ROW OF SILT FENCE IS TO BE INSTALLED IN ALL AREAS WHERE A 50 FOOT BUFFER CANNOT BE MAINTAINED BETWEEN THE DISTURBED AREA AND ALL WoS. A 10 FOOT BUFFER SHOULD BE MAINTAINED BETWEEN THE
- 12. LITTER, CONSTRUCTION DEBRIS, OILS, FUELS AND BUILDING PRODUCTS WITH SIGNIFICANT POTENTIAL FOR IMPACT (SUCH AS STOCKPILES OF FRESHLY TREATED LUMBER) AND CONSTRUCTION CHEMICALS THAT COULD BE EXPOSED TO STORM WATER MUST BE PREVENTED FROM BECOMING A POLLUTANT SOURCE IN STORM WATER DISCHARGES
- SITE OR A NEARBY LOCATION EASILY ACCESSIBLE DURING NORMAL BUSINESS HOURS. FROM THE DATE OF COMMENCEMENT OF CONSTRUCTION ACTIVITIES TO THE DATE THAT FINAL STABILIZATION IS REACHED.
- 14. INITIATE STABILIZATION MEASURES ON ANY EXPOSED STEEP SLOPE (3H:1V OR GREATER) WHERE LAND DISTURBING ACTIVITIES HAVE PERMANENTLY OR TEMPORARILY CEASED, AND WILL NOT RESUME FOR A PERIOD OF 7 CALENDAR DAYS.
- 16. MINIMIZE THE DISCHARGE OF POLLUTANTS FROM EQUIPMENT AND VEHICLE WASHING. WHEEL WASH WATER. AND OTHER WASH WATERS. WASH WATERS MUST BE TREATED IN A SEDIMENT BASIN OR ALTERNATIVE CONTROL THAT
- 17. MINIMIZE THE DISCHARGE OF POLLUTANTS FROM DEWATERING OF TRENCHES AND EXCAVATED AREAS. THESE DISCHARGES ARE TO BE ROUTED THROUGH APPROPRIATE BMPs (SEDIMENT BASIN, FILTER BAG, ETC.).
- WASTEWATER FROM WASHOUT OF CONCRETE, UNLESS MANAGED BY AN APPROPRIATE CONTROL;
- 19. AFTER CONSTRUCTION ACTIVITIES BEGIN, INSPECTIONS MUST BE CONDUCTED AT A MINIMUM OF AT LEAST ONCE EVERY CALENDAR WEEK AND MUST BE CONDUCTED UNTIL FINAL STABILIZATION IS REACHED ON ALL AREAS OF
- 20. IF EXISTING BMPs NEED TO BE MODIFIED OR IF ADDITIONAL BMPs ARE NECESSARY TO COMPLY WITH THE REQUIREMENTS OF THIS PERMIT AND / OR SC'S WATER QUALITY STANDARDS, IMPLEMENTATION MUST BE COMPLETED BEFORE THE NEXT STORM EVENT WHENEVER PRACTICABLE. IF IMPLEMENTATION BEFORE THE NEXT STORM EVENT IS IMPRACTICABLE. THE SITUATION MUST BE DOCUMENTED IN THE SWPPP AND ALTERNATIVE BMPs MUST BE IMPLEMENTED AS SOON AS
- 21. A PRE-CONSTRUCTION CONFERENCE MUST BE HELD FOR EACH CONSTRUCTION SITE WITH AN APPROVED ON-SITE SWPPP PRIOR TO THE IMPLEMENTATION OF CONSTRUCTION ACTIVITIES. FOR NON-LINEAR PROJECTS THAT DISTURB 10 ACRES OR MORE THIS CONFERENCE MUST BE HELD ON-SITE UNLESS THE DEPARTMENT HAS
- 22. THE CONTRACTOR SHALL BE RESPONSIBLE FOR MAINTAINING ALL SILT BARRIERS AND SEDIMENT CONTROL
- 23. EROSION CONTROL DEVICES MUST BE INSTALLED IMMEDIATELY AFTER LAND DISTURBANCE OCCURS. THE LOCATION OF SOME OF THE CONTROL DEVICES MAY BE ALTERED FROM THAT SHOWN ON THE APPROVED PLANS. IF DRAINAGE PATTERNS DURING CONSTRUCTION VARY FROM THE FINAL DRAINAGE PATTERNS. IT SHALL BE THE CONTRACTORS RESPONSIBILITY TO PROVIDE SOIL EROSION CONTROL FOR ALL DRAINAGE PATTERNS DURING ALL STAGES OF CONSTRUCTION. ALL INADEQUACIES IN SOIL EROSION CONTROL DURING ANY PHASE OF CONSTRUCTION
- 24. THE CONTRACTOR SHALL MAINTAIN ALL EROSION CONTROL MEASURES UNTIL PERMANENT VEGETATION HAS BEEN ESTABLISHED. THE CONTRACTOR SHALL INSPECT EROSION CONTROL MEASURES AT THE END OF EACH WORKING DAY
- PLANS OR AS DIRECTED BY THE ENGINEER AND/OR OCRM WILL RESULT IN ALL WORK ON THE CONSTRUCTION SITE BEING STOPPED UNTIL PROPER CORRECTIVE MEASURES HAVE BEEN MET, AS REQUIRED AND/OR DIRECTED. 26. ALL LAND DISTURBING ACTIVITIES REQUIRES COMPLIANCE UNDER THE NPDES GENERAL PERMIT FOR STORM
- WATER DISCHARGES FROM THE CONSTRUCTION ACTIVITIES (PERMIT NO. SCR100000). ANY NONCOMPLIANCE WITH THESE REGULATIONS IS A VIOLATION OF THE FEDERAL CLEAN WATER ACT AND MAY REQUIRE ENFORCEMENT
- 27. CONTRACTOR SHALL PROVIDE A WATER TIGHT ENCLOSURE FOR STORAGE OF THE OCRM CERTIFIED PLANS AND INSPECTION REPORTS. ENCLOSURE SHALL BE LOCATED IN AN AREA ACCESSIBLE TO REGULATORY PERSONNEL.



- SNOW FENCE




A AC AF AFF/G AIC AT AUX AWG	ABBRE VIATIONS AMPERE ALTERNATING CURRENT AMPERE FRAME ABOVE FINISHED FLOOR/GRADE AMPERE INTERRUPTING CAPACITY AMPERE TRIP AUXILIARY AMERICAN WIRE GAUGE	OL P PNL PR PRI PWR Ø PT	OVERLOAD POLE(S) PANEL PAIR PRIMARY POWER PHASE PRESSURE TREATED
BTM BKR BLDG	BOTTOM BREAKER BUILDING	RECEPT RGS RLY RM	RECEPTACLE RIGID GALVANIZED STEEL RELAY ROOM
C CAB CB CIR CKT	CONDUIT CABINET CIRCUIT BREAKER CIRCUIT CIRCUIT	SEC SH SW	SECONDARY SHIELDED SWITCH
	CENTER LINE COMPANY COMMUNICATIONS CONNECTION, CONNECT	TEMP TB TYP	TEMPORARY/TEMPERATURE TERMINAL BOARD TYPICAL
CTRL CU	CONTROL COPPER	UON	UNLESS OTHERWISE NOTED
	DELTA_CONNECTION	V VA	VOLT, VOLTS VOLT-AMPERES
DIA DISC DIST	DIAMETER DISCONNECT DISTRIBUTION	W W/	WATT, WIRE WITH
DIV DN	DIVISION DOWN	WP	WEATHERPROOF
DWG	DRAWING	XFMR/T	TRANSFORMER
EA EF EL	EACH EXHAUST FAN ELEVATION	Ϋ́	WYE CONNECTION
ELEC ENCL	ELECTRIC(AL) ENCLOSURE		DEVICES AND APPURTENANCES
EQUIP ETR	EQUIPMENT EXISTING TO REMAIN EXTERIOR	¶or a standard and a standard a stand A standard a s	EX RECEPTACLE
EXT F	FUSE(D)		- 20 AMP DUPLEX RECEPTACLES UNDER SINGLE COVER
r FC FIXT	FOOTCANDLES FIXTURE		TION BOX
FLR FT	FLOOR FOOT (FEET)		RACEWAYS
FUT	FUTURÈ		
G, GND GALV	GROUND GALVANIZE(D)		- CONDUIT TURNING UP
GC GFI GFP	GENERAL CONTRACTOR GROUND FAULT CIRCUIT INTERRUPTER GROUND FAULT PROTECTION		- CONDUIT TURNING DOWN
HGT	HEIGHT	<u>PP-1</u> 1/3/5	- HOMERUN BACK TO PANEL (PANEL AND CIRCUITS INDICATED)
HPS HTR	HIGH PRESSURE SODIUM HEATER		CIRCUIT CONTINUED OR CONNECTED TO EQUIPMENT AS INDICATED
H∨ HW	HIGH VOLTAGE HOT WATER		UNDERGROUND CONDUIT
ID INCAND	IDENTIFY, IDENTIFICATION INCANDESCENT		POWER DISTRIBUTION EQUIPMENT
J-BOX JCT	JUNCTION BOX JUNCTION	_	URFACE MOUNTED BRANCH CIRCUIT PANELBOARD 208/120V, 1ø, 3W, UON AND HOLE
KCM/Kcmil KVA KW	THOUSAND CIRCULAR MILS KILO VOLT AMPERE KILOWATT		ONTROL RELAY PANEL
LGT LT(S) LED L	LIGHTING LIGHT(S) LIGHT EMITTING DIODE LOUVER	#	<u>GENERAL</u> NUMBER IN CIRCLE, WITH OR WITHOUT ARROW OR LEADER, REFER TO MATCHING NUMBERED CODED NOTE
MAX MCB MC MFR MH MECH MIN MLO MT MTD	MAXIMUM MAIN CIRCUIT BREAKER METAL CLAD CABLE MANUFACTURER METAL HALIDE MECHANICAL MINIMUM MAIN LUGS ONLY MOUNT MOUNTED	BY OTHE 2. ALL WOR	O CIVIL DRAWINGS FOR SYMBOLS ASSOCIATED WITH WORK, EQUIPMENT, ETC.
N NEC NF NL	NORTH NATIONAL ELECTRICAL CODE NON-FUSED NIGHT LIGHT	RUNS SH	RUNS SHOWN ARE DIAGRAMMATIC UON. EXACT LOCATION OF ALL CONDUIT HALL BE DETERMINED IN THE FIELD. COORDINATE INSTALLATIONS AND AVOID T WITH PIPING, DUCTWORK, ACCESS DOORS AND WORK BY OTHER TRADES.

4. GENERAL NOTES APPLY TO ALL ELECTRICAL CONTRACT DRAWINGS.


e: V:\PROJECTS\ANY\K5\36108\CADD_ACAD\E-004-36108.DWG ved: 2/23/2021 1:55:22 PM Plotted: 2/23/2021 2:27:25 PM Current User: Moisidis. Stelios LastSavedBv: NL No/#

NUMBER

			TOTAL_kVA ####					4				
1. E	XISTING POWER PANEL IS SQUARE D NQ SE EXISTING SPARE BREAKER.		####	####	####		####	####	####	1		
41 NOT	 -S:					ŀ						
	EXISTING HAND DRYER	30/3				ŀ				50/3		EXISTING F
35 37	EXISTING HAND DRYER	20/1				╞						
	EXISTING OUTLET	20/1				╞				60/2		EXISTING F
	EXISTING OUTLET	20/1				╞				20/1		EXISTING
	EXISTING OUTLET	20/1								20/1		EXISTING
	EXISTING OUTLET	20/1								20/1		EXIS
25	EXISTING OUTLET	20/1 20/1								20/1		EXIS
23	EXISTING OUTLET	20/1 20/1								20/1		EXISTING
21										20/1		EXISTING
19		30/2								20/1		EXISTING
17	EXISTING CONVENIENCE OUTLET	30/2				ľ				20/1		EXISTING CONVEN
15						╞				20/1		EXISTING CONVEN
13	EXISTING CONVENIENCE OUTLET	20/1 20/1				ŀ				20/1		EXISTING \
	EXISTING CONVENIENCE OUTLET	20/1 20/1								60/3		EXISTING
7 9	EXISTING FEED TO P-C1	100/2								60 /7		
5	EXISTING LIGHTING	20/1								20/1	MIDFIELD	AND FINISH LINE AND GAME CLC
3	EXISTING LIGHTING	20/1				Ī				20/1		EXISTING
1	EXISTING LIGHTING	20/1				ŀ				20/1		EXISTIN
CKT	LOAD DESCRIPTION	CB AMPS/ POLE	CONN LOAD KVA	CONN LOAD KVA	CONN LOAD KVA			CONN LOAD KVA	CONN LOAD KVA			LOAD DESCRIPTION
	SOURCE:	<u>CLOSURE</u> ?	-		PA						IRCUIT RATING	3:
	EXTERIOR WALL IN 1	NEMA 3R		FXI	STIN(NFR		MAINS:		120
	LOCATION:	?			PAN	IEL	ID	[VOLTS, P	HASE, WIRE:	<u>120</u>



NORTH MYRTLE HS ELECTRICAL SITE PLAN SCALE: 1" = 20'



CODED NOTES

1 I'' RGS CONDUIT WITH (2)#8 AND (1)#8G FOR MIDFIELD RECEPTACLE, FINISH LINE RECEPTACLE, AND GAME CLOCKS FROM EXISTING PANEL. CONDUIT TO RUN ALONG UNDERSIDE OF THE EXISTING BLEACHERS.

2 1" SCHEDULE 40 PVC CONDUIT WITH (2)#8 AND (1)#8G FOR MIDFIELD RECEPTACLE, FINISH LINE RECEPTACLES AND GAME CLOCKS.

 \bigcirc PROVIDE COMMUNICATION JUNCTION BOX (SEE DETAILS 1 AND 2 ON C-602).

(4) TRANSITION FROM ABOVE GROUND RGS TO CONDUIT BELOW GRADE SCHEDULE 40 PVC CONDUIT.

(5) 1 1/2" SCHEDULE 40 PVC CONDUIT WITH PULL STRING BETWEEN JUNCTION BOXES FOR INSTALLATION OF COMMUNICATION WIRING.

 \bigcirc PROVIDE JUNCTION BOX WITH GFCI RECEPTACLE (SEE DETAILS 1 & 2 ON C-602).

 $\overline{7}$ existing power panel.



