

ARLINGTON VIRGINIA



ENGINEER
DEPARTMENT OF ENVIRONMENTAL SERVICES

FACILITIES & ENGINEERING DIVISION
ENGINEERING BUREAU
2100 CLARENDON BOULEVARD, SUITE 813
ARLINGTON, VA 22201
PHONE: 703.228.3629 FAX: 703.228.3606
WWW.ARLINGTONVA.US

OWNER
DES/OSEM/WTRSHD

CONTRACTOR
TO BE DETERMINED

LOCATION MAP



ARLINGTON VIRGINIA

DEPARTMENT OF ENVIRONMENTAL SERVICES
FACILITIES & ENGINEERING DIVISION
ENGINEERING BUREAU
2100 CLARENDON BOULEVARD, SUITE 813
ARLINGTON, VA 22201
PHONE: 703.228.3629
FAX: 703.228.3606

COPYRIGHT © 2021 ARLINGTON COUNTY VIRGINIA - ALL RIGHTS RESERVED

SEAL



APPROVALS DATE

<i>Amy Pflaum</i>	08/04/22
QUALITY CONTROL ENGINEER	
<i>[Signature]</i>	8/5/22
CONSTRUCTION SECTION SUPERVISOR	
<i>[Signature]</i>	8/4/22
WATER, SEWER, STREETS BUREAU CHIEF	
<i>Dennis M. Leach</i>	08/03/22
TRANSPORTATION DIRECTOR	
<i>Jennifer Tastad</i>	08/17/22
PROJECT MANAGER	

REVISIONS DATE

CONSTRUCTION DRAWINGS FOR:

STREAM STABILIZATION DONALDSON RUN HEADWATERS

PROJECT NUMBER: S42D

GENERAL NOTES:

GENERAL CONSTRUCTION NOTES

- ALL CONSTRUCTION WORK FOR THIS PROJECT SHALL CONFORM TO THE ARLINGTON COUNTY DEPARTMENT OF ENVIRONMENTAL SERVICES, CONSTRUCTION STANDARDS AND SPECIFICATIONS, AND WHERE APPLICABLE THE VIRGINIA DEPARTMENT OF TRANSPORTATION (VDOT) ROAD AND BRIDGE SPECIFICATIONS, AND ROAD AND BRIDGE STANDARDS. THE LATEST EDITIONS OF EACH RELEVANT MANUAL SHALL BE USED.
- ALL CONSTRUCTION AND WORK ACTIVITIES SHALL COMPLY WITH THE VIRGINIA WORK AREA PROTECTION MANUAL AND ALL OTHER RELEVANT WORK SAFETY REQUIREMENTS, LATEST EDITIONS.
- THE CONTRACTOR SHALL IMMEDIATELY NOTIFY THE PROJECT OFFICER OF ANY DISCREPANCIES BETWEEN ACTUAL FIELD CONDITIONS AND THE APPROVED PLANS.
- THE CONTRACTOR SHALL CONTACT "MISS UTILITY" AT 811 FOR MARKING THE LOCATIONS OF EXISTING UNDERGROUND UTILITIES (i.e. WATER, SEWER, GAS, TELEPHONE, ELECTRIC, AND CABLE TV) AT LEAST 72 HOURS PRIOR TO ANY EXCAVATION OR CONSTRUCTION. THE CONTRACTOR IS REQUIRED TO IDENTIFY AND PROTECT ALL OTHER UTILITY LINES FOUND IN THE WORK SITE AREA BELONGING TO OTHER OWNERS THAT ARE NOT MEMBERS OF "MISS UTILITY". PRIVATE WATER, SEWER AND GAS LATERALS WILL NOT BE MARKED BY MISS UTILITY OR THE COUNTY. THE CONTRACTOR SHALL LOCATE AND PROTECT THESE SERVICES DURING CONSTRUCTION.
- THE CONTRACTOR SHALL BE RESPONSIBLE FOR LAYING OUT THE WORK AND SHALL RETAIN A PROFESSIONAL LAND SURVEYOR LICENSED IN THE COMMONWEALTH OF VIRGINIA TO PROVIDE ALL NECESSARY CONSTRUCTION LAYOUTS AND ESTABLISH ALL CONTROL LINES, GRADES, AND ELEVATION DURING CONSTRUCTION. THE CONTRACTOR SHALL SUBMIT A COPY OF ALL CUT SHEETS FOR REVIEW, PER THE SPECIFICATIONS. THE COST OF ALL NECESSARY SURVEYING SERVICES SHALL BE CONSIDERED INCIDENTAL TO THE WORK AND, UNLESS OTHERWISE SPECIFIED, THE COST SHALL BE INCORPORATED INTO THE COSTS FOR RELEVANT ITEMS.
- THE LOCATION OF ALL EXISTING UTILITIES SHOWN ON THESE PLANS ARE FROM BEST AVAILABLE RECORDS AND SHALL BE CONSIDERED TO BE APPROXIMATE. WHEN CONSTRUCTION ACTIVITY REACHES IN PROXIMITY TO EXISTING UTILITIES, THE TRENCH(ES) SHALL BE OPENED A SUFFICIENT DISTANCE AHEAD OF THE WORK OR TEST PITS SHALL BE MADE TO VERIFY THE EXACT LOCATION AND INVERTS OF THE UTILITY TO ALLOW FOR POSSIBLE CHANGES IN THE LINE OR GRADE AS DIRECTED BY OFFICER. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ANY DAMAGE TO THE EXISTING UTILITIES AND THE RELATED STRUCTURES. ALL EXISTING UTILITY SYSTEMS SHALL BE PROTECTED TO PREVENT DAMAGE DURING THE CONTRACTOR'S OPERATIONS. ANY SYSTEM DAMAGED SHALL BE PROMPTLY REPAIRED AT NO COST TO THE OWNER.
- EXISTING MANHOLE FRAMES, COVERS, VALVE BOXES, AND OTHER APPURTENANCES SHALL BE ADJUSTED TO THE FINAL GRADE OR REPLACED, AS NECESSARY. UNLESS OTHERWISE SPECIFIED, THE COST FOR THIS SHALL BE CONSIDERED INCIDENTAL TO THE WORK, AND SHALL BE INCORPORATED INTO THE COSTS FOR RELEVANT ITEMS.
- THE CONTRACTOR SHALL PROVIDE ADA COMPLIANT ACCESS THROUGH OR AROUND THE SITE AT ALL TIMES AND SHALL ENSURE THE SAFETY OF ALL THOSE PASSING THROUGH OR ADJACENT TO THE SITE.
- ALL SIDEWALK AND CURB AND GUTTER DEMOLITION SHALL BEGIN AND END AT THE CONSTRUCTION JOINT NEAREST TO THE DEPICTED DEMOLITION EXTENTS WITH A NEAT SAWCUT LINE TO FULL DEPTH OF PAVEMENT SECTION.

STORMWATER AND ENVIRONMENTAL PROTECTION

- THE CONTRACTOR SHALL CONFINE ALL ACTIVITIES AT THE SITE ASSOCIATED WITH CONSTRUCTION ACTIVITIES, TO INCLUDE STORAGE OF EQUIPMENT AND OR MATERIALS, ACCESS TO THE WORK, FORMWORK, ETC. TO WITHIN THE DESIGNATED LIMITS OF DISTURBANCE (LOD).

TREE PROTECTION

- TREES SHALL BE PROTECTED PER THE REQUIREMENTS OF ARLINGTON PARKS & RECREATION STANDARD.

TRAFFIC CONTROL

- CONTRACTOR SHALL NOTIFY THE PROJECT OFFICER AT LEAST 3 WORKING DAYS PRIOR TO DISTURBING ANY EXISTING, OR INSTALLING ANY NEW, TRAFFIC SIGNS, SIGNALS, OR OTHER TRAFFIC CONTROL DEVICES.
- THE CONTRACTOR SHALL PREMARK THE LAYOUT OF ANY PERMANENT TRAFFIC CONTROL STRIPING, INDICATING THE PROPOSED LOCATION AND TYPE OF MARKING TO BE INSTALLED. THE PREMARKING MAY CONSIST OF TYPE D TAPE, CHALK, OR LUMBER CRAYONS. THE CONTRACTOR SHALL ALLOW 3 WORKING DAYS FOR THE INSPECTION AND APPROVAL OF THE PREMARKINGS PRIOR TO PLACING THE PERMANENT MARKINGS.
- THE CONTRACTOR SHALL SUBMIT ANY REQUESTS FOR TEMPORARY "NO PARKING" RESTRICTIONS TO THE PROJECT OFFICER AT LEAST 5 BUSINESS DAYS PRIOR TO THE DESIRED ONSET OF RESTRICTIONS. PRIOR TO A REQUEST FOR THE REMOVAL OF ACCESS TO ANY ADA PARKING SPACE THE CONTRACTOR MUST HAVE MADE PROVISION FOR ALTERNATIVE ADA PARKING AS INDICATED ON THE APPROVED PLAN OR AS DIRECTED BY THE PROJECT OFFICER.
- WHEN THE APPROVED PLAN CALLS FOR THE REMOVAL OF ANY PARKING METER THE CONTRACTOR MUST MAKE A REQUEST TO THE PROJECT OFFICER AT LEAST ONE WEEK IN ADVANCE OF THE DESIRED REMOVAL. THE PROJECT OFFICER WILL THEN COORDINATE THE PARKING METER REMOVAL WITH TRAFFIC ENGINEERING AND OPERATIONS.
- THE CONTRACTOR SHALL PRESERVE ALL BUS STOPS, INCLUDING MAINTAINING ADEQUATE ACCESSIBILITY THROUGH AND ADJACENT TO THE CONSTRUCTION FOR BUSES AND THEIR PASSENGERS. THE CONTRACTOR SHALL NOT CLOSE, RELOCATE, OR OTHERWISE MODIFY A BUS STOP WITHOUT PRIOR REQUEST OF THE PROJECT OFFICER. ANY RELOCATION OR CLOSURE OF A BUS STOP SHALL REQUIRE AT LEAST FOUR WEEKS ADVANCE NOTICE FOR COORDINATION WITH THE COUNTY'S BUS STOP COORDINATOR - 703-228-3049.
- WHEN CONDITIONS WARRANT DUE TO TRAFFIC VOLUMES, PATTERNS, OR SPECIAL EVENTS, THE COUNTY MAY SUSPEND OR OTHERWISE DIRECT THE CONTRACTOR'S ACTIVITIES TO PROTECT THE PUBLIC AND OR THE COUNTY'S TRANSPORTATION NETWORK.

WATER DISTRIBUTION, STORM AND SANITARY SEWER SYSTEMS

- UNLESS OTHERWISE DIRECTED, CONTRACTORS ARE EXPRESSLY PROHIBITED FROM OPERATING ANY WATER VALVES OR APPURTENANCES. CONTRACTORS SHALL SUBMIT ALL REQUESTS FOR VALVE OPERATIONS TO THE PROJECT OFFICER AT LEAST 1 WEEK IN ADVANCE OF THE REQUIRED OPERATION.
- IN THE EVENT OF A WATER OR SEWER EMERGENCY, THE CONTRACTOR SHALL IMMEDIATELY NOTIFY THE COUNTY'S WATER CONTROL CENTER AT 703-228-6555 AND THE PROJECT OFFICER.
- THE CONTRACTOR SHALL COORDINATE ALL UTILITY SHUTOFFS, DISCONNECTS, AND/OR ABANDONMENT WITH UTILITY OWNER AND PROJECT OFFICER AT LEAST 1 WEEK IN ADVANCE OF THE REQUIRED INTERRUPTION.

FIRE DEPARTMENT NOTES:

- ALL EXISTING FIRE HYDRANTS AND FIRE DEPARTMENT CONNECTIONS SHALL BE MAINTAINED UNOBSTRUCTED AND ACCESSIBLE AT ALL TIMES IN ACCORDANCE WITH SECTIONS 508.5.4 AND 508.5.5 OF THE ARLINGTON COUNTY FIRE PREVENTION CODE.
- ACCESS TO BUILDINGS FOR FIREFIGHTING SHALL BE MAINTAINED AT ALL TIMES. EXISTING FIRE APPARATUS ACCESS ROADS (FIRE LANES) SHALL BE KEPT CLEAR OF OBSTRUCTIONS IN ACCORDANCE WITH SECTION 503.4 OF THE ARLINGTON COUNTY FIRE PREVENTION CODE. ACCESS TO CONSTRUCTION SITES SHALL BE PROVIDED AND MAINTAINED IN ACCORDANCE WITH SECTION 1410 OF THE ARLINGTON COUNTY FIRE PREVENTION CODE.
- IN THE EVENT THAT EXISTING FIRE DEPARTMENT CONNECTIONS OR FIRE APPARATUS ACCESS ROADS (FIRE LANES) MUST BE OBSTRUCTED TO FACILITATE CONSTRUCTION ACTIVITIES, CONTACT THE ARLINGTON COUNTY FIRE DEPARTMENT FIRE PREVENTION OFFICE AT 703-228-4644 TO COORDINATE REVIEW AND APPROVAL OF TEMPORARY FIRE DEPARTMENT CONNECTIONS AND/OR FIRE APPARATUS ACCESS ROADS PRIOR TO CREATING THE OBSTRUCTION.

SHEET LIST

SHEET NUMBER	SHEET TITLE
C000.1	COVER
C002.1	DETAILS
C004.1	TYPICAL SECTIONS
C006.1	LEGEND
C011.1	EXISTING CONDITIONS PLAN
C011.2	TREE INVENTORY
C031.1	SILTATION AND EROSION CONTROL PLAN
C032.1	SILTATION AND EROSION CONTROL NARRATIVE
C032.2	SILTATION AND EROSION CONTROL DETAILS
C035.1	STORMWATER POLLUTION PREVENTION PLAN
C035.2	STORMWATER POLLUTION PREVENTION PLAN
C042.1	PLAN AND PROFILE
C043.1	WALL PROFILE LEFT
C043.2	WALL PROFILE RIGHT
C044.1	CROSS SECTIONS STA 10+00 TO 12+70
C044.2	CROSS SECTIONS STA 12+80 TO 15+43
C044.3	CROSS SECTIONS STA 15+50 TO 16+50
C045.1	GEOMETRIC CONTROL PLAN
C045.2	GEOMETRIC CONTROL PLAN
C071.1	STORM SEWER DRAINAGE DIVIDES
C075.1	STORM COMPUTATIONS
C081.1	WATER QUALITY IMPACT ASSESSMENT PLAN
C091.1	LANDSCAPE PLAN
C092.1	LANDSCAPE NOTES AND DETAILS
C121.1	MAINTENANCE OF TRAFFIC PLAN

SWM#

SWM# 15-2037

ADT

NOT APPLICABLE

STREET CLASSIFICATION

NOT APPLICABLE

POSTED SPEED

NOT APPLICABLE

STORM DRAINAGE IMPROVEMENTS
S42D
HEADWATERS DONALDSON RUN TRIBUTARY B
(ANALOSTAN BRANCH)


COVER SHEET

DESIGNED: ML
DRAWN: ML
CHECKED: AP


PLOTTED: DECEMBER 29 2022

SCALE: AS SHOWN

C000.1



CROSS VANE - IMBRICATED WALL COMBINATION (CROSS VANES C, D, E, F, K, N, S) (NTS)




Rock Axis Detail (NTS)

Cumulative Percent of particles finer than indicated particle size	PARTICLE SIZE (inches)	PARTICLE TYPE
D10	< 0.04in	sand
D16	1.0-2.0in	gravel
D35	3.0-4.0in	cobble
D50	8.0-10.0in	cobble
D84	14.0-16.0in	boulder


DESCRIPTION	SIZE	BUCKETS	PERCENT
ROCK/BOULDER	WELL GRADED 12-16"	0.5	7-12%
ROCK/COBBLE	WELL GRADED 8-12"	2	35-40%
BANK RUN GRAVEL	0.08-2.5"	2	35-40%
COURSE SAND	0.04-0.08" (1-2 MM)	0.75	12-17%

ALL IMPORTED BEDDING MATERIAL SHALL CONSIST OF FIELD STONE OR NATURAL RIVER ROCK SIMILAR IN COLOR AND APPEARANCE TO IN-SITU MATERIALS. CRUSHED STONE SHALL NOT BE PERMITTED. BANK RUN GRAVEL MAY INCLUDE UP TO 5% CLAY, SILT, AND/OR SAND, AND UP TO 25% COBBLE AND SHALL HAVE NATURAL COLOR (BROWN, TAN, YELLOW, OR WHITE). SAND SHALL BE WELL MIXED AND PREDOMINANTLY 1.0 TO 2.0 MILLIMETERS IN SIZE AND HAVE NATURAL COLOR (BROWN, TAN, YELLOW, OR WHITE). THE GRADATION OF IMPORTED MATERIALS SHALL FALL WITHIN THE ENVELOPE AS INDICATED IN THE TABLE ABOVE. COBBLE-GRAVEL VOID RATIO IS ESTIMATED AT 20%. THEREFORE, 20% BY VOLUME OF CL MATERIAL SHALL BE ADDED TO THE COBBLE-GRAVEL-SAND MATERIAL PRIOR TO PLACEMENT IN THE DESIGNATED AREAS. SEE CONSTRUCTION SPECIFICATIONS FOR DETAILS RELATIVE TO MIXING, PLACING, AND COMPACTING STREAMBED MATERIAL.


Streambed Material




BANK PROTECTION GUIDELINES DECEMBER 2003 VIRGINIA DEPARTMENT OF CONSERVATION RECREATION (MODIFIED)




BANK PROTECTION GUIDELINES DECEMBER 2003 VIRGINIA DEPARTMENT OF CONSERVATION RECREATION



GRADE CONTROL STRUCTURES GUIDELINES DECEMBER 2003 VIRGINIA DEPARTMENT OF CONSERVATION RECREATION (MODIFIED)




GRADE CONTROL STRUCTURES GUIDELINES DECEMBER 2003 VIRGINIA DEPARTMENT OF CONSERVATION RECREATION



HEADWALL (STA 10+03.42) N.T.S.

- NOTES:**
- IN NO CASE SHALL TOP OF ENDWALL PROJECT ABOVE FILL SLOPE.
 - THIS ITEM MAY BE PRECAST OR CAST-IN-PLACE.
 - ALL CAST-IN-PLACE CONCRETE TO BE CLASS ALL PRECAST CONCRETE SHALL BE 4000 PSI MINIMUM COMPRESSIVE STRENGTH.
 - HEADWALL TO BE REVELED IN ALL AREAS EXCEPT WHERE A CONFLICT WITH INVERT OCCURS.
 - HEADWALL AT THE OUTLET END MAY BE EITHER SQUARE EDGE OR BEVEL EDGE.
 - 3/4" CHAMFER MAY BE PROVIDED ON ALL EDGES AT MANUFACTURER'S OPTION.
 - CONTRACTOR SHALL SUBMIT A SIGNED SHOP DRAWING, INCLUDING ANY REQUIRED REINFORCING, FOR APPROVAL PRIOR TO CONSTRUCTION.



PIPE AND BEDDING DETAILS FOR TRENCH CONDITIONS

DEPARTMENT OF ENVIRONMENTAL SERVICES
FACILITIES & ENGINEERING DIVISION
ENGINEERING BUREAU
2100 CLARENDON BOULEVARD, SUITE 813
ARLINGTON, VA 22201
PHONE: 703.228.3629
FAX: 703.228.3606

COPYRIGHT © 2021 ARLINGTON COUNTY VIRGINIA - ALL RIGHTS RESERVED



APPROVALS

NAME	DATE
Amy Pflaum	08/04/22
QUALITY CONTROL ENGINEER	
Dennis M. Leach	8/5/22
CONSTRUCTION SECTION SUPERVISOR	
Jennifer Tastad	8/4/22
WATER, SEWER, STREETS BUREAU CHIEF	
Dennis M. Leach	08/03/22
TRANSPORTATION DIRECTOR	
Jennifer Tastad	08/17/22
PROJECT MANAGER	

REVISIONS

NO.	DESCRIPTION	DATE


STORM DRAINAGE IMPROVEMENTS
S42D
HEADWATERS DONALDSON RUN TRIBUTARY B (ANALOSTAN BRANCH)

DESIGNED: ML
DRAWN: ML
CHECKED: AP

PLOTTED: NOVEMBER 30 2022


SCALE: AS SHOWN

C002.1



APPROVALS	DATE
<i>Amy Pflaum</i> QUALITY CONTROL ENGINEER	08/04/22
<i>[Signature]</i> CONSTRUCTION SECTION SUPERVISOR	8/5/22
<i>[Signature]</i> WATER, SEWER, STREETS BUREAU CHIEF	8/4/22
<i>Dennis M. Leach</i> TRANSPORTATION DIRECTOR	08/03/22
<i>Jennifer Tostad</i> PROJECT MANAGER	08/17/22

REVISIONS	DATE



STORM DRAINAGE IMPROVEMENTS
 S42D
 HEADWATERS DONALDSON RUN TRIBUTARY B
 (ANALOSTAN BRANCH)

TYPICAL SECTIONS

DESIGNED: ML
 DRAWN: ML
 CHECKED: AP
 PLOTTED: NOVEMBER 30 2022

SCALE: AS SHOWN

C004.1

NOTES

1. THE TYPICAL CROSS SECTIONS AS SHOWN AND DIMENSIONED ON THIS SHEET WERE USED TO GUIDE THE PROPOSED GRADING INDICATED ON THE GRADING PLAN SHEETS. CROSS SECTIONS CUT FROM THE GRADING PLAN AS DRAWN ON THE CROSS SECTION SHEETS REPRESENT THE PROPOSED DESIGN DIMENSIONS AT ANY GIVEN STATION ALONG THE STREAM.
2. FOR DETAILS REGARDING THE VEGETATIVE MATERIALS PROPOSED AND THE LIMITS OF PLANTING ZONES, SEE THE LANDSCAPE PLAN ON SHEET C091.1.

LINETYPE LEGEND

FEATURE	EXISTING	PROPOSED
BUILDING	— — — — —	— — — — —
CENTERLINE / BASELINE	— — — — —	— — — — —
COMMUNICATIONS CABLE	— COM — COM —	— COM — COM —
CONTOURS - MAJOR, MINOR	--- 250 --- 250 ---	— 250 —
CRITICAL ROOT ZONE	— CRZ — CRZ —	— CRZ — CRZ —
EASEMENT	— — — — —	— — — — —
ELECTRIC (UNDERGROUND)	— UGE — UGE —	— UGE — UGE —
FENCE (MATERIAL NOTED)	-X-X-X-X-X-X-	-X-X-X-X-X-X-
FIBER OPTIC	— FO — FO —	— FO — FO —
GAS LINE	— GAS — GAS —	— GAS — GAS —
X" GAS LINE (SIZE INCLUDED IF AVAILABLE)	- # " g — # " g — # " g —	— # " G — # " G —
GUARDRAIL	. o . o . o . o . o . o .	. o . o . o . o . o . o .
HARDSCAPE FEATURE (MATERIAL NOTED)	— — — — —	— — — — —
LIMITS OF DISTURBANCE	— LOD — LOD —	— LOD — LOD —
LIMITS OF WORK	— LOW — LOW —	— LOW — LOW —
OVERHEAD WIRES		
PAVEMENT MINI SKIP LINE	— — — — —	— — — — —
PAVEMENT SKIP LINE	— — — — —	— — — — —
PROPERTY LINE	— — — — —	— — — — —
RIGHT-OF-WAY LINE	— — — — —	— — — — —
ROOT PRUNING	— RP — RP —	— RP — RP —
SANITARY SEWER	— SAN —	— SAN —
SANITARY SEWER UNDER 20" (SIZE INCLUDED IF AVAILABLE)	- # " s — # " s —	— — — — —
SANITARY SEWER OVER 20"	== == == == == ==	== == == == == ==
SILT FENCE	-X-X-X-X-X-X-	-X-X-X-X-X-X-
STORM (SIZE NOTED)	— STM — STM —	== == == == == ==
STREAM	—	—
STREET LIGHT CONDUIT	— SL — SL —	— SL — SL —
TELEPHONE (UNDERGROUND)	— UGT — UGT —	— UGT — UGT —
TREE LINE	~ ~ ~ ~ ~	~ ~ ~ ~ ~
TREE PROTECTION FENCE	— TP — TP —	— TP — TP —
WALL	== == == == == ==	== == == == == ==
WATERLINE UNDER 20" (SIZE INCLUDED IF AVAILABLE)	- # " w — # " w —	— — — — —
WATERLINE OVER 20"	== == == == == ==	== == == == == ==

SYMBOL LEGEND

EXISTING FEATURE	PROPOSED FEATURE
EX CABLE PEDESTAL	□
EX ELECTRIC BOX	⊞
EX FIRE HYDRANT	⊙
EX GAS VALVE	●
EX GROUND LIGHT	⚡
EX GUY WIRES	Y
EX IRON PIPE OR PIN	●
EX LIGHT POLE	●
EX MAILBOX	✉
EX MONUMENT	■
EX PARKING METER	⊖
EX PAY STATION	⊞
EX SANITARY MANHOLE	⊙
EX STORM BASIN	⊞
EX STORM MANHOLE	⊞
EX TELEPHONE PEDESTAL	⊞
EX TRAFFIC CONTROL BOX	□
EX TRAFFIC SIGN	●
EX TRASH CAN	●
EX TRAVERSE	⚠
EX TREES, WOODED AREA	⊙
EX UTILITY MANHOLE TYPE INDICATED ELEC, TELE, ETC	⊞
EX UTILITY POLE	⊞
EX WATER MANHOLE	⊙
EX WATER METER	⊙
EX WATER VALVE	⊙
EX YARD INLET	⊞
EX BENCHMARK	⊞
NORTH ARROW	↑

SYMBOL LEGEND

EXISTING FEATURE	PROPOSED FEATURE
EX STRIPING	Ⓐ
EX BUS STOP	Ⓐ


SYMBOL LEGEND

EXISTING	PROPOSED
EXISTING SANITARY STRUCTURE NUMBER	XXXX
EXISTING STORM SEWER STRUCTURE NUMBER	XXXX
PROPOSED SANITARY SEWER STRUCTURE NUMBER	XXXX
PROPOSED STORM SEWER STRUCTURE NUMBER	XXXX

LABEL LEGEND

HATCH LEGEND

PROPOSED MILL & OVERLAY SEE TYPICAL SECTION FOR DETAILS	[Hatch Pattern]
PROPOSED FULL DEPTH ASPHALT SEE TYPICAL SECTION FOR DETAILS	[Hatch Pattern]
PROPOSED CONCRETE	[Hatch Pattern]
REPLACE & MATCH EXISTING DRIVEWAY OR LEADWALK. SEE CONSTRUCTION NOTES	[Hatch Pattern]
DEMOLITION AREA	[Hatch Pattern]



APPROVALS DATE

<i>Amy Pflaum</i>	08/04/22
QUALITY CONTROL ENGINEER	
<i>[Signature]</i>	8/5/22
CONSTRUCTION SECTION SUPERVISOR	
<i>[Signature]</i>	8/4/22
WATER, SEWER, STREETS BUREAU CHIEF	
<i>Dennis M. Leach</i>	08/03/22
TRANSPORTATION DIRECTOR	
<i>Jennifer Tastad</i>	08/17/22
PROJECT MANAGER	

REVISIONS DATE

REVISIONS	DATE

STORM DRAINAGE IMPROVEMENTS S42D HEADWATERS DONALDSON RUN TRIBUTARY B (ANALOSTAN BRANCH)


LEGEND

DESIGNED: ML
DRAWN: ML
CHECKED: AP

PLOTTED: NOVEMBER 30 2022

SCALE: N/A

C006.1



APPROVALS DATE

<i>Amy Pfleum</i>	08/04/22
QUALITY CONTROL ENGINEER	
<i>[Signature]</i>	8/5/22
CONSTRUCTION SECTION SUPERVISOR	
<i>[Signature]</i>	8/4/22
WATER, SEWER, STREETS BUREAU CHIEF	
<i>Dennis M. Leach</i>	08/03/22
TRANSPORTATION DIRECTOR	
<i>Jennifer Tastad</i>	08/17/22
PROJECT MANAGER	


REVISIONS DATE

REVISIONS	DATE

STORM DRAINAGE IMPROVEMENTS
 S42D
 HEADWATERS DONALDSON RUN TRIBUTARY B
 (ANALOSTAN BRANCH)
 EXISTING CONDITIONS PLAN

DESIGNED: ML
 DRAWN: ML
 CHECKED: AP

PLOTTED: NOVEMBER 30 2022



C011.1

GENERAL SURVEY NOTES:


- THIS TOPOGRAPHIC SURVEY WAS COMPLETED UNDER THE DIRECT AND RESPONSIBLE CHARGE OF THE COUNTY SURVEY SECTION FROM AN ACTUAL GROUND SURVEY; THE IMAGE AND/OR ORIGINAL DATA WAS OBTAINED FROM MAY 2015 TO DECEMBER 2016, WITH SPOT UPDATES OBTAINED IN NOVEMBER AND DECEMBER 2020; AND THIS PLAT, MAP OR DIGITAL GEOSPATIAL DATA INCLUDING METADATA MEETS MINIMUM ACCURACY STANDARDS UNLESS OTHERWISE NOTED.
- HORIZONTAL DATUM: VIRGINIA COORDINATE SYSTEM 1983.
- VERTICAL DATUM: NORTH AMERICA VERTICAL DATUM 1988.
- CONTOUR INTERVAL: 1'
- BOUNDARY INFORMATION SHOWN HEREON WAS COMPILED FROM EXISTING LAND RECORDS AND DOES NOT REPRESENT A FIELD RUN BOUNDARY SURVEY.

STORM TABULATION

- #84-068
TOP = 357.04
72" CMP INV. IN = 344.58 (2187)
18" RCP INV. OUT = NO ACCESS (2174)
- #2174
TOP HEAD WALL = 335.4
15" CMP INV. IN = 333.17 (84-068)
- #2184
TOP = 360.37
15" RCP INV. IN = 353.62 (2228)
18" RCP INV. OUT = 367.33 (84-068)
- #2427
APPROXIMATE LOCATION SHOWN.
STRUCTURE NOT FOUND.
- #2430
TOP HEAD WALL = 372.3
18" CMP INV. OUT = 366.37 (2486)
- #2447
TOP = 387.27
18" RCP INV. IN = 367.46 (2441)
18" RCP INV. OUT = 367.33 (29795)
- #2486
TOP = 397.42
15" RCP INV. IN = 391.32 (2496) (PLAN)
18" RCP INV. IN = 391.08 (2534) (PLAN)
18" CMP INV. OUT = 388.60 (2430)

SANITARY TABULATION

- #2496
TOP = 398.39
15" RCP INV. OUT = 393.14 (2486)
- #2521
PIPE END SECTION
18" CMP INV. OUT = 389.62
- #2534
TOP = 406.07
15" RCP INV. IN = 403.02 (2528)
15" RCP INV. IN = 402.57 (2541)
18" RCP INV. IN = 401.97 (2601)
18" RCP INV. OUT = 401.57 (2486)
- #2568
TOP = 403.18
15" RCP INV. IN = 398.67 (2575)
18" CMP INV. OUT = 398.40 (2521)
- #2575
TOP = 403.40
15" RCP INV. IN = 399.40 (2618)
15" RCP INV. IN = 399.38 (2665)
15" RCP INV. OUT = 399.10 (2568)
- #29151
PLASTIC GRATE TOP = 390.73
6" PLASTIC INV. IN = 389.91 (2441)
6" PLASTIC INV. OUT = 389.85 (2447)
- #29795
TOP HEAD WALL = 372.3
21" CMP INV. OUT = 365.00 (2447)
- #6974
TOP = 328.51
C/L INV. = NO ACCESS
- #6975
TOP = 337.65
C/L INV. = 330.65
- #10987
TOP = 337.64
C/L INV. = 331.24
- #10988
TOP = 357.49
C/L INV. = 346.81
- #10989
TOP = 377.83
C/L INV. = 371.77
- #10990
TOP = 388.04
C/L INV. = 380.67
- #13737
TOP = 335.90
C/L INV. = 331.75
- #13738
TOP = 360.48
C/L INV. = 351.45



REVISED ON 01/07/2023
 FILENAME: S42D-214-EXISTING_CONDITIONS.DWG PATH: Q:\DATA\S42D\DESIGN\CAD\ACTIVE PLOTTED BY: MLEONARDI

Tree Number	DBH (inches)	Tree Species (common name)	Tree Species (scientific name)	Condition Rating	Species Rating	Replacement Value	Replacement Trees	CRZ Impact	Remove	Comments
6201	36	White Oak	Quercus alba	100	95	34.2		0		
6202	10	Honey Locust	Gleditsia triacanthos	80	65	5.2		0		
6203	6	Honey Locust	Gleditsia triacanthos	60	65	2.3		0		
6203-1	10	Red Maple	Acer rubrum	60	75	4.5		0		
6204	6	Hawthorn	Crataegus sp.	20	60	0.7		0		Dead
6204-1	12	Red Maple	Acer rubrum	60	75	5.4		0		
6205	12	River Birch	Betula nigra	80	75	7.2		0		
6206	6	Sugar Maple	Acer saccharum	80	80	3.8		0		
6207	28	Yellow Poplar	Liriodendron tulipifera	80	60	13.4		15		
6208	10	Red Bud	Cercis canadensis	80	45	3.6		0		
6209	16	Red Maple	Acer rubrum	80	75	9.6		0		
6210	28	Yellow Poplar	Liriodendron tulipifera	100	60	16.8	4	32	X	
6211	12	Yellow Poplar	Liriodendron tulipifera	80	60	5.8	2	63	X	
6212	8	Yellow Poplar	Liriodendron tulipifera	80	60	3.8		19		
6213	12	Yellow Poplar	Liriodendron tulipifera	80	60	5.8	2	95	X	
6214	14	Slippery Elm	Ulmus rubra	60	50	4.2		26		Canopy Removed
6215	46	White Oak	Quercus alba	20	75	6.9	0	19	X	Canopy Removed; Dead
6216	38	Yellow Poplar	Liriodendron tulipifera	100	60	22.8	5	34	X	
6217	6	Black Gum	Nyssa sylvatica	80	80	3.8	1	78	X	
6218	3	American Beech	Fagus grandifolia	60	90	1.6	1	83	X	
6219	8	Slippery Elm	Ulmus rubra	40	60	1.9	1	92	X	Leaning into the stream
6220	6	Pin Cherry	Prunus pensylvanica	80	55	2.6	1	100	X	
6221	8	Pin Cherry	Prunus pensylvanica	60	55	2.6		5		Covered in ivy
6222	36	Red Oak	Quercus rubra	20	65	4.7	0	36	X	Canopy Removed; Dead
6223	6	Sugar Maple	Acer saccharum	80	80	3.8		0		
6224	7	Pin Cherry	Prunus pensylvanica	80	55	3.1		0		
6225	36	Yellow Poplar	Liriodendron tulipifera	100	60	21.6		18		
6226	15	Yellow Poplar	Liriodendron tulipifera	100	60	9.0		23		
6227	8	American Beech	Fagus grandifolia	60	90	4.3	1	75	X	
6228	24	Yellow Poplar	Liriodendron tulipifera	100	60	14.4	3	43	X	
6229	12	Sugar Maple	Acer saccharum	80	80	7.7	2	37	X	
6230	36	Yellow Poplar	Liriodendron tulipifera	100	60	21.6		23		
6231	8	Black Gum	Nyssa sylvatica	60	80	3.8	1	51	X	
6232	48	Yellow Poplar	Liriodendron tulipifera	20	60	5.8		16		Dead
6233	28	Yellow Poplar	Liriodendron tulipifera	20	60	3.4		23		Dead
6234	8	Sugar Maple	Acer saccharum	60	80	3.8		0		
6235	35	Yellow Poplar	Liriodendron tulipifera	100	60	21.0		20		
6236	28	Yellow Poplar	Liriodendron tulipifera	100	60	16.8		27		
6237	22	Yellow Poplar	Liriodendron tulipifera	20	60	2.6		26		Dead
6238	20	Yellow Poplar	Liriodendron tulipifera	20	60	2.4	0	33	X	Dead
6239	28	Yellow Poplar	Liriodendron tulipifera	80	50	11.2		24		Covered in poison ivy
6240	38	Yellow Poplar	Liriodendron tulipifera	100	60	22.8	5	42	X	
6241	10	Black Gum	Nyssa sylvatica	60	80	4.8		22		Leaning
6242	12	Yellow Poplar	Liriodendron tulipifera	60	60	4.3		9		
6243	32	Yellow Poplar	Liriodendron tulipifera	100	60	19.2	4	39	X	
6244	8	Black Gum	Nyssa sylvatica	60	80	3.8	1	93	X	
6245	5	Pin Cherry	Prunus pensylvanica	60	55	1.7	1	41	X	
6246	28	White Oak	Quercus alba	100	95	26.6		17		
6247	8	Black Gum	Nyssa sylvatica	60	80	3.8		17		
6248	6	Pin Cherry	Prunus pensylvanica	60	55	2.0		0		
6249	8	Black Gum	Nyssa sylvatica	60	80	3.8		32		
6250	36	Yellow Poplar	Liriodendron tulipifera	100	60	21.6		20		
6251	10	Black Gum	Nyssa sylvatica	80	80	6.4	2	87	X	
6252	18	Pin Cherry	Prunus pensylvanica	80	55	7.9	1	60	X	
6253	10	Sugar Maple	Acer saccharum	80	85	6.8		21		
6254	32	Yellow Poplar	Liriodendron tulipifera	100	60	19.2		27		
6255	6	White Oak	Quercus alba	100	95	5.7		24		
6256	10	Pin Cherry	Prunus pensylvanica	80	55	4.4	1	100	X	
6257	28	White Oak	Quercus alba	100	95	26.6		14		
6258	36	White Oak	Quercus alba	100	95	34.2		12		
6259	36	Yellow Poplar	Liriodendron tulipifera	100	60	21.6	5	34	X	
6260	6	Yellow Poplar	Liriodendron tulipifera	60	60	2.2		12		
6261	10	Yellow Poplar	Liriodendron tulipifera	60	60	3.6		0		
6262	10	Yellow Poplar	Liriodendron tulipifera	60	60	3.6		3		
6263	8	Yellow Poplar	Liriodendron tulipifera	80	60	3.8		0		
6264	10	Pin Cherry	Prunus pensylvanica	20	40	0.8		18		Canopy Removed; Barely alive
6265	48	Yellow Poplar	Liriodendron tulipifera	100	60	28.8		15		
6266	18	Yellow Poplar	Liriodendron tulipifera	80	60	8.6		29		
6267	30	Yellow Poplar	Liriodendron tulipifera	100	60	18.0	4	100	X	
6268	42	Sycamore	Platanus occidentalis	40	60	10.1		10		Covered in ivy
6269	10	Red Maple	Acer rubrum	60	75	4.5		0		


Tree Number	DBH (inches)	Tree Species (common name)	Tree Species (scientific name)	Condition Rating	Species Rating	Replacement Value	Replacement Trees	CRZ Impact	Remove	Comments
6270	9	Pin Cherry	Prunus pensylvanica	80	55	4.0		0		
6271	6	Sycamore	Platanus occidentalis	80	60	2.9		0		
6272	6	Alder	Alnus sp.	80	55	2.6		0		
6273	6	Pin Cherry	Prunus pensylvanica	80	55	2.6		0		
6274	4	Red Oak	Quercus rubra	80	95	3.0		0		
6275	7	Slippery Elm	Ulmus rubra	80	65	3.6		0		
6276	3	Slippery Elm	Ulmus rubra	80	65	1.6		0		
6277	8	Black Gum	Nyssa sylvatica	80	80	5.1		0		
6278	30	Yellow Poplar	Liriodendron tulipifera	100	60	18.0	4	36	X	
6279	36	Yellow Poplar	Liriodendron tulipifera	100	60	21.6	5	61	X	
6280	30	Yellow Poplar	Liriodendron tulipifera	100	60	18.0	4	62	X	
6281	18	Black Locust	Robinia pseudoacacia	80	60	8.6		16		
6282	23	Yellow Poplar	Liriodendron tulipifera	80	60	11.0		23		
6283	4	Sugar Maple	Acer saccharum	80	80	2.6		0		
6284	12	Yellow Poplar	Liriodendron tulipifera	80	60	5.8		15		
6285	12	Red Maple	Acer rubrum	80	75	7.2		25		
6286	3	Pin Cherry	Prunus pensylvanica	80	55	1.3		0		
6287	12	Pin Cherry	Prunus pensylvanica	80	55	5.3		0		
6288	12	White Oak	Quercus alba	80	95	9.1		0		
6289	48	Yellow Poplar	Liriodendron tulipifera	100	65	31.2		12		
6290	6	Red Maple	Acer rubrum	80	75	3.6		12		
6291	6	Red Maple	Acer rubrum	80	75	3.6		14		
6292	8	Black Locust	Robinia pseudoacacia	80	65	4.2		0		
6293	8	Sugar Maple	Acer saccharum	80	80	5.1		0		
6294	8	Sugar Maple	Acer saccharum	80	80	5.1		0		
6295	21	Sycamore	Platanus occidentalis	100	60	12.6		0		
6296	14	White Oak	Quercus alba	40	90	5.0		0		Leaning
6297	46	Yellow Poplar	Liriodendron tulipifera	100	60	27.6		0		
6298	12	White Oak	Quercus alba	80	95	9.1		0		Outside RPA
6299	36	Pine	Pinus sp.	80	50	14.4		0		Broken branches; Outside RPA
6300	46	Yellow Poplar	Liriodendron tulipifera	100	60	27.6		0		
6301	30	Yellow Poplar	Liriodendron tulipifera	80	60	14.4		0		Outside RPA
6302	10	Sugar Maple	Acer saccharum	80	75	6.0		0		Outside RPA
6303	10	Juniper	Juniperus sp.	80	35	2.8		0		Outside RPA
6304	18	Crape Myrtle	Lagerstroemia sp.	60	25	2.7		0		Outside RPA
6305	4	Weeping Willow	Salix babylonica	60	55	1.3		0		Outside RPA
6306	8	Sugar Maple	Acer saccharum	80	80	5.1		0		Outside RPA
6307	18	White Oak	Quercus alba	80	95	13.7		0		Outside RPA
6308	12	Black Locust	Robinia pseudoacacia	80	60	5.8		0		Outside RPA
6309	20	Black Locust	Robinia pseudoacacia	80	60	9.6		0		Leaning; Outsiden RPA
6310	18	Crape Myrtle	Lagerstroemia sp.	60	25	2.7		0		Outside RPA
6311	8	American Holly	Ilex opaca	80	45	2.9		0		Outside RPA
6312	8	Sugar Maple	Acer saccharum	80	80	5.1		0		Outside RPA
6313	8	Sugar Maple	Acer saccharum	80	80	5.1		0		Outside RPA
6314	10	Catalpa	Catalpa sp.	80	50	4.0		0		Outside RPA
6315	18	Catalpa	Catalpa sp.	80	50	7.2		0		Outside RPA
6316	42	Norway Spruce	Picea abies	80	60	20.2		1		
6317	24	Yellow Poplar	Liriodendron tulipifera	40	60	5.8	2	43	X	Large Dead Branches
6318	28	Yellow Poplar	Liriodendron tulipifera	80	60	13.4		7		
6319	36	Yellow Poplar	Liriodendron tulipifera	80	60	17.3		17		
6320	42	Yellow Poplar	Liriodendron tulipifera	80	60	20.2		15		
6321	28	White Oak	Quercus alba	100	95	26.6		10		
6322	28	White Oak	Quercus alba	100	95	26.6		12		
6323	28	Yellow Poplar	Liriodendron tulipifera	100	60	16.8		14		
6324	24	Yellow Poplar	Liriodendron tulipifera	80	60	11.5		5		
6325	24	Yellow Poplar	Liriodendron tulipifera	100	60	14.4		4		
6326	8	Yellow Poplar	Liriodendron tulipifera	80	60	3.8		30		
6327	32	Yellow Poplar	Liriodendron tulipifera	100	60	19.2		16		
6328	8	Red Maple	Acer rubrum	80	75	4.8		0		Covered in ivy
6329	10	River Birch	Betula nigra	80	75	6.0		0		Leaning
6330	42	White Oak	Quercus alba	80	95	31.9		1		
6331	42	Yellow Poplar	Liriodendron tulipifera	100	60	25.2		14		
6332	32	Yellow Poplar	Liriodendron tulipifera	100	60	19.2		0		
6333	32	Yellow Poplar	Liriodendron tulipifera	100	60	19.2		0		
6334	36	White Oak	Quercus alba	100	95	34.2		13		
6335	28	White Oak	Quercus alba	100	95	26.6		4		
6336	32	Yellow Poplar	Liriodendron tulipifera	80	60	15.4		0		
6337	18	White Oak	Quercus alba	100	95	17.1		8		
6398	42	White Oak	Quercus alba	100	95	39.9		0		Leaning
6400	14	Black Locust	Robinia pseudoacacia	80	65	7.3		0		Outside RPA

NOTES:

- TREE INVENTORY WAS PERFORMED BY ROBERT HAYLER OF DEWBERRY ENGINEERS, INC. (ISA CERTIFIED ARBORIST #MA-5751).
- 28 TREES WILL BE REMOVED. 63 REPLACEMENT TREES ARE REQUIRED.
- DEAD TREES WITHIN THE LIMIT OF DISTURBANCE THAT ARE NOT INDICATED TO BE REMOVED SHALL BE TOPPED TO A 20-30 FOOT STUB AND REMAIN AS WILDLIFE SNAGS.
- ALL TREES ARE LOCATED WITHIN THE RPA LIMITS UNLESS OTHERWISE NOTED. ALL TREES INDICATED FOR REMOVAL ARE LOCATED WITHIN THE RPA LIMITS.


ARLINGTON VIRGINIA

DEPARTMENT OF ENVIRONMENTAL SERVICES
 FACILITIES & ENGINEERING DIVISION
 ENGINEERING BUREAU
 2100 CLARENDON BOULEVARD, SUITE 813



EROSION AND SEDIMENT CONTROL LEGEND

3.02	TEMPORARY CONSTRUCTION ENTRANCE	CE	
3.05	TEMPORARY SILT FENCE (SEE NOTE 6)	SF	
3.31	TEMPORARY SEEDING	TS	
3.32	PERMANENT SEEDING	PS	
3.38	TREE PROTECTION	TP	
	ROOT PRUNING (SEE NOTE 5)	RP	
	ACCESS ROAD DECK MAT (SEE NOTE 4)	DM	
	ROOT PROTECTION MATTING (SEE NOTE 4)	RM	
	PUMP AROUND		
	SANDBAG DIVERSION		
	CRITICAL ROOT ZONE	CRZ	
	LIMITS OF DISTURBANCE	LOD	



APPROVALS	DATE
<i>Amy Pfleum</i> QUALITY CONTROL ENGINEER	08/04/22
<i>[Signature]</i> CONSTRUCTION SECTION SUPERVISOR	8/5/22
<i>[Signature]</i> WATER, SEWER, STREETS BUREAU CHIEF	8/4/22
<i>Dennis M. Leach</i> TRANSPORTATION DIRECTOR	08/03/22
<i>Jennifer Tastad</i> PROJECT MANAGER	08/17/22


REVISIONS	DATE

STORM DRAINAGE IMPROVEMENTS
 S42D
 HEADWATERS DONALDSON RUN TRIBUTARY B
 (ANALOSTAN BRANCH)

SILTATION AND EROSION CONTROL PLAN

DESIGNED: ML
 DRAWN: ML
 CHECKED: AP

PLOTTED: NOVEMBER 30 2022



C031.1

- NOTES:**
- IN THE EVENT THAT A TREE NOT ALREADY DESIGNATED FOR REMOVAL IS DAMAGED OR DIES DURING CONSTRUCTION, REPLACEMENTS WILL BE PROVIDED ACCORDING TO THE TREE REPLACEMENT CALCULATIONS AND GUIDELINES.
 - PUMP AROUND DEWATERING HOURS OF OPERATION AND EQUIPMENT SELECTION TO COMPLY WITH ARLINGTON COUNTY NOISE CONTROL ORDINANCE. THE PUMP AROUND LINEWORK IS ILLUSTRATIVE ONLY AND PUMPING IS TO BE ACCOMPLISHED ACCORDING TO THE PREVAILING SITE CONDITIONS. THE PUMP AROUND SHOULD NOT BE RUN THROUGH AREAS PROTECTED BY TREE PROTECTION FENCING.
 - VEHICLE TRAFFIC BELOW THE CANOPY OF PRESERVED TREES IS TO BE PROHIBITED EXCEPT FOR AREAS WHERE MATTING IS USED.
 - TOPSOIL IS NOT TO BE SPREAD IN TREE PRESERVATION AREAS OR CRITICAL ROOT ZONES UNDISTURBED BY EXCAVATION (INCLUDING AREAS PROTECTED BY MATTING). WHERE FILL IN A CRITICAL ROOT ZONE IS UNAVOIDABLE, WORK WITH THE URBAN FORESTER TO SELECT AN APPROPRIATE SOIL TEXTURE AND AERATION MATTING. IN SUCH CASES THE INSTALLATION OF SOILS SHOULD BE BACKED OUT, WITH NO TRAFFIC OVER THE AREA AFTER INSTALLATION.
 - ROOT PRUNING EXTENTS TO BE ESTABLISHED AT THE DISCRETION OF THE URBAN FORESTER.
 - INSTALL SILT FENCE ON GRADE WITH NO TRENCH PER ROOT MATTING DETAIL (311300.7NS) ON SHEET C032.2.

- TS ALL DENUDED AREAS WITHIN PROJECT LIMITS
- PS SEE LANDSCAPE PLAN NOTES & DETAILS (SHEET C092.1)

EROSION AND SEDIMENT CONTROL NARRATIVE

PROJECT DESCRIPTION:

THE STREAM STABILIZATION PROJECT FOR DONALDSON RUN HEADWATERS IS NEAR 25TH STREET N, 24TH ROAD N, AND N WAKEFIELD CT JUST EAST OF OLD DOMINION DRIVE. THE PROJECT WILL DISTURB 1.03 ACRES WITHIN THE DONALDSON RUN WATERSHED. THE EXISTING HEADWATERS OF DONALDSON RUN HAVE HAD SIGNIFICANT EROSION AND REQUIRED A STABILIZATION PROJECT ALONG ROUGHLY 650 LINEAR FEET OF THE STREAM. THE LENGTH OF PROJECT WAS DETERMINED BY THE 1% RULE FOR DRAINAGE - FOR CALCULATIONS SEE SHEET C075.1.

EXISTING SITE CONDITIONS:

THE EXISTING SITE IS THE HEADWATERS OF DONALDSON RUN WITH A SMALL BUT STEEP VALLEY ON EITHER SIDE WITH RESIDENCES SURROUNDING THE STREAM. THERE ARE TWO PIPES (18" CMP AND 21" RCP) THAT CREATE THE HEADWATERS OF THE STREAM (THE SOUTH SIDE OF THE PROJECT SITE). THE SITE IS WOODED ALONG BOTH SIDES OF THE STREAM.

ADJACENT PROPERTIES:

SINGLE-FAMILY RESIDENTIAL PROPERTIES (CRULEY, MADAN, STOWE, FRIED) AND TOWNHOUSES (ANALOSTAN) ARE LOCATED ON BOTH SIDES OF THE STREAM. A GENERAL COMMERCIAL PROPERTY (MISSIONHURST) IS LOCATED ON THE NORTHWEST SIDE OF THE STREAM.

OFF-SITE AREAS:

THERE WILL BE NO OFFSITE AREAS USED BUT THE STAGING / STORING LOCATION WILL BE LOCATED ON THE MISSIONHURST PROPERTY NEAR THE CONSTRUCTION ENTRANCE OF THE SITE.

CRITICAL AREAS:

THE PROJECT IS LOCATED WITHIN LIMITS OF A RESOURCE PROTECTION AREA. STEEP SLOPES EXIST ALONG THE EXISTING STREAM BANK.

EROSION AND SEDIMENT CONTROL MEASURES:

THE EROSION AND SEDIMENT CONTROL MEASURES FOR THIS PROJECT AREA INCLUDE SAFETY FENCE, TREE PROTECTION, ROOT MATTING, AND DEWATERING MEASURES. INLET PROTECTION IS REQUIRED OUTSIDE THE PROJECT LIMITS WHEN/WHERE WATER FROM DISTURBED AREA FLOWS.

PERMANENT STABILIZATION:

ALL AREAS DISTURBED BY CONSTRUCTION SHALL BE STABILIZED WITH GRASS, MULCH OR SOD. SEE THE PROPOSED PLANS FOR ADDITIONAL INFORMATION.

STORMWATER RUNOFF CONSIDERATIONS:

NO ADDITIONAL IMPERVIOUS AREA WILL BE ADDED TO THIS PROJECT.

TOTAL LAND DISTURBANCE.....= 44,993 SF (1.03 ACRES)

PRE-IMPROVEMENT IMPERVIOUS AREA.....= 0 SF (0.0 ACRES)

POST-IMPROVEMENT IMPERVIOUS AREA...= 0 SF (0.0 ACRES)

INCREASED IMPERVIOUS AREA.....= 0 SF (0.0 ACRES)

SOILS INFORMATION:

THE FOLLOWING SOILS ARE FOUND ON SITE (SEE SOILS MAP ON SHEET C071.1 FOR LOCATION)

Table with columns: SOIL#, SOIL NAME, HYDROLOGIC GROUP, ERODABILITY. Row 1: 7D, GLENELG-URBANLAND COMPLEX, VARIES, N/A.

FLOODPLAIN AND RESOURCE PROTECTION AREA (RPA):

THE SITE IS WITHIN A RESOURCE PROTECTION AREA BUT HAS NO FLOODPLAIN.

EROSION & SEDIMENT CONTROL PROJECT PHASING

1. PHASE I:

- a. PRE-CONSTRUCTION MEETING WITH THE PROJECT OFFICER, CONTRACTOR, AND COUNTY INSPECTOR.
b. INSTALL THE TEMPORARY CONSTRUCTION ENTRANCE IN THE LOCATION SHOWN ON THE E&S PLAN. MUD AND DEBRIS SHALL BE WASHED FROM ALL TRUCKS EXISTING THE SITE.
c. INSTALL PERIMETER TREE DEMARCATION FENCING IN THE FORM OF TREE PROTECTION FENCE (TP) AS SHOWN ON E&S PLAN.
d. PERFORM INITIAL PERIMETER CLEARING TO INSTALL REMAINDER OF PERIMETER CONTROLS SUCH AS PUMP AROUND, AS PER THE PLAN.
e. SEED AND MULCH ALL EARTHEN CONTROLS.
f. CONTACT ARLINGTON COUNTY PROJECT OFFICER FOR A PERIMETER INSPECTION PRIOR TO CLEARING THE REMAINDER OF THE SITE IN ORDER TO OBTAIN PHASE II GRADING PERMIT.
g. CLEAR THE SITE TO THE LIMITS AS SHOWN ON THE CONSTRUCTION PLANS.

2. PHASE II:

- a. ALL WORK SHALL BE DONE SECTION-BY-SECTION IN DEWATERED AREAS.
b. BEGINNING AT THE DOWNSTREAM END AND WORKING UPSTREAM, PERFORM INITIAL SITE GRADING.
c. ONCE THE SITE IS BROUGHT TO NEAR FINAL GRADE, INSTALL STREAM STABILIZATION MEASURES (IMBRICATED ROCK WALL, CROSS-VANES, ETC.).
d. THE CONTROL MEASURES MAY NOT BE REMOVED UNTIL ALL OF THE DISTURBED AREAS HAVE BEEN STABILIZED AND ONLY AS APPROVED AND DIRECTED BY THE INSPECTOR.

EROSION AND SEDIMENT CONTROL MEASURES

UNLESS OTHERWISE INDICATED, ALL VEGETATIVE AND STRUCTURAL EROSION AND SEDIMENT CONTROL PRACTICES SHALL BE CONSTRUCTED AND MAINTAINED ACCORDING TO MINIMUM STANDARDS AND SPECIFICATIONS OF THE VIRGINIA EROSION AND SEDIMENT CONTROL HANDBOOK AND THE ARLINGTON COUNTY EROSION AND SEDIMENT CONTROL ORDINANCE. THE MINIMUM STANDARDS OF THE VIRGINIA EROSION AND SEDIMENT CONTROL HANDBOOK SHALL BE ADHERED TO UNLESS OTHERWISE WAIVED OR APPROVED BY A VARIANCE.

1. STRUCTURAL PRACTICES

- a. TEMPORARY CONSTRUCTION ENTRANCE - VESCH 3.02
a.a. A TEMPORARY CONSTRUCTION ENTRANCE WITH A WASH RACK SHALL BE INSTALLED AT THE EXISTING ACCESS POINT TO THE SITE. DURING MUDDY CONDITIONS, DRIVERS OF CONSTRUCTION VEHICLES WILL BE REQUIRED TO WASH THEIR WHEELS BEFORE RE-ENTERING THE LOCAL ROADWAYS.
a.b. THE ENTRANCE SHALL BE MAINTAINED IN A CONDITION WHICH WILL PREVENT TRACKING OR FLOW OF MUD ONTO PUBLIC RIGHTS-OF-WAY. THIS MAY REQUIRE PERIODIC WASHING OF THE MATS AND/OR REPLACEMENT OF WOOD CHIPS AS NECESSARY.
a.c. ALL MATERIALS SPILLED, DROPPED, WASHED, OR TRACKED FROM VEHICLES ONTO ROADWAYS OR INTO STORM DRAINS MUST BE REMOVED IMMEDIATELY.
a.d. THE USE OF WATER TRUCKS TO REMOVE MATERIALS DROPPED, WASHED, OR TRACKED INTO ROADWAYS WILL NOT BE PERMITTED UNDER ANY CIRCUMSTANCES.
b. SILT FENCE - VESCH 3.05
b.a. SILT FENCE WILL BE INSTALLED WITH THE E&S PLAN TO FILTER RUNOFF FROM DISTURBED AREAS. RUNOFF SHALL NOT BE DIRECTED PARALLEL TO THE INSTALLATION OF SILT FENCE.
b.b. SILT FENCES SHALL BE INSPECTED IMMEDIATELY AFTER EACH RAINFALL AND AT LEAST DAILY DURING PROLONGED RAINFALL. ANY REQUIRED REPAIRS SHALL BE MADE IMMEDIATELY.
b.c. CLOSE ATTENTION SHALL BE PAID TO THE REPAIR OF DAMAGED SILT FENCE RESULTING FROM UNDERCUTTING.
b.d. SHOULD THE FABRIC ON A SILT FENCE DECOMPOSE OR BECOME INEFFECTIVE PRIOR TO THE END OF THE EXPECTED USABLE LIFE, THE FABRIC SHALL BE REPLACED IMMEDIATELY.
b.e. SEDIMENT DEPOSITS SHALL BE REMOVED AFTER EACH STORM EVENT. THEY MUST BE REMOVED WHEN DEPOSITS REACH APPROXIMATELY ONE-HALF THE HEIGHT OF THE BARRIER.
b.f. ANY SEDIMENT DEPOSITS REMAINING IN PLACE AFTER THE SILT FENCE IS NO LONGER REQUIRED SHALL BE DRESSED TO CONFORM WITH THE EXISTING GRADE, THEN PREPARED AND SEEDED.
c. DEWATERING STRUCTURE - VESCH 3.26
c.a. SEDIMENT LADEN OR TURBID WATER SHALL BE FILTERED, SETTLED OR SIMILARLY TREATED PRIOR TO DISCHARGE.
c.b. THE FILTERING DEVICES MUST BE INSPECTED FREQUENTLY AND REPAIRED OR REPLACED ONCE THE SEDIMENT BUILD-UP PREVENTS THE STRUCTURE FROM FUNCTIONING AS DESIGNED.
c.c. THE ACCUMULATED SEDIMENT WHICH IS REMOVED FROM A DEWATERING DEVICE MUST BE SPREAD ON-SITE AND STABILIZED OR DISPOSED OF AT AN APPROVED DISPOSAL SITE AS PER THE APPROVED PLAN.
d. TREE PROTECTION - VESCH 3.38
d.a. ALL TREES ARE TO BE PROTECTED UNLESS OTHERWISE DIRECTED BY THE COUNTY INSPECTOR AND URBAN FORESTER. THE COUNTY'S URBAN FORESTER (703-228-1863) SHALL INSPECT ALL TREE PROTECTION 72 HOURS PRIOR TO THE START OF CONSTRUCTION. IN SPITE OF PRECAUTIONS, SOME DAMAGE TO PROTECTED TREES MAY OCCUR. IN SUCH CASES, THE FOLLOWING MAINTENANCE GUIDELINES SHALL BE FOLLOWED.
d.a.a. SOIL AERATION: IF THE SOIL HAS BECOME COMPACTED OVER THE ROOT ZONE OF ANY TREE, THE GROUND SHALL BE AERATED BY PUNCHING HOLES WITH AN IRON BAR. THE BAR SHALL BE DRIVEN 1-FOOT DEEP AND THEN MOVED BACK AND FORTH UNTIL THE SOIL IS LOOSENEED. THIS PROCEDURE SHALL BE REPEATED EVERY 18 INCHES UNTIL ALL OF THE COMPACTED SOIL BENEATH THE CROWN OF

- THE TREE HAS BEEN LOOSENEED.
d.a.b. REPAIR OF DAMAGE:
d.a.A.a. ANY DAMAGE TO THE CROWN, TRUNK, OR ROOT SYSTEM OF ANY TREE RETAINED ON THE SITE SHALL BE REPAIRED IMMEDIATELY.
d.a.A.b. WHENEVER MAJOR ROOT OR BARK DAMAGE OCCURS, REMOVE SOME FOLIAGE TO REDUCE THE DEMAND FOR WATER AND NUTRIENTS.
d.a.A.c. DAMAGED ROOTS SHALL IMMEDIATELY BE CUT OFF CLEANLY INSIDE THE EXPOSED OR DAMAGED AREA. CUT SURFACES SHALL BE PAINTED WITH APPROVED TREE PAINT, AND MOIST PEAT MOSS, BURLAP, OR TOPSOIL SHALL BE SPREAD OVER THE EXPOSED AREA.
d.a.A.d. TO TREAT BARK DAMAGE, CAREFULLY CUT AWAY ALL LOOSENEED BARK BACK INTO THE UNDAUNAGED AREA, TAPER THE CUT AT THE TOP AND BOTTOM, AND PROVIDE DRAINAGE AT THE BASE OF THE WOUND.
d.a.A.e. ALL TREE LIMBS DAMAGED DURING CONSTRUCTION OR REMOVED FOR ANY OTHER REASON SHALL BE CUT OFF ABOVE THE COLLAR AT THE PRECEDING BRANCH JUNCTION.
d.a.A.f. CARE FOR SERIOUS INJURIES SHALL BE PRESCRIBED BY A FORESTER OR A TREE SPECIALIST.
d.b. FERTILIZATION: BROADLEAF TREES THAT HAVE BEEN STRESSED OR DAMAGED SHALL RECEIVE A HEAVY APPLICATION OF FERTILIZER TO AID THEIR RECOVERY.
d.b.a. TREES SHALL BE FERTILIZED IN THE LATE FALL (AFTER OCTOBER 1) OR THE EARLY SPRING (FROM THE TIME FROST IS OUT OF THE GROUND UNTIL MAY 1). FALL APPLICATIONS ARE PREFERRED, AS THE NUTRIENTS WILL BE MADE AVAILABLE OVER A LONGER PERIOD OF TIME.
d.b.b. FERTILIZER SHALL BE APPLIED TO THE SOIL OVER THE FEEDER ROOTS. IN NO CASE SHALL IT BE APPLIED CLOSER THAN 3 FEET TO THE TRUNK. THE ROOT SYSTEM OF CONIFERS EXTENDS SOME DISTANCE BEYOND THE DRIP LINE. INCREASE THE AREA TO BE FERTILIZED BY ONE FOURTH THE AREA OF THE CROWN.
d.b.c. FERTILIZER SHALL BE APPLIED USING APPROVED FERTILIZATION METHODS AND EQUIPMENT.
d.b.d. FORMULATIONS AND APPLICATION RATES SHALL CONFORM TO THE GUIDELINES GIVEN IN TABLE 3.38-A OF VESCH.

2. VEGETATIVE PRACTICES

- e. TEMPORARY SEEDING - VESCH 3.31
e.a. ALL DENUDED AREAS, WHICH WILL BE LEFT DORMANT FOR EXTENDED PERIODS OF TIME SHALL BE SEEDED WITH FAST GERMINATING TEMPORARY VEGETATION IMMEDIATELY FOLLOWING GRADING. SELECTION OF THE SEED MIXTURE WILL DEPEND ON THE TIME OF YEAR IT IS APPLIED.
e.b. SEE SHEET III-288 OF THE VIRGINIA EROSION AND SEDIMENT CONTROL HANDBOOK (VESCH) FOR ALLOWABLE PLANTING MATERIAL, SEEDING RATES, AND DATES. THE PLANTING REQUIREMENTS OF THE "SOUTH" SHALL BE FOLLOWED. LIVING SHALL BE BASED ON TABLE 3.31-A OF VESCH. FERTILIZERS SHALL BE APPLIED AS 600 LB/ACRE. THE FERTILIZER SHALL BE INCORPORATED INTO THE TOP 2-4" OF SOIL. SEED SHALL BE EVENLY APPLIED AND SMALL GRAINS SHALL BE PLANTED NO MORE THAN 1.5" DEEP. SEEDING MADE IN FALL FOR WINTER COVER AND DURING HOT SUMMER MONTHS SHALL BE MULCHED.
f. EROSION CONTROL BLANKET AND MULCHING - VESCH 3.36 AND 3.35
f.a. EROSION CONTROL BLANKETS WILL BE INSTALLED OVER FILL SLOPES WHICH HAVE BEEN BROUGHT TO FINAL GRADE AND HAVE BEEN SEEDED TO PROTECT THE SLOPES FROM RILL AND GULLY EROSION AND TO ALLOW SEED TO GERMINATE PROPERLY. SEE SPECIFICATION FOR COIR FIBER MATTING PERFORMANCE STANDARDS. MULCH (STRAW OR FIBER) WILL BE USED ON RELATIVELY FLAT AREAS AND WILL BE APPLIED AS A SECOND STEP IN SEEDING OPERATION.
g. DUST CONTROL - VESCH 3.39
g.a. DUST SHALL BE CONTROLLED USING A VARIETY OF METHODS SUCH AS VEGETATIVE COVER, MULCH, TILLAGE, IRRIGATION, SPRAY-ON ADHESIVES, STONE BARRIERS, AND CALCIUM CHLORIDE. THE IMPLEMENTATION OF THE DUST CONTROL METHODS SHALL BE INSTALLED PER SECTION 3.39 OF VESCH
h. PERMANENT SEEDING - VESCH 3.32
h.a. SEE THE UPLAND WOODLAND SEED MIX ON THE LANDSCAPE NOTES AND DETAILS (SHEET C092.1).

THE EROSION AND SEDIMENT CONTROL INSPECTOR SHALL HAVE THE AUTHORITY TO ADD OR DELETE EROSION AND SEDIMENT CONTROLS AS NEEDED IN THE FIELD. IN ADDITION, NO SEDIMENT TRAPS OR BASINS MAY BE REMOVED WITHOUT PRIOR APPROVAL OF THE INSPECTOR.

EROSION AND SEDIMENT CONTROL MANAGEMENT MEASURES

LANDSCAPE / TREE PRESERVATION NOTES

PRIOR TO ANY LAND DISTURBING ACTIVITY, THE CONTRACTOR SHALL CONTACT THE ARLINGTON COUNTY ARBORIST TO SCHEDULE AN INSPECTION.

LAND CONSERVATION NOTES:

- 1. NO DISTURBED AREA WILL REMAIN DENUDED FOR MORE THAN 7 CALENDAR DAYS UNLESS OTHERWISE AUTHORIZED BY THE DIRECTOR OR HIS AGENT.
2. ALL EROSION AND SEDIMENT CONTROL MEASURES ARE TO BE PLACED PRIOR TO OR AS THE FIRST STEP IN GRADING. FIRST AREAS TO BE CLEARED ARE TO BE THOSE REQUIRED FOR THE PERIMETER CONTROLS.
3. ALL STORM AND SANITARY SEWER LINES NOT IN STREETS ARE TO BE MULCHED AND SEEDED WITHIN 5 DAYS AFTER BACKFILL. NO MORE THAN 100 FEET ARE TO BE OPEN AT ANY ONE TIME.
4. ELECTRIC POWER, TELEPHONE AND GAS SUPPLY TRENCHES ARE TO BE COMPACTED, SEEDED AND MULCHED WITHIN 5 DAYS AFTER BACKFILLING.
5. ALL TEMPORARY EARTH BERMS, DIVERSIONS AND SEDIMENT CONTROL DAMS ARE TO BE MULCHED AND SEEDED FOR TEMPORARY VEGETATIVE COVER IMMEDIATELY AFTER GRADING. STRAW OR HAY MULCH IS REQUIRED. THE SAME APPLIES TO ALL SOIL STOCKPILES.
6. DURING CONSTRUCTION, ALL STORM SEWER INLETS WILL BE PROTECTED BY INLET PROTECTION.
7. ANY DISTURBED AREA NOT COVERED BY NOTE 1 ABOVE AND NOT PAVED, SODDED OR BUILT UPON BY NOV. 1, OR DISTURBED AFTER THAT DATE, SHALL BE MULCHED IMMEDIATELY WITH HAY OR STRAW MULCH AT THE RATE OF 2 TONS/ACRE AND OVER-SEEDED BY APRIL 15.
8. AT THE COMPLETION OF ANY PROJECT CONSTRUCTION AND PRIOR TO BOND RELEASE, ALL TEMPORARY SEDIMENT CONTROLS SHALL BE REMOVED AND ALL DENUDED AREAS SHALL BE STABILIZED.

EROSION & SEDIMENT CONTROL PROGRAM:

- 1. THE EROSION CONTROL PLAN IS INTENDED TO ESTABLISH ENTRANCES AND PERIMETER CONTROL MEASURES WHICH INCLUDES SILT FENCE (SF), INLET PROTECTION (IP), AND OTHER CONTROLS SPECIFIED ON THE PLANS.
2. WHERE CONSISTENT WITH JOB SAFETY REQUIREMENTS, ALL EXCAVATED MATERIAL SHALL BE PLACED ON THE UPHILL SIDE OF TRENCHES. NO MATERIAL SHALL BE PLACED IN STREAMBEDS. ANY STOCKPILED MATERIAL WHICH WILL REMAIN IN PLACE LONGER THAN 7 DAYS SHALL BE SEEDED AND MULCHED. WHEN SPOIL IS PLACED ON THE DOWNHILL SIDE OF TRENCH, IT SHALL BE BACKSLOPED TO DRAIN TOWARD THE TRENCH. WHEN NECESSARY TO DEWATER THE TRENCH, THE PUMP DISCHARGE HOSE SHALL OUTLET IN A STABILIZED AREA OR A SEDIMENT TRAPPING DEVICE.
3. ALL PRACTICES AND CONTROL DEVICES DESCRIBED HEREIN SHALL CONFORM TO THE CURRENT VIRGINIA EROSION AND SEDIMENT CONTROL HANDBOOK (VESCH). IN ADDITION, THE CONTRACTOR SHALL TAKE THE FOLLOWING STEPS TO MINIMIZE THE VOLUME OF SILT:
a. CONTRACTOR SHALL EVALUATE THE SITE TO DETERMINE EXTENSIVE CUT AND FILL AREAS, AND SHALL WORK THOSE AREAS TO MINIMIZE THE USE OF HEAVY EQUIPMENT. CONTRACTOR SHALL BRING DISTURBED AREAS TO GRADE (ROUGH OR FINISHED) AND STABILIZE THOSE AREAS WITH TEMPORARY OR PERMANENT VEGETATION. THESE DISTURBED AREAS SHALL BE STABILIZED PRIOR TO BEGINNING WORK IN ANOTHER AREA.
b. FILL AREAS SHALL BE COMPACTED COMPLETELY PRIOR TO THE END OF EACH WORK DAY. FILL SOLE SURFACES SHALL BE KEPT ROUGH TO REDUCE SHEET EROSION OF THE SLOPES. CONTRACTOR SHALL RE-DIRECT CONCENTRATED RUNOFF, BY EARTH BERMS OR OTHER DEVICES, AROUND ACTIVELY DISTURBED AREAS TO STABILIZED OUTLETS.
c. CUT SLOPES SHALL BE PROTECTED FROM CONCENTRATED FLOW BY BERMS (ABOVE THE SLOPE) AND DIRECTED AROUND THE DISTURBED AREA TO STABILIZED OUTLETS.
4. MEASURES TO CONTROL EROSION AND SILTATION SHALL BE PROVIDED PURSUANT TO AND IN COMPLIANCE WITH CURRENT STATE AND LOCAL REGULATIONS. THE INFORMATION CONTAINED IN THE CONSTRUCTION PLANS AND/OR THE APPROVAL OF THE PLANS SHALL IN NO WAY RELIEVE THE CONTRACTOR OR HIS AGENT OF ANY LEGAL RESPONSIBILITY WHICH MAY BE REQUIRED BY THE CODE OF VIRGINIA AND CHAPTER 57 OF THE ARLINGTON COUNTY CODE.
5. ALL AREAS, ON OR OFF-SITE, THAT ARE DISTURBED BY THIS CONSTRUCTION AND WHICH ARE NOT PAVED OR BUILT UPON SHALL BE ADEQUATELY STABILIZED TO CONTROL EROSION AND SEDIMENTATION. ACCEPTABLE STABILIZATION SHALL CONSIST OF PERMANENT GRASS SEED MIXTURE OR SOD THAT IS INSTALLED IN ACCORDANCE WITH THE PROJECT SPECIFICATIONS. ALL SLOPES 3:1 AND GREATER SHALL BE RECEIVE SOIL STABILIZATION IN ACCORDANCE WITH THE SPECIFICATIONS.
6. WHERE STREAM CROSSINGS ARE REQUIRED FOR EQUIPMENT, TEMPORARY CULVERTS SHALL BE PROVIDED.
7. FOR FURTHER REQUIREMENTS AND DETAILS OF TREE PRESERVATION, PLANTING, EROSION AND SEDIMENT CONTROL, SEE COUNTY CONSTRUCTION STANDARDS AND SPECIFICATIONS AND/OR THE VIRGINIA EROSION AND SEDIMENT CONTROL HANDBOOK.

GENERAL EROSION AND SEDIMENT CONTROL NOTES

- 1. UNLESS OTHERWISE INDICATED, ALL VEGETATIVE AND STRUCTURAL EROSION AND SEDIMENT CONTROL PRACTICES WILL BE CONSTRUCTED AND MAINTAINED ACCORDING TO THE MINIMUM STANDARDS AND SPECIFICATIONS OF THE VIRGINIA EROSION AND SEDIMENT CONTROL HANDBOOK AND VIRGINIA REGULATIONS VR 625-02-00 EROSION AND SEDIMENT CONTROL REGULATIONS.
2. THE PLAN APPROVING AUTHORITY MUST BE NOTIFIED ONE WEEK PRIOR TO THE PRE-CONSTRUCTION CONFERENCE, ONE WEEK PRIOR TO THE COMMENCEMENT OF LAND DISTURBING ACTIVITY, AND ONE WEEK PRIOR TO THE FINAL INSPECTION.
3. ALL EROSION AND SEDIMENT CONTROL MEASURES ARE TO BE PLACED PRIOR TO OR AS THE FIRST STEP IN CLEARING.
4. A COPY OF THE APPROVED EROSION AND SEDIMENT CONTROL PLAN SHALL BE MAINTAINED ON THE SITE AT ALL TIMES.
5. PRIOR TO COMMENCING LAND DISTURBING ACTIVITIES IN THE AREAS OTHER THAN INDICATED ON THESE PLANS (INCLUDING, BUT NOT LIMITED TO, OFF-SITE BORROW OR WASTE AREAS), THE CONTRACTOR SHALL SUBMIT A SUPPLEMENTARY EROSION AND SEDIMENT CONTROL PLAN TO THE OWNER

FOR REVIEW AND APPROVAL BY THE PLAN APPROVING AUTHORITY.

- 6. THE CONTRACTOR IS RESPONSIBLE FOR INSTALLATION OF ANY ADDITIONAL EROSION AND SEDIMENT CONTROL MEASURES NECESSARY TO PREVENT EROSION AND SEDIMENTATION AS DETERMINED BY THE PLAN APPROVING AUTHORITY.
7. ALL DISTURBED AREAS ARE TO DRAIN TO APPROVED SEDIMENT CONTROL MEASURES AT ALL TIMES DURING LAND DISTURBING ACTIVITIES AND DURING SITE DEVELOPMENT UNTIL FINAL STABILIZATION IS ACHIEVED.
8. DURING DEWATERING OPERATIONS, WATER WILL BE PUMPED INTO AN APPROVED FILTERING DEVICE.
9. THE CONTRACTOR SHALL INSPECT ALL EROSION AND SEDIMENT CONTROL MEASURES PERIODICALLY AND AFTER EACH RUNOFF-PRODUCING RAINFALL EVENT. ANY NECESSARY REPAIRS OR CLEANUP TO MAINTAIN THE EFFECTIVENESS OF THE EROSION CONTROL DEVICES SHALL BE MADE IMMEDIATELY.
10. ALL BIOFILTERS SHALL BE KEPT OFF-LINE UNTIL CONSTRUCTION IS COMPLETED AND ALL AREAS HAVE BEEN PROPERLY STABILIZED. THIS SHALL BE ACHIEVED BY USING INLET PROTECTION AT THE CURB CUTS AND STORMWATER CATCH BASINS LEADING DIRECTLY INTO THE BIOFILTERS.
11. ALL TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES SHALL BE REMOVED WITHIN 30 DAYS AFTER FINAL SITE STABILIZATION OR AFTER THE TEMPORARY MEASURES ARE NO LONGER NEEDED.

PRE-STORM EROSION & SEDIMENTATION CHECKLIST:

PER GENERAL EROSION AND SEDIMENT CONTROL NOTE 6, THE CONTRACTOR IS RESPONSIBLE FOR THE INSTALLATION AND MAINTENANCE OF ANY ADDITIONAL EROSION AND SEDIMENT CONTROL (ESC) MEASURES NECESSARY TO PREVENT EROSION AND SEDIMENTATION AS DETERMINED BY THE COUNTY. THESE SUPPLEMENTARY PRACTICES ARE IN ADDITION TO THOSE SHOWN IN AN EROSION AND SEDIMENT CONTROL PLAN. EROSION AND SEDIMENT CONTROL PRACTICES SHALL BE MODIFIED AS NEEDED TO ENSURE ONLY CLEAR WATER IS DISCHARGED FROM THE SITE.

THE FOLLOWING ACTIONS SHALL BE TAKEN PRIOR TO STORM EVENTS WITH PREDICTED HEAVY AND/OR LARGE VOLUME RAINFALL TO PREVENT SEDIMENT DISCHARGES FROM A CONSTRUCTION SITE. A TYPICAL SUMMER THUNDERSTORM IS AN EXAMPLE OF A STORM EVENT WITH PREDICTED HEAVY AND/OR LARGE VOLUME RAINFALL.

- 1. PERIMETER CONTROLS
a. SILT FENCE SHALL BE CHECKED FOR UNDERMINING, HOLES, OR DETEIORATION OF THE FABRIC. FENCING SHALL BE REPLACED IMMEDIATELY IF THE FABRIC IS DAMAGED OR WON. SILT FENCE MUST BE TRENCHED INTO THE GROUND PER STATE SPECIFICATIONS (VESCH STD & SPEC 3.09).
b. WOODEN STAKES OR STEEL POSTS SHALL BE PROPERLY SECURED UPRIGHT INTO THE GROUND. DAMAGED POSTS OR STAKES MUST BE REPLACED.
c. SEDIMENT THAT HAS ACCUMULATED AGAINST THE SILT FENCE SHALL BE REMOVED. ACCUMULATED SEDIMENT MUST BE REMOVED WHEN THE LEVEL REACHES ONE-HALF THE HEIGHT OF THE FENCING.
d. HAY BALES OR A STONE BERM SHALL BE PLACED ACROSS THE CONSTRUCTION ENTRANCE TO PREVENT SEDIMENT FROM LEAVING THE CONSTRUCTION SITE.
2. EXPOSED SLOPES AND SOIL
a. EXPOSED SLOPES NOT AT THE FINAL STABILIZATION PHASE SHALL BE COVERED WITH TARP, PLASTIC SHEETING, OR EROSION CONTROL MATTING. COVERING MATERIAL SHALL BE PROPERLY SECURED/ANCHORED.
b. CONTROLS SHALL BE INSTALLED TO PREVENT CONCENTRATED FLOW DOWN AN EXPOSED SLOPE. BERMS OR DIVERSION DIKES SHALL BE INSTALLED AT THE TOP OF CUT/EXPOSED SLOPES TO DIRECT STORM FLOW AROUND THE DISTURBED AREA.
c. EXPOSED SLOPES AT THE FINAL STABILIZATION PHASE SHALL BE STABILIZED USING SLOPE STABILIZATION PRACTICES SUCH AS SOIL STABILIZATION BLANKETS OR MATTING AS SPECIFIED IN THE VIRGINIA EROSION AND SEDIMENT CONTROL HANDBOOK (VESCH STD & SPEC 3.36). BLANKETS OR MATS MUST BE PROPERLY SECURED AND ANCHORED TO THE SLOPE USING STAPLES, PINS, OR STAKES.
d. SEEDED AREAS SHALL BE CHECKED AND RESEEDED AS NECESSARY TO COVER EXPOSED SOIL. RECENTLY SEEDED AREAS SHALL BE PROTECTED BY STRAW OR SOIL STABILIZATION BLANKETS TO PREVENT SEEDING FROM BEING WASHED AWAY.
3. STOCKPILES
a. STOCKPILED SOIL AND OTHER LOOSE MATERIALS THAT CAN BE WASHED AWAY SHALL BE COVERED WITH A TARP, PLASTIC SHEETING, OR OTHER STABILIZATION MATTING. THE COVER MUST BE PROPERLY SECURED/ANCHORED DOWN TO PREVENT IT FROM BEING BLOWN OFF AND EXPOSING MATERIALS TO RAIN. CONTROLS SUCH AS HAY BALES OR BOOMS SHALL BE PLACED ALONG THE PERIMETER OF THE STOCKPILE (DOWNHILL SIDE).
4. INLET PROTECTION
a. INLET PROTECTION CONTROLS SHALL BE INSPECTED TO ENSURE THEY ARE FUNCTIONING PROPERLY AND FLOODING WILL NOT OCCUR. CLOGGED OR DAMAGED CONTROLS MUST BE REPLACED IMMEDIATELY. ENSURE CONTROLS ALLOW FOR OVERFLOW/BYPASS OF STORMWATER RUNOFF DURING SIGNIFICANT STORM EVENTS.

IN ADDITION TO THESE PRE-STORM ACTIONS, ALL EROSION AND SEDIMENT CONTROL (ESC) MEASURES MUST BE CHECKED DAILY AND AFTER EACH SIGNIFICANT RAINFALL.

POLLUTION PREVENTION PLAN NOTES (STORMWATER MANUAL - SECTION 2.4)

- 1. ONLY THE FOLLOWING NON-STORMWATER DISCHARGES ARE AUTHORIZED BY ARLINGTON COUNTY'S MS4 PERMIT, UNLESS THE STATE WATER CONTROL BOARD, THE VIRGINIA SOIL AND WATER CONSERVATION BOARD (BOARD), OR ARLINGTON COUNTY DETERMINES THE DISCHARGE TO BE A SIGNIFICANT SOURCE OF POLLUTANTS TO SURFACE WATERS:
a. WATER LINE FLUSHING; LANDSCAPE IRRIGATION; DIVERTED STREAM FLOWS; RISING GROUND WATERS; UNCONTAMINATED GROUND WATER INFILTRATION (AS DEFINED AT 40 CFR 35.2005(20)); UNCONTAMINATED PUMPED GROUND WATER; DISCHARGES FROM POTABLE WATER SOURCES; FOUNDATION DRAINS; AIR CONDITIONING CONDENSATION; IRRIGATION WATER; SPRINGS; WATER FROM CRAWL SPACE PUMPS; FOOTING DRAINS; LAWN WATERING; INDIVIDUAL RESIDENTIAL CAR WASHING; FLOWS FROM RIPARIAN HABITATS AND WETLANDS; DECHLORINATED SWIMMING POOL DISCHARGES; DISCHARGES OR FLOWS FROM FIREFIGHTING; AND, OTHER ACTIVITIES GENERATING DISCHARGES IDENTIFIED BY THE DEPARTMENT OF ENVIRONMENTAL QUALITY AS NOT REQUIRING VPDES AUTHORIZATION.
2. APPROPRIATE CONTROLS MUST BE IMPLEMENTED TO PREVENT ANY NON-STORMWATER DISCHARGES NOT INCLUDED ON THE ABOVE LIST (E.G., CONCRETE WASH WATER, PAINT WASH WATER, VEHICLE WASH WATER, DETERGENT WASH WATER, ETC.) FROM BEING DISCHARGED INTO ARLINGTON COUNTY'S MS4 SYSTEM, WHICH INCLUDES THE CURB AND GUTTER SYSTEM, AS WELL AS CATCH BASINS AND OTHER STORM DRAIN INLETS, OR STREAM NETWORK.
3. PER CHAPTER 26 OF THE ARLINGTON COUNTY CODE, IT SHALL BE UNLAWFUL FOR ANY PERSON TO DISCHARGE DIRECTLY OR INDIRECTLY INTO THE STORM SEWER SYSTEM OR STATE WATERS, ANY SUBSTANCE LIKELY, IN THE OPINION OF THE COUNTY MANAGER, TO HAVE AN ADVERSE EFFECT ON THE STORM SEWER SYSTEM OR STATE WATERS.

UTILITY INSTALLATION:

UNDERGROUND UTILITY LINES SHALL BE INSTALLED IN ACCORDANCE WITH THE FOLLOWING STANDARDS IN ADDITION TO OTHER APPLICABLE CRITERIA:

- 1. NO MORE THAN 100 LINEAR FEET OF TRENCH MAY BE OPENED AT ONE TIME.
2. EXCAVATED MATERIAL SHALL BE PLACED ON THE UPHILL SIDE OF TRENCHES.
3. EFFLUENT FROM DEWATERING OPERATIONS SHALL BE FILTERED OR PASSED THROUGH AN APPROVED SEDIMENT TRAPPING DEVICE, OR BOTH, AND DISCHARGED IN A MANNER THAT DOES NOT ADVERSELY AFFECT FLOWING STREAMS OR OFF-SITE PROPERTY.
4. MATERIAL USED FOR BACKFILLING TRENCHES SHALL BE PROPERLY COMPACTED IN ORDER TO MINIMIZE EROSION AND PROMOTE STABILIZATION.
5. STABILIZATION SHALL BE ACCOMPLISHED IN ACCORDANCE WITH THESE REGULATIONS.
6. APPLICABLE SAFETY REGULATIONS SHALL BE COMPLIED WITH.
9. ANY DISTURBED AREA NOT COVERED BY NOTE #1 ABOVE AND PAVED, SODDED OR BUILT UPON BY NOVEMBER 1ST, OR DISTURBED AFTER THAT DATE, SHALL BE MULCHED WITH HAY OR STRAW AT THE RATE OF 2 TONS PER ACRE AND OVER-SEEDED NO LATER THAN MAY 15TH.
10. AT THE COMPLETION OF THE CONSTRUCTION PROJECT AND PRIOR TO BOND RELEASE, ALL TEMPORARY SEDIMENT CONTROLS SHALL BE REMOVED AND ALL DENUDED AREAS SHALL BE STABILIZED. ARLINGTON COUNTY INSPECTOR TO APPROVE REMOVAL OF ALL TEMPORARY SILTATION MEASURES.

MAINTENANCE PROGRAM:

THE FOLLOWING IS A PROGRAM OF MAINTENANCE FOR THE MECHANICAL CONTROLS SPECIFIED IN THIS NARRATIVE AND ON THE PLAN:

- 1. THE SITE SUPERINTENDENT OR HIS/HER REPRESENTATIVE SHALL MAKE A VISUAL INSPECTION OF ALL MECHANICAL CONTROLS AND NEWLY STABILIZED AREA (I.E. SEEDED AND MULCHED AND/OR SODDED AREAS) ON A DAILY BASIS; ESPECIALLY AFTER A HEAVY RAINFALL EVENT TO ENSURE THAT ALL CONTROLS ARE MAINTAINED AND PROPERLY FUNCTIONING. ANY DAMAGED CONTROLS SHALL BE REPAIRED PRIOR TO THE END OF THE WORK DAY INCLUDING RE-SEEDING AND MULCHING OR RE-SODDING IF NECESSARY.
2. ALL SEDIMENT TRAPPING DEVICES SHALL BE CLEARED OUT AT 50% TRAP CAPACITY AND THE SEDIMENT SHALL BE DISPOSED OF BY SPREADING ON THE SITE OR IF NOT SUITABLE FOR FILL, HAULING AWAY AND DEPOSITING AT AN ACCEPTABLE DUMP SITE.
3. THE CONTRACTOR SHALL TAKE SPECIAL CARE TO PREVENT MUD AND/OR OTHER DEBRIS FROM BEING ENTERED ONTO EXISTING SWM/BMP FACILITIES OR DOWNSTREAM WATER WAYS. SHOULD OFF-SITE AREAS BECOME POLLUTED BY CONSTRUCTION ACTIVITIES, THE CONTRACTOR SHALL BE RESPONSIBLE FOR CLEANING THE AFFECTED AREAS TO THE SATISFACTION OF THE INSPECTOR.
4. AT THE COMPLETION OF CONSTRUCTION AND PRIOR TO BOND RELEASE, ALL TEMPORARY SEDIMENT CONTROLS SHALL BE REMOVED AND ANY REMAINING DENUDED AREAS SHALL BE STABILIZED. CERTAIN DEVICES MAY BE REMOVED PRIOR TO CONSTRUCTION COMPLETION BUT ONLY WITH THE APPROVAL OF THE COUNTY INSPECTOR.
5. AFTER CONSTRUCTION OPERATIONS HAVE ENDED, ALL DISTURBED AREAS SHALL BE STABILIZED. UPON APPROVAL OF THE COUNTY INSPECTOR, MECHANICAL SEDIMENT CONTROLS SHALL BE REMOVED AND THE GROUND PERMANENTLY STABILIZED WITH VEGETATION WITHIN 30 DAYS.








Table with columns: APPROVALS, DATE. Includes signatures and dates for Amy Pflaum, Jennifer Tastad, and others.

STORM DRAINAGE IMPROVEMENTS HEADWATERS DONALDSON RUN TRIBUTARY B (ANALOSTAN BRANCH) SILTATION AND SEDIMENT CONTROL NARRATIVE

Table with columns: DESIGNED: ML, DRAWN: ML, CHECKED: AP

PLOTTED: NOVEMBER 30 2022

SCALE: N/A



STREAM WORK MAY EMPLOY PUMPING OF STREAM FLOW IN LIEU OF DIVERSION PIPES OR CHANNELS AS LONG AS THE WORK IS OF SHORT DURATION. (I.E. - PUMP DURING DAYLIGHT, ALLOW FLOW THROUGH WORK AREA AT NIGHT AFTER STABILIZED; OR TWO OR THREE DAYS OF CONTINUOUS 24HR./DAY PUMPING.) IN ADDITION, THIS PRACTICE IS ACCEPTABLE IN CLASS I, III OR IV STREAMS AS LONG AS ALL APPLICABLE STREAM CLOSURE DATES ARE ADHERED TO. ALONG WITH THIS MEASURE, SANDBAG/STONE DIVERSIONS WOULD BE NECESSARY UPSTREAM AND DOWNSTREAM OF WORK AREA IN CONJUNCTION WITH A DEWATERING BASIN TO KEEP WORK AREAS DRY. (PER GENE COPELAND, SECTION CHIEF OF FLOOD PLAIN MANAGEMENT, W.R.A.)







TABLE 3.31-B
ACCEPTABLE TEMPORARY SEEDING PLANT MATERIALS
'QUICK REFERENCE FOR ALL REGIONS'

Planting Dates	Species	Rate (lbs./acre)
Sept. 1 - Feb. 15	50/50 Mix of Annual Ryegrass (<i>Lolium multi-florum</i>) & Cereal (Winter) Rye (<i>Secale cereale</i>)	50 - 100
Feb. 16 - Apr. 30	Annual Ryegrass (<i>Lolium multi-florum</i>)	60 - 100
May 1 - Aug 31	German Millet (<i>Setaria italica</i>)	50

Source: Va. DSWC



APPROVALS DATE

Amy Pflaum 08/04/22
QUALITY CONTROL ENGINEER

[Signature] 8/5/22
CONSTRUCTION SECTION SUPERVISOR

[Signature] 8/4/22
WATER, SEWER, STREETS BUREAU CHIEF

Dennis M. Leach 08/03/22
TRANSPORTATION DIRECTOR

Jennifer Tostad 08/17/22
PROJECT MANAGER

REVISIONS DATE

REVISIONS	DATE

STORM DRAINAGE IMPROVEMENTS
S42D
HEADWATERS DONALDSON RUN TRIBUTARY B
(ANALOSTAN BRANCH)

EROSION AND SEDIMENT CONTROL
DETAILS

DESIGNED: ML
DRAWN: ML
CHECKED: AP

PLOTTED: NOVEMBER 30 2022

SCALE: AS SHOWN

STORMWATER POLLUTION PREVENTION PLAN (SWPPP)

Arlington County Projects
(Linear Development / Stormwater Retrofit)

For Construction Activities At:

Donaldson Run Headwaters - Stream Stabilization
4621 24th Rd N
Arlington, VA 22207

Latitude: 38.9028N (decimal degrees)
Longitude: 77.1232 W (decimal degrees)

Construction Activity Operator:

Arlington County Government DES
OSEM
2100 Clarendon Blvd, Suite 505
Arlington, VA 22201
703-226-3363
ethurber@arlingtonva.us
703-568-2222

SWPPP Preparation Date:
April 7, 2021

CERTIFICATION

I certify under penalty of law that I have read and understand this document and that this document and all attachments were prepared in accordance with a system designed to assure that qualified personnel properly gathered and evaluated the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations.*

Operator Name: _____
Title: _____
Signature: _____
Date: _____

1.0 SWPPP Documents Located Onsite & Available for Review

Table with columns: SWPPP Document Type, Located Onsite & Available for Review?, Yes/No/NA checkboxes.

Required documents must be kept at a centralized location on the project site (i.e. in a mail box or other container)

2.0 Authorized Non-Stormwater Discharges

Table with columns: Type of Authorized Non-Stormwater Discharges, Likely Present at Your Project Site?, Yes/No/NA checkboxes.

3.0 Pollution Prevention Awareness

Employees will be given a "walk through" of the site identifying areas of possible pollution and will be shown Erosion and Sediment Controls and Pollution Prevention Practices (identified in Sections 4.0 and 5.0 of this SWPPP) that are applicable to their assigned job duties. A refresher meeting and "walk through" will be conducted on an as needed basis.

4.0 Erosion & Sediment Controls

Table with columns: Select all that apply, Erosion & Sediment Control, Estimated Installation Date, Estimated Removal Date, Responsible Party.

Table with columns: (Std. & Spec 3.08 and/or Arlington County Std. & Spec from approved ESC plan), Yes/No/NA checkboxes, NTP, March 2024.

Pre-Storm Erosion and Sediment Control Checklist

The following actions shall be taken prior to storm events with predicted heavy and/or large volume rainfall to prevent sediment discharges from a construction site. A typical summer thunderstorm is an example of a storm event with predicted heavy and/or large volume rainfall.

- Perimeter controls (silt fence, hay bales, stone berms) used to prevent sediment from leaving the site shall be checked for undermining, holes, or deterioration and repaired/replaced if needed.
Sediment that has accumulated against perimeter controls shall be removed if the depth exceeds more than 1/2 of the silt fence height.
Exposed soil or slopes shall be covered with straw, tarps, plastic sheeting, or erosion control matting.
Stockpiled soil and other loose materials that can be washed away shall be covered with a tarp, plastic sheeting, or other stabilization matting.

5.0 Potential Sources of Pollution & Pollution Prevention Practices

Table with columns: Pollutant-Generating Activity, Likely Present at your Project Site?, Sediment, Nutrients, Heavy Metals, pH (acids and bases), Pesticides & Herbicides, Oil & Grease, Bacteria & Viruses, Trash, Debris, Solids, Other Toxic Chemicals, Pollution Prevention Practice, Responsible Party.

Pollution Prevention Practices:


- Clearing, grading, excavating, and un-stabilized areas - Maintain as much existing vegetation as practicable. Utilize erosion and sediment controls to prevent sediment from leaving the construction site.
Paving and saw cutting operations - Cover storm drain inlets during paving and saw cutting operations.

Temporary controls (i.e. tarp and block, sand berms, booms, and/or filter fabric) shall be used to cover storm drains during paving and saw cutting operations to prevent any discharges from entering the storm drain.

- Method of covering / protecting storm drains:
Method for containment, collection, disposal of saw cut slurry:

- Concrete operations, washout, and cement waste - Direct concrete wash water into a leak-proof container or leak-proof settling basin that is designed so that no overflows can occur due to inadequate sizing or precipitation.
Washouts must be sized appropriately for the needs of the project.
Do not locate washouts near storm drains.
Concrete wash water is not allowed to enter a storm drain.

The selected concrete wash out facility will be used:



07/22/2022
date

Qianqian Li, P.E.
ESC Program Administrator
Department of Environmental Services
2100 Clarendon Boulevard, Suite 813
Arlington, Virginia 22201

Re: Erosion and Sediment Control Permit Application for:

Headwaters Donaldson Run Tributary B (Analostan Branch)

street address

lot, block, section subdivision

permit number

Dear Mrs. Li:

I hereby certify that I accept the responsibilities of Responsible Land Disturber for the above referenced project. I understand that these responsibilities include:

- Reviewing the erosion and sedimentation (E&S) plan for the project.
Walking the site prior to construction to identify critical areas.
Conducting a pre-construction briefing with earth moving and site contractors to present the E&S plan and highlight the presence of critical areas, the limits of clearing and the required E&S controls and tree protection measures to be installed.
Regularly inspecting the site during construction to ensure that all E&S controls are functioning and are adequate to address erosion and sedimentation.
Reporting to the owner the presence inadequate or non functioning E&S controls when they are observed.
Ensuring that temporary soil stabilization is applied within 7 days to areas denuded that will remain undisturbed for longer than 14 days.
Calling (703) 228-0760 at least 80 hours before demolishing any structure.

I may be reached at (703) 228-7595 with questions about this plan or my execution of the duties of

Responsible Land Disturber.

Sincerely,

Ankur Patel

signed

Ankur Patel

name printed

PE, Lic. No. 57048

professional registration (type and number)

- Sanitary waste - Prevent the discharge of sanitary waste by providing convenient and well-maintained portable sanitary facilities.
Locate portable lavatories away from storm drains and surface waters.
Keep portable lavatories level and provide secondary containment (i.e. trays)
Regularly inspect facilities for leaks
Schedule routine maintenance

- Nutrient management - Apply nutrients in accordance with manufacturer's recommendations. Do not apply during rainfall events or windy conditions. Provide secondary containment and keep fertilizer properly secured when not being used.

Additional information and details can be found in the Arlington County Planning & Field Guide for Pollution Prevention (P2).


6.0 Stormwater Management Controls

Table with columns: Select all that apply, Stormwater Management Control, Estimated Installation Date, Responsible Party.

* In accordance with Arlington County's Chesapeake Bay Total Maximum Daily Load (TMDL) Action Plan, approved by the Virginia Department of Environmental Quality (DEQ) on September 1, 2015, linear development projects conducted by the County are administered and tracked as follows consistent with 9VAC25-870-60 A.4, 9VAC25-870-76, and 9VAC25-870-92:

- Pollutant load changes will be computed as described in Section 3.A of the Action Plan.
Retrofit opportunities will be evaluated for each project, using the screening and selection criteria applied and described in the adopted Stormwater Master Plan.
Retrofit projects that meet the screening criteria and are determined by Arlington to be feasible and cost-effective will be implemented with specific linear development projects.
In cases where retrofit projects are not feasible and cost-effective for a particular linear project, any POC load increases that might occur for that project will be addressed by larger overall POC load reductions in place or added through TMDL action plan implementation.


In the above manner Arlington, as the MS4 operator and the construction site operator for its linear development projects, implements linear projects and retrofit projects in a manner that achieves the most TMDL POC reduction for the least cost, while fully accounting for load changes that occur with linear development project activity consistent with the DEQ Chesapeake Bay TMDL Special Condition Guidelines.



- Pump from Settling Pit
Manufactured System:
Other:

- Material / chemical use and storage - Designate areas of the construction site for material delivery and storage. Locate these areas near construction entrances and away from waterways and storm drains. Enclose, cover or berm construction material storage areas if susceptible to stormwater.

Stockpiled soil and other loose materials that can be washed away shall be covered with a tarp, plastic sheeting, or other stabilization matting. The cover must be properly secured / anchored down to prevent it from being blown off and exposing materials to rain.



- Method used to ensure flow through:
Provide secondary containment for paint, pesticides, cleaners, solvents, and/or other chemicals and keep these items secured and covered when not in use
Regularly inspect containers.

- Equipment and vehicle maintenance - Use a designated area, away from storm drains and surface waters, to refuel vehicle or equipment or perform maintenance.

- Regularly inspect vehicles and equipment for leaks. Clean up all spills and leaks upon discovery.
Use containment measures when conducting fueling (e.g. place spill pad, board, plastic sheeting on ground)
Regularly inspect fuel containers.
Provide secondary containment and secure storage for fuel, oil, and/or lubricants
Keep drip pans, sheeting, and/or absorbent pads under heavy equipment when not in use (i.e. overnight) to capture leaks.

- Waste management / disposal - Designate a waste collection area on the construction site that does not receive a substantial amount of runoff from upland areas and does not drain directly to a waterway. Ensure that waste containers have lids so they can be covered before periods of rain. Schedule waste collection to prevent the containers from overflowing.

- A sufficient number of waste containers must be kept on a site to handle the quantity of waste produced.
Keep roll off containers covered and/or dumpster / trash lids closed.
Check waste containers frequently for damage / leaks and clean using DRY methods when necessary. Never clean out a dumpster by power washing or hosing it out.
Replace containers that are leaking, cracked, corroded, or otherwise deteriorating.
Do not bury waste material. Dispose of excess dry concrete, grout and mortar in the trash.

- Washing / cleaning - Prevent the discharge of wash water to the storm drain system or surface waters.

- Wash water or liquid wastes may not enter a storm drain or surface waters.
Provide a suitable containment system for cleaning equipment such as a drum, prefabricated system, lined container, or portable wash pad.
The wash / containment area must be sized appropriately for the needs of the project.
Locate wash / containment areas away from storm drains.

- Dewatering operations - Construction site dewatering may not be discharged without treatment. Sediment laden or turbid water shall be filtered, settled or similarly treated prior to discharge.

- Dewatering detail on approved ESC plan will be used.
Dewatering option from Planning & Field Guide for Pollution Prevention (P2):
Filter Box
Straw Bale/Silt Fence Pit
Portable Sediment Tank
Filter Bag

DEPARTMENT OF ENVIRONMENTAL SERVICES
FACILITIES & ENGINEERING DIVISION
ENGINEERING BUREAU
2100 CLARENDON BOULEVARD, SUITE 813
ARLINGTON, VA 22201
PHONE: 703.228.3629
FAX: 703.228.3606

COPYRIGHT © 2021 ARLINGTON COUNTY VIRGINIA - ALL RIGHTS RESERVED



APPROVALS DATE

Amy Pflaum 08/04/22

QUALITY CONTROL ENGINEER

8/5/22

CONSTRUCTION SECTION SUPERVISOR

8/4/22

WATER, SEWER, STREETS BUREAU CHIEF

08/03/22

TRANSPORTATION DIRECTOR

08/17/22

PROJECT MANAGER

REVISIONS DATE

DESIGNED: ML
DRAWN: ML
CHECKED: AP

PLOTTED: NOVEMBER 30 2022

SCALE: N/A

STORM DRAINAGE IMPROVEMENTS
S42D
HEADWATERS DONALDSON RUN TRIBUTARY B
(ANALOSTAN BRANCH)

STORMWATER POLLUTION PREVENTION PLAN

C035.1

HEADWATERS DONALDSON RUN TRIBUTARY B (ANALOSTAN BRANCH) S42D

Table with 4 columns: checkbox, description (Sheet flow to Vegetated Filter, Grass Channel, Rainwater Harvesting, Permeable Pavement, Infiltration, Bio-retention, Others), and reference to SWPPP cover page.

7.0 Spill Prevention & Response

Most spills can be cleaned up using a spill kit. Absorbent/dry, sealable containers, plastic bags, and shovels/brooms are suggested minimum spill response items that should be available at the project site.

- 1st Priority: Protect all people
2nd Priority: Protect equipment and property
3rd Priority: Protect the environment

- 1. Check for hazards (flammable material, noxious fumes, cause of spill) - If flammable liquid, turn off engines and nearby electrical equipment.
2. Ensure the spill area is safe to enter and that it does not pose an immediate threat to health or safety of any person.
3. Stop the spill source.
4. Call co-workers and supervisor for assistance and to make them aware of the spill and potential dangers.
5. If possible, stop spill from spreading and/or entering storm drains (use absorbent or other materials as necessary).
6. If spilled material has entered a storm drain, contact Arlington County Fire Department and project manager.
7. Clean up spilled material according to manufacturer specifications, for liquid spills use absorbent materials and do not flush area with water.
8. Properly dispose of cleanup materials and used absorbent material according to manufacturer specifications.

Emergency Contacts:

Local Contacts: Arlington County Fire & Police 703-558-2222, DES Water, Sewer, Streets 24-Hour Emergency 703-228-6555, Washington Gas Emergency 703-750-1400

Nights, Holidays & Weekends: VA Dept. of Emergency Management 804-674-2400, 24 Hour Reporting Service

Spill kit on site: Yes No

Location(s) of spill kit:

8.0 Self Inspection Report & Corrective Action Log (make additional copies as necessary)

Form fields for Company/Organization, Name of Inspector, Telephone Number, and Qualifications.

Inspection Schedule

Discharges to impaired waters, surface waters within a TMDL watershed, or exceptional waters:

Once every 4 business days

Inspection Date:

Describe phase of construction:

Is a copy of the SWPPP available on site? Yes No Is the SWPPP complete? Yes No

Table with 4 columns: Erosion & Sediment Controls/Pollution Prevention Practices, In Compliance?, Corrective Action Needed & Notes, and Date Corrective Action Taken.

Table with 5 columns: Date Grading Activity Initiated, Description of the Grading Activity, Date Grading Activity Ceased, Date Stabilization Measures Initiated, and Description of the Stabilization Measures.

Are there any unauthorized discharges at the time of this inspection? Yes No

Has any unauthorized discharge occurred since the last inspection? Yes No

Non - Compliance Issues: Describe any incidents of non-compliance not described above (use another page if necessary)

Certification: I certify under penalty of law that I have read and understand this document and that this document and all attachments were prepared in accordance with a system designed to assure that qualified personnel properly gathered and evaluated the information submitted.

Operator or Assigned Qualified Personnel Name:

Signature:

Date:

CONSTRUCTION GENERAL PERMIT (VAR10) REGISTRATION STATEMENT 2019

Table with 2 columns: HUC (PL24) and NAME(S) OF RECEIVING WATERBODY (Potomac River - Permit Run)

Section III. Off-site Support Activity Location Information.

Form fields for Off-site Activity Name, Address, City/County, Off-site Activity Entrance Location, Latitude and Longitude, and Will a separate VPDES permit cover this off-site activity?

Section IV. Other Information.

Form fields for A. Stormwater pollution prevention plan, B. Erosion and Sediment Control Plan, C. Land-disturbance commenced, D. Annual Standards and Specifications, E. Billing Information.

9.0 Grading & Stabilization Activities Log

Table with 5 columns: Date Grading Activity Initiated, Description of the Grading Activity, Date Grading Activity Ceased, Date Stabilization Measures Initiated, and Description of the Stabilization Measures.

10.0 SWPPP Modification & Update Log

Table with 3 columns: Modification Date, Description of the Modification / Update, and Modification Prepared By (name & title).

CONSTRUCTION GENERAL PERMIT (VAR10) REGISTRATION STATEMENT 2019

Section V. Certification. A person representing the operator as identified in Section I. A, and meeting the requirements of 9VAC25-880-70, Part III. K must physically sign this certification.

Operator means the owner or operator of any facility or activity subject to the Act and this chapter. In the context of stormwater associated with a large or small construction activity, operator means any person associated with a construction project that meets either of the following two criteria:

- a. For a corporation, by a responsible corporate officer.
b. For a partnership or sole proprietorship, by a general partner or the proprietor, respectively.
c. For a municipality, state, federal, or other public agency, by either a principal executive officer or ranking elected official.

Certification: I certify under penalty of law that I have read and understand this Registration Statement and that this document and all attachments were prepared in accordance with a system designed to assure that qualified personnel properly gathered and evaluated the information submitted.

Printed Name: Ankur Patel
Signature (typed in ink): Ankur Patel
Date Signed: 07/22/2022

Section VI. Submittal Instructions. Submit this form to the VSMP Authority. If the locality is the VSMP Authority, please send your Registration Statement submittal directly to the locality; do NOT send this form to DEQ.


Department of Environmental Quality
Office of Stormwater Management Suite 1400
PO Box 1105
Richmond VA 23218
construction@deq.virginia.gov

The Local VSMP Authority (insert address below)
Department of Environmental Services
Development Services Bureau
2100 Clarendon Blvd., Suite 800
Arlington, VA 22201

DEPARTMENT OF ENVIRONMENTAL SERVICES
FACILITIES & ENGINEERING DIVISION
ENGINEERING BUREAU
2100 CLARENDON BOULEVARD, SUITE 813
ARLINGTON, VA 22201
PHONE: 703.228.3629
FAX: 703.228.3606

COPYRIGHT © 2021 ARLINGTON COUNTY VIRGINIA - ALL RIGHTS RESERVED

SEAL



APPROVALS DATE

Approval list with names and dates: Amy Pfaffm (8/04/22), Construction Section Supervisor (8/5/22), Water, Sewer, Streets Bureau Chief (8/4/22), Transportation Director (08/03/22), Project Manager (08/17/22).

REVISIONS DATE

Table for tracking revisions with columns for revision number and date.


STORM DRAINAGE IMPROVEMENTS S42D S42D HEADWATERS DONALDSON RUN TRIBUTARY B (ANALOSTAN BRANCH) STORMWATER POLLUTION PREVENTION PLAN

DESIGNED: ML
DRAWN: ML
CHECKED: AP



PLOTTED: NOVEMBER 30 2022

SCALE: N/A

WALL PROFILE ALONG LEFT SIDE OF CHANNEL



WALL HEIGHT ABOVE LEFT SIDE OF CHANNEL




APPROVALS	DATE
<i>Amy Pflaum</i> QUALITY CONTROL ENGINEER	08/04/22
<i>[Signature]</i> CONSTRUCTION SECTION SUPERVISOR	8/5/22
<i>[Signature]</i> WATER, SEWER, STREETS BUREAU CHIEF	8/4/22
<i>Dennis M. Leach</i> TRANSPORTATION DIRECTOR	08/03/22
<i>Jennifer Tostad</i> PROJECT MANAGER	08/17/22

REVISIONS	DATE

STORM DRAINAGE IMPROVEMENTS
 S42D
 HEADWATERS DONALDSON RUN TRIBUTARY B
 (ANALOSTAN BRANCH)
 CHANNEL WALL PROFILE LEFT

DESIGNED: ML
 DRAWN: ML
 CHECKED: AP
 PLOTTED: NOVEMBER 30 2022
 SCALE: AS SHOWN

C043.1




REVISION ON 01/07/2021
 FILENAME: S42D-23D-PLAN_PROFILE.DWG PATH: Q:\DATA\S42D\DESIGN\CAD\ACTIVE PLOTTED BY: MLEOMARDI


REVISED ON 01/07/2021

FILENAME: S42D-23D-PLAN_PROFILE.DWG PATH: Q:\DATA\S42D\DESIGN\CAD\ACTIVE PLOTTED BY: MLEONARDI

WALL PROFILE ALONG RIGHT SIDE OF CHANNEL



WALL HEIGHT ABOVE RIGHT SIDE OF CHANNEL




APPROVALS	DATE
<i>Amy Pflaum</i> QUALITY CONTROL ENGINEER	08/04/22
<i>[Signature]</i> CONSTRUCTION SECTION SUPERVISOR	8/5/22
<i>[Signature]</i> WATER, SEWER, STREETS BUREAU CHIEF	8/4/22
<i>Dennis M. Leach</i> TRANSPORTATION DIRECTOR	08/03/22
<i>Jennifer Tostad</i> PROJECT MANAGER	08/17/22


REVISIONS	DATE

STORM DRAINAGE IMPROVEMENTS
 S42D
 HEADWATERS DONALDSON RUN TRIBUTARY B
 (ANALOSTAN BRANCH)
 CHANNEL WALL PROFILE RIGHT

DESIGNED: ML
 DRAWN: ML
 CHECKED: AP
 PLOTTED: NOVEMBER 30 2022
 SCALE: AS SHOWN

C043.2





APPROVALS DATE

Amy Pflaum 08/04/22 QUALITY CONTROL ENGINEER
Dennis M. Leach 8/5/22 CONSTRUCTION SECTION SUPERVISOR
Dennis M. Leach 8/4/22 WATER, SEWER, STREETS BUREAU CHIEF
Dennis M. Leach 08/03/22 TRANSPORTATION DIRECTOR
Jennifer Tastad 08/17/22 PROJECT MANAGER

REVISIONS DATE





























Table with 2 columns: REVISIONS, DATE. Contains several empty rows for revisions.

STORM DRAINAGE IMPROVEMENTS S42D HEADWATERS DONALDSON RUN TRIBUTARY B (ANALOSTAN BRANCH) CROSS SECTIONS STA 10+00 TO 12+70

DESIGNED: ML
DRAWN: ML
CHECKED: AP

PLOTTED: NOVEMBER 30 2022
SCALE: AS SHOWN

C044.1




LEGEND


- EXISTING GRADE
PROPOSED GRADE
RECP INSTALLATION EL.

NOTES

- 1. LOCATION OF SANITARY SEWER IS APPROXIMATE AND THE EXACT LOCATION MUST BE DETERMINED BY THE CONTRACTOR PRIOR TO CONSTRUCTION.
2. CONTRACTOR TO HAND DIG AND LOCATE THE SANITARY SEWER PRIOR TO STABILIZATION.
3. CONTRACTOR WILL BE RESPONSIBLE FOR ANY BREAKS AND CLEAN-UPS.

- 4. EXISTING SANITARY SEWER PIPES UNDER THE STREAM BED ARE TO BE CONCRETE ENCASED PER ARLINGTON COUNTY STD. M-3.0.
5. INSTALL EROSION CONTROL MATTING CM-700 OR APPROVED EQUAL 2.5 FT (UNLESS SPECIFIED OTHERWISE) ABOVE PROPOSED STREAM INVERT ALONG BANKS WITHOUT STACKED STONE WALLS. APPROXIMATE ELEVATIONS ARE SHOWN AT EACH APPLICABLE CROSS SECTION ABOVE. SEE SHEET C002.1 FOR DETAILS AND INSTALLATION REQUIREMENTS. SEE SHEET C075.1 FOR COMPUTED WATER SURFACE ELEVATIONS AT EACH CROSS SECTION.






APPROVALS	DATE
<i>Amy Pflaum</i> QUALITY CONTROL ENGINEER	08/04/22
<i>[Signature]</i> CONSTRUCTION SECTION SUPERVISOR	8/5/22
<i>[Signature]</i> WATER, SEWER, STREETS BUREAU CHIEF	8/4/22
<i>Dennis M. Leach</i> TRANSPORTATION DIRECTOR	08/03/22
<i>Jennifer Tastad</i> PROJECT MANAGER	08/17/22

REVISIONS	DATE

STORM DRAINAGE IMPROVEMENTS
 S42D
 HEADWATERS DONALDSON RUN TRIBUTARY B
 (ANALOSTAN BRANCH)
CROSS SECTIONS STA 12+80 TO 15+43

DESIGNED: ML
 DRAWN: ML
 CHECKED: AP
 PLOTTED: NOVEMBER 30 2022
SCALE: AS SHOWN

C044.2




LEGEND

- EXISTING GRADE
- PROPOSED GRADE
- RECP INSTALLATION EL.

NOTES


1. LOCATION OF SANITARY SEWER IS APPROXIMATE AND THE EXACT LOCATION MUST BE DETERMINED BY THE CONTRACTOR PRIOR TO CONSTRUCTION.
2. CONTRACTOR TO HAND DIG AND LOCATE THE SANITARY SEWER PRIOR TO STABILIZATION.
3. CONTRACTOR WILL BE RESPONSIBLE FOR ANY BREAKS AND CLEAN-UPS.

4. EXISTING SANITARY SEWER PIPES UNDER THE STREAM BED ARE TO BE CONCRETE ENCASED PER ARLINGTON COUNTY STD. M-3.0.
5. INSTALL EROSION CONTROL MATTING CM-700 OR APPROVED EQUAL 2.5 FT (UNLESS SPECIFIED OTHERWISE) ABOVE PROPOSED STREAM INVERT ALONG BANKS WITHOUT STACKED STONE WALLS. APPROXIMATE ELEVATIONS ARE SHOWN AT EACH APPLICABLE CROSS SECTION ABOVE. SEE SHEET C002.1 FOR DETAILS AND INSTALLATION REQUIREMENTS. SEE SHEET C075.1 FOR COMPUTED WATER SURFACE ELEVATIONS AT EACH CROSS SECTION.



REVISED ON 01/07/2021

FILENAME: S42D-234-CROSS_SECTIONS.DWG PATH: Q:\DATA\S42D\DESIGN\CD\ACTIVE PLOTTED BY: MLEONARDI



INSTALL CM-700 TO THE ELEVATION INDICATED ON THE CROSS SECTIONS IN THE VICINITY OF THE STOWE PROPERTY (APPROX. CROSS SECTIONS 16+10 TO DOWNSTREAM PROJECT LIMITS).


LEGEND

- EXISTING GRADE
- PROPOSED GRADE
- RECP INSTALLATION EL.

NOTES

1. LOCATION OF SANITARY SEWER IS APPROXIMATE AND THE EXACT LOCATION MUST BE DETERMINED BY THE CONTRACTOR PRIOR TO CONSTRUCTION.
2. CONTRACTOR TO HAND DIG AND LOCATE THE SANITARY SEWER PRIOR TO STABILIZATION.
3. CONTRACTOR WILL BE RESPONSIBLE FOR ANY BREAKS AND CLEAN-UPS.

4. EXISTING SANITARY SEWER PIPES UNDER THE STREAM BED ARE TO BE CONCRETE ENCASED PER ARLINGTON COUNTY STD. M-3.0.
5. INSTALL EROSION CONTROL MATTING CM-700 OR APPROVED EQUAL 2.5 FT (UNLESS SPECIFIED OTHERWISE) ABOVE PROPOSED STREAM INVERT ALONG BANKS WITHOUT STACKED STONE WALLS. APPROXIMATE ELEVATIONS ARE SHOWN AT EACH APPLICABLE CROSS SECTION ABOVE. SEE SHEET C002.1 FOR DETAILS AND INSTALLATION REQUIREMENTS. SEE SHEET C075.1 FOR COMPUTED WATER SURFACE ELEVATIONS AT EACH CROSS SECTION.



ARLINGTON VIRGINIA

DEPARTMENT OF ENVIRONMENTAL SERVICES
 FACILITIES & ENGINEERING DIVISION
 ENGINEERING BUREAU
 2100 CLARENDON BOULEVARD, SUITE 813
 ARLINGTON, VA 22201
 PHONE: 703.228.3629
 FAX: 703.228.3606

COPYRIGHT © 2021 ARLINGTON COUNTY VIRGINIA - ALL RIGHTS RESERVED

SEAL



APPROVALS DATE

<i>Amy Pflaum</i>	08/04/22
QUALITY CONTROL ENGINEER	
<i>[Signature]</i>	8/5/22
CONSTRUCTION SECTION SUPERVISOR	
<i>[Signature]</i>	8/4/22
WATER, SEWER, STREETS BUREAU CHIEF	
<i>Dennis M. Leach</i>	08/03/22
TRANSPORTATION DIRECTOR	
<i>Jennifer Tastad</i>	08/17/22
PROJECT MANAGER	

REVISIONS DATE

REVISIONS	DATE

STORM DRAINAGE IMPROVEMENTS
 HEADWATERS DONALDSON RUN TRIBUTARY B
 (ANALOSTAN BRANCH)


CROSS SECTIONS STA 15+50 TO 16+50

DESIGNED: ML
 DRAWN: ML
 CHECKED: AP

PLOTTED: NOVEMBER 30 2022

SCALE: AS SHOWN

C044.3



ALIGNMENT: Phase I and II

Curve/Line #	Length	Radius	Line/Chord Bearing	Chord Length	Delta (Δ)	Tangent	STA (Start)	STA (End)	Northing, Easting (Start)	Northing, Easting (End)
C1	1.10'	10.00'	N23° 52' 42.77"E	1.10'	6° 19' 43"	0.55	10+48.45	10+49.55	7014516.62, 11874703.34	7014517.63, 11874703.79
C2	4.92'	10.00'	N6° 36' 54.86"E	4.87'	28° 11' 53"	2.51	10+69.74	10+74.66	7014536.51, 11874710.93	7014541.35, 11874711.49
C3	4.73'	10.00'	N6° 04' 19.43"E	4.69'	27° 06' 42"	2.41	11+09.20	11+13.94	7014575.60, 11874706.99	7014580.26, 11874707.48
C4	2.75'	10.00'	N11° 44' 52.56"E	2.74'	15° 45' 36"	1.38	11+24.35	11+27.10	7014590.07, 11874710.98	7014592.75, 11874711.54
C5	4.24'	10.00'	N8° 17' 04.52"W	4.21'	24° 18' 18"	2.15	11+33.25	11+37.49	7014598.89, 11874711.95	7014603.06, 11874711.35
C6	2.40'	10.00'	N13° 33' 27.17"W	2.40'	13° 45' 33"	1.21	11+65.06	11+67.47	7014628.89, 11874701.72	7014631.22, 11874701.16
C7	0.58'	10.00'	N8° 20' 28.13"W	0.58'	3° 19' 35"	0.29	11+86.22	11+86.80	7014649.85, 11874698.98	7014650.42, 11874698.89
C8	0.70'	10.00'	N12° 00' 32.58"W	0.70'	4° 00' 34"	0.35	12+02.58	12+03.28	7014665.96, 11874696.15	7014666.65, 11874696.01
C9	5.43'	10.00'	N1° 33' 18.06"E	5.37'	31° 08' 15"	2.79	12+19.25	12+24.68	7014682.14, 11874692.14	7014687.50, 11874692.28
C10	5.94'	10.00'	N0° 06' 07.19"E	5.85'	34° 02' 37"	3.06	12+38.96	12+44.90	7014701.15, 11874696.49	7014707.00, 11874696.50
C11	4.47'	10.00'	N4° 06' 35.72"W	4.43'	25° 37' 11"	2.27	12+71.84	12+76.31	7014732.77, 11874688.66	7014737.20, 11874688.34
C12	5.76'	10.00'	N25° 12' 51.55"E	5.69'	33° 01' 43"	2.96	12+77.44	12+83.20	7014738.32, 11874688.51	7014743.46, 11874690.94
C13	4.77'	10.00'	N28° 03' 27.65"E	4.73'	27° 20' 31"	2.43	13+14.07	13+18.84	7014766.49, 11874711.48	7014770.66, 11874713.70
C14	3.74'	10.00'	N25° 05' 22.26"E	3.71'	21° 24' 20"	1.89	13+38.49	13+42.23	7014789.70, 11874718.58	7014793.06, 11874720.16
C15	1.47'	5.00'	N44° 11' 52.14"E	1.46'	16° 48' 40"	0.74	13+60.21	13+61.68	7014807.65, 11874730.68	7014808.70, 11874731.70
C16	7.44'	10.00'	N31° 18' 04.16"E	7.27'	42° 36' 16"	3.90	13+76.10	13+83.54	7014817.46, 11874743.16	7014823.67, 11874746.93
C17	2.03'	5.00'	N1° 36' 41.46"W	2.01'	23° 13' 16"	1.03	14+00.69	14+02.72	7014840.56, 11874749.91	7014842.57, 11874749.85
C18	1.73'	5.00'	N3° 16' 58.85"W	1.73'	19° 52' 41"	0.88	14+28.27	14+30.01	7014867.45, 11874744.01	7014869.17, 11874743.91
C19	9.21'	10.00'	N33° 01' 45.01"E	8.88'	52° 44' 47"	4.96	14+31.29	14+40.49	7014870.44, 11874744.06	7014877.89, 11874748.90
C20	3.55'	10.00'	N49° 13' 37.34"E	3.53'	20° 21' 02"	1.79	14+48.06	14+51.62	7014881.75, 11874755.42	7014884.05, 11874758.09
C21	3.14'	10.00'	N30° 02' 47.77"E	3.13'	18° 00' 37"	1.58	14+68.83	14+71.97	7014897.42, 11874768.94	7014900.13, 11874770.51
C22	12.85'	10.00'	N57° 50' 56.15"E	11.98'	73° 36' 54"	7.48	14+79.45	14+92.30	7014907.11, 11874773.19	7014913.49, 11874783.34
C23	6.68'	10.00'	N75° 31' 01.60"E	6.56'	38° 16' 43"	3.47	15+08.82	15+15.50	7014912.15, 11874799.80	7014913.79, 11874806.15
C24	6.32'	10.00'	N38° 17' 06.44"E	6.21'	36° 11' 07"	3.27	15+42.06	15+48.37	7014928.50, 11874828.26	7014933.37, 11874832.11
C25	6.32'	10.00'	N2° 05' 58.95"E	6.21'	36° 11' 07"	3.27	15+61.61	15+67.92	7014945.79, 11874836.68	7014952.00, 11874836.68
C26	5.65'	10.00'	N0° 10' 57.37"E	5.57'	32° 21' 04"	2.90	15+73.19	15+78.84	7014957.06, 11874835.46	7014962.63, 11874835.47
C27	6.40'	10.00'	N34° 41' 20.34"E	6.29'	36° 39' 42"	3.31	15+86.08	15+92.48	7014969.59, 11874837.52	7014974.76, 11874841.10
C28	6.82'	10.00'	N33° 28' 39.81"E	6.69'	39° 05' 03"	3.55	16+02.57	16+09.39	7014980.83, 11874849.16	7014986.41, 11874852.85
L1	48.45'		N27° 02' 34.11"E				10+00.00	10+48.45	7014473.47, 11874681.31	7014516.62, 11874703.34
L2	20.19'		N20° 42' 51.42"E				10+49.55	10+69.74	7014517.63, 11874703.79	7014536.51, 11874710.93
L3	34.54'		N7° 29' 01.71"W				10+74.66	11+09.20	7014541.35, 11874711.49	7014575.60, 11874706.99
L4	10.41'		N19° 37' 40.56"E				11+13.94	11+24.35	7014580.26, 11874707.48	7014590.07, 11874710.98
L5	6.15'		N3° 52' 04.56"E				11+27.10	11+33.25	7014592.75, 11874711.54	7014598.89, 11874711.95
L6	27.57'		N20° 26' 13.60"W				11+37.49	11+65.06	7014603.06, 11874711.35	7014628.89, 11874701.72
L7	18.75'		N6° 40' 40.75"W				11+67.47	11+86.22	7014631.22, 11874701.16	7014649.85, 11874698.98
L8	15.78'		N10° 00' 15.51"W				11+86.80	12+02.58	7014650.42, 11874698.89	7014665.96, 11874696.15
L9	15.97'		N14° 00' 49.65"W				12+03.28	12+19.25	7014666.65, 11874696.01	7014682.14, 11874692.14
L10	14.28'		N17° 07' 25.78"E				12+24.68	12+38.96	7014687.50, 11874692.28	7014701.15, 11874696.49
L11	26.94'		N16° 55' 11.39"W				12+44.90	12+71.84	7014707.00, 11874696.50	7014732.77, 11874688.66
L12	1.13'		N8° 41' 59.95"E				12+76.31	12+77.44	7014737.20, 11874688.34	7014738.32, 11874688.51
L13	30.86'		N41° 43' 43.15"E				12+83.20	13+14.07	7014743.46, 11874690.94	7014766.49, 11874711.48
L14	19.65'		N14° 23' 12.15"E				13+18.84	13+38.49	7014770.66, 11874713.70	7014789.70, 11874718.58
L15	17.98'		N35° 47' 32.36"E				13+42.23	13+60.21	7014793.06, 11874720.16	7014807.65, 11874730.68
L16	14.43'		N52° 36' 11.92"E				13+61.68	13+76.10	7014808.70, 11874731.70	7014817.46, 11874743.16
L17	17.15'		N9° 59' 56.41"E				13+83.54	14+00.69	7014823.67, 11874746.93	7014840.56, 11874749.91
L18	25.56'		N13° 13' 19.32"W				14+02.72	14+28.27	7014842.57, 11874749.85	7014867.45, 11874744.01
L19	1.28'		N6° 39' 21.62"E				14+30.01	14+31.29	7014869.17, 11874743.91	7014870.44, 11874744.06
L20	7.57'		N59° 24' 08.41"E				14+40.49	14+48.06	7014877.89, 11874748.90	7014881.75, 11874755.42
L21	17.21'		N39° 03' 06.27"E				14+51.62	14+68.83	7014884.05, 11874758.09	7014897.42, 11874768.94
L22	7.48'		N21° 02' 29.27"E				14+71.97	14+79.45	7014900.13, 11874770.51	7014907.11, 11874773.19
L23	16.52'		S85° 20' 36.98"E				14+92.30	15+08.82	7014913.49, 11874783.34	7014912.15, 11874799.80
L24	18.55'		N56° 22' 40.18"E				15+15.50	15+34.05	7014913.79, 11874806.15	7014924.06, 11874821.59
L25	8.01'		N56° 22' 40.18"E				15+34.05	15+42.06	7014924.06, 11874821.59	7014928.50, 11874828.26
L26	13.23'		N20° 11' 32.69"E				15+48.37	15+61.61	7014933.37, 11874832.11	7014945.79, 11874836.68
L27	5.27'		N15° 59' 34.79"W				15+67.92	15+73.19	7014952.00, 11874836.61	7014957.06, 11874835.46
L28	7.25'		N16° 21' 29.54"E				15+78.84	15+86.08	7014962.63, 11874835.47	7014969.59, 11874837.52
L29	10.09'		N53° 01' 11.14"E				15+92.48	16+02.57	7014974.76, 11874841.10	7014980.83, 11874849.16
L63	21.32'		N13° 56' 08.49"E				16+09.39	16+30.71	7014986.41, 11874852.85	7015007.10, 11874857.98
L64	4.62'		N19° 20' 00.61"E				16+30.71	16+35.33	7015007.10, 11874857.98	7015011.46, 11874859.51
L65	11.20'		N26° 26' 00.88"E				16+39.05	16+50.26	7015014.88, 11874860.95	7015024.92, 11874865.94

NOTES


- CROSS SECTIONS OF THE STREAM SHOWING VERTICAL INFORMATION FOR WALL SEGMENTS CAN BE FOUND ON SHEETS C044.1 TO C044.3
- REFER TO SHEET C002.1 FOR STACKED STONE WALL DETAIL AND SHEET C042.1 TO C042.3 FOR PLAN AND PROFILE VIEWS

BENCHMARK TABLE

BM#	NORTHING	EASTING
NA	7,014,493.93	11,874,744.03

DEPARTMENT OF ENVIRONMENTAL SERVICES
 FACILITIES & ENGINEERING DIVISION
 ENGINEERING BUREAU
 2100 CLARENDON BOULEVARD, SUITE 813
 ARLINGTON, VA 22201
 PHONE: 703.228.3629
 FAX: 703.228.3606

COPYRIGHT © 2021 ARLINGTON COUNTY VIRGINIA - ALL RIGHTS RESERVED



APPROVALS DATE

- | | |
|------------------------------------|----------|
| <i>Amy Pfau</i> | 08/04/22 |
| QUALITY CONTROL ENGINEER | |
| <i>[Signature]</i> | 8/5/22 |
| CONSTRUCTION SECTION SUPERVISOR | |
| <i>[Signature]</i> | 8/4/22 |
| WATER, SEWER, STREETS BUREAU CHIEF | |
| <i>Dennis M. Leach</i> | 08/03/22 |
| TRANSPORTATION DIRECTOR | |
| <i>Jennifer Tastad</i> | 08/17/22 |
| PROJECT MANAGER | |


REVISIONS DATE

NO.	DESCRIPTION	DATE

STORM DRAINAGE IMPROVEMENTS
 S42D
 HEADWATERS DONALDSON RUN TRIBUTARY B
 (ANALOSTAN BRANCH)
 GEOMETRIC CONTROL PLAN


DESIGNED: ML
 DRAWN: ML
 CHECKED: AP

PLOTTED: NOVEMBER 30 2022



C045.1

WALL SEGMENT 1




ALIGNMENT: WALL SEGMENT 1 LT BASE OF WALL

Curve/Line #	Length	Radius	Line/Chord Bearing	Chord Length	Delta (Δ)	Tangent	STA (Start)	STA (End)	Northing, Easting (Start)	Northing, Easting (End)
L31	4.00'		N27° 02' 34.11"E				10+00.00	10+04.00	7014474.20, 11874679.87	7014477.77, 11874681.69
L32	6.12'		N15° 45' 42.35"E				10+04.00	10+10.12	7014477.77, 11874681.69	7014483.65, 11874683.35
L33	28.96'		N27° 02' 34.11"E				10+10.12	10+39.08	7014483.65, 11874683.35	7014509.45, 11874696.52

ALIGNMENT: WALL SEGMENT 1 RT BASE OF WALL

Curve/Line #	Length	Radius	Line/Chord Bearing	Chord Length	Delta (Δ)	Tangent	STA (Start)	STA (End)	Northing, Easting (Start)	Northing, Easting (End)
L34	4.00'		N27° 02' 34.11"E				10+00.00	10+04.00	7014471.65, 11874684.87	7014475.21, 11874686.69
L35	6.12'		N15° 51' 13.08"E				10+04.00	10+10.12	7014475.21, 11874686.69	7014481.10, 11874688.36
L36	28.96'		N27° 02' 34.11"E				10+10.12	10+39.08	7014481.10, 11874688.36	7014506.90, 11874701.53

WALL SEGMENT 3




ALIGNMENT: WALL SEGMENT 3 LT BASE OF WALL

Curve/Line #	Length	Radius	Line/Chord Bearing	Chord Length	Delta (Δ)	Tangent	STA (Start)	STA (End)	Northing, Easting (Start)	Northing, Easting (End)
C39	3.43'	7.19'	N28° 03' 27.65"E	3.40'	27° 20' 31"	1.75	13+14.91	13+18.34	7014768.36, 11874709.38	7014771.36, 11874710.98
C40	4.79'	12.81'	N25° 05' 22.26"E	4.76'	21° 24' 20"	2.42	13+37.99	13+42.77	7014790.40, 11874715.86	7014794.71, 11874717.88
C41	2.29'	7.81'	N44° 11' 52.14"E	2.28'	16° 48' 40"	1.15	13+60.76	13+63.05	7014809.29, 11874728.40	7014810.93, 11874729.99
C42	3.22'	7.19'	N39° 46' 36.75"E	3.19'	25° 39' 10"	1.64	13+77.48	13+80.70	7014819.69, 11874741.45	7014822.15, 11874743.49
L49	16.93'		N41° 43' 43.15"E				12+97.97	13+14.91	7014755.73, 11874698.11	7014768.36, 11874709.38
L50	19.65'		N14° 23' 12.15"E				13+18.34	13+37.99	7014771.36, 11874710.98	7014790.40, 11874715.86
L51	17.98'		N35° 47' 32.36"E				13+42.77	13+60.76	7014794.71, 11874717.88	7014809.29, 11874728.40
L52	14.43'		N52° 36' 11.92"E				13+63.05	13+77.48	7014810.93, 11874729.99	7014819.69, 11874741.45

ALIGNMENT: WALL SEGMENT 3 RT BASE OF WALL

Curve/Line #	Length	Radius	Line/Chord Bearing	Chord Length	Delta (Δ)	Tangent	STA (Start)	STA (End)	Northing, Easting (Start)	Northing, Easting (End)
C43	6.11'	12.81'	N28° 03' 27.65"E	6.06'	27° 20' 31"	3.12	13+13.46	13+19.58	7014764.62, 11874713.58	7014769.97, 11874716.42
C44	2.69'	7.19'	N25° 05' 22.26"E	2.67'	21° 24' 20"	1.36	13+39.23	13+41.91	7014789.00, 11874721.31	7014791.42, 11874722.44
C45	0.64'	2.19'	N44° 11' 52.14"E	0.64'	16° 48' 40"	0.32	13+59.90	13+60.54	7014806.01, 11874732.96	7014806.47, 11874733.40
C46	5.74'	12.81'	N39° 46' 36.75"E	5.69'	25° 39' 10"	2.92	13+74.97	13+80.70	7014815.23, 11874744.86	7014819.60, 11874748.50
L53	16.93'		N41° 43' 43.15"E				12+96.53	13+13.46	7014751.98, 11874702.30	7014764.62, 11874713.58
L54	19.65'		N14° 23' 12.15"E				13+19.58	13+39.23	7014769.97, 11874716.42	7014789.00, 11874721.31
L55	17.98'		N35° 47' 32.36"E				13+41.91	13+59.90	7014791.42, 11874722.44	7014806.01, 11874732.96
L56	14.43'		N52° 36' 11.92"E				13+60.54	13+74.97	7014806.47, 11874733.40	7014815.23, 11874744.86

WALL SEGMENT 2




ALIGNMENT: WALL SEGMENT 2 LT BASE OF WALL

Curve/Line #	Length	Radius	Line/Chord Bearing	Chord Length	Delta (Δ)	Tangent	STA (Start)	STA (End)	Northing, Easting (Start)	Northing, Easting (End)
C29	3.54'	7.19'	N6° 36' 54.86"E	3.50'	28° 11' 53"	1.81	10+69.55	10+73.09	7014537.51, 11874708.30	7014540.99, 11874708.70
C30	6.06'	12.81'	N6° 04' 19.43"E	6.01'	27° 06' 42"	3.09	11+07.63	11+13.69	7014575.23, 11874704.20	7014581.21, 11874704.84
C31	1.98'	7.19'	N11° 44' 52.56"E	1.97'	15° 45' 36"	1.00	11+24.10	11+26.08	7014591.01, 11874708.33	7014592.94, 11874708.73
C32	3.05'	7.19'	N8° 17' 04.52"W	3.03'	24° 18' 18"	1.55	11+32.23	11+35.28	7014599.08, 11874709.15	7014602.08, 11874708.71
C33	3.08'	12.81'	N13° 33' 27.17"W	3.07'	13° 45' 33"	1.55	11+62.85	11+65.93	7014627.91, 11874699.09	7014630.90, 11874698.37
L37	9.61'		N20° 42' 51.42"E				10+59.94	10+69.55	7014528.52, 11874704.90	7014537.51, 11874708.30
L38	34.54'		N7° 29' 01.71"W				10+73.09	11+07.63	7014540.99, 11874708.70	7014575.23, 11874704.20
L39	10.41'		N19° 37' 40.56"E				11+13.69	11+24.10	7014581.21, 11874704.84	7014591.01, 11874708.33
L40	6.15'		N3° 52' 04.56"E				11+26.08	11+32.23	7014592.94, 11874708.73	7014599.08, 11874709.15
L41	27.57'		N20° 26' 13.60"W				11+35.28	11+62.85	7014602.08, 11874708.71	7014627.91, 11874699.09
L42	11.52'		N6° 40' 40.75"W				11+65.93	11+77.45	7014630.90, 11874698.37	7014642.34, 11874697.03

ALIGNMENT: WALL SEGMENT 2 RT BASE OF WALL


Curve/Line #	Length	Radius	Line/Chord Bearing	Chord Length	Delta (Δ)	Tangent	STA (Start)	STA (End)	Northing, Easting (Start)	Northing, Easting (End)
C34	6.30'	12.81'	N6° 36' 54.86"E	6.24'	28° 11' 53"	3.22	10+70.17	10+76.47	7014535.52, 11874713.55	7014541.72, 11874714.27
C35	3.40'	7.19'	N6° 04' 19.43"E	3.37'	27° 06' 42"	1.73	11+11.01	11+14.42	7014575.97, 11874709.77	7014579.32, 11874710.13
C36	3.52'	12.81'	N11° 44' 52.56"E	3.51'	15° 45' 36"	1.77	11+24.83	11+28.35	7014589.12, 11874713.63	7014592.56, 11874714.34
C37	5.43'	12.81'	N8° 17' 04.52"W	5.39'	24° 18' 18"	2.76	11+34.50	11+39.94	7014598.70, 11874714.76	7014604.04, 11874713.98
C38	1.73'	7.19'	N13° 33' 27.17"W	1.72'	13° 45' 33"	0.87	11+67.51	11+69.24	7014629.87, 11874704.35	7014631.55, 11874703.95
L43	9.61'		N20° 42' 51.42"E				10+60.56	10+70.17	7014526.53, 11874710.16	7014535.52, 11874713.55
L44	34.54'		N7° 29' 01.71"W				10+76.47	11+11.01	7014541.72, 11874714.27	7014575.97, 11874709.77
L45	10.41'		N19° 37' 40.56"E				11+14.42	11+24.83	7014579.32, 11874710.13	7014589.12, 11874713.63
L46	6.15'		N3° 52' 04.56"E				11+28.35	11+34.50	7014592.56, 11874714.34	7014598.70, 11874714.76
L47	27.57'		N20° 26' 13.60"W				11+39.94	11+67.51	7014604.04, 11874713.98	7014629.87, 11874704.35
L48	11.52'		N6° 40' 40.75"W				11+69.24	11+80.75	7014631.55, 11874703.95	7014642.99, 11874702.61

WALL SEGMENT 4



ALIGNMENT: WALL SEGMENT 4 RT BASE OF WALL

Curve/Line #	Length	Radius	Line/Chord Bearing	Chord Length	Delta (Δ)	Tangent	STA (Start)	STA (End)	Northing, Easting (Start)	Northing, Easting (End)
C47	4.55'	12.81'	N49° 13' 37.34"E	4.53'	20° 21' 02"	2.30	14+46.59	14+51.14	7014879.33, 11874756.85	7014882.28, 11874760.28
C48	1.53'	12.81'	N35° 38' 14.94"E	1.53'	6° 49' 43"	0.76	14+68.36	14+69.88	7014895.65, 11874771.12	7014896.89, 11874772.01
L57	2.20'		N59° 24' 08.41"E				14+44.39	14+46.59	7014878.21, 11874754.95	7014879.33, 11874756.85
L58	17.21'		N39° 03' 06.27"E				14+51.14	14+68.36	7014882.28, 11874760.28	7014895.65, 11874771.12



APPROVALS DATE

Amy Pflaum 08/04/22
QUALITY CONTROL ENGINEER
[Signature] 8/5/22
CONSTRUCTION SUPERVISOR
[Signature] 8/4/22
WATER, SEWER, STREETS BUREAU CHIEF
Dennis M. Leach 08/03/22
TRANSPORTATION DIRECTOR
Jennifer Tastad 08/17/22
PROJECT MANAGER


REVISIONS DATE

NO.	DESCRIPTION	DATE

STORM DRAINAGE IMPROVEMENTS
S42D
HEADWATERS DONALDSON RUN TRIBUTARY B
(ANALOSTAN BRANCH)
GEOMETRIC CONTROL PLAN

DESIGNED: ML
DRAWN: ML
CHECKED: AP

PLOTTED: NOVEMBER 30 2022



C045.2

REVISED ON 01/07/2021

FILENAME: S42D-250-DRAINAGE_DIVIDES.DWG PATH: Q:\DATA\S42D\DESIGN\ACTIVE PLOTTED BY: MLEONARDI

PROJECT BACKGROUND NARRATIVE

THE DONALDSON RUN STREAM STABILIZATION PROJECT CONSISTS OF THE STABILIZATION OF THE EXISTING STREAM BANKS AND OUTFALL PIPES ALONG DONALDSON RUN. STABILIZATION WILL BEGIN AT THE OUTFALL THAT IS LOCATED ON 4621 24TH RD AND WILL EXTEND SOUTH OF THE MISSIONHURST PROPERTY, AS SHOWN ON THE PLANS.

THE SEVERITY OF EROSION OF THE EXISTING STREAM BANKS HAS UNDERMINED OUTFALL PIPES AND PRIVATELY-OWNED RETAINING WALLS ALONG THE ANALOSTAN SUBDIVISION, AND WILL EVENTUALLY TAKE ITS TOLL ON LARGER STRUCTURES, IF NOT IMMEDIATELY ADDRESSED. SINCE THE BANKS TO BE STABILIZED ARE ON PRIVATE PROPERTY, TEMPORARY EASEMENTS HAVE BEEN ACQUIRED. ALSO, THIS PROJECT MEETS REGULATORY REQUIREMENTS FOR AN ADEQUATE OUTFALL. THE PLANS INCLUDE AN OUTFALL LOCATION MAP, CONTRIBUTING DRAINAGE AREAS, AND DETAILED HYDROLOGIC AND HYDRAULIC CALCULATIONS.

OUTFALL ANALYSIS NARRATIVE

THE IMPROVEMENTS ON THIS PLAN IMPACT THE DRAINAGE AREA SERVED BY SEVERAL EXISTING STORM DRAINAGE SYSTEMS (ALONG 25TH ST N, 24TH RD N, AND N. WAKEFIELD CT).

THESE STORM SEWERS DISCHARGE INTO THE HEADWATERS OF DONALDSON RUN TRIBUTARY B, APPROXIMATELY 600LF UPSTREAM OF A COUNTY STREAM RESTORATION PROJECT CONSTRUCTED IN 2007. STRUCTURE #2430 IS THE OUTFALL STRUCTURE AND CONSISTS OF A HEADWALL CONSTRUCTED OF CONCRETE RUBBLE. THE NATURAL CHANNEL HAS BEEN EVALUATED USING THE ROSGEN CLASSIFICATION AS A4 DUE TO THE CHANNEL SLOPE OF 2.44% - 7.9%, LOW SINUOSITY, ENRICHMENT RATIO. THE NATURAL CHANNEL BED MATERIALS CONSIST OF EASILY ERODED SILTY SAND WITH GRAVEL AND COBBLES. THERE WERE NO RECORDED DRAINAGE EASEMENTS FOR PORTIONS OF THE PIPED SYSTEM, THE OUTFALL, OR STREAM CHANNEL. AS PART OF THIS PLAN, A COMBINATION OF TEMPORARY AND PERMANENT EASEMENTS HAVE ALREADY BEEN RECORDED.



THE TOTAL AREA DRAINING TO THE OUTFLOW CHANNEL IS 22.5 ACRES. THIS AREA IS MOSTLY URBAN SINGLE FAMILY HOMES WITH THE ASSOCIATED LAWNS, HOWEVER, A SIGNIFICANT LAND AREA CONSISTS OF WOODLANDS. CLEARING FOR THE CONSTRUCTION OF THE CHANNEL IMPROVEMENTS WILL CONVERT SOME LAND FROM "WOODS-FAIR" TO "WOODS-POOR". THE PLANTING AND LANDSCAPING ON THIS LAND WILL EVENTUALLY RESTORE THE WOODED CONDITION, BUT IMMEDIATELY AFTER THE CONSTRUCTION, THE TREES WILL BE SMALL AND IMMATURE; HENCE THE HYDROLOGIC COMPUTATIONS TREATED THE AREA AS "WOODS-POOR". SEE SHEET C075.1 FOR ALL STORM COMPUTATIONS.

UPON COMPLETION OF THE IMPROVEMENTS PROPOSED HEREIN, THE OUTFALL FROM #2430 WILL BE STABILIZED AGAINST THE EXPECTED EROSION VELOCITIES.

DOWNSTREAM ANALYSIS - 1% RULE

ANALYSIS OF THE DOWNSTREAM CHANNEL WAS COMPLETED USING THE FLOW CRITERION. SINCE THE Q10 FOR THE LOD ONLY IN THE POST DEVELOPED CONDITION IS 0.68 CFS, THE DOWNSTREAM CHANNEL WAS ANALYZED TO A POINT WHERE THE FLOW EXCEEDED 68 CFS. THE 0.68 CFS WAS CALCULATED USING THE TR55 METHOD. A WEIGHTED CURVE NUMBER OF 59 WAS USED FOR THE ORIGINAL LOD OF 0.4 ACRES AND A TIME OF CONCENTRATION OF 0.1 HOURS. THE ORIGINAL PROJECT LIMITS OF DISTURBANCE IS SIGNIFICANTLY SMALLER THAN SHOWN AS THE SCOPE ONLY INCLUDED WORK TO INSTALL A NEW STORM SEWER PIPE TO THE HEADWATERS AS WELL AS WORK ON THE TURNAROUND AT THE END OF 24TH RD NORTH (THE TURNAROUND HAS SINCE BEEN REMOVED FROM THE PROPOSED IMPROVEMENTS) AND ~150FT OF STREAM RESTORATION.

THIS POINT WHERE THE TOTAL DRAINAGE AREA EQUALS 22.5 ACRES - SEE ON THIS SHEET - GIVES A Q10 OF 85CFS. THE POINT CHOSEN IS AT THE BEGINNING OF THE PREVIOUS STREAM RESTORATION PROJECT CONSTRUCTED UNDER CONTRACT 313-06. THE ANALYSIS OF THE STREAM SECTIONS IS SHOWN ON SHEET C075.1. BY THE START OF THE PREVIOUSLY CONSTRUCTED PROJECT THE Q10 FLOW IS 85 CFS, WHICH IS GREATER THAN THE 1% RULE FLOW NEEDED OF 68CFS. SINCE THE PROJECT HAD INITIALLY ONLY CONSIDERED A PORTION OF THE STREAM UPSTREAM OF THAT POINT, THE PROJECT SCOPE WAS CHANGED TO INCLUDE THE STABILIZATION FROM THE HEADWATERS TO THAT POINT. THE PLANS INCLUDE THE ENTIRETY OF THE STREAM STABILIZATION NEEDED TO SATISFY AN ADEQUATE OUTFALL ANALYSIS.



APPROVALS	DATE
<i>Amy Pflaum</i>	08/04/22
QUALITY CONTROL ENGINEER	
<i>[Signature]</i>	8/5/22
CONSTRUCTION SECTION SUPERVISOR	
<i>[Signature]</i>	8/4/22
WATER, SEWER, STREETS BUREAU CHIEF	
<i>Dennis M. Leach</i>	08/03/22
TRANSPORTATION DIRECTOR	
<i>Jennifer Tastad</i>	08/17/22
PROJECT MANAGER	


REVISIONS	DATE

STORM DRAINAGE IMPROVEMENTS
S42D-250
HEADWATERS DONALDSON RUN TRIBUTARY B
(ANALOSTAN BRANCH)

DRAINAGE DIVIDES

DESIGNED: ML
DRAWN: ML
CHECKED: AP

PLOTTED: NOVEMBER 30 2022



C071.1

NOT FOR CONSTRUCTION
THIS SHEET FOR CALCULATION PURPOSES ONLY

OUTFALL ANALYSIS

THE IMPROVEMENTS IN THIS PLAN IMPACT THE DRAINAGE AREA SERVED BY EXISTING STORM DRAINAGE SYSTEMS:

- 1. STRUCTURE #22631 TO #2430 - SERVES 25" ST. N AND AREAS TO THE NORTH
2. STRUCTURE #2663 TO #2430 - SERVES 24" RD. N AND AREAS SOUTH OF ITEM #1 ABOVE
3. STRUCTURE # 2665 TO # 2521 - DRAINS OVERLAND AND VIA ERODED CHANNELS TO THE OPEN CHANNEL LOCATED AT THE OUTFALL #2430 - SERVES 24" ST. N.

THESE STORM DRAINS DISCHARGE INTO THE HEADWATERS OF DONALDSON RUN TRIBUTARY B, APPROXIMATELY 600 LF. UPSTREAM OF A COUNTY STREAM RESTORATION PROJECT CONSTRUCTED IN 2007. STRUCTURE #2430 IS THE OUTFALL STRUCTURE AND CONSISTS OF A HEADWALL CONSTRUCTED OF CONCRETE RUBBLE. THE NATURAL CHANNEL HAS BEEN EVALUATED USING THE ROSEN CLASSIFICATION AS A4 DUE TO THE CHANNEL SLOPE OF 2.44% - 7.9%...

THE TOTAL AREA DRAINING TO THE OUTFLOW CHANNEL IS 22.5 ACRES. THIS AREA IS MOSTLY URBAN SINGLE FAMILY HOMES WITH THE ASSOCIATED LAWNS. HOWEVER, A SIGNIFICANT LAND AREA CONSISTS OF WOODLANDS. CLEARING FOR THE CONSTRUCTION OF THE CHANNEL IMPROVEMENTS WILL CONVERT SOME LAND FROM WOODS - FAIR TO WOODS - POOR. THE PLANTING AND LANDSCAPING ON THIS LAND WILL EVENTUALLY RESTORE THE WOODED CONDITION...

THE TIME OF CONCENTRATION WAS UNAFFECTED BY THE LAND USE CHANGES AND WAS COMPUTED TO BE 0.223 HRS. FOR BOTH PRE AND POST CONDITIONS. THE CURVE NUMBER CHANGED FROM 64 TO 65 DUE TO THE LAND USE CHANGES. FLOWS FOR THE PRE AND POST CONDITION ARE LISTED BELOW:

Table with 4 columns: RETURN PERIOD, PRE-DEVELOPMENT Q, POST-DEVELOPED Q, V POST. Rows for 2 YR, 10 YR, 100 YR.

IT CAN BE SEEN THAT THE PRE AND POST FLOWS DO NOT CHANGE BY MUCH. HOWEVER, THE VELOCITY IN THE CHANNEL EXCEEDS 4 FPS AND WILL ERODE THE SILTY SANDY CHANNEL BOTTOM. HENCE THE CHANNEL IS PROPOSED TO BE STABILIZED WITH A FLUNGE POOL AT THE OUTFALL STRUCTURE...

UPON COMPLETION OF THE IMPROVEMENTS PROPOSED HEREIN, THE OUTFALL FROM STRUCTURE #2430 WILL BE STABILIZED AGAINST THE EXPECTED EROSION VELOCITIES. IN ADDITION, THE STORM SYSTEM WILL HAVE CONTIGUOUS DRAINAGE EASEMENTS MAKING FUTURE MAINTENANCE POSSIBLE.

DOWNSTREAM ANALYSIS - 1% RULE

ANALYSIS OF THE DOWNSTREAM CHANNEL WAS COMPLETED USING THE FLOW CRITERION. SINCE THE Q 10 FOR THE LOD ONLY IN THE POST DEVELOPED CONDITION IS 0.68 CFS, THE DOWNSTREAM CHANNEL WAS ANALYZED TO A POINT WHERE THE FLOW EXCEEDED 68 CFS. THE POINT CHOSEN WAS AT THE BEGINNING OF THE PREVIOUS STREAM RESTORATION PROJECT...

Table with 3 columns: RETURN PERIOD, POST-DEVELOPED Q, V POST. Rows for 2 YR, 10 YR, 100 YR.

IN SOME AREAS, BUT NOT ALL, THE V 2 OR V 10 FOR THE EXISTING CHANNEL IS NOT STABLE AND SO PHASE II WILL BE REQUIRED TO COMPLETE THE STABILIZATION OF THE ENTIRE STREAM.

HYDROLOGIC AND HYDRAULIC ANALYSIS

HYDROLOGIC ANALYSIS

THE RATIONAL METHOD WAS USED TO DEVELOPED THE PEAK DESIGN FLOWS INTO THE STREAM. SEE THE SPREADSHEET PRINTOUT BELOW FOR THE PEAK 1YR, 2YR, AND 10YR FLOWS.

Table with 3 columns: Drainage Area, Pervious, Impervious. Values: 979,493 sf, 560,545 sf, 418,948 sf.

Weighted C 0.56

Table with 2 columns: Intensity (1-year), Intensity (2-year), Intensity (10-year), Intensity (100-year). Values: 4.40, 5.21, 6.79, 9.1.

Q=c*I*A

Table with 2 columns: Flow (1-year), Flow (2-year), Flow (10-year). Values: 55.45 cfs, 62.65 cfs, 85.55 cfs.

HYDRAULIC ANALYSIS

THE EXISTING CHANNEL IS HIGHLY ERODED. SELECTION OF A SUITABLE CHANNEL LINING MATERIAL TO DECREASE EROSION AND LOCAL INSTABILITY IS KEY TO STABILIZING THE CHANNEL. FILLING IN THE CHANNEL AND FLATTENING THE CHANNEL GRADE ARE TWO STRATEGIES IMPLEMENTED IN THE PROPOSED STABILIZATION...

TO FULLY ANALYZE THE EFFECT OF THE PROPOSED CHANNEL DIMENSIONS, PROFILE, AND GRADE CONTROL STRUCTURES ON THE STABILITY OF THE PROPOSED CHANNEL FOR THE DESIGN FLOWS, A HEC-RAS HYDRAULIC MODEL WAS DEVELOPED. TYPICAL SECTIONS USED IN THE HEC-RAS MODEL ARE PROVIDED ON THIS SHEET WITH BANK STATIONS AND THE DESIGN 10YR WATER SURFACE ELEVATION ALSO SHOWN.

CROSS SECTIONS WERE CUT AT EACH CROSS VANE AND THE SLUNGE POOL AT THE UPSTREAM END OF THE REACH. FOUR CROSS SECTIONS WERE CUT FOR EACH CROSS VANE, CORRESPONDING TO THE FOUR PVI POINTS LISTED FOR EACH VANE ON SHEET C042.1. TO MORE ACCURATELY CAPTURE THE WATER SURFACE ELEVATION THROUGH THE GRADE CONTROL STRUCTURES, CROSS SECTIONS WERE INTERPOLATED BETWEEN EACH OF THE FOUR CROSS VANE SECTIONS...

THE 'CROSS-SECTION SUMMARY' TABLE BELOW LISTS VELOCITY AND SHEAR VALUES IN THE CHANNEL AT THESE LOCATIONS.

CROSS-SECTION SUMMARY

Large table with columns: RAS River Station, Stream Station, Channel Invert (ft), Water Surface Elevation (ft), Velocity (ft/s), Shear Stress (lb/ft^2), D50 (in) for 1-Year Storm, 2-Year Storm, and 10-Year Storm.

TYPICAL HEC-RAS CROSS-SECTIONS




Table 7-1 Allowable Velocity and Shear Stress Values for Lined Channels. Columns: Type of Lining, Maximum Allowable Velocity (ft/s), Maximum Allowable Shear Stress (lb/ft^2).

Table 7-2 Recommended Manning's n Values for Lined Channels. Columns: Lining Type, Minimum, Typical, Maximum.

CHANNEL SUBSTRATE AND SEDIMENT TRANSPORT

CHANNEL BED AND BANK LINING MATERIALS WERE SELECTED BASED ON THE ANTICIPATED RANGE OF TRACTIVE FORCES IN THE CHANNEL. THE MEDIAN STONE SIZE (D50) FOR THE CHANNEL BED MATERIAL WAS SELECTED USING THE SHIELD'S EQUATION (SEE SAMPLE CALCULATION TO THE RIGHT)...

A PERMANENT ROLLED EROSION CONTROL PRODUCT (REC-P) WILL BE USED TO STABILIZE THE CHANNEL BANKS IN SECTIONS OF THE CHANNEL WITHOUT STACKED STONE WALLS. VDOT EC-3 TYPE 1 IS APPROPRIATE FOR TRACTIVE FORCES OF APPROX. 2.25 TO 6 LB/SF (VDOT DRAINAGE MANUAL 7.4.6.3.1, SEE TABLE 7-1 ON THIS SHEET)...

THE AVERAGE DEPTH OF FLOW IN THE CHANNEL FOR THE 10YR STORM IS APPROX. 2.1 FT. THE REC LINING FOR CHANNEL BANKS WITHOUT WALLS WILL BE INSTALLED 2.5 FT ABOVE THE PROPOSED STREAM INVERT (ELEVATIONS INDICATED ON THE CROSS SECTIONS ON SHEETS C044.1 TO C044.3).

SHIELD'S EQUATION

tau_s = shear stress = gamma*S
where:
gamma = specific weight of water (lb/ft^3)
R = hydraulic radius = A/P (ft)
A = cross-sectional flow area (ft^2)
P = wetted perimeter (ft)
S = maximum riffle slope (ft/ft)

STABLE MEAN DIAMETER BED MATERIAL

D50 = 3.07 * (tau_s / (16.1 * gamma))^(0.8244)
tau_s = 1.66 lb/ft^2
D50 = 3.07 * (1.66 / (16.1 * 62.4))^(0.8244)
D50 = 5.2 in

CROSS-VANE SUMMARY

Table with columns: Station, Cross-Vane ID, Elevation (Upper), Elevation (Lower), Height (ft), Scour Hole Length (ft), Scour Hole Depth (ft). Rows for stations 10+39.08 to 16+37.09.

STORM SEWER ANALYSIS

STORM SEWER COMPUTATIONS

Table with columns: Structure, Drainage Area (acre), C, CA, Tc, I, Q, Slope (%), n, DIA (in), DISCHARGE CAPACITY, VELOCITY, LENGTH, TIME IN PIPE, Upper Inv, Lower Inv, Remarks, TOP, Q/OFULL.

HYDRAULIC GRADELINE COMPUTATIONS


Table with columns: Structure Number, Surface, Inlet, Outlet, V, HGL @ Structure, Top of Struct, HGL @ Inlet, HGL @ Outlet, HGL @ Back of Top Struct, HGL @ Back of Bottom Struct.

ARLINGTON VIRGINIA

DEPARTMENT OF ENVIRONMENTAL SERVICES FACILITIES & ENGINEERING DIVISION ENGINEERING BUREAU 2100 CLARENDON BOULEVARD, SUITE 813 ARLINGTON, VA 22201

PHONE: 703.228.3629 FAX: 703.228.3606

COPYRIGHT © 2021 ARLINGTON COUNTY VIRGINIA - ALL RIGHTS RESERVED



APPROVALS DATE

Approval signatures and dates: Amy Pflaum (08/04/22), Construction Section Supervisor (8/5/22), Water, Sewer, Streets Bureau Chief (8/4/22), Transportation Director (08/03/22), Project Manager (08/17/22).

REVISIONS DATE

Table with 2 columns: REVISIONS, DATE. Multiple empty rows for revisions.

STORM DRAINAGE IMPROVEMENTS S42D HEADWATERS DONALDSON RUN TRIBUTARY B (ANALOSTAN BRANCH) STORM SEWER COMPUTATIONS

DESIGNED: ML DRAWN: ML CHECKED: AP

PLOTTED: NOVEMBER 30 2022

SCALE: AS SHOWN

C075.1

IMMACULATE HEART OF MARY MISSION

Appendix C. Water Quality Impact Assessment Data Sheet

Project Address: DONALDSON RUN HEADWATERS, ARLINGTON, VIRGINIA
 Applicant Name: ARLINGTON COUNTY DES...
 Applicant Contact Information (phone and email): (703) 228-7595 (apatel@arlingtonva.us)
 Consultant Name: ARLINGTON COUNTY DES...
 Consultant Contact Information (phone and email):

Section 1: Type of activity proposed

Activity type (check all that apply):
 New construction (residential, commercial, public, etc.)
 Alteration of new residential structure
 Residential addition
 Detached residential structure
 Deck, patio, or retaining wall
 Landscaping (includes tree removal)
 Utility work
 Fence
 Other (please describe): Stream Stabilization

Section 2: Key details of the proposed activity

Complete all that apply	Explanation
Total area of disturbance on parcel (sf)	44,960
Area of disturbance within RPA (sf)	40,271
Area of disturbance on slopes greater than or equal to 15 percent located adjacent to adjacent RPA boundary (sf)	2,175

Complete all fields	Existing condition	Proposed condition	Explanation
RPA encroachment (ft)	0	0	The distance (in feet) from the existing or proposed structure to the designated RPA feature edge or stream or open channel, wetland, etc.)
Total development footprint in RPA (sf)	21,898	21,898	The existing footprint includes the area of any existing structures, patios, decks, walkways, etc. Proposed footprint is the anticipated post-project area of all structures, additions, decks, walkways, patios, decks, etc. (including any existing structures).
Impervious footprint in RPA (sf)	0	0	Total area of impervious surfaces within the RPA (roads, pavement, etc.)

STAFF USE ONLY

Building/Modification/Fence permit number(s):
 Major WQA required? Yes No
 Date WQA/Exception request information complete:
 Date Chesapeake Bay Preservation Ordinance and ES ordinance (if applicable) approved issued in Permit Plus: --

Section 3: Plan and Narrative

Provide a plan showing the location of the proposed activity, along with the RPA boundary. Briefly describe the proposed project, including any potential water quality impacts and mitigation measures proposed. The narrative must address three impact categories: 1. Tree vegetation impacts, 2. Stormwater and runoff, 3. Erosion and sediment control. Please refer to the WQA plan/narrative checked for additional information.

THE PROJECT CONSISTS OF STABILIZING A PORTION OF DONALDSON RUN TRIBUTARY B STREAM CORRIDOR FROM THE HEADWATERS AT 24TH RD N TO THE BEGINNING OF THE PREVIOUSLY RESTORED PORTION APPROXIMATELY 600 LINEAR FEET DOWNSTREAM. STABILIZATION ACTIVITIES INCLUDE: INSTALLING IMBRICATED ROCK WALLS ALONG THE CHANNEL BANKS TO REDUCE EROSION AND STABILIZE THE STEEP SLOPES; INSTALLING NATURAL ROCK BOLLARD STRUCTURES CROSS-VARIABLE TO PROVIDE FOR GRAZE CONTROL AND REDUCE THE OVERALL SLOPE OF THE STREAM CHANNEL; AND LINING THE BANKS WITH EROSION CONTROL MATTING. THE EXISTING SANITARY SEWER WILL BE CONCRETE ENCASED WHERE IT FALLS WITHIN THE FOOTPRINT OF THE PROPOSED STREAM CHANNEL IMPROVEMENTS. THE DISTURBED AREA WILL BE PLANTED WITH A VARIETY OF NATIVE TREES AND GROUND COVER TO FURTHER PROMOTE SOIL STABILIZATION. THE WORK WILL BE CONDUCTED IN AN ENVIRONMENTALLY SENSITIVE AREA (i.e. RPA, AND WATERS OF THE US). THE LANDSCAPING WORK CONSISTS OF FURNISHING AND INSTALLING THE REPLACEMENT TREES AND GROUND COVER AS DESCRIBED IN THE PLANTING PLAN (SHEETS C081.1 AND C081.2). EXISTING TREES WILL BE SAVED WHERE PRACTICALLY POSSIBLE. THE PROPOSED LANDSCAPING WILL REPLACE TREES REMOVED FOR THE STREAM STABILIZATION WORK. FOR THE PROJECT, 29 TREES WILL BE REMOVED. TREES NEAR THE STREAM WORK BUT NOT IDENTIFIED TO BE REMOVED WILL BE PROTECTED DURING CONSTRUCTION USING TREE PROTECTION FENCING, ROOT MATTING AND ROOT PRUNING, AND ARE LIKELY TO SURVIVE CONSTRUCTION. A TOTAL OF 83 REPLACEMENT TREES ARE REQUIRED. THE QUANTITY OF PROPOSED PLANTS MAY BE INCREASED AS DIRECTED. SUCH VARIATIONS IN QUANTITY WILL NOT BE CONSIDERED AS ALTERATIONS IN THE DETAILS OF CONSTRUCTION OR A CHANGE IN THE CHARACTER OF THE WORK. EROSION AND SEDIMENT CONTROL MEASURES WILL BE INSTALLED AND MAINTAINED IN ACCORDANCE WITH THE VIRGINIA EROSION AND SEDIMENT CONTROL HANDBOOK (VESC), CURRENT EDITION. THERE IS NO INCREASE IN IMPERVIOUS AREA DUE TO THE PROJECT, AND NO CHANGES TO IMPERVIOUS AREA WITHIN THE RPA. SEE SHEETS C081.1, C081.2, AND C081.3 FOR TREE REMOVAL AND PLANTING WITHIN THE RPA.

Additional Water Quality Impact Assessment Information

The information supplied on this form satisfies the minimum requirements for a Minor Water Quality Impact Assessment. For projects that disturb over 2500 square feet, elements of a Major Water Quality Impact Assessment may also be required, depending on the nature and extent of the proposed RPA encroachment, as outlined in Section 61-12 of the ordinance.

Appendix D. Exception Request Form

Applicant: N/A Project address: N/A

Section 1: Brief description of exception request

N/A

Section 2: Parcel, structure, and ownership information

Date parcel ownership began: N/A Date of construction of any prior work by current owner (alterations, additions, decks, patios, etc.): --
 Date existing principal structure built: N/A Date of construction of any prior work by previous owner (alterations, additions, decks, patios, etc.): --
 Will existing principal structure remain intact? Yes No


STAFF USE ONLY

Allowable development in RPA (§ 61-7-A)
 Allowable modification in RPA (§ 61-7-B)
 Allowable encroachment in RPA (§ 61-7-C)
 Expansion of existing structure or use in RPA (§ 61-14) (exception request required)
 New development on the RPA, development that increases impervious area in the RPA or encroaches further into the RPA or any other proposed disturbance of an RPA (exception request required)
 Exemplified activity in RPA (§ 61-15)
 Proposed development in RPA on 15 percent slopes adjacent to RPA
 Other (please describe):

CBORC hearing required? Yes No
 Date public notification sent certified mail:
 Hearing date:
 Public hearing: Approved Not approved
 Date of final approval: --

Legend

- PROPERTY LINE
- - - EXISTING 2-FOOT CONTOUR
- LOD — LIMIT OF DISTURBANCE (LOD)
- RESOURCE PROTECTION AREA (RPA)
- WATERS OF THE U.S.



ARLINGTON VIRGINIA

DEPARTMENT OF ENVIRONMENTAL SERVICES
 FACILITIES & ENGINEERING DIVISION
 ENGINEERING BUREAU
 2100 CLARENDON BOULEVARD, SUITE 813
 ARLINGTON, VA 22201
 PHONE: 703.228.3629
 FAX: 703.228.3606

COPYRIGHT © 2021 ARLINGTON COUNTY VIRGINIA - ALL RIGHTS RESERVED

SEAL

COMMONWEALTH OF VIRGINIA
 Ankur B. Patel
 ANKUR B. PATEL
 Lic. No. 57048
 7/6/2022
 PROFESSIONAL ENGINEER

APPROVALS DATE

Amy Pflaum	08/04/22
QUALITY CONTROL ENGINEER	
Dennis M. Leach	8/5/22
CONSTRUCTION SECTION SUPERVISOR	
8/4/22	
WATER, SEWER, STREETS BUREAU CHIEF	
Dennis M. Leach	08/03/22
TRANSPORTATION DIRECTOR	
Jennifer Tastad	08/17/22
PROJECT MANAGER	

REVISIONS DATE

STORM DRAINAGE IMPROVEMENTS S42D-22D-E AND S NOTES SWPPP.DWG PATH: Q:\DATA\S42D\DESIGN\CAD\ACTIVE PLOTTED BY: MLEONARDI

HEADWATERS DONALDSON RUN TRIBUTARY B (ANALOSTAN BRANCH)

WATER QUALITY IMPACT ASSESSMENT PLAN

DESIGNED: ML
 DRAWN: ML
 CHECKED: AP



PLOTTED: NOVEMBER 30 2022

SCALE: N/A

GRAPHIC SCALE

0 40 80

C081.1



APPROVALS	DATE
<i>Amy Pflaum</i>	08/04/22
QUALITY CONTROL ENGINEER	
<i>[Signature]</i>	8/5/22
CONSTRUCTION SECTION SUPERVISOR	
<i>[Signature]</i>	8/4/22
WATER, SEWER, STREETS BUREAU CHIEF	
<i>Dennis M. Leach</i>	08/03/22
TRANSPORTATION DIRECTOR	
<i>Jennifer Tastad</i>	08/17/22
PROJECT MANAGER	

REVISIONS	DATE

STORM DRAINAGE IMPROVEMENTS
 S42D
 HEADWATERS DONALDSON RUN TRIBUTARY B
 (ANALOSTAN BRANCH)
LANDSCAPE PLAN

PLANTING NARRATIVE:
 THE DESIGN INTENT OF THESE PLANTING SHEETS IS TO ESTABLISH STREAMSIDE AND UPLAND VEGETATION AT APPROPRIATE ELEVATIONS TO PROVIDE HABITAT AND SEDIMENT STABILIZATION. THESE COMMUNITIES ARE DESCRIBED AS FOLLOWS. UPLAND AREAS ARE GENERALLY LOCATED UPSLOPE FROM THE STREAM CHANNEL AND ARE NOT INUNDATED BY STREAM FLOW, EVEN UNDER HIGH FLOW CONDITIONS. THE STEEP SLOPE AREAS ARE GENERALLY LOCATED DIRECTLY ADJACENT TO THE STREAM AND CONSIST OF STEEPLY SLOPING HILLSIDE OR STREAM CHANNEL BANK. THESE AREAS ARE VULNERABLE TO EROSION AND CARE SHOULD BE TAKEN TO LIMIT DISTURBANCE DURING PLANTING ACTIVITIES. ANNUAL RYEGRASS SHALL BE PLANTED IN ALL DISTURBED AREAS AS A TEMPORARY SOIL STABILIZATION TECHNIQUE.
 ALL TREES AND SHRUBS SHALL BE PLANTED IN A NATURALISTIC PATTERN. ALL SHRUBS SHALL BE PLANTED WITHIN 15 FEET OF THE TOP OF STREAM BANK. ALL PLANTING LOCATIONS SHALL BE REVIEWED BY THE ARLINGTON COUNTY URBAN FORESTER PRIOR TO COMMENCEMENT OF PLANTING.

- PLANTING NOTES:**
- CONTRACTOR TO CONTACT ARLINGTON COUNTY URBAN FORESTER 72 HOURS PRIOR TO PLANTING TO SCHEDULE INSPECTION OF THE TREE STOCK AND TO APPROVE LOCATIONS OF PLANT MATERIAL.
 - THE EXISTING SOILS WHERE REFORESTATION OCCURS SHALL BE AMENDED WITH LEAF COMPOST & TOPSOIL AND SHALL BE THOROUGHLY WATERED. SEE SPECS.
 - NO CULTIVARS OR SUBSTITUTIONS OF SPECIES WILL BE PERMITTED. USE LOCAL ECOTYPES TO THE MAXIMUM EXTENT POSSIBLE. PLANTINGS SHALL BE LAID OUT IN THE FIELD BY CONTRACTOR WITH COUNTY STAFF ON-SITE. CARE SHALL BE TAKEN TO AVOID ROOTS OF EXISTING TREES.
 - PRIOR TO PLANTING OF THE REFORESTATION AREA, WITHIN DISTURBED AREAS ADJACENT TO THE NEW STREAM BANK ONLY, CONTRACTOR SHALL INSTALL COIR MAT CM-700 (OR APPROVED EQUAL) ATOP THE AMENDED SOILS WITHIN THE ENTIRE PROPOSED REFORESTATION AREA. THE MATTING SHALL BE SECURED TO THE GROUND WITH BIODEGRADABLE STAKES ON A 3' x 3' GRID. THE PURPOSE OF THE MATTING IS TO SUPPRESS COMPETING VEGETATION GROWTH, RETAIN SOIL MOISTURE AND REDUCE EROSION.
 - WHEN PLANTING PROPOSED TREES AND SHRUBS, WHERE MATTING IS USED, CONTRACTOR SHALL CUT-OUT A SMALL SECTION OF THE MATTING IN ORDER TO DIG A HOLE TO RECEIVE THE PLANT. PERENNIALS AND GRASSES SHALL BE PLANTED BETWEEN THE GRID OF THE MATTING.
 - TREES MAY BE SPACED CLOSER THAN OPTIMAL SPACING THAN TYPICAL AS NOTED ON PLANTING LIST TO ENCOURAGE LESS VEGETATION COMPETITION AND MAINTENANCE. THIS SPACING WILL BE DETERMINED IN THE FIELD. DO NOT STAKE NEWLY PLANTED TREES.
 - TREES MAY BE PLANTED OUTSIDE OF THE LOD AREA (SHOWN ABOVE). THIS WILL BE DETERMINED AT THE TIME OF INSTALLATION UNDER DIRECTION OF ARLINGTON COUNTY URBAN FORESTER.
 - PLANTS SHALL BE PLANTED ON THE DAY OF DELIVERY IF/WHEN PRACTICAL. IN THE EVENT THIS IS NOT POSSIBLE, THE CONTRACTOR SHALL PROTECT STOCK NOT PLANTED. PLANTS SHALL NOT REMAIN UNPLANTED FOR LONGER THAN A THREE-DAY PERIOD. ANY PLANTS NOT INSTALLED DURING THIS PERIOD SHALL BE REJECTED, UNLESS ARLINGTON COUNTY FORESTER AND CONTRACTOR PROVIDE OTHERWISE BY WRITTEN AGREEMENT.
 - PLANTING OPERATIONS SHALL BE PERFORMED DURING PERIODS WITHIN THE PLANTING SEASON WHEN WEATHER AND SOIL CONDITIONS ARE SUITABLE AND IN ACCORDANCE WITH ARLINGTON COUNTY PLANTING STANDARDS.
 - PLANTS SHALL BE PLANTED IN IN-SITU SOIL THAT IS THOROUGHLY WATERED.
 - SET ALL PLANTS PLUMB AND STRAIGHT AT SUCH LEVEL THAT NORMAL OR NATURAL RELATIONSHIP BETWEEN THE PLANT AND THE GROUND SURFACE SHALL BE ESTABLISHED.
 - LEADERS OF TREES SHALL NOT BE CUT BACK.
 - AFTER PLANTING TREES AND SHRUBS, THE CONTRACTOR SHALL OVERSEED WITH ERNST SEED MIX "ARLINGTON VIRGINIA UPLAND WOODLAND SLOPE MIX" (OR APPROVED EQUAL). SEE SEED MIX ON DETAIL SHEET. UPLAND, STREAMSIDE AND STEEP SLOPE AREAS SHALL BE SEEDDED BETWEEN MARCH 1ST AND MAY 31ST OR OCTOBER 1ST AND NOVEMBER 15TH.
 - SEED SHALL BE APPLIED USING ONE OF THE FOLLOWING METHODS: 1) HYDROSEEDING, OR 2) BROADCASTING THE SEED, THEN SPRAYING A 1/4 TO 1/2 INCH LAYER OF MOIST COMPOST ON TOP.
 - SEED SHOULD BE TRACKED INTO THE SOIL AFTER BROADCASTING.
 - GENERAL CONTRACTOR OR SUBCONTRACTOR TO THE GENERAL CONTRACTOR SHALL EMPLOY A LICENSED CERTIFIED ARBORIST TO OVERSEE TREE PROTECTION AND TREE PLANTING. ARBORIST SHALL BE ON SITE DURING ALL PLANTING ACTIVITIES.
 - NEWLY PLANTED TREES TO BE WATERED FOR UNTIL FINAL COMPLETION OF PROJECT BY GENERAL CONTRACTOR.
 - DEER PROTECTION CAGES SHALL BE INSTALLED FOR ALL TREES AND SHRUBS (TO BE CONFIRMED AT PRE-CONSTRUCTION MEETING). CAGES SHALL BE CONSTRUCTED OF 12 GAUGE WELDED WIRE MESH WITH A 2" x 4" OPENING. MESH WILL BE ATTACHED TO ONE METAL U-POST, WITH GALVANIZED WIRE. TREE PROTECTION SHALL BE A MINIMUM OF 4-5 FEET TALL. SHRUB PROTECTION SHALL BE A MINIMUM OF 3 FEET TALL.

Planting List
 Donaldson Run Phase 1 and 2
 11/30/2022

Key	Botanical Name	Common Name	Category	Remarks	Size	Quantity
Trees:						
AA	Amelanchier arborea	Downy Serviceberry	Understory Deciduous		Upland	1 gal/3'-4" 30
BN	Betula nigra	River Birch	Overstory Deciduous	Low lying areas/Floodplain with sun	Upland	1 gal/3'-4" 20
CG	Carya glabra	Pignut Hickory	Overstory Deciduous		Upland	1 gal/3'-4" 50
CT	Carya tomentosa	Mockernut Hickory	Overstory Deciduous		Upland	1 gal/3'-4" 50
CF	Cornus florida	American Dogwood	Understory Deciduous		Upland	1 gal/3'-4" 40
FG	Fagus grandifolia	American Beech	Overstory Deciduous		Upland	1 gal/3'-4" 60
LT	Liriodendron tulipifera	Tulip Poplar	Overstory Deciduous		Upland	1 gal/3'-4" 50
NS	Nyssa sylvatica	Blackgum	Overstory Deciduous		Upland	1 gal/3'-4" 50
PO	Platanus occidentalis	American Sycamore	Overstory Deciduous	Low lying areas/Floodplain with sun	Upland	1 gal/3'-4" 20
QB	Quercus bicolor	Swamp White Oak	Overstory Deciduous	Low lying areas/Floodplain with sun	Upland	1 gal/3'-4" 20
QM	Quercus marilandica	Black Jack Oak	Overstory Deciduous		Upland	1 gal/3'-4" 60
QP	Quercus prinus	Chestnut Oak	Overstory Deciduous		Upland	1 gal/3'-4" 60
QS	Quercus shumardii	Shumard Oak	Overstory Deciduous		Upland	1 gal/3'-4" 60
SA	Sassafras albidum	Sassafras	Overstory Deciduous		Upland	1 gal/3'-4" 60
Note: ALL trees shall have two-thirds (2/3) minimum canopy by height. Trees should have a single, straight leader (unless noted as a multi-stem tree) and all trees and shrubs shall have quality roots which meet ANSI specifications for plant size.						630
Key: Shrubs:						
CA	Corylus americana	American Hazelnut				1 gal 35
CO	Cephalanthus occidentalis	Butterbush				1 gal 43
LB	Lindera benzoin	American Spicebush				1 gal 35
SC	Sambucus canadensis	Elderberry				1 gal 40
VP	Viburnum prunifolium	Blackhaw Viburnum				1 gal 35
Total Shrubs Planted with reforestation calculation (.047 AC)						188
Total required shrubs to be planted 15' from stream bank						188
Key: Live Stakes:						
CO	Cephalanthus occidentalis	Butterbush		Plant 3'-6' apart on triangular spacing		3' stake
SD	Cornus amomum	Silky Dogwood		Plant 3'-6' apart on triangular spacing		3' stake
PO	Platanus occidentalis	American Sycamore		Plant 3'-6' apart on triangular spacing		3' stake
Note: Install stakes during their dormancy (late fall to early spring). Do not allow them to dry out. Soaking prior to planting significantly increases survival.						

Legend

- REFORESTATION
40,064 SF
- UPLAND PLANTINGS
26,019 SF
- STEEP SLOPE PLANTINGS
6,933 SF
- LIVE STAKES (APPROX. 150 STAKES REQUIRED)

DESIGNED: BG
 DRAWN: KV
 CHECKED: KV
 PLOTTED: NOVEMBER 30 2022
SCALE:
 0 25 50
 GRAPHIC SCALE

ERNST SEED MIX -ARLINGTON VIRGINIA

UPLAND WOODLAND SLOPE MIX

(OR APPROVED EQUAL)

SEEDING RATE: 60 LB. PER ACRE


MIX COMPOSITION

- 16.7% AGROSTIS HYEMALIS (WINTER BENTGRASS)
18.8% AGROSTIS PERENNANS (AUTUMN BENTGRASS)
1.0% CHAMAECRISTA FASCICULATA, PA ECOTYPE (PARTRIDGE PEA)
16.7% ELYMUS VIRGINICUS (VIRGINIA WILDGRASS)
20.0% LOLIUM MULTIFLORUM (ANNUAL RYGRASS)
13.3% PANICUM ANCEPS (BEAKED PANICGRASS)
13.3% PANICUM CLANDESTINUM (DEERTONGUE)
0.1% SOLIDAGO JUNCEA (EARLY GOLDENROD)
0.1% SOLIDAGO ODORA (LICORICE SCENTED GOLDENROD)

100.0%

99.8% GRASS-LIKE SPECIES BY SEED COUNT
0.2% WILDFLOWER BY SEED COUNT

APPLY THIS MIX AT 60LBS/ACRE. THE COVER CROP IS PART OF THE MIX. WHERE SLOPES ARE 3:1 OR STEEPER, USE EROSION CONTROL PLANKETS TO STABILIZE SOIL WHILE PLANTS ESTABLISH.



PLANTING ON SLOPE WITH ESC FABRIC

NOT TO SCALE

ELEVATION 329300.12

ARLINGTON DFR

NOTES

- 1. PLANTS SHALL BE FURNISHED AND INSTALLED AS INDICATED ON THE APPROVED LANDSCAPE PLAN.
2. PLANTS SHALL BE TYPICAL OF SPECIES AND VARIETY, AND COMPLY WITH THE MOST RECENT ANSI Z60.1 STANDARDS.
3. TREES SHALL BE NURSERY GROWN SPECIMENS THAT MEET THE LATEST EDITION OF THE AMERICAN STANDARDS FOR NURSERY STOCK (ANSI Z60).
4. CALL MISS UTILITY AT (800) 552-7001 FOR UTILITY LOCATIONS PRIOR TO EXCAVATION.
5. AT TIME OF PLANTING PRUNE ONLY CROSSING LIMBS, BROKEN OR DEAD BRANCHES, AND ANY BRANCHES THAT POSE A HAZARD TO PEDESTRIANS.
6. PLANTS SHALL BE PLANTED ON THE DAY OF DELIVERY.
7. PLANTS SHALL NOT BE BOUND WITH WIRE OR ROPE AT ANY TIME.
8. SITE CHARACTERISTICS, SUCH AS OVERHEAD POWER LINES, EXISTING VEGETATION, AND INFRASTRUCTURE ITEMS SUCH AS CURBS, SIDEWALKS AND UTILITIES SHALL BE CONSIDERED.
9. BACKFILL SOIL MIXTURE SHALL BE 3/4 EXISTING SOIL CLEANED OF DEBRIS (GRAVEL, ROCKS, STICKS, TRASH, ETC.) AND MIXED WITH 1/4 ORGANIC MATERIAL (COMPOSTED BARK, LEAF MOLD, OR OTHER PLANT DEBRIS PROCESSED TO A POINT OF DECAY AND APPROVED BY THE COUNTY URBAN FORESTER.
10. REFER TO PLANTING DETAILS AND SPECIFICATIONS FOR SPECIFIC INSTRUCTIONS.
11. TREES PLANTED SHALL RECEIVE A 3-INCH LAYER OF SHREDDED HARDWOOD MULCH.
12. TREES MAY ONLY BE STAKED IF REQUIRED BY THE COUNTY URBAN FORESTER.
13. MULCH SHALL BE CLEAN, SCREENED, DOUBLE-HAMMERED HARDWOOD BARK MULCH, UNIFORM IN SIZE AND FREE OF STONES, CLODS, NON-ORGANIC DEBRIS AND OTHER FOREIGN MATERIAL.
14. ALL PLANTS SHALL BE WATERED TWICE: ONCE AT INSTALLATION AND AGAIN WITHIN 48-HOURS OF INSTALLATION.
15. CONTRACTOR SHALL LEGALLY REMOVE EXCESS SOIL & DEBRIS FROM SITE.
16. AT PROJECT COMPLETION, PRIOR TO FINAL ACCEPTANCE, PRESERVED AND PLANTED TREES SHALL BE INSPECTED BY AN ARLINGTON COUNTY URBAN FORESTER.

GENERAL PLANTING NOTES

329300.14 (2019)

ARLINGTON DFR

NOTES

- 1. AT PLANTING PRUNE ONLY BROKEN OR DEAD BRANCHES PER ANSI 300 STANDARD.
2. PLANTING PIT/TRENCH SHALL BE DUG DEEP ENOUGH TO ALLOW AT LEAST 1/8TH OF ROOT BALL TO SET ABOVE EXISTING GRADE.
3. SET PLANTS IN ERECT, STABLE, AND UNIFORM POSITIONS IN THE CENTER OF THE PLANTING PIT. ORIENT BEST FACE OF PLANT TO BE THE MOST VISIBLE.
4. UNLESS OTHERWISE DIRECTED BY COUNTY URBAN FORESTER, BACKFILL SOIL MIXTURE WILL BE 3/4 EXISTING SOIL CLEANED OF DEBRIS (GRAVEL, ROCKS, STICKS, TRASH, ETC.) AND MIXED WITH 1/4 ORGANIC MATERIAL (COMPOSTED BARK, LEAF MOLD, OR OTHER PLANT DEBRIS PROCESSED TO A POINT OF DECAY AND APPROVED BY THE COUNTY URBAN FORESTER.
5. CONTRACTOR SHALL REMOVE EXCESS SOIL & DEBRIS FROM SITE.
6. DO NOT PLACE MULCH IN CONTACT WITH STEM OF SHRUBS.
7. MULCH SHALL BE CLEAN, SCREENED, DOUBLE-HAMMERED HARDWOOD BARK MULCH, UNIFORM IN SIZE AND FREE OF STONES, CLODS, NON-ORGANIC DEBRIS AND OTHER FOREIGN MATERIAL.
8. CONTRACTOR SHALL LEGALLY REMOVE EXCESS SOIL & DEBRIS FROM SITE.
9. BACKFILL SOIL MIXTURE FOR ENTIRE TREE PIT AREA X ROOTBALL DEPTH SHALL BE FIRMED IN 6" LIFTS.
10. REFER TO PLANTING PLAN & PLANT LIST FOR SPACING.
11. PLACE TOP 1/8 OF ROOT BALL ABOVE FINISHED GRADE (TYP.)
12. 3" SHREDDED HARDWOOD MULCH OVER ENTIRE SHRUB BED FINISHED GRADE.
13. BACKFILL SOIL MIXTURE (TYP.) FOR CONTAINER. LOOSEN THE ROOT BALL OF ANY ROOT BOUND PLANTS.
14. UNDISTURBED SUBGRADE OR COMPACTED BACKFILL SOIL MIXTURE.
15. CAREFULLY REMOVE ALL TWINE, ROPE, WIRE, AND BURLAP FROM ROOT BALL.
16. ALL PLANTS MUST BE WATERED TWICE ONCE AT INSTALLATION AND AGAIN WITHIN 48-HOURS OF INSTALLATION, PER THE SPECIFICATIONS.

SHRUB PLANTING

ELEVATION 329300.8 (2021)

ARLINGTON DFR

NOTES

- 1. AT PLANTING PRUNE ONLY CROSSING LIMBS, BROKEN OR DEAD BRANCHES, AND ANY BRANCHES THAT POSE A HAZARD TO PEDESTRIANS per ANSI STANDARD A300. DO NOT PRUNE INTO OLD WOOD ON EVERGREENS.
2. CONTRACTOR SHALL MAXIMIZE EXCAVATED AREA FOR TREE PIT WITHOUT ADVERSELY IMPACTING ADJACENT SITE FEATURES.
3. UNLESS OTHERWISE DIRECTED BY THE ARLINGTON COUNTY URBAN FORESTER, BACKFILL SOIL MIXTURE WILL BE 3/4 EXISTING SOIL CLEANED OF DEBRIS (GRAVEL, ROCKS, STICKS, TRASH, ETC.) AND MIXED WITH 1/4 ORGANIC MATERIAL (COMPOSTED BARK, LEAF MOLD, OR OTHER PLANT DEBRIS PROCESSED TO A POINT OF DECAY AND APPROVED BY THE URBAN FORESTER.
4. CONTRACTOR SHALL LEGALLY REMOVE EXCESS SOIL & DEBRIS FROM SITE.
5. TREES PLANTED WITHOUT THE TRUNK FLARE VISIBLE WILL BE REJECTED.
6. TREES MAY ONLY BE STAKED IF REQUIRED BY THE COUNTY URBAN FORESTER.
7. MULCH SHALL BE CLEAN, SCREENED, DOUBLE-HAMMERED HARDWOOD BARK MULCH, UNIFORM IN SIZE AND FREE OF STONES, CLODS, NON-ORGANIC DEBRIS AND OTHER FOREIGN MATERIAL.
8. CONTRACTOR SHALL LEGALLY REMOVE EXCESS SOIL & DEBRIS FROM SITE.
9. BACKFILL SOIL MIXTURE FOR ENTIRE TREE PIT AREA X ROOTBALL DEPTH SHALL BE FIRMED IN 6" LIFTS.
10. REFER TO PLANTING PLAN & PLANT LIST FOR SPACING.
11. PLACE TOP 1/8 OF ROOT BALL ABOVE FINISHED GRADE (TYP.)
12. 3" SHREDDED HARDWOOD MULCH OVER ENTIRE TREE BED FINISHED GRADE.
13. BACKFILL SOIL MIXTURE (TYP.) FOR CONTAINER. LOOSEN THE ROOT BALL OF ANY ROOT BOUND PLANTS.
14. UNDISTURBED SUBGRADE OR COMPACTED BACKFILL SOIL MIXTURE.
15. CAREFULLY REMOVE ALL TWINE, ROPE, WIRE, AND BURLAP FROM ROOT BALL.
16. ALL PLANTS MUST BE WATERED TWICE ONCE AT INSTALLATION AND AGAIN WITHIN 48-HOURS OF INSTALLATION, PER THE SPECIFICATIONS.

TREE PLANTING ON SLOPE

FOR OPEN PLANTING AREAS FREE OF PAVING OR GRATES

329300.2 (2019)

1/2" = 1'-0"

ARLINGTON DFR

NOTES

- 1. AT PLANTING PRUNE ONLY CROSSING LIMBS, BROKEN OR DEAD BRANCHES, AND ANY BRANCHES THAT POSE A HAZARD TO PEDESTRIANS per ANSI STANDARD A300. DO NOT PRUNE INTO OLD WOOD ON EVERGREENS.
2. CONTRACTOR SHALL MAXIMIZE EXCAVATED AREA FOR TREE PIT WITHOUT ADVERSELY IMPACTING ADJACENT SITE FEATURES.
3. UNLESS OTHERWISE DIRECTED BY ARLINGTON COUNTY URBAN FORESTER, BACKFILL SOIL MIXTURE WILL BE 3/4 EXISTING SOIL CLEANED OF DEBRIS (GRAVEL, ROCKS, STICKS, TRASH, ETC.) AND MIXED WITH 1/4 ORGANIC MATERIAL (COMPOSTED BARK, LEAF MOLD, OR OTHER PLANT DEBRIS PROCESSED TO A POINT OF DECAY AND APPROVED BY THE URBAN FORESTER.
4. CONTRACTOR SHALL LEGALLY REMOVE EXCESS SOIL & DEBRIS FROM SITE.
5. TREES PLANTED WITHOUT THE TRUNK FLARE VISIBLE WILL BE REJECTED.
6. TREES MAY ONLY BE STAKED IF REQUIRED BY THE COUNTY URBAN FORESTER.
7. MULCH SHALL BE CLEAN, SCREENED, DOUBLE-HAMMERED HARDWOOD BARK MULCH, UNIFORM IN SIZE AND FREE OF STONES, CLODS, NON-ORGANIC DEBRIS AND OTHER FOREIGN MATERIAL.
8. CONTRACTOR SHALL LEGALLY REMOVE EXCESS SOIL & DEBRIS FROM SITE.
9. BACKFILL SOIL MIXTURE FOR ENTIRE TREE PIT AREA X ROOTBALL DEPTH SHALL BE FIRMED IN 6" LIFTS.
10. REFER TO PLANTING PLAN & PLANT LIST FOR SPACING.
11. PLACE TOP 1/8 OF ROOT BALL ABOVE FINISHED GRADE (TYP.)
12. 3" SHREDDED HARDWOOD MULCH OVER ENTIRE TREE BED FINISHED GRADE.
13. BACKFILL SOIL MIXTURE (TYP.) FOR CONTAINER. LOOSEN THE ROOT BALL OF ANY ROOT BOUND PLANTS.
14. UNDISTURBED SUBGRADE OR COMPACTED BACKFILL SOIL MIXTURE.
15. CAREFULLY REMOVE ALL TWINE, ROPE, WIRE, AND BURLAP FROM ROOT BALL.
16. ALL PLANTS MUST BE WATERED TWICE ONCE AT INSTALLATION AND AGAIN WITHIN 48-HOURS OF INSTALLATION, PER THE SPECIFICATIONS.



TREE PLANTING DETAIL

FOR OPEN PLANTING AREAS FREE OF PAVING OR GRATES

329300.1 (2021)

NOT TO SCALE

ARLINGTON DFR




NOTES

- 1. A PLANTING BAR MAY BE USED TO PUNCH A HOLE FOR THE CUTTING. IN SOFTER SOILS, LIVE STAKES MAY BE DIRECTLY PUSHED OR HAMMERED, PROVIDED THE STAKE IS NOT DAMAGED.
2. INSTALL THE LIVE STAKE WITH THE CORRECT SIDE UP, BUDS MUST POINT UPWARD. LIVE STAKES SHOULD BE CUT ON AN ANGLE ON THE BOTTOM AND FLAT ON THE TOP.
3. TWO-THIRDS OF THE LIVE STAKE LENGTH SHALL BE PLANTED BELOW GRADE.
4. TAMP IN AROUND THE CUTTING TO ENSURE THAT THERE ARE NO AIR POCKETS ALONG THE STEM.

DEPARTMENT OF ENVIRONMENTAL SERVICES FACILITIES & ENGINEERING DIVISION ENGINEERING BUREAU 2100 CLARENDON BOULEVARD, SUITE 813 ARLINGTON, VA 22201 PHONE: 703.228.3629 FAX: 703.228.3606

COPYRIGHT © 2021 ARLINGTON COUNTY VIRGINIA - ALL RIGHTS RESERVED



APPROVALS DATE


Table with columns for Name, Title, and Date. Approvals include Amy Pflaum (Quality Control Engineer, 08/04/22), Dennis M. Leach (Construction Section Supervisor, 8/5/22), Jennifer Tastad (Project Manager, 08/17/22), and others.

REVISIONS DATE

Table with columns for Revision Number and Date. No revisions are currently listed.

STORM DRAINAGE IMPROVEMENTS HEADWATERS DONALDSON RUN TRIBUTARY B (ANALOSTAN BRANCH) LANDSCAPE NOTES AND DETAILS

DESIGNED: BG
DRAWN: KV
CHECKED: KV
PLOTTED: NOVEMBER 30 2022
SCALE: AS SHOWN



CONSTRUCTION NOTES

- FOR ALL ARTERIAL STREETS, PORTABLE VARIABLE MESSAGE SIGNS WITH CLOSURE INFORMATION MUST BE INSTALLED AHEAD OF THE PROJECT SITE AT EACH VEHICULAR APPROACH 3 WEEKS PRIOR TO STREET CLOSURE IN LOCATIONS DIRECTED BY THE PROJECT OFFICER.
- CONTRACTOR SHALL REMOVE EXISTING PAVEMENT MARKINGS IN CONFLICT WITH TEMPORARY PAVEMENT MARKINGS.
- CONTACT TRANSPORTATION ENGINEERING OPERATIONS AT 703-228-6598 OR 571-437-1077 AND THE PROJECT OFFICER TO APPROVE MARKING LAYOUT 48 HOURS PRIOR TO INSTALLATION OF MARKINGS.
- ONE LANE CLOSURE IN EACH DIRECTION OF TRAFFIC WILL BE PERMITTED FOR FINAL PAVEMENT OVERLAY.
- DURING CONSTRUCTION, THE CONTRACTOR SHALL MAINTAIN THE FLOW OF TRAFFIC ON ANY INTERSECTION WITHIN THE WORK AREA.
- THE CONTRACTOR SHALL NOTIFY ARLINGTON COUNTY PUBLIC SCHOOLS TWO WEEKS PRIOR TO STARTING CONSTRUCTION.
- THE CONTRACTOR SHALL SUBMIT ANY REQUESTS FOR TEMPORARY "NO PARKING" RESTRICTIONS TO THE PROJECT OFFICER AT LEAST 3 WORKING DAYS PRIOR TO THE DESIRED ONSET OF RESTRICTIONS. PRIOR TO A REQUEST FOR THE REMOVAL OF ACCESS TO ANY ADA PARKING SPACE THE CONTRACTOR MUST HAVE MADE PROVISION FOR ALTERNATIVE ADA PARKING AS INDICATED ON THE APPROVED PLAN OR AS DIRECTED BY THE PROJECT OFFICER.
- WHEN THE APPROVED PLAN CALLS FOR THE REMOVAL OF ANY PARKING METER THE CONTRACTOR MUST MAKE A REQUEST TO THE PROJECT OFFICER AT LEAST ONE WEEK IN ADVANCE OF THE DESIRED REMOVAL. THE PROJECT OFFICER WILL THEN COORDINATE THE PARKING METER REMOVAL WITH TRAFFIC ENGINEERING AND OPERATIONS.
- THE CONTRACTOR SHALL MINIMIZE THE DURATION OF ANY BLOCKAGE TO PRIVATE ENTRANCES AND DRIVEWAYS. THE AFFECTED PROPERTY OWNER SHALL BE NOTIFIED A MINIMUM OF 24 HOURS IN ADVANCE OF SUCH ACTIVITIES, AND THE CONTRACTOR SHALL MAKE ALL PRIVATE ENTRANCES AND DRIVEWAYS ACCESSIBLE AT THE CONCLUSION OF EACH WORKDAY.
- ALL EXISTING FIRE HYDRANTS AND FIRE DEPARTMENT CONNECTIONS SHALL BE MAINTAINED UNOBSERVED AND ACCESSIBLE AT ALL TIMES IN ACCORDANCE WITH SECTIONS 508.5.4 AND 508.5.5 OF THE ARLINGTON COUNTY FIRE PREVENTION CODE.
- ACCESS TO BUILDINGS FOR FIREFIGHTING SHALL BE MAINTAINED AT ALL TIMES. EXISTING FIRE APPARATUS ACCESS ROADS (FIRE LANES) SHALL BE KEPT CLEAR OF OBSTRUCTIONS IN ACCORDANCE WITH SECTION 503.4 OF THE ARLINGTON COUNTY FIRE PREVENTION CODE. ACCESS TO CONSTRUCTION SITES SHALL BE PROVIDED AND MAINTAINED IN ACCORDANCE WITH SECTION 1410 OF THE ARLINGTON COUNTY FIRE PREVENTION CODE.
- IN THE EVENT THAT EXISTING FIRE DEPARTMENT CONNECTIONS OR FIRE APPARATUS ACCESS ROADS (FIRE LANES) MUST BE OBSTRUCTED TO FACILITATE CONSTRUCTION ACTIVITIES, CONTACT THE ARLINGTON COUNTY FIRE DEPARTMENT FIRE PREVENTION OFFICE AT 703-228-4644 TO COORDINATE REVIEW AND APPROVAL OF TEMPORARY FIRE DEPARTMENT CONNECTIONS AND/OR FIRE APPARATUS ACCESS ROADS PRIOR TO CREATING THE OBSTRUCTION.
- PROJECT WORK HOURS SHALL BE AS FOLLOWS: IN ARLINGTON RIGHT-OF-WAY 9:00AM TO 4:00PM (MON-FRI).
- COORDINATE WITH ARLINGTON COUNTY TRANSIT BUREAU, 703-228-3049, AT LEAST 2 WEEKS PRIOR TO COMMENCEMENT OF WORK APPROVAL, IF TRANSIT IS AFFECTED.
- CONSTRUCTION DURATION IS EXPECTED TO BE APPROXIMATELY 10 MONTHS.

MOT NOTES:


- PARKING SHALL BE RESTRICTED BY THE COUNTY AS PART OF THE RIGHT OF WAY PERMIT. CONTACT DES-PERMITTING SECTION, 703-228-4798, AT LEAST 72 HOURS PRIOR TO COMMENCEMENT OF WORK.
- ALL TEMPORARY BUS TRAVEL LANES MUST BE MINIMUM 11' WIDE.
- THE CONTRACTOR SHALL MAINTAIN ADA ACCESSIBLE PARKING SPACES AT ALL TIMES DURING CONSTRUCTION. THE CONTRACTOR SHALL CONTACT DES - PERMITTING, 703-228-4798, TO COORDINATE RELOCATION OF EXISTING ADA ACCESSIBLE PARKING SPACES OR TO INSTALL TEMPORARY SIGNAGE OUT OF AND ADJACENT TO THE WORK ZONE AS CONSTRUCTION PROGRESSES. MULTIPLE RELOCATIONS MAY BE NECESSARY DURING EACH PHASE.

PEDESTRIAN NOTE:

- PEDESTRIANS SHALL BE APPROPRIATELY DIRECTED WITH ADVANCED WARNING SIGNS PLACED AT INTERSECTIONS, TO CROSS TO THE OPPOSITE SIDE OF THE ROADWAY IN ORDER TO PREVENT CONFLICT WITH MIDBLOCK WORK SITES.
- PEDESTRIAN TRAFFIC SHALL BE MAINTAINED AT ALL TIMES, INCLUDING ACCESS TO BUS STOP SHELTERS.
- PEDESTRIAN TRAFFIC SHALL BE SEPARATED FROM WORK ZONES WITH APPROPRIATE MEASURES IN ACCORDANCE WITH MUTCD.
- PEDESTRIANS SHALL NOT BE LED INTO CONFLICT WITH WORK SITE EQUIPMENT, OPERATIONS, AND/OR VEHICLES MOVING THROUGH OR AROUND THE WORK SITE.

DEPARTMENT OF ENVIRONMENTAL SERVICES
 FACILITIES & ENGINEERING DIVISION
 ENGINEERING BUREAU
 2100 CLARENDON BOULEVARD, SUITE 813
 ARLINGTON, VA 22201
 PHONE: 703.228.3629
 FAX: 703.228.3606

COPYRIGHT © 2021 ARLINGTON COUNTY VIRGINIA - ALL RIGHTS RESERVED



APPROVALS DATE

<i>Amy Pflaum</i>	08/04/22
QUALITY CONTROL ENGINEER	
<i>[Signature]</i>	8/5/22
CONSTRUCTION SECTION SUPERVISOR	
<i>[Signature]</i>	8/4/22
WATER, SEWER, STREETS BUREAU CHIEF	
<i>Dennis M. Leach</i>	08/03/22
TRANSPORTATION DIRECTOR	
<i>Jennifer Tastad</i>	08/17/22
PROJECT MANAGER	


REVISIONS DATE

REVISIONS	DATE

STORM DRAINAGE IMPROVEMENTS
 S42D
 HEADWATERS DONALDSON RUN TRIBUTARY B
 (ANALOSTAN BRANCH)

MAINTENANCE OF TRAFFIC PLAN

DESIGNED: ML
 DRAWN: ML
 CHECKED: AP
 PLOTTED: NOVEMBER 30 2022



C121.1

Legend

	TRAFFIC CONTROL SIGN
	FLAGGER
	TRAFFIC DIRECTION
	PEDESTRIAN ROUTE
	CONSTRUCTION HAUL ROUTE