


PHASE I IMPROVEMENTS FOR THE FLORENCE COUNTY INDUSTRIAL PARK EAST FLORENCE COUNTY, SC

PREPARED FOR: FLORENCE COUNTY ECONOMIC DEVELOPMENT PARTNERSHIP 1951 PISGAH ROAD FLORENCE, SC 29501

HAVE PLACED MY SIGNATURE AND SEAL ON THE DESIGN OCUMENTS SUBMITTED SIGNIFYING THAT I ACCEPT ESPONSIBILITY FOR THE DESIGN OF F TITLE 48. CHAPTER 14 OF THE CODE OF LAWS OF SC 976 AS AMENDED, PURSUANT TO REGULATION 72-300 ET SEQ.(IF APPLICABLE, AND IN ACCORDANCE WITH THE TERMS AND CONDITIONS OF SCRI00000








J-28601.0001

PREPARED BY:

THOMAS

06/07/2021

TMS# 306-01-042



Sheet List Table Sheet Number Sheet Title CS COVER SHEET G0.1 **GENERAL NOTES & INDEX** UTILITY DETAIL C2.6 UTILITY DETAILS \bigtriangleup PAVING, GRADING, & DRAINAGE PLAN C3.0 C3.1 ROAD PLAN AND PROFIL C3.2 **OFF-SITE ROADWAY PLAN** C3.3 **TYPICAL ROADWAY SECTIONS** C3.4 **DRAINAGE PROFILES** C5.0 STRIPING AND SIGNAGE PLAN C5.1-C5.3 SITE DETAILS **CROSS SECTIONS** C6.1-C6.3 C7.1-C7.2 TRAFFIC CONTROL DETAILS LANDSCAPING L1.1-L2.3

REVISION HISTORY								
			_					
3	REVISED PER CITY OF FLORENCE	NJH	2021/06/					
2	REVISED PER FLORENCE COUNTY	NJH	2021/06/					
I	REVISED PER SCDOT	NJH	2021/06/					
REV. NO.	REVISION	BY	DATE					

SUBMITTAL HISTORY

RESUBMITTAL TO FLORENCE COUNTY	2021/06/07
RESUBMITTAL TO SCDOT	2021/06/07
FLORENCE COUNTY, SCDHEC, SCDOT	2021/04/28
SUBMITTED TO	DATE





œ
0
ō.
No.
•
~
-
5
-
- L
5
-
ч.
-
Ĕ.
- E -
•
-
/
s
1
5
ž
E
-
9
2
L
~
-
<u> </u>
vd_myr\My Documents\Drawingl.dwg - Jul 21, 2008
1
E C
5
τ
s.

	ABBREVIATIONS							
DBL DOUBLE FM FORCE MAIN (SANITARY SEWER) PC POINT OF CURVE TC TOP OF CURB								
вот	воттом	FP	FINISH PAD		PH	POST HYDRANT	ТН	THROAT ELEVATION
СВ	CATCH BASIN	FR	FRAME		РТ	POINT OF TANGENT	TG	TOP OF GUTTER
CI	CURB INLET	GI	GRATE INLET		PVC	POLYVINYL CHLORIDE	ТР	TOP OF PAVEMENT
со	CLEAN OUT	GV	GATE VALVE		RCP	REINFORCED CONCRETE PIPE	тw	TOP OF WALK
СРР	CORRUGATED PLASTIC PIPE	HDPE	HIGH DENSITY POLYETHYLENE		RC	ROLL CURB INLET	TY	P TYPICAL
DBL	DOUBLE	н	HOODED INLET		RCP	REINFORCED CONCRETE PIPE	VI	VALLEY INLET
DI	DITCH INLET	INV	INVERT ELEVATION		RI	ROOF INLET	w	WATER
DIP	DUCTILE IRON PIPE	JB	JUNCTION BOX		RJP	RESTRAINED JOINT PIPE	w/	WITH
EL	ELEVATION	LF	LINEAR FEET		R/W	RIGHT-OF-WAY	wv	WATER VALVE
ES	END SECTION	MAX	MAXIMUM		SD	STORM DRAINAGE	YI	YARD INLET
FES	FLARED END SECTION	MIN	MINIMUM		SDMH	STORM DRAINAGE MANHOLE	YI	YARD INLET
FG	FINISH GRADE	мн	MANHOLE		SF	SQUARE FEET		
FH	FIRE HYDRANT	ос	ON CENTER		SS	SANITARY SEWER		


DRAINAGE LEGEND						
DESCRIPTION	EXISTING	PROPOSED				
PIPE	_ · _ · _ · _ · _ · _ · _ · _					
DITCH		→ · · · ·				
CURB INLET (CI) CATCH BASIN (CB)	0					
CONTROL STRUCTURE (CS)						
JUNCTION BOX (JB)	\bigcirc					
MANHOLE (SDMH)	0	۲				
ROOF INLET (RI)	\bigcirc					
FLARED END SECTION (FES)	А					

DESCRIPTION	EXISTING	PROPOSED
ATER MAIN		10"w
INGLE SERVICE LATERAL		
OUBLE SERVICE LATERAL	>	>
ALVE AND BOX	\otimes	$\mathbf{\Theta}$
IRE HYDRANT W/VALVE & BOX	\otimes - φ -	
POST HYDRANT) DH))
EDUCER		
ACKFLOW PREVENTOR		
ROSS		I_I
EE	_	ı—ı
00° BEND - HORIZONTAL		
5° BEND - HORIZONTAL	×	× 1
2-½° BEND - HORIZONTAL	/	/
% BEND - HORIZONTAL	/	1
END - VERTICAL		
AP		

SEWER LEGEND						
DESCRIPTION	EXISTING	PROPOSED				
GRAVITY PIPE	ss •					
SINGLE SERVICE LATERAL						
DOUBLE SERVICE LATERAL		>				
MANHOLE	\bigcirc					
CLEANOUT	Он	H				
FORCEMAIN	IO"FM IO"FM	10"FM 10"FM				
PLUG \ CAP						

- OWNER.

- REQUEST



OTHER UTILITIES LEGEND						
DESCRIPTION	EXISTING					
NATURAL GAS	UGG UGG					
TELEPHONE	ОНТ ОНТ					
UNDERGROUND TELEPHONE	UTL UTL					
ELECTRICITY	OHP OHP					
UNDERGROUND ELECTRICITY	UGP UGP					

I. CONTRACTOR SHALL COORDINATE TIE-IN OF NEW WATER AND SEWER FACILITIES TO CITY OF FLORENCE WATER AND SEWER.

2. CONTRACTOR SHALL MAINTAIN MINIMUM COVER OVER THE WATER MAIN PIPE BARREL OF 3'-O" UNLESS OTHERWISE INDICATED. TOP OF PIPE ELEVATIONS ARE SHOWN FOR CASES WHERE FUTURE STORM SEWERS ARE TO BE INSTALLED. IN NO CASE SHALL THE WATER MAIN BE INSTALLED AT A LOWER ELEVATION THAN THAT SHOWN.

3. SHOULD PIPE, FITTINGS, AND OTHER MATERIALS BE NEEDED IN ADDITION TO THAT SHOWN ON THE DRAWINGS BECAUSE PIPELINE WAS NOT INSTALLED TO THE ALIGNMENT AND PROFILE SHOWN, THEN THE CONTRACTOR IS RESPONSIBLE FOR OBTAINING THOSE NECESSARY MATERIALS AND PROVIDING THE EQUIPMENT AND LABOR TO INSTALL THEM TO MEET THE DESIGN INTENT OF THE WATERMAIN AT NO ADDITIONAL COST TO THE

4. THE CONTRACTOR SHALL NOTIFY THE OWNER AND THE ENGINEER 48 HOURS IN ADVANCE OF ALL REQUIRED TESTS AND INSPECTIONS.

5. THE CONTRACTOR WILL NOTIFY THE ENGINEER IF UNSUITABLE MATERIAL IS DISCOVERED PRIOR TO BEGINNING ANY REMOVAL OPERATION.

6. TOPOGRAPHIC SURVEYING AND BOUNDARY INFORMATION BY THOMAS AND HUTTON

7. ALL ELEVATIONS SHOWN ARE BASED ON NAVD88.

8. CONTRACTOR IS TO VERIFY ACCURACY OF ANY TEMPORARY BENCHMARKS SHOWN PRIOR TO UTILIZING THEM FOR CONSTRUCTION.

9. THE EXISTING UNDERGROUND UTILITIES SHOWN HEREON ARE BASED UPON AVAILABLE INFORMATION. THE CONTRACTOR SHALL BE RESPONSIBLE FOR DETERMINING THE EXACT LOCATION OF ALL UTILITIES OTHER THAN THOSE SHOWN ARE ENCOUNTERED DURING CONSTRUCTION, THE CONTRACTOR SHALL NOTIFY THE ENGINEER IMMEDIATELY AND TAKE STEPS TO PROTECT THE LINE(S) AND ENSURE CONTINUED SERVICE. DAMAGE CAUSED TO EXISTING UTILITIES BY THE CONTRACTOR SHALL BE REPAIRED BY THE CONTRACTOR. ADDITIONALLY, THE CONTRACTOR SHALL CONFIRM THE CONNECTION POINTS OF NEW UTILITIES TO EXISTING UTILITIES PRIOR TO BEGINNING NEW CONSTRUCTION.

IO. IF WORK IS SUSPENDED OR DELAYED FOR 14 DAYS, THE CONTRACTOR SHALL TEMPORARILY STABILIZE THE DISTURBED AREA AT NO ADDITIONAL COST TO THE OWNER.

II. THE CONTRACTOR SHALL INSTALL ANY BARRICADES PRIOR TO BEGINNING CONSTRUCTION 12. ANY DAMAGE TO EXISTING PAVEMENT MUST BE REPAIRED AT CONTRACTORS EXPENSE AND TO THE SATISFACTION OF THE COUNTY ENGINEER AND THE PROJECT ENGINEER.


13. WHERE FIELD INSPECTIONS ARE REQUIRED BY THE COUNTY, THE CONTRACTOR SHALL NOTIFY THE ENGINEERING DIVISION A <u>MINIMUM OF 48 HOURS</u> IN ADVANCE TO SCHEDULE SUCH INSPECTIONS. 14. A COMPLETE SET OF APPROVED DRAWINGS AND SPECIFICATIONS MUST BE MAINTAINED ON SITE AT ALL TIMES THAT THE CONTRACTOR IS PERFORMING WORK. THESE DRAWINGS SHALL BE MADE AVAILABLE UPON


15. ANY REVISIONS DURING CONSTRUCTION WHICH ALTER THE ROAD LAYOUT, CONSTRUCTION METHODS, RIGHT-OF-WAY LOCATION OR DRAINAGE MUST BE SUBMITTED AND APPROVED IN WRITING BY THE ENGINEER. I6. THE CONTRACTOR SHALL INSTALL ALL EROSION CONTROL AND PREVENTION STRUCTURES SHOWN ON THE PLANS. BOTH MUST BE APPROVED BY FLORENCE COUNTY PRIOR TO BEGINNING ANY LAND DISTURBING ACTIVITIES.


17. THE CONTRACTOR SHALL NOTIFY THE ENGINEER IF UNSUITABLE MATERIAL IS DISCOVERED PRIOR TO BEGINNING ANY REMOVAL OPERATION.


18. ALL EROSION AND SEDIMENT CONTROL DEVICES SHALL BE CONSTRUCTED SIMULTANEOUSLY WITH THE DISTURBANCE OF THE LAND AND SHALL REMAIN FUNCTIONAL UNTIL THE CONTRIBUTING DISTURBED AREAS ARE STABILIZED. SILT BARRIERS WILL BE INSTALLED AS NECESSARY TO PREVENT EXCESSIVE SEDIMENTATION OF DOWNSTREAM AREAS. DEVICES SHALL BE IN ACCORDANCE WITH SCDHEC REGULATIONS.

			OWNER
COL	JNTY	FLORENCE	FLORE
ТОМ	٧N	FLORENCE	DEVEL
ZON	NING	N/A	1951 PI (843)
			ENGINE THOMA









SITE	DESCRIPTION				2. STORM WATER MANAGEMENT
A. PR	DJECT DESCRIPTION				RUNOFF FROM THIS PROJECT WILL DISCHARGE INTO TREATMENT WILL OCCUR IN STORM WATER DETENT
	PROJECT AREA		330 ACRES		3. OTHER CONTROLS
	AREA DISTURBED PERCENT IMPERVIOUS AREA BEFORE CONS		8.5 ACRES) %		
	RUNOFF COEFFICIENT BEFORE CONSTRUCT PERCENT IMPERVIOUS AREA AFTER CONST		72.02 CN 35.5 %		3.1. WASTE DISPOSAL
	RUNOFF COEFFICIENT AFTER CONSTRUCTIO	N 71.97 CN	(CURRENT PHASE)		3.1.1. NO SOLID MATERIALS, INCLUDING BUILDING M RECEIVING WATERS.
		81.56 CN	(FULL BUILD OUT)		3.1.2. OFFSITE VEHICLE TRACKING OF SEDIMENTS A
	SCRIPTION OF CONSTRUCTION ACTIVITY				MINIMIZED. 3.1.3. THIS PLAN SHALL COMPLY WITH STATE AND/C
	IRK CONSISTS OF CLEARING AND GRUBBING TH ADWAY ENTRANCE TO THE PARK, MASS GRADIN	,			OR SEPTIC SYSTEM REGULATIONS. 3.1.4. DUST CONTROL ON DISTURBED AREAS - CONTR
	STORMWATER MANAGEMENT STRUCTURES, AN SOCIATED STORM DRAINAGE PIPES, INSTALLATI				ON CONSTRUCTION SITE AND HAUL ROUTES.
CO	NSTRUCTION OF A ENTRANCE SIGN FOR THE PA				THE PRESENCE OF AIRBORNE SUBSTANCES, HUMAN HEALTH, WELFARE OR SAFETY, OR TO
	. SOIL CLASSIFICATIONS: . LAND USE(S):	(HSG) A, C/D WOODS/BRUSH/UNDEVELC	PED	III.	MAINTENANCE
D. RE	CEIVING WATERS				1. MAINTENANCE PROGRAM
	CLOSEST RECEIVING WATERS:	Long Branch			1.1. THE SITE SUPERINTENDENT, OR HIS/HER REPRE OF ALL MECHANICAL CONTROLS AND NEWLY ST
E. FLC		Great Pee Dee River			AND/OR SODDED AREAS) ON A DAILY BASIS; ESF INSURE THAT ALL CONTROLS ARE MAINTAINED A
	FEMA FLOOD ZONE(S):	х			CONTROLS SHALL BE REPAIRED PRIOR TO THE I
E.2	FEMA FLOOD INSURANCE MAP(S):	45041C0180E			AND MULCHING OR RE-SODDING IF NECESSARY
CON	ROL MEASURES				1.2. EROSION CONTROL MEASURES WILL BE MAINTA OF THE APPROVED PLAN DOES NOT PROVIDE FO
1. ER	DSION AND SEDIMENT CONTROLS				EROSION AND SEDIMENTATION CONTROL MEAS
	RIOR TO START OF CONSTRUCTION, ALL EXTER		STALLED AS SHOWN		TREAT THE SEDIMENT SOURCE. ALL DRAINAGE AND OUTLET DITCHES SHALL DRAIN EFFECTIVE
	IN THE PLANS.	ION SIET FENCE WILL DE ING	STALLED AS SHOWN		THAT MAY OCCUR SHALL BE REPAIRED BY THE
1.1.	CLEARING				FROM BEHIND THE SEDIMENT FENCE WHEN IT R SEDIMENT FENCE WILL BE REPAIRED AS NECES
11	1. AS CLEARING IS COMPLETED, ADDITIONAL S	ITEENCE WILL BE INSTALL	ED WHERE		MAINTAIN THE CONSTRUCTION EXIT IN A CONDIT LEAVING THE SITE. THIS MAY REQUIRE PERIODIC
1.1.	NECESSARY, SUCH AS POINTS WHERE FLOW	S BECOME CHANNELIZED,			IMMEDIATELY REMOVE ALL OBJECTIONABLE MA
1.1.	WHERE EXCESSIVE RUNOFF VELOCITIES MA 2. INSTALL CONSTRUCTION ENTRANCES / EXIT		RING		PUBLIC ROADWAYS. RESEED AND MULCH AREA WHERE EROSION OCCURS. PROTECT FROM TRA
	3. CONSTRUCTION DELAYS IN ANY ONE AREA O	REATER THAN 14 DAYS PRI	OR TO START OF		MULCHES PERIODICALLY, AND AFTER RAINSTOR
	ROUGH GRADING WILL MANDATE STABILIZAT STABILIZATION INCLUDE MULCHING AND TEM		TABLE METHODS OF		FAILURE. IF WASHOUT OCCURS, REPAIR THE SL FOLLOW THE CONSTRUCTION SEQUENCE THRO
1.1.	 MAINTAIN EXISTING VEGETATION WHENEVER DISTURBANCE. RETAIN AND PROTECT TREE 				CHANGES IN CONSTRUCTION ACTIVITIES ARE NE ADVANCE TO MAINTAIN MANAGEMENT CONTROL
	AND REDUCE RAINDROP IMPACT.				COPY OF THE MODIFIED SCHEDULE TO THE ENG
1.1.	 INSTALL ALL SEDIMENT CONTROL PRACTICE ACTIVITIES. 	S PRIOR TO ANY UP-SLOPE	SOIL DISTURBING		MEASURES WILL REMAIN IN PLACE AND BE MAIN STABILIZED.
1.1.	6. PHASE CONSTRUCTION ACTIVITIES TO MININ				2. SILT FENCE
	WILL ALSO ALLOW COMPLETED AREAS TO B DISTURBING ADJACENT SITES. THE NEED FO				SILT FENCES WILL BE MONITORED DURING CONST
	MAY BE AVOIDED BY COMPLETING A PHASE . CONTROL MEASURES WHEN THE FINAL GRA		IT EROSION		FUNCTIONING PROPERLY WILL BE PROMPTLY REP REACHES 1/3 THE HEIGHT OF THE FENCE OR REPL
1.1.	7. MAINTAIN AND PROTECT ALL NATURAL WATE	RWAYS. RETAIN AT LEAST			HOURS. USE OF HOSES AND WATER TO FLUSH TH
	UNDISTURBED BUFFER OF NATURAL VEGET/ SEDIMENT AND OTHER POLLUTANTS. MAINT				UNACCEPTABLE. 3. SEDIMENTATION BASINS
11	SENSITIVE WATERS. 8. INSTALL SILT FENCE (OR BIO ROLLS/ROCK SI	OCK PRODUCTS) ON THE DO			SEDIMENTATION BASINS WHICH ARE AT 50% USED
	PERIMETER OF ALL DISTURBED AREAS PRIO	R TO ANY SOIL DISTURBING	ACTIVITIES		SHALL BE RE-EXCAVATED TO ORIGINAL DIMENSIO
	(INCLUDING CLEARING AND GRUBBING). SIL FEET PER LINEAL FOOT OF FENCE. INSTALL				4. SEDIMENT LOGS/ROLLS
	CONTOUR WITH EACH END TURNED UP-SLO ALSO BE PROTECTED WITH SILT FENCE, BIO		ND AREAS SHOULD		SEDIMENT LOGS/ROLLS OR OTHER CONTROL MEA
1.1.	9. IN AREAS OF CONCENTRATED FLOW INSTAL	STRAW BALE CHECKS, RO			FUNCTION INEFFECTIVELY SHALL BE PROMPTLY R 5. VEGETATION COVER
	TRIANGULAR DIKES, BIO ROLL BLANKETS, OF SEDIMENT.	R ROCK SOCKS TO SLOW RU	INOFF AND TRAP		ANY VEGETATION COVER SERVING TO STABILIZE I
1 1	10. USE TEMPORARY SLOPE DRAINS OR ROCK (SHALL IMMEDIATELY BE REPLACED.
1.1.	10. USE TEMPORARY SLOPE DRAINS OR ROCK C	HUTES TO MOVE WATER DO	JWN STEEP SLOPES.		6. CONSTRUCTION ENTRANCE
1.1.	11. CONSTRUCT SEDIMENT BASINS FOR DRAINA	GE AREAS GREATER THAN	10 ACRES		MAINTAIN ROCK CONSTRUCTION ENTRANCE AND (TRACKED ONTO THEM.
1.2.	ROUGH GRADING				HOURED ON TO THEM.
1.2.	1. ALL EXISTING CONTROLS WILL BE MAINTAIN			IV.	INSPECTIONS
	GREATER THAN 14 DAYS PRIOR TO START O PROCEDURES. ACCEPTABLE METHODS OF S				1. QUALIFIED PERSONNEL WILL INSPECT DISTURBED A
12	TEMPORARY SEEDING. 2. ALL AREAS NOT SUBJECT TO FURTHER CON	STRUCTION (DRAINAGE SAI	NITARY SEWER		USED FOR STORAGE OF MATERIALS THAT ARE EXPO FINALLY STABILIZED, STRUCTURAL CONTROL MEASI
	ROADS, WATER DISTRIBUTION SYSTEMS, OR	•			ENTER OR EXIT THE SITE AT LEAST ONCE EVERY SE BEEN FINALLY STABILIZED SUCH INSPECTIONS SHAI
1.2.	WITH A PERMANENT COVER. 3. COVER ANY STOCK PILED TOPSOIL WITH PL/	STIC (OR OTHER IMPERVIO	US COVERING) OR		MONTH DURING THE WARRANTY PERIOD.
	USE A TEMPORARY SEED MIX. USE STOCKP TEMPORARY SEDIMENT BASINS.	LED TOPSOIL AS EARTHEN	BERMS TO SERVE AS		2. DISTURBED AREAS AND AREAS USED FOR STORAGE
1.3.	DRAINAGE				PRECIPITATION SHALL BE INSPECTED FOR EVIDENCI ENTERING THE DRAINAGE SYSTEM. EROSION AND S
					THE PLAN SHALL BE OBSERVED TO ENSURE THAT T DISCHARGE LOCATIONS OR POINTS ARE ACCESSIBL
	 ALL EXISTING CONTROLS WILL BE MAINTAIN CONSTRUCTION DRAINAGE WILL BE ROUTED 				WHETHER EROSION CONTROL MEASURES ARE EFFI
1 2	SEDIMENT BASINS OR OTHER ACCEPTABLE 3. STORM DRAIN INLET PROTECTION AS SHOW				TO RECEIVING WATERS. LOCATIONS WHERE VEHICL INSPECTED FOR EVIDENCE OF OFFSITE SEDIMENT T
	CURB INLETS, STORM DRAIN MANHOLES, JU	NCTION BOXES, AND GRATE	INLETS.		3. A WRITTEN REPORT SUMMARIZING THE SCOPE OF T
1.3.	 DELAYS OF GREATER THAN 14 DAYS PRIOR SEQUENCE WILL MANDATE STABILIZATION P 				OF PERSONNEL MAKING THE INSPECTION, THE DATE INFORMATION FOR THE PERIOD SINCE THE LAST INS
1.0	STABILIZATION INCLUDE MULCHING AND TEM 5. ALL STORM LINES NOT IN STREETS OR OTHE				CONSTRUCTION ACTIVITY) INCLUDING A BEST ESTIM EVENT. DURATION OF EACH STORM EVENT. APPROX
1.3.	SEEDED WITHIN 5 DAYS AFTER BACKFILL.	R PAVED AREAS ARE TO BE	MULCHED AND		EVENT (IN INCHES) AND WHETHER ANY DISCHARGES
14	WASTE DISTRIBUTION SYSTEM INSTALLATION				SEDIMENT OR OTHER POLLUTANTS FROM THE SITE, MAINTENANCE, LOCATION(S) OF BMP'S THAT FAILED
					INADEQUATE FOR A PARTICULAR LOCATION, LOCATI THAT DID NOT EXIST AT THE TIME OF INSPECTION AN
1.4.	 ALL EXISTING CONTROLS WILL BE MAINTAIN DISTRIBUTION SYSTEM. 	ED DURING INSTALLATION C	F THE WATER		INCLUDING ANY CHANGES TO SWPPP NECESSARY A
1.4.	 DELAYS OF GREATER THAN 14 DAYS PRIOR STABILIZATION PROCEDURES. ACCEPTABLE 				4. THE REPORT SHALL BE MAINTAINED AT LEAST THRE
	MULCHING AND TEMPORARY SEEDING.				STABILIZED. THE REPORT MUST BE SIGNED AND SH. FACILITY IS IN COMPLIANCE WITH THE STORM WATE
1.5.	WASTEWATER COLLECTION SYSTEM INSTALLA	TION			NPDES PERMIT REFERENCED ABOVE. THE CONTRAC REPORT SHALL BE SUBMITTED TO THE ENGINEER AN
15	1. ALL EXISTING CONTROLS WILL BE MAINTAIN	ED DURING INSTALLATION C	F THE WASTFWATER	V	LONG TERM MAINTENANCE OF DRAIN
	SYSTEM.			۷.	MANAGEMENT SYSTEM
1.5.	 DELAYS OF GREATER THAN 14 DAYS PRIOR STABILIZATION PROCEDURES. ACCEPTABLE 				
	MULCHING AND TEMPORARY SEEDING.				THE ROADS AND DRAINAGE SYSTEM WILL BE OWNEI AFTER CONSTRUCTION IS COMPLETE.
1.6.	CONSTRUCTION OF ROADS			۱ <i>۲</i> ۱	SC DHEC STANDARD NOTES
	1. ALL EXISTING CONTROLS WILL BE MAINTAIN			۷I.	OU DITLU STANDARD NUTES
1.6.	2. DELAYS OF GREATER THAN 14 DAYS PRIOR STABILIZATION PROCEDURES. ACCEPTABLE				1. IF NECESSARY, SLOPES WHICH EXCEED EIGHT (8) VE
	MULCHING AND TEMPORARY SEEDING.				SYNTHETIC OR VEGETATIVE MATS, IN ADDITION TO C NECESSARY TO INSTALL TEMPORARY SLOPE DRAIN
1.7.	GRASSING				BERMS MAY BE NEEDED UNTIL THE SLOPE IS BROUG
	1. ALL EXISTING CONTROLS WILL BE MAINTAIN				2. STABILIZATION MEASURES SHALL BE INITIATED AS S SITE WHERE CONSTRUCTION ACTIVITIES HAVE TEMP
1.7.	 ANY AREAS THAT ERODE OR WHERE GRASS RE-GRADED AND RE-GRASSED. 	DOES NOT ESTABLISH ITSE	LF SHALL BE		NO CASE MORE THAN FOURTEEN (14) DAYS AFTER V

- ELY SHALL BE PROMPTLY REPLACED.
- E REPLACED. CF
- RUCTION ENTRANCE AND CLEAN ADJACENT ROADS OF ANY MUD
- RANTY PERIOD.
- CE OF OFFSITE SEDIMENT TRACKING.
- THE INSPECTION, THE DATE(S) OF THE INSPECTION, WEATHER LUTANTS FROM THE SITE LOCATION(S) OF BMP'S THAT NEED I(S) OF BMP'S THAT FAILED TO OPERATE AS DESIGNED OR PROVED TO SWPPP NECESSARY AND IMPLEMENTATION DATES.
- TTED TO THE ENGINEER AND OWNER.
- ENANCE OF DRAINAGE AND STORM WATER FM

GE SYSTEM WILL BE OWNED AND MAINTAINED BY FLORENCE COUNTY S COMPLETE.

- RD NOTES
- JNTIL THE SLOPE IS BROUGHT TO GRADE.
- BELOW:
- 2.1. WHERE STABILIZATION BY THE 14TH DAY IS PRECLUDED BY SNOW COVER OR FROZEN GROUND
- CONDITIONS STABILIZATION MEASURES MUST BE INITIATED AS SOON AS PRACTICABLE. 2.2. WHERE CONSTRUCTION ACTIVITY ON A PORTION OF THE SITE IS TEMPORARILY CEASED, AND EARTH-DISTURBING ACTIVITIES WILL BE RESUMED WITHIN 14 DAYS. TEMPORARY STABILIZATION MEASURES DO NOT HAVE TO BE INITIATED ON THAT PORTION OF THE SITE.
- 3. ALL SEDIMENT AND EROSION CONTROL DEVICES SHALL BE INSPECTED ONCE EVERY CALENDAR WEEK. IF SITE INSPECTIONS IDENTIFY BMP'S THAT ARE DAMAGED OR ARE NOT OPERATING EFFECTIVELY. MAINTENANCE MUST BE PERFORMED AS SOON AS PRACTICAL OR AS REASONABLY POSSIBLE BEFORE THE NEXT STORM EVENT WHENEVER PRACTICAL

IECT WILL DISCHARGE INTO A STORM WATER MANAGEMENT SYSTEM. IN STORM WATER DETENTION PONDS.

- LS, INCLUDING BUILDING MATERIALS, SHALL BE DISCHARGED TO ANY
- RACKING OF SEDIMENTS AND THE GENERATION OF DUST SHALL BE
- COMPLY WITH STATE AND/OR LOCAL WASTE DISPOSAL, SANITARY SEWER
- DISTURBED AREAS CONTROLLING SURFACE AND AIR MOVEMENT OF DUST N SITE AND HAUL ROUTES. THE PURPOSE OF THE MEASURE IS TO REDUCE AIRBORNE SUBSTANCES, WHICH MAY BE HARMFUL OR INJURIOUS TO ELFARE OR SAFETY, OR TO ANIMALS OR PLANT LIFE.

NDENT, OR HIS/HER REPRESENTATIVE, SHALL MAKE VISUAL INSPECTIONS CONTROLS AND NEWLY STABILIZED AREAS (I.E. SEEDED AND MULCHED EAS) ON A DAILY BASIS; ESPECIALLY AFTER HEAVY RAINFALL EVENT TO NTROLS ARE MAINTAINED AND PROPERLY FUNCTIONING. ANY DAMAGED REPAIRED PRIOR TO THE END OF THE WORK DAY INCLUDING RE-SEEDING

A MEASURES WILL BE MAINTAINED AT ALL TIMES. IF FULL IMPLEMENTATION LAN DOES NOT PROVIDE FOR EFFECTIVE EROSION CONTROL, ADDITIONAL ENTATION CONTROL MEASURES SHALL BE IMPLEMENTED TO CONTROL OR T SOURCE. ALL DRAINAGE SWALES, POCKETS, DEPRESSION, LOW LINES, S SHALL DRAIN EFFECTIVELY AT ALL TIMES. SETTLEMENT OR WASHING ALL BE REPAIRED BY THE CONTRACTOR. SEDIMENT WILL BE REMOVED EDIMENT FENCE WHEN IT REACHES 1/3 THE HEIGHT OF THE FENCE. THE LL BE REPAIRED AS NECESSARY TO MAINTAIN AN EFFECTIVE BARRIER FRUCTION EXIT IN A CONDITION TO PREVENT MUD OR SEDIMENT FROM HIS MAY REQUIRE PERIODIC TOP DRESSING WITH ADDITIONAL STONE. VE ALL OBJECTIONABLE MATERIALS SPILLED, WASHED, OR TACKED ONTO RESEED AND MULCH AREA WHERE SEEDING EMERGENCE IS POOR, OR CURS. PROTECT FROM TRAFFIC AS MUCH AS POSSIBLE. INSPECT ALL ALLY, AND AFTER RAINSTORMS TO CHECK FOR EROSION, DISLOCATION OR IT OCCURS, REPAIR THE SLOPE GRADE, RESEED AND REINSTALL MULCH. RUCTION SEQUENCE THROUGHOUT THE PROJECT DEVELOPMENT. WHEN RUCTION ACTIVITIES ARE NEEDED. AMEND THE SEQUENCE SCHEDULE IN AIN MANAGEMENT CONTROL. IF MAJOR CHANGES ARE NECESSARY, SEND A ED SCHEDULE TO THE ENGINEER, SEDIMENT AND EROSION CONTROL IAIN IN PLACE AND BE MAINTAINED UNTIL THE DISTURBED AREAS ARE

IONITORED DURING CONSTRUCTION. ANY SILT FENCE WHICH IS NOT Y WILL BE PROMPTLY REPAIRED. CLEAN OUT THE SILT FENCE WHEN IT TOF THE FENCE OR REPLACE WITH FUNCTIONAL SILT FENCE WITHIN 24 AND WATER TO FLUSH THE SEDIMENT INTO THE STORM INLETS IS

WHICH ARE AT 50% USED CAPACITY OR APPROACHING SUCH CAPACITY ED TO ORIGINAL DIMENSIONS AND THE SILT PROPERLY DISPOSED OF

OR OTHER CONTROL MEASURES WHICH BEGIN TO DISINTEGRATE OR

ER SERVING TO STABILIZE DISTURBED SOILS WHICH IS ITSELF DISTURBED

ATERIALS THAT ARE EXPOSED TO PRECIPITATION THAT HAVE NOT BEEN UCTURAL CONTROL MEASURES AND LOCATIONS WHERE VEHICLES AT LEAST ONCE EVERY SEVEN CALENDAR DAYS. WHERE SITES HAVE D SUCH INSPECTIONS SHALL BE CONDUCTED AT LEAST ONCE EVERY

AREAS USED FOR STORAGE OF MATERIALS THAT ARE EXPOSED TO INSPECTED FOR EVIDENCE OF. OR THE POTENTIAL FOR. POLLUTANTS SYSTEM. EROSION AND SEDIMENT CONTROL MEASURES IDENTIFIED IN ERVED TO ENSURE THAT THEY ARE OPERATING CORRECTLY. WHERE OR POINTS ARE ACCESSIBLE, THEY SHALL BE INSPECTED TO ASCERTAIN TROL MEASURES ARE EFFECTIVE IN PREVENTING SIGNIFICANT IMPACTS OCATIONS WHERE VEHICLES ENTER OR EXIT THE SITE SHALL BE

MARIZING THE SCOPE OF THE INSPECTION, NAME(S) AND QUALIFICATIONS FRIOD SINCE THE LAST INSPECTION (OR SINCE COMMENCEMENT OF () INCLUDING A BEST ESTIMATE OF THE BEGINNING OF EACH STORM CH STORM EVENT, APPROXIMATE AMOUNT OF RAINFALL FOR EACH STORM /HETHER ANY DISCHARGES OCCURRED, LOCATION(S) OF DISCHARGES OF

ICULAR LOCATION, LOCATION(S) WHERE ADDITIONAL BMP'S ARE NEEDED HE TIME OF INSPECTION AND ANY CORRECTIVE ACTION REQUIRED

AINTAINED AT LEAST THREE YEARS FROM THE DATE THE SITE IS FINALLY MUST BE SIGNED AND SHALL CONTAIN A CERTIFICATION THAT THE CE WITH THE STORM WATER POLLUTION PREVENTION PLAN AND THE CED ABOVE. THE CONTRACTOR SHALL MAINTAIN THIS REPORT. THE

VHICH EXCEED EIGHT (8) VERTICAL FEET SHOULD BE STABILIZED WITH IVE MATS, IN ADDITION TO GRASSING / HYDROSEEDING. IT MAY BE TEMPORARY SLOPE DRAINS DURING CONSTRUCTION. TEMPORARY

S SHALL BE INITIATED AS SOON AS PRACTICABLE IN PORTIONS OF THE TION ACTIVITIES HAVE TEMPORARILY OR PERMANENTLY CEASED. BUT IN JRTEEN (14) DAYS AFTER WORK HAS CEASED, EXCEPT AS STATED

STORMWATER POLLUTION PREVENTION PLAN

- 4. PROVIDE SILT FENCE AND/OR OTHER CONTROL DEVICES, AS MAY BE REQUIRED, TO CONTROL SOIL EROSION DURING UTILITY CONSTRUCTION. ALL DISTURBED AREAS SHALL BE CLEANED, GRADED AND STABILIZED WITH GRASSING IMMEDIATELY AFTER THE UTILITY INSTALLATION. FILL, COVER, AND TEMPORARY SEEDING AT THE END OF EACH DAY ARE RECOMMENDED. IF WATER IS ENCOUNTERED WHILE TRENCHING, THE WATER SHOULD BE FILTERED TO REMOVE ANY SEDIMENTS BEFORE BEING PUMPED INTO ANY WATERS OF THE STATE.
- 5. ALL EROSION CONTROL DEVICES SHALL BE PROPERLY MAINTAINED DURING ALL PHASES OF CONSTRUCTION UNTIL THE COMPLETION OF ALL CONSTRUCTION ACTIVITIES AND ALL DISTURBED AREAS HAVE BEEN STABILIZED. ADDITIONAL CONTROL DEVICES MAY BE REQUIRED DURING CONSTRUCTION IN ORDER TO CONTROL EROSION AND/OR OFFSITE SEDIMENTATION. ALL TEMPORARY CONTROL DEVICES SHALL BE REMOVED ONCE CONSTRUCTION IS COMPLETE AND THE SITE IS STABILIZED.
- THE CONTRACTOR MUST TAKE NECESSARY ACTION TO MINIMIZE THE TRACKING OF MUD ONTO THE PAVED ROADWAY FROM CONSTRUCTION AREAS AND THE GENERATION OF DUST. THE CONTRACTOR SHALL DAILY REMOVE MUD/SOIL FROM PAVEMENT AS MAY BE REQUIRED.
- RESIDENTIAL SUBDIVISIONS REQUIRE EROSION CONTROL FEATURES FOR INFRASTRUCTURE AS WELL AS FOR INDIVIDUAL LOT CONSTRUCTION. INDIVIDUAL PROPERTY OWNERS SHALL FOLLOW THESE PLANS DURING CONSTRUCTION OR OBTAIN APPROVAL OF AN INDIVIDUAL PLAN IN ACCORDANCE WITH S.C. REG. 72-300 AND SCR100000.
- 8. TEMPORARY DIVERSION BERMS AND/OR DITCHES WILL BE PROVIDED AS NEEDED DURING CONSTRUCTION TO PROTECT WORK AREAS FROM UPSLOPE RUNOFF AND/OR TO DIVERT SEDIMENT LADEN WATER TO APPROPRIATE TRAPS OR STABLE OUTLETS.
- ALL WATERS OF THE STATE (WOS), INCLUDING WETLANDS, ARE TO BE FLAGGED OR OTHERWISE CLEARLY MARKED IN THE FIELD. A DOUBLE ROW OF SILT FENCE IS TO BE INSTALLED IN ALL AREAS WHERE A 50-FOOT BUFFER CAN NOT BE MAINTAINED BETWEEN THE DISTURBED AREA AND ALL WOS. A 10-FOOT BUFFER SHOULD BE MAINTAINED BETWEEN THE LAST ROW OF SILT FENCE AND ALL WOS
- 10. LITTER, CONSTRUCTION DEBRIS, OILS, FUELS, AND BUILDING PRODUCTS WITH SIGNIFICANT POTENTIAL FOR IMPACT (SUCH AS STOCKPILES OF FRESHLY TREATED LUMBER) AND CONSTRUCTION CHEMICALS THAT COULD BE EXPOSED TO STORM WATER MUST BE PREVENTED FROM BECOMING A POLLUTANT SOURCE IN STORM WATER DISCHARGES.
- 11. A COPY OF THE SWPPP, INSPECTION RECORDS AND RAINFALL DATA MUST BE RETAINED AT THE CONSTRUCTION SITE OR A NEARBY LOCATION FASILY ACCESSIBLE DURING NORMAL BUSINESS. HOURS, FROM THE DATE OF COMMENCEMENT OF CONSTRUCTION ACTIVITIES TO THE DATE THAT FINAL STABILIZATION IS REACHED.
- 12 INITIATE STABILIZATION MEASURES ON ANY EXPOSED STEEP SLOPE (3H-1V OR GREATER) WHERE LAND DISTURBING ACTIVITIES HAVE PERMANENTLY OR TEMPORARILY CEASED, AND WILL NOT RESUME FOR A PERIOD OF 7 CALENDAR DAYS.
- 13. MINIMIZE SOIL COMPACTION IN AREAS NOT UNDER PAVEMENTS AND /OR STRUCTURES AND, UNLESS INFEASIBLE, PRESERVE TOPSOIL.
- 14. MINIMIZE THE DISCHARGE OF POLLUTANTS FROM EQUIPMENT AND VEHICLE WASHING, WHEEL WASH WATER AND OTHER WASH WATERS. WASH WATERS MUST BE TREATED IN A SEDIMENT BASIN OR ALTERNATIVE CONTROL THAT PROVIDES EQUAL OR BETTER TREATMENT PRIOR TO DISCHARGE.
- 15. MINIMIZE THE DISCHARGE OF POLLUTANTS FROM DEWATERING OF TRENCHES AND EXCAVATED AREAS. THESE DISCHARGES ARE TO BE ROUTED THROUGH APPROPRIATE BMPS (SEDIMENT BASIN, FILTER BAG, ETC.).
- 16. THE FOLLOWING DISCHARGES ARE PROHIBITED:
- 16.1. WASTEWATER FROM WASHOUT OF CONCRETE, UNLESS MANAGED BY AN APPROPRIATE CONTROL: 16.2. WASTEWATER FROM WASHOUT AND CLEANOUT OF OF STUCCO, PAINT, FORM RELEASE OILS,
- CURING COMPOUNDS AND OTHER CONSTRUCTION MATERIALS; 16.3. FUELS, OILS OR OTHER POLLUTANTS USED IN VEHICLE AND EQUIPMENT OPERATION AND MAINTENANCE: AND
- 16.4. SOAPS OR SOLVENTS USED IN VEHICLE AND EQUIPMENT WASHING.
- 17. AFTER CONSTRUCTION ACTIVITIES BEGIN, INSPECTIONS MUST BE CONDUCTED AT A MINIMUM OF AT LEAST ONCE EVERY CALENDAR WEEK AND MUST BE CONDUCTED UNTIL FINAL STABILIZATION IS REACHED ON ALL AREAS OF THE CONSTRUCTION SITE.
- 18. IF EXISTING BMPS NEED TO BE MODIFIED OR IF ADDITIONAL BMPS ARE NECESSARY TO COMPLY WITH THE REQUIREMENTS OF PERMIT SCR100000 AND/OR SC'S WATER QUALITY STANDARDS, IMPLEMENTATION MUST BE COMPLETED BEFORE THE NEXT STORM EVENT WHENEVER PRACTICABLE IF IMPLEMENTATION BEFORE THE NEXT STORM EVENT IS IMPRACTICABLE THE SITUATION MUST BE DOCUMENTED IN THE SWPPP AND ALTERNATIVE BMPS MUST BE IMPLEMENTED THESE PERFORMANCE STANDARDS APPLY TO ALL SITES. AS SOON AS REASONABLY POSSIBLE.
- 19. A PRE-CONSTRUCTION CONFERENCE MUST BE HELD FOR EACH CONSTRUCTION SITE WITH AN APPROVED ON-SITE SWPPP PRIOR TO THE IMPLEMENTATION OF CONSTRUCTION ACTIVITIES. FOR NON-LINEAR PROJECTS THAT DISTURB 10 ACRES OR MORE, THIS CONFERENCE MUST BE HELD ON-SITE UNLESS THE DEPARTMENT HAS APPROVED OTHERWISE.

VILL INSPECT DISTURBED AREAS OF THE CONSTRUCTION SITE, AREAS VII. EROSION, SEDIMENTATION & POLLUTION CONTROL NOTES

- 1. THE IMPLEMENTATION OF THESE EROSION SEDIMENT CONTROL (ESC) PLANS AND THE CONSTRUCTION, MAINTENANCE, REPLACEMENT, AND UPGRADING OF THESE ESC FACILITIES IS THE RESPONSIBILITY OF THE CONTRACTOR UNTIL ALL CONSTRUCTION IS COMPLETED AND APPROVED AND VEGETATION/LANDSCAPING IS ESTABLISHED.
- 2. THE ESC FACILITIES SHOWN ON THIS PLAN MUST BE CONSTRUCTED IN CONJUNCTION WITH ALL CLEARING AND GRADING ACTIVITIES, AND IN SUCH A MANNER AS TO INSURE THAT SEDIMENT AND SEDIMENT LADEN WATER DO NOT ENTER THE DRAINAGE SYSTEM, ROADWAYS, OR VIOLATE APPLICABLE WATER STANDARDS
- THE ESC FACILITIES SHOWN ON THIS PLAN ARE THE MINIMUM REQUIREMENTS FOR ANTICIPATED SITE CONDITIONS. DURING THE CONSTRUCTION PERIOD, THESE ESC FACILITIES SHALL BE UPGRADED AS NEEDED FOR UNEXPECTED STORM EVENTS AND TO ENSURE THAT SEDIMENT AND SEDIMENT LADEN WATER DO NOT LEAVE THE SITE.
- 4. THE ESC FACILITIES SHALL BE INSPECTED DAILY BY THE CONTRACTOR AND MAINTAINED AS NECESSARY TO ENSURE THEIR CONTINUED FUNCTIONING.
- THE ESC FACILITIES ON INACTIVE SITES SHALL BE INSPECTED AND MAINTAINED A MINIMUM OF ONCE A MONTH OR WITHIN THE 24 HOURS FOLLOWING A MAJOR STORM EVENT.
- 6. AT NO TIME SHALL MORE THAN ONE FOOT OF SEDIMENT BE ALLOWED TO ACCUMULATE WITHIN A CATCH BASIN. ALL CATCH BASINS AND CONVEYANCE LINES SHALL BE CLEANED PRIOR TO PAVING AND PRIOR TO FINAL INSPECTION. THE CLEANING OPERATION SHALL NOT FLUSH SEDIMENT LADEN WATER INTO THE DOWNSTREAM SYSTEM
- STABILIZED CONSTRUCTION ENTRANCES SHALL BE INSTALLED AT THE BEGINNING OF CONSTRUCTION AND MAINTAINED FOR THE DURATION OF THE PROJECT. ADDITIONAL MEASURES MAY BE REQUIRED TO INSURE THAT ALL PAVED AREAS ARE KEPT CLEAN FOR THE DURATION OF THE PROJECT
- 8. BEFORE COMMENCING ANY LAND DISTURBING ACTIVITY, THE EXISTING STORM WATER INLET(S) THAT RECEIVING RUNOFF FROM THE PROPOSED WORK AREA SHALL BE PROTECTED. THE TEMPORARY INLET PROTECTION MUST REMAIN IN PLACE UNTIL THE CONSTRUCTION ACTIVITY IS COMPLETED, THE STREET HAS BEEN SWEPT AND ANY EXPOSED SOILS ARE STABILIZED. THE CONTRACTOR IS ALSO RESPONSIBLE FOR REMOVING ANY TEMPORARY INLET PROTECTION INSTALLED; AFTER ALL DISTURBED AREAS ARE STABILIZED. TEMPORARY PROTECTION OF THE INLETS MAY BE ACCOMPLISHED BY ONE OR MORE OF THE FOLLOWING:
- 8.1. USE OF GRAVEL BAGS TO FILTER THE SEDIMENT FROM ANY RUNOFF. TO MAKE A GRAVEL BAG, USE A BAG MADE OF GEOTEXTILE FABRIC (NOT BURLAP) AND FILL WITH EITHER 3/4 INCH ROCK OR 1/4 INCH PEA GRAVEL.
- 8.2. USE OF SEDIMENT LOGS TO FILTER THE SEDIMENT FROM ANY RUNOFF (AVAILABLE THROUGH LOCAL EROSION CONTROL SUPPLIERS).
- 8.3. USE OF ABOVE OR UNDER-GRATE FILTER BAGS OR DEVICES TO FILTER THE SEDIMENT FROM ANY RUNOFF (AVAILABLE THROUGH EROSION CONTROL SUPPLIERS).
- 9. WATER MAY NOT BE DISCHARGED IN A MANNER THAT CAUSES EROSION, SEDIMENTATION, OR FLOODING ON THE SITE, ON DOWNSTREAM PROPERTIES, IN THE RECEIVING CHANNELS, OR IN ANY STORM WATER INLET. WHEN SITE DEWATERING, WATER PUMPED FROM THE SITE, INCLUDING TRENCHES, SHALL BE TREATED BY ONE OF THE FOLLOWING:
- 9.1. TEMPORARY SEDIMENTATION BASINS 9.2. SEDIMENT FILTERING BAGS
- 10. THE CONTRACTOR SHALL VERIFY THE SIZE AND LOCATION OF ALL EXISTING UTILITIES. EXISTING UTILITIES ARE ALL UTILITIES THAT EXIST ON THE PROJECT IN AN ORIGINAL. RELOCATED OR NEWLY INSTALLED POSITION. THE CONTRACTOR SHALL BE HELD RESPONSIBLE FOR THE COST OF REPAIRS TO DAMAGED UNDERGROUND OR OVERHEAD FACILITIES, EVEN IF THE UTILITY IS NOT SHOWN ON THE SITE DEVELOPMENT PLANS. THE CONTRACTOR SHALL CONTACT THE LOCAL UTILITIES PROTECTION CENTER TO COORDINATE THE MARKING OF EXISTING UTILITY LINES A MINIMUM OF 96 HOURS PRIOR TO COMMENCEMENT OF ANY WORK.

- 11. THE CONTRACTOR SHALL FLUSH ALL INLETS AND PIPE AT THE COMPLETION OF CONSTRUCTION TO REMOVE SILT AND DEBRIS. THE CLEANING AND FLUSHING OF INLETS AND PIPE (EXISTING AND PROPOSED) SHALL BE CONSIDERED PART OF THE COST FOR THE PROJECT.
- 12. EGRESS FROM THE SITE SHALL BE CONTROLLED SUCH THAT VEHICLES LEAVING THE SITE MUST TRAVERSE CONSTRUCTION EXITS TO REMOVE MUD FROM TIRES.
- 13. SCHEDULE CONSTRUCTION ACTIVITIES TO MINIMIZE THE EXPOSED AREA AND DURATION OF EXPOSURE. IN SCHEDULING, TAKE INTO ACCOUNT THE SEASON AND THE WEATHER FORECAST.
- 14. EROSION CONTROL MEASURES ARE THE MINIMUM REQUIRED. THE CONTRACTOR SHALL PROVIDE ADDITIONAL CONTROL MEASURES AS DICTATED BY ACTUAL FIELD CONDITIONS AT THE TIME OF CONSTRUCTION IN ORDER TO PREVENT EROSION AND CONTROL SEDIMENT. EROSION AND SEDIMENT CONTROL MEASURES WILL REMAIN IN PLACE AND BE MAINTAINED UNTIL THE ENTIRE PROJECT IS TERMINATED OR SUSPENDED FOR AND INDEFINITE LENGTH OF TIME, ALL DISTURBED AREAS SHALL BE PLANTED WITH PERMANENT VEGETATION.
- 5. THE DATA, TOGETHER WITH ALL OTHER INFORMATION SHOWN ON THESE PLANS, OR IN ANY WAY INDICATED THEREBY, WHETHER BY DRAWINGS OR NOTES, OR IN ANY OTHER MANNER, IS BASED UPON FIELD INVESTIGATIONS AND IS BELIEVED TO BE INDICATIVE OF ACTUAL CONDITIONS. HOWEVER, THE SAME IS SHOWN AS INFORMATION ONLY, IS NOT GUARANTEED AND DOES NOT BIND THOMAS & HUTTON, OR THE OWNER IN ANY WAY.
- 16. CONTRACTOR SHALL MAINTAIN SITE ON A DAILY BASIS TO PROVIDE FOR POSITIVE DRAINAGE. CONTRACTOR, AT HIS COST, SHALL GRADE SITE AND PROVIDE NECESSARY TEMPORARY DRAINAGE SWALES TO INSURE STORM WATER DOES NOT POND ON SITE.
- 17. SITE DRAINAGE SHALL BE ESTABLISHED TO PREVENT ANY PONDED WATER CONDITIONS WITHIN THE CONSTRUCTION AREA AND TO FACILITATE STORM WATER DISCHARGE.
- 18. THE ESCAPE OF SEDIMENT FROM THE SITE SHALL BE PREVENTED BY THE INSTALLATION OF EROSION AND SEDIMENT CONTROL MEASURES AND PRACTICES PRIOR TO, OR CONCURRENT WITH, LAND DISTURBING ACTIVITIES.
- 19. LIME RATES AND ANALYSIS:
- 19.1. AGRICULTURAL LIME SHALL BE APPLIED AT THE RATE SHOWN IN THE SEEDING SECTION UNLESS SOIL TESTS INDICATE OTHERWISE. GRADED AREAS REQUIRE LIME APPLICATION. IF LIME IS APPLIED WITHIN SIX MONTHS OF PLANTING PERMANENT PERENNIAL VEGETATION. ADDITIONAL LIME IS NOT REQUIRED. AGRICULTURAL LIME APPLICATION SHALL BE WITHIN THE SPECIFICATIONS OF THE SOUTH CAROLINA DEPARTMENT OF AGRICULTURE.
- 20. MULCHING:

MULCHING IS REQUIRED FOR ALL PERMANENT VEGETATION APPLICATIONS. MULCH APPLIED TO SEEDED AREAS SHALL ACHIEVE 75% SOIL COVER. SELECT THE MULCHING MATERIAL FROM THE FOLLOWING AND APPLY AS INDICATED:

- 20.1. DRY STRAW OR DRY HAY OF GOOD QUALITY AND FREE OF WEED SEEDS CAN BE USED. DRY STRAW SHALL BE APPLIED AT THE RATE OF TWO TONS PER ACRE. DRY HAY SHALL BE APPLIED AT THE RATE OF 2 1/2 TONS PER ACRE.
- 20.2. WOOD CELLULOSE MULCH OR WOOD PULP FIBER SHALL BE USED WITH HYDRAULIC SEEDING IT SHALL BE APPLIED AT A RATE OF 500 POUNDS PER ACRE. DRY STRAW OR DRY HAY SHALL BE APPLIED (AT THE RATE INDICATED ABOVE) AFTER HYDRAULIC SEEDING.
- 20.3. ONE THOUSAND POUNDS OF WOOD CELLULOSE OR WOOD PULP FIBER, WHICH INCLUDES A TACKIFIER, SHALL BE USED WITH HYDRAULIC SEEDING ON SLOPES 3/4:1 OR STEEPER.
- 20.4. SERICEA LESPEDEZA HAY CONTAINING MATURE SEED SHALL BE APPLIED AT A RATE OF 3 TONS PER ACRE. 20.5. PINE STRAW OR PINE BARK SHALL BE APPLIED AT A THICKNESS OF 3 INCHES FOR BEDDING
- PURPOSES. OTHER SUITABLE MATERIALS IN SUFFICIENT QUANTITY MAY BE USED WHERE ORNAMENTALS OR OTHER GROUND COVERS ARE PLANTED. THIS IS NOT APPROPRIATE FOR SEEDED AREAS.
- 20.6. WHEN USING TEMPORARY EROSION CONTROL BLANKETS OR BLACK SOD, MULCH IS NOT REQUIRED 20.7. ON SLOPES GREATER THAN 10 FEET IN LENGTH AND 4:1 OR STEEPER, USE THE FOLLOWING
- EROSION CONTROL BLANKETS THAT HAVE BEEN PROPERLY ANCHORED TO THE SLOPE ACCORDING TO THE MANUFACTURER'S INSTRUCTIONS:
- 2:1 SLOPES OR STEEPER: STRAW/COCONUT BLANKET OR HIGH VELOCITY WOOD BLANKET • 3:1 SLOPES OR STEEPER: - WOOD OR STRAW BLANKET WITH NET ON BOTH SIDES • 4:1 SLOPES OR FLATTER: - WOOD OR STRAW MULCH BLANKET WITH NET ON ONE SIDE

VIII. HOUSEKEEPING

- 1. PETROLEUM PRODUCTS: INCLUDING OIL, GASOLINE, LUBRICANTS AND ASPHALTIC SUBSTANCES
- 1.1. HAVE EQUIPMENT TO CONTAIN AND CLEAN UP PETROLEUM SPILLS IN FUEL STORAGE AREAS OR ON MAINTENANCE AND FUELING VEHICLES
- 1.2. STORE IN COVERED AREAS PROTECTED WITH DIKES
- SPILLS: PREVENTION AND RESPONSE
- 2.1. STORE AND HANDLE MATERIALS TO PREVENT SPILLS
- 2.2. TIGHTLY SEALED CONTAINERS. NEAT AND SECURE STACKING. ETC. 2.3 REDUCE STORM WATER CONTACT IF SPILL OCCURS 2.3.1. CLEANUP PROCEDURES SHOULD BE CLEARLY POSTED
- 2.3.2. CLEANUP MATERIALS SHOULD BE READILY AVAILABLE 2.3.3. STOP THE SOURCE 2.3.4. CONTAIN THE SPILL
- NON-STORM WATER DISCHARGES

THE FOLLOWING NON-STORMWATER DISCHARGES MUST BE PROTECTED FROM CAUSING POLLUTION OR EROSION:

- 3.1. DISCHARGES FROM FIRE-FIGHTING ACTIVITIES
- 3.2. FIRE HYDRANT FLUSHINGS
- 3.3. WATERS USED TO WASH VEHICLES WHERE DETERGENTS ARE NOT USED 3.4. WATER USED TO CONTROL DUST
- 3.5. POTABLE WATER INCLUDING UNCONTAMINATED WATER LINE FLUSHINGS
- 3.6. ROUTINE EXTERNAL BUILDING WASH DOWN THAT DOES NOT USE DETERGENTS PAVEMENT WASH WATERS WHERE SPILLS OR LEAKS OF TOXIC OR HAZARDOUS MATERIALS 3.7. HAVE NOT OCCURRED (UNLESS ALL SPILLED MATERIAL HAS BEEN REMOVED) AND WHERE
- DETERGENTS ARE NOT USED 3.8. UNCONTAMINATED AIR CONDITIONING OR COMPRESSOR CONDENSATE
- 3.9. UNCONTAMINATED GROUND WATER OR SPRING WATER 3.10. FOUNDATION OR FOOTING DRAINS WHERE FLOWS ARE NOT CONTAMINATED WITH PROCESS
- MATERIALS SUCH AS SOLVENTS 3.11. UNCONTAMINATED EXCAVATION DEWATERING
- 3.12. LANDSCAPE IRRIGATION
- 3.13. DECHLORINATED SWIMMING POOL DISCHARGES.

4.1. SELECT A DESIGNATED WASTE COLLECTION AREA

4.2. PROVIDE LIDS FOR WASTE CONTAINERS

5.1. STORE IN A DRY COVERED AREA

4. CONSTRUCTION WASTES: DEMOLITION RUBBLE, PACKAGING MATERIALS, SCRAP BUILDING SUPPLIES, ETC.

5.3. STRICTLY FOLLOW RECOMMENDED APPLICATION RATES

AVAILABLE FOR CONTACT WITH STORM WATER.

4.3. WHEN POSSIBLE LOCATE CONTAINERS IN COVERED AREA 4.4. MAINTAIN CONSISTENT REMOVAL SCHEDULE FOR WASTE

5.2. INSTALL CURBS OR DIKES AROUND STORAGE AREA TO PROTECT AGAINST SPILLS

6. FERTILIZERS AND DETERGENTS: REDUCE THE AMOUNT OF FERTILIZERS AND DETERGENTS

6.1. LIMIT APPLICATION OF FERTILIZERS TO THE MINIMUM NEEDED

6.2. APPLY MORE FREQUENTLY BUT AT LOWER APPLICATION RATES

6.3. LIMIT USE OF DETERGENTS ON-SITE 6.4. DO NOT DISCHARGE WASH WATER INTO STORM WATER SYSTEM

6.5. MAINTAIN STRUCTURAL AND VEGETATIVE BMP'S 6.6. APPLY ACCORDING TO SOIL TEST RECOMMENDATIONS PRIOR TO SEEDING.

IX. GRASSING NOTES

1. SOD

ALL SOD SHALL BE NURSERY GROWN AS CLASSIFIED IN THE ASPS GSS. MACHINE CUT SOD AT A UNIFORM THICKENS OF 3/4" WITHIN A TOLERANCE OF 1/4", EXCLUDING TOP GROWTH AND THATCH EACH INDIVIDUAL SOD PIECE SHALL BE STRONG ENOUGH TO SUPPORT ITS OWN WEIGHT WHEN LIFTED BY THE ENDS. BROKEN PODS, IRREGULARLY SHAPED PIECES, AND TORN OR UNEVEN ENDS WILL BE REJECTED. WOOD PEGS AND / OR WIRE STAPLES SHALL REPLACE SOD WITH AN EQUAL SOD COMPOSITION AS THAT WHICH IS EXISTING. IF NO SOD TYPE EXIST. THEN THE FOLLOWING SC COMPOSITION SHALL BE USED.

SODDING SCHEDULE:

LAY SOD FROM MAY 1 TO SEPTEMBER 15 FOR SPRING PLANTING AND FROM SEPTEMBER 15 TO NOVEMBER 1 FOR FALL PLANTING.

3 SEED

ALL SEED SHALL CONFORM TO ALL STATE LAWS AND TO ALL REQUIREMENTS AND REGULATIONS OF THE SOUTH CAROLINA DEPARTMENT OF AGRICULTURE. THE SEVERAL VARIETIES OF SEED SHALL BE INDIVIDUALLY PACKAGED OR BAGGED, AND TAGGED TO SHOW NAME OF SEED, NET WEIGHT, ORIGIN, GERMINATION, LOT NUMBER, AND OTHER INFORMATION REQUIRED BY THE DEPARTMENT OF AGRICULTURE.

3.1. PENNISETUM GLAUCIUM (BROWNTOP MILLET): TESTING 98 PERCENT PURITY AND 85 PERCENT GERMINATION

3.2. BERMUDA COMMON: TESTING 98 PERCENT PURITY AND 85 PERCENT GERMINATION. 3.3. DOMESTIC ITALIAN RYE: TESTING 98 PERCENT PURITY AND 90 PERCENT GERMINATION.

4. MISCELLANEOUS:

- 4.1. PERMANENT SEEDING SHALL COVER ALL DISTURBED AREA NOT TO BE COVERED BY
- LANDSCAPE PLANTING BEDS. STRUCTURE. OR PAVEMENT. 4.2. SEED ALL DISTURBED AREAS WITHIN SEVEN DAYS OF FINAL GRADING AND TEMPORARY
- SEED/MULCH ALL AREAS THAT WILL BE LEFT INACTIVE FOR MORE THAN FOURTEEN (14) DAYS. 4.3. ALL PERMANENT GRASS PLANTINGS SHALL BE MULCHED
- 4.4. CENTIPEDE SOD CAN BE USED AS PERMANENT COVER ANYTIME EXCEPT JUNE THRU OCTOBER 4.5. IF GRASSING OCCURS DURING A MONTH REQUIRING TEMPORARY COVER, THE CONTRACTOR SHALL APPLY PERMANENT COVER (IN ADDITION TO THE TEMPORARY COVER) AT THE APPROPRIATE TIME AT NO NO ADDITIONAL COST. THE CONTRACTOR MUST ACHIEVE A STRAND OF PERMANENT GRASS WITH AT LEAST 95% COVER. BARE SPOTS CAN NOT BE MORE THAN 1 INCH SQUARE IN ANY 10 SF.

X. PERMANENT STABILIZATION

NEWLY SEEDED OR SODDED AREAS MUST BE PROTECTED FROM VEHICLE TRAFFIC EXCESSIVE PEDESTRIAN TRAFFIC. AND CONCENTRATED RUNOFF UNTIL THE VEGETATION IS WELL ESTABLISHED. NECESSARY, AREAS MUST BE RE-WORKED AND RE-STABILIZED IF GERMINATION IS SPARSE, PLANT COVERAGE IS SPOTTY ,OR TOPSOIL EROSION IS EVIDENT. ONE OR MORE OF THE FOLLOWING MAY APPLY TO THE SITE.

4.1. SEEDED AREAS

FOR SEEDED AREAS, PERMANENT STABILIZATION MEANS A 90% COVER OF THE DISTURBED AREA WITH MATURE, HEALTHY PLANTS WITH NO EVIDENCE OF WASHING OR RILLING OF THE TOPSOIL.

4.2. SODDED AREAS

FOR SODDED AREAS, PERMANENT STABILIZATION MEANS THE COMPLETE BINDING OF THE SOD ROOTS INTO THE APPROVED MULCH MATERIAL

4.3. PERMANENT MULCH

FOR MULCHED AREAS, PERMANENT MULCHING MEANS TOTAL COVERAGE OF THE EXPOSED AREA WITH AN APPROVED MULCH MATERIAL.

4.4. RIPRAP

FOR AREAS STABILIZED WITH RIPRAP. PERMANENT STABILIZATION MEANS THAT SLOPES STABILIZED WITH RIPRAP HAVE AN APPROPRIATE BACKING OF AN APPROVED GEOTEXTILE TO PREVENT SOIL MOVEMENT FROM BEHIND THE RIPRAP.

4.5. DITCHES, CHANNELS, AND SWALES

FOR OPEN CHANNELS, PERMANENT STABILIZATION MEANS THE CHANNEL IS STABILIZED WITH MATURE VEGETATION AT LEAST THREE INCHES IN HEIGHT. WITH WELL-GRADED RIPRAP LINING OR WITH ANOTHER NON-EROSIVE LINING CAPABLE OF WITHSTANDING THE ANTICIPATED FLOW VELOCITIES AND FLOW DEPTHS WITHOUT RELIANCE ON CHECK DAMS TO SLOW FLOW. THERE MUST BE NO EVIDENCE OF SLUMPING OF THE LINING, UNDERCUTTING OF THE BANKS, OR DOWN CUTTING OF THE CHANNEL.

XI. FERTILIZER REQUIREMENTS

1. TEMPORARY SEEDING FERTILIZER


APPLY A MINIMUM OF 500 LBS PER ACRE OF A COMPLETE 10-10-10 FERTILIZER (11.5 POUNDS PER 1000 SQUARE FEET) OR EQUIVALENT DURING TEMPORARY SEEDING OF GRASSES UNLESS A SOIL TEST INDICATES A DIFFERENT REQUIREMENT. INCORPORATE FERTILIZER AND LIME (IF USED) INTO THE TOP 4-6 INCHES OF THE SOIL BY DISKING OR OTHER MEANS WHERE CONDITIONS ALLOW. LIME IS NOT REQUIRED FOR TEMPORARY SEEDING UNLESS A SOIL TEST SHOWS THAT THE SOIL PH IS BELOW 5.0. IT IS DESIRABLE TO APPLY LIME DURING THE TEMPORARY SEEDING OPERATION TO BENEFIT THE LONG-TERM PERMANENT SEEDING. APPLY A MINIMUM OF 1.5 TONS OF LIME / ACRE (70LBS. / 1000 SQ. FT.).

2. PERMANENT SEEDING FERTILIZER

APPLY A MINIMUM OF 1000 LBS PER ACRE OF A COMPLETE 10-10-10 FERTILIZER (23 POUNDS PER 1000 SQUARE FEET) OR EQUIVALENT DURING PERMANENT SEEDING OF GRADES UNLESS A SOIL TEST INDICATES A DIFFERENT REQUIREMENT. INCORPORATE FERTILIZER AND LIME (IF USED) INTO THE TOP 4-6 INCHES OF THE SOIL BY DISKING OR OTHER MEANS WHERE CONDITIONS ALLOW. DO NOT MIX THE LIME AND THE FERTILIZER PRIOR TO THE FIELD APPLICATION. UNLESS A SPECIFIC SOIL TEST INDICATES OTHERWISE, APPLY 1 & 1/2 TONS OF GROUND COARSE TEXTURED AGRICULTURAL LIMESTONE PER ACRE (70 LBS. / 1000 SQ.FT.).

XII. SWPP PREPARER CERTIFICATION

I HAVE PLACED MY SIGNATURE AND SEAL ON THE DESIGN DOCUMENTS SUBMITTED SIGNIFYING THAT I ACCEPT RESPONSIBILITY FOR THE DESIGN OF THE SYSTEM. FURTHER, I CERTIFY TO THE BEST OF MY KNOWLEDGE AND BELIEF THAT THE DESIGN IS CONSISTENT WITH THE REQUIREMENTS OF TITLE 48. CHAPTER 14 OF THE CODE OF LAWS OF SC, 1976 AS AMENDED, PURSUANT TO REGULATION 72-300 ET SEQ. 5. PESTICIDES: REDUCE THE AMOUNT OF PESTICIDES AVAILABLE FOR CONTACT WITH STORM WATER. (IF APPLICABLE), AND IN ACCORDANCE WITH THE TERMS AND CONDITIONS OF SCR100000.





FLORENCE COUNTY ECONOMIC DEVELOPMENT PARTNERSHIP FLORENCE COUNTY, SC	FLORENCE COUNTY INDUSTRIAL PARK EAST	EROSION CONTROL NOTES
	1	

.0001\engineering\Drawings\construction plans\28601.0001 - EC - NT - DT.dwg - Apr 2.

				TEN	/IPORARY	SEEDING	- COASTA	۸L	
SPECIES	LBS/AC	JAN	FEB	MAR	APR	MAY	JUN	JUL	AUG
		•			SANDY, D	ROUGHT	SITES		
BROWNTOP MILLET	40								
RYE, GRAIN	56								
RYEGRASS	50								
	·		•	WELL	DRAINED,	CLAYEY/L	OAMEY S	ITES	
BROWNTOP MILLET	40								
JAPANESE MILLET	40								
RYE, GRAIN	56								
OATS	75								
RYEGRASS	50								

SPECIES	LBS/AC	JAN	FEB	MAR	APR	MAY	JUN	JUL	AUG	SEP	OCT	NOV	DEC
	1				SANDY, [Y SITES			1			I
BROWNTOP MILLET	10												
BAHIAGRASS	40												
BROWNTOP MILLET	10												
BAHIAGRASS	30												
SERICEA LESPEDEZA	40												
BROWNTOP MILLET	10												
ATLANTIC COASTAL	15												
PANICGRASS	PLS												
BROWNTOP MILLET	10												
SWITCHGRASS	8												
(ALAMO)	PLS												
LITTLE BLUESTEM	4												
SERICEA LESPEDEZA	20												
BROWNTOP MILLET	10												
WEEPING LOVEGRASS	8												
	1		I	WELL	DRAINED,	, CLAYEY/L	OAMEY S	ITES			I	I	I
BROWNTOP MILLET	10												
BAHIAGRASS	40												
RYE, GRAIN	10												
BAHIAGRASS	40												
CLOVER, CRIMSON (ANNUAL)	5												
BROWNTOP MILLET	10												
BAHIAGRASS	30												
SERICEA LESPEDEZA	40												
BROWNTOP MILLET	10												
BERMUDA, COMMON	10												
SERICEA LESPEDEZA	40												
BROWNTOP MILLET	10												
BERMUDA, COMMON	12												
KOBE LESPEDEZA (ANNUAL)	10												
BROWNTOP MILLET	10	1											
BAHIAGRASS	20												
BERMUDA, COMMON	6												
SERICEA LESPEDEZA	40												
BROWNTOP MILLET	10	1											
SWITCHGRASS	8			_									
LITTLE BLUESTEM	PLS												
INDIANGRASS	3												


STORMWATER POLLUTION PREVENTION PLAN

SEP OCT NOV DEC

EROSION CON	TROL LEGEND
DESCRIPTION	PLAN SYMBOL
SILT FENCE	
LIMITS OF DISTURBANCE	LOD
DIVERSION BERM	⇒ DB ⇒
TEMPORARY SEEDING	TS
PERMANENT SEEDING	PS
RIPRAP	
STORM DRAIN INLET PROTECTION - TYPE A FILTER FABRIC	A
OUTLET PROTECTION - RIP RAP	
SEDIMENT TRAP	
SEDIMENT TUBE	
ROCK CHECK DAM	
STABILIZED CONSTRUCTION ENTRANCE	
CONCRETE WASHOUT	


LIST OF ACRONYMS FOR SEDIMENT AND EROSION CONTROL


AASHTO	AMERICAN ASSOCIATION OF STATE HIGHWAY AND TRANSPORTATION OFFICIALS
AMD	ACRYLAMIDE POLYMER
BFM	BONDED FIBER MATRIX
BMP(S)	BEST MANAGEMENT PRACTICE(S)
CFS	CUBIC FEET PER SECOND
CMP	CORRUGATED METAL PIPE
DHEC	DEPARTMENT OF HEATH AND ENVIRONMENTAL CONTROL
ECB	EROSION CONTROL BLANKET
EPA	UNITED STATES ENVIRONMENTAL PROTECTION AGENCY
EPSC	EROSION PREVENTION AND SEDIMENTATION CONTROL
FDA	UNITED STATES FOOD AND DRUG ADMINISTRATION
FGM	FLEXIBLE GROWTH MATRIX
HDPE	HIGH DENSITY POLYETHYLENE
MS4	MUNICIPAL SEPARATE STORM SEWER SYSTEM
MSDS	MATERIAL SAFETY DATA SHEETS
NPDES	NATIONAL POLLUTANT DISCHARGE ELIMINATION SYSTEM
PAM	POLYACRYLAMIDE OR POLYMER
RCP	REINFORCED CONCRETE PIPE
SCS	SOIL CONSERVATION SERVICE
SWPPP	STORMWATER POLLUTION PREVENTION PROGRAM
TRM	TURF REINFORCEMENT MAT
VFS	VEGETATED FILTER STRIP




	CONSTRUCTION SEQUENCE
	CONSTRUCTION ACTIVITY
	INITIAL PHASE
1	RECEIVE NPDES COVERAGE FROM SCDHEC.
2	PRE-CONSTRUCTION MEETING WITH SCDHEC.
3	NOTIFY DHEC EQC REGIONAL OFFICE PRIOR TO BEGINNING LAND-DISTURBING ACTIVITIES.
4	INSTALLATION OF CONSTRUCTION ENTRANCES.
5	CLEARING & GRUBBING ONLY AS NECESSARY FOR INSTALLATION OF PERIMETER CONTROLS.
6	INSTALLATION OF PERIMETER CONTROLS (E.G., SILT FENCE).
7	CLEARING & GRUBBING ONLY IN AREAS OF POND.
8	INSTALLATION OF POND & INSTALLATION OF DIVERSIONS TO THAT STRUCTURE (AREAS DRAINING TO THIS STRUCTURE CANNOT BE DISTURBED UNTIL THE DIVERSIONS TO THE STRUCTURES ARE COMPLETELY INSTALLED).
	CONSTRUCTION PHASE
9	CLEARING & GRUBBING OF SITE OR DEMOLITION (SEDIMENT & EROSION CONTROL MEASURES FOR THESE AREAS MUST ALREADY BE INSTALLED).
10	ROUGH GRADING.
11	INSTALLATION OF STORM DRAIN SYSTEM & PLACEMENT OF INLET PROTECTION AS EACH INLET IS INSTALLED.
12	BUILDING PAD CONSTRUCTION.
13	FINE GRADING, PAVING, ETC.
_	STABILIZATION PHASE
14	PERMANENT/FINAL STABILIZATION.
15	CLEAN-OUT OF DETENTION BASIN THAT WAS USED AS A SEDIMENT CONTROL STRUCTURE & RE-GRADING OF DETENTION POND BOTTOM; IF NECESSARY, MODIFICATION OF SEDIMENT BASIN RISER TO CONVERT TO DETENTION BASIN OUTLET STRUCTURE.
16	REMOVAL OF TEMPORARY SEDIMENT & EROSION CONTROL MEASURES AFTER ENTIRE AREA DRAINING TO THE STRUCTURE IS FINALLY STABILIZED.
17	PERFORM AS-BUILT SURVEY OF DETENTION STRUCTURE & SUBMIT TO SCDHEC FOR ACCEPTANCE.
18	SUBMIT NOTICE OF TERMINATION (NOT) TO DHEC AS APPROPRAITE.


	CONSTRUCT INITIAL 1 RECEIVE NPDES COVERA 2 PRE-CONSTRUCTION ME 3 NOTIFY DHEC EQC REGIO 3 BEGINNING LAND-DISTUR 4 INSTALLATION OF CONST 5 CLEARING & GRUBBING OF INSTALLATION OF PERIME 6 FENCE). 7 CLEARING & GRUBBING OF INSTALLATION OF POND &	AGE FROM SCDHEC. ETING WITH SCDHEC. DNAL OFFICE PRIOR TO BING ACTIVITIES. RUCTION ENTRANCES. DNLY AS NECESSARY FOR ETER CONTROLS. ETER CONTROLS (E.G., SILT DNLY IN AREAS OF POND. & INSTALLATION OF	95-	
	THE DIVERSIONS TO THE COMPLETELY INSTALLED).		LOD
DESCRIPT	<u>С</u> ГІО <u>М</u>	O PLAN SYMBOL		
SILT FENCE				
LIMITS OF DIS	STURBANCE	LOD		400
RIPRAP		<u>E</u>		
ROCK CHECK	DAM			95
STABILIZED C	ONSTRUCTION ENTRANCE			
 			FLORENCE COUNTY 306-01-042	
<u>`95</u> 0 47	I.E.: 92.39			
		24" CPP <u>=</u>		
		12"FM _LOD12"FM	LOD LOD LOD LOD US HIGHWAY 76 & 301 (60 MPH SPEED LIMIT, 157.5' R/W)	LOD TYPE A INLET FILTER
				(SEE SHEET EC4.2) STORM INLET (TO BE REMOVED)
		91.12		<u></u>
		FLOYD FAMILY properties llc. 307-01-011		EVANS, RONN 307-01-





	 ROUGH GRADING. INSTALLATION OF STORM PLACEMENT OF INLET PRO IS INSTALLED. BUILDING PAD CONSTRUC FINE GRADING, PAVING, E 	DTECTION AS EACH INLET	LIMI	TS OF DISTURBAN (TYP.)(±18.5 A
	EROSION CON	FROL LEGEND		
	SILT FENCE			LOD
	LIMITS OF DISTURBANCE	LOD		
	DIVERSION BERM	⇒DB⇒		
	TEMPORARY SEEDING	TS		
l	RIPRAP			
	STORM DRAIN INLET PROTECTION - TYPE A FILTER FABRIC			
	OUTLET PROTECTION - RIP RAP		95	
	SEDIMENT TUBE			
; 	ROCK CHECK DAM		NCE COUNTY	
	STABILIZED CONSTRUCTION ENTRANCE		\$ 5	
	CONCRETE WASHOUT		INSTALL IZ	2 SY OF RIP RAP - EE SHEET EC4.I)
				LOP
			INSTALL 20 SY OF RIP RAP (SEE SHEET EC4.I)	Т
		CPP		STABILIZED ENTRANCE (SE
A		LOD 12"FM LOD 12"FM LOD 12"FM - LOD LOD LOD		0D <u>12"1-M</u> 8"W -0D
			91	HEET EC4.2)
<u> </u>	 I.E.: 91.12	<u> </u>	<u></u> '(10 	BE REMOVED) === OUT: 92.98
		FLOYD FAMILY		EVANS, ROM








	CONSTRUCTION SEQUENCE
	CONSTRUCTION ACTIVITY
	CONSTRUCTION PHASE
9	CLEARING & GRUBBING OF SITE OR DEMOLITION (SEDIMENT & EROSION CONTROL MEASURES FOR THESE AREAS MUST ALREADY BE INSTALLED).
10	ROUGH GRADING.
11	INSTALLATION OF STORM DRAIN SYSTEM & PLACEMENT OF INLET PROTECTION AS EACH INLET IS INSTALLED.
12	BUILDING PAD CONSTRUCTION.
13	FINE GRADING, PAVING, ETC.

EROSION CON	TROL LEGEND
DESCRIPTION	PLAN SYMBOL
SILT FENCE	
LIMITS OF DISTURBANCE	LOD
TEMPORARY SEEDING	TS
RIPRAP	
ROCK CHECK DAM	
ROCK CHECK DAM	


		ON SEQUENCE		
		TION PHASE		
	14 PERMANENT/FINAL STAE CLEAN-OUT OF DETENTI	ILIZATION. ON BASIN THAT WAS USED		
	AS A SEDIMENT CONTRO RE-GRADING OF DETENT	TION POND BOTTOM; IF		
		TION OF SEDIMENT BASIN DETENTION BASIN OUTLET		
	CONTROL MEASURES AF	RY SEDIMENT & EROSION TER ENTIRE AREA DRAINING		
	TO THE STRUCTURE IS F			
	PERFORM AS-BUILT SUR 17 STRUCTURE & SUBMIT T ACCEPTANCE.			
		MINATION (NOT) TO DHEC AS		
		TROL LEGEND		
			- 95-	
	DESCRIPTION	PLAN SYMBOL		
	SILT FENCE			
	LIMITS OF DISTURBANCE	LOD		
	DIVERSION BERM			
	PERMANENT SEEDING	PS		<00
		682		\backslash
	RIPRAP			
I				
	OUTLET PROTECTION - RIP RAP			
1			95	
1	SEDIMENT TUBE			
	BOCK CHECK DAM	OR B		
1	ROCK CHECK DAM	OR OR		
1 				
	STABILIZED CONSTRUCTION ENTRANCE		NCE COUNTY	
	CONCRETE WASHOUT		ý l	
			INSTALL 12	2 SY OF RIP RAP —
				EE SHEET EC4.I)
		г— I.E.: 92.79	INSTALL 20 SY OF RIP RAP —	10 ⁰
	I.E.: 92.39		(SEE SHEET EC4.I)	
				PS PS E
	LOD LOD	<u>1297 M</u> <u>LOD</u> <u>38</u> <u>COD</u>		
	<u> LOD LOD LOD</u>			
			JS HIGHWAY 76 & 301	
				DRM INLET
·	I.E.: 91.12			BE REMOVED) ==== OUT: 92.98
				I.E.:
		FLOYD FAMILY		EVANS, RONNIE
		PROPERTIES LLC. 307-01-011		307-01-04
			1	









STORMWATER POLLUTION PREVENTION PLAN








UNDER THIS SPECIFICATION.
BARE SOIL, MULCHED AREAS OR EROSION CONTROL BLANKETS. OF GEOTEXTILES, CURLED EXCELSIOR WOOD, NATURAL COCONUT FIBER OR HARDWOOD MULCH ENCLOSED BY A FLEXIBLE NETTING MATER V FIBER, STRAW BALES, PINE NEEDLES AND LEAF MULCH ARE NOT ALLOWED.
DIAMETER SHOULD BE 18 INCHES




WET DETENTIC	N POND							
Installation:								
larger wet dete	ntion pond area	by barriers or	baffles that	t may be con	structed of eart	aced upstream of h, stones, riprap, ove the elevation	gabions, or	geotextiles.
The permanent	pool shall be fo	our (4) to six ((6) feet in a	depth.				
Acceptable tras	h guards include	2:						
Hoods the	t extend at leas	st 6-inches belo	ow the perm	nanent pool w	ater surface ele	evation.		
Reverse f	ow pipes where	the outlet struc	cture inlet is	s located at I	ast 6-inches b	pelow the perman	ent pool wat	er surface elev
Trash box	es made of stur	dy wire mesh.						
Inspection and	Maintenance:							
The side slope	s of the pond sł	nall be mowed	monthly.					
Since decompo the decaying v	sing vegetation c egetation can ex	captured in the port pollutants	wetpond ca out of the	an release pol pond and als	utants, especial can cause nu	ly nutrients, it m isance conditions	ay be necess to occur.	sary to harvest
Debris shall be	cleared from al	I inlet and outl	let structures	s monthly.				
All eroded or i	indercut areas s	hall be repaired	d as needed.					
A sediment mo	rker shall be plo	aced in the fore	ebay to dete	ermine when	ediment removo	al is required.		
	nulations in the volume has bee					be removed whe	en the	
								epartment on mental Cor
						WET	DETENT	TION POND
						STANDARD DRAWING N	^{10.} WQ-02	Page 2 of










100	TIE INTO EXISTING MANHOLE	2.62 1: 78.03 (W)					
95	TIE II MANI	FR: 92 INV. IN					
90		· · · · ·					
85							
80							
75					400 LF 12" F	PVC - SDR 26	0 (
	92.6	92.62	81.19 0.29	92.03 92.6	92.62 92.5	92.54 92.3	92.30
L	0+	00	 +(00	2+	00	












llO	
105	
100	II# HW
95	
90	
85	
80	
75	
	95.7
<u>.</u>	0+










SEWER – RUN 3 STATIONS: -0+25 - 1+50 SCALE: HORZ.: 1" = 50' VERT.: 1" = 5'


FOR CON





			2021/06/07	2021/06/07	NJH 2021/06/07	DATE
			HUN	HUN	ΗΓΝ	BҮ
			REVISED PER CITY OF FLORENCE	REVISED PER FLORENCE COUNTY	REVISED PER SCDOT	REVISIONS
			ю	2	_	NO.



















					96 96
	98·	<u>SCDOT TYPE II2</u>		92 93 92 93 TP 97.47 TP 97.76	97 96 Full De 2" Mill 0
- 98	98	FR: 96.52 INV. OUT: 93.76 (E) -97 -12"FM 96 96 96 96 96 96 96 96		TP.97.30	
	US HIGHWAY 76 & 301 (60 MPH SPEED LIMIT, 157.5' R/W)		2" MILL & RESURFACE	INV. IN INV. IN INV. IN 95-94-93-92-91	<u>JB#</u> I FR: 97.50 I: 92.94 (E) : 92.94 (₩)
	96959493				I.E.: 89.53-
	EDGELINE OF PAN 2. ALL CONSTRUCTI	ON WITHIN SCDOT RIGHT-OF-WA SPECIFICATIONS. CONTRACTOR	PAVEMENT ELEVATIONS ALC	E WITH SCDOT	
95	94				
	SS	> >	• · · · · · · · · · · · · · · · · · · ·	\$\$	····
	93 93 93 93 93 93 93 93 93 93 93 93 93 9	94 94 011P 0HP 0HP			START 4 N: 863,4 E: 2,419,5
TP-96.93	FULL DEPTH ASPHALT REMOV			TP 96.84 97 TP 96.84 TP 97.10 US HIGHWAY 76 & 301 (60 MPH SPEED LIMIT, 157.5' R/W)	
.95 — — — — — — — — — — — — —	12"FM 12"FM 12	<u>8"w</u>	96		
	97·				





CE	COURSE	-
ΥP	ΕB	

TACK COAT BETWEEN LIFTS SCDOT SPEC. TYPE B

	— PR	IME	COAT	
		E E E E E E E		

10" GRADED AGGREGATE BASE COURSE PER SCDOT

-24" compacted sub-base at 95% maximum DRY DENSITY (AS PER SPECIFICATIONS) BY STANDARD PROCTOR TEST

ASPHALT PAVEMENT SECTION FLEXIBLE HEAVY DUTY


(REFER TO GEOTECHNICAL REPORT)


O SCALE
TYPE B
COAT BETWEEN LIFTS 3
4" HMA INTERMEDIATE COURSE 3
PRIME COAT
3
GRADED AGGREGATE BASE COURSE
TED SUB-BASE AT 95% MAXIMUM (AS PER SPECIFICATIONS) BY ROCTOR TEST
ZEMENT SECTION
SCDOT R/W)
O SCALE ADED AGGREGATE BASE COURSE PER SCDOT
ION-WOVEN GEOTEXTILE FABRIC
<u> </u>


GRAVEL ROAD SECTION


NOT TO SCALE


			1
THOMAS	No. COO285		INCITOL INTOINCO
TH CARO		Thing S. OAN W	
	2021/06/07 2021/06/07	2021/06/07 DATE	
	02 HUN		-
	REVISED PER CITY OF FLORENCE REVISED PER FLORENCE COUNTY	REVISED PER SCDOT REVISIONS	
	n u	– ÖN	
	1501 Main Street • Suite 760	www.thomasandhutton.com	
FLORENCE COUNTY ECONOMIC DEVELOPMENT PARTNERSHIP FLORENCE COUNTY, SC	FLORENCE COUNTY INDUSTRIAL PARK EAST	TYPICAL ROADWAY SECTIONS	
	1		
C3	3.3	}	
			1




















ENTRANCE ROAD CROSS SECTIONS

BID SET - NOT FOR CONSTRUCTION



































DATE CHK



 \Box

VISTA PRO

COUNTY, AND CITY CODES AND SHALL MEET OR EXCEED THE NATIONAL ELECTRICAL CODE. CONTRACTOR IS RESPONSIBLE FOR ACQUIRING ALL PERMITS AND APPROVALS REQUIRED. SYSTEM INSTALLATION SHALL BE GUARANTEED FOR ONE YEAR, PARTS AND LABOR, DUE TO FAILURE BASED ON FAULTY WORKMANSHIP

CONSISTENCY OF BULB OUTPUT FROM FIXTURE-TO-FIXTURE REGARDLESS OF

OTHER ITEMS FINAL LOCATIONS SHALL BE PLACED IN SUCH A LOCATION TO

PLACEMENT OF FIXTURES. FINAL AIMING AND ADJUSTMENT SHALL BE MADE AT NIGHT WITH OWNER'S REPRESENTATIVE PRESENT TO GIVE FINAL APPROVAL.

3

FOR REVIEW AND ACCEPTANCE.

INSTRUCTIONS AND RECOMMENDATIONS.

MINIMIZE VISIBILITY AS MUCH AS POSSIBLE.

ELECTRICAL ENGINEER DESIGN.

FINAL CONNECTION LOCATION.

FOR REVIEW AND ACCEPTANCE.

PRIOR TO INSTALLATION.

LOCATION.

OR EQUIPMENT FAILURE.

TREES	S					
QNTY	ABBRV	2NTY ABBRV SCIENTIFIC NAME	COMMON NAME	PLANTING SIZE	SPACING	MISCELLANEOUS / REMARKS
0	LIS	Lagerstroemia indica 'Sarah's Favorite' Sarah's Favorite Crape	Sarah's Favorite Crape Myrtle	Myrtle B & B OR CONT. ; 2.5" CAL. 10'-12' HT. 4' SPD. AS SHOWN Specimen, Standard	AS SHOWN	Specimen, Standard
				B B B DR CONT. ; 2.5" CAL. 12'-24' HT. 3'		
4	QN	Quercus nuttallii	Nuttall Oak	SPD.	AS SHOWN Specimen	Specimen
2	QP	Quercus phellos 'RT3' PPI6,444	Upperton® Willow Oak	B B B D C CONT : 3" CAL. I2'-I4' HT. 4' SPD. AS SHOWN Specimen	AS SHOWN	Specimen
23	gs	Quercus shumardii	Shumard Oak	B B B B OR CONT.; 2.5" CAL. 10-12' HT. 4' SPD. AS SHOWN Specimen	AS SHOWN	Specimen


SHRUBS	JBS					
QNTY	ABBRV	QNTY ABBRV SCIENTIFIC NAME	COMMON NAME	PLANTING SIZE	SPACING	MISCELLANEOUS / REMARKS
59	ILVS	llex vomitoria 'Stokes'	Dwarf Schillings Holly	3 GAL. I8" X I8"	AS SHOWN	AS SHOWN Full to ground and well formed
8	LSS	Ligustrum sinenese 'Sunshine'	Sunshine Ligustrum	3 GAL. I8" X I8"	AS SHOWN	AS SHOWN Full to ground and well formed
65	LOCM I	Loropetalum chinense 'NCIOO2'	Carolina Moonlight Loropetalum	-oropetalum 3 GAL. 24" X 24"	AS SHOWN	AS SHOWN Full to ground and well formed

ORNAME	NTAL G	DRNAMENTAL GRASSES AND GROUNDCOVERS				
QNTY	ABBRV	ABBRV SCIENTIFIC NAME	COMMON NAME	PLANTING SIZE	SPACING	MISCELLANEOUS / REMARKS
103	AGA	Agapanthus 'Blue Globe'	Blue Globe African Lily	3 GAL. IB" X IB"	2'	Full, Well Formed
65,000SF SOD	SOD	Cynodon dactylon 'Tifsport'	Tifsport Bermudagrass			Dense roots
94	JUNB	Juniperus squamata expansa 'Parsonii'	Parson's Juniper	I GAL. 24" X 24"	2.5'	Full and well formed
15	LISB	Liriope muscari 'Super Blue'	Super Blue Liriope	I GAL. I8" X I8"	18"	Full and well formed
31	MUHC	Muhlenbergia capillaris	Pink Muhly Grass	I GAL. IB" X IB"	2'	Full and well formed
67	NEP	Nepta Racemosa 'Walker's Low'	Walker's Low Catmint	3 GAL. 24" X 24"	2.5'	Full, Well Formed

PRODUCT (or Accepted Equals)

SIGN LIGHT-GR-5103-B-LED-FR

	PRELIMINARY					BY DATE	
				1501 Main Street • Suite 760	Columbia SC 20201 • 803 451 4780	www.thomasandhutton.com	
FLORENCE COUNTY ECONOMIC	DEVELOF	FLORENCE COUNTY, SC		FLORENCE COUNTY INDUSTRIAL PARK EAST			
JOB N DATE: DRAWN DESIGI REVIE APPRC SCALE	N: NED: WED: OVED:	J-2: 06/ BCG JLG JLG	'07,				



NOI \mathbf{C} 0 R 4 RUC PRELIMIN \vdash Ο .SNO Ž $\cdot \longrightarrow \cdot \cdot \cdot \cdots \longrightarrow \cdot \cdot \cdot \cdots \longrightarrow \cdot$ THOMAS Z 45.45 0 • • 201 201 z z SP/ AS AS AS AS AS ΗŢ 150 Columt wwv HT. 4' SPD. HT. 4' SPD

 PLANT SCHEDULE

 PLANT SCHEDULE

 Crope Myrtle

 B & B OR CONT.; 2.5" CAL.

 SPD.

 Ook
 B & B OR CONT.; 3." CAL.

 B & B OR CONT.; 2.5" CAL.

 SPD.

 Ook
 B & B OR CONT.; 2.5" CAL.

 B & B OR CONT.; 2.5" CAL.

 2.5" CAI 2.5" CAI FLORENCE COUNTY INDUSTRIAL PARK EAST PLANTING SIZE 3 GAL. IB" X IB" --- ---1 GAL. 24" X 24" 1 GAL. IB" X IB" 1 GAL. 18" X 18" 3 GAL. 24" X 24" PLANTING SIZE 3 GAL. I8" X I8" 3 GAL. I8" X I8" m 3 GAL. 24" X 24" FLORENCE COUNTY ECONOMIC DEVELOPMENT PARTNERSHIP FLORENCE COUNTY, SC SHRUBSONTYABBrVSCIENTIFIC NAMECOMMON NAMEF59ILVSllex vomitoria 'Stokes'Dwarf Schillings Holly359ILVSLigustrum sinenese 'Sunshine'Sunshine Ligustrum365LOCMLoropetalum chinense 'NCIOO2'Carolina Moonlight Loropetalum37ORTYABBRVSCIENTIFIC NAME365AGAAgapanthus 'Blue Globe'Blue Globe African Lily103AGAAgapanthus 'Blue Globe'Blue Globe African Lily65,000SFSODCynodon dactylon 'Tifsport'Tifsport Bermudagrass94JUNBJuniperus squamata expansa 'Parsonii'Parson's Juniper51MUHCMuhlenbergia capillarisPink Muhly Grass67NEPNepta Racemosa 'Walker's Low'Walker's Low Catmint LANDSCAPE PLAN St. Nuttall (Shumar 'RT3' PP Quercus nuttallii Quercus phellos 'I Quercus shumardi
 JOB NO:
 J-28601.0001

 DATE:
 06/07/2021


 DRAWN:
 BCG

 DESIGNED:
 BCG

 REVIEWED:
 JLG

 APPROVED:
 JLG

 SCALE:
 I" = 20'
 TREESONTYABBIOLIS4ON2QP23QS 80 L1.2



LANDSCAPING

PART 1 - GENERAL

1.1 DESCRIPTION

- A. The work covered in this section consists of soil preparation, fine grading, lawns, trees, shrubs and ground cover plantings, their protection and maintenance of planted areas until acceptance.
- 1.2 RELATED WORK
- A. See Civil and Landscape plans and specifications.

1.3 QUALITY ASSURANCE

- A. Qualifications of Workmen: Contractor shall provide at least one person present at all times during execution of work that is thoroughly familiar with the type of materials being installed and proper equipment and methods for their installation and who shall direct all work performed under this section.
- B. Standards: All seed, sod, trees, shrubs, and ground covers shall meet or exceed the specifications of Federal, State, County and / or Municipality laws requiring inspection for disease and insect control.
- 1. Plants and planting methods shall conform to the latest edition of American Standard for Nursery Stock, American Nursery & Landscape Association, 1000 Vermont Avenue, NW, Suite 300, Washington, DC 20005
- 2. Plants shall be true and representative of their genus, species, cultivar, or variety. Nursery stock shipped in accordance with the required specifications shall be deemed to be acceptable within the terms of this section if it is typical in size and habit for the species in the region of the country in which it is grown unless the specifications include additional details.
- 3. Prior to ordering any plant material, representative photos of each species shall be provided for review and <u>acceptance.</u>
- 4. One of each bundle or lot shall be tagged with name and size of the plant in accordance with American Nursery & Landscape Association standards. In all cases, botanical names shall take precedence over common names. Landscape Architect should be consulted in the event questions arise about nomenclature of plants to be used and their availability.

1.4 DELIVERY, STORAGE, AND HANDLING

- A. Deliver grass seed in original containers showing analysis of seed mixture, percentage of pure seed, year of production, net weight, date of packaging and location of packaging. Damaged packages are not acceptable.
- B. Deliver fertilizer in waterproof bags showing weight, chemical analysis, and name of manufacturer.
- C. Deliver sod on pallets.
- D. Handling of plants shall be by lifting the root mass or container and not by lifting plant by trunk or branches. Handling of plants in an improper fashion shall be cause for rejection of plant materials. Care must be taken during all phases of the location and planting procedures not to damage root system, trunk or branches. All plant materials shall be planted as soon after arrival at the site as possible. Contractor is responsible for keeping plants safe from injury by the construction activity and watered to prevent drying out before planting. Balled and burlapped plants shall be "Healed-in" and protected with burlap or other accepted material if they cannot be planted upon delivery. Plants with broken major branches, badly bruised or damaged bark are not acceptable and will be rejected.

1.5 PLANTING DATES

- A. The planting season for trees, shrubs and groundcovers is between October 1st and June 1st of the following year. Do not plant if temperature is below freezing or above 90 degrees. Planting at any other time other than the planting season is the Contractor's option and full responsibility and without additional compensation. Planting may, at the option of the Contractor, be postponed into the following planting season but without additional compensation provided the Owner and local governing jurisdiction have approved.
- C. Planting dates for sod, sprigging or seeding shall be per the grassing specification.

1.6 MEASUREMENT AND PAYMENT

- A. Measurement The items listed in the proposal shall be considered as sufficient to complete the work in accordance with the plans and specifications. Any portion of the work not listed in bid form, but required to complete the work, shall be deemed to be a part of the item with which it is associated and shall be included in the cost of the unit shown on the bid form.
- B. Payment Payment for the unit shown on the bid form shall be considered to cover the cost of all labor, material, equipment, and performing all operations necessary to complete the work in place. No payment will be made for any material wasted, used for the convenience of the Contractor, unused or rejected.
- 1. Trees, Shrubs, and Groundcovers Will be paid for at the contract unit price for planted/installed and accepted trees, shrubs, and groundcovers.
- 2. Payment for grassing will be made per the grassing specification.
- 3. Clearing Will be paid for at the lump sum price for clearing.

PART 2 - PRODUCTS

2.1 MATERIALS

A. Contractor shall, at time of delivery, furnish Owner and / or Landscape Architect with invoices of all materials received; in order the quality and source of materials may be reviewed.

2.2 TOPSOIL

- A. TOPSOIL SHALL BE FERTILE, FRIABLE SOIL CONTAINING LESS THAN 5% TOTAL VOLUME OF THE COMBINATION OF SUBSOIL, REFUSE, ROOTS LARGER THAN 1 INCH DIAMETER, HEAVY, STICKY OR STIFF CLAY, STONES LARGER THAN 2 INCHES IN DIAMETER, NOXIOUS SEEDS, STICKS, BRUSH, LITTER, OR ANY SUBSTANCES DELETERIOUS TO PLANT GROWTH. THE PERCENT (%) OF THE ABOVE OBJECTS SHALL BE CONTROLLED BY SOURCE SELECTION NOT BY SCREENING THE SOIL. TOPSOIL SHALL BE SUITABLE FOR THE GERMINATION OF SEEDS AND THE SUPPORT OF VEGETATIVE GROWTH. IMPORTED TOPSOIL SHALL NOT CONTAIN WEED SEEDS IN QUANTITIES THAT CAUSE NOTICEABLE WEED INFESTATIONS IN THE FINAL PLANTING BEDS. IMPORTED TOPSOIL SHALL MEET THE FOLLOWING PHYSICAL AND CHEMICAL CRITERIA:
- 1. SOIL TEXTURE: USDA LOAM, SANDY CLAY LOAM OR SANDY LOAM WITH CLAY CONTENT BETWEEN 15 AND 25%. AND A COMBINED CLAY/SILT CONTENT OF NO MORE THAN 55%.
- 2. PH VALUE SHALL BE BETWEEN 5.5 AND 7.0.
- 3. PERCENT ORGANIC MATTER (OM): 2.0-5.0%, BY DRY WEIGHT.
- 4. SOLUBLE SALT LEVEL: LESS THAN 2 MMHO/CM.
- 5. SOIL CHEMISTRY SUITABLE FOR GROWING THE PLANTS SPECIFIED.
- B. IMPORTED TOPSOIL SHALL BE A HARVESTED SOIL FROM FIELDS OR DEVELOPMENT SITES. THE ORGANIC CONTENT AND PARTICLE SIZE DISTRIBUTION SHALL BE THE RESULT OF NATURAL SOIL FORMATION. MANUFACTURED SOILS WHERE COARSE SAND, COMPOSTED ORGANIC MATERIAL OR CHEMICAL ADDITIVES HAS BEEN ADDED TO THE SOIL TO MEET THE REQUIREMENTS OF THIS SPECIFICATION SECTION SHALL NOT BE ACCEPTABLE. RETAINED SOIL PEDS SHALL BE THE SAME COLOR ON THE INSIDE AS IS VISIBLE ON THE OUTSIDE.
- C. IMPORTED TOPSOIL FOR PLANTING SOIL SHALL NOT HAVE BEEN SCREENED AND SHALL RETAIN SOIL PEDS OR CLODS LARGER THAN 2 INCHES IN DIAMETER THROUGHOUT THE STOCKPILE AFTER HARVESTING.
- D. STOCKPILED EXISTING TOPSOIL AT THE SITE MEETING THE ABOVE CRITERIA MAY BE ACCEPTABLE.
- PROVIDE A ONE GALLON SAMPLE FROM EACH IMPORTED TOPSOIL SOURCE(S) WITH REQUIRED SOIL TESTING RESULTS OF ALL EXISTING TOPSOIL TO BE USED. THE SAMPLE SHALL BE A MIXTURE OF THE RANDOM SAMPLES TAKEN AROUND THE SOURCE STOCKPILE OR FIELD.

LANDSCAPING SPECIFICATION

2.3 SEED See grassing specification.

2.4 SPRIG A. See grassing specification.

2.5 SOD

A. See grassing specification. 2.6 PLANT MATERIALS

A. Provide all plant materials as indicated on the plans. In the event of any discrepancies between quantities of plants indicated on the plant schedule and those indicated on the plan, plan quantities shall govern.

- B. Plants shall be sound, healthy and vigorous, well branched and densely foliated when in leaf. They shall be free of disease, insect pests, eggs or larvae, and shall have healthy, well developed root systems. Plants shall be from a nursery within 300 miles north or south of the project location and shall have been grown under climate conditions similar to those in the locality of project. Trees for planting in rows shall be uniform in size and shape.
- B. Plants shall possess a normal balance between height and width. Plants shall be measured when branches are in their normal position. Height and spread dimensions specified refer to the main body of plant and not from branch tip to tip. Plants larger in size than specified may be used with no change in contract price.
- C. Plants shall be dug with firm natural balls of earth, of diameter not less than recommended by American Standard for Nursery Stock and of sufficient depth to include fibrous and feeding roots. Plants will not be accepted if ball is cracked or broken before or during planting operations.
- D. Trees specified for Street Tree Grade shall conform to standards of the A.N.L.A.:
- 1. Suitable for planting as street trees.
- 2. Free of branches to approximately 50% of height from ground.
- 3. Crown of tree shall be in good balance with the trunk.

2.7 FERTILIZER

A. Commercial fertilizer shall be slow release 5-10-10 or 6-12-12 (or as recommended by soil test), uniform in composition, free flowing, and suitable for application with appropriate equipment. Deliver to site unopened in manufacturer's standard containers showing weight, analysis and name of manufacturer. If stored on site, protect from the elements.

2.8 PEAT MOSS

A. Peat moss shall be finely shredded, 90% organic moss peat, brown in color and suitable for horticultural purposes. Peat shall be measured in air dry condition, containing not more than 35% moisture by weight. Ash content shall not exceed 10%.

2.9 MULCH FOR TREES, SHRUBS, AND GROUND COVERS

A. Mulch for non bio-retention areas shall be as shown on plans.

B. Mulch for bio-retention areas shall be shredded hardwood.

2.10 STAKING EQUIPMENT

A. Trees and palms shall be staked as shown in landscape plans.

2.11 WATER

Contractor shall provide water to the project via the installation of a new irrigation system for the area shown on the plans.

PART 3 - EXECUTION

3.1 FINE GRADING

- A. All areas within limits of construction shall be fine graded to the desired grades. All areas within limits of construction are to be fine graded, free of roots, debris and/or other objectionable material, before planting or grassing commence. Any additional fill material needed to fill low or uneven areas shall be provided by the Contractor. Positive drainage away from structures shall be provided in all plant beds so standing water does not occur. Planting beds shall be raised above adjacent lawn areas to provide good drainage conditions.
- B. Planting and grassed areas, if not loose, shall be loosened to a minimum depth of 3-inches before fertilizer, seed or sod is applied.

3.2 FERTILIZER AND SOIL AMENDMENTS

- A. Contractor shall provide Topsoil Analysis Tests that has been performed by a State Agricultural Experiment Station, Soil and Water Conservation District, State University, or other qualified private testing laboratory, as approved by Landscape Architect.
- B. Apply fertilizer and soil amendments after fine grading and mix thoroughly into upper 2 inches of soil.
- C. Fertilizer and other necessary soil amendments shall be applied at the rate recommended by Topsoil Analysis Test.

3.3 SODDING

A. See grassing specification.

3.4 SPRIGGING

A. See grassing specification.

3.5 SEEDING

A. See grassing specification.

3.6 SEED PROTECTION

A. See grassing specification.

3.7 LAYOUT OF TREES, SHRUBS, AND GROUND COVERS

A. All plants shall be placed in the proper location as shown on construction plans, allowing Landscape Architect to review all plant locations prior to actual planting. Landscape Architect may make minor adjustments which shall not be cause for changes to the contract price.

3.8 OBSTRUCTIONS BELOW GROUND

- A. Prior to excavating planting holes, Contractor shall determine the exact location of electrical, phone, or television cables or conduits, water, drainage or sewer lines, and any other subsurface structures and take precautions to protect them. Any damage to underground utilities shall be repaired immediately at the Contractor's expense.
- B. In the event rock, underground construction work, or other obstructions are encountered in any plant hole excavation under this contract, alternate locations may be selected. Where locations cannot be changed, the obstructions shall be removed to a depth of not less than three (3) feet below grade and not less than six (6) inches below bottom of ball or roots when plant is properly set at the required grade. The Contractor shall be responsible for the removal of such rock or other underground obstructions encountered.

3.9 PLANTING HOLES

3.10 PLANTING TREES AND SHRUBS

3.11 PLANTING GROUND COVERS

between planting and watering.

3.12 WATERING

3.13 SOIL MIX

3.14 STAKING OF TALL PLANTS

plans.

3.15 MULCHING

3.16 PRUNING

3.17 WEEDING

A. All planted areas shall be kept free from weeds and undesirable grasses until final acceptance by the Owner. See General notes on plans for additional information.

3.18 INSECT AND DISEASE CONTROL

Contractor's expense.

3.19 CLEAN UP

PART 4 - MAINTENANCE AND WARRANTY

4.1 MAINTENANCE

- contract.

4.2 WARRANTY

	BID SET - NOT FOR CONSTRUCTION
DAIE	


NO

 \mathcal{L}

၀ ပ

Ľ

NIN



A. Shall be same as grown in the nursery and/or container soil level. Adjust bottom soil mix to insure proper planting level with the proposed surrounding grades. Check plants to insure proper vertical alignment.

B. Fill holes to proper height to receive plant, and thoroughly tamp before setting the plant. Set plant in upright position in the center of the hole, and compact the backfill mixture around the ball or roots. Add soil amendments as required to improve fertility of existing soil and plant growing conditions.

1. When balled or burlapped plants are set, compact topsoil around base of ball to fill all voids. All bindings shall be removed and the top half of burlap removed from around root ball. If burlap is made of natural fibers it can be laid back from the root mass or can be cut away. Remove all burlap if it is made of non-degradable material/fabric. All weeds growing on the root mass shall be removed prior to planting.

2. Containerized plants shall have the container removed prior to planting. Care shall be taken to protect root mass from injury and the root mass intact. If root mass shows evidence of being bound or matted, three vertical 1/2" deep cuts shall be made on alternate sides of the root mass and roots pulled away slightly. This is to untangle roots which have begun to "circle" the root mass and to encourage new root growth. All weeds growing in the root mass shall be removed prior to planting.

3. Roots of bare root plants shall be spread out and topsoil carefully worked in among them. Remove with a clean cut, any broken or frayed roots.

A. Planting beds shall be thoroughly worked to a depth of twelve (12) inches incorporating fertilizer and other soil improvements at the recommended rate suggest by the soils test. Rake prepared planting bed until level, smooth and free from all soil, lumps, rocks, sticks and other deleterious materials. Bed area should be neatly outlined. Space the plants evenly as indicated on the drawings. Plant only in soil that is moist and friable, and not wet or soggy. In the case of planting in the open on hot days, shorten the time

A. Thoroughly water each plant when the hole is 1/3 full, again at 2/3 full and then complete backfilling. Once backfilling is complete, water again, then tamp the soil in place until the surface of the backfill is level with the surrounding area and the plant bears the same relation of finished grade as it bore to existing grade before being dug.

B. Earth saucers shall be constructed around the perimeter of planting holes of all trees and all single planted shrubs. Earth saucers shall be minimum 3" high and compacted to retain water. Earth saucers shall not be installed in areas where the subsoil is very poorly drained or around mass shrub / groundcover plantings.

C. All trees and shrubs to be hand watered on a regular basis as necessary during the warranty period.

A. Shall be per existing soils on site with recommended amendments from soils test.

A. Shall be done only if site / environment conditions make if required. If required, trees and palms shall be staked as indicated on the

A. All plants shall be mulched with an evenly thick layer of clean mulch immediately after planting. Mass plant beds shall be completely mulched to the limits of the bed as shown on the plans. Limit of mulching for individual trees and shrubs shall be slightly beyond the saucer berm. The areas mulched shall be tidy and clean in appearance.

A. Remove dead, broken or bruised branches after planting using clean, sharp tools

A. All plant materials shall be disease or insect free upon arrival to the site, however, should any plants show signs of insect or disease infestations, Contractor shall identify nature of infestation and submit to Landscape Architect a proposed method of control. Contractor shall treat all infested plants at its expense. Should the infestation be wide spread and uncontrollable, plants affected shall be removed from site, fresh plants brought in and all other plants treated to prevent infestation of remaining plants at

A. Contractor is responsible for removing all trash, debris, rubbish and all other materials associated with the construction from site on a daily basis. All tags, flags, and labels will be removed from plants and trees. The site shall be left broom clean and tidy. Clean up of the site is a prerequisite to final acceptance by the Owner.

A. Protect all plantings (grass, plants and trees) until accepted by Owner. All damage, regardless of cause, shall be immediately repaired and plants replaced if necessary. Erect temporary fences, barricades, signs and other protection as needed to prevent trampling. Contractor is not responsible for replacement of damaged or missing plants and plant materials due to vandalism or other acts beyond the control of the Contractor if proper barriers or other safeguards have been maintained.

B. Maintenance shall include but is not limited to watering, weeding, cultivating, removal of dead material, mulch reapplication, resetting plants to proper grades or upright position, lawn mowing, fertilizing, and other necessary operations.

C. The Contractor shall repair immediately any areas damaged as a result of construction operations or erosion.

E. The Contractor shall maintain all proposed plantings until final acceptance is issued by the Owner.

F. At the end of the maintenance period, all plants shall be in a healthy growing condition. During the maintenance period, should the appearance of any plant indicate weakness and probability of dying, immediately replace without additional cost to the Owner. Replacements required because of vandalism or other causes beyond the control of the Contractor are not part of this

A. All shrubs, ground cover, and trees shall be guaranteed by the Contractor to be alive and healthy for a one year period after substantial completion is issued by the Owner. A final inspection with the Owner shall be conducted at the end of the warranty period to determine if any plants will be required to be replaced.

B. Any lawn, plant, or tree which is dead or not showing satisfactory growth shall be replaced at Contractor's expense at the end of warranty period. All replacements shall be of original quality and of a size equal to adjacent plants or trees of the same kind.

END OF SECTION

PART 1 - GENERAL

1.1 SECTION INCLUDES

- A. Seeding, planting grass, and fertilizing graded areas around buildings, structures, soccer fields and sidewalk shoulders and other disturbed areas.
- B. Seed protection.
- C. Maintaining grassed areas until final acceptance.
- 1.2 RELATED WORK
- A. Civil and Landscape plans and specifications.
- 1.3 DELIVERY, STORAGE, AND HANDLING
- A. Deliver grass seed in original containers showing analysis of seed mixture, percentage of pure seed, year of production, net weight, date of packaging, and location of packaging. Damaged packages are not acceptable. Store in cool, dry locations away from contaminants.
- B. Deliver fertilizer in waterproof bags showing weight, chemical analysis, and name of manufacturer. Damaged bags are not acceptable. Store in cool, dry locations away from contaminants.
- C. Deliver sod on pallets.
- D. All material shall be acceptable to Engineer prior to use.

1.4 PLANTING DATES

A. This specification provides for establishment of a permanent grass cover between the dates of March 1 and September 30. If finished earth grades are not completed in time to permit planting and establishment of permanent grass during the favorable season between dates specified above unless otherwise accepted, Contractor will be required to plant a temporary cover to protect new graded areas from erosion and to keep windborne dust to a minimum. The temporary cover shall be planted between October 1 and February 28 unless otherwise permitted.

1.5 MEASUREMENT AND PAYMENT

- A. When the season or stage of project is such results of grassing work cannot be determined, conditional acceptance will be made on work completed. When conditional acceptance is made for items of work covered, Contractor shall be entitled to 50% of bid price for the actual work placed and shall receive remaining 50% of bid price when final acceptance is made. Conditional acceptance shall not apply to the remaining items of work, and full bid price payment shall be made when work is acceptably placed and completed in accordance with specifications.
- B. Payment for grassing will be made at contract unit price for the item "Grassing" and such payment shall constitute full compensation for furnishing and placing seed and fertilizer or sod where directed and protecting and maintaining seed and sod in all graded and disturbed areas.

PART 2 - PRODUCTS

Contractor shall submit source and species certification documents to Engineer and Owner's Representative for review prior to installation. Supply complete information on all analysis / test methodologies and results; laboratory certifications, manufacturer's specifications, and agency approvals to the Landscape Architect prior to placement of soil mixtures. In addition, provide the Landscape Architect with thoroughly mixed sample of soil mixes for approval prior to placement. Landscape Contractor shall make modifications and improvements to soil mixes deemed necessary by the soil analysis to meet requirements specified here in before, and to ensure proper growing medium for plant material.

2.1 SEED

- A. All seed shall conform to all State Laws and to all requirements and regulations of the State Department of Agriculture.
- B. The varieties of seed, as specified in Section 2.2, shall be individually packaged or bagged, and tagged to show name of seed, net weight, origin, germination, lot number, and other information required by the State Department of Agriculture.
- C. The Engineer reserves the right to test, reject, or accept all seed before seeding.

2.2 SEEDING SCHEDULE

Annual Rye (Temp only)

(EDIT GRASS TYPES, RATES AND PLANTING DATES TO BE CONSISTENT WITH SPECIFIC PROJECT) A. <u>SEED</u> PLANTING DATES <u>RATE</u> 'Princess 77' Bermuda 75 lbs/ acre March 1 -September 30

75 lbs/acre

October 1 -February 28

2.3 FERTILIZER

A. Commercial fertilizer of approved type, conforming to state fertilizer laws at the rate as recommended by soils test.

2.4 LIME

2.5 SPRIG

A. Agricultural grade, ground limestone at the rate as recommended by soils test.

soil, including two to three nodes and from 4 to 6 inches long. Obtain from heavy, dense certified sod. Provide sprigs which have been grown under climatic conditions similar to those in the locality of the project. Coordinate harvesting and planting operations to prevent exposure of sprigs to the sun for more than 30 minutes before covering and moistening. Sprigs showing signs of wilt, mold, containing weeds or other detrimental material or that are heat damaged will be rejected.

- Department of Agriculture.
- matter.
- crowns with only a few green leaves.

2.6 SPRIGGING SCHEDULE

- (EDIT GRASS TYPES, RATES A A. <u>SPRIG</u>
- 'Tifway 419' Bermuda 1,000 bushels / ac. (or approved equal)
- Stabilize site with temporary grass seed (See section 2.2)
- recommended by sprig distributor.

2.7 SOD

- planting.

2.8 ACCESSORIES

- and in dry condition.

2.9 PRODUCT REVIEW

PART 3 - EXECUTION

3.1 PREPARATION

- grade indicated on plans.
- sprig or sod is applied.
- soils test

3.2 STAND OF GRASS

A. Healthy living stems, stolons, or rhizomes and attached roots of locally adapted grass without adhering

GRASSING SPECIFICATION

B. The varieties of sprig, as specified in section 2.6, shall be individually packaged or bagged, and tagged to show name of sprig, net weight, origin and other information required by the State

C. Sprigs shall be pure to variety specified and shall be free of other grass species, weeds or foreign

D. Sprigs shall be harvested by digging (not collected above soil level) shredding sod, by rototilling sod and raking, by vericutting or by a sprig harvester. Sprigs shall consist of mostly rhizomes and

AND PLANTING DATES TO BE CO	NSISTENT WITH SPECIFIC PROJECT)
RATE	PLANTING DATES

1,000 bushels / ac.	April 1 - August 31
(Coverage in 3 months)	
rary grass seed	September 1 - March 31

B. In areas where existing grass is to be matched, Contractor shall sprig at the rate and dates

A. Sod shall be premium grade, densely rooted, good quality grass of the species and certified variety as shown on the plans, free from noxious weeds with no surface soil being visible. The sod shall be obtained from areas where the soil is reasonably fertile. Sod of specified species with not less than 95 percent germination, not less than 85 percent pure seed, and not more than 0.5 percent weed seed. The sod shall be machine cut to a uniform soil thickness that shall contain practically all of the dense root system and not be less than 1-inch thick.

Before cutting, sod shall be mowed to a height of not less that 1-1/2" or more than 2". Sod shall be cut in uniform widths min. 12" and in lengths min. 24 inches.

C. Sod shall be delivered to site in a fresh, moist condition with healthy green foliage. It shall be unloaded from delivery trucks on pallets or rolls and placed in final position within 24 hours of delivery. Sod shall be protected from wind and sun and shall not be allowed to dry out before

D. Sod shall be strong enough to support its own weight and retain its size and shape when suspended vertically from a firm grasp on the upper 10 percent of the section.

A. Straw Mulch: Oat or wheat straw, reasonably free from weeds, foreign matter detrimental to plant life,

B. Excelsior Mulch: Excelsior mulch shall consist of wood fibers cut from sound, green timber. The average length of fibers shall be 4 to 6 inches. Cut shall be made in such a manner as to provide maximum strength of fiber, but at a slight angle to natural grain of the wood to cause splintering of fibers when weathering in order to provide adherence to each other and to soil.

C. Wood cellulose fiber shall be made from wood chip particles manufactured particularly for discharging uniformly on the ground surface when dispersed by a hydraulic water sprayer. It shall remain in uniform suspension in water under agitation and blend with grass seed and fertilizer to form a homogenous slurry. Mulch fibers shall intertwine physically to form a strong moisture holding mat on the ground surface and allow rainfall to percolate into underlying soil. The mulch shall be heat processed to contain no germination or growth-inhibiting factors. It shall be dyed (non-toxic) an appropriate color to facilitate metering of material.

A. Contractor shall provide the Engineer with a complete description of all products before ordering. The Engineer will review all products before they are ordered.

A. Areas to be seeded or sprigged shall be made smooth and uniform and shall conform to the finished

B. Remove foreign materials, plants, roots, stones, and debris from surfaces to be seeded.

C. Grassing areas, if not loose, shall be loosened to a minimum depth of 3 inches before fertilizer, seed,

D. Amendments to soils shall be incorporated into loosened 3 inch top soil layer as recommended by

E. No seeding shall occur until acceptance of the seed bed preparation has occurred. Contractor shall notify owner and landscape architect once seed bed is prepared for review and acceptance

vegetation, Contractor will be required to produce a satisfactory stand of perennial grass root system shall be developed sufficiently to survive dry periods and winter weather capable of re-establishment in spring.

Β. Before acceptance of seeding performed for the establishment of temporary vegetation, Cor will be required to produce a stand of grass sufficient to control erosion for a given are length of time before the next phase of construction or establishment of permanent veget to commence.

3.3 SEEDING AND SPRIGGING DATES

A. Seeding and sprigging shall be performed during periods and at rates specified in their res schedules. Seeding and sprigging work may, at discretion of Contractor, be perf throughout the year using schedule prescribed for given period. Seeding and sprigging wa not be conducted when the ground is frozen or excessively wet. Contractor will be requ produce a satisfactory stand of grass regardless of the period of year work is performed.

3.4 APPLYING LIME AND FERTILIZER

A. Following advance preparation and placing selected material for shoulders and slopes, lin fertilizer, if called for based on soil tests, shall be spread uniformly over the designated are shall be thoroughly mixed with the soil to a depth of approximately 2 inches. Fertilizer of shall be applied at the rate at the rate recommended by required soils test. Unless of provided, lime will not be applied for temporary seeding. In all cases where pract acceptable mechanical spreaders shall be used for spreading fertilizer. On steep slopes to slides and inaccessible to power equipment, the slopes shall be adequately scarified. may be applied on steep slopes by hydraulic methods as a mixture of fertilizer and seed fertilizer is applied with combination seed and fertilizer drills, no further incorporation necessary. The fertilizer and seed shall be applied together when Wood Cellulose Fiber used. Any stones larger than 2 1/2 inches in any dimension, larger clods, roots, or other brought to the surface shall be removed.

3.5 SEEDING

- A. Seed shall be sown within 24 hours following application of fertilizer and lime and preparatio seedbed as specified in Section 3.4. Seed shall be uniformly sown at rate specified by the acceptable mechanical seed drills. Rotary hand seeders, power sprayers or other satis equipment may be used on steep slopes or on other areas inaccessible to seed drills.
- R Seeds shall be covered and lightly compacted by means of cultipacker or light roller if the c not perform this operation. On slopes inaccessible to compaction equipment, the seed covered by dragging spiked chains, by light harrowing or by other satisfactory methods.
- C. Apply water with fine spray immediately after each area has been sown.
- D. Do not sow seed when ground is too dry, during windy periods or immediately following a rain.
- E. If permitted by the special provisions, wood cellulose fiber mulch or excelsior fiber mulch may be
- 3.6 SEED PROTECTION (STRAW MULCH)
- A. All seeded areas seeded with permanent grasses shall be uniformly mulched in a continuous I immediately following seeding and compacting operations, using at least 2 tons of stre acre.

3.7 SEED PROTECTION (EXCELSIOR MULCH)

A. Seed shall be sown as specified in Section 3.5. Within 24 hours after covering of seed, excelsion shall be uniformly applied at the rate of 2 tons per acre. The mulch may be applied hydro or by other acceptable methods. Should the mulch be placed in a dry condition, it thoroughly wetted immediately after placing. Engineer may require light rolling of the m form a tight mat.

3.8 SEED PROTECTION (WOOD CELLULOSE FIBER MULCH)

A. After the lime has been applied and ground prepared as specified in Section 3.4, wood cellulo mulch shall be applied at a rate of 1,500 pounds per acre in a mixture of seed and Hydraulic equipment shall be used for application of fertilizer, seed, and slurry of the prowood pulp. This equipment shall have a built-in agitation system with an operating co sufficient to agitate, suspend, and homogeneously mix a slurry of the specified amount fertilizer, seed, and water. The slurry distribution lines shall be large enough to prevent stop The discharge line shall be equipped with a set of hydraulic spray nozzles which will prov even distribution of slurry on various areas to be seeded. The slurry tank shall have a m capacity of 1,000 gallons.

Seed, fertilizer, wood pulp mulch, and water shall all be combined into the slurry distribution of all ingredients in one operation by hydraulic seeding method specified Materials shall be combined in a manner recommended by the manufacturer. The slurry shall be regulated so amounts and rates of application shall result in a uniform applicatio materials at rates not less than amount specified. Using the color of wood pulp as a equipment operator shall spray prepared seedbed with a uniform visible coat. The slurry s applied in a sweeping motion, in an arched stream to fall like rain, allowing wood fibers t upon each other until an even coat is achieved.

3.9 SPRIGGING

- A. Sprigs shall be placed at the date and rates as shown in section 2.6. The sprigging method shall be by broadcast sprigging, hydroplanting or row planter. Sprigging procedure shall ensure even coverage.
- B. Sprigs applied by broadcast over the site with a distributor or hydroseeder shall be planted at the rates listed in section 2.6. Cover broadcast sprigs with straw mulch immediately after broadcast and water in immediately (within 2 hours).
- C. Sprigs installed by row planter creating a narrow furrow that covers 50 to 80% of the sprig with soil may use less sprig material. Rate shall be as recommended by sprig supplier to provide a solid stand of turf within the time required in Section 2.6. Water in immediately (within 1 hour).

3.10 SODDING

A. Before acceptance of seeding or sprigging is performed for the establishment of permanent

A. Sod shall be placed between March 1st and December 1st. However, if sod is to be placed during

ss whose and be		periods of temperatures over 90 degrees F., the contractor shall take extra care for quick placement of sod with adequate, consistent watering necessary to ensure sod thrives as planted.	ARY	א דוסN	
	В.	Sod shall be placed within 24 hours of cutting.		к - -	
ontractor rea and etation is	C.	Place top elevation of sod 1/2 inch below adjoining paving or curbs.	≥ ·	- Ч - Г - Г	
spective erformed vork shall quired to	D.	All areas to be sodded shall be brought to the proper line grade or cross section as was existing prior to construction. Sod shall be placed so that, upon completion, the edges of the sodded areas will be smooth and will conform to the proposed finished grade. Sod shall be laid smooth, edge to edge, with staggered joints. Sod shall be immediately pressed firmly into contact with the sod bed by tamping or rolling, to eliminate any air pockets. A true and even surface shall be provided, to insure knitting without displacement of the sod or deformation of the surfaces of the sodded areas. Do not stretch or overlap sod pieces. Following compaction, screened soil of good quality shall be used to fill all cracks, and excess soil shall be worked into the grass with rakes or other suitable equipment. On slopes steeper than 4 to1, the sod shall be fastened in place with suitable wood or metal pins to hold the sod in place. Any damage by erosion or other causes that may have occurred after completion of grading operations shall be repaired, before	PRELIMINARY NOT FOR CONSTRUCTIO		ATE
	E.	commencing with the sodding operations. Immediately before sodding, moisten topsoil with a fine spray to a minimum 1" depth. Sod shall not be			BY
me and eas, and and lime		laid on soil that is dry and powdery.			
therwise cticable, s subject Fertilizer d. When n will be Mulch is er debris	F.	Sod shall be moist when laid and placed on moist ground. The sod shall be carefully placed by hand, beginning at the toe of slopes and working upwards. The length of the strips shall be at right angles to the flow of surface water. All joints shall be tightly butted and end joints shall be staggered at least 12 inches. The sod shall be immediately pressed firmly into the ground by tamping or rolling. Fill all joints between strips with fine screened soil. Sod on slopes shall be pegged with sod pegs to prevent movement. The sod shall be watered, mowed, weeded, repaired, or otherwise maintained, to insure the establishment of a uniform healthy stand of grass until acceptance.			SNOISI
n of the e use of	G.	Within 2 hours after sod has been placed, thoroughly water to a minimum depth of 4". After sod and soil have dried, roll sodded areas to ensure good bond between sod and soil and to remove depressions and irregularities. Roll sodded areas with a roller not exceeding 150 lbs. per foot of roller width. Top dress and roll again as necessary to create a smooth even surface.			REV
isfactory	PAR	RT 4 - MAINTENANCE, WARRANTY AND ACCEPTANCE			
drill does shall be	4.1	MAINTENANCE			ÖN
	A.	Maintenance shall consist of providing protection against traffic, watering to ensure uniform seed germination and to keep surface of soil damp, and repairing any areas damaged as a result of construction operations or erosion. Maintenance shall also include, but is not limited to, watering, weeding, cultivating, removal of dead material, lawn mowing, fertilizing, and other necessary operations.		Suite 760 2013 151 2780	
be used.	В.	The Contractor shall maintain all proposed plantings until the date of final acceptance by the Owner.		Suite 760	tion.co
	4.2	WARRANTY	∑.;⊢ ⊢ 0	•	, hut
blanket raw per	A.	All grassed areas shall be guaranteed by the Contractor to be alive and healthy for a one year period from the date of substantial completion issued by the Owner. A final inspection with the Owner shall be conducted at the end of the warranty period to determine if any areas require replanting. At the end of the warranty period, the sod shall show evidence of rooting to the underlying soil and shall have no competitive weed growth from either the sod or from between the sod joints.		1501 Main Street	
or mulch aulically shall be nulch to	В.	Any grassed area which is dead or not showing satisfactory growth shall be replaced at Contractor's expense at the end of warranty period. All replacements shall be of original quality and of a size equal to adjacent plants or trees of the same kind. Replacements required because of vandalism, excessive use or other causes beyond the control of the Contractor are not part of this contract.			<u>,</u>
	4.3	ACCEPTANCE		A S S	
ose fiber fertilizer. repared apacity	A.	Before acceptance of seeding performed for the establishment of permanent vegetation, Contractor will be required to produce a satisfactory stand of perennial grass whose root system shall be developed sufficiently to survive dry periods and winter weather and be capable of reestablishment in spring.	CONOMIC	PARK E	NS
of fiber, oppage. ovide an ninimum	В.	A minimum coverage of 80% density over 100% of the disturbed area is required for seeded areas before project acceptance. Sprig and sod areas shall have 95 % coverage over 100% of the disturbed area prior project acceptance.		TRIAL	ICATION.
tank for I herein. Mixture on of all a guide, shall be to build		END OF SECTION	ENCE COUNTY LOPMENT PA	COUNTY INDUS	ASSING SPECIF
					Ř

DATE:

DRAWN: BCG

DESIGNED: BCG

REVIEWED: JLG

APPROVED: JLG

CALE: ########

RЕN

 \cap

06/07/2021