

**ESCAMBIA COUNTY
CDBG SEPTIC TO SEWER CONVERSION**

OWNER: Robert Laster
ADDRESS: 2202 W. Blount Street
Pensacola Florida 32505
PHONE: 850-426-9037

JOB #: C-S-2019-1
DATE PREPARED: 8/01/2019
OPENING DATE: 8/09/2019
CLOSING DATE: 8/23/2019
CLOSING TIME: 12:00 noon

I/(we) certify that I/(we) have carefully examined the Septic to Sewer Conversion Specifications and Contractor Requirements related to the above referenced job, as furnished by Escambia County, and I/(we) have also examined the site on which the proposed work is to be performed. On the basis of these examinations, I (we) propose to furnish all materials, tools, machinery and labor necessary to complete the work in a professional, workmanship manner and to complete the work at the prices listed.

\$ _____
TOTAL JOB COST

CONTRACTOR'S SIGNATURE

TITLE

BID OPENING DATE: _____
 ACCEPTED **REJECTED**

FIRM

FIRM PHONE NUMBER

BID COMMITTEE REPRESENTATIVE

REQUIRED PERMITS AND INSPECTIONS:

Plumbing **Septic System**

Type of Construction: Concrete Block Outside Dimensions: n/a

Mandatory On Site Pre-Bid Conference: August 16, 2019 at 8:30 AM

INSTRUCTIONS TO BIDDERS

Submit cover sheet with signature of Contractor and bid price in ink. Specifications in pencil will be rejected. Bids must be in a sealed envelope and hand-delivered to Neighborhood Enterprise Division Office, 221 Palafox Place (Ernie Lee Magaha Government Building), Suite 200, Pensacola, FL 32502 office by 12:00 noon at the closing date specified. NO email or fax submissions will be accepted.

The bids will be opened by the Bid Committee on Monday August 19, 2019 at 2:15 PM. The bid will be awarded based upon the lowest eligible bidder with the most reasonable combined bid for the work specified.

Labor, overhead, permits, insurance, and profit must be included into each itemized price and not listed as a separate itemized price or listed under "miscellaneous." Non-compliance will result in rejection of bid.

All repair work performed must be inspected (rough and final) and conform to County Ordinances, State Laws, and Florida Building Code.

The Contractor is responsible for proper reattachment/hook-up of any/all of the following that apply: appliances, existing coaxial cable, telephone and interface, electric, water, and sewage.

HOMEOWNER'S RESPONSIBILITIES AND OBLIGATIONS

The Homeowner is responsible for maintaining existing utilities for the Contractor's use during the rehabilitation period.

The Homeowner is responsible for the removal of all belongings/furnishings from the designated work areas prior to the start date. The Contractor is not responsible for removal of Homeowner's trash and/or discarded belongings or furnishings

PAYMENT SCHEDULE

Lump sum payment at job's completion.

The Contractor will be eligible for Final Payment after the following conditions have been fulfilled:

- Completion of Write-Up
- Inspection/Sign-off by Building Inspections and/or Health Department
- Acceptance by the Homeowner (Homeowner's Release & Warranty)
- Premises free from all construction debris
- Submission of RRP Checklist Form & Contractor's Final Affidavit
- Original Invoice from Contractor

COMPLETION DATE

There is a FOURTEEN (14) day time limit on each rehabilitation job. For every day worked in excess of the FOURTEEN day contract period, a FIFTY DOLLAR (\$50.00) per day penalty will be assessed.

ESCAMBIA COUNTY NEIGHBORHOOD ENTERPRISE DIVISION HOUSING REPAIR PROGRAMS CONTRACTOR REQUIREMENTS

If your firm is awarded the bid for housing repair (SHIP or HUD programs), the following items must be current and on file in order to issue a Purchase Order.

- *Current W9 (less than one year old).
- *County Vendor Information sheet (less than one year old).
- *Worker's Compensation as required by State Law **OR** exemption form.
- *Commercial General Liability (\$1,000,000 coverage) listing Escambia County as Certificate Holder and additional insured.
- *Automobile Liability (\$1,000,000 coverage) listing Escambia County as Certificate Holder and additional insured.

GL and Auto Liability Certificates must state the following under the Additional Interest:

Escambia County
C/O Neighborhood Enterprise Division
221 Palafox Place
Suite 200
Pensacola, FL 32502-5844

All correspondence should be directed to Neighborhood Enterprise Division, 221 Palafox Place, Suite 200, Pensacola, FL 32502 for review.

***For jobs valued at \$25,000 or higher, 100% Performance and Payment Bonds will be required.**

Performance and Payment Bond format will be provided.

Contractor will be responsible for the recording of all bonds with Pam Childers, Clerk of The Circuit Court of Escambia County Florida.

Refer to BCC Office of Purchasing Risk Management Guidelines Procedure No: PP-180 (Performance and Payment Bonds) and PP-185 (Risk Management Guidelines) for further details.

[<http://www.myescambia.com/business/purchasing-policies-and-procedures>]

Additionally, Neighborhood Enterprise Division will maintain the following info in the Contractor's file:

- *Contractor may not be federally debarred from participating in programs as per www.sam.gov
- *State registered or State Certified Contractor License
- *Escambia County Competency Board License
- *Escambia County Business/Occupational License
- *EPA RRP Renovator and Firm Certifications

Firms bidding on Lead Based Paint Abatement jobs must also submit proof of Lead Abatement firm certification.

All information must be current at time of award. IF INFORMATION CANNOT BE PRODUCED IN A TIMELY MANNER, THE COUNTY RESERVES THE RIGHT TO AWARD THE BID TO THE NEXT MOST RESPONSIVE BIDDER.

CDBG Sewer Connection Assistance Specifications
Robert Laster
2202 W. Blount Street
Pensacola, FL 32505

GENERAL:

- Federal funds (Escambia County CDBG) are being used to renovate this property (septic to sewer).
- Contractor is responsible for all required permits to decommission existing septic tanks and tie the unit into the public sewer system.
- Contractors are required to call for utility spots 72 hours prior to commencement of work, with no work to begin until all spots have been made.

SEWER TAP and LATERAL:

There are no tap or lateral fees. There is one (1) sewer lateral that is visible and is located on Blount Street to the right of the driveway.

There is one (1) existing septic tank and it is in the back yard just beyond the white cleanout.

Connect drain lines from the house to the existing sewer tap. Note: there is a line of landscaping that may need to be removed to reach the tap in the most direct route.

Tie all drains into the ECUA municipal sewer system.

Check the existing vents to assure that all are to code and are functioning properly.

SEWER LINE and SEPTIC TANK ABANDONMENT:

Decommission the existing septic tank, per the State of Florida Environmental Health Department regulation/requirements (pump tank, punch holes in bottom and back fill), permit and inspection required.

Sewer line (PVC schedule 40) is to run from house drain and connect to the sewer system with "two-way" clean-outs as required by code.

Following the installation of the new sewer line and decommissioning of the septic tank/grease trap, grade area and leave in a uniform/smooth condition, then provide grass seed and hay for stabilization.

All indentations (created by trucks and other equipment used to accomplish work herein), are to be filled to grade with brown fill or topsoil, then seeded and stabilized with hay.

TOTAL JOB COST \$ _____ (TO FRONT COVER)