

BID FORM - LANDSCAPE SITE IMPROVEMENTS

PROJECT NAME: Wright Family Park
LOCATION: Bluffton, South Carolina
OWNER: Town of Bluffton
VERSIONS: 190321

LEGEND

C.Y. - Cubic Yard Ea. - Each
S.Y. - Square Yard L.F. - Lineal Foot
Allow - allowance L.S. - Lump Sum
L.F.T. - Lineal Foot of Tread S.F. - Square Foot
F.S.F. - Face Square Foot Ac. - Acre

**Bidders' responsibility to verify all quantities.*

ASSUMPTION OF LANDSCAPE SITE IMPROVEMENTS - BASE BID

**Bidders' responsibility to verify all quantities.*

Description	Total Qty.*	Unit	Unit cost (\$)	Sub total (\$)
Temporary stair assembly	1	Ea.		
Selective low-growth vegetation, stump removal & limbing	1	L.S.		
Fine Grade & Site Preparation	1	L.S.		
4" Concrete Sidewalk Assembly - non trafficable	7,500	S.F.		
6" Concrete Sidewalk Assembly - bike rack / misc. footings	75	S.F.		
Unit Paving	175	S.F.		
Crushed Stone/Shell Paving	800	S.F.		
Decorative Rail Fence	200	L.F.		
Decorative Pier Fence	70	L.F.		
LT-4 Plaza Rail Light	8	Ea.		
TR-1 Trash Receptacle	8	Ea.		
DB-1 Dog Bag Dispensary	2	Ea.		
BL-1 Bollard	7	Ea.		
BR-1 Bike Rack	7	Ea.		
BN-1 Bench - type 1	2	Ea.		
BN-2 Bench - type 2	4	Ea.		
BN-3 Bench - type 3	2	Ea.		

SS-1 Primary Park ID	1	Ea.		
SS-2 Wayfinding Kiosk	2	Ea.		
SS-3 Park Rules	2	Ea.		
SS-4 Community Events Kiosk	1	Ea.		
SS-5 Decorative Parking Sign	17	Ea.		
SS-6 Embankment Caution	2	Ea.		

Irrigation System	1	L.S.		
-------------------	---	------	--	--

Planting Soils	1	L.S.		
----------------	---	------	--	--

Turf & Grasses

CYNODON DACTYLON CELEBRATION CELEBRATION BERMUDA SOD	34,361	S.F.		
---	--------	------	--	--

Trees Supply & Install

QUERCUS VIRGINIANA SOUTHERN LIVE OAK CALIPER: 6"	3	Ea.		
SABAL PALMETTO SABAL PALM HEIGHT: 12'-18'	10	Ea.		
JUNIPERUS VIRGINIANA EASTERN RED CEDAR CALIPER: 6"	1	Ea.		

Shrubs & Groundcover Supply & Install

ILEX CASSINE DAHOON HOLLY HEIGHT: 8' MIN.	4	Ea.		
CLEYERA JAPONICA JAPANESE CLEYERA HEIGHT: 6' MIN.	6	Ea.		
AZALEA INDICA 'FORMOSA' FORMOSA AZALEA HEIGHT: 24"	53	Ea.		

RHODODENDRON 'CONLED' AUTUMN CORAL ENCORE AZALEA HEIGHT: 24" MIN.	154	Ea.		
PODOCARPUS MACROPHYLLUS 'PRINGLES DWARF' PRINGLES DWARF YEW HEIGHT: 24" MIN.	53	Ea.		
BUDDLEIA X LO AND BEHOLD 'LILAC CHIP' BUTTERFLY BUSH HEIGHT: 18" MIN.	18	Ea.		
PENNISETUM ALOPECUROIDES 'LITTLE BUNNY' LITTLE BUNNY GRASS SPACING: 18" O.C.	409	Ea.		
CHASMANTHIUM LATIFOLIUM INLAND SEA OATS SPACING: 24" O.C.	120	Ea.		
LIRIOPE MUSCARI 'EMERALD GODDESS' EMERALD GODDESS LIRIOPE SPACING: 18" O.C.	2,022	Ea.		
Planting Accessories - Mulch,	1	L.S.		
General Requirements - Bonding, overhead and other operational expenses	1	L.S.		
CONSTRUCTION COST OF BASE BID LANDSCAPE SITE IMPROVEMENTS*	1	L.S.		
ASSUMPTION OF LANDSCAPE SITE IMPROVEMENTS - ADD ALTERNATE BID				
Alternate 1: Driveway - 6" Concrete Sidewalk Assembly - traffic (driveway)	725	S.F.		
Alternate 2: Slope bank stabilization and landscape planting. Includes temporary irrigation until establishment.	1	L.S.		
Alternate 3: Landscape Maintenance - 1 year from substantial completion (provide detailed proposal)	1	L.S.		